

**J-1502000-49 Re-Lamping Services at the National Naval Medical Center (NNMC)**

The contractor will provide all necessary labor, materials, and equipment to perform interior relamping services in Buildings 1 through 10, 54 and 55 at the National Naval Medical Center (NNMC). Government will furnish lists of specific work to be done.

1. Work can include: Contractor will restore light fixtures to full, normal operation by replacing materials with equivalent or better items, suitable for the purpose, and bearing UL or FM approval, including, but not limited to:
  - a) Light bulbs
  - b) Starters
  - c) Ballasts
  - d) Lenses
  - e) Sockets
  - f) Other related parts as needed to restore lights to full operation
  - g) Clean all lenses prior to re-installation
2. Dispose of used light bulbs, ballasts and other components per environmental regulations.
3. Used fluorescent bulbs shall not be disposed of as regular solid waste, but turned in for recycle or else managed as a universal hazardous waste according to base requirements and federal, state, and local environmental regulations.
4. In addition to the Contractor's effort expended to inspect and replace lights, the Government will submit service calls to repair burned out lights.
5. Annual estimated light work will be as follows:

Annual estimated total of lights to be replaced at NNMC is 5,000 lights of all types.  
Included in the work is the requirement to repair or replace items other than lights (ballasts/starters, lenses, fixture components, etc.). Expect the requirement to replace 500 non-light bulb components per year in addition to the replacement of light bulbs.

(End of Attachment J-1502000-49)