PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP1** VOLTAGE: 480Y/277 AMPERES: 400 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	3.0			OA-2 SUPPLY	12	20/3	1	2	25/3	10	CT-1	5.0			3/4"	10
			3.0					3	4					5.0			
				3.0				5	6						5.0		
12	3/4"	2.1			OA-2 RETURN	12	15/3	7	8	15/3	12	P-5	2.1			3/4"	12
			2.1					9	10					2.1			
				2.1				11	12						2.1		
12	3/4"	0.9			P-3	12	15/3	13	14	15/3	12	P-6	2.1			3/4"	12
			0.9					15	16					2.1			
				0.9				17	18						2.1		
12	3/4"	0.9			P-4	12	15/3	19	20	40/3	10	P-7	5.8			3/4"	10
			0.9					21	22					5.8			
				0.9				23	24						5.8		
12	3/4"	0.8			FCU- 3 1C27	12	15	25	26	40/3	10	P-8	55.8			3/4"	10
12	3/4"		2.0		VHP-18	12	15	27	28					5.8			
12	3/4"			2.0	HHP-18	12	15	29	30						5.8		
12	3/4"	1.7			HHP-12	12	15	31	32	25/3	10	VHP-120	6.0			3/4"	10
12	3/4"		2.0		HHP-18	12	15	33	34					6.0			
12	3/4"			2.0	HHP-18	12	15	35	36						6.0		
					SPACE ONLY			37	38	15/3	12	HHP-30	2.7			3/4"	12
					SPACE ONLY			39	40					2.7			
					SPACE ONLY			41	42						2.7		
					SPACE ONLY			43	44	15/3	12	HHP-36	3.0			3/4"	12
					SPACE ONLY			45	46					3.0			
					SPACE ONLY			47	48						3.0		
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		10.4	11.9	11.9	**SUB-TOTAL** KVA				KVA			**SUB-TOTAL**	83.5	33.5	33.5		184.7
									KVA			**GROSS-TOTAL**	93.9	45.4	45.4		

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP2** VOLTAGE: 480Y/277 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
10	3/4"	6.0			VHP-120 1C03.1	10	25/3	1	2	25/3	10	VHP-120 1C03.2	6.0			3/4"	10
			6.0					3	4					6.0			
				6.0				5	6						6.0		
12	3/4"	2.0			VHP-24 1A09	12	15/3	7	8	15	12	VHP-12 1A12	1.7			3/4"	12
			2.0					9	10			SPACE ONLY					
				2.0				11	12			SPACE ONLY					
10	3/4"	5.0			VHP-72 1C01	10	25/3	13	14			SPACE ONLY					
			5.0					15	16			SPACE ONLY					
				5.0				17	18			SPACE ONLY					
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		14.0	14.0	14.0	**SUB-TOTAL** KVA				KVA			**SUB-TOTAL**	8.7	7.0	7.0		64.7
									KVA			**GROSS-TOTAL**	22.7	21.0	21.0		

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP3** VOLTAGE: 480Y/277 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	1.1			VHP-36-1A32	12	15	1	2	15/3	12	VHP-36-1C39	3.0			3/4"	12
12	3/4"		1.1		VHP-36-1A34	12	15	3	4			-		3.0			
12	3/4"			1.7	VHP-12-1A19	12	15	5	6			-			3.0		
10	3/4"	5.0			VHP-72 1C00A	10	25/3	7	8	15/3	12	VHP-36-1C41	3.0			3/4"	12
			5.0		-			9	10			-		3.0			
				5.0	-			11	12			-			3.0		
12	3/4"	0.6			FCU-1-1S02	12	15	13	14	20/3	12	VHP-60 1C00B	4.5			3/4"	12
12	3/4"		0.6		FCU-2-1S02	12	15	15	16					4.5			
12	3/4"			1.7	VHP-12-1A31	12	15	17	18						4.5		
12	3/4"	2.8			VHP-30 2C04	12	15/3	19	20	15/3	12	VHP-30 2C05	2.8			3/4"	12
			2.8					21	22					2.8			
				2.8				23	24						2.8		
12	3/4"	4.0			VHP-48 2C09	12	15/3	25	26	15/3	12	VHP-18 2C07	2.8			3/4"	12
			4.0					27	28			SPACE ONLY					
				4.0				29	30			SPACE ONLY					
12	3/4"	3.0			VHP-36 2C01	12	15/3	31	32			SPACE ONLY					
			3.0					33	34			SPACE ONLY					
				3.0				35	36			SPACE ONLY					
					SPACEO NLY			37	38			SPACE ONLY					
					SPACEO NLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		17.5	17.5	19.2	**SUB-TOTAL** KVA				KVA			**SUB-TOTAL**	17.2	14.4	14.4		100.0
									KVA			**GROSS-TOTAL**	34.6	31.8	33.5		

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP4** VOLTAGE: 480Y/277 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	3.9			VHP-48-1D16	12	15/3	1	2	15	12	FCU-1-1B05	0.6			3/4"	12
			3.9		-			3	4	15	12	FCU-1- 1S03		0.6		3/4"	12
				3.9	-			5	6			SPACE ONLY					
12	3/4"	3.9			VHP-48-1B12	12	15/3	7	8			SPACE ONLY					
			3.9		-			9	10			SPACE ONLY					
				3.9	-			11	12			SPACE ONLY					
12	3/4"	3.9			VHP-48-1B10	12	15/3	13	14			SPACE ONLY					
			3.9		-			15	16			SPACE ONLY					
				3.9	-			17	18			SPACE ONLY					
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		12.6	12.6	12.6	**SUB-TOTAL** KVA				KVA			**SUB-TOTAL**	1.6	1.6	1.0		42.1
									KVA			**GROSS-TOTAL**	14.2	14.2	13.6		
									FED FROM			SDP3					

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO: DATE

BWR KDM BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND – WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

PANEL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091421

SHEET 667 OF 789

E710

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP5** VOLTAGE: 480Y/277 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	2.0			VHP-24 1B06	12	15/3	1	2	15/3	12	VHP-36 1E01	3.0			3/4"	12
			2.0					3	4					3.0			
				2.0				5	6						3.0		
12	3/4"	3.6			VHP-42 1B01	12	15/3	7	8	15/3	12	VHP-36 1B00	3.0			3/4"	12
			3.6					9	10					3.0			
				3.6				11	12						3.0		
12	3/4"	3.0			VHP-36 2E00	12	15/3	13	14	15/3	12	VHP-24 2B02	2.0			3/4"	12
			3.0					15	16					2.0			
				3.0				17	18						2.0		
12	3/4"	3.6			VHP-42 2B01	12	15/3	19	20	15/3	12	VHP-36 2B00	3.0			3/4"	12
			3.6					21	22					3.0			
				3.6				23	24						3.0		
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		13.2	13.2	13.2	**SUB-TOTAL** KVA							KVA **SUB-TOTAL**	12.0	12.0	12.0		
												KVA **GROSS-TOTAL**	25.2	25.2	25.2		75.6
												FED FROM SDP3					

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP6** VOLTAGE: 480Y/277 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	2.0			VHP-24 1D04	15/3	12	1	2	15/3	12	VHP-36 1D00	3.0			3/4"	12
			2.0					3	4					3.0			
				2.0				5	6						3.0		
12	3/4"	2.8			VHP-30 1D06	15/3	12	7	8	15/3	12	VHP-48 1D12	4.0			3/4"	12
			2.8					9	10					4.0			
				2.8				11	12						4.0		
12	3/4"	4.0			VHP-48 1D10	15/3	12	13	14	15	12	FCU-2 1S04	0.6			3/4"	12
			4.0					15	16			SPACE ONLY					
				4.0				17	18			SPACE ONLY					
12	3/4"	1.7			DEMONSTRATION HP-12	15	12	19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		11.5	9.8	9.8	**SUB-TOTAL** KVA							KVA **SUB-TOTAL**	8.6	8.0	8.0		
												KVA **GROSS-TOTAL**	20.1	17.8	17.8		55.7
												FED FROM SDP3					

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP7** VOLTAGE: 480Y/277 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	2.0			VHP-24 2B04	12	15/3	1	2	15/3	12	VHP-48 2D16	4.0			3/4"	12
			2.0		-			3	4			-		4.0			
				2.0	-			5	6			-			4.0		
12	3/4"	4.0			VHP-48 2B10	12	15/3	7	8	15/3	12	VHP-48 2B14	4.0			3/4"	12
			4.0		-			9	10			-		4.0			
				4.0	-			11	12			-			4.0		
12	3/4"	0.9			MUA-1	12	15/3	13	14			SPACE ONLY					
			0.9		-			15	16			SPACE ONLY					
				0.9	-			17	18			SPACE ONLY					
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		7.9	7.9	7.9	**SUB-TOTAL** KVA							KVA **SUB-TOTAL**	9.0	9.0	9.0		
												KVA **GROSS-TOTAL**	16.9	16.9	16.9		50.8
												FED FROM SDP3					

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP8** VOLTAGE: 480Y/277 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	2.0			VHP-24 2D02	12	15/3	1	2	15/3	12	VHP-36 2D00	3.0			3/4"	12
			2.0					3	4					3.0			
				2.0				5	6						3.0		
12	3/4"	4.0			VHP-48 2D10	12	15/3	7	8	15/3	12	VHP-48 2D12	4.0			3/4"	12
			4.0					9	10					4.0			
				4.0				11	12						4.0		
					SPACE ONLY			13	14			SPACE ONLY					
					SPACE ONLY			15	16			SPACE ONLY					
					SPACE ONLY			17	18			SPACE ONLY					
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		7.0	7.0	7.0	**SUB-TOTAL** KVA							KVA **SUB-TOTAL**	8.0	8.0	8.0		
												KVA **GROSS-TOTAL**	15.0	15.0	15.0		45.0
												FED FROM SDP3					

Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO:	DATE
BWR KDM BKB	
PM/DM	
BRANCH MANAGER	
CHIEF ENGINEER	
FIRE PROTECTION	

DEPARTMENT OF THE NAVY
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND – WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

PANEL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091422

SHEET 668 OF 789

E711

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **TRP1** VOLTAGE: 208Y/120 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	1.0			BACKBOARD REC TR1	12	20	1	2	20	12	BACKBOARD REC TR1	1.0			3/4"	12
12	3/4"		1.0		BACKBOARD REC TR1	12	20	3	4	20	12	BACKBOARD REC TR1		1.0		3/4"	12
12	3/4"			1.0	BACKBOARD REC TR1	12	20	5	6	20	12	BACKBOARD REC TR1			0.5	3/4"	12
12	3/4"	1.0			RACK REC TR1	12	20	7	8	20	12	BACKBOARD REC TR1	0.5			3/4"	12
12	3/4"		1.0		RACK REC TR1	12	20	9	10	20	12	RACK REC TR1		1.0		3/4"	12
12	3/4"			1.0	RACK REC TR1	12	20	11	12	20	12	RACK REC TR1			1.0	3/4"	12
12	3/4"	1.0			RACK REC TR1	12	20	13	14	20	12	RACK REC TR1	1.0			3/4"	12
12	3/4"		0.4		REC 1C23	12	20	15	16	20	12	RACK REC TR1		1.0		3/4"	12
12	3/4"			0.4	REC 1C23	12	20	17	18	30/2	10	CU-36 1C25			2.4	3/4"	10
12	3/4"	0.8			REC 1C23	12	20	19	20			-	2.4				
12	3/4"		0.6		REC 1C23	12	20	21	22			SPACE ONLY					
10	3/4"			2.5	UPS IN ROW COOLING	10	25/2	23	24			SPACE ONLY					
		2.5						25	26			SPACE ONLY					
6	1 1/2"		7.0		UPS	1	100/3	27	28			SPACE ONLY					
				7.0				29	30			SPACE ONLY					
		7.0						31	32			SPACE ONLY					
					SPACE ONLY		20	33	34			SPACE ONLY					
					SPACE ONLY		20	35	36			SPACE ONLY					
					SPACE ONLY		20	37	38			SPACE ONLY					
					SPACE ONLY		20	39	40			SPACE ONLY					
					SPACE ONLY		20	41	42			SPACE ONLY					
		1.0			SPARE		20	43	44			SPACE ONLY					
			1.0		SPARE		20	45	46			SPACE ONLY					
				1.0	SPARE		20	47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		15.3	12.0	13.9	**SUB-TOTAL** KVA							KVA **SUB-TOTAL**	5.9	4.0	4.9		56.0
												KVA **GROSS-TOTAL**	21.2	16.0	18.8		

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **TRP2** VOLTAGE: 208Y/120 AMPERES: 100 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	1.0			BACKBOARD REC TR2	12	20	1	2	20	12	RACK RCPT TR2	1.0			3/4"	12
12	3/4"		1.0		BACKBOARD REC TR2	12	20	3	4	20	12	RACK RCPT TR2		1.0		3/4"	12
12	3/4"			1.0	BACKBOARD REC TR2	12	20	5	6	20	12	RACK RCPT TR2			1.0	3/4"	12
12	3/4"	1.0			BACKBOARD REC TR2	12	20	7	8	20	12	RACK RCPT TR2	1.0			3/4"	12
12	3/4"		1.0		BACKBOARD REC TR2	12	20	9	10	20/2	12	CU-18-1ED6		1.4		3/4"	12
					SPACE ONLY			11	12						1.4		
					SPACE ONLY			13	14			SPACE ONLY					
					SPACE ONLY			15	16			SPACE ONLY					
					SPACE ONLY			17	18			SPACE ONLY					
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPARE		20	25	26	20		SPARE					
					SPARE		20	27	28	20		SPARE					
					SPARE		20	29	30	20		SPARE					
		2.0	2.0	1.0	**SUB-TOTAL** KVA							KVA **SUB-TOTAL**	2.0	2.4	2.4		11.8
												KVA **GROSS-TOTAL**	4.0	4.4	3.4		
												FED FROM: SDP3					

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **TRP3** VOLTAGE: 208Y/120 AMPERES: 100 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	1.0			BACKBOARD REC TR3	12	20	1	2	20	12	RACK RCPT TR3	1.0			3/4"	12
12	3/4"		1.0		BACKBOARD REC TR3	12	20	3	4	20	12	RACK RCPT TR3		1.0		3/4"	12
12	3/4"			1.0	BACKBOARD REC TR3	12	20	5	6	20/2	12	CU-18 1A22			1.4	3/4"	12
12	3/4"	1.0			BACKBOARD REC TR3	12	20	7	8				1.4				
					SPACE ONLY			9	10			SPACE ONLY					
					SPACE ONLY			11	12			SPACE ONLY					
					SPACE ONLY			13	14			SPACE ONLY					
					SPACE ONLY			15	16			SPACE ONLY					
					SPACE ONLY			17	18			SPACE ONLY					
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
		1.0			SPARE		20	25	26	20		SPARE	1.0				
			1.0		SPARE		20	27	28	20		SPARE		1.0			
				1.0	SPARE		20	29	30	20		SPARE			1.0		
		3.0	2.0	2.0	**SUB-TOTAL** KVA							KVA **SUB-TOTAL**	3.4	2.0	2.4		14.8
												KVA **GROSS-TOTAL**	6.4	4.0	4.4		

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **TRP4** VOLTAGE: 208Y/120 AMPERES: 100 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	0.8			RCPTS RM 2ED6	12	20	1	2	20	12	COMM RACK TR4	1.0			3/4"	12
12	3/4"		0.8		RCPTS RM 2ED6	12	20	3	4	20	12	COMM RACK TR4		1.0		3/4"	12
					SPACE ONLY	12	20	5	6	20/2	12	CU-18 2ED6			1.4	3/4"	12
					SPACE ONLY	12	20	7	8				1.4				
					SPACE ONLY	12	20	9	10			SPACE ONLY					
					SPACE ONLY	12	20	11	12			SPACE ONLY					
					SPACE ONLY	12	20	13	14			SPACE ONLY					
					SPACE ONLY	12	20	15	16			SPACE ONLY					
					SPACE ONLY	12	20	17	18			SPACE ONLY					
					SPACE ONLY	12	20	19	20			SPACE ONLY					
					SPACE ONLY	12	20	21	22			SPACE ONLY					
					SPACE ONLY	12	20	23	24			SPACE ONLY					
		1.0			SPARE		20	25	26	20		SPARE	1.0				
			1.0		SPARE		20	27	28	20		SPARE		1.0			
				1.0	SPARE		20	29	30	20		SPARE			1.0		
		1.8	1.8	1.0	**SUB-TOTAL** KVA							KVA **SUB-TOTAL**	3.4	2.0	2.4		12.4
												KVA **GROSS-TOTAL**	5.2	3.8	3.4		
												FED FROM SDP3					

	APPR.
	DATE
	DESCRIPTION
	SYM

NAVFAC

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO	DATE
BWR KDM BKB	
PM/DM	
BRANCH MANAGER	
CHIEF ENG/ ARCH	
FIRE PROTECTION	

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND – WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

PANEL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091423

SHEET 669 OF 789

E712

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **TRP5** VOLTAGE: 208Y/120 AMPERES: 100 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	0.4			REC RM 2C06	12	20	1	2	20	12	COMM RACK TR5	1.0			3/4"	12
12	3/4"		0.4		REC RM 2C06	12	20	3	4			SPACE ONLY					
12	3/4"			0.4	REC RM 2C06	12	20	5	6	20/2	12	CU-18 2C06			1.4	3/4"	12
					SPACE ONLY			7	8				1.4				
					SPACE ONLY			9	10			SPACE ONLY					
					SPACE ONLY			11	12			SPACE ONLY					
					SPACE ONLY			13	14			SPACE ONLY					
					SPACE ONLY			15	16			SPACE ONLY					
					SPACE ONLY			17	18			SPACE ONLY					
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
		1.0			SPARE	12	20	25	26			SPARE	1.0				
			1.0		SPARE	12	20	27	28			SPARE		1.0			
				1.0	SPARE	12	20	29	30			SPARE			1.0		
		1.4	1.4	1.4	SUB-TOTAL KVA							KVA SUB-TOTAL	3.4	1.0	2.4		
												KVA GROSS-TOTAL	4.8	2.4	3.8		11.0

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **PP1** VOLTAGE: 208Y/120 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
10	3/4"	2.4			B-1	10	25	1	2	20	12	OA-2 ENERGY RECOVERY	1.9			3/4"	12
10	3/4"		2.4		B-2	10	25	3	4	15	12	RP-1		0.5		3/4"	12
12	3/4"			0.2	WH-1	12	15	5	6	15	1	RP-2			0.5	3/4"	12
12	3/4"	0.2			WH-2	12	15	7	8	30/2	10	CU-36 1C21	2.4			3/4"	10
12	3/4"		1.4		CU-18 1F09	12	20/2	9	10			-		2.4			
				1.4	-			11	12	20/2	12	CU-18 1C21			1.4	3/4"	12
12	3/4"	1.0			GM-1	12	20	13	14			-	1.4				
					SPACE ONLY			15	16	100/3	4	DOMESTIC WATER BOOSTERS		5.8		1 1/4"	8
8	1"			2.6	UPS COND UNIT	8	40	17	18						5.8		
		2.6			-			19	20				5.8				
12	3/4"		0.4		TP-1	12	15	21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		7.2	5.2	5.2	SUB-TOTAL KVA							KVA SUB-TOTAL	12.5	9.7	8.7		
												KVA GROSS-TOTAL	19.7	14.9	13.9		48.5

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **PP2** VOLTAGE: 208Y/120 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
10	3/4"	1.2			CF-1	12	15	1	2			SPACE ONLY					
10	3/4"		1.2		CF-1	12	15	3	4			SPACE ONLY					
12	3/4"			1.2	CF-1	12	15	5	6			SPACE ONLY					
12	3/4"	0.2			ROOFTOP RCPT	12	20	7	8			SPACE ONLY					
12	3/4"				SPACE ONLY			9	10			SPACE ONLY					
					SPACE ONLY			11	12			SPACE ONLY					
10	3/4"				SPACE ONLY			13	14			SPACE ONLY					
					SPACE ONLY			15	16			SPACE ONLY					
8	1"				SPACE ONLY			17	18	30/2	10	CL-36 1A13			2.4	3/4"	10
					SPACE ONLY			19	20				2.4				
					SPACE ONLY			21	22	30/2	10	CL-36 2E07		2.4		3/4"	10
					SPACE ONLY			23	24						2.4		
					SPACE ONLY			25	26	30/2	10	CL-36 1E07	2.4			3/4"	10
					SPACE ONLY			27	28					2.4			
					SPACE ONLY			29	30	20/2	12	CL-18 1C53			1.4	3/4"	12
					SPACE ONLY			31	32				1.4				
					SPACE ONLY			33	34	20/2	12	CL-18 2B05		1.4		3/4"	12
					SPACE ONLY			35	36						1.4		
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		2.4	2.2	2.2	SUB-TOTAL KVA							KVA SUB-TOTAL	7.2	7.2	8.6		
												KVA GRCSS-TOTAL	9.6	9.4	10.8		29.8
												FED FROM SDP3					

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **KP1** VOLTAGE: 480Y/277 AMPERES: 400 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
10	1"	7.74			DISHWASHER	8	40/3	1	2	50/3	6	BOOSTER HEATER	10			1"	10
			7.74					3	4					10			
				7.74				5	6						10		
12	3/4"	1.3			HOOD EXHAUST FAN EF-1	12	20/3	7	8	20/3	12	KITCHEN MAKE UP AIR FAN S-1	2.1			3/4"	12
			1.3					9	10					2.1			
				1.3				11	12						2.1		
					SPACE ONLY			13	14	175/3	2/0	MAKE UP AIR HEAT EDH-1	34			2"	6
					SPACE ONLY			15	16					34			
					SPACE ONLY			17	18						34		
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
		1			SPARE		20	37	38	20		SPARE	1.0				
			1		SPARE		20	39	40	20		SPARE		1.0			
				1	SPARE		20	41	42	20		SPARE			1.0		
		10.0	10.0	10.0	SUB-TOTAL KVA							KVA SUB-TOTAL	47.1	47.1	47.1		
												KVA GROSS-TOTAL	57.1	57.1	57.1		171.4

APPR	DATE	DESCRIPTION	SYM

NAVFAC

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO	DATE
BWR	KDM BKB
PM/DM	
BRANCH MANAGER	
CHIEF ENG/ ARCH	
FIRE PROTECTION	

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND – WASHINGTON
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

PANEL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091424

SHEET 670 OF 789

E713

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **KR1** VOLTAGE: 208Y/120 AMPERES: 400 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	1.3			COMBI OVEN	12	20	1	2	30/3	10	BOILERLESS STEAMER	2.7			3/4"	10
12	3/4"		1.8		BRAISING PAN	12	20	3	4					2.7			
12	3/4"			0.4	DOUBLE CONVECTION OVEN	12	20	5	6						2.7		
12	3/4"	0.4			DOUBLE CONVECTION OVEN	12	20	7	8	30/3	10	BOILERLESS STEAMER	2.7			3/4"	10
12	3/4"		1.8		EXHAUST HOOD	12	20	9	10					2.7			
12	3/4"			0.4	FOOD PROCESSOR	12	20	11	12						2.7		
12	3/4"	1			PASS THRU FRIDGE	12	20	13	14	70/3	4	TABLE TOP KETTLE	6.6			1 1/4"	6
12	3/4"		2.1		PASS THRU HOT HOLD	12	20	15	16					6.6			
12	3/4"			0.9	6 PAN COLD WELL	12	20	17	18						6.6		
12	3/4"	1			REFRIGERATED MERCHANDISER	12	20	19	20	20/3	12	MIXER 40QT	1.2			3/4"	12
12	3.4"		0.6		ICE CREAM CABINET	12	20	21	22					1.2			
12	3/4"			1	WALK IN COOLER LIGHTS	12	20	23	24						1.2		
12	3/4"	1			WALK IN FREEZER LIGHTS	12	20	25	26	30/2	10	MICROWAVE	2			3/4"	10
12	3/4"		1		SLICER	12	20	27	28					2			
					SPACE ONLY			29	30	20/2	12	BLAST CHILLER			1.6	3/4"	12
					SPACE ONLY			31	32				1.6				
					SPACE ONLY			33	34	50/2	6	6 PAN HOT WELL		3.0		1"	8
					SPACE ONLY			35	36						3.0		
					SPACE ONLY			37	38	20/2	6	WASHER/DRYER	5			1"	8
					SPACE ONLY			39	40			SPACE ONLY		5			
					SPACE ONLY			41	42			SPACE ONLY					
		1			SPARE		20	43	44			SPACE ONLY					
			1		SPARE		20	45	46			SPACE ONLY					
				1	SPARE		20	47	48			SPACE ONLY					
		1			SPARE		20	49	50			SPACE ONLY					
			1		SPARE		20	51	52			SPACE ONLY					
				1	SPARE		20	53	54			SPACE ONLY					
		6.7	9.3	4.7	SUB-TOTAL KVA							KVA SUB-TOTAL	21.8	23.2	17.8		
												KVA GROSS-TOTAL	28.5	32.5	22.5		83.5

ALL 20A/1P BREAKERS SERVING RECEPTACLES SHALL BE GFI

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **KR2** VOLTAGE: 208Y/120 AMPERES: 225 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
8	1"	4			FREEZER COMPRESSOR	8	40/3	1	2	80/2	3	DISHWASHER	6.6			1 1/4"	6
			4					3	4					6.6			
				4				5	6	20/2	12	DISPOSER			0.8	3/4"	12
10	3/4"	1.6			COOLER COMPRESSOR	10	30/3	7	8				0.8				
			1.6					9	10	20	12	GENERAL RECEPTACLES		0.6		3/4"	12
				1.6				11	12	20	12	GENERAL RECEPTACLES			0.6	3/4"	12
12	3/4"	0.9			KITCHEN MUA	12	*20/3	13	14	20	12	GENERAL RECEPTACLES	1.2			3/4"	12
			0.9					15	16	20	12	E-STOP CIRCUIT		1		3/4"	12
				0.9				17	18	20	12	GENERAL RECEPTACLES			0.6	3/4"	12
12	3/4"	0.4			TP-1	12	15	19	20	20	12	GENERAL RECEPTACLES	1.4			3/4"	12
12	3/4"		0.8		EVAPORATOR	12	20/2	21	22	20	12	GENERAL RECEPTACLES		1		3/4"	12
				0.8				23	24	20	12	GENERAL RECEPTACLES			0.6	3/4"	12
12	3/4"	0.2			EVAPORATOR	12	20	25	26	20	12	GENERAL RECEPTACLES	0.8			3/4"	12
					SPACE ONLY			27	28	20	12	CASH REGISTER		0.4		3/4"	12
					SPACE ONLY			29	30	20	12	CASH REGISTER			0.4	3/4"	12
					SPACE ONLY			31	32	20	12	RCPTS RM 1C01	0.4			3/4"	12
					SPACE ONLY			33	34	20	12	RCPTS ROOF		0.2		3/4"	12
					SPACE ONLY			35	36			SPACE ONLY					
		1			SPARE		20	37	38	20		SPARE	1.0				
			1		SPARE		20	39	40	20		SPARE		1.0			
				1	SPARE		20	41	42	20		SPARE			1.0		
		9.1	9.3	9.3	SUB-TOTAL KVA							KVA SUB-TOTAL	13.2	11.8	5.0		
												KVA GROSS-TOTAL	22.3	21.1	14.3		57.7

ALL 20A/1P BREAKERS SERVING RECEPTACLES SHALL BE GFI, CONTRACTOR FIELD VERIFY * SHUNT TRIP BREAKER FOR KITCHEN FIRE SUPPRESSION SYSTEM

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **ADP1** VOLTAGE: 480Y/277 AMPERES: 225 MCB 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
10	1"	0.1			TVSS	10	30/3	1	2	30/3	10	SOFTBALL LTG SS1	2.3			1 1/4"	10
			0.1					3	4					2.2			
				0.1				5	6						2.3		
10	1 1/4"	5.7			FOOTBALL LTG SF1	10	30/3	7	8	30/3	10	SOFTBALL LTG SS2	2.3			1 1/4"	10
			5.7					9	10					2.2			
				5.7				11	12						2.3		
10	1 1/4"	5.7			FOOTBALL LTG SF2	10	30/3	13	14	30/3	8	SOFTBALL LTG SS3	2.8			1 1/4"	8
			5.7					15	16					2.8			
				5.7				17	18						2.8		
8	1 1/4"	2.8			FOOTBALL LTG SF3	8	30/3	19	20	30/3	8	SOFTBALL LTG SS4	2.8			1 1/4"	8
			2.8					21	22					2.8			
				2.8				23	24						2.8		
8	1 1/4"	2.8			FOOTBALL LTG SF4	8	30/3	25	26			SPACE ONLY					
			2.8					27	28			SPACE ONLY					
				2.8				29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		18.1	18.1	18.1	SUB-TOTAL KVA							KVA SUB-TOTAL	11.2	11.1	11.2		
												KVA GROSS-TOTAL	29.3	29.2	29.3		87.8

PANELBOARD AND WIRING SCHEDULE - NEMA 3R

PANELBOARD: **ADP2** VOLTAGE: 480Y/277 AMPERES: 225 MCB 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
10	1"	0.1			TVSS	10	30/3	1	2	30/3	8	BASEBALL LTG SB2	2.8			1 1/4"	8
			0.1					3	4					2.8			
				0.1				5	6						2.8		
10	1 1/4"	2.8			BASEBALL LTG SB1	10	30/3	7	8	30/3	8	BASEBALL LTG SB4	5.7			1 1/4"	8
			2.8					9	10					5.7			
				2.8				11	12						5.7		
10	1 1/4"	5.7			BASEBALL LTG SB3	10	30/3	13	14	30/3	8	BASEBALL LTG SB6	2.8			1 1/4"	8
			5.7					15	16					2.8			
				5.7				17	18						2.8		
8	1 1/4"	2.8			BASEBALL LTG SB5	8	30/3	19	20	30/3	8	BASEBALL LTG SB8	2.8			1 1/4"	8
			2.8					21	22					2.8			
				2.8				23	24						2.8		
8	1 1/4"	2.8			BASEBALL LTG SB7	8	30/3	25	26			SPACE ONLY					
			2.8					27	28			SPACE ONLY					
				2.8				29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		15.2	15.2	15.2	SUB-TOTAL KVA							KVA SUB-TOTAL	15.1	15.1	15.1		
												KVA GROSS-TOTAL	30.3	30.3	30.3		90.9

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO: DATE

BWR KDM BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND – WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

PANEL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.: W91236-15-C-0023

NAVFAC DRAWING NO.: 13091425

SHEET 671 OF 789

E714

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **RP3A** | VOLTAGE: 208Y/120 | AMPERES: 150 | MLO | 3PH/4W | AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	0.4			RCPTS RM 1C00	12	20	1	2	20	12	MOTORIZED SHADES GYM	1.0			3/4"	12
12	3/4"		0.6		RCPTS RM 1C00	12	20	3	4	20	12	MOTORIZED SHADES GYM		1.0		3/4"	12
12	3/4"			0.4	RCPTS RM 1A01, 1A03	12	20	5	6	20	12	MOTORIZED SHADES GYM			1.0	3/4"	12
12	3/4"	1.0			CONNECTION FOR FACP	12	20	7	8	20	12	MOTORIZED SHADES GYM	1.0			3/4"	12
12	3/4"		1.0		CONNECTION FOR MNCP	12	20	9	10	20	12	MOTORIZED SHADES GYM		1.0		3/4"	12
12	3/4"			1.0	DOOR PWR SUPPLY	12	20	11	12	20	12	MOTORIZED SHADES GYM			1.0	3/4"	12
12	3/4"	0.7			PRINTER RECEPT 1A10	12	20/2	13	14	20	12	MOTORIZED SHADES GYM	1.0			3/4"	12
			0.7					15	16	20	12	MOTORIZED SHADES GYM		1.0		3/4"	12
12	3/4"			1.0	DURESS DIALER CONNECTION	12	20	17	18	20	12	MOTORIZED SHADES GYM			1.0	3/4"	12
12	3/4"	1.0			AV RACK POWER RM 1A12	12	20	19	20	20	12	MOTORIZED SHADES GYM	1.0			3/4"	12
12	3/4"		0.4		RCPTS RM 1C01	12	20	21	22	20	12	MOTORIZED SHADES GYM		1.0		3/4"	12
12	3/4"			1.0	CONNECTION FOR SECURITY I PANEL	12	20	23	24	20	12	MOTORIZED SHADES GYM			1.0	3/4"	12
12	3/4"	1.0			DOOR PWR SUPPLY 1C01	12	20	25	26	20	12	MOTORIZED SHADES GYM	1.0			3/4"	12
12	3/4"		1.0		DOOR PWR SUPPLY 1C03	12	20	27	28	20	12	SPACE ONLY				3/4"	12
12	3/4"			1.0	DOOR PWR SUPPLY 1C08	12	20	29	30	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	31	32	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	33	34	20	12	SPACE ONLY				3/4"	12
12	3/4'				SPACE ONLY	12	20	35	36	20	12	SPACE ONLY				3/4"	12
8	1"				SPACE ONLY	6	30	37	38	20	12	SPACE ONLY				3/4"	12
12	3/4'				SPACE ONLY	12	20	39	40	20	12	SPACE ONLY				3/4"	12
12	3/4'				SPACE ONLY	12	20	41	42	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	43	44	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	45	46	20	12	SPACE ONLY				3/4"	12
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		5.1	4.7	5.4	SUB-TOTAL KVA						KVA	SUB-TOTAL	6.0	5.0	5.0		
											KVA	GROSS-TOTAL	11.1	9.7	10.4		31.1

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **RP12A** | VOLTAGE: 208Y/120 | AMPERES: 150 | MCB | 3PH/4W | AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	1			DMX RACK	12	20	1	2	15	12	TP-3	0.4			3/4"	12
			1		DMX RACK	12	20	3	4	15	12	TP-3		0		3/4"	12
				0	SPACE ONLY			5	6			SPACE ONLY			0		
		0			SPACE ONLY			7	8			SPACE ONLY	0				
			0		SPACE ONLY			9	10			SPACE ONLY		0			
				0	SPACE ONLY			11	12			SPACE ONLY			0		
		0			SPACE ONLY			13	14			SPACE ONLY	0				
			0		SPACE ONLY			15	16			SPACE ONLY		0			
				0	SPACE ONLY			17	18			SPACE ONLY			0		
		0			SPACE ONLY			19	20			SPACE ONLY	0				
			0		SPACE ONLY			21	22			SPACE ONLY		0			
				0	SPACE ONLY			23	24			SPACE ONLY			0		
		0			SPACE ONLY			25	26			SPACE ONLY	0				
			0		SPACE ONLY			27	28			SPACE ONLY		0			
				0	SPACE ONLY			29	30			SPACE ONLY			0		
12	3/4"	1			DDC PANEL MECH 1C53	12	20	31	32			SPACE ONLY					
					SPACE ONLY		20	33	34			SPACE ONLY					
					SPACE ONLY		20	35	36			SPACE ONLY					
		1			SPARE		20	37	38	20		SPARE	1.0				
			1		SPARE		20	39	40	20		SPARE		1.0			
				1	SPARE		20	41	42	20		SPARE			1.0		
		3.0	2.0	1.0	SUB-TOTAL KVA						KVA	SUB-TOTAL	1.4	1.0	1.0		
											KVA	GROSS-TOTAL	4.4	3.0	2.0		9.4
											FED FROM						

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **RP2A** | VOLTAGE: 208Y/120 | AMPERES: 150 | MCB | 3PH/4W | AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"	0.8			RCPT BATTALION HQ 1C33	12	20	1	2	20		SPACE ONLY					
12	3/4"		0.8		RCPT BATTALION HQ 1C33	12	20	3	4	20		SPACE ONLY					
12	3/4"			0.8	RCPT BATTALION HQ 1C33	12	20	5	6	20		SPACE ONLY					
12	3/4"	0.8			RCPT BATTALION HQ 1C33	12	20	7	8	20		SPACE ONLY					
12	3/4"		0.8		RCPT BATTALION HQ 1C33	12	20	9	10	20		SPACE ONLY					
12	3/4"				SPACE ONLY	12	20	11	12	20		SPACE ONLY					
12	3/4"				SPACE ONLY		20	13	14	20		SPACE ONLY					
12	3/4"				SPACE ONLY		20	15	16	20		SPACE ONLY					
12	3/4"				SPACE ONLY		20	17	18	20		SPACE ONLY					
12	3/4"				SPACE ONLY		20	19	20	20		SPACE ONLY					
12	3/4"				SPACE ONLY		20	21	22	20		SPACE ONLY					
12	3/4"				SPACE ONLY		20	23	24	20		SPACE ONLY					
		1.0			SPARE		20	25	26	20		SPARE	1.0				
			1.0		SPARE		20	27	28	20		SPARE		1.0			
				1.0	SPARE		20	29	30	20		SPARE			1.0		
		2.6	2.6	1.8	SUB-TOTAL KVA						KVA	SUB-TOTAL	1.0	1.0	1.0		
											KVA	GROSS-TOTAL	3.6	3.6	2.8		10.0

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **MP9** | VOLTAGE: 480Y/277 | AMPERES: 225 | MLO | 3PH/4W | AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
12	3/4"				VHP12-1C55	12	15	1	2	20/3	12	OA-1 SUPPLY	3.0			3/4"	12
12	3/4"		1.9		VHP-24-1C47.1	12	15/3	3	4					3.0			
				1.9	-			5	6						3.0		
		1.9			-			7	8	20/3	12	OA-1 RETURN	3.0			3/4"	12
12	3/4"		3.6		VHP-42-1C49	12	15	9	10					3.0			
12	3/4"			0.6	FCU-2-1S05	12	15	11	12						3.0		
12	3/4"	0.6			FCU-2-1C00b	12	15	13	14	20/3	12	VHP-96 1C47	4.5			3/4"	12
					SPACE ONLY			15	16					4.5			
					SPACE ONLY			17	18						4.5		
					SPACE ONLY			19	20			SPACE ONLY					
					SPACE ONLY			21	22			SPACE ONLY					
					SPACE ONLY			23	24			SPACE ONLY					
					SPACE ONLY			25	26			SPACE ONLY					
					SPACE ONLY			27	28			SPACE ONLY					
					SPACE ONLY			29	30			SPACE ONLY					
					SPACE ONLY			31	32			SPACE ONLY					
					SPACE ONLY			33	34			SPACE ONLY					
					SPACE ONLY			35	36			SPACE ONLY					
					SPACE ONLY			37	38			SPACE ONLY					
					SPACE ONLY			39	40			SPACE ONLY					
					SPACE ONLY			41	42			SPACE ONLY					
					SPACE ONLY			43	44			SPACE ONLY					
					SPACE ONLY			45	46			SPACE ONLY					
					SPACE ONLY			47	48			SPACE ONLY					
		1.0			SPARE		20	49	50	20		SPARE	1.0				
			1.0		SPARE		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		3.5	6.5	3.5	SUB-TOTAL KVA						KVA	SUB-TOTAL	11.5	11.5	11.5		
											KVA	GROSS-TOTAL	15.0	18.0	15.0		48.1
											FED FROM	SDP3					

SYM | DESCRIPTION | DATE | APPR

SEAL: STATE OF KENTUCKY, BRADLEY WYNN REEVES, 20984, LICENSED PROFESSIONAL ENGINEER

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952
A/E INFO

APPROVED
FOR COMMANDER NAVFAC
ACTIVITY
SATISFACTORY TO DATE
BWR KDM BKB
PM/DM
BRANCH MANAGER
CHIEF ENG/ ARCH
FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
DoDEA
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

PANEL SCHEDULES

SCALE:
PROJECT NO.: P-021
CONSTR. CONTR. NO. W91236-15-C-0023
NAVFAC DRAWING NO. 13091426
SHEET 672 OF 789
E715

RTA SUBMISSION - 10/13/2016

DRAWFORM REVISION: 10 MARCH 2009

File Path

PANELBOARD AND WIRING SCHEDULE

PANELBOARD: **RP18A** VOLTAGE: 208Y/120 AMPERES: 150 MLO 3PH/4W AIC: 10,000

GND	CON	LOAD A	LOAD B	LOAD C	DESIGNATION	WIRE	BKR	CKT	CKT	BKR	WIRE	DESIGNATION	LOAD A	LOAD B	LOAD C	CON	GND
		1.0			FUTURE ELEC HANDDRYERS		20	1	2	20	12	CORD REELS HS CTE 2C05	0.4			3/4"	12
			1.0		FUTURE ELEC HANDDRYERS		20	3	4	20	12	CORD REELS HS CTE 2C05		0.4		3/4"	12
				1.0	FUTURE ELEC HANDDRYERS		20	5	6	20	12	CORD REELS HS CTE 2C05			0.4	3/4"	12
		1.0			FUTURE ELEC HANDDRYERS		20	7	8	20	12	CORD REELS HS CTE 2C05	0.4			3/4"	12
12	3/4"		0.4		RCPTS HS CTE 2C05	12	20	9	10	20	12	CORD REELS HS CTE 2C05		0.4		3/4"	12
12	3/4"			0.4	RCPTS HS CTE 2C05	12	20	11	12	20	12	CORD REELS HS CTE 2C05			0.4	3/4"	12
12	3/4"	0.4			RCPTS HS CTE 2C05	12	20	13	14	20	12	AIR MONITORING SYSTEM	1.0			3/4"	12
12	3/4"		0.8		RCPTS HS CTE 2C05	12	20	15	16	20	12	AIR MONITORING SYSTEM		1.0		3/4"	12
12	3/4"			0.8	RCPTS RM 2C07	12	20	17	18	20	12	RCPTS VIDEO BROAD 2C04			0.8	3/4"	12
12	3/4"	0.8			RCPTS RM 2C07	12	20	19	20	20	12	RCPTS VIDEO BROAD 2C04	0.6			3/4"	12
12	3/4"		0.8		RCPTS RM 2C07	12	20	21	22	20	12	RCPTS VIDEO BROAD 2C04		0.6		3/4"	12
12	3/4"			0.4	RCPTS RM SC04	12	20	23	24	20	12	POKE-THRU				3/4"	12
12	3/4"	0.4			RCPTS HS CTE 2C05	12	20	25	26	20	12	POKE-THRUS RM 2C09	1.1			3/4"	12
12	3/4"		0.8		RCPTS RM 2C07	12	20	27	28	20	12	RCPTS VIDEO BROAD 2C04		0.7		3/4"	12
12	3/4"			0.8	RCPTS RM 2C09	12	20	29	30	20	12	SPACE ONLY				3/4"	12
12	3/4"	0.8			RCPTS RM 2C09	12	20	31	32	20	12	SPACE ONLY				3/4"	12
12	3/4"		0.8		RCPTS RM 2C09	12	20	33	34	20	12	SPACE ONLY				3/4"	12
12	3/4"			0.8	RCPTS RM 2C09	12	20	35	36	20	12	SPACE ONLY				3/4"	12
12	3/4"	0.8			RCPTS RM 2C09	12	20	37	38	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	39	40	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	41	42	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	43	44	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	45	46	20	12	SPACE ONLY				3/4"	12
12	3/4"				SPACE ONLY	12	20	47	48			SPACE ONLY					
					SPACE ONLY		20	49	50	20		SPARE	1.0				
					SPACE ONLY		20	51	52	20		SPARE		1.0			
				1.0	SPARE		20	53	54	20		SPARE			1.0		
		5.2	4.6	5.2	SUB-TOTAL KVA							KVA SUB-TOTAL	4.5	4.1	2.6		
												KVA GROSS-TOTAL	9.7	8.7	7.8		26.2

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO DATE

BWR KDM BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA

NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA

MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

PANEL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO. W91236-15-C-0023

NAVFAC DRAWING NO. 13091427

SHEET 673 OF 789

E716

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR1	1	A	1	EQUIPMENT STORAGE 1C35	Data	Blue	125		
TR1	1	A	2	BATTALION HQ 1C33	Data	Blue	116		
TR1	1	A	3	BATTALION HQ 1C33	Data	Blue	116		
TR1	1	A	4	BATTALION HQ 1C33	Data	Blue	107		
TR1	1	A	5	BATTALION HQ 1C33	Data	Blue	107		
TR1	1	A	6	BATTALION HQ 1C33	Printer	Green	117		
TR1	1	A	7	JROTC 1C32	Data	Blue	126		
TR1	1	A	8	JROTC 1C32	Data	Blue	129		
TR1	1	A	9	JROTC 1C32	Data	Blue	129		
TR1	1	A	10	JROTC 1C32	Printer	Green	129		
TR1	1	A	11	JROTC 1C32	Data	Blue	157		
TR1	1	A	12	JROTC 1C32	Data	Blue	157		
TR1	1	A	13	JROTC 1C32	Data	Blue	146		
TR1	1	A	14	JROTC 1C32	Data	Blue	146		
TR1	1	A	15	JROTC 1C30	Data	Blue	128		
TR1	1	A	16	JROTC 1C30	Data	Blue	128		
TR1	1	A	17	JROTC 1C30	Data	Blue	118		
TR1	1	A	18	JROTC 1C30	Data	Blue	118		
TR1	1	A	19	JROTC 1C30	Data	Blue	90		
TR1	1	A	20	JROTC 1C30	Data	Blue	90		
TR1	1	A	21	JROTC 1C30	Printer	Green	90		
TR1	1	A	22	JROTC 1C30	Data	Blue	90		
TR1	1	A	23	STAFF WORK 1C31	Data	Blue	93		
TR1	1	A	24	STAFF WORK 1C31	Data	Blue	93		
TR1	1	A	25	STAFF WORK 1C31	Data	Blue	87		
TR1	1	A	26	STAFF WORK 1C31	Data	Blue	87		
TR1	1	A	27	STAFF WORK 1C31	Data	Blue	84		
TR1	1	A	28	STAFF WORK 1C31	Printer	Green	84		
TR1	1	A	29	STAFF WORK 1C31	Data	Blue	69		
TR1	1	A	30	JROTC STORAGE 1C29	Data	Blue	57		
TR1	1	A	31	MECH 1C27	Data	Blue	68		
TR1	1	A	32	MECH 1C27	Data	Blue	68		
TR1	1	A	33	TR1 1C25	Data	Blue	13		
TR1	1	A	34	TR1 1C25	Data	Blue	13		
TR1	1	A	35	AT WORKSPACE 1C23	Data	Blue	41		
TR1	1	A	36	AT WORKSPACE 1C23	Data	Blue	41		
TR1	1	A	37	AT WORKSPACE 1C23	Data	Blue	55		
TR1	1	A	38	AT WORKSPACE 1C23	Data	Blue	55		
TR1	1	A	39	AT WORKSPACE 1C23	Printer	Green	55		
TR1	1	A	40	ELECTRICAL 1C21	Data	Blue	58		
TR1	1	A	41	ELECTRICAL 1C21	Data	Blue	58		
TR1	1	A	42	CENTRAL STORAGE 1C19	Data	Blue	98		
TR1	1	A	43	RECEIVING 1C17	Data	Blue	99		
TR1	1	A	44	RECEIVING 1C17	Data	Blue	82		
TR1	1	A	45	RECEIVING 1C17	Data	Blue	82		
TR1	1	A	46	RECEIVING 1C17	Printer	Green	82		
TR1	1	A	47	TEAM STORAGE 1C10	Data	Blue	180		
TR1	1	A	48	TEAM STORAGE 1C10	Data	Blue	180		
TR1	1	B	1	TEAM STORAGE 1C19	Data	Blue	134		
TR1	1	B	2	TEAM STORAGE 1C19	Data	Blue	134		
TR1	1	B	3	ATHLETIC STORAGE 1C11	Data	Blue	170		
TR1	1	B	4	TRAINING ROOM 1C09	Data	Blue	169		
TR1	1	B	5	TRAINING ROOM 1C09	Data	Blue	183		
TR1	1	B	6	TRAINING ROOM 1C09	Printer	Green	183		
TR1	1	B	7	TRAINING ROOM 1C09	Data	Blue	172		
TR1	1	B	8	TRAINING ROOM 1C09	Data	Blue	172		
TR1	1	B	9	ATHLETIC WORK 1C26	Data	Blue	121		
TR1	1	B	10	ATHLETIC WORK 1C26	Data	Blue	121		
TR1	1	B	11	ATHLETIC WORK 1C26	Printer	Green	121		
TR1	1	B	12	PE STAFF COLLAB 1C22	Data	Blue	83		
TR1	1	B	13	PE STAFF COLLAB 1C22	Data	Blue	83		
TR1	1	B	14	PE STAFF COLLAB 1C22	Printer	Green	83		
TR1	1	B	15	TEAM ROOM 1C18.1	Data	Blue	105		
TR1	1	B	16	TEAM ROOM 1C18.1	Data	Blue	105		
TR1	1	B	17	TEAM ROOM 1C18.1	Data	Blue	117		
TR1	1	B	18	TEAM ROOM 1C18.1	Data	Blue	122		
TR1	1	B	19	TEAM ROOM 1C18.1	Data	Blue	122		
TR1	1	B	20	TEAM ROOM 1C18.1	Printer	Green	122		
TR1	1	B	21	WEIGHT ROOM 1C18	Data	Blue	81		
TR1	1	B	22	WEIGHT ROOM 1C18	Data	Blue	81		
TR1	1	B	23	WEIGHT ROOM 1C18	Data	Blue	92		
TR1	1	B	24	WEIGHT ROOM 1C18	Data	Blue	95		
TR1	1	B	25	WEIGHT ROOM 1C18	Data	Blue	95		
TR1	1	B	26	WEIGHT ROOM 1C18	Printer	Green	95		
TR1	1	B	27	MAINT OFFICE 1C16	Data	Blue	100		
TR1	1	B	28	MAINT OFFICE 1C16	Data	Blue	100		
TR1	1	B	29	MAINT OFFICE 1C16	Printer	Green	100		
TR1	1	B	30	GYM 1C03	Data	Blue	87		
TR1	1	B	31	GYM 1C03	Data	Blue	90		
TR1	1	B	32	GYM 1C03	Data	Blue	90		
TR1	1	B	33	GYM 1C03	Printer	Green	90		
TR1	1	B	34	GYM 1C03	Data	Blue	158		
TR1	1	B	35	GYM 1C03	Data	Blue	158		
TR1	1	B	36	GYM 1C03	Data	Blue	221		
TR1	1	B	37	GYM 1C03	Data	Blue	221		
TR1	1	B	38	GYM 1C03	Data	Blue	220		
TR1	1	B	39	GYM 1C03	Data	Blue	220		
TR1	1	B	40	GYM 1C03	Data	Blue	173		
TR1	1	B	41	GYM 1C03	Data	Blue	173		
TR1	1	B	42	GYM 1C03	Data	Blue	190		
TR1	1	B	43	GYM 1C03	Data	Blue	190		
TR1	1	B	44	MECH 1C05	Data	Blue	240		
TR1	1	B	45	MECH 1C05	Data	Blue	240		
TR1	1	B	46	MECH 1C07	Data	Blue	206		
TR1	1	B	47	MECH 1C07	Data	Blue	206		
TR1	1	B	48		Data	Blue			

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR1	1	C	1	FOOD SERVICE 1C04	Data	Blue	163		
TR1	1	C	2	FOOD SERVICE 1C04	Data	Blue	163		
TR1	1	C	3	KITCHEN OFFICE 1F04	Data	Blue	120		
TR1	1	C	4	KITCHEN OFFICE 1F04	Data	Blue	120		
TR1	1	C	5	KITCHEN OFFICE 1F04	Data	Blue	120		
TR1	1	C	6	KITCHEN OFFICE 1F04	Data	Blue	131		
TR1	1	C	7	KITCHEN OFFICE 1F04	Data	Blue	124		
TR1	1	C	8	FOOD SERVICE 1C04	Data	Blue	168		
TR1	1	C	9	FOOD SERVICE 1C04	Data	Blue	168		
TR1	1	C	10	FOOD SERVICE 1C04	Data	Blue	170		
TR1	1	C	11	FOOD SERVICE 1C04	Data	Blue	170		
TR1	1	C	12	COMMONS 1C01	Data	Blue	173		
TR1	1	C	13	COMMONS 1C01	Data	Blue	173		
TR1	1	C	14	COMMONS 1C01	Data	Blue	173		
TR1	1	C	15	COMMONS 1C01	Data	Blue	173		
TR1	1	C	16	COMMONS 1C01	Data	Blue	167		
TR1	1	C	17	COMMONS 1C01	Data	Blue	167		
TR1	1	C	18	AT WORKSPACE 1C23	Data	Blue	48		
TR1	1	C	19	AT WORKSPACE 1C23	Data	Blue	48		
TR1	1	C	20	AT WORKSPACE 1C23	Data	Blue	56		
TR1	1	C	21	AT WORKSPACE 1C23	Data	Blue	56		
TR1	1	C	22	ATHLETIC STORAGE 1C11	Data	Blue	164		
TR1	1	C	23	FOOD SERVICE 1C04	Data	Blue	133		
TR1	1	C	24		Data	Blue			
TR1	1	C	25		Data	Blue			
TR1	1	C	26		Data	Blue			
TR1	1	C	27		Data	Blue			
TR1	1	C	28		Data	Blue			
TR1	1	C	29		Data	Blue			
TR1	1	C	30		Data	Blue			
TR1	1	C	31		Data	Blue			
TR1	1	C	32		Data	Blue			
TR1	1	C	33		Data	Blue			
TR1	1	C	34		Data	Blue			
TR1	1	C	35		Data	Blue			
TR1	1	C	36		Data	Blue			
TR1	1	C	37		Data	Blue			
TR1	1	C	38		Data	Blue			
TR1	1	C	39		Data	Blue			
TR1	1	C	40		Data	Blue			
TR1	1	C	41		Data	Blue			
TR1	1	C	42		Data	Blue			
TR1	1	C	43		Data	Blue			
TR1	1	C	44		Data	Blue			
TR1	1	C	45		Data	Blue			
TR1	1	C	46		Data	Blue			
TR1	1	C	47		Data	Blue			
TR1	1	C	48		Data	Blue			
TR1	1	D	1		Data	Blue			
TR1	1	D	2		Data	Blue			
TR1	1	D	3		Data	Blue			
TR1	1	D	4		Data	Blue			
TR1	1	D	5		Data	Blue			
TR1	1	D	6		Data	Blue			
TR1	1	D	7		Data	Blue			
TR1	1	D	8		Data	Blue			
TR1	1	D	9		Data	Blue			
TR1	1	D	10		Data	Blue			
TR1	1	D	11		Data	Blue			
TR1	1	D	12		Data	Blue			
TR1	1	D	13		Data	Blue			
TR1	1	D	14		Data	Blue			
TR1	1	D	15		Data	Blue			
TR1	1	D	16		Data	Blue			
TR1	1	D	17		Data	Blue			
TR1	1	D	18		Data	Blue			
TR1	1	D	19		Data	Blue			
TR1	1	D	20		Data	Blue			
TR1	1	D	21		Data	Blue			
TR1	1	D	22		Data	Blue			
TR1	1	D	23		Data	Blue			
TR1	1	D	24		Data	Blue			
TR1	1	D	25		Data	Blue			
TR1	1	D	26		Data	Blue			
TR1	1	D	27		Data	Blue			
TR1	1	D	28		Data	Blue			
TR1	1	D	29		Data	Blue			
TR1	1	D	30		Data	Blue			
TR1	1	D	31		Data	Blue			
TR1	1	D	32		Data	Blue			
TR1	1	D	33		Data	Blue			
TR1	1	D	34		Data	Blue			
TR1	1	D	35		Data	Blue			
TR1	1	D	36		Data	Blue			
TR1	1	D	37		Data	Blue			
TR1	1	D	38		Data	Blue			
TR1	1	D	39		Data	Blue			
TR1	1	D	40		Data	Blue			
TR1	1	D	41		Data	Blue			
TR1	1	D	42		Data	Blue			
TR1	1	D	43		Data	Blue			
TR1	1	D	44		Data	Blue			
TR1	1	D	45		Data	Blue			
TR1	1	D	46		Data	Blue			
TR1	1	D	47		Data	Blue			
TR1	1	D	48		Data	Blue			

APPR. | DATE | DESCRIPTION | STM

NAVFAC

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO DATE

BWR XDM BKB

PMDM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
MARINE CORPS BASE QUANTICO
MARINE CORPS BASE QUANTICO, VIRGINIA
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091428

SHEET 674 OF 789

E717

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR1	2	A	1	JROTC 1C32	Video	Red	126		
TR1	2	A	2	JROTC 1C30	Video	Red	90		
TR1	2	A	3	STAFF WORK 1C31	Video	Red	69		
TR1	2	A	4	RECEIVING 1C17	Video	Red	86		
TR1	2	A	5		Video	Red			
TR1	2	A	6	ATHLETIC WORK 1C26	Video	Red	113		
TR1	2	A	7	PE STAFF COLLAB 1C22	Video	Red	79		
TR1	2	A	8	PE STAFF COLLAB 1C22	Video	Red	71		
TR1	2	A	9	TEAM ROOM 1C18.1	Video	Red	77		
TR1	2	A	10	TEAM ROOM 1C18.1	Video	Red	117		
TR1	2	A	11	WEIGHT ROOM 1C18	Video	Red	92		
TR1	2	A	12	GYM 1C03	Video	Red	87		
TR1	2	A	13	GYM 1C03	Video	Red	160		
TR1	2	A	14	FOOD SERVICE 1C04	Video	Red	189		
TR1	2	A	15	FOOD SERVICE 1C04	Video	Red	180		
TR1	2	A	16	KITCHEN OFFICE 1F04	Video	Red	117		
TR1	2	A	17	FOOD SERVICE 1C04	Video	Red	104		
TR1	2	A	18	BATALLION HQ 1C33	Video	Red	117		
TR1	2	A	19		Video	Red			
TR1	2	A	20		Video	Red			
TR1	2	A	21		Video	Red			
TR1	2	A	22		Video	Red			
TR1	2	A	23		Video	Red			
TR1	2	A	24		Video	Red			
TR1	2	A	25		Video	Red			
TR1	2	A	26		Video	Red			
TR1	2	A	27		Video	Red			
TR1	2	A	28		Video	Red			
TR1	2	A	29		Video	Red			
TR1	2	A	30		Video	Red			
TR1	2	A	31		Video	Red			
TR1	2	A	32		Video	Red			
TR1	2	A	33		Video	Red			
TR1	2	A	34		Video	Red			
TR1	2	A	35		Video	Red			
TR1	2	A	36		Video	Red			
TR1	2	A	37		Video	Red			
TR1	2	A	38		Video	Red			
TR1	2	A	39		Video	Red			
TR1	2	A	40		Video	Red			
TR1	2	A	41		Video	Red			
TR1	2	A	42		Video	Red			
TR1	2	A	43		Video	Red			
TR1	2	A	44		Video	Red			
TR1	2	A	45		Video	Red			
TR1	2	A	46		Video	Red			
TR1	2	A	47		Video	Red			
TR1	2	A	48		Video	Red			
TR1	2	B	1	EQUIPMENT STORAGE 1C35	Voice	Yellow	119		
TR1	2	B	2	JROTC 1C32	Voice	Yellow	115		
TR1	2	B	3	JROTC 1C30	Voice	Yellow	101		
TR1	2	B	4	STAFF WORKSPACE 1C31	Voice	Yellow	97		
TR1	2	B	5	JROTC STORAGE 1C29	Voice	Yellow	60		
TR1	2	B	6	MECH 1C27	Voice	Yellow	65		
TR1	2	B	7	TR1 1C25	Voice	Yellow	12		
TR1	2	B	8	AT WORKSPACE 1C23	Voice	Yellow	47		
TR1	2	B	9	ELEC 1C21	Voice	Yellow	56		
TR1	2	B	10	RECEIVING 1C17	Voice	Yellow	76		
TR1	2	B	11	TRAINING ROOM 1C09	Voice	Yellow	180		
TR1	2	B	12	ATHLETIC WORK 1C26	Voice	Yellow	123		
TR1	2	B	13	PE STAFF COLLAB 1C22	Voice	Yellow	78		
TR1	2	B	14	PE STAFF COLLAB 1C22	Voice	Yellow	78		
TR1	2	B	15	TEAM ROOM 1C18.1	Voice	Yellow	90		
TR1	2	B	16	WEIGHT ROOM 1C18	Voice	Yellow	50		
TR1	2	B	17	MAINTENANCE 1C16	Voice	Yellow	100		
TR1	2	B	18	GYM 1C03	Voice	Yellow	189		
TR1	2	B	19	MECH 1C05	Voice	Yellow	238		
TR1	2	B	20	MECH 1C07	Voice	Yellow	204		
TR1	2	B	21	FOODSERVICE 1C04	Voice	Yellow	187		
TR1	2	B	22	FOODSERVICE 1C04	Voice	Yellow	163		
TR1	2	B	23	KITCHEN OFFICE 1F04	Voice	Yellow	114		
TR1	2	B	24	BATALLION HQ 1C33	Voice	Yellow	117		
TR1	2	B	25	FOODSERVICE 1C04	Voice	Yellow	133		
TR1	2	B	26	FOODSERVICE 1C04	Voice	Yellow	116		
TR1	2	B	27		Voice	Yellow			
TR1	2	B	28		Voice	Yellow			
TR1	2	B	29		Voice	Yellow			
TR1	2	B	30		Voice	Yellow			
TR1	2	B	31		Voice	Yellow			
TR1	2	B	32		Voice	Yellow			
TR1	2	B	33		Voice	Yellow			
TR1	2	B	34		Voice	Yellow			
TR1	2	B	35		Voice	Yellow			
TR1	2	B	36		Voice	Yellow			
TR1	2	B	37		Voice	Yellow			
TR1	2	B	38		Voice	Yellow			
TR1	2	B	39		Voice	Yellow			
TR1	2	B	40		Voice	Yellow			
TR1	2	B	41		Voice	Yellow			
TR1	2	B	42		Voice	Yellow			
TR1	2	B	43		Voice	Yellow			
TR1	2	B	44		Voice	Yellow			
TR1	2	B	45		Voice	Yellow			
TR1	2	B	46		Voice	Yellow			
TR1	2	B	47		Voice	Yellow			
TR1	2	B	48		Voice	Yellow			

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR1	2	C	1	JROTC 1C32	Wireless	Orange	150		
TR1	2	C	2	JROTC 1C32	Wireless	Orange	150		
TR1	2	C	3	JROTC 1C30	Wireless	Orange	120		
TR1	2	C	4	JROTC 1C30	Wireless	Orange	120		
TR1	2	C	5	STAFF WORKSPACE 1C31	Wireless	Orange	40		
TR1	2	C	6	STAFF WORKSPACE 1C31	Wireless	Orange	40		
TR1	2	C	7	ATHLETIC WORKROOM 1C26	Wireless	Orange	118		
TR1	2	C	8	ATHLETIC WORKROOM 1C26	Wireless	Orange	118		
TR1	2	C	9	PE STAFF COLLAB 1C22	Wireless	Orange	82		
TR1	2	C	10	PE STAFF COLLAB 1C22	Wireless	Orange	82		
TR1	2	C	11	MAINTENANCE OFFICE 1C16	Wireless	Orange	92		
TR1	2	C	12	MAINTENANCE OFFICE 1C16	Wireless	Orange	92		
TR1	2	C	13	GYM 1C03	Wireless	Orange	180		
TR1	2	C	14	GYM 1C03	Wireless	Orange	180		
TR1	2	C	15	GYM 1C03	Wireless	Orange	184		
TR1	2	C	16	GYM 1C03	Wireless	Orange	184		
TR1	2	C	17	KITCHEN OFFICE 1F04	Wireless	Orange	122		
TR1	2	C	18	KITCHEN OFFICE 1F04	Wireless	Orange	122		
TR1	2	C	19		Wireless	Orange			
TR1	2	C	20		Wireless	Orange			
TR1	2	C	21		Wireless	Orange			
TR1	2	C	22		Wireless	Orange			
TR1	2	C	23		Wireless	Orange			
TR1	2	C	24		Wireless	Orange			
TR1	2	C	25		Wireless	Orange			
TR1	2	C	26		Wireless	Orange			
TR1	2	C	27		Wireless	Orange			
TR1	2	C	28		Wireless	Orange			
TR1	2	C	29		Wireless	Orange			
TR1	2	C	30		Wireless	Orange			
TR1	2	C	31		Wireless	Orange			
TR1	2	C	32		Wireless	Orange			
TR1	2	C	33		Wireless	Orange			
TR1	2	C	34		Wireless	Orange			
TR1	2	C	35		Wireless	Orange			
TR1	2	C	36		Wireless	Orange			
TR1	2	C	37		Wireless	Orange			
TR1	2	C	38		Wireless	Orange			
TR1	2	C	39		Wireless	Orange			
TR1	2	C	40		Wireless	Orange			
TR1	2	C	41		Wireless	Orange			
TR1	2	C	42		Wireless	Orange			
TR1	2	C	43		Wireless	Orange			
TR1	2	C	44		Wireless	Orange			
TR1	2	C	45		Wireless	Orange			
TR1	2	C	46		Wireless	Orange			
TR1	2	C	47		Wireless	Orange			
TR1	2	C	48		Wireless	Orange			

APPR | DATE | DESCRIPTION | SYM

NAVFAC

STATE OF KENTUCKY
ZBRADLEY ALLEN REEVES
20...
PROFESSIONAL ENGINEER

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO: DATE

BWR KDM BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091429

SHEET 675 OF 789

E718

DRAWFORM REVISION: 12 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR2	1	A	1	LEARNING STUDIO 1B12	Data	Blue	153		
TR2	1	A	2	LEARNING STUDIO 1B12	Data	Blue	153		
TR2	1	A	3	LEARNING STUDIO 1B12	Printer	Green	153		
TR2	1	A	4	LEARNING STUDIO 1B12	Data	Blue	169		
TR2	1	A	5	LEARNING STUDIO 1B12	Data	Blue	185		
TR2	1	A	6	LEARNING STUDIO 1B12	Data	Blue	185		
TR2	1	A	7	LEARNING STUDIO 1B12	Data	Blue	193		
TR2	1	A	8	LEARNING STUDIO 1B12	Data	Blue	193		
TR2	1	A	9	LEARNING STUDIO 1B14	Data	Blue	215		
TR2	1	A	10	LEARNING STUDIO 1B14	Data	Blue	215		
TR2	1	A	11	LEARNING STUDIO 1B14	Data	Blue	225		
TR2	1	A	12	LEARNING STUDIO 1B14	Data	Blue	225		
TR2	1	A	13	LEARNING STUDIO 1B14	Data	Blue	226		
TR2	1	A	14	LEARNING STUDIO 1B14	Data	Blue	218		
TR2	1	A	15	LEARNING STUDIO 1B14	Data	Blue	218		
TR2	1	A	16	LEARNING STUDIO 1B14	Printer	Green	218		
TR2	1	A	17	LEARNING STUDIO 1B18	Data	Blue	218		
TR2	1	A	18	LEARNING STUDIO 1B18	Data	Blue	218		
TR2	1	A	19	LEARNING STUDIO 1B18	Printer	Green	218		
TR2	1	A	20	LEARNING STUDIO 1B18	Data	Blue	235		
TR2	1	A	21	LEARNING STUDIO 1B18	Data	Blue	240		
TR2	1	A	22	LEARNING STUDIO 1B18	Data	Blue	240		
TR2	1	A	23	LEARNING STUDIO 1B18	Data	Blue	232		
TR2	1	A	24	LEARNING STUDIO 1B18	Data	Blue	232		
TR2	1	A	25	LEARNING STUDIO 1D16	Data	Blue	216		
TR2	1	A	26	LEARNING STUDIO 1D16	Data	Blue	216		
TR2	1	A	27	LEARNING STUDIO 1D16	Data	Blue	208		
TR2	1	A	28	LEARNING STUDIO 1D16	Data	Blue	208		
TR2	1	A	29	LEARNING STUDIO 1D16	Data	Blue	194		
TR2	1	A	30	LEARNING STUDIO 1D16	Data	Blue	194		
TR2	1	A	31	LEARNING STUDIO 1D16	Printer	Green	194		
TR2	1	A	32	LEARNING STUDIO 1D16	Data	Blue	180		
TR2	1	A	33	LEARNING STUDIO 1D14	Data	Blue	172		
TR2	1	A	34	LEARNING STUDIO 1D14	Data	Blue	172		
TR2	1	A	35	LEARNING STUDIO 1D14	Printer	Green	172		
TR2	1	A	36	LEARNING STUDIO 1D14	Data	Blue	189		
TR2	1	A	37	LEARNING STUDIO 1D14	Data	Blue	206		
TR2	1	A	38	LEARNING STUDIO 1D14	Data	Blue	206		
TR2	1	A	39	LEARNING STUDIO 1D14	Data	Blue	215		
TR2	1	A	40	LEARNING STUDIO 1D14	Data	Blue	215		
TR2	1	A	41	LEARNING STUDIO 1D12	Data	Blue	194		
TR2	1	A	42	LEARNING STUDIO 1D12	Data	Blue	194		
TR2	1	A	43	LEARNING STUDIO 1D12	Data	Blue	184		
TR2	1	A	44	LEARNING STUDIO 1D12	Data	Blue	184		
TR2	1	A	45	LEARNING STUDIO 1D12	Data	Blue	162		
TR2	1	A	46	LEARNING STUDIO 1D12	Data	Blue	162		
TR2	1	A	47	LEARNING STUDIO 1D12	Printer	Green	162		
TR2	1	A	48	LEARNING STUDIO 1D12	Data	Blue	151		
TR2	1	B	1	MECH 1D13	Data	Blue	144		
TR2	1	B	2	MECH 1D13	Data	Blue	144		
TR2	1	B	3	LEARNING STUDIO 1D10	Data	Blue	138		
TR2	1	B	4	LEARNING STUDIO 1D10	Data	Blue	138		
TR2	1	B	5	LEARNING STUDIO 1D10	Printer	Green	138		
TR2	1	B	6	LEARNING STUDIO 1D10	Data	Blue	148		
TR2	1	B	7	LEARNING STUDIO 1D10	Data	Blue	167		
TR2	1	B	8	LEARNING STUDIO 1D10	Data	Blue	167		
TR2	1	B	9	LEARNING STUDIO 1D10	Data	Blue	180		
TR2	1	B	10	LEARNING STUDIO 1D10	Data	Blue	180		
TR2	1	B	11	LEARNING STUDIO 1D08	Data	Blue	177		
TR2	1	B	12	LEARNING STUDIO 1D08	Data	Blue	177		
TR2	1	B	13	LEARNING STUDIO 1D08	Data	Blue	172		
TR2	1	B	14	LEARNING STUDIO 1D08	Data	Blue	172		
TR2	1	B	15	LEARNING STUDIO 1D08	Data	Blue	150		
TR2	1	B	16	LEARNING STUDIO 1D08	Data	Blue	150		
TR2	1	B	17	LEARNING STUDIO 1D08	Printer	Green	150		
TR2	1	B	18	LEARNING STUDIO 1D08	Data	Blue	127		
TR2	1	B	19	HS CHEMISTRY 1D06	Data	Blue	200		
TR2	1	B	20	HS CHEMISTRY 1D06	Data	Blue	200		
TR2	1	B	21	HS CHEMISTRY 1D06	Data	Blue	205		
TR2	1	B	22	HS CHEMISTRY 1D06	Data	Blue	205		
TR2	1	B	23	HS CHEMISTRY 1D06	Data	Blue	209		
TR2	1	B	24	HS CHEMISTRY 1D06	Data	Blue	209		
TR2	1	B	25	HS CHEMISTRY 1D06	Data	Blue	226		
TR2	1	B	26	HS CHEMISTRY 1D06	Data	Blue	226		
TR2	1	B	27	HS CHEMISTRY 1D06	Data	Blue	223		
TR2	1	B	28	HS CHEMISTRY 1D06	Data	Blue	223		
TR2	1	B	29	HS CHEMISTRY 1D06	Data	Blue	219		
TR2	1	B	30	HS CHEMISTRY 1D06	Data	Blue	219		
TR2	1	B	31	HS CHEMISTRY 1D06	Data	Blue	188		
TR2	1	B	32	HS CHEMISTRY 1D06	Data	Blue	188		
TR2	1	B	33	HS CHEMISTRY 1D06	Printer	Green	188		
TR2	1	B	34	HS CHEMISTRY 1D06	Data	Blue	173		
TR2	1	B	35	ENTRY CORR 1C00	Data	Blue	199		
TR2	1	B	36	ENTRY CORR 1C00	Data	Blue	199		
TR2	1	B	37	ENTRY CORR 1C00	Data	Blue	188		
TR2	1	B	38	ENTRY CORR 1C00	Data	Blue	188		
TR2	1	B	39	SCI PREP 1D03	Data	Blue	166		
TR2	1	B	40	SCI PREP 1D03	Data	Blue	166		
TR2	1	B	41	HS PHYSICAL SCIENCE 1D04	Data	Blue	194		
TR2	1	B	42	HS PHYSICAL SCIENCE 1D04	Data	Blue	194		
TR2	1	B	43	HS PHYSICAL SCIENCE 1D04	Data	Blue	189		
TR2	1	B	44	HS PHYSICAL SCIENCE 1D04	Data	Blue	189		
TR2	1	B	45	HS PHYSICAL SCIENCE 1D04	Data	Blue	172		
TR2	1	B	46	HS PHYSICAL SCIENCE 1D04	Data	Blue	172		
TR2	1	B	47	HS PHYSICAL SCIENCE 1D04	Data	Blue	162		
TR2	1	B	48	HS PHYSICAL SCIENCE 1D04	Data	Blue	162		

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR2	1	C	1	HS PHYSICAL SCIENCE 1D04	Data	Blue	151		
TR2	1	C	2	HS PHYSICAL SCIENCE 1D04	Data	Blue	151		
TR2	1	C	3	HS PHYSICAL SCIENCE 1D04	Data	Blue	138		
TR2	1	C	4	HS PHYSICAL SCIENCE 1D04	Data	Blue	138		
TR2	1	C	5	HS PHYSICAL SCIENCE 1D04	Data	Blue	164		
TR2	1	C	6	HS PHYSICAL SCIENCE 1D04	Data	Blue	168		
TR2	1	C	7	HS PHYSICAL SCIENCE 1D04	Data	Blue	168		
TR2	1	C	8	HS PHYSICAL SCIENCE 1D04	Printer	Green	168		
TR2	1	C	9	STAFF COLLAB 1E00	Data	Blue	124		
TR2	1	C	10	STAFF COLLAB 1E00	Data	Blue	124		
TR2	1	C	11	STAFF COLLAB 1E00	Printer	Green	124		
TR2	1	C	12	STAFF COLLAB 1E00	Data	Blue	114		
TR2	1	C	13	STAFF COLLAB 1E00	Data	Blue	114		
TR2	1	C	14	STAFF COLLAB 1E00	Printer	Green	114		
TR2	1	C	15	STAFF COLLAB 1E00	Data	Blue	117		
TR2	1	C	16	STAFF COLLAB 1E00	Data	Blue	90		
TR2	1	C	17	STAFF COLLAB 1E00	Data	Blue	90		
TR2	1	C	18	STAFF COLLAB 1E00	Data	Blue	90		
TR2	1	C	19	STAFF COLLAB 1E00	Data	Blue	90		
TR2	1	C	20	STAFF COLLAB 1E00	Data	Blue	67		
TR2	1	C	21	STAFF COLLAB 1E00	Data	Blue	67		
TR2	1	C	22	STAFF COLLAB 1E00	Data	Blue	67		
TR2	1	C	23	STAFF COLLAB 1E00	Data	Blue	67		
TR2	1	C	24	STAFF COLLAB 1E00	Data	Blue	76		
TR2	1	C	25	STAFF COLLAB 1E00	Data	Blue	76		
TR2	1	C	26	STAFF COLLAB 1E00	Data	Blue	76		
TR2	1	C	27	STAFF COLLAB 1E00	Data	Blue	76		
TR2	1	C	28	STAFF COLLAB 1E00	Data	Blue	88		
TR2	1	C	29	STAFF COLLAB 1E00	Data	Blue	88		
TR2	1	C	30	STAFF COLLAB 1E00	Data	Blue	88		
TR2	1	C	31	STAFF COLLAB 1E00	Data	Blue	88		
TR2	1	C	32	STAFF COLLAB 1E00	Data	Blue	72		
TR2	1	C	33	STAFF COLLAB 1E00	Data	Blue	72		
TR2	1	C	34	STAFF COLLAB 1E00	Data	Blue	72		
TR2	1	C	35	STAFF COLLAB 1E00	Data	Blue	72		
TR2	1	C	36		Data	Blue	94		
TR2	1	C	37		Data	Blue			
TR2	1	C	38		Data	Blue			
TR2	1	C	39		Data	Blue			
TR2	1	C	40		Data	Blue			
TR2	1	C	41		Data	Blue			
TR2	1	C	42		Data	Blue			
TR2	1	C	43		Data	Blue			
TR2	1	C	44		Data	Blue			
TR2	1	C	45		Data	Blue			
TR2	1	C	46		Data	Blue			
TR2	1	C	47		Data	Blue			
TR2	1	C	48		Data	Blue			
TR2	1	D	1		Data	Blue			
TR2	1	D	2		Data	Blue			
TR2	1	D	3		Data	Blue			
TR2	1	D	4		Data	Blue			
TR2	1	D	5		Data	Blue			
TR2	1	D	6		Data	Blue			
TR2	1	D	7		Data	Blue			
TR2	1	D	8		Data	Blue			
TR2	1	D	9	OT/PT GROSS 1B02	Data	Blue	157		
TR2	1	D	10	OT/PT GROSS 1B02	Data	Blue	157		
TR2	1	D	11	OT/PT GROSS 1B02	Data	Blue	162		
TR2	1	D	12	OT/PT GROSS 1B02	Data	Blue	162		
TR2	1	D	13	OT/PT GROSS 1B02	Data	Blue	174		
TR2	1	D	14	OT/PT GROSS 1B02	Data	Blue	174		
TR2	1	D	15	OT/PT GROSS 1B02	Data	Blue	179		
TR2	1	D	16	OT/PT GROSS 1B02	Data	Blue	179		
TR2	1	D	17	OT/PT GROSS 1B02	Data	Blue	182		
TR2	1	D	18	OT/PT GROSS 1B02	Data	Blue	182		
TR2	1	D	19	OT/PT GROSS 1B02	Data	Blue	162		
TR2	1	D	20	OT/PT GROSS 1B02	Data	Blue	162		
TR2	1	D	21	OT/PT GROSS 1B02	Printer	Green	162		
TR2	1	D	22	OT/PT GROSS 1B02	Data	Blue	167		
TR2	1	D	23	OT/PT FINE 1B06	Data	Blue	137		
TR2	1	D	24	OT/PT FINE 1B06	Data	Blue	137		
TR2	1	D	25	OT/PT FINE 1B06	Data	Blue	142		
TR2	1	D	26	OT/PT FINE 1B06	Data	Blue	142		
TR2	1	D	27	OT/PT FINE 1B06	Data	Blue	131		
TR2	1	D	28	OT/PT FINE 1B06	Data	Blue	131		
TR2	1	D	29	MS ONE TO ONE 1B04	Data	Blue	120		
TR2	1	D	30	MS ONE TO ONE 1B04	Data	Blue	120		
TR2	1	D	31	MS ONE TO ONE 1B04	Data	Blue	130		
TR2	1	D	32	MS ONE TO ONE 1B04	Data	Blue	128		
TR2	1	D	33	MS ONE TO ONE 1B04	Data	Blue	128		
TR2	1	D	34	FIRE 1B05	Data	Blue	174		
TR2	1	D	35	LEARNING STUDIO 1B08	Data	Blue	148		
TR2	1	D	36	LEARNING STUDIO 1B08	Data	Blue	155		
TR2	1	D	37	LEARNING STUDIO 1B08	Data	Blue	155		
TR2	1	D	38	LEARNING STUDIO 1B08	Printer	Green	155		
TR2	1	D	39	LEARNING STUDIO 1B08	Data	Blue	173		
TR2	1	D	40	LEARNING STUDIO 1B08	Data	Blue	173		
TR2	1	D	41	LEARNING STUDIO 1B08	Data	Blue	195		
TR2	1	D	42	LEARNING STUDIO 1B08	Data	Blue	195		
TR2	1	D	43	LEARNING STUDIO 1B10	Data	Blue	185		
TR2	1	D	44	LEARNING STUDIO 1B10	Data	Blue	185		
TR2	1	D	45	LEARNING STUDIO 1B10	Data	Blue	175		
TR2	1	D	46	LEARNING STUDIO 1B10	Data	Blue	175		
TR2	1	D	47	LEARNING STUDIO 1B10	Data	Blue	153		
TR2	1	D	48	LEARNING STUDIO 1B10	Data	Blue	153		

SYM | DESCRIPTION | DATE | APPR

NAVFAC

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO DATE
BWR KDM BKB
PM/DM
BRANCH MANAGER
CHIEF ENG/ ARCH
FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
DoDEA
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:
PROJECT NO.: P-021
CONSTR. CONTR. NO. W91236-15-C-0023
NAVFAC DRAWING NO. 13091430
SHEET 676 OF 789
E719

RTA SUBMISSION - 10/13/2016

DRAWFORM REVISION: 10 MARCH 2009

File Path

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR2	1	E	1	LEARNING STUDIO 1B10	Printer	Green	153		
TR2	1	E	2	LEARNING STUDIO 1B10	Data	Blue	140		
TR2	1	E	3	MECH 1B07	Data	Blue	151		
TR2	1	E	4	MECH 1B07	Data	Blue	151		
TR2	1	E	5	MS HUB 1B00	Data	Blue	100		
TR2	1	E	6	MS HUB 1B00	Data	Blue	100		
TR2	1	E	7	MS HUB 1B00	Data	Blue	110		
TR2	1	E	8	MS HUB 1B00	Data	Blue	110		
TR2	1	E	9	MS HUB 1B00	Data	Blue	72		
TR2	1	E	10	MS HUB 1B00	Data	Blue	77		
TR2	1	E	11	MS HUB 1B00	Data	Blue	77		
TR2	1	E	12	MS HUB 1B00	Printer	Green	77		
TR2	1	E	13	FLEX HUB 1D01	Data	Blue	74		
TR2	1	E	14	FLEX HUB 1D01	Data	Blue	74		
TR2	1	E	15	FLEX HUB 1D01	Data	Blue	68		
TR2	1	E	16	FLEX HUB 1D01	Data	Blue	68		
TR2	1	E	17	FLEX HUB 1D01	Data	Blue	62		
TR2	1	E	18	FLEX HUB 1D01	Data	Blue	62		
TR2	1	E	19	FLEX HUB 1D01	Data	Blue	59		
TR2	1	E	20	FLEX HUB 1D01	Data	Blue	59		
TR2	1	E	21	FLEX HUB 1D01	Printer	Green	59		
TR2	1	E	22	FLEX HUB 1D01	Data	Blue	61		
TR2	1	E	23	FLEX HUB 1D01	Data	Blue	64		
TR2	1	E	24	FLEX HUB 1D01	Data	Blue	64		
TR2	1	E	25		Data	Blue			
TR2	1	E	26		Data	Blue			
TR2	1	E	27		Data	Blue			
TR2	1	E	28		Data	Blue			
TR2	1	E	29		Data	Blue			
TR2	1	E	30		Data	Blue			
TR2	1	E	31		Data	Blue			
TR2	1	E	32		Data	Blue			
TR2	1	E	33		Data	Blue			
TR2	1	E	34		Data	Blue			
TR2	1	E	35		Data	Blue			
TR2	1	E	36		Data	Blue			
TR2	1	E	37		Data	Blue			
TR2	1	E	38		Data	Blue			
TR2	1	E	39		Data	Blue			
TR2	1	E	40		Data	Blue			
TR2	1	E	41		Data	Blue			
TR2	1	E	42		Data	Blue			
TR2	1	E	43		Data	Blue			
TR2	1	E	44		Data	Blue			
TR2	1	E	45		Data	Blue			
TR2	1	E	46		Data	Blue			
TR2	1	E	47		Data	Blue			
TR2	1	E	48		Data	Blue			

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR2	2	A	1	LEARNING STUDIO 1B12	Video	Red	169		
TR2	2	A	2	LEARNING STUDIO 1B14	Video	Red	226		
TR2	2	A	3	LEARNING STUDIO 1D18	Video	Red	235		
TR2	2	A	4	LEARNING STUDIO 1D16	Video	Red	180		
TR2	2	A	5	LEARNING STUDIO 1D14	Video	Red	189		
TR2	2	A	6	LEARNING STUDIO 1D12	Video	Red	151		
TR2	2	A	7	LEARNING STUDIO 1D10	Video	Red	148		
TR2	2	A	8	LEARNING STUDIO 1D08	Video	Red	127		
TR2	2	A	9	HS CHEMISTRY 1D06	Video	Red	173		
TR2	2	A	10	ENTRY CORR 1C00	Video	Red	205		
TR2	2	A	11	HS PHYSICAL SCIENCE 1D04	Video	Red	164		
TR2	2	A	12	STAFF COLLAB 1E01	Video	Red	114		
TR2	2	A	13	STAFF COLLAB 1E01	Video	Red	85		
TR2	2	A	14	STAFF COLLAB 1E01	Video	Red	91		
TR2	2	A	15	STAFF COLLAB 1E01	Video	Red	117		
TR2	2	A	16	OT/PT GROSS 1B02	Video	Red	167		
TR2	2	A	17	MS ONE TO ONE 1B04	Video	Red	112		
TR2	2	A	18	LEARNING STUDIO 1B08	Video	Red	148		
TR2	2	A	19	LEARNING STUDIO 1B10	Video	Red	140		
TR2	2	A	20	MS HUB 1B00	Video	Red	72		
TR2	2	A	21	FLEX HUB 1D01	Video	Red	61		
TR2	2	A	22	MS HUB 1D00	Video	Red	62		
TR2	2	A	23	HS ONE TO ONE 1D02	Video	Red	153		
TR2	2	A	24	CENTRAL WORKROOM 1E05	Video	Red	39		
TR2	2	A	25	MS LI MODERATE 1B01	Video	Red	27		
TR2	2	A	26	HS ACADEMIC 1D07	Video	Red	38		
TR2	2	A	27	HS GROUP LEARNING 1D09	Video	Red	56		
TR2	2	A	28	ONE TO ONE 1D11	Video	Red	52		
TR2	2	A	29	MS GROUP LEARNING 1B03	Video	Red	49		
TR2	2	A	30		Video	Red			
TR2	2	A	31		Video	Red			
TR2	2	A	32		Video	Red			
TR2	2	A	33		Video	Red			
TR2	2	A	34		Video	Red			
TR2	2	A	35		Video	Red			
TR2	2	A	36		Video	Red			
TR2	2	A	37		Video	Red			
TR2	2	A	38		Video	Red			
TR2	2	A	39		Video	Red			
TR2	2	A	40		Video	Red			
TR2	2	A	41		Video	Red			
TR2	2	A	42		Video	Red			
TR2	2	A	43		Video	Red			
TR2	2	A	44		Video	Red			
TR2	2	A	45		Video	Red			
TR2	2	A	46		Video	Red			
TR2	2	A	47		Video	Red			
TR2	2	A	48		Video	Red			
TR2	2	B	1	LEARNING STUDIO 1B12	Voice	Yellow	150		
TR2	2	B	2	LEARNING STUDIO 1B14	Voice	Yellow	218		
TR2	2	B	3	LEARNING STUDIO 1D18	Voice	Yellow	216		
TR2	2	B	4	LEARNING STUDIO 1D16	Voice	Yellow	189		
TR2	2	B	5	LEARNING STUDIO 1D14	Voice	Yellow	189		
TR2	2	B	6	LEARNING STUDIO 1D12	Voice	Yellow	142		
TR2	2	B	7	MECH 1D13	Voice	Yellow	142		
TR2	2	B	8	LEARNING STUDIO 1D10	Voice	Yellow	132		
TR2	2	B	9	LEARNING STUDIO 1D08	Voice	Yellow	117		
TR2	2	B	10	HS CHEMISTRY 1D06	Voice	Yellow	194		
TR2	2	B	11	HS PHYSICAL SCIENCE 1D04	Voice	Yellow	181		
TR2	2	B	12	STAFF COLLAB 1E01	Voice	Yellow	128		
TR2	2	B	13	STAFF COLLAB 1E01	Voice	Yellow	115		
TR2	2	B	14	OT/PT GROSS 1B02	Voice	Yellow	134		
TR2	2	B	15	OT/PT FINE 1B06	Voice	Yellow	121		
TR2	2	B	16	MS ONE TO ONE 1B04	Voice	Yellow	119		
TR2	2	B	17	LEARNING STUDIO 1B08	Voice	Yellow	119		
TR2	2	B	18	LEARNING STUDIO 1B10	Voice	Yellow	121		
TR2	2	B	19	MECH 1B07	Voice	Yellow	147		
TR2	2	B	20	MS HUB 1B00	Voice	Yellow	95		
TR2	2	B	21	MS HUB 1D00	Voice	Yellow	157		
TR2	2	B	22	CENTRAL WORKROOM 1E05	Voice	Yellow	45		
TR2	2	B	23	MECH 1E07	Voice	Yellow	78		
TR2	2	B	24	MS LI MODERATE 1B01	Voice	Yellow	74		
TR2	2	B	25	TR2 1E06	Voice	Yellow	32		
TR2	2	B	26	HS ACADEMIC 1D07	Voice	Yellow	65		
TR2	2	B	27	HS GROUP LEARNING 1D09	Voice	Yellow	88		
TR2	2	B	28	ONE TO ONE 1D11	Voice	Yellow	61		
TR2	2	B	29	MS GROUP LEARNING 1B03	Voice	Yellow	75		
TR2	2	B	30	STAFF COLLAB 1E00	Voice	Yellow	90		
TR2	2	B	31	STAFF COLLAB 1E00	Voice	Yellow	90		
TR2	2	B	32	STAFF COLLAB 1E00	Voice	Yellow	90		
TR2	2	B	33	STAFF COLLAB 1E00	Voice	Yellow	90		
TR2	2	B	34	STAFF COLLAB 1E00	Voice	Yellow	67		
TR2	2	B	35	STAFF COLLAB 1E00	Voice	Yellow	67		
TR2	2	B	36	STAFF COLLAB 1E00	Voice	Yellow	67		
TR2	2	B	37	STAFF COLLAB 1E00	Voice	Yellow	67		
TR2	2	B	38	STAFF COLLAB 1E00	Voice	Yellow	76		
TR2	2	B	39	STAFF COLLAB 1E00	Voice	Yellow	76		
TR2	2	B	40	STAFF COLLAB 1E00	Voice	Yellow	76		
TR2	2	B	41	STAFF COLLAB 1E00	Voice	Yellow	76		
TR2	2	B	42	STAFF COLLAB 1E00	Voice	Yellow	72		
TR2	2	B	43	STAFF COLLAB 1E00	Voice	Yellow	72		
TR2	2	B	44	STAFF COLLAB 1E00	Voice	Yellow	72		
TR2	2	B	45	STAFF COLLAB 1E00	Voice	Yellow	72		
TR2	2	B	46	HS ONE TO ONE 1D02	Voice	Yellow	150		
TR2	2	B	47	COMMONS 1C01	Voice	Yellow	213		
TR2	2	B	48		Voice	Yellow			

APPR | DATE | DESCRIPTION | STM

NAVFAC

STATE OF KENTUCKY · 27884 · CHRISTOPHER J. REEVES · 12/31/2016 · PROFESSIONAL ENGINEER

SEAL

EWING COLE

Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO DATE

BWR KDM BKB

PMDM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091431

SHEET 677 OF 789

E720

DRAWFORM REVISION: 10 MARCH 2009

File Path

RTA SUBMISSION - 10/13/2016

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR2	2	C	1	LEARNING STUDIO 1B12	Wireless	Orange	170		
TR2	2	C	2	LEARNING STUDIO 1B12	Wireless	Orange	170		
TR2	2	C	3	LEARNING STUDIO 1B14	Wireless	Orange	239		
TR2	2	C	4	LEARNING STUDIO 1B14	Wireless	Orange	239		
TR2	2	C	5	LEARNING STUDIO 1D18	Wireless	Orange	240		
TR2	2	C	6	LEARNING STUDIO 1D18	Wireless	Orange	240		
TR2	2	C	7	LEARNING STUDIO 1D16	Wireless	Orange	196		
TR2	2	C	8	LEARNING STUDIO 1D16	Wireless	Orange	196		
TR2	2	C	9	LEARNING STUDIO 1D14	Wireless	Orange	194		
TR2	2	C	10	LEARNING STUDIO 1D14	Wireless	Orange	194		
TR2	2	C	11	LEARNING STUDIO 1D12	Wireless	Orange	170		
TR2	2	C	12	LEARNING STUDIO 1D12	Wireless	Orange	170		
TR2	2	C	13	EXTERIOR LEARNING AREA	Wireless	Orange	192		
TR2	2	C	14	EXTERIOR LEARNING AREA	Wireless	Orange	192		
TR2	2	C	15	LEARNING STUDIO 1D10	Wireless	Orange	124		
TR2	2	C	16	LEARNING STUDIO 1D10	Wireless	Orange	124		
TR2	2	C	17	LEARNING STUDIO 1D08	Wireless	Orange	130		
TR2	2	C	18	LEARNING STUDIO 1D08	Wireless	Orange	130		
TR2	2	C	19	HS CHEMISTRY 1D06	Wireless	Orange	193		
TR2	2	C	20	HS CHEMISTRY 1D06	Wireless	Orange	193		
TR2	2	C	21	EXTERIOR LEARNING AREA	Wireless	Orange	168		
TR2	2	C	22	EXTERIOR LEARNING AREA	Wireless	Orange	168		
TR2	2	C	23	HS PHYSICAL SCIENCE 1D04	Wireless	Orange	144		
TR2	2	C	24	HS PHYSICAL SCIENCE 1D04	Wireless	Orange	144		
TR2	2	C	25	STAFF COLLAB 1E01	Wireless	Orange	69		
TR2	2	C	26	STAFF COLLAB 1E01	Wireless	Orange	69		
TR2	2	C	27	OT/PT GROSS 1B02	Wireless	Orange	150		
TR2	2	C	28	OT/PT GROSS 1B02	Wireless	Orange	150		
TR2	2	C	29	COMMONS 1C01	Wireless	Orange	181		
TR2	2	C	30	COMMONS 1C01	Wireless	Orange	181		
TR2	2	C	31	OT/PT FINE 1B06	Wireless	Orange	147		
TR2	2	C	32	OT/PT FINE 1B06	Wireless	Orange	147		
TR2	2	C	33	LEARNING STUDIO 1B08	Wireless	Orange	136		
TR2	2	C	34	LEARNING STUDIO 1B08	Wireless	Orange	136		
TR2	2	C	35	LEARNING STUDIO 1B10	Wireless	Orange	136		
TR2	2	C	36	LEARNING STUDIO 1B10	Wireless	Orange	136		
TR2	2	C	37	MS HUB 1B00	Wireless	Orange	95		
TR2	2	C	38	MS HUB 1B00	Wireless	Orange	95		
TR2	2	C	39	MS HUB 1B00	Wireless	Orange	120		
TR2	2	C	40	MS HUB 1B00	Wireless	Orange	120		
TR2	2	C	41	FLEX HUB 1D01	Wireless	Orange	74		
TR2	2	C	42	FLEX HUB 1D01	Wireless	Orange	74		
TR2	2	C	43	FLEX HUB 1D01	Wireless	Orange	82		
TR2	2	C	44	FLEX HUB 1D01	Wireless	Orange	82		
TR2	2	C	45	HS HUB 1D00	Wireless	Orange	93		
TR2	2	C	46	HS HUB 1D00	Wireless	Orange	93		
TR2	2	C	47	HS HUB 1D00	Wireless	Orange	90		
TR2	2	C	48	HS HUB 1D00	Wireless	Orange	90		
TR2	2	D	1	CENTRAL WORKROOM 1E05	Wireless	Orange	47		
TR2	2	D	2	CENTRAL WORKROOM 1E05	Wireless	Orange	47		
TR2	2	D	3	MS LI MODERATE 1B01	Wireless	Orange	58		
TR2	2	D	4	MS LI MODERATE 1B01	Wireless	Orange	58		
TR2	2	D	5	HS ACADEMIC 1D07	Wireless	Orange	42		
TR2	2	D	6	HS ACADEMIC 1D07	Wireless	Orange	42		
TR2	2	D	7	HS GROUP LEARNING 1D09	Wireless	Orange	64		
TR2	2	D	8	HS GROUP LEARNING 1D09	Wireless	Orange	64		
TR2	2	D	9	MS GROUP LEARNING 1B03	Wireless	Orange	64		
TR2	2	D	10	MS GROUP LEARNING 1B03	Wireless	Orange	64		
TR2	2	D	11	ENTRY CORRIDOR 1C00	Wireless	Orange	130		
TR2	2	D	12	ENTRY CORRIDOR 1C00	Wireless	Orange	130		
TR2	2	D	13	ENTRY CORRIDOR 1C00	Wireless	Orange	140		
TR2	2	D	14	ENTRY CORRIDOR 1C00	Wireless	Orange	140		
TR2	2	D	15	EXTERIOR LEARNING AREA	Wireless	Orange	215		
TR2	2	D	16	EXTERIOR LEARNING AREA	Wireless	Orange	215		
TR2	2	D	17		Wireless	Orange			
TR2	2	D	18		Wireless	Orange			
TR2	2	D	19		Wireless	Orange			
TR2	2	D	20		Wireless	Orange			
TR2	2	D	21		Wireless	Orange			
TR2	2	D	22		Wireless	Orange			
TR2	2	D	23		Wireless	Orange			
TR2	2	D	24		Wireless	Orange			
TR2	2	D	25		Wireless	Orange			
TR2	2	D	26		Wireless	Orange			
TR2	2	D	27		Wireless	Orange			
TR2	2	D	28		Wireless	Orange			
TR2	2	D	29		Wireless	Orange			
TR2	2	D	30		Wireless	Orange			
TR2	2	D	31		Wireless	Orange			
TR2	2	D	32		Wireless	Orange			
TR2	2	D	33		Wireless	Orange			
TR2	2	D	34		Wireless	Orange			
TR2	2	D	35		Wireless	Orange			
TR2	2	D	36		Wireless	Orange			
TR2	2	D	37		Wireless	Orange			
TR2	2	D	38		Wireless	Orange			
TR2	2	D	39		Wireless	Orange			
TR2	2	D	40		Wireless	Orange			
TR2	2	D	41		Wireless	Orange			
TR2	2	D	42		Wireless	Orange			
TR2	2	D	43		Wireless	Orange			
TR2	2	D	44		Wireless	Orange			
TR2	2	D	45		Wireless	Orange			
TR2	2	D	46		Wireless	Orange			
TR2	2	D	47		Wireless	Orange			
TR2	2	D	48		Wireless	Orange			

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR2	2	E	1	STAFF COLLAB 1E00	Voice	Yellow	88		
TR2	2	E	2	STAFF COLLAB 1E00	Voice	Yellow	88		
TR2	2	E	3	STAFF COLLAB 1E00	Voice	Yellow	88		
TR2	2	E	4	STAFF COLLAB 1E00	Voice	Yellow	88		
TR2	2	E	5	STAFF COLLAB 2E04	Voice	Yellow	100		
TR2	2	E	6	STAFF COLLAB 2E04	Voice	Yellow	100		
TR2	2	E	7	STAFF COLLAB 2E04	Voice	Yellow	90		
TR2	2	E	8	STAFF COLLAB 2E04	Voice	Yellow	90		
TR2	2	E	9	STAFF COLLAB 2E04	Voice	Yellow	80		
TR2	2	E	10	STAFF COLLAB 2E04	Voice	Yellow	80		
TR2	2	E	11	STAFF COLLAB 2E04	Voice	Yellow	60		
TR2	2	E	12	STAFF COLLAB 2E04	Voice	Yellow	60		
TR2	2	E	13	STAFF COLLAB 2E04	Voice	Yellow	70		
TR2	2	E	14	STAFF COLLAB 2E04	Voice	Yellow	70		
TR2	2	E	15	STAFF COLLAB 2E04	Voice	Yellow	80		
TR2	2	E	16	STAFF COLLAB 2E04	Voice	Yellow	80		
TR2	2	E	17	STAFF COLLAB 2E04	Voice	Yellow	80		
TR2	2	E	18	STAFF COLLAB 2E04	Voice	Yellow	80		
TR2	2	E	19	STAFF COLLAB 2E04	Voice	Yellow	90		
TR2	2	E	20	STAFF COLLAB 2E04	Voice	Yellow	90		
TR2	2	E	21	STAFF COLLAB 2E04	Voice	Yellow	100		
TR2	2	E	22	STAFF COLLAB 2E04	Voice	Yellow	100		
TR2	2	E	23		Voice	Yellow			
TR2	2	E	24		Voice	Yellow			
TR2	2	E	25		Voice	Yellow			
TR2	2	E	26		Voice	Yellow			
TR2	2	E	27		Voice	Yellow			
TR2	2	E	28		Voice	Yellow			
TR2	2	E	29		Voice	Yellow			
TR2	2	E	30		Voice	Yellow			
TR2	2	E	31		Voice	Yellow			
TR2	2	E	32		Voice	Yellow			
TR2	2	E	33		Voice	Yellow			
TR2	2	E	34		Voice	Yellow			
TR2	2	E	35		Voice	Yellow			
TR2	2	E	36		Voice	Yellow			
TR2	2	E	37		Voice	Yellow			
TR2	2	E	38		Voice	Yellow			
TR2	2	E	39		Voice	Yellow			
TR2	2	E	40		Voice	Yellow			
TR2	2	E	41		Voice	Yellow			
TR2	2	E	42		Voice	Yellow			
TR2	2	E	43		Voice	Yellow			
TR2	2	E	44		Voice	Yellow			
TR2	2	E	45		Voice	Yellow			
TR2	2	E	46		Voice	Yellow			
TR2	2	E	47		Voice	Yellow			
TR2	2	E	48		Voice	Yellow			

SYM | DESCRIPTION | DATE | APPR

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952
A/E INFO

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO DATE

BWR KDM BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY NAVAL FACILITES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
DoDEA MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO. W91236-15-C-0023

NAVFAC DRAWING NO. 13091432

SHEET 678 OF 789

E721

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR2	3	A	1	FLEX HUB 1D01	Data	Blue	60		
TR2	3	A	2	FLEX HUB 1D01	Data	Blue	60		
TR2	3	A	3	MS HUB 1D00	Data	Blue	139		
TR2	3	A	4	MS HUB 1D00	Data	Blue	139		
TR2	3	A	5	MS HUB 1D00	Data	Blue	62		
TR2	3	A	6	MS HUB 1D00	Data	Blue	66		
TR2	3	A	7	MS HUB 1D00	Data	Blue	66		
TR2	3	A	8	MS HUB 1D00	Printer	Green	66		
TR2	3	A	9	MS HUB 1D00	Data	Blue	93		
TR2	3	A	10	MS HUB 1D00	Data	Blue	93		
TR2	3	A	11	MS ONE TO ONE 1D02	Data	Blue	133		
TR2	3	A	12	MS ONE TO ONE 1D02	Data	Blue	133		
TR2	3	A	13	MS ONE TO ONE 1D02	Data	Blue	140		
TR2	3	A	14	MS ONE TO ONE 1D02	Data	Blue	161		
TR2	3	A	15	MS ONE TO ONE 1D02	Data	Blue	161		
TR2	3	A	16	CENTRAL WORKROOM 1E05	Data	Blue	51		
TR2	3	A	17	CENTRAL WORKROOM 1E05	Data	Blue	51		
TR2	3	A	18	CENTRAL WORKROOM 1E05	Printer	Green	37		
TR2	3	A	19	CENTRAL WORKROOM 1E05	Data	Blue	35		
TR2	3	A	20	CENTRAL WORKROOM 1E05	Data	Blue	35		
TR2	3	A	21	MECH 1E07	Data	Blue	75		
TR2	3	A	22	MECH 1E07	Data	Blue	75		
TR2	3	A	23	MS LI MILD 1B01	Data	Blue	65		
TR2	3	A	24	MS LI MILD 1B01	Data	Blue	65		
TR2	3	A	25	MS LI MILD 1B01	Data	Blue	27		
TR2	3	A	26	MS LI MILD 1B01	Data	Blue	34		
TR2	3	A	27	MS LI MILD 1B01	Data	Blue	34		
TR2	3	A	28	MS LI MILD 1B01	Printer	Green	34		
TR2	3	A	29	MS LI MILD 1B01	Data	Blue	32		
TR2	3	A	30	MS LI MILD 1B01	Data	Blue	32		
TR2	3	A	31						
TR2	3	A	32	HS ACADEMIC SUPPORT 1D07	Data	Blue	36		
TR2	3	A	33	HS ACADEMIC SUPPORT 1D07	Data	Blue	36		
TR2	3	A	34	HS ACADEMIC SUPPORT 1D07	Printer	Green	36		
TR2	3	A	35	HS ACADEMIC SUPPORT 1D07	Data	Blue	38		
TR2	3	A	36	HS ACADEMIC SUPPORT 1D07	Data	Blue	57		
TR2	3	A	37	HS ACADEMIC SUPPORT 1D07	Data	Blue	57		
TR2	3	A	38	HS ACADEMIC SUPPORT 1D07	Data	Blue	57		
TR2	3	A	39	HS ACADEMIC SUPPORT 1D07	Data	Blue	63		
TR2	3	A	40	HS GROUP LEARNING 1D09	Data	Blue	48		
TR2	3	A	41	HS GROUP LEARNING 1D09	Data	Blue	48		
TR2	3	A	42	HS GROUP LEARNING 1D09	Printer	Green	48		
TR2	3	A	43	HS GROUP LEARNING 1D09	Data	Blue	56		
TR2	3	A	44	HS GROUP LEARNING 1D09	Data	Blue	56		
TR2	3	A	45	HS GROUP LEARNING 1D09	Data	Blue	58		
TR2	3	A	46	HS GROUP LEARNING 1D09	Data	Blue	63		
TR2	3	A	47	HS GROUP LEARNING 1D09	Data	Blue	63		
TR2	3	A	48		Data	Blue			
TR2	3	B	1	ONE TO ONE 1D11	Data	Blue	51		
TR2	3	B	2	ONE TO ONE 1D11	Data	Blue	51		
TR2	3	B	3	ONE TO ONE 1D11	Data	Blue	54		
TR2	3	B	4	ONE TO ONE 1D11	Data	Blue	57		
TR2	3	B	5	ONE TO ONE 1D11	Data	Blue	57		
TR2	3	B	6	MS GROUP LEARNING 1B03	Data	Blue	73		
TR2	3	B	7	MS GROUP LEARNING 1B03	Data	Blue	73		
TR2	3	B	8	MS GROUP LEARNING 1B03	Data	Blue	67		
TR2	3	B	9	MS GROUP LEARNING 1B03	Data	Blue	67		
TR2	3	B	10	MS GROUP LEARNING 1B03	Data	Blue	58		
TR2	3	B	11	MS GROUP LEARNING 1B03	Data	Blue	58		
TR2	3	B	12	MS GROUP LEARNING 1B03	Printer	Green	58		
TR2	3	B	13	MS GROUP LEARNING 1B03	Data	Blue	49		
TR2	3	B	14	TR2 1E06	Data	Blue	32		
TR2	3	B	15	TR2 1E06	Data	Blue	32		
TR2	3	B	16	TR2 1E06	Data	Blue	32		
TR2	3	B	17		Data	Blue			
TR2	3	B	18	STAFF COLLAB 2E01	Data	Blue	100		
TR2	3	B	19	STAFF COLLAB 2E01	Data	Blue	100		
TR2	3	B	20	STAFF COLLAB 2E01	Data	Blue	90		
TR2	3	B	21	STAFF COLLAB 2E01	Data	Blue	90		
TR2	3	B	22	STAFF COLLAB 2E01	Data	Blue	80		
TR2	3	B	23	STAFF COLLAB 2E01	Data	Blue	80		
TR2	3	B	24	STAFF COLLAB 2E01	Data	Blue	80		
TR2	3	B	25	STAFF COLLAB 2E01	Data	Blue	80		
TR2	3	B	26	STAFF COLLAB 2E01	Data	Blue	70		
TR2	3	B	27	STAFF COLLAB 2E01	Data	Blue	70		
TR2	3	B	28	STAFF COLLAB 2E01	Data	Blue	60		
TR2	3	B	29	STAFF COLLAB 2E01	Data	Blue	60		
TR2	3	B	30	STAFF COLLAB 2E01	Data	Blue	100		
TR2	3	B	31	STAFF COLLAB 2E01	Data	Blue	100		
TR2	3	B	32	STAFF COLLAB 2E01	Data	Blue	90		
TR2	3	B	33	STAFF COLLAB 2E01	Data	Blue	90		
TR2	3	B	34	STAFF COLLAB 2E01	Data	Blue	80		
TR2	3	B	35	STAFF COLLAB 2E01	Data	Blue	80		
TR2	3	B	36	HS CHEMISTRY 1D06	Data	Blue	207		
TR2	3	B	37	HS CHEMISTRY 1D06	Data	Blue	207		
TR2	3	B	38	HS CHEMISTRY 1D06	Data	Blue	194		
TR2	3	B	39	HS CHEMISTRY 1D06	Data	Blue	194		
TR2	3	B	40	HS CHEMISTRY 1D06	Data	Blue	200		
TR2	3	B	41	HS CHEMISTRY 1D06	Data	Blue	200		
TR2	3	B	42	HS CHEMISTRY 1D06	Data	Blue	186		
TR2	3	B	43	HS CHEMISTRY 1D06	Data	Blue	186		
TR2	3	B	44	HS CHEMISTRY 1D06	Data	Blue	226		
TR2	3	B	45	HS CHEMISTRY 1D06	Data	Blue	226		
TR2	3	B	46	HS CHEMISTRY 1D06	Data	Blue	226		
TR2	3	B	47	HS CHEMISTRY 1D06	Data	Blue	226		
TR2	3	B	48		Data	Blue			

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR2	3	C	1		Data	Blue			
TR2	3	C	2		Data	Blue			
TR2	3	C	3		Data	Blue			
TR2	3	C	4		Data	Blue			
TR2	3	C	5		Data	Blue			
TR2	3	C	6		Data	Blue			
TR2	3	C	7		Data	Blue			
TR2	3	C	8		Data	Blue			
TR2	3	C	9		Data	Blue			
TR2	3	C	10		Data	Blue			
TR2	3	C	11		Data	Blue			
TR2	3	C	12		Data	Blue			
TR2	3	C	13		Data	Blue			
TR2	3	C	14		Data	Blue			
TR2	3	C	15		Data	Blue			
TR2	3	C	16		Data	Blue			
TR2	3	C	17		Data	Blue			
TR2	3	C	18		Data	Blue			
TR2	3	C	19		Data	Blue			
TR2	3	C	20		Data	Blue			
TR2	3	C	21		Data	Blue			
TR2	3	C	22		Data	Blue			
TR2	3	C	23		Data	Blue			
TR2	3	C	24		Data	Blue			
TR2	3	C	25		Data	Blue			
TR2	3	C	26		Data	Blue			
TR2	3	C	27		Data	Blue			
TR2	3	C	28		Data	Blue			
TR2	3	C	29		Data	Blue			
TR2	3	C	30		Data	Blue			
TR2	3	C	31		Data	Blue			
TR2	3	C	32		Data	Blue			
TR2	3	C	33		Data	Blue			
TR2	3	C	34		Data	Blue			
TR2	3	C	35		Data	Blue			
TR2	3	C	36		Data	Blue			
TR2	3	C	37		Data	Blue			
TR2	3	C	38		Data	Blue			
TR2	3	C	39		Data	Blue			
TR2	3	C	40		Data	Blue			
TR2	3	C	41		Data	Blue			
TR2	3	C	42		Data	Blue			
TR2	3	C	43		Data	Blue			
TR2	3	C	44		Data	Blue			
TR2	3	C	45		Data	Blue			
TR2	3	C	46		Data	Blue			
TR2	3	C	47		Data	Blue			
TR2	3	C	48		Data	Blue			

APPR. | DATE | DESCRIPTION | SYM

NAVFAC

STATE OF KENTUCKY · BRADLEY ALLEN REEVES · 20... · PROFESSIONAL ENGINEER

SEAL

EWING COLE

Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO | DATE

BWR | KDM | BKB

PMDM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
MARINE CORPS BASE QUANTICO
MARINE CORPS BASE QUANTICO, VIRGINIA
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091433

SHEET 679 OF 789

E722

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR3	1	A	1	ENTRY CORR 1C00	Data	Blue	225		
TR3	1	A	2	ENTRY CORR 1C00	Data	Blue	220		
TR3	1	A	3	ENTRY CORR 1C00	Data	Blue	220		
TR3	1	A	4	ENTRY CORR 1C00	Data	Blue	230		
TR3	1	A	5	ENTRY CORR 1C00	Data	Blue	230		
TR3	1	A	6	ENTRY CORR 1C00	Printer	Green	230		
TR3	1	A	7	MS CTE 1C41	Data	Blue	175		
TR3	1	A	8	MS CTE 1C41	Data	Blue	175		
TR3	1	A	9	MS CTE 1C41	Data	Blue	185		
TR3	1	A	10	MS CTE 1C41	Data	Blue	190		
TR3	1	A	11	MS CTE 1C41	Data	Blue	190		
TR3	1	A	12	MS CTE 1C41	Printer	Green	190		
TR3	1	A	13	MS CTE 1C41	Data	Blue	200		
TR3	1	A	14	MS CTE 1C41	Data	Blue	200		
TR3	1	A	15	MS CTE 1C41	Data	Blue	190		
TR3	1	A	16	MS CTE 1C41	Data	Blue	190		
TR3	1	A	17	ART 1C39	Data	Blue	165		
TR3	1	A	18	ART 1C39	Data	Blue	165		
TR3	1	A	19	ART 1C39	Data	Blue	155		
TR3	1	A	20	ART 1C39	Data	Blue	165		
TR3	1	A	21	ART 1C39	Data	Blue	165		
TR3	1	A	22	ART 1C39	Printer	Green	165		
TR3	1	A	23	ART 1C39	Data	Blue	175		
TR3	1	A	24	ART 1C39	Data	Blue	175		
TR3	1	A	25	ART 1C39	Data	Blue	135		
TR3	1	A	26	ART 1C39	Data	Blue	135		
TR3	1	A	27	ART 1C39	Data	Blue	145		
TR3	1	A	28	ART 1C39	Data	Blue	145		
TR3	1	A	29		Data	Blue			
TR3	1	A	30	CAREER INFO 1A27	Data	Blue	114		
TR3	1	A	31	CAREER INFO 1A27	Data	Blue	114		
TR3	1	A	32	CAREER INFO 1A27	Data	Blue	106		
TR3	1	A	33	CAREER INFO 1A27	Data	Blue	106		
TR3	1	A	34	CAREER INFO 1A27	Data	Blue	101		
TR3	1	A	35	CAREER INFO 1A27	Data	Blue	101		
TR3	1	A	36	CAREER INFO 1A27	Printer	Green	101		
TR3	1	A	37	REGISTRAR 1A29	Data	Blue	104		
TR3	1	A	38	REGISTRAR 1A29	Data	Blue	104		
TR3	1	A	39	REGISTRAR 1A29	Printer	Green	104		
TR3	1	A	40		Data	Blue			
TR3	1	A	41		Data	Blue			
TR3	1	A	42	RECORDS 1A31	Data	Blue	89		
TR3	1	A	43	RECORDS 1A31	Data	Blue	89		
TR3	1	A	44	RECORDS 1A31	Printer	Green	81		
TR3	1	A	45	COUNSELOR 1A33	Data	Blue	91		
TR3	1	A	46	COUNSELOR 1A33	Data	Blue	91		
TR3	1	A	47	COUNSELOR 1A33	Printer	Green	91		
TR3	1	A	48		Data	Blue			
TR3	1	B	1	PYSCH 1A35	Data	Blue	84		
TR3	1	B	2	PYSCH 1A35	Data	Blue	84		
TR3	1	B	3	PYSCH 1A35	Printer	Green	84		
TR3	1	B	4	STORAGE 1A26	Data	Blue	115		
TR3	1	B	5	ASSESSOR 1A28	Data	Blue	108		
TR3	1	B	6	ASSESSOR 1A28	Data	Blue	108		
TR3	1	B	7	ASSESSOR 1A28	Printer	Green	108		
TR3	1	B	8	ASSESSMENT 1A30	Data	Blue	97		
TR3	1	B	9	ASSESSMENT 1A30	Data	Blue	97		
TR3	1	B	10	ASSESSMENT 1A30	Printer	Green	97		
TR3	1	B	11	CAREER COUNSELOR 1A32	Data	Blue	55		
TR3	1	B	12	CAREER COUNSELOR 1A32	Data	Blue	55		
TR3	1	B	13	CAREER COUNSELOR 1A32	Printer	Green	55		
TR3	1	B	14	CONFERENCE 1A34	Data	Blue	52		
TR3	1	B	15	CONFERENCE 1A34	Data	Blue	52		
TR3	1	B	16	CONFERENCE 1A34	Printer	Green	52		
TR3	1	B	17	CONFERENCE 1A34	Data	Blue	49		
TR3	1	B	18	CONFERENCE 1A34	Data	Blue	58		
TR3	1	B	19	CONFERENCE 1A34	Data	Blue	58		
TR3	1	B	20	MECH 1A21	Data	Blue	82		
TR3	1	B	21	MECH 1A21	Data	Blue	82		
TR3	1	B	22	NURSE SCREENING 1A23	Data	Blue	81		
TR3	1	B	23	NURSE 1A19	Data	Blue	53		
TR3	1	B	24	NURSE 1A19	Printer	Green	53		
TR3	1	B	25	NURSE 1A17	Data	Blue	53		
TR3	1	B	26	NURSE 1A17	Printer	Green	35		
TR3	1	B	27	NURSE 1A17	Data	Blue	46		
TR3	1	B	28	NURSE 1A17	Data	Blue	46		
TR3	1	B	29	NURSE 1A17	Data	Blue	52		
TR3	1	B	30	NURSE 1A17	Data	Blue	52		
TR3	1	B	31	ELEV MACH 1A20	Data	Blue	36		
TR3	1	B	32	ELEV MACH 1A20	Data	Blue	36		
TR3	1	B	33	TR3 1A22	Printer	Green	15		
TR3	1	B	34	TR3 1A22	Data	Blue	15		
TR3	1	B	35	TR3 1A22	Data	Blue	15		
TR3	1	B	36	VESTIBULE 1A00	Data	Blue	120		
TR3	1	B	37	COMMONS 1C01	Data	Blue	132		
TR3	1	B	38	PARENTS CENTER 1A02	Data	Blue	123		
TR3	1	B	39	PARENTS CENTER 1A02	Data	Blue	123		
TR3	1	B	40	PARENTS CENTER 1A02	Data	Blue	123		
TR3	1	B	41	CLERICAL 1A03	Data	Blue	167		
TR3	1	B	42	WORK ROOM 1A08	Data	Blue	167		
TR3	1	B	43	WORK ROOM 1A08	Data	Blue	167		
TR3	1	B	44	WORK ROOM 1A08	Printer	Green	167		
TR3	1	B	45		Data	Blue			
TR3	1	B	46		Data	Blue			
TR3	1	B	47		Data	Blue			
TR3	1	B	48		Data	Blue			

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR3	1	C	1	WORK ROOM 1A08	Data	Blue	163		
TR3	1	C	2	WORK ROOM 1A08	Data	Blue	163		
TR3	1	C	3		Data	Blue			
TR3	1	C	4	ADMIN CONF 1A12	Data	Blue	186		
TR3	1	C	5	ADMIN CONF 1A12	Data	Blue	212		
TR3	1	C	6	ADMIN CONF 1A12	Data	Blue	198		
TR3	1	C	7	ADMIN CONF 1A12	Data	Blue	195		
TR3	1	C	8	ADMIN CONF 1A12	Data	Blue	195		
TR3	1	C	9	ADMIN CONF 1A12	Printer	Green	195		
TR3	1	C	10	MECH 1A14	Data	Blue	218		
TR3	1	C	11	MECH 1A14	Data	Blue	218		
TR3	1	C	12	ELEC 1A16	Data	Blue	220		
TR3	1	C	13	COMMONS 1C01	Data	Blue	218		
TR3	1	C	14	COMMONS 1C01	Data	Blue	220		
TR3	1	C	15	COMMONS 1C01	Data	Blue	220		
TR3	1	C	16	COMMONS 1C01	Printer	Green	220		
TR3	1	C	17	PRINCIPAL 1A09	Data	Blue	207		
TR3	1	C	18	PRINCIPAL 1A09	Data	Blue	207		
TR3	1	C	19	PRINCIPAL 1A09	Printer	Green	207		
TR3	1	C	20	ASST PRINCIPAL 1A07	Data	Blue	199		
TR3	1	C	21	ASST PRINCIPAL 1A07	Data	Blue	199		
TR3	1	C	22	ASST PRINCIPAL 1A07	Printer	Green	199		
TR3	1	C	23	SMSS 1A05	Data	Blue	174		
TR3	1	C	24	SMSS 1A05	Data	Blue	174		
TR3	1	C	25	SMSS 1A05	Printer	Green	174		
TR3	1	C	26	CLERICAL 1A03	Data	Blue	147		
TR3	1	C	27	CLERICAL 1A03	Data	Blue	147		
TR3	1	C	28	CLERICAL 1A03	Printer	Green	147		
TR3	1	C	29	CLERICAL 1A03	Data	Blue	167		
TR3	1	C	30	CLERICAL 1A03	Data	Blue	167		
TR3	1	C	31	RECEPTION 1A01	Data	Blue	135		
TR3	1	C	32	RECEPTION 1A01	Data	Blue	135		
TR3	1	C	33	RECEPTION 1A01	Printer	Green	135		
TR3	1	C	34	COMMONS 1C01	Data	Blue	143		
TR3	1	C	35	COMMONS 1C01	Data	Blue	143		
TR3	1	C	36	COMMONS 1C01	Data	Blue	135		
TR3	1	C	37	COMMONS 1C01	Data	Blue	135		
TR3	1	C	38	COMMONS 1C01	Data	Blue	127		
TR3	1	C	39	COMMONS 1C01	Data	Blue	127		
TR3	1	C	40	COMMONS 1C01	Data	Blue	119		
TR3	1	C	41	COMMONS 1C01	Data	Blue	119		
TR3	1	C	42	COMMONS 1C01	Data	Blue	111		
TR3	1	C	43	COMMONS 1C01	Data	Blue	111		
TR3	1	C	44	COMMONS 1C01	Data	Blue	103		
TR3	1	C	45	COMMONS 1C01	Data	Blue	103		
TR3	1	C	46		Data	Blue			
TR3	1	C	47		Data	Blue			
TR3	1	C	48		Data	Blue			
TR3	1	D	1		Data	Blue			
TR3	1	D	2		Data	Blue			
TR3	1	D	3		Data	Blue			
TR3	1	D	4		Data	Blue			
TR3	1	D	5		Data	Blue			
TR3	1	D	6		Data	Blue			
TR3	1	D	7		Data	Blue			
TR3	1	D	8		Data	Blue			
TR3	1	D	9		Data	Blue			
TR3	1	D	10		Data	Blue			
TR3	1	D	11		Data	Blue			
TR3	1	D	12		Data	Blue			
TR3	1	D	13		Data	Blue			
TR3	1	D	14		Data	Blue			
TR3	1	D	15		Data	Blue			
TR3	1	D	16		Data	Blue			
TR3	1	D	17		Data	Blue			
TR3	1	D	18		Data	Blue			
TR3	1	D	19		Data	Blue			
TR3	1	D	20		Data	Blue			
TR3	1	D	21		Data	Blue			
TR3	1	D	22		Data	Blue			
TR3	1	D	23		Data	Blue			
TR3	1	D	24		Data	Blue			
TR3	1	D	25		Data	Blue			
TR3	1	D	26		Data	Blue			
TR3	1	D	27		Data	Blue			
TR3	1	D	28		Data	Blue			
TR3	1	D	29		Data	Blue			
TR3	1	D	30		Data	Blue			
TR3	1	D	31		Data	Blue			
TR3	1	D	32		Data	Blue			
TR3	1	D	33		Data	Blue			
TR3	1	D	34		Data	Blue			
TR3	1	D	35		Data	Blue			
TR3	1	D	36		Data	Blue			
TR3	1	D	37		Data	Blue			
TR3	1	D	38		Data	Blue			
TR3	1	D	39		Data	Blue			
TR3	1	D	40		Data	Blue			
TR3	1	D	41		Data	Blue			
TR3	1	D	42		Data	Blue			
TR3	1	D	43		Data	Blue			
TR3	1	D	44		Data	Blue			
TR3	1	D	45		Data	Blue			
TR3	1	D	46		Data	Blue			
TR3	1	D	47		Data	Blue			
TR3	1	D	48		Data	Blue			

SYM DESCRIPTION DATE APPR

SEAL

Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO DATE

BWR KDM BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
DoDEA
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO. W91236-15-C-0023

NAVFAC DRAWING NO. 13091434

SHEET 680 OF 789

E723

RTA SUBMISSION - 10/13/2016

DRAWFORM REVISION: 10 MARCH 2009

File Path

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR3	2	A	1	ENTRY CORRIDOR 1C00	Video	Red	230		
TR3	2	A	2	ENTRY CORRIDOR 1C00	Video	Red	220		
TR3	2	A	3	ENTRY CORRIDOR 1C00	Video	Red	220		
TR3	2	A	4	MS CTE 1C41	Video	Red	215		
TR3	2	A	5	ART 1C39	Video	Red	133		
TR3	2	A	6	CAREER INFO 1A27	Video	Red	103		
TR3	2	A	7	COMMONS 1C01	Video	Red	121		
TR3	2	A	8	CONF 1A34	Video	Red	61		
TR3	2	A	9	CONF 1A34	Video	Red	55		
TR3	2	A	10	CONF 1A34	Video	Red	49		
TR3	2	A	11	COMMONS 1C01	Video	Red	130		
TR3	2	A	12	COMMONS 1C01	Video	Red	122		
TR3	2	A	13	COMMONS 1C01	Video	Red	123		
TR3	2	A	14	COMMONS 1C01	Video	Red	125		
TR3	2	A	15	PARENTS CENTER 1A02	Video	Red	134		
TR3	2	A	16	COMMONS 1C01	Video	Red	167		
TR3	2	A	17	ADMIN CONF 1A12	Video	Red	200		
TR3	2	A	18	ADMIN CONF 1A12	Video	Red	207		
TR3	2	A	19	ADMIN CONF 1A12	Video	Red	198		
TR3	2	A	20	COMMONS 1C01	Video	Red	218		
TR3	2	A	21	PRINCIPAL 1A09	Video	Red	200		
TR3	2	A	22	ASST PRINCIPAL 1A07	Video	Red	185		
TR3	2	A	23	SMSS 1A05	Video	Red	173		
TR3	2	A	24	RECEPTION 1A01	Video	Red	137		
TR3	2	A	25	RECEPTION 1A01	Video	Red	154		
TR3	2	A	26		Video	Red			
TR3	2	A	27		Video	Red			
TR3	2	A	28		Video	Red			
TR3	2	A	29		Video	Red			
TR3	2	A	30		Video	Red			
TR3	2	A	31		Video	Red			
TR3	2	A	32		Video	Red			
TR3	2	A	33		Video	Red			
TR3	2	A	34		Video	Red			
TR3	2	A	35		Video	Red			
TR3	2	A	36		Video	Red			
TR3	2	A	37		Video	Red			
TR3	2	A	38		Video	Red			
TR3	2	A	39		Video	Red			
TR3	2	A	40		Video	Red			
TR3	2	A	41		Video	Red			
TR3	2	A	42		Video	Red			
TR3	2	A	43		Video	Red			
TR3	2	A	44		Video	Red			
TR3	2	A	45		Video	Red			
TR3	2	A	46		Video	Red			
TR3	2	A	47		Video	Red			
TR3	2	A	48		Video	Red			
TR3	2	B	1	MS CTE 1C41	Voice	Yellow	190		
TR3	2	B	2	ART 1C39	Voice	Yellow	170		
TR3	2	B	3	MECH 1C37	Voice	Yellow	135		
TR3	2	B	4	CAREER INFO 1A27	Voice	Yellow	110		
TR3	2	B	5	REGISTRAR 1A29	Voice	Yellow	66		
TR3	2	B	6	RECORDS 1A31	Voice	Yellow	85		
TR3	2	B	7	COUNSELOR 1A33	Voice	Yellow	93		
TR3	2	B	8	PSYCH 1A35	Voice	Yellow	86		
TR3	2	B	9	ASSESSOR 1A26	Voice	Yellow	99		
TR3	2	B	10	CAREER COUNSELOR 1A32	Voice	Yellow	59		
TR3	2	B	11	CONF 1A34	Voice	Yellow	66		
TR3	2	B	12	MECH 1A21	Voice	Yellow	80		
TR3	2	B	13	NURSE SCREENING 1A23	Voice	Yellow	69		
TR3	2	B	14	NURSE 1A18	Voice	Yellow	51		
TR3	2	B	15	ELEV MACH 1A20	Voice	Yellow	38		
TR3	2	B	16	ELEV MACH 1A20	Voice	Yellow	38		
TR3	2	B	17	TR3 1A22	Voice	Yellow	15		
TR3	2	B	18	PARENTS CENTER 1A02	Voice	Yellow	134		
TR3	2	B	19	CLERICAL 1A03	Voice	Yellow	178		
TR3	2	B	20	MAIL ROOM 1A10	Voice	Yellow	169		
TR3	2	B	21	ADMIN CONF 1A12	Voice	Yellow	184		
TR3	2	B	22	MECH 1A14	Voice	Yellow	209		
TR3	2	B	23	ELEC 1A16	Voice	Yellow	216		
TR3	2	B	24	PRINCIPAL 1A09	Voice	Yellow	209		
TR3	2	B	25	ASST PRINCIPAL 1A07	Voice	Yellow	201		
TR3	2	B	26	SMSS 1A05	Voice	Yellow	177		
TR3	2	B	27	CLERICAL 1A03	Voice	Yellow	179		
TR3	2	B	28	CLERICAL 1A03	Voice	Yellow	169		
TR3	2	B	29	RECEPTION 1A01	Voice	Yellow	142		
TR3	2	B	30	RECEPTION 1A01	Voice	Yellow	130		
TR3	2	B	31	COMMONS 1C01	Voice	Yellow	184		
TR3	2	B	32		Voice	Yellow			
TR3	2	B	33		Voice	Yellow			
TR3	2	B	34		Voice	Yellow			
TR3	2	B	35		Voice	Yellow			
TR3	2	B	36		Voice	Yellow			
TR3	2	B	37		Voice	Yellow			
TR3	2	B	38		Voice	Yellow			
TR3	2	B	39		Voice	Yellow			
TR3	2	B	40		Voice	Yellow			
TR3	2	B	41		Voice	Yellow			
TR3	2	B	42		Voice	Yellow			
TR3	2	B	43		Voice	Yellow			
TR3	2	B	44		Voice	Yellow			
TR3	2	B	45		Voice	Yellow			
TR3	2	B	46		Voice	Yellow			
TR3	2	B	47		Voice	Yellow			
TR3	2	B	48		Voice	Yellow			

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR3	2	C	1	MS CTE 1C41	Wireless	Orange	180		
TR3	2	C	2	MS CTE 1C41	Wireless	Orange	180		
TR3	2	C	3	ART 1C39	Wireless	Orange	150		
TR3	2	C	4	ART 1C39	Wireless	Orange	150		
TR3	2	C	5	ART 1C39	Wireless	Orange	150		
TR3	2	C	6	ART 1C39	Wireless	Orange	150		
TR3	2	C	7	CAREER INFO 1A27	Wireless	Orange	120		
TR3	2	C	8	CAREER INFO 1A27	Wireless	Orange	120		
TR3	2	C	9	CAREER INFO 1A27	Wireless	Orange	90		
TR3	2	C	10	CAREER INFO 1A27	Wireless	Orange	90		
TR3	2	C	11	CONF 1A34	Wireless	Orange	58		
TR3	2	C	12	CONF 1A34	Wireless	Orange	58		
TR3	2	C	13	COMMONS 1C01	Wireless	Orange	84		
TR3	2	C	14	COMMONS 1C01	Wireless	Orange	84		
TR3	2	C	15	PARENTS CENTER 1A02	Wireless	Orange	208		
TR3	2	C	16	PARENTS CENTER 1A02	Wireless	Orange	208		
TR3	2	C	17	EXTERIOR LEARNING AREA	Wireless	Orange	160		
TR3	2	C	18	EXTERIOR LEARNING AREA	Wireless	Orange	160		
TR3	2	C	19	ADMIN CONF 1A12	Wireless	Orange	194		
TR3	2	C	20	ADMIN CONF 1A12	Wireless	Orange	194		
TR3	2	C	21	CLERICAL 1A03	Wireless	Orange	205		
TR3	2	C	22	CLERICAL 1A03	Wireless	Orange	205		
TR3	2	C	23	RECEPTION 1A01	Wireless	Orange	152		
TR3	2	C	24	RECEPTION 1A01	Wireless	Orange	152		
TR3	2	C	25	COMMONS 1C01	Wireless	Orange	200		
TR3	2	C	26	COMMONS 1C01	Wireless	Orange	200		
TR3	2	C	27	COMMONS 1C01	Wireless	Orange	146		
TR3	2	C	28	COMMONS 1C01	Wireless	Orange	146		
TR3	2	C	29		Wireless	Orange			
TR3	2	C	30		Wireless	Orange			
TR3	2	C	31		Wireless	Orange			
TR3	2	C	32		Wireless	Orange			
TR3	2	C	33		Wireless	Orange			
TR3	2	C	34		Wireless	Orange			
TR3	2	C	35		Wireless	Orange			
TR3	2	C	36		Wireless	Orange			
TR3	2	C	37		Wireless	Orange			
TR3	2	C	38		Wireless	Orange			
TR3	2	C	39		Wireless	Orange			
TR3	2	C	40		Wireless	Orange			
TR3	2	C	41		Wireless	Orange			
TR3	2	C	42		Wireless	Orange			
TR3	2	C	43		Wireless	Orange			
TR3	2	C	44		Wireless	Orange			
TR3	2	C	45		Wireless	Orange			
TR3	2	C	46		Wireless	Orange			
TR3	2	C	47		Wireless	Orange			
TR3	2	C	48		Wireless	Orange			

APPR. | DATE | DESCRIPTION | SYM

NAVFAC

STATE OF KENTUCKY
ZBIGNIEW WINN REEVES
20...
LICENSED PROFESSIONAL ENGINEER

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO | DATE

BWR | KDM | BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND – WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091435

SHEET 681 OF 789

E724

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR4	1	A	1	LEARNING STUDIO 2B14	Data	Blue	161		
TR4	1	A	2	LEARNING STUDIO 2B14	Data	Blue	161		
TR4	1	A	3	LEARNING STUDIO 2B14	Printer	Green	161		
TR4	1	A	4	LEARNING STUDIO 2B14	Data	Blue	179		
TR4	1	A	5	LEARNING STUDIO 2B14	Data	Blue	193		
TR4	1	A	6	LEARNING STUDIO 2B14	Data	Blue	193		
TR4	1	A	7	LEARNING STUDIO 2B14	Data	Blue	202		
TR4	1	A	8	LEARNING STUDIO 2B14	Data	Blue	202		
TR4	1	A	9	LEARNING STUDIO 2B16	Data	Blue	209		
TR4	1	A	10	LEARNING STUDIO 2B16	Data	Blue	209		
TR4	1	A	11	LEARNING STUDIO 2B16	Data	Blue	201		
TR4	1	A	12	LEARNING STUDIO 2B16	Data	Blue	201		
TR4	1	A	13	LEARNING STUDIO 2B16	Data	Blue	179		
TR4	1	A	14	LEARNING STUDIO 2B16	Data	Blue	179		
TR4	1	A	15	LEARNING STUDIO 2B16	Printer	Green	179		
TR4	1	A	16	LEARNING STUDIO 2B16	Data	Blue	167		
TR4	1	A	17	LEARNING STUDIO 2D18	Data	Blue	169		
TR4	1	A	18	LEARNING STUDIO 2D18	Data	Blue	181		
TR4	1	A	19	LEARNING STUDIO 2D18	Data	Blue	181		
TR4	1	A	20	LEARNING STUDIO 2D18	Printer	Green	181		
TR4	1	A	21	LEARNING STUDIO 2D18	Data	Blue	193		
TR4	1	A	22	LEARNING STUDIO 2D18	Data	Blue	193		
TR4	1	A	23	LEARNING STUDIO 2D18	Data	Blue	201		
TR4	1	A	24	LEARNING STUDIO 2D18	Data	Blue	201		
TR4	1	A	25	LEARNING STUDIO 2D16	Data	Blue	256		
TR4	1	A	26	LEARNING STUDIO 2D16	Data	Blue	256		
TR4	1	A	27	LEARNING STUDIO 2D16	Data	Blue	248		
TR4	1	A	28	LEARNING STUDIO 2D16	Data	Blue	248		
TR4	1	A	29	LEARNING STUDIO 2D16	Data	Blue	227		
TR4	1	A	30	LEARNING STUDIO 2D16	Data	Blue	227		
TR4	1	A	31	LEARNING STUDIO 2D16	Printer	Green	227		
TR4	1	A	32	LEARNING STUDIO 2D16	Data	Blue	215		
TR4	1	A	33	LEARNING STUDIO 2D14	Data	Blue	209		
TR4	1	A	34	LEARNING STUDIO 2D14	Data	Blue	209		
TR4	1	A	35	LEARNING STUDIO 2D14	Printer	Green	209		
TR4	1	A	36	LEARNING STUDIO 2D14	Data	Blue	223		
TR4	1	A	37	LEARNING STUDIO 2D14	Data	Blue	238		
TR4	1	A	38	LEARNING STUDIO 2D14	Data	Blue	238		
TR4	1	A	39	LEARNING STUDIO 2D14	Data	Blue	246		
TR4	1	A	40	LEARNING STUDIO 2D14	Data	Blue	246		
TR4	1	A	41	LEARNING STUDIO 2D12	Data	Blue	229		
TR4	1	A	42	LEARNING STUDIO 2D12	Data	Blue	229		
TR4	1	A	43	LEARNING STUDIO 2D12	Data	Blue	219		
TR4	1	A	44	LEARNING STUDIO 2D12	Data	Blue	219		
TR4	1	A	45	LEARNING STUDIO 2D12	Data	Blue	189		
TR4	1	A	46	LEARNING STUDIO 2D12	Data	Blue	174		
TR4	1	A	47	LEARNING STUDIO 2D12	Data	Blue	174		
TR4	1	A	48	LEARNING STUDIO 2D12	Printer	Green	174		
TR4	1	B	1	MECH 2D09	Data	Blue	167		
TR4	1	B	2	MECH 2D09	Data	Blue	167		
TR4	1	B	3	LEARNING STUDIO 2D10	Data	Blue	158		
TR4	1	B	4	LEARNING STUDIO 2D10	Data	Blue	158		
TR4	1	B	5	LEARNING STUDIO 2D10	Data	Blue	158		
TR4	1	B	6	LEARNING STUDIO 2D10	Data	Blue	170		
TR4	1	B	7	LEARNING STUDIO 2D10	Data	Blue	183		
TR4	1	B	8	LEARNING STUDIO 2D10	Data	Blue	183		
TR4	1	B	9	LEARNING STUDIO 2D10	Data	Blue	191		
TR4	1	B	10	LEARNING STUDIO 2D10	Data	Blue	191		
TR4	1	B	11	LEARNING STUDIO 2D08	Data	Blue	181		
TR4	1	B	12	LEARNING STUDIO 2D08	Data	Blue	181		
TR4	1	B	13	LEARNING STUDIO 2D08	Data	Blue	175		
TR4	1	B	14	LEARNING STUDIO 2D08	Data	Blue	175		
TR4	1	B	15	LEARNING STUDIO 2D08	Data	Blue	153		
TR4	1	B	16	LEARNING STUDIO 2D08	Data	Blue	153		
TR4	1	B	17	LEARNING STUDIO 2D08	Data	Blue	153		
TR4	1	B	18	LEARNING STUDIO 2D08	Data	Blue	142		
TR4	1	B	19	HS GROUP LEARNING 2D06	Data	Blue	146		
TR4	1	B	20	HS GROUP LEARNING 2D06	Data	Blue	145		
TR4	1	B	21	HS GROUP LEARNING 2D06	Data	Blue	158		
TR4	1	B	22	HS GROUP LEARNING 2D06	Data	Blue	152		
TR4	1	B	23	HS GROUP LEARNING 2D06	Data	Blue	152		
TR4	1	B	24	HS GROUP LEARNING 2D06	Printer	Green	152		
TR4	1	B	25	HS GROUP LEARNING 2D06	Data	Blue	155		
TR4	1	B	26	HS GROUP LEARNING 2D06	Data	Blue	155		
TR4	1	B	27	HS ONE TO ONE 2D04	Data	Blue	158		
TR4	1	B	28	HS ONE TO ONE 2D04	Data	Blue	158		
TR4	1	B	29	HS ONE TO ONE 2D04	Data	Blue	160		
TR4	1	B	30	HS ONE TO ONE 2D04	Data	Blue	164		
TR4	1	B	31	HS ONE TO ONE 2D04	Data	Blue	164		
TR4	1	B	32	LI MODERATE/SEVERE 2D02	Data	Blue	166		
TR4	1	B	33	LI MODERATE/SEVERE 2D02	Data	Blue	166		
TR4	1	B	34	LI MODERATE/SEVERE 2D02	Data	Blue	158		
TR4	1	B	35	LI MODERATE/SEVERE 2D02	Data	Blue	158		
TR4	1	B	36	LI MODERATE/SEVERE 2D02	Data	Blue	123		
TR4	1	B	37	LI MODERATE/SEVERE 2D02	Data	Blue	120		
TR4	1	B	38	LI MODERATE/SEVERE 2D02	Data	Blue	120		
TR4	1	B	39	LI MODERATE/SEVERE 2D02	Printer	Green	120		
TR4	1	B	40	MS SCIENCE 2B04	Data	Blue	120		
TR4	1	B	41	MS SCIENCE 2B04	Data	Blue	120		
TR4	1	B	42	MS SCIENCE 2B04	Data	Blue	130		
TR4	1	B	43	MS SCIENCE 2B04	Data	Blue	130		
TR4	1	B	44	MS SCIENCE 2B04	Data	Blue	143		
TR4	1	B	45	MS SCIENCE 2B04	Data	Blue	143		
TR4	1	B	46	MS SCIENCE 2B04	Data	Blue	114		
TR4	1	B	47	MS SCIENCE 2B04	Data	Blue	114		
TR4	1	B	48	MS SCIENCE 2B04	Data	Blue	114		

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR4	1	C	1	MS SCIENCE 2B04	Data	Blue	98		
TR4	1	C	2	MS SCIENCE 2B04	Data	Blue	98		
TR4	1	C	3	MS SCIENCE 2B04	Data	Blue	88		
TR4	1	C	4	MS SCIENCE 2B04	Data	Blue	88		
TR4	1	C	5	MS SCIENCE 2B04	Data	Blue	88		
TR4	1	C	6	MS SCIENCE 2B04	Data	Blue	88		
TR4	1	C	7	MS SCIENCE 2B04	Printer	Green	88		
TR4	1	C	8	MS SCIENCE 2B04	Data	Blue	97		
TR4	1	C	9	READING LAB 2B02	Data	Blue	75		
TR4	1	C	10	READING LAB 2B02	Data	Blue	75		
TR4	1	C	11	READING LAB 2B02	Data	Blue	92		
TR4	1	C	12	READING LAB 2B02	Data	Blue	92		
TR4	1	C	13	READING LAB 2B02	Data	Blue	96		
TR4	1	C	14	READING LAB 2B02	Data	Blue	96		
TR4	1	C	15	READING LAB 2B02	Data	Blue	92		
TR4	1	C	16	READING LAB 2B02	Data	Blue	92		
TR4	1	C	17	READING LAB 2B02	Printer	Green	92		
TR4	1	C	18	READING LAB 2B02	Data	Blue	83		
TR4	1	C	19	MS ONE TO ONE 2B08	Data	Blue	88		
TR4	1	C	20	MS ONE TO ONE 2B08	Data	Blue	91		
TR4	1	C	21	MS ONE TO ONE 2B08	Data	Blue	91		
TR4	1	C	22	MS ONE TO ONE 2B08	Data	Blue	98		
TR4	1	C	23	MS ONE TO ONE 2B08	Data	Blue	98		
TR4	1	C	24	SCI PREP 2B06	Data	Blue	94		
TR4	1	C	25	SCI PREP 2B06	Data	Blue	94		
TR4	1	C	26	LEARNING STUDIO 2B10	Data	Blue	84		
TR4	1	C	27	LEARNING STUDIO 2B10	Data	Blue	84		
TR4	1	C	28	LEARNING STUDIO 2B10	Printer	Green	84		
TR4	1	C	29	LEARNING STUDIO 2B10	Data	Blue	95		
TR4	1	C	30	LEARNING STUDIO 2B10	Data	Blue	110		
TR4	1	C	31	LEARNING STUDIO 2B10	Data	Blue	110		
TR4	1	C	32	LEARNING STUDIO 2B10	Data	Blue	119		
TR4	1	C	33	LEARNING STUDIO 2B10	Data	Blue	119		
TR4	1	C	34	LEARNING STUDIO 2B12	Data	Blue	135		
TR4	1	C	35	LEARNING STUDIO 2B12	Data	Blue	135		
TR4	1	C	36	LEARNING STUDIO 2B12	Data	Blue	143		
TR4	1	C	37	LEARNING STUDIO 2B12	Data	Blue	143		
TR4	1	C	38	LEARNING STUDIO 2B12	Data	Blue	144		
TR4	1	C	39	LEARNING STUDIO 2B12	Data	Blue	144		
TR4	1	C	40	LEARNING STUDIO 2B12	Printer	Green	144		
TR4	1	C	41	LEARNING STUDIO 2B12	Data	Blue	131		
TR4	1	C	42	MECH 2B05	Data	Blue	142		
TR4	1	C	43	MECH 2B05	Data	Blue	142		
TR4	1	C	44	MS HUB 2B00	Data	Blue	94		
TR4	1	C	45	MS HUB 2B00	Data	Blue	94		
TR4	1	C	46	MS HUB 2B00	Data	Blue	126		
TR4	1	C	47	MS HUB 2B00	Data	Blue	126		
TR4	1	C	48	MS HUB 2B00	Data	Blue	84		
TR4	1	D	1	MS HUB 2B00	Data	Blue	87		
TR4	1	D	2	MS HUB 2B00	Data	Blue	87		
TR4	1	D	3	MS HUB 2B00	Printer	Green	87		
TR4	1	D	4	FLEX HUB 2D01	Data	Blue	174		
TR4	1	D	5	FLEX HUB 2D01	Data	Blue	174		
TR4	1	D	6	FLEX HUB 2D01	Data	Blue	91		
TR4	1	D	7	FLEX HUB 2D01	Data	Blue	91		
TR4	1	D	8	FLEX HUB 2D01	Data	Blue	85		
TR4	1	D	9	FLEX HUB 2D01	Data	Blue	85		
TR4	1	D	10	FLEX HUB 2D01	Data	Blue	89		
TR4	1	D	11	FLEX HUB 2D01	Data	Blue	89		
TR4	1	D	12	FLEX HUB 2D01	Data	Blue	91		
TR4	1	D	13	FLEX HUB 2D01	Data	Blue	91		
TR4	1	D	14	FLEX HUB 2D01	Data	Blue	82		
TR4	1	D	15	FLEX HUB 2D01	Data	Blue	78		
TR4	1	D	16	FLEX HUB 2D01	Data	Blue	78		
TR4	1	D	17	FLEX HUB 2D01	Printer	Green	78		
TR4	1	D	18	HS HUB 2D00	Data	Blue	89		
TR4	1	D	19	HS HUB 2D00	Data	Blue	92		
TR4	1	D	20	HS HUB 2D00	Data	Blue	92		
TR4	1	D	21	HS HUB 2D00	Printer	Green	92		
TR4	1	D	22	HS HUB 2D00	Data	Blue	157		
TR4	1	D	23	HS HUB 2D00	Data	Blue	157		
TR4	1	D	24	HS HUB 2D00	Data	Blue	119		
TR4	1	D	25	HS HUB 2D00	Data	Blue	119		
TR4	1	D	26	HS ACADEMIC SUPPORT 2D05	Data	Blue	59		
TR4	1	D	27	HS ACADEMIC SUPPORT 2D05	Data	Blue	59		
TR4	1	D	28	HS ACADEMIC SUPPORT 2D05	Printer	Green	59		
TR4	1	D	29	HS ACADEMIC SUPPORT 2D05	Data	Blue	67		
TR4	1	D	30	HS ACADEMIC SUPPORT 2D05	Data	Blue	86		
TR4	1	D	31	HS ACADEMIC SUPPORT 2D05	Data	Blue	86		
TR4	1	D	32	HS ACADEMIC SUPPORT 2D05	Data	Blue	93		
TR4	1	D	33	HS ACADEMIC SUPPORT 2D05	Data	Blue	93		
TR4	1	D	34	MS GROUP LEARNING 2D07	Data	Blue	65		
TR4	1	D	35	MS GROUP LEARNING 2D07	Data	Blue	68		
TR4	1	D	36	MS GROUP LEARNING 2D07	Data	Blue	68		
TR4	1	D	37	MS GROUP LEARNING 2D07	Printer	Green	68		
TR4	1	D	38	MS GROUP LEARNING 2D07	Data	Blue	73		
TR4	1	D	39	MS GROUP LEARNING 2D07	Data	Blue	73		
TR4	1	D	40	MS GROUP LEARNING 2D07	Data	Blue	80		
TR4	1	D	41	MS GROUP LEARNING 2D07	Data	Blue	80		
TR4	1	D	42	MS GROUP LEARNING 2B03	Data	Blue	80		
TR4	1	D	43	MS GROUP LEARNING 2B03	Data	Blue	80		
TR4	1	D	44	MS GROUP LEARNING 2B03	Data	Blue	73		
TR4	1	D	45	MS GROUP LEARNING 2B03	Data	Blue	73		
TR4	1	D	46	MS GROUP LEARNING 2B03	Data	Blue	71		
TR4	1	D	47	MS GROUP LEARNING 2B03	Data	Blue	71		
TR4	1	D	48	MS GROUP LEARNING 2B03	Printer	Green	71		

APPR. | DATE | NO. | DESCRIPTION

NAVFAC

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO DATE

BWR KDM BKB

PM/DM
BRANCH MANAGER
CHIEF ENGI ARCH
FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:
PROJECT NO.: P-021
CONSTR. CONTR. NO. W91236-15-C-0023
NAVFAC DRAWING NO. 13091436
SHEET 682 OF 789
E725

DRAWFORM REVISION: 12 MARCH 2009

File Path

RTA SUBMISSION - 10/13/2016

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR4	1	E	1	MS GROUP LEARNING 2B03	Data	Blue	78		
TR4	1	E	2	HS LI MODERATE 2D03	Data	Blue	62		
TR4	1	E	3	HS LI MODERATE 2D03	Data	Blue	62		
TR4	1	E	4	HS LI MODERATE 2D03	Data	Blue	46		
TR4	1	E	5	HS LI MODERATE 2D03	Data	Blue	46		
TR4	1	E	6	HS LI MODERATE 2D03	Printer	Green	46		
TR4	1	E	7	HS LI MODERATE 2D03	Data	Blue	51		
TR4	1	E	8	HS LI MODERATE 2D03	Data	Blue	68		
TR4	1	E	9	HS LI MODERATE 2D03	Data	Blue	68		
TR4	1	E	10	MS ACADEMIC SUPPORT 2B01	Data	Blue	74		
TR4	1	E	11	MS ACADEMIC SUPPORT 2B01	Data	Blue	74		
TR4	1	E	12	MS ACADEMIC SUPPORT 2B01	Data	Blue	69		
TR4	1	E	13	MS ACADEMIC SUPPORT 2B01	Data	Blue	69		
TR4	1	E	14	MS ACADEMIC SUPPORT 2B01	Data	Blue	44		
TR4	1	E	15	MS ACADEMIC SUPPORT 2B01	Data	Blue	47		
TR4	1	E	16	MS ACADEMIC SUPPORT 2B01	Data	Blue	47		
TR4	1	E	17	MS ACADEMIC SUPPORT 2B01	Printer	Green	47		
TR4	1	E	18	CENTRAL WORKROOM 2E05	Data	Blue	26		
TR4	1	E	19	CENTRAL WORKROOM 2E05	Data	Blue	26		
TR4	1	E	20	CENTRAL WORKROOM 2E05	Printer	Green	40		
TR4	1	E	21	CENTRAL WORKROOM 2E05	Data	Blue	45		
TR4	1	E	22	CENTRAL WORKROOM 2E05	Data	Blue	45		
TR4	1	E	23	TR4 2E06	Data	Blue	15		
TR4	1	E	24	TR4 2E06	Data	Blue	15		
TR4	1	E	25	TR4 2E06	Printer	Green	15		
TR4	1	E	26	MECH 2E07	Data	Blue	36		
TR4	1	E	27	MECH 2E07	Data	Blue	36		
TR4	1	E	28	ASAC 2C14	Data	Blue	106		
TR4	1	E	29	ASAC 2C14	Data	Blue	106		
TR4	1	E	30	ASAC 2C14	Printer	Green	106		
TR4	1	E	31	ASAC 2C14	Data	Blue	118		
TR4	1	E	32	STAFF COLLAB 2E01	Data	Blue	113		
TR4	1	E	33	STAFF COLLAB 2E01	Data	Blue	113		
TR4	1	E	34	STAFF COLLAB 2E01	Printer	Green	113		
TR4	1	E	35	STAFF COLLAB 2E01	Data	Blue	104		
TR4	1	E	36	STAFF COLLAB 2E01	Data	Blue	93		
TR4	1	E	37	STAFF COLLAB 2E01	Data	Blue	93		
TR4	1	E	38	STAFF COLLAB 2E01	Data	Blue	93		
TR4	1	E	39	STAFF COLLAB 2E01	Data	Blue	104		
TR4	1	E	40	CIRCULATION 2C18	Data	Blue	100		
TR4	1	E	41		Data	Blue			
TR4	1	E	42		Data	Blue			
TR4	1	E	43		Data	Blue			
TR4	1	E	44		Data	Blue			
TR4	1	E	45		Data	Blue			
TR4	1	E	46		Data	Blue			
TR4	1	E	47		Data	Blue			
TR4	1	E	48		Data	Blue			

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR4	2	A	1	LEARNING STUDIO 2B14	Video	Red	179		
TR4	2	A	2	LEARNING STUDIO 2B16	Video	Red	167		
TR4	2	A	3	LEARNING STUDIO 2D18	Video	Red	179		
TR4	2	A	4	LEARNING STUDIO 2D16	Video	Red	215		
TR4	2	A	5	LEARNING STUDIO 2D14	Video	Red	223		
TR4	2	A	6	LEARNING STUDIO 2D12	Video	Red	189		
TR4	2	A	7	LEARNING STUDIO 2D10	Video	Red	170		
TR4	2	A	8	LEARNING STUDIO 2D08	Video	Red	142		
TR4	2	A	9	HS GROUP LEARNING 2D06	Video	Red	158		
TR4	2	A	10	HS ONE TO ONE 2D04	Video	Red	164		
TR4	2	A	11	LI MODERATE/SEVERE 2D02	Video	Red	123		
TR4	2	A	12	MS SCIENCE 2B04	Video	Red	97		
TR4	2	A	13	READING LAB 2B02	Video	Red	83		
TR4	2	A	14	MS ONE TO ONE 2B08	Video	Red	81		
TR4	2	A	15	LEARNING STUDIO 2B10	Video	Red	95		
TR4	2	A	16	LEARNING STUDIO 2B12	Video	Red	131		
TR4	2	A	17	MS HUB 2B00	Video	Red	84		
TR4	2	A	18	FLEX HUB 2D01	Video	Red	82		
TR4	2	A	19	HS HUB 2D00	Video	Red	89		
TR4	2	A	20	HS ACADEMIC SUPPORT 2D05	Video	Red	67		
TR4	2	A	21	MS GROUP LEARNING 2D07	Video	Red	65		
TR4	2	A	22	MS GROUP LEARNING 2B03	Video	Red	78		
TR4	2	A	23	MS ACADEMIC SUPPORT 2B01	Video	Red	44		
TR4	2	A	24	HS LI MODERATE 2D03	Video	Red	51		
TR4	2	A	25	CENTRAL WORKROOM 2E05	Video	Red	47		
TR4	2	A	26	STAFF COLLAB 2E01	Video	Red	104		
TR4	2	A	27	STAFF COLLAB 2E01	Video	Red	83		
TR4	2	A	28	STAFF COLLAB 2E01	Video	Red	104		
TR4	2	A	29	CIRCULATION 2C18	Video	Red	98		
TR4	2	A	30	CIRCULATION 2C18	Video	Red	96		
TR4	2	A	31	STAFF COLLAB 2E01	Video	Red	86		
TR4	2	A	32	ASAC 2C14	Video	Red	118		
TR4	2	A	33	CIRCULATION 2C18	Video	Red	89		
TR4	2	A	34		Video	Red			
TR4	2	A	35		Video	Red			
TR4	2	A	36		Video	Red			
TR4	2	A	37		Video	Red			
TR4	2	A	38		Video	Red			
TR4	2	A	39		Video	Red			
TR4	2	A	40		Video	Red			
TR4	2	A	41		Video	Red			
TR4	2	A	42		Video	Red			
TR4	2	A	43		Video	Red			
TR4	2	A	44		Video	Red			
TR4	2	A	45		Video	Red			
TR4	2	A	46		Video	Red			
TR4	2	A	47		Video	Red			
TR4	2	A	48		Video	Red			
TR4	2	B	1	LEARNING STUDIO 2B14	Voice	Yellow	159		
TR4	2	B	2	LEARNING STUDIO 2B16	Voice	Yellow	158		
TR4	2	B	3	LEARNING STUDIO 2D18	Voice	Yellow	158		
TR4	2	B	4	LEARNING STUDIO 2D16	Voice	Yellow	207		
TR4	2	B	5	LEARNING STUDIO 2D14	Voice	Yellow	207		
TR4	2	B	6	LEARNING STUDIO 2D12	Voice	Yellow	166		
TR4	2	B	7	MECH 2D09	Voice	Yellow	167		
TR4	2	B	8	LEARNING STUDIO 2D10	Voice	Yellow	150		
TR4	2	B	9	LEARNING STUDIO 2D08	Voice	Yellow	131		
TR4	2	B	10	HS GROUP LEARNING 2D06	Voice	Yellow	138		
TR4	2	B	11	HS ONE TO ONE 2D04	Voice	Yellow	149		
TR4	2	B	12	LI MODERATE/SEVERE 2D02	Voice	Yellow	130		
TR4	2	B	13	LIMS SHOWER 2D02.3	Voice	Yellow	158		
TR4	2	B	14	MS SCIENCE 2B04	Voice	Yellow	105		
TR4	2	B	15	READING LAB 2B02	Voice	Yellow	61		
TR4	2	B	16	MS ONE TO ONE 2B08	Voice	Yellow	82		
TR4	2	B	17	SCI PREP 2B06	Voice	Yellow	103		
TR4	2	B	18	LEARNING STUDIO 2B10	Voice	Yellow	79		
TR4	2	B	19	LEARNING STUDIO 2B12	Voice	Yellow	126		
TR4	2	B	20	MECH 2B05	Voice	Yellow	141		
TR4	2	B	21	MS HUB 2B00	Voice	Yellow	56		
TR4	2	B	22	HS HUB 2D00	Voice	Yellow	164		
TR4	2	B	23	HS ACADEMIC SUPPORT 2D05	Voice	Yellow	92		
TR4	2	B	24	MS GROUP LEARNING 2D07	Voice	Yellow	90		
TR4	2	B	25	MS GROUP LEARNING 2B03	Voice	Yellow	94		
TR4	2	B	26	MS ACADEMIC SUPPORT 2B01	Voice	Yellow	55		
TR4	2	B	27	HS LI MODERATE 2D03	Voice	Yellow	80		
TR4	2	B	28	CENTRAL WORKROOM 2E05	Voice	Yellow	40		
TR4	2	B	29	TR4 2E06	Voice	Yellow	15		
TR4	2	B	30	MECH 2E07	Voice	Yellow	38		
TR4	2	B	31	STAFF COLLAB 2E01	Voice	Yellow	125		
TR4	2	B	32	ASAC 2C14	Voice	Yellow	115		
TR4	2	B	33	STAFF COLLAB 2E01	Voice	Yellow	109		
TR4	2	B	34		Voice	Yellow			
TR4	2	B	35		Voice	Yellow			
TR4	2	B	36		Voice	Yellow			
TR4	2	B	37		Voice	Yellow			
TR4	2	B	38		Voice	Yellow			
TR4	2	B	39		Voice	Yellow			
TR4	2	B	40		Voice	Yellow			
TR4	2	B	41		Voice	Yellow			
TR4	2	B	42		Voice	Yellow			
TR4	2	B	43		Voice	Yellow			
TR4	2	B	44		Voice	Yellow			
TR4	2	B	45		Voice	Yellow			
TR4	2	B	46		Voice	Yellow			
TR4	2	B	47		Voice	Yellow			
TR4	2	B	48		Voice	Yellow			

APPR. | DATE | DESCRIPTION | SYM

NAVFAC

STATE OF KENTUCKY · BRADLEY ALLEN REEVES · 20... · PROFESSIONAL ENGINEER

SEAL

EWING COLE

Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-823-2020 Fax: 215-574-0952

A/E INFO

APPROVED

FOR COMMANDER NAVFAC
ACTIVITY

SATISFACTORY TO | DATE

BWR | KDM | BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
DoDEA
NAVAL FACILITIES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND – WASHINGTON
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO.
W91236-15-C-0023

NAVFAC DRAWING NO.
13091437

SHEET 683 OF 789

E726

DRAWFORM REVISION: 10 MARCH 2009

RTA SUBMISSION - 10/13/2016

File Path

1 2 3 4 5

D C B A

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR4	2	C	1	LEARNING STUDIO 2B14	Wireless	Orange	180		
TR4	2	C	2	LEARNING STUDIO 2B14	Wireless	Orange	180		
TR4	2	C	3	LEARNING STUDIO 2B16	Wireless	Orange	180		
TR4	2	C	4	LEARNING STUDIO 2B16	Wireless	Orange	180		
TR4	2	C	5	LEARNING STUDIO 2D18	Wireless	Orange	180		
TR4	2	C	6	LEARNING STUDIO 2D18	Wireless	Orange	180		
TR4	2	C	7	LEARNING STUDIO 2D16	Wireless	Orange	227		
TR4	2	C	8	LEARNING STUDIO 2D16	Wireless	Orange	227		
TR4	2	C	9	LEARNING STUDIO 2D14	Wireless	Orange	228		
TR4	2	C	10	LEARNING STUDIO 2D14	Wireless	Orange	228		
TR4	2	C	11	LEARNING STUDIO 2D12	Wireless	Orange	190		
TR4	2	C	12	LEARNING STUDIO 2D12	Wireless	Orange	190		
TR4	2	C	13	LEARNING STUDIO 2D10	Wireless	Orange	150		
TR4	2	C	14	LEARNING STUDIO 2D10	Wireless	Orange	150		
TR4	2	C	15	LEARNING STUDIO 2D08	Wireless	Orange	130		
TR4	2	C	16	LEARNING STUDIO 2D08	Wireless	Orange	130		
TR4	2	C	17	HS GROUP LEARNING 2D06	Wireless	Orange	140		
TR4	2	C	18	HS GROUP LEARNING 2D06	Wireless	Orange	140		
TR4	2	C	19	LI MODERATE/SEVERE 2D02	Wireless	Orange	177		
TR4	2	C	20	LI MODERATE/SEVERE 2D02	Wireless	Orange	177		
TR4	2	C	21	STAFF COLLAB 2E01	Wireless	Orange			
TR4	2	C	22	STAFF COLLAB 2E01	Wireless	Orange			
TR4	2	C	23	READING LAB 2B02	Wireless	Orange			
TR4	2	C	24	READING LAB 2B02	Wireless	Orange			
TR4	2	C	25	MS SCIENCE 2B04	Wireless	Orange	110		
TR4	2	C	26	MS SCIENCE 2B04	Wireless	Orange	110		
TR4	2	C	27	LEARNING STUDIO 2B10	Wireless	Orange	103		
TR4	2	C	28	LEARNING STUDIO 2B10	Wireless	Orange	103		
TR4	2	C	29	LEARNING STUDIO 2B12	Wireless	Orange	145		
TR4	2	C	30	LEARNING STUDIO 2B12	Wireless	Orange	145		
TR4	2	C	31	MS HUB 2B00	Wireless	Orange	97		
TR4	2	C	32	MS HUB 2B00	Wireless	Orange	97		
TR4	2	C	33	HS HUB 2D00	Wireless	Orange	71		
TR4	2	C	34	HS HUB 2D00	Wireless	Orange	71		
TR4	2	C	35	CENTRAL WORKROOM 2E05	Wireless	Orange	33		
TR4	2	C	36	CENTRAL WORKROOM 2E05	Wireless	Orange	33		
TR4	2	C	37	HS ACADEMIC SUPPORT 2D05	Wireless	Orange	50		
TR4	2	C	38	HS ACADEMIC SUPPORT 2D05	Wireless	Orange	50		
TR4	2	C	39	MS GROUP LEARNING 2B03	Wireless	Orange	81		
TR4	2	C	40	MS GROUP LEARNING 2B03	Wireless	Orange	81		
TR4	2	C	41	MS GROUP LEARNING 2D07	Wireless	Orange	70		
TR4	2	C	42	MS GROUP LEARNING 2D07	Wireless	Orange	70		
TR4	2	C	43	HS ACADEMIC SUPPORT 2D05	Wireless	Orange			
TR4	2	C	44	HS ACADEMIC SUPPORT 2D05	Wireless	Orange			
TR4	2	C	45	HS LI MODERATE 2D03	Wireless	Orange	65		
TR4	2	C	46	HS LI MODERATE 2D03	Wireless	Orange	65		
TR4	2	C	47		Wireless	Orange			
TR4	2	C	48		Wireless	Orange			
TR4	2	D	1				92		
TR4	2	D	2				92		
TR4	2	D	3						
TR4	2	D	4						
TR4	2	D	5						
TR4	2	D	6						
TR4	2	D	7						
TR4	2	D	8						
TR4	2	D	9						
TR4	2	D	10						
TR4	2	D	11						
TR4	2	D	12						
TR4	2	D	13						
TR4	2	D	14						
TR4	2	D	15						
TR4	2	D	16						
TR4	2	D	17						
TR4	2	D	18						
TR4	2	D	19						
TR4	2	D	20						
TR4	2	D	21						
TR4	2	D	22						
TR4	2	D	23						
TR4	2	D	24						
TR4	2	D	25						
TR4	2	D	26						
TR4	2	D	27						
TR4	2	D	28						
TR4	2	D	29						
TR4	2	D	30						
TR4	2	D	31						
TR4	2	D	32						
TR4	2	D	33						
TR4	2	D	34						
TR4	2	D	35						
TR4	2	D	36						
TR4	2	D	37						
TR4	2	D	38						
TR4	2	D	39						
TR4	2	D	40						
TR4	2	D	41						
TR4	2	D	42						
TR4	2	D	43						
TR4	2	D	44						
TR4	2	D	45						
TR4	2	D	46						
TR4	2	D	47						
TR4	2	D	48						

CABLE PULL SCHEDULE

Telecom Room	Rack Designation	Patch Panel	Port Number	Room	Application Type	Cable Color	Cable Length (<250 Ft)	POE	Remarks
TR5	1	A	1	COMP CENTER 2C09	Data	Blue	174		
TR5	1	A	2	COMP CENTER 2C09	Data	Blue	174		
TR5	1	A	3	COMP CENTER 2C09	Data	Blue	174		
TR5	1	A	4	COMP CENTER 2C09	Printer	Green	174		
TR5	1	A	5	COMP CENTER 2C09	Data	Blue	180		
TR5	1	A	6	COMP CENTER 2C09	Data	Blue	180		
TR5	1	A	7	COMP CENTER 2C09	Data	Blue	190		
TR5	1	A	8	COMP CENTER 2C09	Data	Blue	193		
TR5	1	A	9	COMP CENTER 2C09	Data	Blue	193		
TR5	1	A	10	COMP CENTER 2C09	Printer	Green	193		
TR5	1	A	11	COMP CENTER 2C09	Data	Blue	86		
TR5	1	A	12	COMP CENTER 2C09	Data	Blue	186		
TR5	1	A	13	COMP CENTER 2C09	Data	Blue	181		
TR5	1	A	14	COMP CENTER 2C09	Data	Blue	181		
TR5	1	A	15	COMP CENTER 2C09	Data	Blue	176		
TR5	1	A	16	COMP CENTER 2C09	Data	Blue	76		
TR5	1	A	17	COMP CENTER 2C09	Data	Blue	171		
TR5	1	A	18	COMP CENTER 2C09	Data	Blue	171		
TR5	1	A	19	COMP CENTER 2C09	Data	Blue	166		
TR5	1	A	20	COMP CENTER 2C09	Data	Blue	166		
TR5	1	A	21	COMP CENTER 2C09	Data	Blue	163		
TR5	1	A	22	COMP CENTER 2C09	Data	Blue	163		
TR5	1	A	23	COMP CENTER 2C09	Data	Blue	167		
TR5	1	A	24	COMP CENTER 2C09	Data	Blue	167		
TR5	1	A	25	COMP CENTER 2C09	Data	Blue	172		
TR5	1	A	26	COMP CENTER 2C09	Data	Blue	172		
TR5	1	A	27	COMP CENTER 2C09	Data	Blue	177		
TR5	1	A	28	COMP CENTER 2C09	Data	Blue	177		
TR5	1	A	29	COMP CENTER 2C09	Data	Blue	180		
TR5	1	A	30	COMP CENTER 2C09	Data	Blue	180		
TR5	1	A	31	INFO CENTER 2C01	Data	Blue	158		
TR5	1	A	32	INFO CENTER 2C01	Data	Blue	158		
TR5	1	A	33	INFO CENTER 2C01	Data	Blue	152		
TR5	1	A	34	INFO CENTER 2C01	Data	Blue	152		
TR5	1	A	35	INFO CENTER 2C01	Data	Blue	148		
TR5	1	A	36	INFO CENTER 2C01	Data	Blue	148		
TR5	1	A	37	INFO CENTER 2C01	Data	Blue	141		
TR5	1	A	38	INFO CENTER 2C01	Data	Blue	141		
TR5	1	A	39	INFO CENTER 2C01	Data	Blue	120		
TR5	1	A	40	INFO CENTER 2C01	Data	Blue	118		
TR5	1	A	41	INFO CENTER 2C01	Data	Blue	118		
TR5	1	A	42	INFO CENTER 2C01	Printer	Green	118		
TR5	1	A	43	INFO CENTER 2C01	Data	Blue	114		
TR5	1	A	44	INFO CENTER 2C01	Data	Blue	114		
TR5	1	A	45	INFO CENTER 2C01	Data	Blue	116		
TR5	1	A	46	INFO CENTER 2C01	Data	Blue	116		
TR5	1	A	47	INFO CENTER 2C01	Data	Blue	150		
TR5	1	A	48	INFO CENTER 2C01	Data	Blue	150		
TR5	1	B	1	INFO CENTER 2C01	Data	Blue	117		
TR5	1	B	2	STAFF COLLAB 2C02	Data	Blue	117		
TR5	1	B	3	STAFF COLLAB 2C02	Data	Blue	120		
TR5	1	B	4	STAFF COLLAB 2C02	Data	Blue	120		
TR5	1	B	5	STAFF COLLAB 2C02	Data	Blue	129		
TR5	1	B	6	STAFF COLLAB 2C02	Data	Blue	129		
TR5	1	B	7	STAFF COLLAB 2C02	Data	Blue	124		
TR5	1	B	8	STAFF COLLAB 2C02	Data	Blue	124		
TR5	1	B	9	STAFF COLLAB 2C02	Printer	Green	119		
TR5	1	B	10	VIDEO BROADCASTING 2C04	Data	Blue	82		
TR5	1	B	11	VIDEO BROADCASTING 2C04	Data	Blue	82		
TR5	1	B	12	VIDEO BROADCASTING 2C04	Printer	Green	82		
TR5	1	B	13	VIDEO BROADCASTING 2C04	Data	Blue	85		
TR5	1	B	14	VIDEO BROADCASTING 2C04	Data	Blue	85		
TR5	1	B	15	VIDEO BROADCASTING 2C04	Data	Blue	90		
TR5	1	B	16	VIDEO BROADCASTING 2C04	Data	Blue	90		
TR5	1	B	17	VIDEO BROADCASTING 2C04	Data	Blue	79		
TR5	1	B	18	VIDEO BROADCASTING 2C04	Data	Blue	79		
TR5	1	B	19	VIDEO BROADCASTING 2C04	Data	Blue	73		
TR5	1	B	20	VIDEO BROADCASTING 2C04	Data	Blue	80		
TR5	1	B	21	VIDEO BROADCASTING 2C04	Data	Blue	80		
TR5	1	B	22	VIDEO BROADCASTING 2C04	Data	Blue	75		
TR5	1	B	23	VIDEO BROADCASTING 2C04	Data	Blue	62		
TR5	1	B	24	VIDEO BROADCASTING 2C04	Printer	Green	62		
TR5	1	B	25	VIDEO BROADCASTING 2C04	Data	Blue	59		
TR5	1	B	26	VIDEO BROADCASTING 2C04	Data	Blue	59		
TR5	1	B	27	HS CTE 2C05	Data	Blue	60		
TR5	1	B	28	HS CTE 2C05	Data	Blue	60		
TR5	1	B	29	HS CTE 2C05	Data	Blue	54		
TR5	1	B	30	HS CTE 2C05	Data	Blue	54		
TR5	1	B	31	HS CTE 2C05	Data	Blue	35		
TR5	1	B	32	HS CTE 2C05	Data	Blue	35		
TR5	1	B	33	HS CTE 2C05	Data	Blue	48		
TR5	1	B	34	HS CTE 2C05	Data	Blue	52		
TR5	1	B	35	HS CTE 2C05	Data	Blue	52		
TR5	1	B	36	HS CTE 2C05	Printer	Green	52		
TR5	1	B	37	MECH 2C08	Data	Blue	34		
TR5	1	B	38	MECH 2C08	Data	Blue	34		
TR5	1	B	39	TR5 2C06	Data	Blue	6		
TR5	1	B	40	TR5 2C06	Data	Blue	6		
TR5	1	B	41	TR5 2C06	Printer	Green	6		
TR5	1	B	42	HS CTE HUB 2C07	Data	Blue	71		
TR5	1	B	43	HS CTE HUB 2C07	Data	Blue	71		
TR5	1	B	44	HS CTE HUB 2C07	Data	Blue	64		
TR5	1	B	45	HS CTE HUB 2C07	Data	Blue	64		
TR5	1	B	46	HS CTE HUB 2C07	Printer	Green	64		
TR5	1	B	47	HS CTE HUB 2C07	Data	Blue	66		
TR5	1	B	48	HS CTE HUB 2C07	Data	Blue			

SYM DESCRIPTION DATE APPR

SEAL

EWING COLE
Federal Reserve Bank Building
100 North 6th Street
Philadelphia, PA 19106-1590
Tel: 215-923-2020 Fax: 215-574-0952
A/E INFO

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO DATE

BWR KDM BKB

PM/DM

BRANCH MANAGER

CHIEF ENG/ ARCH

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND ~ WASHINGTON
DoDEA
MARINE CORPS BASE QUANTICO, VIRGINIA
MARINE CORPS BASE QUANTICO
QUANTICO, VA

REPLACE QUANTICO M/H SCHOOL

CABLE PULL SCHEDULES

SCALE:

PROJECT NO.: P-021

CONSTR. CONTR. NO. W91236-15-C-0023

NAVFAC DRAWING NO. 13091438

SHEET 684 OF 789

E727

RTA SUBMISSION - 10/13/2016

DRAWFORM REVISION: 10 MARCH 2009

File Path