


DEMOLITION LEGEND

REMOVE

REMOVE

- GENERAL NOTES:
- EXISTING CONDITIONS COMPILED FROM GIS INFORMATION PROVIDED BY THE GOVERNMENT AND ARE NOT THE RESULT OF A SURVEY. NO WARRANTY IS GIVEN OR IMPLIED REGARDING THE ACCURACY OF THE FEATURES SHOWN HEREIN. FIELD VERIFY ALL EXISTING FEATURES PRIOR TO DEMOLITION WORK. NOTIFY THE DESIGN ENGINEER IMMEDIATELY IF DISCREPANCIES ARE NOTED.
 - UNDERGROUND UTILITIES ARE SHOWN FROM GIS INFORMATION PROVIDED BY THE GOVERNMENT. ALL EXISTING UTILITY LOCATIONS SHOULD BE CONSIDERED APPROXIMATE.
 - ALL DEMOLITION SHALL BE IN ACCORDANCE WITH CAMP LEJEUNE AND NAVFAC STANDARDS AND SPECIFICATIONS.
 - COORDINATE WITH CONTRACTING OFFICER REGARDING EXISTING UTILITIES ON SITE THAT ARE TO REMAIN IN PLACE. ADDITIONALLY, COORDINATE WITH CONTRACTING OFFICER REGARDING PHASING OF UTILITY REMOVAL AND SERVICE OUTAGES DURING DEMOLITION.
 - FEATURES AND MATERIALS TO BE REMOVED SHALL BE DISPOSED OF ACCORDING TO CAMP LEJEUNE, STATE, AND LOCAL REGULATIONS AND CODES.
 - COORDINATE ALL COMMUNICATIONS, TELEPHONE, FIBER OPTIC, OVERHEAD POWER, AND UNDERGROUND UTILITY LINE REMOVAL OR RELOCATION WITH CONTRACTING OFFICER.
 - HAZARDOUS MATERIALS AND ASBESTOS HAVE BEEN LOCATED IN THE DEMOLITION AREA. REFER TO 'ASBESTOS INSPECTION REPORT OF BUILDING 1041' BY MCE CAMP LEJEUNE FOR FURTHER DETAILS.
 - REMOVE EXISTING BRIG AFTER PROPOSED CONFINEMENT FACILITY IS COMPLETE AND OPERATIONAL. COORDINATE WITH CONTRACTING OFFICER REGARDING DEMOLITION SCHEDULE. REFER TO DEMOLITION SCHEDULE, THIS SHEET.

- DEMOLITION SEQUENCE:
- REMOVE EXISTING FEATURES ON MAIN PROJECT SITE AS INDICATED ON DRAWING C-100. DEMOLITION SHALL BE PERFORMED IN ACCORDANCE WITH APPROVED EROSION CONTROL PLAN CONSTRUCTION SEQUENCE.
 - BEGIN CONSTRUCTION OF NEW PRE-TRIAL CONFINEMENT FACILITY SITE AS SHOWN ON DRAWING C-102.
 - ONCE NEW FACILITY IS COMPLETED, OPERATIONAL, AND OCCUPIED, BEGIN DEMOLITION OF EXISTING BRIG FACILITY AS INDICATED ON THIS PLAN.
 - ONCE ALL FEATURES OF EXISTING BRIG ARE REMOVED, FINE GRADE THE AREA FOR A SMOOTH APPEARANCE AND STABILIZE PER SEEDING SCHEDULE.
 - REFER TO EROSION CONTROL PLAN C-112 FOR EROSION CONTROL MEASURES REQUIRED FOR DEMOLITION AND THE NECESSARY SEEDING OF DEMOLITION OPERATIONS.



NO. 1	DATE	DESCRIPTION
2	10/20/2011	ISSUED FOR PERMITTING
3	08/20/2011	REVISED FOR PERMITTING
4	08/20/2011	REVISED FOR PERMITTING
5	08/20/2011	REVISED FOR PERMITTING
6	08/20/2011	REVISED FOR PERMITTING

TIMMONS GROUP
 10000 W. STATE ST. SUITE 100
 GREENSBORO, NC 27409
 TEL: 336-846-9551 FAX: 336-846-9552 WWW.TIMMONSGROUP.COM

THIS DRAWING PREPARED AT THE
RALPH OFFICE
 1415 W. 10TH ST. SUITE 200
 RALEIGH, NC 27603
 TEL: 919-846-9551 FAX: 919-846-9552 WWW.TIMMONSGROUP.COM

DEPARTMENT OF THE NAVY
 NAVAL FACILITIES ENGINEERING COMMAND - MIDLAND
 MARINE CORPS BASE CAMP LEJEUNE
**P-1310 CAMP LEJEUNE
 PRE-TRIAL CONFINEMENT FACILITY**
 DEMOLITION PLAN-EXISTING BRIG FACILITY

PROJECT NO. P-1310
 DRAWING NO. N40085-10-C-5335
 12509037
 DATE: 10/20/11

ISSUED FOR PERMITTING C-101