

## **REPAIR AND IMPROVE BUILDING 1039**

### **AMMENDMENT 001**

1. Contract Specification 01 50 00, "Temporary Construction Facilities and Controls": Delete section 3.6 "Government Field Office" in its entirety.
2. Add the attached Temporary Occupant Trailer Information to the project scope of work.
3. Contract Drawing PH1.1: Delete note 4 in its entirety. Replace with "Provide two each 4" conduits from Building 1039 Telecommunications (TC) Room to the temporary occupant trailer. One 4" conduit shall be utilized for temporary CAT6 telephone lines and the other for temporary CAT6 data lines. Provide additional hand holes as is required by note 6.
4. Due to a scheduled air show at MCAS Beaufort, the project will have to be shut down from Monday April 24<sup>th</sup> 2017 thru Monday May 1<sup>st</sup> 2017.