

DEPARTMENT OF THE NAVY
Southwest Regional Maintenance Center

3755 Brisner St. Suite 4
SAN DIEGO, CALIFORNIA 92136-5205



USS ALBUQUERQUE (SSN-706)

SPECIFICATIONS FOR WORK TO BE ACCOMPLISHED
SPECIFICATION NUMBER: SSP:SSSD-118-12

29 JUN 2012

DATE PREPARED

I N D E X

ITEMS THAT ARE STRUCK OUT ON THIS INDEX DO NOT APPLY TO THIS CONTRACT.

CATEGORY I. FY-13 STANDARD ITEMS APPLICABLE TO THIS JOB ORDER WITHOUT FURTHER REFERENCE

<u>ITEM NO.</u>	<u>TITLE</u>	<u>DATE</u>
009-01	General Criteria; accomplish	29-JUL-11
009-02	Environmental Compliance Reports for Material Usage at Naval Facilities; provide	29-JUL-11
009-03	Toxic and Hazardous Substances; control	29-JUL-11
009-04	Quality Management System; provide	29-JUL-11
009-05	Temporary Accesses; provide	29-JUL-11
009-06	Maintaining Protection and Cleanliness from Non-Radioactive Contaminate-Producing Operations; accomplish	15-JUN-12
009-07	Confined Space Entry, Certification, Fire Prevention and Housekeeping; accomplish	15-JUN-12
009-08	Fire Protection at Contractor's Facility; accomplish	15-JUN-12
009-10	Shipboard Asbestos-Containing Material (ACM); control	29-JUL-11
009-18	Magnetic Material; control	29-JUL-11
009-19	Provisioning Technical Documentation (PTD); provide	29-JUL-11
009-20	Government Property; control	29-JUL-11
009-21	Logistics and Technical Data; provide	29-JUL-11
009-23	Interferences; remove and install	29-JUL-11
009-24	Authorization, Control, Isolation, Blanking, and Tagging Requirements; accomplish	08-DEC-11
009-29	Asbestos-Free Pipe Hanger Liner Material; install	29-JUL-04
009-34	Fire Protection of Unmanned Vessels at Contractor's Facility; provide	15-JUN-12
009-35	Confined Space Entry, Certification, Fire Prevention Utilizing Military Fire Watches, and Housekeeping; accomplish	15-JUN-12

I N D E X

009-39	Technical Manual Contract Requirement (TMCR) for New Technical Manuals for Commercial Equipment/ Component; provide	19-JUL-07
009-40	Requirements for Contractor Cranes, Multi-Purpose Machines and Material Handling Equipment at Naval Facilities; accomplish	29-JUL-11
009-59	Organotin Antifouling Material; control	29-JUL-11
009-60	Schedule and Associated Reports for Availabilities Over 9 Weeks in Duration; provide and manage	29-JUL-11
009-61	Shipboard Use of Fluorocarbons; control	24-JUL-09
009-64	Synthetic Fire-Resistant Hydraulic Fluid; control	29-JUL-11
009-65	Polychlorinated Biphenyls (PCBs); control	29-JUL-11
009-67	Integrated Total Ship Testing; manage	29-JUL-11
009-69	Heavy Weather Plan; provide	15-JUN-12
009-70	Confined Space Entry, Certification, Fire Prevention and Housekeeping for Unmanned Vessels; accomplish	15-JUN-12
009-72	Physical Security at Private Contractor's Facility; accomplish	29-JUL-11
009-73	Shipboard Electrical/Electronic/Fiber Optic Cable; remove, relocate, repair, and install	29-JUL-11
009-74	Occupational, Safety and Health Requirements; accomplish	29-JUL-11
009-77	Cofferdam Requirements; accomplish	29-JUL-11
009-79	Government Owned Material (GOM); status reporting	29-JUL-11
009-80	Ship's Facilities; provide	29-JUL-11
009-81	Compartment Closeout; accomplish	29-JUL-11
009-82	Data Requirements When Installing an Equal Component Vice Specified Component; provide	29-JUL-11
009-83	Wire Rope Fitting Verification; provide	29-JUL-11

I N D E X

009-84	Accountability of Temporary Fasteners; provide	29-JUL-11
009-86	Recovery of Chlorofluorocarbon (CFC) Refrigerants and Fire Suppressant Halon (H) Materials; accomplish	01-AUG-08
009-87	Chemical Disinfection Procedures; accomplish	29-JUL-11
009-88	Collection, Holding and Transfer (CHT) and Mogas Tanks, Spaces, and Piping, including Sewage or Mogas-Contaminated Tanks, Spaces, and Piping; certify	29-JUL-11
009-89	Purchase and Inspection Requirements for Contractor Furnished Anodes; accomplish	29-JUL-11
009-93	Emergency Planning and Community Right-to-Know Act (EPCRA) and Pollution Prevention Act (PPA) Information; provide	29-JUL-11
009-94	General Environmental Requirements for Work at Contractor's Facility; accomplish	29-JUL-11
009-95	Mechanically Attached Fittings (MAF's) for Piping Systems; install	29-JUL-11
009-97	Shipbuilding and Ship Repair Operations National Emission Standard for Hazardous Air Pollutants (NESHAPS) for Surface Coating Information; provide	29-JUL-11
009-99	Ship Departure Report; provide	30-JUL-10
009-100	Ship's Stability Process Control Procedure (PCP); maintain	30-JUL-10
009-101	Requirements for Mooring, Entry to and Departure from Contractor's Facility; accomplish	29-JUL-11
009-102	Alteration Verification; provide	29-JUL-11
009-103	Weight and Moment Change Data; provide	29-JUL-11
009-106	Work Authorization Form Coordinator (WAFCOR); provide	30-JUL-10
009-108	Aircraft Carrier Requirements for Mooring, Entry to, Movement within, and Departure from Contractor's Facility; accomplish	29-JUL-11
009-109	Special Requirements for Non-SUBSAFE Work on SUBSAFE-Certified Vessels; accomplish	29-JUL-11
009-110	Special Requirements for Non-Nuclear Work on Nuclear Vessels; accomplish	29-JUL-11

I N D E X

009-111 Schedule and Associated Reports for Availabilities 9 Weeks 29-JUL-11
 or Less in Duration; provide and manage

~~009-112 Prevention of Radiographic-Inspection Ionizing-Radiation 29-JUL-11~~
 Hazards; accomplish

I N D E X

CATEGORY II. FY-13 STANDARD ITEMS WHICH MAY BE INVOKED IN THE WORK ITEMS OF THIS JOB ORDER

<u>ITEM NO.</u>	<u>TITLE</u>	<u>DATE</u>
009-09	Process Control Procedure (PCP); provide and accomplish	29-JUL-11
009-11	Insulation and Lagging Requirements; accomplish	29-JUL-11
009-12	Welding, Fabrication, and Inspection Requirements; accomplish	29-JUL-11
009-13	Meters; repair and certify calibration	29-JUL-11
009-14	Gages and Thermometers; repair and certify calibration	29-JUL-11
009-15	Rotating Machinery; balance	29-JUL-11
009-16	Electronic Equipment; repair	29-JUL-11
009-17	Rotating Electrical Equipment; repair	29-JUL-11
009-22	Shipboard Electric Cable; test	29-JUL-11
009-25	Structural Boundary Test; accomplish	29-JUL-11
009-26	Deck Covering Requirements; accomplish	29-JUL-11
009-27	Material Identification and Control (MIC) for Level I Systems; accomplish	29-JUL-11
009-28	Cancelled 30 JUL 2010	
009-30	Boiler Sample Tubes; inspect	29-JUL-11
009-31	Boiler Waterjet Cleaning; accomplish	29-JUL-11
009-32	Cleaning and Painting Requirements; accomplish	31-JAN-11
009-33	Rotating Electrical Equipment; rewind	29-JUL-11
009-36	Controller; repair	29-JUL-11
009-37	General Procedures for Woodwork; accomplish	30-JUL-10

I N D E X

009-38	Boiler Dry Lay-up; accomplish	29-JUL-11
009-41	Technical Manual Contract Requirement (TMCR) for a Topically Structured Technical Manual; provide	19-JUL-07
009-42	Technical Manual Contract Requirement (TMCR) for Updating Technical Manuals; provide	19-JUL-07
009-43	Light-Off Assessment (LOA) Support for Steam Propulsion System; provide	29-JUL-11
009-44	Light-Off Assessment (LOA) Support for Gas Turbine Propulsion System; provide	29-JUL-11
009-45	Tapered Plug Valve; repair	29-JUL-11
009-46	Butterfly Valve, Synthetic and Metal Seated; repair	29-JUL-11
009-47	Gate Valve; repair	29-JUL-11
009-48	Pressure Seal Bonnet Valve; repair (shop)	29-JUL-11
009-49	Pressure Seal Bonnet Valve; repair (in-line)	29-JUL-11
009-50	Horizontal Swing Check Valve; repair	29-JUL-11
009-51	Globe, Globe Angle, and Globe Stop Check Valve; repair	29-JUL-11
009-52	Relief Valve; repair	29-JUL-11
009-53	Bolted Bonnet Steam Valve; repair (shop)	29-JUL-11
009-54	Bolted Bonnet Steam Valve; repair (in-line)	30-JUL-10
009-55	Regulating/Reducing Valve; repair	30-JUL-10
009-56	Main Propulsion Boiler Wet Lay-Up; accomplish	29-JUL-11
009-57	Reduction Gear Security Requirements; accomplish	08-DEC-11
009-58	Pump and Driver Shaft Alignment; accomplish	29-JUL-11
009-62	Boiler Handhole and Manhole Seats and Plates; inspect	29-JUL-11
009-63	Lubricating Oils and Hydraulic Fluids; analyze	29-JUL-11

I N D E X

009-66	Light-Off Assessment (LOA) Support for Diesel Propulsion System; provide	29-JUL-11
009-68	Bolted Bonnet Valve; repair	29-JUL-11
009-71	Testing Requirements for Piping Systems; accomplish	30-JUL-10
009-75	Circuit Breaker; repair	29-JUL-11
009-76	Waveguide and Transmission Line Temporary Lay-Up, Pressurization, and Purging; accomplish	29-JUL-11
009-78	Passive Countermeasures System (PCMS) Material Repair/Installation Requirements; accomplish	30-JUL-10
009-85	Government Sponsored Planning Yard/Configuration Data Manager (CDM) On-Site Representative Facility; provide	19-JUL-07
009-90	Technical Representative; provide	29-JUL-11
009-91	Propeller In-Place Inspection; accomplish	29-JUL-11
009-92	Resilient Mount; remove and install	29-JUL-11
009-96	Ball Valve; repair	29-JUL-11
009-98	Monel Fasteners; inspect	30-JUL-10
009-104	Vibration Testing and Analysis; accomplish	29-JUL-11
009-105	Thermal Sprayed Coatings for Machinery Component Repair; accomplish	14-JUL-05
009-107	Piping System Cleanliness (Non-Nuclear); accomplish	29-JUL-11
009-113	Rotating Electrical Equipment with Sealed Insulation Systems (SIS); rewind	29-JUL-11
009-114	Mold Remediation; accomplish	30-JUL-10
009-115	Bearing Rebabbiting; accomplish	29-JUL-11
009-116	Auxiliary and Waste Heat Boiler Sodium Nitrate Wet Layup; accomplish	29-JUL-11
009-117	AEGIS Light Off (ALO) Support for AEGIS Weapons Systems Assessments (AWSA); provide	29-JUL-11

SHIP: USS ALBUQUERQUE (SSN-706)

SSP-118-12

I N D E X

ITEM NO.

TITLE

593-11-001 Tank; pump and clean

ITEM NO: 593-11-001

PCN: EAMC-Q036

CMP : NONE

PLANNER: LOEPFE

1. SCOPE :

1.1 Title: Tank; pump and clean

1.2 Location of Work:

1.2.1 PLO Sump Tank

1.3 Identification:

1.3.1 Quantity; (One) Each, Propulsion Lube Oil Sump Tank
(Approximately 1600 gals)

2. REFERENCES :

2.1 NAVSEA Standard Items

3. REQUIREMENTS :

3.1 The contractor shall provide all cleaning equipment, holding tank(s), machinery and material, lights and ventilation to accomplish work required in this work item.

3.2 Contractor shall prohibit the wearing of any "yellow" colored clothing or coveralls and utilizing "yellow" colored containers, or equipment.

3.2.1 Ensure equipment internal components are not damaged during the cleaning evolution.

3.3 Clean, vent, gas free and certify each equipment listed in 1.2.1 "Safe For Workers".

3.3.1 Submit 2 legible copies of the certified marine chemist certificate to the SUPERVISOR.

(V) (G) "CLEANLINESS"

3.4 Notify the SUPERVISOR for surface cleanliness inspection of tank interior surfaces. Advanced notice of one working day is required for inspection notification.

SHIP: USS ALBUQUERQUE (SSN-706)

3.4.1 Cleanliness is defined as no visible or detectable by hand touch oil, grease, debris or surface contaminants.

3.4.2 Submit one legible copy, in hard copy or electronic media, of a report listing results of the requirements of 3.4 to the SUPERVISOR.

4. NOTES:

4.1 Point of contact is the 3-MC.

5. GOVERNMENT FURNISHED MATERIAL (GFM):

5.1 LLTM:

1. None.

5.2 PUSH MATERIAL:

1. None.

5.3 KITTED MATERIAL:

1. None.