

SPECIFICATIONS
Naval Base San Diego
3210 McCandless Blvd, Bldg. 3202
San Diego, CA 92136

1. **GENERAL:** This requirement is to modify height of existing room dividers and install etched glass on top, provide and install Corian tray slides over existing stainless steel tray slides on all serving lines, replace existing sneeze guards, replace existing plastic fruit bar with dual temp drop in well, replace existing laminate at the VIP serving line with vertical grade to match existing custom cabinets and provide new room dividers at Naval Base San Diego dining facility.
2. **INSTALLATION REQUIREMENTS:** This requirement is to provide an install vertical grade laminate surfaces; provide an install Corian countertops on all serving lines with tray slides; provide and install new sneeze guards on hot lines; modify existing room dividers; provide and install etched sneeze guard on room dividers; provide new room dividers; provide and install new dual temp drop in well. Listed below are sections and requirements for each section.

I: VIP SECTION

1. Corian Solid Surface Tray Slide on Existing Hot Line and Beverage Counter
2. Re-Laminate Existing Hot Line
3. Modify height of Entry Room Divider and Install Etched Glass
4. Install Etched glass on Room Divider behind Beverage line

II: SPEED LINE SECTION

1. Demo existing room divider in front of serving line, fabricate and install mobile room divider with etched glass
2. Provide solid surface top at existing serving line tray slide
3. Provide 2 each dual temp 4 hole refrigerator/hotwell
4. Provide new sneeze guards (Match NASNI Style at Bistro)
5. Modify height of existing room divider at main entry to speed line

III: MAIN LINE SECTION

1. Modify height of existing room divider in front of main serving line and install etched glass
2. Provide solid surface top at existing serving line tray slide
3. Provide 2 each dual temp 4 hole refrigerator/hotwell
4. Provide new sneeze guards (Match NASNI Style at Bistro)
5. Modify height of existing room divider at main entry to main line and Install Etched Glass

IV: CPO SECTION

1. Modify height of existing room divider CPO Section entry and Install Etched Glass
2. Provide new sneeze guards (Match NASNI Style at Bistro)
3. Provide mobile counter with solid surface top to accommodate tray and plate lowerator
4. Provide solid surface top at existing serving line tray slide

3. **SCOPE OF WORK:** The contractor shall provide all management, tools, materials, supplies, equipment, fabrication and labor necessary to ensure proper installation of all items listed below:

All Solid Surface Corian Material to be SAND CASTLE by LIVINGSTONE

All Laminate to be Vertical grade Wilsonart #7923 VERSAILLES

I: VIP SECTION:

1. Solid Surface Tray Slide on Existing Hot Line and Beverage Counter

- The contractor shall provide and install Corian countertops on serving line and beverage line tray slides in the VIP section. Corian tops to be Sand Castle by Livingstone, 13 inches wide with 3 stainless steel rub strips. Rub strips to be 304 stainless steel, 1/2" wide by 1/4" high. Front edge to be turned down 2"
- Length of Serving Line is 41 FEET
- Length of Beverage Counter is 26'-5"

2. Re-Laminate Existing Hot Line and Beverage Counter

- Remove existing laminate surfaces from the VIP serving line and beverage line and install vertical grade laminate.
- Laminate to be Wilsonart #7923 VERSAILLES.
- Length of Serving Line is 41 FEET
- Length of Beverage Counter is 26'-5"

3. Modify height of Entry Room Divider and Install Etched Glass

- Modify height of existing room divider to 42" (does not include the divider behind the existing beverage counter). Remove glass and laminate.
- Laminate the modified room divider on all exposed sides with Wilsonart #7923 VERSAILLES
- Cap the modified room divider with Solid Surface Material matching the Corian counter tops
- Provide etched glass with logos of ships. Glass to be 1/2" tempered with 24 inch high vertical posts supporting each end of each glass. Glass sections to be 42" long. Vertical support post to be 24" High and 1-1/2" diameter. Stainless Steel Brushed Finish
- Length of Room Divider is 25 FEET

4. Install Etched glass on Room Divider behind Beverage line

- Cap the modified room divider with Solid Surface Material matching the Corian counter tops
- Provide etched glass with logos of ships. Glass to be 1/2" tempered with 24 inch high vertical posts supporting each end of each glass. Glass sections to be 42" long. Vertical support post to be 24" High and 1-1/2" diameter. Stainless Steel Brushed Finish
- Remove glass section and install vertical grade laminate
- Length of Room Divider is 26'-6"

5. Provide new sneeze guard to match NASNI style Bistro

- Replace existing sneeze guards with new sneeze guards. The new sneeze guards to be 1 1/2" diameter stainless steel tubing with front breath guard and glass shelf top. Glass to be 3/8" tempered glass. Length of sneeze guards at VIP serving line 35 feet total, two sections.

II: SPEED LINE SECTION

1. Demo existing room divider in front of serving line leading to training room in speed line section and fabricate and install mobile room divider with etched glass

- Cap the modified room divider with Corian Solid Surface Material SAND CASTLE by LIVINGSTONE
 - Provide etched glass with logos of ships. Glass to be 1/2" tempered with 24 inch high vertical posts supporting each end of each glass. Glass sections to be 42" long. Vertical support post to be 24" High and 1-1/2" diameter. Stainless Steel Brushed Finish
 - Length of Room Divider is 24'-6"
 - New room divider to be 42" high
 - Laminate room divider on all exposed sides with Wilsonart #7923 VERSAILLES
2. Provide solid surface top at existing tray slide in Speed line
- The contractor shall provide and install Corian countertops on Speed Line tray slide. Corian tops to be Wilsonart #7923 VERSAILLES, 13 inches wide with 3 stainless steel rub strips. Rub strips to be 304 stainless steel, 1/2" wide by 1/4" high. Front edge to be turned down 2"
 - Length of Serving Line is 41 FEET
3. Provide 2 each dual temp 4 hole refrigerator/hotwell
- Provide and install new dual temp drop in well. Vollrath # 3667402D
4. Provide new sneeze guards (Match NASNI Style at Bistro)
- Replace existing sneeze guards with new sneeze guards. The new sneeze guards to be 1-1/2" diameter stainless steel tubing with front breath guard and glass shelf on top. Glass to be 3/8" tempered glass. Total length of sneeze guard 35 feet, two sections.
5. Modify height of existing room divider at main entry to Speed Line section
- Modify height of existing room divider to 42". Laminate the modified room divider on all exposed sides with Wilsonart #7923 VERSAILLES
 - Cap the modified room divider with Solid Surface Material matching the Corian counter tops
 - Provide etched glass with logos of ships. Glass to be 1/2" tempered with 24 inch high vertical posts supporting each end of each glass. Glass sections to be 42" long. Vertical support post to be 24" High and 1-1/2" diameter. Stainless Steel Brushed Finish
 - Length of Room Divider is 70 feet

III: MAIN LINE SECTION

1. Modify height of existing room divider in front of main serving line leading to scullery room and install etched glass
- Modify height of existing room divider to 42" high. Laminate the modified room divider on all exposed sides with Wilsonart #7923 VERSAILLES
 - Cap the modified room divider with Solid Surface Material SAND CASTLE by LIVINGSTONE
 - Provide etched glass with logos of ships. Glass to be 1/2" tempered with 24 inch high vertical posts supporting each end of each glass. Glass sections to be 42" long. Vertical support post to be 24" High and 1-1/2" diameter. Stainless Steel Brushed Finish
 - Length of Room Divider is 25'-6"
2. Provide solid surface top at existing serving line tray slide in Main Line section

- The contractor shall provide and install Corian countertops on serving line tray slide. Corian tops to be SAND CASTLE by LIVINGSTONE, 13 inches wide with 3 stainless steel rub strips. Rub strips to be 304 stainless steel, 1/2" wide by 1/4" high. Front edge to be turned down 2"
 - Length of Serving Line is 41 FEET
3. Provide 2 each dual temp 4 hole refrigerator/hotwell
 - Provide and install new dual temp drop in well. Vollrath # 3667402D
 4. Provide new sneeze guards (Match NASNI Style at Bistro)
 - Replace existing sneeze guards with new sneeze guards. The new sneeze guards to be 1-1/2" diameter stainless steel tubing with front breath guard and glass shelf on top. Glass to be 3/8" tempered glass. Total length of sneeze guard at main line is approximately 35 feet, two sections.
 5. Modify height of existing room divider at main entry to Main Line section
 - Modify height of existing room divider to 42". Laminate the modified room divider on all exposed sides with Wilsonart #7923 VERSAILLES
 - Cap the modified room divider with Solid Surface Material matching the Corian counter tops
 - Provide etched glass with logos of ships. Glass to be 1/2" tempered with 24 inch high vertical posts supporting each end of each glass. Glass sections to be 42" long. Vertical support post to be 24" High and 1-1/2" diameter. Stainless Steel Brushed Finish
 - Length of Room Divider is 70 feet

IV: CPO SECTION

1. Modify height of existing room divider CPO section entry and Install Etched Glass
 - Modify height of existing room divider to 42". Laminate the modified room divider on all exposed sides with Wilsonart #7923 VERSAILLES
 - Cap the modified room divider with Solid Surface Material matching the Corian counter tops
 - Provide etched glass with logos of ships. Glass to be 1/2" tempered with 24 inch high vertical posts supporting each end of each glass. Glass sections to be 42" long. Vertical support post to be 24" High and 1-1/2" diameter. Stainless Steel Brushed Finish
 - Length of Room Divider is 65 FEET
2. Provide new sneeze guards (Match NASNI Style at Bistro)
 - Replace existing sneeze guards with new sneeze guards. The new sneeze guards to be 1-1/2" diameter stainless steel tubing with front breath guard and glass shelf on top. Glass to be 3/8" tempered glass. Total length of sneeze guard at CPO is 20 feet, two sections.
3. Provide mobile counter with solid surface top to accommodate tray and plate lowerator
 - Provide and set in place 1 mobile counter. Mobile counter to be of 304 stainless steel construction with laminated exterior. Dimensions to be 36" x 36" x 34" high" and able to accommodate 2 each drop in style plate dispensers and 1 each drop-in style tray dispenser. Plate dispenser to be Lakeside #922; Tray dispenser to be Lakeside #976
 - Finish material on top of counter to be SAND CASTLE by LIVINGSTONE
 - Laminated base to be Wilsonart #7923 VERSAILLES
 - Casters to be 5"

4. Provide solid surface top at existing CPO serving line tray slide.

- The contractor shall provide and install Corian countertops on CPO serving line tray slide. Corian tops to be SAND CASTLE by LIVINGSTONE, 13 inches wide with 3 stainless steel rub strips. Rub strips to be 304 stainless steel, 1/2" wide by 1/4" high. Front edge to be turned down 2"
- Length of Serving Line is 25'-10"

4. CONTRACTOR RESPONSIBILITIES:

- Contractor is responsible for verifying all dimensions prior to bidding and fabrication.
- The contractor will provide certified technicians on site at Naval Base San Diego galley, Building 3202.
- Contractor will be permitted to work inside of the Dining Facility during the following hours: Monday through Friday - 0730-1700 except during meal hours and holidays. Night shift may be coordinated with Food Service Officer with no additional cost in pricing. Night shift is preferred if project involves loud noise and heavy dust to not interfere with patrons during meal hours and must be coordinated with the FSO. Exact days of work will be coordinated before commencement to ensure space availability. Coordinate with LCPO /FSO before commencing work to ensure serving line or each section is secured for work while utilizing different serving lines to serve the patrons. Immediate work area will be properly secured by the contractor and will not conflict with meals being served or dining area being utilized.
- Contractor responsible for removal of existing equipment and reinstallation of all existing equipment, if needed.
- Contractor will provide plastic dust barriers to contain dust.
- DISPOSAL: Contractor is responsible for daily clean up and disposal of all generated debris/materials to proper recycling or disposal containers at the back dock.

5. **Government responsibilities:** The Government shall coordinate the disconnection and reconnection of electrical power, if necessary. The contractor will notify the government representative no less than 2 working days in advance to schedule and coordinate electrical power requirements

6. **SITE VISIT: Site visit is recommended.** The purpose of this site visit is to clarify technical specifications, final measurements, color selections, questions and concerns. Color selections, patterns and designs to be finalized with FSO before fabrication. Each representative will be required to bring 2 valid forms of photo identification, such as driver's license or passport. Individuals without photo identification will not be permitted to enter the installation.

7. **DELIVERY/INSTALLATION:** Project to be completed within 60 day after contract award date.

8. **Points of contact:**

9. **Place of Performance:** Naval Base San Diego, 3210 McCandless Blvd, Bldg. 3202, San Diego, CA 92136