0100000 – General Information		
Spec Item	**Title**	**Description**
1	General Information	
1.1	Outline of Services	Except where otherwise stated, the Contractor shall furnish all labor, supervision, management, tools, materials, equipment, facilities, transportation, incidental engineering, and other items necessary to provide the services outlined below and described in this Performance Work Statement (PWS) at the Naval Medical Center, Portsmouth, Virginia, and it's outlying clinics. This is a combination firm-fixed price (FFP) and indefinite delivery-indefinite quantity (IDIQ) type contract.. The PWS is organized into annexes. Annex 1 is "General Information". Annex 2 contains the on-site project management and administration requirements. Annexes 15 contain the technical requirements. Annex 1 General Information Annex 2 Management and Administration Annex 3 Command and Staff N/A Annex 4 Public Safety N/A Annex 5 Air Operations N/A Annex 6 Port Operations N/A Annex 7 Ordnance N/A Annex 8 Range Operations N/A Annex 9 Health Care Support N/A Annex 10 Supply N/A Annex 11 Personnel Support N/A Annex 12 Morale, Welfare and Recreation Support N/A Annex 13 Galley N/A Annex 14 Housing N/A Annex 15 Facilities Support, 1502000 C Facility Investment Annex 16 Utilities N/A Annex 17 Base Support Vehicles and Equipment N/A Annex 18 Environmental N/A
1.2	Project Location	The work shall be performed at the Naval Medical Center, Portsmouth and it's outlying medical and dental clinics located at Norfolk Naval Station, Naval Security Group Activity Northwest, Yorktown Naval Weapons Station, Little Creek Amphibious Base, Naval Air Station Oceana, Fleet Combat Training Center Dam Neck, and the Norfolk Naval Shipyard and in locations within a 50 mile radius of the above locations.
1.3	Acquisition of Additional Work	The Government reserves the right to acquire additional DDC control services at additional locations in addition to the services and locations identified in the Firm-Fixed Price requirements of this contract. Additional services will be incorporated into the contract in accordance with the CHANGES clause, SECTION I or ordered under the indefinite delivery indefinite quantity provisions of the contract. Items of work not covered by this contract but within the general intent are considered in the scope of this contract.
1.4	Background Information	The Region is located on Virginia's Atlantic Shore near where the first Jamestown settlers landed, where the infamous Blackbeard and other pirates were said to have buried treasures in the dunes of the nearby beach resort, where battles of the Revolutionary War were fought, where the Monitor and Merrimac fired on one another, where the blue and gray clashed during the Civil War, and where German Submarines sank American shipping vessels within yards of nearby beaches in World War II. This area is surrounded with colorful old English names such as

DRAFT

0100000 – General Information		
Spec Item	**Title**	**Description**
		London Bridge, Great Bridge, Princess Anne, Isle of Wight, and Williamsburg, and tribal names such as Pungo, Buckroe and Zuni.
1.5	Verification of Workload and Conditions	Throughout the PWS, the workload data is generally referred to as being located in Section J. Section J provides data such as inventories, maps, floor plans, and tables to represent the type, quantity and location of services to be provided. However, offerors are encouraged to visit the project site during the site visit for offerors as part of its due diligence to assess the nature of work and conditions under which work is to be performed.
1.6	Climate Patterns	Virginia's climate results from global-scale weather patterns that are modified by the diverse landscape of the Commonwealth. In the Hampton Roads Area the Atlantic Ocean and its "river of warm water", commonly called the Gulf Stream, play a dominate role in differentiating Virginia's precipitation and climate. Winter storms in the vicinity of the east coast generally move northeastward paralleling the coast and the Gulf Stream. The climate is generally mild and wet but for the last five years there has been a moderate to severe drought. The summers have been quite dry with some recovery during the fall and winter months.
1.7	Related Information	There are four types of Related Information that can be found in the Description and Related Information columns of the specification as follows: Informational Notes as used throughout this PWS provides additional information to offerors to be used in developing a thorough understanding of the work to be performed in this contract. Any block of text marked “Informational Notes” throughout Annexes 1 through 18 is subject to this disclaimer. Offerors may not rely upon the "Informational Notes" as material representations of the Government. Information provided in "Informational Notes" does not create a contractual requirement on either party to this contract. Clarifying Information describes client expectations in a more detailed manner than the Performance Objective and Performance standard alone. Constraining Information describes limitations to the work performed to meet the Performance Objective and Performance Standard. Requirement Information further describes client requirements associated with each Performance Objective.
1.8	Navy Approach to Service Contracting	The Department of Navy (DoN) spends over $1 billion in annual obligations to meet global requirements for facility operations and maintenance provided through Facility Support Contracts (FSC) and additional billions to provide other base operations support services (OBOS). The Head of the Contracting Activity (HCA) of the Naval Facilities Engineering Command (NAVFAC) has focused increased attention on re-engineering FSC contracts in response to customer and industry feedback, budget constraints, and the impact of a variety of contracting, program management and financial management regulations. The Navy also supports the following principles:

DRAFT

0100000 – General Information		
Spec Item	**Title**	**Description**
1.8.1	Partnering Philosophy	The first principle is that the Navy views its contractors as partners and not just abstract service providers. The Navy wants its contractors to succeed because partners' success drives the Navy's successful mission completion. Within the bounds of acquisition policy the Navy intends to work to find solutions that will be beneficial to both the Government and its partners.
1.8.2	Contractor's Knowledge	The second principle is that the Navy will receive insightful management from its contractors. This management will include the knowledge, skills, authority and willingness to use contractor resources to find better ways of serving Navy clients' strategic and operational goals and objectives. The Navy's use of performance-based objectives evidences this principle. Although performance work statements will typically contain several levels of performance assessment, the Navy wants its contractors to exercise maximum discretion within bounds of prudent risk management to adjust processes and resources needed to reach specified objectives at the highest performance level.
1.8.3	Industry Best Practices	The third principle is that the Navy will adopt industry best commercial practices and maintain state-of-the-art service delivery. It is the Navy's and contractor's responsibility as partners to reach this goal. To that end, the Navy's emphasis will be in evaluating performance objectives (end results).
1.9	Standard Template	Key to implementing a programmatic approach is using a standard template that ensures Navy-wide consistency yet affords appropriate tailoring to meet local needs. This contract conforms to the standard template and has been tailored for this solicitation. NAVFAC intends to use this template-based approach for future service contracts. Offerors should develop an understanding of the template as part of performing due diligence in reaching an understanding of the Navy's requirements and expectations. The standard template contains 18 standard annexes. Annex 1 will always contain information that is relevant to the entire scope of the contract. Annex 2 contains on-site project management and administration requirements that are relevant to the entire scope of the contract. Annexes 3 through 18 contain the technical information and requirements peculiar to that technical annex. Within each technical annex, the organization of information and requirements are also standardized. Specification item 1 will always contain General Information. Specification item 2 will always contain the management and administrative requirements. Specification item 3 will always contain the Firm Fixed-Price (FFP) requirements. Specification item 4 will always contain the Indefinite Delivery-Indefinite Quantity (IDIQ) requirements. Requirements and standards for higher level specification items apply to all subordinate specification items, e.g., Specification Item 3 standards apply to all firm fixed priced specification items. Specification Item 3.1 is applicable to all 3.1 subordinate specification items. Specification Items 3.2 and 3.3 are not considered subordinate to 3.1. All costs associated with Annexes 1 and 2 and Specification items 1 and 2 must be priced and distributed within Specification Item 3 of Annexes 3 through 18.
1.10	Navy PBSA Approach	The Navy's approach to performance-based service acquisition (PBSA) includes four component parts which are 1) performance outcomes, 2) measurable standards, 3) consideration of incentives, and 4) performance assessment plan.

DRAFT

0100000 – General Information		
Spec Item	**Title**	**Description**
1.11	Technical Proposal Certification	The Contractor warrants that its proposal incorporated herein by reference will meet or exceed the performance objectives set forth in this contract.

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
2	Management and Administration	
2.1	Definitions and Acronyms	Definitions and Acronyms are listed in J-0200000-01.
2.2	General Information	
2.2.1	Government Regular Working Hours	The Government's regular working hours are from 0700-1600, five days per week, Monday through Friday, except observed Federal holidays. Exceptions to the regular hours of operation are detailed in subsequent sections of this PWS. Work in certain annexes or sub-annexes require Contractor continuous operations, 24 hours a day, every day of the year including holidays. The performance of other work requirements shall be accomplished within the Government's regular working hours unless the specific work requirement specified herein necessitates otherwise. Any other work outside Government regular working hours requires prior KO approval.
2.2.1.1	Observed Federal Holidays	The Government observes the following holidays: New Year's Day, Martin Luther King Jr.'s Birthday, President's Day, Memorial Day, Independence Day, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day, and Christmas Day.
2.2.1.2	Restriction to Contractor Working Hours	If the Contractor wishes to work outside of the Government's regular working hours for the Contractor's convenience, the Contractor shall submit a written Request to Work Outside Government's Regular Working Hours to the KO for approval at least seven calendar days prior to requested day. Excludes work to be performed during specified hours.
2.2.2	Wage Determinations	Wage determinations are included in J-0200000-02.
2.2.3	Requirements Hierarchy	Requirements or definitions specified in each spec item of this contract apply to subordinate paragraphs. For example, requirements shown in spec item 3.1 would apply to spec items 3.1.1, 3.1.2, 3.1.2.1 and so on.
2.3	General Administrative Requirements	
2.3.1	Required Conferences and Meetings	The Contractor may be required to attend administrative and coordination meetings. The Contractor shall attend meetings as shown below.
2.3.2	Partnering	To increase the likelihood of successful performance of this contract, the Government requires cohesive partnerships with its Contractors and subcontractors. Key stakeholders, including the clients who will receive services, principal individuals from NAVFAC, the performance assessment team, and representative(s) of the installation(s) will be invited to participate in the partnering process. Key members of the prime and subcontractors teams, including senior management personnel must participate. The partnership will draw on the strength of each organization in an effort to achieve quality contract services done right the first time, within the contract price, as scheduled, and without any safety mishaps. A project's characteristics determine the process level to be used. As such the following partnering level applies to this contract:
2.3.2.1	Contract Partnering Level C	This level of partnering discusses partnering concepts and benefits and should become a part of the pre-performance conference. The senior Government and Contractor stakeholders present will jointly host the partnering sessions. The

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		partners will determine the frequency of the follow-on sessions. The partnering sessions should be held at locations agreed to by the partners.
2.3.2.2	Contract Partnering Administration	Upon award, the ACO will contact the Contractor, client(s), Region, and Installation(s) stakeholders, and the performance assessment team to discuss implementation of partnering. The initial session must be scheduled as soon as possible after award of the contract. A partnership agreement, The Charter, should be in place as early as possible so issues arising, even before work begins, can be resolved using the issues resolution process. Replacement of Core Management Team members (stakeholders who attended the initial session and manage the contract work day-to-day) is discouraged since it will disrupt the synergy that has been developed. If replacement of a team member proves to be unavoidable, a follow-on partnering session must be held to officially turn the responsibilities of the position over to the new member. The Core Management Team consisting of the attendees below must be present during the initial and all follow-on partnering sessions. These are the core mandatory attendees. Other stakeholders may attend if they desire or as recommended by the partners. For more information concerning Partnering read NAVFACINST 11013.40A, which can be viewed in the Government's Contracts Office.
2.3.2.3	Contract Partnering Session Attendees	The Contractor shall bring the necessary personnel to successfully partner on this contract. Asterisk indicates mandatory personnel. President/Vice President *Contract/Project Manager *Supervisor/Superintendent *Quality Control Manager Safety Manager
2.3.3	Permits and Licenses	The Contractor shall obtain all required permits, licenses, and authorizations to perform work under this contract and comply with all the applicable Federal, state and local laws and regulations. Provide evidence of such Permits and Licenses to the KO before work commences and at other times as requested by the KO.
2.3.4	Insurance	Within 15 calendar days after award of this contract, the Contractor shall furnish the KO a Certificate of Insurance as evidence of the existence of the following insurance coverage in amounts not less than the amounts specified below in accordance with the FAR Clause 52.228-05, INSURANCE – WORK ON A GOVERNMENT INSTALLATION. This insurance must be maintained during the performance period.
2.3.4.1	Certificate of Insurance	The Certificate of Insurance shall provide for at least 30 calendar days written notice to the KO by the insurance company prior to cancellation or material change in policy coverage. Other requirements and information are contained in the aforementioned insurance clause.
2.3.4.2	Minimum Insurance Amounts	The Contractor shall procure and maintain, during the entire period of performance under this contract, the following minimum insurance coverage: Comprehensive General Liability: $500,000 per occurrence Automobile Liability: $200,000 per person, $500,000 per occurrence, $20,000 per occurrence for property damage Workmen's Compensation: As required by Federal and State worker's compensation and occupational disease statutes

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		Employer's Liability coverage: $100,000, except in states where worker's compensation may not be written by private carriers.
2.3.5	Protection of Government Property	During execution of the work, the Contractor shall protect Government property. The Contractor shall return areas damaged as a result of negligence under this contract to their original condition at no cost to the Government.
2.3.6	Instructions, Directives, and References	Applicable Department of Defense (DoD), Secretary of the Navy (SECNAV), Chief of Naval Operations (OPNAV), and other directives, instructions, and references are listed in J-0200000-03.
2.4	Government-Furnished Property, Materials and Services	In accordance with FAR 52.245, GOVERNMENT PROPERTY and NAVFAC Clause 5252.245-9300, GOVERNMENT-FURNISHED PROPERTY, MATERIALS AND SERVICES, and the following paragraphs, the Government will furnish or make available to the Contractor certain Government-owned facilities, utilities, materials, and equipment for use in connection with this contract. Refer to J-0200000-04.
2.4.1	Government-Furnished Facilities (GFF)	The Government shall furnish at a minimum 100 SF for material storage and contractors terminal placement.
2.4.2	Government-Furnished Utilities	The Government will furnish water and electric current at existing outlets as may be required for the work to be performed under this contract at no cost to the Contractor. Information concerning the location of existing outlets may be obtained from the Contracting Officer Representative. The Contractor shall provide and maintain, at no cost to the Government, the necessary service lines from existing Government outlets to the site of work.
2.4.2.1	Availability of Utilities	The Government will furnish water and electricity at existing outlets required for the work to be performed under the contract at no cost to the Contractor. Information concerning the location of existing outlets may be secured from the KO. The Contractor shall provide and maintain, at its expense, the necessary service lines from the existing Government outlets to the work site. Provide and maintain backflow prevention devices on connections to domestic water lines and electrical transformer provisions on connections to electric lines. Meet all Federal, State, local, and activity codes and regulations for backflow prevention devices and electrical transformer provisions. Services required by the Contractor, for which there are no available Government outlets, shall be provided by the Contractor at no cost to the Government.
2.4.3	Government-Furnished Materials (GFM)	The Government will provide protective clothing, (operating room type scrub suits) to be worn during inspections, testing, maintenance, and repairs done under this contract. This clothing is only to be worn when performing work in the operating rooms, when required.
2.4.4	Government-Furnished Equipment (GFE)	The contractor will have access to Government DDC system computers for system troubleshooting, updating, etc.
2.5	Contractor-Furnished Items	Except for items identified as Government Furnished, the Contractor shall provide all equipment, materials, parts, supplies, components, and facilities to perform the requirements of this contract. The KO may inspect Contractor-furnished items for adequacy and compliance with contract requirements. Inadequate or unsafe items shall be removed and replaced by the Contractor at no cost to the Government. Materials containing asbestos, lead, and PCB's shall not be brought on site. The KO may at any time require Samples, Material Safety Data Sheets (MSDS) or Manufacturer's Data Cut Sheets of Materials used in this contract. The Contractor shall provide all manufacturers' (Metasys) software, equipment, materials, and services to perform the requirements of this

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		contract. All materials shall be provided at the General Services Administration prices as listed in the latest GSA catalog.
2.6	Management	The Contractor shall manage the total work effort associated with the services required herein to meet the performance objectives and standards. Such management includes but is not limited to planning, scheduling, cost accounting, report preparation, establishing and maintaining records, and quality control. The Contractor shall provide a staff with the necessary management expertise to assure performance objectives and standards are met.
2.6.1	Work Reception	The Contractor shall establish a work reception function with the capability to receive, classify, issue, correspond, and respond to trouble calls and task orders. The Contractor shall maintain a work reception desk continuously from 7:00 AM to 3:30 PM Monday through Friday to receive any contract related calls (i.e., service calls (emergency and routine), Task Orders, questions, and complaints) from the Contracting Officer or a designated representative. The person attending the work reception desk shall be fully familiar with the Contractor's organization and customer service procedures used by general industry as well as the terms of the contract. The work reception desk shall be capable of being in constant communication with the Contractor's superintendent.
2.6.2	Work Control	The Contractor shall implement all necessary work control procedures to ensure timely accomplishment of work requirements, as well as to permit tracking and reporting of work in progress. The Contractor shall plan and schedule work to assure material, labor, and equipment are available to complete work requirements within the specified time limits and in conformance with the quality standards established herein. Verbal scheduling and Work Status Reports shall be provided when requested by the KO. A written status report of any item of work must be provided within two hours of the inquiry during regular working hours, and by 0800 the following work day for inquiries after regular working hours.
2.6.3	Work Schedule	The Contractor's work shall not interfere with normal Government business. In those cases where some interference is unavoidable, the Contractor shall minimize the impact and effects of the interference. The Contractor shall provide advance access of all of its work schedules to the Government. The Contractor shall notify the KO of any difficulty in scheduling work due to Government controls.
2.6.4	Service Interruptions	If any utilities or other services must be discontinued (even temporarily) due to scheduled contract work, the Contractor shall notify the KO, affected tenants, and customers in accordance with local procedures. If the discontinued service is due to an emergency breakdown the Contractor shall notify the KO, affected tenants and customers as soon as practicable.
2.6.4.1	Service Interruption Request Form NNSY	Utilities outages at NNSY are to be requested on the Service Interruption Request Form NNSY to be provided upon request by the Contracting Officer.
2.6.5	Quality Management System (QMS)	The Contractor shall establish and maintain a complete QMS program in accordance with the provisions specified herein. The Contractor’s QMS program shall provide an effective and efficient means of identifying and correcting problems throughout the entire scope of operations. The Contractor's QMS program shall address: • Accurate documentation of work processes, procedures, and output measures. • A systematic procedure for assessing compliance with performance

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		objectives and standards. • Accurate documentation of quality inspections conducted throughout the execution of work. • Assessment-driven corrective actions and process adjustments as appropriate in a timely manner.
2.6.5.1	Quality Control Plan (QCP)	Within 15 calendar days after award of the contract, the Contractor shall submit to the KO a QCP. The QCP shall describe the QMS methodology and approaches used under this contract. Within seven calendar days of any change during period of performance, submit to the KO a revised QCP for acceptance.
2.6.5.2	QC Inspection	The Contractor shall establish and maintain an inspection system in accordance with the FAR Clause 52.246-4, INSPECTION OF SERVICES – FIXED PRICE, to ensure that the work performed conforms to the contract requirements. The Contractor shall maintain a file of all scheduled and performed QC inspections, inspection results, and dates and details of corrective and preventive actions. The file shall be the property of the Government and made available during the Government's regular working hours. The QC Inspection File shall be turned over to the KO within five calendar days of completion/termination of the contract.
2.6.5.3	Contractor Quality Control/Assessment Reports	The Contractor shall submit a copy of the Contractor Quality Control/Assessment Report to the KO monthly for the quality control events performed and assessment-driven corrective actions and process adjustments during the previous month. The Government may adjust the frequency of the submittal based on the Contractor's quality of performance.
2.6.6	Environmental Management System (EMS)	The Contractor shall perform work under this contract consistent with the following EMS goals and policy. Goals: • Reduce purchase and use of toxic and hazardous materials; • Expand purchase of green products and services; increase recycling; • Reduce energy and water use; • Increase use of alternative fuels and renewable energy; • Integrate green building concepts in major renovations and new construction; • Prevent pollution at the source; and • Continual improvement policy: • Preserve our natural, historic and cultural resources; • Conserve natural resources by reducing what we discard, reusing items, and recycling materials, which includes purchasing products made from recycled materials; • Integrate sound environmental practices into all our operations and business decisions; Integrate environmental protection requirements and pollution prevention initiatives into the early planning, design and procurement of facilities, equipment and material, as well as the planning and implementation of military training activities; • Prevent or minimize pollution at its source as we seek out ways to eliminate or further minimize use of hazardous materials and generation of hazardous waste; • Maintain a sound partnership with regulatory agencies to sustain our compliance with existing and new environmental laws and regulations; • Enhance our program as we develop and implement an Environmental Management System; and • Adhere to this policy, remind one another to do so, and ensure that our entire community knows this is our policy by our actions as well as our

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		words. The Contractor shall maintain monitoring and measurement information to address the EMS goals and policy and provide the EMS Goals and Policy Measurement Information to the KO when requested. In the event an EMS nonconformance or environmental noncompliance associated with the contracted services, tasks, or actions occurs, the Contractor shall take corrective and/or preventative actions. In the case of a noncompliance, the Contractor shall assume legal and financial liability for the noncompliance and take corrective action immediately to remedy the noncompliance. In the case of a nonconformance, the Contractor shall respond and take corrective action based on the time schedule established by the KO. The Contractor shall ensure that its employees are aware of their roles and responsibilities under the EMS and how these EMS roles and responsibilities affect work performed under the contract.
2.6.7	Use of Recovered Materials	The Government has an affirmative procurement program to promote the purchase of products containing recovered materials. The intent is to reduce the solid waste stream and conserve natural resources by establishing markets for recycled content products and encouraging manufacturers to produce quality products containing recovered materials. Participate in this program by using, for Environmental Protection Agency (EPA) designated items, recovered materials to the maximum extent practicable without jeopardizing the intended end use of the item. The percentage of recovered materials content levels for use in the performance of this contract will be, at a minimum, the amount recommended in the EPA Comprehensive Procurement Guideline (CPG) Product Index (website http://www.epa.gov./cpg/products). Use of EPA designated products is not required for products that are either not available within a reasonable period of time, are not available at a reasonable price, are not available from a sufficient number of sources to maintain a satisfactory level of competition, or fail to meet performance standards based on technical verification. EPA designation of products is an on going process. Listings of EPA designated products containing recovered materials are found in 40 CFR 247. Make recommendation and submit Recovered Material Certification, to the KO, when a product containing recovered materials is equal to or better than the original and could be used for this contract. All changes of products shall be accepted by the KO before it is used.
2.7	Personnel Requirements	The Contractor shall comply with the personnel requirements stated below.
2.7.1	Key Personnel	Within 15 calendar days after award of the contract, the Contractor shall submit to the KO an Organizational Chart showing lines of authority of the key personnel and on-site supervisor(s) for this contract. The chart shall include names of personnel and their position title in this contract. As a minimum, include the PM, QCM, SSHO, and on-site supervisor(s) and who they will report directly to for this contract. The PM, SSHO and QCM may be the same person
2.7.1.1	Project Manager (PM)	The Contractor shall provide a PM who has relevant experience at a comparable level of responsibility in projects of similar size, scope and complexity. The PM or alternate shall have full authority to act for the Contractor on all contract matters relating to this contract. The PM or alternate shall be on-site within two hours after notification.
2.7.1.2	Quality Control Manager (QCM)	The Contractor shall provide a QCM who shall have full authority and responsibility for assuring performance objectives and standards identified in this contract are met. The QCM may be the same person as the project manager. The QCM or alternate shall be available on-site within one hour after the Government's request.

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
2.7.1.3	Site Safety and Health Officer (SSHO)	The Contractor shall provide a SSHO whose primary duty and responsibility is to prepare and enforce the Contractor's safety program on this contract. The SSHO shall have fulfilled the following pre-requisite training and experiences before being hired as the SSHO under this contract: The SSHO shall have satisfactory experience in preparing and enforcing safety programs on contracts of similar size and complexity in the past, and have completed the OSHA 10-hour construction safety class or equivalent within the last three years. The SSHO may be the same person as the project manager but shall have fulfilled the pre-requisite qualification and experience.
2.7.2	Employee Requirements	The Contractor shall provide experienced, qualified, and capable personnel to perform the work in this contract. Personnel shall be fully knowledgeable of all safety and environmental requirements associated with the work they perform. Competent personnel shall be provided as required. Personnel shall speak, read, and comprehend English to the extent that they can perform the contract requirements and comply with installation emergency procedures.
2.7.2.1	Employee Appearance	The Contractor shall ensure that all employees present a professional appearance that is appropriate for their position. The KO reserves the right to determine the acceptability of any clothing worn. All Contractor/subcontractor employees working under this contract shall be identified by a distinctive nameplate, emblem, or patch attached in a prominent place on an outer garment. Employee identification shall not be substituted for station required passes or badges.
2.7.2.2	Employee Conduct	Contractor employees shall conduct themselves in a proper, efficient, courteous and businesslike manner.
2.7.2.3	Removal of Employees	The Contractor shall remove from the site any individual whose continued employment is deemed by the KO to be contrary to the public interest or inconsistent with the best interests of National Security.
2.7.2.4	Proof of Legal Residency	No employee or representative of the Contractor will be admitted to the site of work unless satisfactory Proof of Legal Residency is furnished.
2.8	Security Requirements	The Contractor shall comply with all Federal, state, and local security statutes, regulations, and requirements. The Contractor shall become acquainted with and comply with all Government regulations as posted, or as requested by the KO when required to enter a Government site. The Contractor shall ensure that all security/entrance clearances are obtained.
2.8.1	Employee Listing	The Contractor shall maintain and provide upon request a current Employee List. The list shall include the employee's name, social security number, and level of security clearance.
2.8.2	Vehicles	The company name shall be displayed on each of the Contractor's vehicles in a manner and size that is clearly visible. All vehicles shall display a valid state license plate that complies with State Vehicle Code. Vehicles shall meet all other requirement of the State Vehicle Code, such as safety standards, and shall carry proof of insurance and state registration, if applicable.
2.8.3	Passes and Badges	All Contractor employees shall obtain the required employee and vehicle passes. The Government will issue badges without charge. The Contractor employees must be able to obtain CAC in accordance with security requirements. Each employee shall wear the Government issued badge over the front of the outer clothing. When an employee leaves the Contractor's service, the employee's Passes and Badges shall be returned within 10 calendar days.
2.8.3.1	Requirements for Obtaining Passes and Badges	1.Contractor's employees requiring access for periods from one day to one year shall submit to the Security Office the following: a. An installation sponsor request forwarded to the security office.

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		b. A valid form of Federal or state government identification. c. If driving a motor vehicle, a valid driver's license, vehicle registration and proof of insurance. d. Proof of employment on a valid Government contract (e.g. a letter from the prime contractor including contract number and term) e. Proof of an employee background check conducted within the past year. The background check must include or establish the employee's citizenship or legal alien status. Acceptable documents shall include birth certificate, Immigration and Naturalization Service (INS) forms and passports. 2. All information will be subject to Government verification. The Government may randomly screen contractor submissions through the FBI National Crime Information Center (NCIC) Interstate Identification Index (III) system. All NCIC III checks must follow by the submission of fingerprint records to the FBI Automated Fingerprint Identification System (AFIS) data. NCIC checks and fingerprinting will be performed at Government expense. 3.Access may be denied if it is determined that an employee: a. Is on the National Terrorist Watch List. b. Is illegally present in the United States. c. Is subject to an outstanding warrant. d. Has knowingly submitted an employment questionnaire with false or fraudulent information. e. Has been issued a debarment order and is currently banned from a military installation. The Contractor may visit the following website for additional information, requirements and guidance for base access. http://www.cnrma.navy.mil/cnrma05/CVS.htm. Additional NNSY security and base access information can be obtained at the following web site http://www.nnsy1.navy.mil/Security/docs/Contractor%20Access%20Guidelines-July%2007.doc
2.8.4	Access to Buildings	The Contractor shall monitor and control access into restricted areas under their responsibility, allowing only those individuals who have been properly cleared into restricted areas or other controlled access areas. The Contractor shall comply with security requirements, plus those imposed by the installation Commander at all times. Personnel with access to special areas will have the appropriate screening and/or security clearance, and personnel requiring routine access to restricted areas will wear special badges authorizing access for those areas. Contractor personnel shall not enter restricted or controlled areas or installation facilities unless specifically authorized in performance of their duties. The Contractor shall secure all buildings and facilities entered during non-duty hours and will secure all building and facilities under the Contractor's cognizance at the end of each work day or shift period.
2.8.5	Access Arrangements	The Contractor shall make all arrangements through the appropriate office necessary to obtain access to buildings, facilities and other work areas, and when necessary, arrange for them to be opened and closed by the controlling authority. The Government may issue keys to the Contractor. The Contractor shall use due diligence and be responsible for compromised security systems to include replacement costs that result from its action or inaction.
2.8.6	Security Clearances	The Contractor shall obtain all required corporate and personnel Security

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		Clearances prior to commencement of work. The Contractor shall ensure that a list of all personnel with Security Clearances is maintained current, including clearances that are pending.
2.8.7	Special Security NNSY	
2.8.7.1	Photographs NNSY	Unofficial photography is prohibited in the Naval Shipyard. When operationally required, submit a written request containing specific justification and details to the Security Officer prior to release.
2.8.7.2	Marine Corps Security Force (MCSF) NNSY	MCSF Battalion Atlantic, Fleet Anti-Terrorism Security Team or "FAST" will assist the Security Operations Division, Code 1121, in providing perimeter security during special operations at Norfolk Naval Shipyard. MCSF personnel perform duties within the controlled industrial area (CIA) and the non-industrial areas of the Shipyard. MCSF personnel can be easily identified by their combat dress which includes the following items: Camouflage utilities, radio, sidearm and shoulder fired weapons, field protective mask, cartridge belt, armored vest, and various types of ammunitions. Follow these guidelines when interfacing with MCSF personnel in performance of their duties. Individuals Shall: 1) Follow all instructions received from Marines. 2) Obey all security signs posted on or around facilities protected by MCSF. Individuals who violate these areas are subject to apprehension, treated as intruders, detained for further investigation and/or administrative or disciplinary actions as deemed necessary/appropriate. 3) Report any security violations or hostile threats to one of the following: a) Marine Corps Corporal of the Guard b) DoD Security Police Officer c) Security Police Dispatcher, phone 396-7266 d) Code 1121 phone 396-1330/6-2883 e) Shipyard Duty Officer, phone 396-3221, (weekends, backshifts, and holidays). Individuals Shall Not: 1) Attempt to converse with, sneak up on, touch, or closely approach an armed Marine. 2) Make idle threats or joke about assets the MCSF are protecting or attempt to position yourself between MCSF personnel and these assets.
		3) Loiter near assets protected by MCSF or the MCSF barracks. iii. Actions During Drills or Alerts: 1) Stay well clear of MCSF response forces and avoid making any threatening gestures. 2) If possible, leave the vicinity of the DRILL / ALERT location, make your job radiological safe, seek a safe covered position near you and await further instructions from:

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		a. Security personnel: Code 1121, Marines, and DOD Security Police. b. Code 105 control point personnel, if within a radiological controlled area. c. Your immediate supervisor. d. Ship's force, if shipboard or in dry dock. 3) Marines will treat all personnel in a courteous but forceful manner. You should report any disrespectful treatment by Marines to your immediate supervisor.
2.8.7.3	Material Storage NNSY	Ensure that no material is stacked within 10 feet of the Controlled Industrial Area (CIA) perimeter. Remove from the work site, or secure ladders or other such equipment that could be used to climb the CIA perimeter fence. Ensure that no vehicles are parked within 10 feet of the CIA perimeter.
2.8.7.4	Contractor Created Openings NNSY	Ensure that no opening in the roof / walls / windows / fence of the building exist at the end of the workday and do not exist where penetration is possible during non-working hours. If the building cannot be secured at the end of the workday, coordinate action with the Contracting Office to notify the responsible code to arrange for a security watch by their personnel.
2.8.7.5	Contractor Created Penetrations NNSY	Seventy-two (72) hours prior to making any penetrations (such as tunneling under, cutting through a fence or building) in a restricted area contact the Shipyard Security Office to make arrangements for a security guard or other measures required to meet all security requirements.
2.8.7.6	Trustworthiness Security – Navy Contract/Task Orders	Reference is hereby made to Navy awarded contracts requiring Contractor access to sensitive unclassified information. Although these contracts are not classified and Contractor employees are not required to have a security clearance, the Department of the Navy (DoN) has determined that all DoN information systems are sensitive regardless of whether the information is classified or unclassified. A Contractor whose work involves access to sensitive unclassified information warrants a judgment of an employee's trustworthiness. Therefore, all personnel must undergo a National Agency Check to verify their trustworthiness. Also, the Government will include Facility Access Determination (FAD) program requirements in the contract specifications when trustworthiness determinations will be required on the Contractor employees. The following addresses those requirements for Trustworthiness Security. a. Each Contractor employee must have a favorably completed National Agency Check (NAC). b. If Contractor personnel currently have a favorably adjudicated NAC the Contractor shall notify the Security Manager of the Government command they will visit who will validate this in the Joint Personnel Adjudication System (JPAS). The request shall be renewed annually or for the duration of the contract if less than one year. c. If no previous investigation exists the Contractor personnel shall complete the requirement for a Trustworthiness NAC. Investigations for public trust positions, to include IT-II (Limited Privileged) and IT-III (Non-Privileged) positions that access unclassified sensitive information when clearance eligibility is not required, will be submitted to the Office of Personnel Management (OPM) utilizing the SF-85P (code 08B for IT-II and code 02B for IT-III) and will include the SF-87 Fingerprint Card or electronic fingerprint transmission. The Government Security Manager will process the Trustworthiness NAC. The contract employee shall provide the completed Personnel Security Investigation (PSI) to the Security Manager along with the original signed release statements and applicant fingerprint card

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		(FD87). The responsibility for providing the fingerprint card rests with the Contractor. The Security Manager will review the form for completeness, accuracy and suitability issues and will forward the completed SF85P along with attachments to OPM. The Department of Navy Central Adjudication Facility (DoN CAF) will perform adjudicating contractor investigations for public trust positions. Contractor fitness determinations made by the DoN CAF will be maintained in the Joint Personnel Adjudication System (JPAS). Favorable fitness determinations will support public trust positions only and not national security eligibility. If no issues are discovered, according to respective guidelines a "Favorable Determination" will be populated in JPAS and will be reciprocal within DoN. If issues are discovered, the DoN CAF will place a "No Determination Made" in the JPAS and forward the investigation to the submitting office for Government command's final determination.
2.9	Contractor Safety Program	The Contractor shall develop and implement a Safety Program detailing how the Contractor plans, staffs, performs, and controls all safety practices while delivering best value services to the Government without any accidents or mishaps. The Contractor's safety program shall comply with all safety standards identified in the U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM-385-1-1 and Public Law 91-596, Occupational Safety and Health Act.
2.9.1	Accident Prevention Plan (APP)	To ensure that the Contractor has a well organized and thorough Safety Program, the Contractor shall prepare an Accident Prevention Plan (APP). The APP shall be prepared by the Contractor's SSHO and shall be followed by all Contractor employees, subcontractors, and vendors at each service site. The APP shall follow the format and cover all topics as delineated in Appendix A of EM-385-1-1. The APP shall incorporate Activity Hazard Analyses (AHAs) and Situation Specific Safety Plans that are relevant to the site specific hazards and controls for each activity and type of work that may be encountered in the performance of this contract. The Contractor shall submit an APP to the KO within for acceptance. The Contractor shall review, update, and submit the revised APP to the KO whenever a change in work conditions, hazards, or activities occur.
2.9.2	Activity Hazard Analysis (AHA)	The Contractor shall prepare Activity Hazard Analyses (AHAs) for all common recurring work activities performed under this contract. AHAs shall be submitted with the APP and shall be updated as work activities or conditions change and additional AHAs prepared as new work activities are required. Specifically: For combination FFP/IDIQ contracts, the Contractor shall submit an AHA on task orders, with the associated proposal, whenever the service environment or required task is different from the firm-fixed-priced services. AHAs shall follow format of Figure 1-1 of EM-385-1-1 and shall explain the following as detailed in the EM-385-1-1: • The steps of the service process; • Identify potential hazards that exist as a result of the Contractor's service process within the environment; • Measures or plans of actions to safely remove potential hazards away from people in and around the service process and environment; • Specific materials and equipment necessary to safely remove potential hazards away from people in and around the service process and

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		environment; • Inspection requirements to assure service activity is safe; and • Training of service personnel to be aware of potential hazards and measures or plans of actions to be used to remove hazards from service environment. During performance of services, the SSHO shall periodically review the AHA at each service site and for each sub-annex to assess the effectiveness of the Contractor's overall APP. If changes to the AHAs are required, such changes shall be submitted to the KO for review and acceptance.
2.9.3	Hazard Specific Safety Plans	The Contractor shall develop and implement hazard specific safety plans, as listed below, as necessary for the situation or types of work to be performed under this contract. These Hazard Specific Safety Plans shall be submitted with the APP and shall be updated as situations change. Additional hazard specific safety plans developed as applicable when new types of work are required under this contract.
2.9.3.1	Confined Space Access Plan	The Contractor shall develop a plan to explain how it will assure its service employees have safe access to a confined work space. The plan shall: (1) identify the competent person's name, qualifications, training, and experiences; (2) delineate the competent person's authority to direct work and stoppages in adverse conditions; (3) air quality and ventilation system requirements; (4) include procedures to rescue Contractor/subcontractor/vendor personnel in distress; and (5) coordinate with emergency responders. See relevant requirements of paragraph 06.I of EM-385-1-1, 29 CFR 1910, 29 CFR 1915, and 29 CFR 1926, and any other Federal, state and local regulatory standards.
2.9.3.2	Drug Abuse Prevention Plan	The Contractor shall develop a plan to explain how it will satisfy the drug-free work force requirement as stated in DFARS Clause 252.223-7004.
2.9.3.3	Emergency Response Plan	The Contractor shall develop an emergency response plan to ensure safe evacuation of people during emergencies, before the hazard or natural disaster is imminent, and to minimize the consequences of accidents during evacuations. See Section 01E of EM 385-1-1.
2.9.3.4	Fall Protection Plan	The Contractor shall develop a plan to explain how it will eliminate falls at the service site. The plan will explain how the Contractor will protect and prevent its service workers from falling from heights of 1.8m (6 feet) or more. A competent person for fall protection shall prepare and sign the plan. See EM 385-1-1, ANSI A10.32, ANSI Z359.1, and ANSI/ASSE A10.34.
2.9.3.5	Fire Prevention Plan	The Contractor shall develop a plan to explain how it will eliminate or contain fires when using hot kettles or welding equipment at facilities and service sites. This plan shall be used by Contractor employees to: (1) obtain hot work permits and identify emergency first responders to fire hazards; (2) identify and make available materials and equipment to suppress or contain fires; and (3) emergency evacuation procedures. See Sections 6 and 9 of EM 385-1-1, NFPA10, NFPA 241, NFPA 51B, NFPA 70, NFPA 70E, and NARA 29 CFR 1926.500.
2.9.3.6	Hazard Communication Plan	The Contractor shall develop a plan to explain how it will identify hazardous substances at the service site. This plan shall address: (1) training (to include potential safety and health effects from exposure); (2) labeling of hazardous substances; (3) maintaining an inventory listing of hazardous chemicals at the service site; and (4) location of a library of Material Safety Data Sheets (MSDSs) in the office to satisfy 29 Code of Federal Regulations (CFR) 1910.1200 or 1926.59 requirements.
2.9.3.7	Hazardous Energy	The Contractor shall develop a plan to explain how it will control hazardous

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
	Control Plan	energy within an existing service environment. This plan shall address: (1) intended operations and procedures; (2) means to coordinate and communicate the control of hazardous energy; (3) procedural steps and responsibilities for shutting down, isolating, blocking, and securing systems to control hazardous energy; (4) steps and responsibilities for the placement, removal, and transfer of lockout and tagged out devices; (5) steps and responsibilities for placing and tagging, and moving or removing and un-tagging, protective grounds; (6) requirements for testing the system to verify the effectiveness of lockout and tag-out isolation devices; (7) courses of actions to implement during emergencies; (8) requirements when removing hazardous energy control devices must be transferred from one authorized person to another, and the name of the individuals qualified for receiving such a transfer; and (9) the means to enforce compliance with the procedures.
2.9.3.8	Health Hazard Control Plan	The Contractor shall develop a plan to explain how it will determine the presence of hazardous or toxic agents at the service environment and explain what safety measures are to be taken. This plan shall satisfy relevant topics of Section 6 of EM385-1-1.
2.9.3.9	Lead Abatement Compliance Plan	The Contractor shall develop a plan to explain how it will protect its service work force from lead exposure. This plan shall also address relevant procedures, requirements, and protocols of 29 CFR 1910.1025 and 29 CFR 1926.62.
2.9.3.10	Respiratory Protection Plan	The Contractor shall develop a plan Contractor to explain how it will protect the health of its employees whenever respirators are needed. This plan shall include service-site-specific procedures in accordance with EM 385-1-1 Section 05.E and OSHA's respiratory protection standard at 29 CFR 1910.134.
2.9.4	Accident and Damage Reporting	The Contractor shall notify the KO of all damages, accidents, mishaps, and near misses that occur on or related to Government property as soon as practical, but not later than four hours. For recordable injuries and illnesses, property damage accidents resulting in at least $2,000 in damages, and Weight Handling Equipment (WHE) accidents, the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident. (a) For recordable injuries and illnesses and property damage accidents resulting in at least $2,000 in damages complete the Navy Contractor Significant Incident Report (CSIR) form and provide the report to the KO within 1 calendar day of the accident. The KO will provide a blank copy of any required or special forms. (1) Recordable Injuries or Illnesses. Any work-related injury or illness that results in: (i) Death, regardless of the time between the injury and death, or the length of the illness; (ii) Days away from work (any time lost after day of injury/illness onset); (iii) Restricted work; (iv) Transfer to another job; (v) Medical treatment beyond first aid; (vi) Loss of consciousness; or (vii) A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (1) through (6) above. (b) For WHE accidents (including rigging gear accidents) complete the WHE Accident Report (Crane and Rigging Gear) form and provide the report to

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		the KO within 30 calendar days of the accident. The KO will provide a blank copy of the accident report form. (1) WHE Accident. A WHE accident occurs when any one or more of the six elements in the operating envelope fails to perform correctly during operation, including operation during maintenance or testing resulting in personnel injury or death; material or equipment damage; dropped load; derailment; two-blocking; overload; and/or collision, including unplanned contact between the load, crane, and/or other objects. A dropped load, derailment, two-blocking, overload and collision are considered accidents even though no material damage or injury occur. A component failure (e.g., motor burnout, gear tooth failure, bearing failure) is not considered an accident solely due to material or equipment damage unless the component failure results in damage to other components (e.g., dropped boom, dropped load, roll over, etc.). Comply with current 29CFR1904 for OSHA/HIOSH record keeping and reporting requirements.
2.9.4.1	Accident Reporting Notification	The Contractor shall report all accidents, mishaps, and near misses to the KO in a timely manner as described below: • An Initial Accident Reporting Notification Report shall be developed by the Contractor and provided to the KO immediately after that an accident, or near miss, has occurred. The Contractor may not have all the facts and information regarding the actual incident or near miss at the time of the initial report. However, it is the Government's desire to receive notification of all mishap situations as early as possible. • The Contractor shall develop a Follow-on Accident Reporting Notification Report and shall and provide a copy to the KO by close of business the day of the accident, or if the accident occurs after hours, at start of business the following morning. Follow-on reports shall be required daily until the Contractor can send a final, conclusive report of the nature, cause, and outcome of the accident. • The Contractor shall provide a Final Accident Reporting Notification Report of the accident to the KO within 24 hours after completing the investigation of the accident.
2.9.5	Fire Protection	The Contractor shall know where fire alarms are located and how to activate them. The Contractor shall handle and store all combustible supplies, materials, waste and trash in a manner that prevents fire or hazards to persons, facilities, and materials.
2.9.6	Monthly On-Site Labor Report	The Contractor shall provide a monthly On-Site Labor Report to the KO. This report is a compilation of employee-hours worked each month for all site workers, both prime and subcontractor.
2.9.7	OSHA Citations and Violations	The Contractor shall correct violations and citations promptly and provide a copy of each OSHA citation and OSHA report with written OSHA Citations and Violations Corrective Action Report to the KO within 48 hours after receiving a citation.
2.9.8	Safety Inspections and Monitoring	The Contractor shall be responsible for regularly inspecting its work areas, job sites, and work crews to ensure that all Contractor operations are being conducted safely. These inspections shall ensure: • The site is safe and free of job-site hazards • Proper PPE is being utilized and worn. • Safe work practices and processes are being followed. • Workers are familiar with the hazards covered in the respective AHA

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		for that work activity. • All equipment and tools are in good condition and being used safely. The Government reserves the right to inspect and monitor Contractor operations for safety compliance. In general, the Government approach will be to conduct Performance Assessment on the quality and effectiveness of the Contractor's safety program. The Government reserves the right to stop any work activity that it deems to be unsafe. Contractor personnel shall work in a safe manner and comply with all applicable safety regulations. The Contractor shall be subject to safety inspections of its work sites by the Government. Contractor safety records shall be available to the KO upon request. Whenever the KO becomes aware of any safety noncompliance or any condition which poses a serious or imminent danger or hazard to the health or safety of the public or Government Personnel, the KO will notify the Contractor orally, with written confirmation, and request immediate corrective action. This notice, when delivered to the Contractor's representative or SSHO, shall be deemed sufficient notice of noncompliance and that corrective action is required. After receiving this notice, the Contractor shall immediately take corrective action. If the Contractor fails, delays, or refuses to promptly take corrective action, the KO may issue a stop work order for all or part of the services or work until satisfactory corrective action has been taken. Whenever such a stop work order has been issued, the Contractor shall waive all equitable adjustments to the contract related to the stop work ordered issued. The Contractor shall include this requirement in all of its subcontracts and vendor contracts in support of contract safety.
2.9.9	Safety Certification	The Contractor shall submit copies of all the required Federal, state, county, city or industry safety related Safety Certifications for work performed under this contract. These certifications shall be kept up to date by the Contractor. The Contractor shall submit new versions of certifications to the KO as the old certifications expire. No work, that requires a certification, shall start without a valid and approved certification.
2.9.10	Safety Apparel on Jobsites	Appropriate garment shall be based on the worker hazards and tasks, complexity of the work environment or background, and vehicular traffic and speed. As a minimum, the Contractor personnel shall wear ANSI/ISEA 107-2004 Class I compliant apparel.
2.9.11	Additional Safety Requirements for Norfolk Naval Shipyard	All spec items that are specific to the Norfolk Naval Ship Yard will have NNSY at the bottom of the title block.
2.9.11.1	Emergency Response Requirement NNSY	The Norfolk Naval Shipyard has instituted a requirement for all personnel to take shelter for personal safety in the event of certain emergencies. This policy includes Contractors, Subcontractors, and any person who is employed by the Contractor. The most appropriate protective action for certain emergencies is to take shelter. Personnel shall immediately seek shelter while an assessment is made of the threat and determinations are being made regarding subsequent actions such as "all clear" or selected building evacuations
2.9.11.2	Notification NNSY	The primary means of alerting personnel shall be emergency alert signals. The alerting signal to seek shelter shall be three steady tones that last for thirty seconds separated by ten seconds of silence. The notification for "all clear" shall be three short tones repeated three times.
2.9.11.3	Sheltering	When personnel hear the alert signal, the area of work must be secured in a

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
	NNSY	manner that will leave the site in a safe condition. Personnel shall seek shelter in the nearest occupied building in calm and orderly manner. If possible, secure all windows and doors and shut off ventilation. If working aboard ship, proceed into the interior of the ship and wait for further directions from official personnel. If in a vehicle, park the vehicle so that it does not block the normally traveled portion of the road and proceed into the nearest occupied building.
2.9.11.4	Evacuation NNSY	In the event of an evacuation, personnel shall receive directions from team members of the Crowd Control Center (CCC) or the building custodian acting on the directions from the CCC. Contract personnel shall comply with instructions given at all times.
2.9.11.5	Incident Report NNSY	Contractor shall instruct their personnel, including subcontractors, assigned to a job within NNSY, upon witnessing flooding, fire, injury to personnel, or any other incident or casualty requiring emergency response, to immediately contact the following - NNSY Fire Department 396-3333, any NNSY Supervisor / Manager and, the KO. Provide the location and other pertinent details.
2.9.12	Fire Protection NNSY	Contractor employees shall know how to turn in a fire alarm. The Contractor shall handle and store all combustible supplies, materials, waste and trash in a manner that prevents fire or hazard to persons, facilities, and material. Contractor employees operating critical equipment shall be trained to properly respond during a fire alarm or fire in accordance with activity instruction procedure number NAVSHIPYDNORINST P11320.6 29 April 1982 or latest revision.
2.9.13	Hot Work Permit NNSY	The Contractor shall be responsible for obtaining a Hot Work Permit from the Norfolk Naval Shipyard Fire Department, phone No. (757) 396-3333 prior to any burning or welding. When using a grinder for grinding flowed metal, no hot work permit shall be required as long as the diameter of the grinding wheel does not exceed 3 inches. Should the Contractor decide to use a grinder with a grinding wheel that exceeds 3 inches in diameter, the Contractor shall be required to obtain a Hot Work Permit.
2.9.14	Traffic Cones and Signs NNSY	Contractor shall provide 36 inch tall Traffic Cones to be placed around each vehicle when areas of work are located in areas that do not provide parking slots.
2.9.15	Access to Radiological Controlled Areas NNSY	Contractor personnel shall not, under any circumstances, enter a radiological controlled area or cross any posted radiological boundary. This paragraph applies to all phases of contract work. Radiation areas are posted with signs consistent with OSHA requirements. Ensure that employees are familiar with the radiation signs and symbols. All personnel entering the shipyard for the first time are required to receive radiological indoctrination training. Should contract workers encounter radiological postings and/or boundaries that appear to limit their ability to access or carry out their intended work, they shall notify their Contract Administrator for resolution of the problem.
2.9.15.1	Restrictions On Use of Yellow Materials NNSY	Contractors shall refrain from the use of yellow or yellow-orange materials for the following purposes: sheeting, tarpaulins, polyethylene bottles or other containers, tapes, bags, raingear, banding of identification marks on tools and boundary markers such as ribbons. Contractor generated yellow waste materials such as torn foul weather gear shall be disposed of by the contractor off-yard. Shipyard dumpsters and trashcans shall not be used for disposal of Contractor generated waste materials. Yellow colored items such as described above are of special significance within the shipyard and are subject to strict controls.
2.9.16	Danger Tags and Locks NNSY	Lockouts and tag outs for the servicing and / or maintenance work in shops, buildings and other locations within the shipyard on facilities owned and operated by NNSY by outside activities shall be performed by authorized

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		Contractor employees after receiving authorization to isolate the system(s) from the building custodian Assistance in identifying the proper isolation points will be available from the building custodian. The Contractor shall also provide and attach danger tags to all mechanical and electrical equipment being serviced that may cause damage or injury to property and personnel working in the area. After all services have been completed the Contractor shall notify the Contracting Officer's Representative within one hour that electrical service can be restored.
2.10	Environmental Protection	The Contractor shall comply with all applicable Federal, state, and local laws, and with the regulations and standards listed in. All environmental protection matters shall be coordinated with the KO. Inspection of any of the facilities operated by the Contractor may be accomplished by the Activity Environmental Protection Coordinator, or authorized officials on a no-notice basis during Government regular working hours. In the event that a regulatory agency assesses a monetary fine against the Government for violations caused by Contractor negligence, the Contractor shall reimburse the Government for the amount of that fine, costs of defending against administrative or other legal action, remedial action, and other costs. The Contractor shall comply with the instructions of the cognizant Navy Medical Department with respect to avoidance of conditions which create a nuisance or which may be hazardous to the health of military or civilian personnel. The Contractor is responsible for ensuring that its employees receive applicable environmental and occupational health and safety training, and are kept up to date on regulatory required specific training for the type of work to be conducted onsite. All on-site Contractor personnel, and their subcontractor personnel, performing tasks that have the potential to cause a significant environmental impact shall be competent on the basis of appropriate education, training or experience.
2.10.1	Disposal	
2.10.1.1	Non-Hazardous Waste	The Contractor shall dispose of debris and rubbish resulting from the work under this contract off-installation.
2.10.1.2	Hazardous Waste	All hazardous waste generated as a result of this contract shall be turned over to the Government for proper disposal, in accordance with the Resource Conservation and Recovery Act and all other applicable Federal, state and local laws and regulations. No on-installation disposal of hazardous waste is allowed.
2.10.2	Spill Prevention, Containment, and Clean-up	The Contractor shall prevent, contain, clean up, and report all spills on Government property, caused by the Contractor, in a manner that complies with applicable Federal, state, and local laws and regulations or otherwise stated herein, and the installation spill control plan as specified in EM-385 1-1 at no cost to the Government.
2.10.3	Hazardous Material Management	The Contractor shall ensure that procedures are in place to deal with hazardous materials, pursuant to the FAR Clause 52.223-3, HAZARDOUS MATERIAL IDENTIFICATION AND MATERIAL SAFETY DATA.
2.10.4	Protection of Endangered and Threatened Species (Flora and Fauna)	The Contractor shall not disturb endangered and threatened species and their habitat. The Contractor shall carefully protect in-place and report immediately to the KO endangered and threatened species discovered in the course of work. The Contractor shall stop work in the immediate area of the discovery until directed by the KO to resume work.
2.10.5	Noise Control	The Contractor shall comply with all applicable Federal, state and local laws, ordinances, and regulations relative to noise control.
2.10.6	Asbestos Containing Material (ACM)	Asbestos containing insulation, flooring, and other building materials may be encountered by the Contractor during the performance of work under this contract, and the Contractor shall remain alert to this possibility. If ACM is

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		encountered or suspected in the performance of work, the Contractor shall avoid removing, sanding, abrading, or disturbing the material. The Contractor shall verbally notify the KO within one hour and follow-up with written ACM Notification within 24 hours.
2.11	Additional Environmental Protection at Norfolk Naval Shipyard	All spec items that are specific to the Norfolk Naval Ship Yard will have NNSY at the bottom of the title block.
2.11.1	Hazardous Material/Hazardous Waste NNSY	The Contractor shall provide and maintain for the life of the contract, environmental protection as defined. Plan for and provide Environmental Protective measures to control pollution that develops during the normal course of work. Plan for and provide environmental protective measures to correct conditions that develop during the normal course of work. Comply with Federal, State and Local regulations pertaining to the environment, including but not limited to water, air and noise pollution. Ten days after the award of the Contract, the Contractor shall meet with the Contracting Officer to discuss the proposed Environmental Protection Plan and to develop mutual understanding relative to the details of environmental protection, including measures for protecting natural resources, required reports, and other measures to be taken.
2.11.2	Hazardous materials (HM) to be brought onto the station NNSY	Any Hazardous materials planned for use on the station shall be included in the station Hazardous Material Tracking Program maintained by the Safety Department. To assist this effort, the Contractor shall submit a list (including quantities) (Form to be provided by the Contracting Officer when requested) of HM to be brought to the station and copies of the corresponding material safety data sheets (MSDS). All hazardous material must be properly labeled in accordance with OSHA requirements. This list shall be submitted to the Contracting Officer. At project completion, the Contractor shall remove any hazardous material brought onto the station from the site. The Contractor shall account for the quantity of HM brought to the station, the quantity used or expended during the job, and the leftover quantity, which (1) may have additional useful life as a HM and shall be removed by the Contractor, or (2) may be a hazardous waste, which shall then be removed as specified herein.
2.11.2.1	Equipment Containing Radioactive Material	Before EVERY entry to NNSY, the Contractors must contact the Radiation Safety Officer (RSO) for approval prior to transporting any equipment containing radioactive material and/or machine source (i.e. x-ray producing instrument) on NNSY property. The Radiation Safety Officer can be contacted at 396-5766, 2921 or 5959.
2.11.3	Hazardous waste (HW) generated NNSY	The Environmental Protection Plan shall list and quantify any HW to be generated during the project.
2.11.4	Storage of hazardous waste NNSY	In accordance with station regulations, hazardous waste shall be stored near the point of generation up to a total quantity of one quart of acutely hazardous waste or 55 gallons of hazardous waste. Any volume exceeding these quantities shall be moved to a HW permitted area within 3 days. Prior to generation of HW, contact the Contracting Officer for labeling requirements for storage of hazardous wastes. The Contractor's Environmental Coordinator is responsible to contact Code 106 for waste pick up.
2.11.5	Minimization of hazardous waste NNSY	In accordance with station regulations, the Contractor should substitute materials as necessary to reduce the generation of HW and include a statement to that effect in the Environmental Plan.

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
2.11.6	Hazardous Material Use NNSY	With respect to hazardous materials, safety program shall include provisions to deal with hazardous materials, pursuant to the Contract Clause "FAR 52.223-3, Hazardous Material Identification and Material Safety Data" In addition to FAR 52.223-3, the plan shall consist of: 1) An index of hazardous materials to be introduced to the site; 2) Plan .for protecting personnel and property during the transport, storage and use of the materials; 3) Procedures for spill response and disposal; 4) Material Safety Data Sheets for materials listed in the index of the plan and not required in the technical section of the specification. Post Material Safety Data Sheets at the worksite where the products will be used. Material Safety Data Sheets meeting the requirements of 29 CFR 1910.1200 must be submitted for all Title 29 Part 1910.1200 used on this project. The Material Safety Data Sheets must be submitted to the Shipyard Occupational Safety, Health, and Environment Officer (Code 106), located in Building M-22, 3rd floor at NNSY prior to the hazardous chemical/materials being brought into the Shipyard. 5) Approved labeling system to identify contents an all containers on site. 6) Personnel training plan. 7) Evidence of compliance with 29 CFR 1910.1200 requirements. 8) Each hazardous material must receive approval prior to bringing onto the job site or prior to any other use in conjunction with this contract. Allow a minimum of 10 working days for processing of the request for use of a hazardous material. Any work or storage involving hazardous chemicals or materials must be done in a manner that will not expose shipyard employees to any unsafe or unhealthful conditions. Adequate protective measures must be taken to prevent shipyard employees from being exposed to any hazardous condition that could result from the work or storage. Approval by the Contracting Officer of protective measures and storage area is required prior to the start of work.
2.11.7	Unforeseen Hazardous Material NNSY	All known hazardous materials are indicated on the drawings. If additional material that is not indicated on the drawings is encountered that may be dangerous to human health upon disturbance during construction operations, stop that portion of work and notify the Contracting Officer immediately. Intent is to identify materials such as PCB, lead paint, and friable and nonfriable asbestos. Within 14 calendar days the Contractor will determine if the material is hazardous. If the material is not hazardous or -poses no danger, the Government will direct the Contractor to proceed without change. If the material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification pursuant to "FAR 52.243-4, Changes" and "FAR 52.236-2, Differing Site Conditions."
2.11.8	Health and Safety Plan (HASP) NNSY	COE EM-385-1-1, Perform a Hazard Analysis, and submit a detailed job specific HASP for the work procedures to be used in the removal, demolition, and disposal of materials. A certified Industrial hygienist shall prepare, sign, and seal the plan (The industrial hygienist shall be retained by the Contractor for

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		the duration of the contract). Prior to beginning the work, obtain approval of the plan and meet with the Contracting Officer to discuss work procedures and safety precautions. The HASP shall include: 1) Locations size and details of control areas. 2) Location and details of decontamination systems. 3) Interface of trades involved in the construction. 4) Sequencing of work. 5) Disposal plan. 6) Sampling protocols and testing labs. 7) Protective equipment. 8) Detailed description of method of controlling pollution. 9) Evidence of compliance with 29 CFR 1910.120.
2.11.9	Asbestos Certification / Asbestos containing materials NNSY	Items, components, or materials to be worked under this contract may involve asbestos. Other materials, especially thermal insulation, in the general work area may also contain asbestos. All thermal insulation in all work areas should be considered to be asbestos unless positively identified by laboratory analysis certifying asbestos free. The contractor shall not remove or perform work on any such materials without the proper approval of the Contracting Officer. The Contractor shall not engage in any activity that would remove or damage such materials or cause the generation of fibers from such materials. The Contractor shall immediately stop all work which would generate further damage to the material, evacuate the potential asbestos exposed area, and notify the Contracting Officer for resolution of the situation prior to resuming normal work activities in the affected area.
2.11.10	Safety And Health Requirements For Control Of Asbestos Material NNSY	Accomplish Asbestos work in accordance with the requirements of references in J-0200000-03. The KO's written approval of the Asbestos Abatement Plan must be received by the Contractor prior to performing Asbestos work. Submit to Code 106 a copy of the approved plan and the completed Asbestos Check Off List (Form to be provided by the Contracting Officer when requested). For all Asbestos work performed, provide the COR and Code 106 with a copy of the 10 working day notification form required by NESHAPS 40 CFR 61 Subpart M, prior to performing any Class I Asbestos renovation work involving greater than 160 sq. ft. or 260 ln. ft. or any demolition of a facility. An Asbestos inspection must be performed by a qualified AHERA Asbestos inspector to determine the presence of any Asbestos Containing Material (ACM). A copy of a written Asbestos inspection report and laboratory results must be forwarded to the KO and Code 106 for review. If material has been assumed to contain Asbestos, the Asbestos inspection and report are not required. Any material assumed to be, or identified as, Asbestos must be encapsulated / removed by a licensed Asbestos removal contractor employing licensed Asbestos personnel. See J-02000000-03 for required references.
2.12	Water Pollution Control NNSY	1) Discharges/flushes to the river, storm drainage system, utility tunnels, sanitary sewerage system, and Dry-dock shall be strictly controlled to maintain compliance with various NNSY operating permits. 2) Precautions shall be taken to prevent fuels, oils, paints, thinners, paint chips, dust or related debris from entering the river or storm drain system or dry dock de-watering system. 3) Use of detergents and cleaning compounds for cleaning over or near the water or storm drains is not permitted without prior approval from NNSY OSHE

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		(Code 106.31) at 396-7231. Obtain approval same as for Water Pollution Control Requirements of this Guidance. Residue from sweeping, compressed air or water pressure cleaning operations shall not be allowed to enter the river or storm drain system. 4) Liquid discharges/flushes (including potable water) shall not be directed to the river or storm drain system without written approval from NNSY Code 106. Obtain the approval by: Submit to NNSY Code 106.31 a completed (Discharge / Flush Authorization Form) (To be provided by the Contracting Officer upon request) at least two weeks in advance of actual work operations that will generate the liquid waste stream desired to be discharged to the river or storm drain system. 5) During the work the liquid to be discharged shall be containerized. 6) Upon completion of the work, sample the liquid and submit the analysis results to Code 106.31 for final discharge approval. 7) If the liquid fails to meet permitted levels for river discharge, Code 106.31 will notify the contractor and KO so that an appropriate discharge strategy can be developed. 8) For Sanitary Sewerage System and Collection, Holding, Transfer (CHT) system discharges/flushes: Do not place any additives (e.g. chemical cleaning agents) into CHT systems without the written approval from Code 106.3. Do not dump paint, thinner, paint debris or brush/roller cleanup residue of any kind into the CHT system, restroom facilities or deep sinks. Black water / gray water wastes resulting from cleaning or hydroblasting of CHT system piping / tanks shall not be directed to the sanitary sewerage system without the written approval from Code 106.323. Obtain the approval by:
		Submit to NNSY Code 106.323 a completed (Discharge / Flush Authorization Form) (To be provided by the Contracting Officer upon request) at least two weeks in advance of actual work operations that involve hydroblasting or CHT tank cleaning. Include in this notification the 24-hour telephone number(s) and the name of the contractor's project supervisor. During the work the liquid to be discharged shall be containerized. Upon completion of the work, sample the liquid and submit the analysis results to Code 106.323 for final discharge approval. When analysis indicates that approval for discharge cannot be granted, Code 106.323 will notify the contractor and COR. All wastewater not approved for discharge through the NNSY sanitary sewerage system shall be disposed of per NAVYSHIPYDNORINST P5090.2, Volume II: Chapter 40. Submit a copy of the HRSD permit to Code 106.323 before any wastewater is taken off yard.
2.13	Housekeeping Requirements NNSY	1) Many safety and fire hazards are caused by cluttering areas, passageways, and spaces with debris and material during work. Work areas shall be cleaned as a minimum, at the end of each shift. All dust or dirt producing operations

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
		shall be contained to the space/area of the work by using methods such as engineering controls (e.g., exhaust ventilation), shrink wrap, containments, temporary boundaries, etc. Take prompt corrective actions upon notification by the COR of unacceptable operations / conditions that degrade cleanliness. At the discretion/direction of the COR, operations may be suspended until proper corrective actions have been accomplished to return the space, area or equipment / component to the level of cleanliness that was originally established. Should the contractor fail to comply, additional contractual remediation efforts will be initiated to effectively rectify the situation in a timely manner. 2) Work areas open to the environment shall be cleaned as a minimum, at the end of each shift to minimize the possibility that spent abrasives, paints, solvents, cleaners, anti-corrosive compounds, paint chips, scrap metal, trash, garbage, petroleum products or other debris will be released to the environment. 3) The contractors shall provide trash receptacles as necessary to maintain good housekeeping in contractors' work areas. These receptacles shall be emptied as necessary to prevent trash from being released to the environment. 4) There are no acceptable amounts of spent abrasives, solvents, cleaners, anti-corrosive compounds, paint chips, scrap metal, trash, garbage, petroleum products or other debris which may be released to the environment. 5)Best management controls must be established to prevent any amount of spent abrasives, solvents, cleaners, anti-corrosive compounds, paint chips, scrap metal, trash, garbage, petroleum products or other debris from being released to the environment. 6) When waste containers are provided by the contractor, J-0200000-05 / J-0200000-06 are applicable. Information for disposal of wastes not addressed above and customer complaints concerning waste containers service should be directed to NNSY via the COR.
2.14	Mercury Materials NNSY	Mercury is prohibited in the construction of this facility, unless specified otherwise, and with the exception of mercury vapor lamps and fluorescent lamps. Dumping of mercury-containing materials and devices such as mercury vapor lamps, fluorescent lamps, and mercury switches, in rubbish containers is prohibited. All used broken or unbroken fluorescent tubes and mercury vapor lamps will be properly boxed (original tube shipping cartons), and turned over to the Government for disposal. The Contractor shall not dispose of spent fluorescent tubes or mercury vapor lamps inside the Shipyard. Immediately report to the shipyard fire department Mercury Control Coordinator via the Contracting Officer instances of breakage or mercury spillage. The fire department telephone number is 396-3333. Clean mercury spill area to the satisfaction of the Contracting Officer. Mercury may have harmful effects on personnel, materials and the environment. The Occupational Safety, Health and Environment Office (Code 106) must be contacted for approval prior to using any mercury, mercury compounds, mercury containing items, equipment, materials or prior to using any materials contaminated by mercury. Mercury containing items, including fluorescent / mercury vapor lamps, must be properly disposed of in accordance with Federal, State and, local requirements.
2.15	Disaster Preparedness	The Contractor shall comply with the activity's Contingency Instruction. The Contractor shall support the installation contingency response plan as directed by the KO.
2.16	Energy	The Contractor shall comply with the activity's energy conservation program.

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
	Management	Use of high energy consuming tools or equipment is subject to approval by the KO prior to use.
2.17	Warranty Management	Prior to performing repair work, the Contractor shall report to the KO all defects in workmanship, material, parts, or improper installation and found by the Contractor to be covered by a warranty. The Contractor is responsible for knowing which equipment and components are covered by the original warranty and the warranty duration. The KO will provide available warranty documents.
2.18	Notification to the Government for Work Above the FFP Limitations	The Contractor is fully responsible for work up to the firm-fixed price limits of $2500.00. When work is expected to exceed the FFP limits, the Contractor shall notify the KO within two hours of identification for further direction. The Government may issue a task order in accordance with the IDIQ portion of the contract detailed below.
2.19	FFP Exhibit Line Item Numbers (ELINs)	FFP ELINS are provided in J-0200000-7.
2.20	IDIQ Work	IDIQ work is identified in each applicable annex or sub-annex. IDIQ work may consist of Unit Priced Tasks (UPT) Work (non-negotiated) and Unit Priced Labor (UPL) Work (negotiated). The Contractor shall perform all IDIQ task work as ordered by the KO per Section G and DoD EMALL requirements in Section H. IDIQ work will consist of Unit Priced Tasks and Unit Priced Labor Work which may be ordered by the Government as separate items or in combinations of items from the Schedule of Indefinite Delivery Indefinite Quantity Work (Bid Schedule) in Section B on an as needed basis.
2.20.1	Unit Priced Task Work (Non-Negotiated)	A Unit Priced Task (UPT) is defined as an IDIQ work item that includes all direct and indirect costs plus profit associated with the particular unit of work. All materials and equipment (rented or owned) required for the accomplishment of a UPT shall be included within the respective exhibit line item prices. The FFP for the task order is determined by multiplying the exhibit line item unit prices by the quantities ordered. The Contractor is not required to submit cost estimates for UPTs.
2.20.1.1	Acceptance and Performance	The Contractor shall possess the capability to accept and perform IDIQ work via an electronic medium with supported commands utilizing their Government Purchase Card (GPC). DoD EMALL is the electronic medium for authorized Government personnel to place orders for service to the Contractor. DoD EMALL is located at www.emall.dla.mil under NAVFAC contract. The Contractor is required to report all IDIQ quantities ordered via EMALL monthly to the KO.
2.20.1.2	Invoicing and Receiving Payment	Payment for completed EMALL orders will be made using the GPC. Reference “payment by third party” clause [FAR 52.232-36]. The Contractor shall submit one Consolidated IDIQ Invoice for IDIQ work completed during the preceding month. The Contractor shall possess the capability to invoice and receive payment for IDIQ work via an electronic medium with supported commands utilizing their GPC.
2.20.2	Unit Priced Labor Work (Negotiated)	The Contractor shall perform all UPL work in accordance with the scope and delivery schedule negotiated per each task order. Unit Priced Labor (UPL) work is defined as IDIQ work that utilizes negotiated labor hours and materials to accomplish a task not required by the fixed-price portion of the contract. UPL includes separately priced labor, materials, and equipment exhibit line items. The Contractor shall prepare and furnish a detailed cost estimate identifying proposed labor, material, and equipment costs, which upon approval by the KO, becomes a FFP task order.
2.20.2.1	IDIQ Preparation of	In response to the Government's Request for Proposal (RFP), the Contractor

DRAFT

0200000 - Management and Administration		
Spec Item	**Title**	**Description**
	Proposals	shall submit an IDIQ Proposal to the KO within two weeks for each potential task order which includes: 1) A complete list of all tasks necessary to perform the required scope of work, 2) The number of hours set forth to perform each task and 3) The projected quantity and costs of materials to perform the required scope of work.
2.20.2.1.1	Labor Requirements	Current R. S. Means or similar estimating sources shall be used for determining the number of labor hours required to complete the scope of work. The total labor cost will be determined by totaling the number of direct labor hours and then multiplying by the labor hour unit price from the Schedule of Indefinite Quantity Work.
2.20.2.1.2	Material Requirements	Current R. S. Means or similar estimating sources shall be used for determining the material estimate. Projected material requirements will include a list of materials establishing the size, quality, number of units, and unit prices. Pre-expended bin supplies and materials will not be included in the list of materials since the cost for these items were included in the labor hour unit price bid. Material prices provided by the Contractor shall be the lowest price available considering the availability of materials and the time constraints of the job. The direct material price shall be adjusted by all discounts, burden rates, and rebates for core value or salvage value that accrue to the Contractor.
2.20.2.2	Issuance of Final Task Order	The KO will order unit priced labor by issuing to the Contractor a copy of the approved scope of work and a task order for the work described, in accordance with Section G. Task order completion times will be specified on each task order.
2.20.3	IDIQ ELINS	IDIQ ELINs are provided in J-0200000-7

DRAFT

1502000 – Facility Investment Table of Content	
Spec Item	**Title**
1	General Information
1.1	Concept of Operations
2	Management and Administration
2.1	Definitions and Acronyms
2.2	Personnel
2.2.1	Certification, Training, and Licensing
2.3	Special Requirements
2.3.1	Workmanship and Material Standards (General)
2.3.2	Workmanship and Material Standards
2.3.3	Historical Preservation
2.4	References and Technical Documents
2.4.1	ODS Requirements for Refrigerant Recycling
3	FFP Work
3.1	Integrated Maintenance Program (IMP)
3.1.1	Government Identified Breakdowns
3.1.2	Government Identified Emergency Breakdowns
3.1.3	Life Safety Testing
4	IDIQ Work

DRAFT

1502000 – Facility Investment		
Spec Item	**Title**	**Description**
1	General Information	The Contractor shall provide all labor, management, supervision, tools, material, and equipment required to perform Facility Investment services for DDC equipment and systems at Naval Medical Center Portsmouth and its outlying clinics at each site in tidewater Virginia. The contractor shall be aware that the DDC provides ventilation and conditioned air to critical hospital and patient treatment rooms, monitors critical laboratory exhaust, and isolation rooms and must be maintained to a very high standard.
1.1	Concept of Operations	The intent of 1502000 Facility Investment is to specify the requirements for Sustainment, Restoration, and Modernization (SRM) sub-functions only. The Facility Investment requirements within this sub-annex primarily consist of infrastructure sustainment and minimal restoration and modernization work. Sustainment is the maintenance and repair necessary to keep an inventory of facilities and other assets in good working order. Restoration and modernization normally consists of major rehabilitation and capital improvements that is accomplished through other Navy programs. Some major repair, minor construction and stand-alone demolition may be accomplished as part of Facility Investment. The Contractor shall perform maintenance, repair, alteration, demolition and minor construction for the following: Building Systems Direct Digital Controls (DDC)

DRAFT

1502000 – Facility Investment		
Spec Item	**Title**	**Description**
2	Management and Administration	
2.1	Definitions and Acronyms	Definitions and Acronyms are listed in J-1502000-01.
2.2	Personnel	The Contractor shall provide personnel with the qualifications, technical knowledge, experience and skills required for efficient operations within the FI function.
2.2.1	Certification, Training, and Licensing	All maintenance and repair shall be performed by personnel trained and certified by the OEM. Personnel working on systems, equipment or components containing chlorofluorocarbons (CFCs) and/or hydro-chlorofluorocarbons (HCFCs) must be certified under an Environmental Protection Agency (EPA) approved technical certification program per OPNAVINST 5090.1 Chapter 6 Personnel working with or on electrical or electronic equipment must be trained and certified per NAVFAC MO-200. All maintenance trade personnel certifying or inspecting repair or maintenance work that does not require an inspector certified by a governing directive shall be qualified at the journeyman level. Service personnel should possess knowledge of commonly used programs in use at NMCP and its outlying clinics for controlling HVAC systems. (i.e. HVAC PRO, GPL and JCBASIC.) Service personnel should be able to create, modify and maintain these processes. Service personnel shall be certified by the original equipment manufacturer as fully competent to operate and service the DDC Systems at NMC Portsmouth and its Clinics. Minimum service personnel requirements shall include graduation from a technical course of instruction teaching operation and maintenance of the types of systems at Naval Medical Center Portsmouth and a minimum of three (3) years working experience within the past five (5) years. Service personnel must be similarly experienced on pneumatic control systems and mechanical HVAC equipment. Service personnel must be certified in refrigerant recovery.
2.3	Special Requirements	
2.3.1	Workmanship and Material Standards (General)	The Contractor shall be responsible for maintaining all facilities, systems, and equipment, identified in this technical sub-annex, to a standard that prevents deterioration beyond that which results from normal wear and tear and corrects deficiencies in a timely manner to assure full life expectancy of the facilities, systems, and equipment. Best commercial practices shall be applied in the performance of work. All work shall be completed per approved and accepted industry and equipment manufacturers' standards and shall comply with building and safety codes, applicable activity, local, state, and federal regulations, and other technical requirements identified within this technical sub-annex. Workmanship for maintenance and repair shall include all work necessary to complete facility and system restoration, including touch-up painting and operational checks. Upon completion of work, the Contractor shall ensure all facilities, systems, and equipment are free of missing components or defects which would affect the safety, appearance, or habitability of the facilities and structures or would prevent any

DRAFT

1502000 – Facility Investment		
Spec Item	**Title**	**Description**
		electrical, mechanical, plumbing or structural system from functioning in accordance with design intent. Repairs shall be made in accordance with the manufacturers' specifications and guidelines, and standard building codes. The quality of repairs shall meet the applicable standards and shall prevent any malfunction reoccurrences caused by poor workmanship or other contractor inadequacies. The quality of the repaired areas shall be fully compatible with adjacent surfaces or equipment. Except where otherwise specified, replacements shall match existing in dimensions, finish, color, design, and functionality and shall have an appearance similar to the original finished appearance with only minor unobjectionable deterioration resulting from normal use. The Contractor shall not allow debris to spread unnecessarily into adjacent areas nor accumulate in the work area. All such debris, excess material, and parts shall be cleaned up and removed at the completion of the job and at the end of each day work is in progress. Upon completion of work, any stains and other unsightly marks shall be removed.
2.3.2	Workmanship and Material Standards	Maintain the DDC systems in accordance with the instructions and recommendations of the Original Equipment Manufacturer to maintain stable temperature control and energy management. <u>Back Up:</u> Each field panel database and system file shall be backed up monthly. Testing will include the field tests and the performance verification tests. Field tests shall demonstrate proper calibration of input and output devices, and the operation of specific equipment. Performance verification test shall ensure proper execution of the sequence of operation and proper tuning of control loops. <u>System Modifications</u>: Provide recommendation(s) for system modification in writing to the Contracting Officer. <u>Do not</u> make system modification, including operating parameters and control settings, without prior approval of the Contracting Office. The Contractor shall be responsible for providing the most current revision of manufacturers (Metasys and M5 Platform) software on the operator workstations, lap-top computers, diagnostic tools, configuration tools, network control modules, and application specific controllers (i.e. AHU's, UUT's, DX9100's, LCP's, and VAV's). <u>Software Updates:</u> The Contractor shall be responsible for all operating software updates/upgrades, including virus protection, within 30 calendar days of their release. Installation of the updates/upgrades on the associated devices shall not impact normal hospital operations. Where non-Metasys systems exist, the most current manufacturer revisions must be compatible to the existing Metasys system or the Contractor will include a conversion process. The above work will be performed during other than normal hospital working hours at no additional cost to the Government. Copies of software updates shall be kept in Systems Control and become the property of the Government within 30 days of their release. Documentation for software updates will be provided to the Contracting Office prior to installing the updates. <u>Documentation</u>. The Contractor shall have on hand at all times a complete listing of all software programming and data contained in the DDC systems. This documentation shall be available to the Government Representative at all times throughout the life of the contract. This documentation shall be the property of the Government and shall be kept in Systems Control.
2.3.3	Historical Preservation	Buildings and facilities designated as historical sites shall be maintained in accordance with Federal, State, and local historical policies and regulations.

DRAFT

1502000 – Facility Investment		
Spec Item	**Title**	**Description**
2.4	References and Technical Document	References and Technical Documents are listed in J-1502000-02.
2.4.1	ODS Requirements for Refrigerant Recycling	1. Technicians must be certified through an EPA approved program. Copies of the certifications shall be maintained at the employee's place of business and/or carried as a wallet card by the technician. 2. Records are maintained for all refrigerant removal operations performed prior to **small appliance** or **motor vehicle air condition appliance** disposal. The recovery date, technician's name and a statement that all refrigerant that had not previously leaked was removed in accordance with 40 CFR 82 shall be included in the disposal records. 3. Records kept for all refrigerant recovery operations/services performed on equipment that normally contains 50 pounds or more refrigerant will include the service date, service description, amount of refrigerant purchased, and amount of refrigerant added. 4. Refrigerant leaks on equipment, which normally contain 50 pounds or more refrigerant, are repaired within 30 days of leak discovery. 5. Leak repairs for equipment normally containing 50 pounds or more refrigerant are documented, including the date of leak discovery and date repaired, technician's name, amount of refrigerant vented, and amount purchased and added. Satisfactory leak repair verification tests are documented within 30 days of repair. 6. Records detailing accidental venting of ODS are maintained; these records shall include as a minimum the date, type, location, amount vented, and reason for venting. 7. Records detailing the type and amount of refrigerant purchases shall be kept. 8. Only excess class I ODS are to be returned to DLA and NOT private contractors (R-11, 12, 113, 114, 500, 502). All reclaimed class I refrigerant shall be stored in approved containers, made for the intended purpose and transported by the Contractor to the Defense Logistic Agency (DLA) at the following address: Defense Depot Richmond Va. (DDVA) SW0400 Cylinder Operations 800 Jefferson Davis Highway Richmond, Virginia 23297-5000 Once the contractor has delivered the refrigerant to DLA in Richmond, he shall provide to the Contracting Officer a document stating the amount and type of refrigerant received by DLA. This document shall contain the name and if possible the signature of the person who received the refrigerant. In the eight items listed about requiring record keeping, such records are to be submitted to the Contracting Officer.

DRAFT

1502000 – Facility Investment				
Spec Item	**Title**	**Performance Objective**	**Related Information**	**Performance Standard**
3	FFP Work	The Contractor shall provide operator training for, maintain, repair, and alter the Direct Digital Control Systems (DDC), that control HVAC systems located at the Naval Medical Center, Portsmouth, Virginia, and its outlying clinics to ensure they are fully functional and in normal working condition.	The Contractor shall develop, implement, and execute an Integrated Maintenance Program, to maintain, update and repair Direct Digital Controls (DDC) equipment and systems that regulate the HVAC. The Contractor shall assume total responsibility for the maintenance and repair of the equipment as set forth under the terms of the contract. The Contractor shall be responsible for obtaining from the manufacturer all hardware, software, maintenance service instructions, operating instructions, spare parts information, control prints, wiring diagrams and any other information and / or technical data on the systems and equipment necessary for the performance of this contract. The Contractor shall maintain all maintenance, repair, and alteration data and warranty records in a technical library to be turned over to the government at the end of the contract with the final invoice. The Contractor shall study the characteristics of the installed equipment; location of all system components, controls, and regulating points; manufacturer's operation, maintenance, and trouble-shooting instructions; and is responsible to notify the Contracting Officer of any deficiencies in the system and changes required in order to meet applicable regulations, codes, and standards The Contractor shall be responsible for all repairs found by PM and Service call to the limit of $2,500. The Contractor shall submit a	The Direct Digital Control Systems (DDC) are in normal working condition and function properly in accordance with specified standards.

DRAFT

1502000 – Facility Investment				
Spec Item	**Title**	**Performance Objective**	**Related Information**	**Performance Standard**
			Maintenance/ repair Summary Report monthly. The current building inventory is provided in J-1502000-03.	
3.1	Integrated Maintenance Program (IMP)	The Contractor shall develop and implement an IMP for systems and equipment to ensure they are safe, fully functional, and operational.	The Contractor shall submit an IMP to the KO to validate completeness. The IMP shall include the Contractor's approach for Integrated Maintenance, including maintenance and inspection tasks, schedules for planned work accomplishment, plan for minimizing occurrence of repair and downtime, process for the identification of the need for repairs, and the process for scheduling and completing repair work. The systems and equipment, including associated inventories, which shall be included in the IMP are addressed in the IMP Spec Items below. As part of the IMP, the Contractor has full responsibility for any individual occurrence of repair, including replacement. The Contractor shall perform all repairs, whether identified as part of their routine IMP accomplishment, QC inspections, or notification from the Government that a breakdown or malfunction has occurred. If the Government identifies a problem or a need for repair, the Government will contact the Contractor's work reception desk. Service calls will not be issued for accomplishment of repairs on systems and equipment maintained under IMP. List of buildings containing equipment subject to IMP repairs is provided in J-1502000-03. List of equipment and data points covered by IMP is provided in J-	The Contractor's IMP is submitted within 30 days following award. IMP is accomplished per Contractor's program and work schedule. When a problem or a need for repair is identified, the Contractor shall respond within one hour and complete the repair within two days. Systems and equipment are maintained and repaired to sustain a fully functional and operable condition in accordance with OEM specifications. Work is accomplished per Spec Item 2.4.1 and 2.4.2 Workmanship and Material Standards. When repair is complete the facility, system, or equipment does not present any hazard or danger to personnel or property.

DRAFT

1502000 – Facility Investment				
Spec Item	**Title**	**Performance Objective**	**Related Information**	**Performance Standard**
			1502000-04 and J1502000-05 The Contractor shall submit a monthly IMP schedule and IMP Maintenance and Repair Status Report. The Contractor shall submit a weekly Service Call Status Report and Completed service call status report.	
3.1.1	Government Identified Breakdowns	The Contractor shall respond to Government Identified Breakdown Work in a timely manner and ensure that DDC equipment is restored to a safe, normal working condition or software has been updated and is functioning properly.	The Contractor shall receive Government Identified Breakdown calls in accordance with the work reception requirements in the IMP. The Contractor shall schedule and perform Government Identified Breakdowns according to their IMP in a way that minimizes disruptions to customers and Government operations. The Contractor shall perform any DDC Government Identified Breakdown work identified within the entire boundary of the installation and its outlying clinics.	Government Identified Breakdown work is responded to and completed within the specified time. Installed equipment and systems are restored to normal working condition, including recertification if applicable.
3.1.2	Government Identified Emergency Breakdowns	The Contractor shall respond to Government Identified emergency Breakdown calls and work until they arrest the emergency conditions to minimize and mitigate damage to facilities, ground structures, systems and danger to personnel.	The Contractor shall respond to emergency breakdown calls 24 hours a day, seven days a week throughout the contract period. The Contractor shall respond to emergency breakdown calls within 1 hour during normal working hours and within 2 hours after normal working hours. The Contractor shall respond with the appropriate service personnel and equipment to commence work immediately. The Contractor shall remain at the work site until the emergency has been mitigated. Once the emergency is mitigated, the Contractor shall schedule the remaining work if any, according to his IMP during normal working hours.	Government Identified Emergency Breakdowns responded to within required timeframe after receipt of call. Work was continued without interruption until emergency condition was mitigated.
3.1.3	Life Safety	The Contractor shall	The Contractor shall perform	The Contractor's Life

DRAFT

1502000 – Facility Investment				
Spec Item	**Title**	**Performance Objective**	**Related Information**	**Performance Standard**
	Testing	perform life safety testing on air handling equipment located in building 2 Naval Medical Center.	annual Life Safety testing including smoke damper testing on all air handlers building 2. A list of air handlers is located in J-15020001-06. Life safety check list is located in J-15020001-07 Smoke Damper list is located in J-15020001-08 The contractor shall provide life safety testing reports.	Safety testing schedule is submitted within 30 days following award. Life Safety testing schedule is accomplished per Contractor's program and work schedule. When a problem or a need for repair is identified, the Contractor shall complete the repair within two days for work that is covered up to $2,500. If repair exceeds the $2,500 dollar limit the Contractor shall report to the KO within 24 hours of identifying the repair. Systems and equipment are maintained and repaired to sustain a fully functional and operable condition in accordance with OEM specifications. Work is accomplished per Spec Item 2.4.1 and 2.4.2 Workmanship and Material Standards. When repair is complete the facility, system, or equipment does not present any hazard or danger to personnel or property.
3.1.4	Freeze stat Testing	The Contractor shall perform Annual Freeze stat testing on air handling equipment located in building 1.2 and 3 Naval Medical Center. Provide a freeze stat test report to the CO after testing is complete	Annual Freeze stat testing shall take place in preparation for the winter season. Building 1 has 13 Building 2 has 41 Building 3 has 28	All freeze stats are tested and their status is reported to the CO before the winter season.

DRAFT

1502000 – Facility Investment				
Spec Item	**Title**	**Performance Objective**	**Related Information**	**Performance Standard**
1502000 – Facility Investment				
Spec Item	**Title**	**Performance Objective**	**Related Information**	**Performance Standard**
4	IDIQ Work	IDIQ work may be ordered utilizing DoD EMALL in accordance with Section H or on a task order in accordance with the PROCEDURES FOR ISSUING ORDERS clause in Section G. The order will specify the exact locations and types of work to be accomplished. The period of performance will be specified in each order.	Refer to IDIQ ELINs for task listings, descriptions and related requirements. All periods of performance are measured from issue date of order to acceptance of the work. Performance Standards for IDIQ work will be the same as those in Spec Item 3 where applicable.	

DRAFT

0200000 – Management and Administration

SECTION F: DELIVERIES OR PERFORMANCE

DELIVERABLES						
				Distribution		
Annex/Spec Item	Form Attachment Number	Deliverable Title	Date (s) of Submission	Original	Copies (including original)	Frequency
0200000/ 2.2.1.2	N/A	Request to Work Outside Government's Regular Working Hours	As specified	KO	1	At least seven calendar days prior to requested day.
0200000/ 2.3.3	N/A	Permits and Licenses	As specified	KO	1	Before work commences and as requested by the KO.
0200000/ 2.3.4	N/A	Certificate of Insurance	As specified	KO	1	Within 15 calendar days after award.
0200000/ 2.5	N/A	Samples, MSDS, Manufacturer's Data Cut Sheets of Materials	As specified	KO	1	When requested.
0200000/ 2.6.2	N/A	Work Status Report	As specified	KO	1	Within two hours of the inquiry during regular working hours, and by 0800 the following work day for inquiries after regular working hours.
0200000/ 2.6.4	N/A	Service Interruptions	As specified	KO	1	15 calendar days before a required Interruption or as soon as practicable in an emergency.
0200000/ 2.6.4.1	N/A	Service Interruption Request Form NNSY	As specified	KO	1	15 calendar days before a required Interruption or as soon as practicable in an emergency.
0200000/ 2.6.5.1	N/A	Quality Control Plan	As specified	KO	1	Within 15 calendar days after award and within seven calendar days of changes.

DRAFT

DELIVERABLES						
Annex/Spec Item	Form Attachment Number	Deliverable Title	Date (s) of Submission	Distribution		Frequency
				Original	Copies (including original)	
0200000/ 2.6.5.2	N/A	QC Inspection File	As specified	KO	1	Within five calendar days of completion/termination of the contract.
0200000/ 2.6.5.3	N/A	Contractor Quality Control/ Assessment Report	First work day of each month.	KO	1	Monthly
0200000/ 2.6.6	N/A	Environmental Management System Goals and Policy Measurement Information	As specified	KO	1	When requested.
0200000/ 2.6.7	N/A	Recovered Material Certification	As specified	KO	1	When a product containing recovered materials is equal to or better than the original and could be used.
0200000/ 2.7.1	N/A	List of Key Personnel and Qualifications	As specified	KO	1	Within 15 calendar days after award.
0200000/ 2.7.1	N/A	Organizational Chart	As specified	KO	1	Within 15 calendar days after award.
0200000/ 2.7.2.4	N/A	Proof of Legal Residency	As specified	KO	1	Prior to be admitted to site of work.
0200000/ 2.8.1	N/A	Employee List	As specified	KO	1	Upon request.
0200000/ 2.8.3	N/A	Passes and Badges	As specified	KO	1	Within 10 calendar days when an employee leaves the Contractor's service.
0200000/ 2.8.7.6	N/A	SF-85P and SF-87 Fingerprint Card	As specified	KO/ Government Security Manager	1	Prior to use of Government computers, IT, etc.
0200000/ 2.9.1	N/A	Accident Prevention Plan	As specified	KO	1	Within 15 calendar days after award and within seven calendar days of changes.

DRAFT

DELIVERABLES						
				Distribution		
Annex/Spec Item	Form Attachment Number	Deliverable Title	Date (s) of Submission	Original	Copies (including original)	Frequency
0200000/ 2.9.2	N/A	Activity Hazard Analysis	As specified	KO	1	Together with the Accident Prevention Plan and for changes.
0200000/ 2.9.3 & 2.11.8	N/A	Hazard Specific Safety Plans	As specified	KO	1	Together with the Accident Prevention Plan and for changes.
0200000/ 2.9.4	N/A	Navy Contractor Significant Incident Report	As specified	KO	1	Within one calendar day of accident.
0200000/ 2.9.4	N/A	Weight Handling Equipment Accident Report	As specified	KO	1	Within 30 calendar day of accident.
0200000/ 2.9.4.1	N/A	Initial Accident Reporting Notification Report	As specified	KO	1	Immediately after that an accident or near miss.
0200000/ 2.9.4.1	N/A	Follow-on Accident Reporting Notification Report	As specified	KO	1	Close of business the day of the accident, or if the accident occurs after hours, at start of business the following morning.
0200000/ 2.9.4.1	N/A	Final Accident Reporting Notification Report	As specified	KO	1	Within 24 hours after completing the investigation of the accident.
0200000/ 2.9.6	N/A	On-Site Labor Report	First work day of each month.	KO	1	Monthly, by the fifth day of the month
0200000/ 2.9.7	N/A	OSHA Citations and Violations Corrective Action Report	As specified	KO	1	Within 48 hours after receiving a citation.
0200000/ 2.9.9	N/A	Safety Certifications	As specified	KO	1	Prior to start of work and as old certifications expire.
0200000/ 2.10.6	N/A	Asbestos Containing Material Notification	As specified	KO	1	Within 24 hours if ACM is encountered or suspected in the performance of work.

DRAFT

DELIVERABLES						
Annex/Spec Item	Form Attachment Number	Deliverable Title	Date (s) of Submission	Distribution		Frequency
				Original	Copies (including original)	
0200000/ 2.11.6	N/A	Material Safety Data Sheets	As specified	KO & Shipyard Occupational Safety, Health, and Environment Officer (Code 106	1	Prior to the hazardous chemical/materials being brought into the Shipyard.
0200000/ 2.11.10	N/A	Asbestos Abatement Plan	As specified	KO & Shipyard Occupational Safety, Health, and Environment Officer (Code 106	1	Prior to the Asbestos work
0200000/ 2.11.10	N/A	Asbestos inspection report and laboratory results	As specified	KO & Shipyard Occupational Safety, Health, and Environment Officer (Code 106)	1	Prior to the Asbestos work
0200000/ 2.12	N/A	Discharge / Flush Authorization Form	As specified	KO & Shipyard Occupational Safety, Health, and Environment Officer (Code 106.31)	1	two weeks in advance of actual work operations
0200000/ 2.18	N/A	Notification to Government for work over FFP limitations	As specified	KO	1	When work is expected to exceed the FFP limits, the Contractor shall notify the KO within two hours of identification for further direction.
0200000/ 2.20.1.2	N/A	Consolidated IDIQ Invoice	First work day of each month.	KO	1	Monthly

DRAFT

DELIVERABLES						
Annex/Spec Item	Form Attachment Number	Deliverable Title	Date (s) of Submission	Distribution		Frequency
				Original	Copies (including original)	
0200000/ 2.34.2.1	J-0200000-XX	IDIQ Proposal	As specified	KO	1	Within two weeks after Government's Request for Proposal.
1502000 C/ 3.1	NA	IMP Maintenance and Repair Status	Monthly	KO		Monthly no later than the 5th calendar day with invoice
1502000 C/ 3.1	NA	IMP Maintenance Schedule	Monthly	KO	12	25th day proceeding month/ monthly
1502000 C/ 3.1	NA	Service call status report	First day of the week	KO	52	No later than 0900 hours Monday
1502000 C/ 3.1.3	N/A	Life Saftey Testing		KO		10 working days after completion of the testing
1502000 C/ 4	N/A	Task order updates	Second day of the week	KO	52	Weekly by the close of business Tuesday

DRAFT

SECTION J
DOCUMENTS, EXHIBITS, AND OTHER ATTACHMENTS
TABLE OF CONTENTS

ATTACHMENT NUMBER	ATTACHMENT TITLE
J-0200000-01	DEFINITIONS AND ACRONYMS
J-0200000-02	WAGE DETERMINATIONS
J-0200000-03	INSTRUCTIONS, DIRECTIVES, AND REFERENCES
J-0200000-04	GOVERNMENT-FURNISHED PROPERTY, MATERIALS AND SERVICES
J-0200000-05	SOLID WASTE MANAGEMENT
J-0200000-06	HAZARDOUS WASTE MANAGEMENT PROCEDURES
J-0200000-7	EXHIBIT LINE ITEM NUMBERS
J-15020001-01	DEFINITIONS AND ACRONYMS
J-15020001-02	REFERENCES AND TECHNICAL DOCUMENTS
J-15020001-03	BUILDING INVENTORY
J-15020001-04	LIST OF EQUIPMENT BY BUILDING
J-15020001-05	PORTSMOUTH NAVAL HOSPITAL DATA POINTS
J-15020001-06	Life safety tested air hanlders
J-15020001-07	Life safety test check list
J-15020001-8	Smoke Damper Listing

J-0200000-01	DEFINITIONS AND ACRONYMS
Competent Person	A person who has the professional experience and training necessary to identify existing and predictable hazards at a work or service environment, and who has the authority to take prompt and corrective action to eliminate or remove dangers from the environment.
Confined Work Space	A space that is large enough and so configured that a person may bodily enter a space (such as in tanks, vessels, silos, storage bins, hoppers, vaults, pits, and like spaces where there is limited means of entry) and is hindered or restricted from escaping during an emergency.
Contracting Officer (KO)	That individual with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings. The term includes certain authorized representatives of the Contracting Officer acting within the limits of their authority as delegated by the Contracting Officer.
Contractor	That entity or its representative responsible for the delivery of the services or materials specified in this contract, as designated by contract award. The term Contractor as used herein refers to both the prime Contractor and any subcontractors. The prime Contractor shall insure that subcontractors comply with the provision of this contract.
Contractor Representative	That individual appointed by the Contractor, either orally or in writing, who has been assigned responsibility for executing the requirements of this contract.
Direct Material Costs	The actual vendor invoice charges for materials used for performance of work under this contract. Direct material costs shall include transportation charges when such charges are included on the invoice by the vendor, as well as any discounts allowed for prompt payment and discounts or rebates for core value or salvage value that accrue to the Contractor. When questions arise concerning the cost of materials, material costs will be based on the lowest of quotes provided by the Contractor from at least three different commercial vendors for the direct material cost. The Government retains the right to obtain additional quotes in questionable situations. The lowest price will be used.
Equipment	Tangible asset that is functionally complete for its intended purpose, durable, and non-expendable.
Facility	A building or structure designed and created to serve a particular function.

DRAFT

J-0200000-01	DEFINITIONS AND ACRONYMS
Maintenance And Repair	The preservation or restoration of a piece of equipment, system, or facility to such condition that it may be effectively used for its designated purposes. Maintenance/repair may be adjustment, overhaul, reprocessing, or replacement of constituent parts or materials that are missing or have deteriorated by action of the elements or usage, or replacement of the entire unit or system if beyond economical repair.
R. S. Means	A data collection and organization system developed by R. S. Means Company which can be used to prepare accurate, dependable construction estimates and budgets in a variety of ways. The Contractor shall use the latest edition. Material prices are based on a national average and computed labor costs are based on a 30-city national average. An estimate prepared using this data is called a Means estimate; data may simply be referred to as Means.
Monthly On-Site Labor Report	A compilation of all Contractor and subcontractor employee-hours involved in delivering contract services on a Government property.
Performance Assessment	A method used by the Government to provide some measure of control over the quality of purchased goods and services received.
Performance Assessment Representative (PAR)	That individual designated by the KO to be responsible for the monitoring of Contractor performance.
Pre-Expended Bin Materials And Supplies	The minor materials and supplies that are incidental to the job, for which the total direct cost of any one material line item shown on the material estimate is $10.00 or less. Examples of pre-expended bin materials and supplies include, but are not limited to, solder, lead, flux, electrical connectors, electrical tape, fuses, nails, screws, bolts, nuts, washers, spacers, masking tape, sand paper, solvent, cleaners, lubricants, grease, oil, rags, mops, glue, epoxy, spackling compound, joint tape, plumbers tape and compound, clips, welding rods, and touch up paint.
Property Administrator	An authorized representative of the Contracting Officer who is responsible for administering contract property requirements, terms and conditions of the contract
Property Management Program	A Government program established for the purpose of reviewing and approving the Contractor's Property Management Plan and System through performance of a system analysis whenever government property is in the possession of the Contractor.
Quality Control (QC)	A method used by the Contractor to control the quality of goods and services produced.
Response Time	The time allowed the Contractor after initial notification of a work requirement to be physically on the premises at the work site with appropriate personnel, tools, equipment, and materials, ready to perform the work required.
Unit Priced Labor (UPL) Hour	The unit price bid by the Contractor to perform one hour of work-in-place. With the exception of direct material and construction equipment costs, the unit price includes all indirect and direct costs associated with performing work. The price includes the Contractor's hourly composite trade wage, adjusted to allow for workforce productivity; costs for pre-expended bin materials, union agreements, crew sizes, hand tools, payroll burdens and fringes, overtime, job (field) overhead (including clerical support, supervision, inspection, fees, taxes, licenses, permits, and insurance), general and administrative (home office) overhead, and profit. Additionally, time for job preparation, safety standby personnel, and similar indirect labor elements are included.

DRAFT

Acronym	Title
ACO	Administrative Contracting Officer
BW	Biweekly
CDR	Contract Discrepancy Report
CIA	Controlled Industrial Area
CMMS	Computerized Maintenance Management System
COR	Condition of Readiness
DBH	Diameter at Breast Height
DoD	Department of Defense
DoN	Department of Navy
DRMO	Defense Reutilization Management Office
EPA	Environmental Protection Agency
EPCRA	Emergency Planning and Community Right-to-Know Act
FAR	Federal Acquisition Regulation
FFP	Firm Fixed Price
FIFRA	Federal Insecticide, Fungicide, and Rodenticide Act
FSC	Facility Support Contract
GFE	Government-furnished Equipment
GFF	Government-furnished Facilities
GFM	Government-furnished Materials
GPWS	Guide Performance Work Statements
HCA	Head Contracting Agency
ICP	Integrated Contingency Plan
IDIQ	Indefinite Delivery Indefinite Quantity
IPM	Integrated Pest Management
IPMIS	Integrated Pest Management Information System
IPMP	Integrated Pest Management Plan
KO	Contracting Officer
LAN	Local Area Network
M	Monthly
MSDS	Material Safety Data Sheets
NAVFAC	Naval Facilities Engineering Command
NFPA	**National Fire Protection Association**
NMCI	Navy Marine Corps Intranet
NOSC	Navy-On-Scene Coordinator
PAP	Performance Assessment Plan
PAR	Performance Assessment Representative
PAW	Performance Assessment Worksheet
PEO	Program Executive Officer
PM	Project Manager
PRCSP	Permit Required Confined Space Program
PWS	Performance Work Statement
Q	Quarterly
QC	Quality Control
SC	Security Clearances
SM	Semimonthly
SPAR	Senior Performance Assessment Representative
TE	Technical Exhibit
VIQ	Variation in Quantity
WBS	Work Breakdown Structure

DRAFT

ATTACHMENT J-0200000-02 WAGE DETERMINATIONS
Placeholder for Service Contract Act and Davis-Bacon Act Determinations. To be inserted by AQ

DRAFT

ATTACHMENT J-0200000-03
REFERENCES, INSTRUCTIONS, DIRECTIVES

Reference	Title
EM 385-1-1	U.S. Army Corps of Engineers Safety and Health Requirements
P.L. 91-190	National Environmental Policy Act (NEPA) pf 1969
P.L. 91-596	Occupational Safety and Health Act
ANSI Standards	A10.14, A10.4, A10.5, C2, A14.3, Z35.1, Z89.1, and Z49.1
NFPA Standards	70 and 101
NEMA Standards	PB2.1
EPA Regulations	40CFR, Part 761
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 15 Personal Protective Equipment
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 25 Man made Vitreous Fibers
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 27 Hazardous Material Controls and Management
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 38 Non-Bulk Recovery Material Control
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 40 Emergency & Hazardous Materials Discharge Contingency Plan
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 45 Bulk Recovery Material Program
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 51 Environmental Coordinators Program
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 52 Solid Waste Management
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST P.5090.2, Volume II	Chapter 58 Water Pollution Control Plan
NAVY OSHE Program Manual(s) NAVSHIPYDNORINST	Chapter 63 Clean Air Act (CAA) Compliance

DRAFT

ATTACHMENT J-0200000-03 REFERENCES, INSTRUCTIONS, DIRECTIVES	
Reference	Title
P.5090.2, Volume II	
DOD Instruction 1000-18	Federal and State Occupational Safety and Health Inspection and Investigation at Contractor Work Places on Department of Defense Installations

DRAFT

ATTACHMENT J-0200000-04 GOVERNMENT-FURNISHED PROPERTY, MATERIALS, AND SERVICES
Government-Furnished Facilities (GFF)- The Government shall furnish at a minimum 100 SF for material storage and contractors terminal placement.
Availability of Utilities- The Government will furnish water and electricity at existing outlets required for the work to be performed under the contract at no cost to the Contractor. Information concerning the location of existing outlets may be secured from the KO. The Contractor shall provide and maintain, at its expense, the necessary service lines from the existing Government outlets to the work site. Provide and maintain backflow prevention devices on connections to domestic water lines and electrical transformer provisions on connections to electric lines. Meet all Federal, State, local, and activity codes and regulations for backflow prevention devices and electrical transformer provisions. Services required by the Contractor, for which there are no available Government outlets, shall be provided by the Contractor at no cost to the Government.
Government-Furnished Materials (GFM)- The Government will provide protective clothing, (operating room type scrub suits) to be worn during inspections, testing, maintenance, and repairs done under this contract. This clothing is only to be worn when performing work in the operating rooms, when required.
Government-Furnished Equipment (GFE)- The contractor will have access to Government DDC system computers for system troubleshooting, updating, etc.

DRAFT

ATTACHMENT J-0200000-05

SOLID WASTE MANAGEMENT

I DEFINITIONS

1) Solid Waste: For purposes of the waste management program, solid waste shall be categorized as material for disposal in a landfill or incinerator (for energy recovery such as SEPSA), or as waste materials for salvage or resale, salvage for reuse, or recycling.
2) Recyclable Materials: Products and materials that can be recovered and remanufactured into a new product. Recyclable materials include, but are not limited to, the following:
   a) Metals (ferrous and non-ferrous), including banding, metal studs, ductwork, piping
   b) Asphalt
   c) Concrete, including concrete compression test cylinders, and rubble
   d) Land clearing and grubbing debris, dirt and soil
   e) Gypsum board
   f) Paper and cardboard
   g) Wood products, including crates and pallets
   h) Brick and masonry
   i) Carpet and padding
   j) Plastics
   k) Aluminum, including beverage cans
   l) Copper wiring
   m) Mechanical and electrical products and equipment
3) Recycling Facility: A business that specializes in collecting, handling, processing, distributing, or remanufacturing waste materials such as those generated by this project, into products or materials that can be used by others.
4) Salvage and Reuse: Existing usable product or material that can be saved and reused in some manner on the project site. Materials that can be salvaged and reused must comply with the applicable technical specifications and include, but are not limited to, the following:
   a) Dimensional lumber and other wood products
   b) Metal scrap
   c) Structural steel items
   d) Mechanical or electrical equipment
   e) Gypsum board
   f) Brick and masonry
5) Salvage for Resale: Existing usable product or material that can be saved and removed intact (as is) from the project site to another site for resale to others without re-manufacturing.
6) Trash: Product or material unable to be salvaged for resale, salvaged and reused, returned, or recycled.

II SOLID WASTE MANAGEMENT

1) General Intent: The Contracting Officer is concerned with the polluting effect, on the local environment, associated with waste generated by this project being sent to a landfill or SEPSA incinerator. Therefore, it is the intent of the Contracting Officer, to the greatest extent practical and economically feasible, to provide for affirmative procurement requirements IAW reference 2.12, that all solid waste materials generated be salvaged for resale, salvaged and reused, or appropriately recycled, rather than transported to a landfill, and control and dispose of solid waste IAW reference 2.13.

DRAFT

2) An effective waste management program will benefit the Contractor through reduced landfill tipping fees and reduction in material usage.

3) Waste Management Operations: Take a pro-active, responsible role in management of waste and require all subcontractors, vendors, and suppliers to participate in the effort. Establish a management program that includes, but is not limited to:

a) Salvage for resale

b) Salvage and reuse

c) Recycling

d) Disposal

e) Minimizing Packaging Waste

4) Salvage and Reuse: Salvage and reuse is a better waste management method than recycling because little or no reprocessing is necessary, thus less pollution is created when items are reused in their original form. Therefore, a diligent effort shall be made to salvage and reuse products and materials. Waste materials that cannot be salvaged and reused, and have value as being recyclable, shall be recycled. Only trash shall be transported to a landfill or SEPSA incinerator. The Contractor shall be responsible for implementation of any special programs involving rebates or similar incentives related to recycling waste for this project. Revenues or other savings obtained for recycling or returns shall accrue to the Contractor.

5) Solid Waste Management Plan: Perform a waste analysis to determine the types and quantity of waste anticipated and identify salvage for resale, salvage and reuse , recycling and disposal options available. Within 30 days after contract award and prior to performing work, submit a Waste Management Plan for review and approval. The Solid Waste Management Plan shall include the following:

a) Project waste analysis.

b) Landfill or incinerator name, address and phone number, tipping fee amounts, projected cost of disposing of all trash and waste materials in the landfill or incinerator as if there would be no salvage or recycling on this project.

c) A list of waste materials that will be salvaged for resale and salvaged and reused, and the recycling facilities that will be utilized.

d) Anticipated net cost savings determined by subtracting the cost of separating and recycling from the following:

1. Revenue from the sale of salvaged for resale products and materials.
2. Revenue from the sale of recycled products and materials.
3. Landfill or incinerator tipping fees saved due to diversion of materials to recycling.

e) Description of the means by which waste materials, selected for recycling, will be protected from contamination and a description of the means to be employed in recycling waste materials so they will be consistent with the requirements for acceptance by the recycling facilities.

f) Description of the means of transportation of recyclable materials and the destination of the materials.

6) Transportation of Recyclable Materials: Contractor must comply with all federal, state, and local environmental regulations and laws, including, but not limited to, the following:

a) DOT requirements for 49 CFR 173 and 178.

III EXECUTION

1. Program Implementation And Monitoring: Implement and maintain, for the duration of the project, the solid waste management program. Establish a method of documenting and monitoring the program, and submit a report by the 10th of the next month for the prior month with each application for payment that includes the following:

a) Amount and type of material that is recycled, by weight, including the means of transportation and the destination.

b) Amount and type of material disposed of in a landfill or SEPSA incinerator, by weight.

c) Earned revenue and the savings projected from tipping fee savings.

DRAFT

d) Cost benefit to the Project and general effectiveness of the program.

1) Salvage And Reuse: Encourage the practice of efficient waste management when using, sizing, cutting, and installing the products and materials required for this project, and reuse as many discarded original materials as possible (that would traditionally become waste) that are within the limits of other specification requirements concerning material quality.

2) Separation Of Recyclable Waste Materials: Provide the necessary containers and bins, to facilitate the solid waste management program, that are clearly and appropriately marked with Contractor Name and acceptable waste. Prevent contamination of recyclable materials from non-compatible products and materials. Separate waste at the project site by one of the following methods:

   a) Source Separated Method: Waste products and materials, that are recyclable, are separated from trash and sorted into appropriately marked separate containers and then transported to the respective recycling facility for further processing. Trash is transported to a landfill or SEPSA incinerator.

   b) Co-Mingled Method: All waste is placed into a single container and then transported to a recycling facility where the recyclable materials are sorted and processed and the remaining trash is transported to a landfill or SEPSA incinerator.

Other methods that are proposed by the Contractor and approved by the Contracting Office.

DRAFT

ATTACHMENT J-0200000-06
HAZARDOUS WASTE MANAGEMENT PROCEDURES

COMMANDER NAVY REGION
MID - ATLANTIC

REGIONAL ENVIRONMENTAL GROUP

HAZARDOUS WASTE MANAGEMENT

PROCEDURES

FOR CONTRACT OPERATIONS

The Navy's Regional Environmental Group has established several procedures to ensure that the processes associated with a contract or a contractor's generation, accumulation, storage, transportation and disposal of a Hazardous Waste is conducted in accordance with all applicable Federal, State and Navy regulations. Procedures related to the generation, accumulation and storage of Hazardous Waste are consistent regardless of what the contract states. Procedures associated with the transportation and disposal of Hazardous Waste are dependent on the specific language of the contract.

PROCEDURES FOR THE GENERATION, ACCUMULATION AND

STORAGE OF HAZARDOUS WASTE

1. The Regional Environmental Group must be contacted prior to the generation of any Hazardous Waste. The Regional Hazardous Waste Program Managers are:

Ms. Crystal St. Clair-Canaii	445-6775
Naval Station Norfolk Craney Island Fuel Depot	
Ms. Alyson Miller	445-6618
Naval Air Station Oceana Naval Air Station Oceana Dam Neck Annex	
Ms Sara Diebel	445-5576

DRAFT

Naval Amphibious Base Little Creek

Ms Valery Walker 445-6615
St. Juliens Creek Annex
Naval Weapons Station Yorktown
Naval Weapons Station Yorktown Cheatham Annex
NNSY

PROCEDURES FOR TRANSPORTING AND DISPOSING OF HAZARDOUS WASTE

DRAFT

<u>If the contract states that the Contractor will turn over all Hazardous Waste to the Navy for disposal, or if the contract does not pay the contractor for the disposal of hazardous wastes (either generated or discovered) the following procedures are to be followed.</u>

When the hazardous waste container is approaching 40 gallons for waste in a satellite accumulation area, or the 60th days of the 90-day storage time limits in a hazardous waste accumulation area, the designated Navy site custodian, is to contact the Contract Administrator, who will in-turn contact the Environmental Services Department to schedule a pick-up of the container(s). The contractor is still responsible for ensuring removal of the waste out the waste accumulation area in time.

<u>If the contract states that the Contractor will manage and dispose of all Hazardous Waste either generated or discovered during the project the following procedures are to be followed.</u>

If the contractor is designated under contract for the management and eventual disposal of hazardous waste, the contractor is responsible and liable to ensure that all wastes are disposed of according to all Federal and State Environmental Regulations. Also the contractor is responsible to ensure that all associated paperwork and records are signed and turned over to the Navy.
NOTE: All aspects of Hazardous Waste Management are subject to inspection by the Regional Environmental Group to ensure that Federal, State and Navy regulatory compliance is maintained at all times.

<u>Waste Determination</u> The contractor must determine if the waste is a solid or hazardous waste using documented process knowledge or the appropriate analytical methods. A copy of the documentation must be submitted to the Regional Environmental Group.

While the container is in the possession of the contractor, the designated site custodian must ensure the container is managed according to all applicable Federal, State, and Navy regulations as follows:

1 The contractor shall designate a Site Custodian or Site Manager. The Site Custodian or Site Manager must provide a 24-hour phone number where he may be contacted in the event of an emergency.
2 The contractor shall ensure that personnel are trained in hazardous waste management procedures to comply with the requirements of 40 CFR 262.34 and 265.16.

The Regional Environmental Group Hazardous Waste Media Managers or designated environmental official will review the waste generating processes to determine the best management practice concerning the identification, generation, management, accumulation, and disposal of any hazardous

waste.

1. The contractor, in conjunction with the HW Manager, shall establish a temporary 90-Day Hazardous Waste Accumulation Area (HWAA) or a Satellite Accumulation Area (SAA). These accumulation areas are **not** contractor lay-down areas.

NOTE: All Hazardous Waste Accumulation Areas (HWAA) require Virginia State Department of Environmental Quality. It is requested that, when possible, the HW receives notification 15 days prior to the start of accumulation. All notifications to regulators will originate from the Regional Environmental Group.

2. The HW Manager shall provide a training session for the Site Custodian or Site Manager for management of SAA or HWAA.

While the waste container is in the possession of the contractor, the designated site custodian must ensure the container is managed according to all applicable Federal, State, and Navy regulations.

- **Satellite Accumulation Areas (SAA)** must be: Established at or near the point of generation, Free of any spills, Located within 50 feet of a fire extinguisher, Equipped with a spill response kit. Have a cumulative total of not more than 55 gallon of all non-acute hazardous wastes OR Have a total of one quart of all acutely hazardous wastes

AND

The container must be: Maintained to a volume of 55 gallons or less, Kept closed at all times except when adding waste, Maintained in good condition,
Marked with the words HAZARDOUS WASTE and name of the waste,
Dated when full.

- **90-Day Hazardous Waste Accumulation Areas (HWAA)** must be: Designated in writing, Located within 50 feet of a fire extinguisher, Equipped with a spill response kit, Inspected (written) every 7 days, Managed by trained personnel.

AND

The containers must be:
DOT approved,
Kept closed at all times except when adding waste,
Maintained in good condition,
Marked with the words HAZARDOUS WASTE and name of the waste,
Dated when first drop is added,
Stored less than 90-days.

Once hazardous waste has been accumulated:

1 The Navy will be considered the generator (EPA definition) for any and all wastes that are generated on Naval Station property, regardless if the waste was generated as result of contractor activity.

2 In regards to the Hazardous Waste Manifest, the Regional Hazardous Waste Program Manager will provide

DRAFT

the Contractor with the appropriate EPA Hazardous Waste Identification Number (EPA ID#).

NOTE: The generators EPA ID# is required for transportation of hazardous waste.

3. Only a designated representative of the Regional Environmental Group can sign the Hazardous Waste Manifest. *NOTE: Contact the Regional Hazardous Waste Program Manager or the Environmental Services Department Dispatcher to schedule this service.*

4. The contractor is to ensure that the Certificate of Disposal and Manifests are to be mailed to the Regional Environmental Group, in accordance with the all Federal and State regulations. The mailing address is listed below:

Commander, Navy Region Mid-Atlantic
Regional Environmental Group
Code N454
1510 Gilbert Street
Norfolk, VA 23511-2737

DRAFT

ATTACHMENT J-0200000-07

EXHIBIT LINE ITEM NUMBERS

DRAFT

ATTACHMENT J-0200000-10
EXHIBIT LINE ITEM NUMBERS
SOLICITATION/CONTRACT #N40085-10-B-3067
EXHIBIT A - CLIN 9000

Line Item 001 Firm Fixed Price - Base Period
PROVIDE PRICES FOR FACILITY INVESTMENT - FIRM FIXED PRICE - IN ACCORDANCE WITH SECTION C, SPEC ITEM 3
ELINs A001 through A002

ELIN /Sub ELIN	Description	Quantity	Unit of Issue	Unit Price	Total	CAC
A001	**Maintain DDC systems for Naval Hospital Buildings.**					
A001AA	Building 1	12	MO	$0.00	$0.00	
A001AB	Building 2	12	MO	$0.00	$0.00	
A001AC	Building 3	12	MO	$0.00	$0.00	
A001AD	Building 20	12	MO	$0.00	$0.00	
A001AE	Building 104	12	MO	$0.00	$0.00	
A001AF	Building 249	12	MO	$0.00	$0.00	
A001AG	Building 250	12	MO	$0.00	$0.00	
A001AH	Building 252	12	MO	$0.00	$0.00	
A001AJ	Building 256	12	MO	$0.00	$0.00	
A001AK	Building 272	12	MO	$0.00	$0.00	
A001AL	Building 273	12	MO	$0.00	$0.00	
A001AM	Building 274	12	MO	$0.00	$0.00	
A001AN	Building 276	12	MO	$0.00	$0.00	
A001AO	Building 282	12	MO	$0.00	$0.00	
A001AP	Building 288	12	MO	$0.00	$0.00	
	Subtotal				$0.00	
A002	**Maintain DDC systems for Naval Hospital Outlying Clynic Buildings.**					
A002AA	Building 277, NNSY	12	MO		$0.00	
A002AB	Building 3505, LCREEK	12	MO		$0.00	
A002AC	Building 390, NAVSECGRUACT	12	MO		$0.00	
A002AD	Building 504, FCTCLANT	12	MO		$0.00	
A002AE	Building 285, NAS Oceana	12	MO		$0.00	
A002AF	Building 1806, Yorktown Naval Weapons Station	12	MO		$0.00	
A002AG	Building CD2 Sewells Point Area	12	MO		$0.00	
A002AH	Building CD3 Sewells Point Area	12	MO		$0.00	
A002AJ	Building CD4 Sewells Point Area	12	MO		$0.00	
	Subtotal				$0.00	
	TOTAL FFP LINE ITEMS			**TOTAL**	$0.00	

ATTACHMENT J-0200000-10
EXHIBIT LINE ITEM NUMBERS
N40085-10-B-3067
EXHIBIT A - CLIN 9000

Line Item 002 Firm Fixed Price - Base Period
PROVIDE PRICES FOR FACILITY INVESTMENT - INDEFINITE DELIVERY / INDEFINITE QUANTITY - IN ACCORDANCE WITH SECTION C, SPEC ITEM 4
ELINs A700 through A703

ELIN	Product Name	Description Extended	Estimated Quantity	Unit of Issue	Unit Price	Extended Price	IMAP CAC
A700	Unit Priced Labor Work - MUST BE NEGOTIATED BY KO.	Provide labor to perform all Unit Priced Labor work subject to the Service Contract Act per the scope and delivery schedule specified in the order. This shall include updating buildings to MSEA. **MUST BE NEGOTIATED BY KO USING ETO PROCESS.**	300	HR	$ -	$0.00	
A701	Material Costs- MUST BE NEGOTIATED BY KO.	Provide all materials and equipment to perform Unit Priced Labor work per the scope and delivery schedule specified in the order. This shall include updating buildings to MSEA. Use with ELIN A702. These material costs **MUST BE NEGOTIATED BY**	$15,000	EA	$ 1.00	$15,000.00	
A702	One Week Training sessions.	Provide all materials, tuition, travel, and per diem necessary to complete a weeks training for up to 4 individuals. Training dates to be decided by customer.	2	EA		$0.00	
A703	Relocate thermostats	Provide labor, material, tools, transportation, and management to relocate thermostats and/or room temperature sensors as requried to properly monitor room temperature.	100	EA		$0.00	
		TOTAL INDEFINITE QUANTITY PRICE BASE YEAR				***$15,000.00***	

ATTACHMENT J-1502000-01
DEFINITIONS AND ACRONYMS

Acronyms	**Description**
AD	Analog Data point
ADX	Extended Application and Data Server
AGA	Advanced Graphics Application
AHU	Air handling unit device
AI	Analog input point
ANSI	American National Standards Institute
AO	Analog output point
AOS	Analog Output Setpoint
ASC	Application Specific Controller
ASHRAE	American Society Heating, Refrigerating and Air Conditioning Engineers
AV	Analog Value object
BACnet	Building Automation Control Network
BAS	Building Automation System
BD	Binary Data point
BI	Binary Input point
BO	Binary Output pint
BV	Binary Value object
CCT	Controller configuration Tool
CS	Control System
DCM	Digital Control Module
DDC	Direct Digital Controls
DP	Dew point
DX9100	Metasys Extended controller
FC	Fan Coil
FEC	Field Equipment Controller
FM	Function Module
FMS	Facilities Management System
GPL	Graphic Programming Language
HP	Heat pump
HRW	Hardware
HVAC	Heating, Ventilation, and Air Conditioning
IMP	Integrated Maintenance Program
JCB	Johnson Control Basic (programming language)
LAN	Local Area Network
LCP	Lab and Central plant ASC device
LCT	Logic Connector Tool
MC	Multistate Command (as in a process)
MO	Multistate output as in a process
MSD	Multistate Data (as in a process)
MSI	Multistate Input Object
MSO	Multistate Output object
MSV	Multistate Value object
MV	Multistate value (as in a process)
NAE	Network automation Engine
NC	Network Controller

DRAFT

NCM	Network Control Module
NCU	Network Control unit
NEU	Network Expansion Unit
NFPA	National Fire Protection Association
NIE	Network Integration Engine
NT	Network Terminal
OEM	Original Equipment Manufacturer
PIDL	Proportional Integral Derivative Loop Object
RTU	Roof Top Unit
SCT	System Configuration Tool
UBC	Unified Building Code
UNT	Unitary controller
VAV	Variable Air Volume controller
VFD	Variable Frequency Drive
VMA	Variable Air Volume Modular Assembly
VSD	Variable Speed Drive.
XM	Point Multiplex Module
XRE	Latching Relay point Multiplex that drops contact state on loss of power.
XRL	Latching Relay Point Multiplex module
XRM	Momentary Relay Point Multiplex Module

DRAFT

ATTACHMENT J-1502000-02 REFERENCES AND TECHNICAL DOCUMENTS	
AMERICAN SOCIETY OF HEATING, REFRIGERATING, AND AIR-CONDITIONING ENGINEERS, INC. (ASHRAE)	
ASHRAE 127	(2001) Method of Testing for Rating Computer and Data Processing Room Unitary Air-Conditioners
ASHRAE 15	(2001; Errata 2002) Safety Standard for Refrigeration Systems
ASHRAE 34	(2001; Errata 2002) Designation and Safety Classification of Refrigerants
ASHRAE 52.1	(1992) Gravimetric an Dust-Spot Procedures for Testing Air-Cleaning
ASHRAE 64	(1995) Methods of Testing Remote Mechanical-Draft Evaporative Refrigerant Condensers
ASHRAE Gdln3	(1996) Reducing Emission of Halogenated Refrigerants in Refrigeration and Air-Conditioning Equipment and Systems
ASHRAE HA	(2003) HVAC Applications Handbook
ASHRAE Hdbk-IP	(2001) Fundamentals Handbook, I-P Edition

DRAFT

ATTACHMENT J-1502000-03 BUILDING INVENTORY
NMCP, BUILDING 1
NMCP, BUILDING 2
NMCP, BUILDING 3
NMCP, BUILDING 20
NMCP, BUILDING 104
NMCP, BUILDING 249
NMCP, BUILDING 250
NMCP, BUILDING 252
NMCP, BUILDING 256
NMCP, BUILDING 272
NMCP, BUILDING 273
NMCP, BUILDING 274
NMCP, BUILDING 276
NMCP, BUILDING 282
NMCP, BUILDING 288
NAB, LITTLE CREEK, BOONE CLINIC, BUILDING 3505
SEWELLS POINT, CD-2, CD-3, CD-4 (PNEUMATIC CONTROLS)
NAS DAM NECK, BUILDING 504
NAS OCEANA, BUILDING 285
NNSY, BUILDING 277
YORKTOWN NAVAL WEAPONS STATION, BUILDING 1806
NAVSECGRUACT, NORTHWEST, BUILDING 390

DRAFT

ATTACHMENT J-1502000-04
LIST OF EQUIPMENT BY BUILDING

	BUILDING 1	
Location	Equipment	Type
NC20-HRW	2A_FC01	36, 1, 3, VAV
NC20-HRW	2A_FC02	34, 1, 3, VAV
NC20-HRW	2A_FC03	20, 1, 3, VAV
NC20-HRW	2A_FC04	21, 1, 3, VAV
NC20-HRW	2A_FC05	24, 1, 3, VAV
NC20-HRW	2A_FC06	31, 1, 3, VAV
NC20-HRW	2A_FC07	30, 1, 3, VAV
NC20-HRW	2A_FC08	29, 1, 3, VAV
NC20-HRW	2A_FC09	28, 1, 3, VAV
NC20-HRW	2A_FC10	27, 1, 3, VAV
NC20-HRW	2A_FC11	26, 1, 3, VAV
NC20-HRW	2A_FC12	25, 1, 3, VAV
NC20-HRW	2A_FC13	23, 1, 3, VAV
NC20-HRW	2A_FC14	22, 1, 3, VAV
NC20-HRW	2A_FC15	32, 1, 3, VAV
NC20-HRW	2A_FC16	33, 1, 3, VAV
NC20-HRW	2A_FC17	35, 1, 3, VAV
NC20-HRW	2B_FC01	37, 1, 3, VAV
NC20-HRW	2B_FC02	38, 1, 3, VAV
NC20-HRW	2B_FC03	39, 1, 3, VAV
NC20-HRW	2B_FC04	41, 1, 3, VAV
NC20-HRW	2B_FC05	42, 1, 3, VAV
NC20-HRW	2B_FC06	43, 1, 3, VAV
NC20-HRW	2B_FC07	44, 1, 3, VAV
NC20-HRW	2B_FC08	45, 1, 3, VAV
NC20-HRW	2B_FC09	46, 1, 3, VAV
NC20-HRW	2B_FC10	47, 1, 3, VAV
NC20-HRW	2B_FC11	48, 1, 3, VAV
NC20-HRW	2B_FC12	40, 1, 3, VAV
NC20-HRW	2C_FC01	19, 1, 3, VAV
NC20-HRW	2C_FC02	17, 1, 3, VAV
NC20-HRW	2C_FC03	16, 1, 3, VAV
NC20-HRW	2C_FC04	10, 1, 3, VAV
NC20-HRW	2C_FC05	9, 1, 3, VAV
NC20-HRW	2C_FC06	11, 1, 3, VAV
NC20-HRW	2C_FC07	12, 1, 3, VAV
NC20-HRW	2C_FC08	14, 1, 3, VAV
NC20-HRW	2C_FC09	13, 1, 3, VAV
NC20-HRW	2C_FC10	15, 1, 3, VAV
NC20-HRW	2C_FC11	18, 1, 3, VAV
NC20-HRW	2D_FC01	49, 1, 3, VAV

DRAFT

	BUILDING 1	
Location	Equipment	Type
NC20-HRW	2D_FC02	1, 1, 3, VAV
NC20-HRW	2D_FC03	2, 1, 3, VAV
NC20-HRW	2D_FC04	3, 1, 3, VAV
NC20-HRW	2D_FC05	5, 1, 3, VAV
NC20-HRW	2D_FC06	6, 1, 3, VAV
NC20-HRW	2D_FC07	4, 1, 3, VAV
NC20-HRW	2D_FC08	7, 1, 3, VAV
NC20-HRW	2D_FC09	8, 1, 3, VAV
NC20-HRW	2D_FC10	53, 1, 3, VAV
NC20-HRW	2D_FC11	52, 1, 3, VAV
NC20-HRW	2D_FC12	51, 1, 3, VAV
NC20-HRW	2D_FC13	50, 1, 3, VAV
NC20-HRW	1A_FC01	75, 1, 3, VAV
NC20-HRW	1A_FC02	76, 1, 3, VAV
NC20-HRW	1A_FC03	85, 1, 3, VAV
NC20-HRW	1A_FC04	86, 1, 3, VAV
NC20-HRW	1A_FC05	84, 1, 3, VAV
NC20-HRW	1A_FC06	83, 1, 3, VAV
NC20-HRW	1A_FC07	82, 1, 3, VAV
NC20-HRW	1A_FC08	81, 1, 3, VAV
NC20-HRW	1A_FC09	79, 1, 3, VAV
NC20-HRW	1A_FC10	80, 1, 3, VAV
NC20-HRW	1A_FC11	78, 1, 3, VAV
NC20-HRW	1A_FC12	77, 1, 3, VAV
NC20-HRW	1A_FC13	74, 1, 3, VAV
NC20-HRW	1A-FC14	112, 1, 3, VAV
NC20-HRW	1A-FC15	113, 1, 3, VAV
NC20-HRW	1B_FC01	73, 1, 3, VAV
NC20-HRW	1B_FC02	72, 1, 3, VAV
NC20-HRW	1B_FC03	70, 1, 3, VAV
NC20-HRW	1B_FC04	69, 1, 3, VAV
NC20-HRW	1B_FC05	68, 1, 3, VAV
NC20-HRW	1B_FC06	67, 1, 3, VAV
NC20-HRW	1B_FC07	66, 1, 3, VAV
NC20-HRW	1B_FC08	71, 1, 3, VAV
NC20-HRW	1C_FC01	92, 1, 3, VAV
NC20-HRW	1C_FC02	93, 1, 3, VAV
NC20-HRW	1C_FC03	90, 1, 3, VAV
NC20-HRW	1C_FC04	91, 1, 3, VAV
NC20-HRW	1C_FC05	89, 1, 3, VAV
NC20-HRW	1C_FC06	88, 1, 3, VAV
NC20-HRW	1C_FC07	87, 1, 3, VAV
NC20-HRW	1D_FC01	65, 1, 3, VAV
NC20-HRW	1D_FC02	64, 1, 3, VAV
NC20-HRW	1D_FC03	63, 1, 3, VAV

DRAFT

	BUILDING 1	
Location	Equipment	Type
NC20-HRW	1D_FC04	62, 1, 3, VAV
NC20-HRW	1D_FC05	61, 1, 3, VAV
NC20-HRW	1D_FC06	94, 1, 3, VAV
NC20-HRW	1D_FC07	58, 1, 3, VAV
NC20-HRW	1D_FC08	59, 1, 3, VAV
NC20-HRW	1D_FC09	57, 1, 3, VAV
NC20-HRW	1D_FC10	60, 1, 3, VAV
NC20-HRW	1D_FC11	56, 1, 3, VAV
NC20-HRW	1D_FC12	54, 1, 3, VAV
NC20-HRW	1D_FC13	55, 1, 3, VAV
BO	1A_FC01	Occupied Command
AI	1A_FC01	Zone Temp
AI	1A_FC01	Zone Setpoint
AOS	1A_FC01	Heating Valve Command
AOS	1A_FC01	Cooling Valve Command
BO	1A_FC01	Fan Command
BI	1A_FC01	Fan Status
BI	1A_FC01	Pan Alarm Status
CS	1A_FC01	Temp Occ.Status C.S.
BO	1A_FC02	Occupied Command
AI	1A_FC02	Zone Temp
AI	1A_FC02	Zone Setpoint
AOS	1A_FC02	Heating Valve Command
AOS	1A_FC02	Cooling Valve Command
BO	1A_FC02	Fan Command
BI	1A_FC02	Fan Status
BI	1A_FC02	Pan Alarm Status
CS	1A_FC02	Temp Occ.Status C.S.
BO	1A_FC03	Occupied Command
AI	1A_FC03	Zone Temp
AI	1A_FC03	Zone Setpoint
AOS	1A_FC03	Heating Valve Command
AOS	1A_FC03	Cooling Valve Command
BO	1A_FC03	Fan Command
BI	1A_FC03	Fan Status
BI	1A_FC03	Pan Alarm Status
CS	1A_FC03	Temp Occ.Status C.S.
BO	1A_FC04	Occupied Command
AI	1A_FC04	Zone Temp
AI	1A_FC04	Zone Setpoint
AOS	1A_FC04	Heating Valve Command
AOS	1A_FC04	Cooling Valve Command
BO	1A_FC04	Fan Command
BI	1A_FC04	Fan Status
BI	1A_FC04	Pan Alarm Status

DRAFT

	BUILDING 1	
Location	Equipment	Type
CS	1A_FC04	Temp Occ.Status C.S.
BO	1A_FC06	Occupied Command
AI	1A_FC06	Zone Temp
AI	1A_FC06	Zone Setpoint
AOS	1A_FC06	Heating Valve Command
AOS	1A_FC06	Cooling Valve Command
BO	1A_FC06	Fan Command
BI	1A_FC06	Fan Status
BI	1A_FC06	Pan Alarm Status
CS	1A_FC06	Temp Occ.Status C.S.
BO	1A_FC08	Occupied Command
AI	1A_FC08	Zone Temp
AI	1A_FC08	Zone Setpoint
AOS	1A_FC08	Heating Valve Command
AOS	1A_FC08	Cooling Valve Command
BO	1A_FC08	Fan Command
BI	1A_FC08	Fan Status
BI	1A_FC08	Pan Alarm Status
CS	1A_FC08	Temp Occ.Status C.S.
BO	1A_FC09	Occupied Command
AI	1A_FC09	Zone Temp
AI	1A_FC09	Zone Setpoint
AOS	1A_FC09	Heating Valve Command
AOS	1A_FC09	Cooling Valve Command
BO	1A_FC09	Fan Command
BI	1A_FC09	Fan Status
BI	1A_FC09	Pan Alarm Status
CS	1A_FC09	Temp Occ.Status C.S.
BO	1A_FC10	Occupied Command
AI	1A_FC10	Zone Temp
AI	1A_FC10	Zone Setpoint
AOS	1A_FC10	Heating Valve Command
AOS	1A_FC10	Cooling Valve Command
BO	1A_FC10	Fan Command
BI	1A_FC10	Fan Status
BI	1A_FC10	Pan Alarm Status
CS	1A_FC10	Temp Occ.Status C.S.
BO	1A_FC11	Occupied Command
AI	1A_FC11	Zone Temp
AI	1A_FC11	Zone Setpoint
AOS	1A_FC11	Heating Valve Command
AOS	1A_FC11	Cooling Valve Command
BO	1A_FC11	Fan Command
BI	1A_FC11	Fan Status
BI	1A_FC11	Pan Alarm Status
CS	1A_FC11	Temp Occ.Status C.S.

DRAFT

	BUILDING 1	
Location	Equipment	Type
BO	1A_FC12	Occupied Command
AI	1A_FC12	Zone Temp
AI	1A_FC12	Zone Setpoint
AOS	1A_FC12	Heating Valve Command
AOS	1A_FC12	Cooling Valve Command
BO	1A_FC12	Fan Command
BI	1A_FC12	Fan Status
BI	1A_FC12	Pan Alarm Status
CS	1A_FC12	Temp Occ.Status C.S.
BO	1A_FC13	Occupied Command
AI	1A_FC13	Zone Temp
AI	1A_FC13	Zone Setpoint
AOS	1A_FC13	Heating Valve Command
AOS	1A_FC13	Cooling Valve Command
BO	1A_FC13	Fan Command
BI	1A_FC13	Fan Status
BI	1A_FC13	Pan Alarm Status
CS	1A_FC13	Temp Occ.Status C.S.
BO	1B_FC01	Occupied Command
AI	1B_FC01	Zone Temp
AI	1B_FC01	Zone Setpoint
AOS	1B_FC01	Heating Valve Command
AOS	1B_FC01	Cooling Valve Command
BO	1B_FC01	Fan Command
BI	1B_FC01	Fan Status
BI	1B_FC01	Pan Alarm Status
CS	1B_FC01	Temp Occ.Status C.S.
BO	1B_FC02	Occupied Command
AI	1B_FC02	Zone Temp
AI	1B_FC02	Zone Setpoint
AOS	1B_FC02	Heating Valve Command
AOS	1B_FC02	Cooling Valve Command
BO	1B_FC02	Fan Command
BI	1B_FC02	Fan Status
BI	1B_FC02	Pan Alarm Status
CS	1B_FC02	Temp Occ.Status C.S.
BO	1B_FC03	Occupied Command
AI	1B_FC03	Zone Temp
AI	1B_FC03	Zone Setpoint
AOS	1B_FC03	Heating Valve Command
AOS	1B_FC03	Cooling Valve Command
BO	1B_FC03	Fan Command
BI	1B_FC03	Fan Status
BI	1B_FC03	Pan Alarm Status
CS	1B_FC03	Temp Occ.Status C.S.
BO	1B_FC04	Occupied Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1B_FC04	Zone Temp
AI	1B_FC04	Zone Setpoint
AOS	1B_FC04	Heating Valve Command
AOS	1B_FC04	Cooling Valve Command
BO	1B_FC04	Fan Command
BI	1B_FC04	Fan Status
BI	1B_FC04	Pan Alarm Status
CS	1B_FC04	Temp Occ.Status C.S.
BO	1B_FC08	Occupied Command
AI	1B_FC08	Zone Temp
AI	1B_FC08	Zone Setpoint
AOS	1B_FC08	Heating Valve Command
AOS	1B_FC08	Cooling Valve Command
BO	1B_FC08	Fan Command
BI	1B_FC08	Fan Status
BI	1B_FC08	Pan Alarm Status
CS	1B_FC08	Temp Occ.Status C.S.
BO	1C_FC02	Occupied Command
AI	1C_FC02	Zone Temp
AI	1C_FC02	Zone Setpoint
AOS	1C_FC02	Heating Valve Command
AOS	1C_FC02	Cooling Valve Command
BO	1C_FC02	Fan Command
BI	1C_FC02	Fan Status
BI	1C_FC02	Pan Alarm Status
CS	1C_FC02	Temp Occ.Status C.S.
BO	1C_FC03	Occupied Command
AI	1C_FC03	Zone Temp
AI	1C_FC03	Zone Setpoint
AOS	1C_FC03	Heating Valve Command
AOS	1C_FC03	Cooling Valve Command
BO	1C_FC03	Fan Command
BI	1C_FC03	Fan Status
BI	1C_FC03	Pan Alarm Status
CS	1C_FC03	Temp Occ.Status C.S.
BO	1C_FC05	Occupied Command
AI	1C_FC05	Zone Temp
AI	1C_FC05	Zone Setpoint
AOS	1C_FC05	Heating Valve Command
AOS	1C_FC05	Cooling Valve Command
BO	1C_FC05	Fan Command
BI	1C_FC05	Fan Status
BI	1C_FC05	Pan Alarm Status
CS	1C_FC05	Temp Occ.Status C.S.
BO	1C_FC07	Occupied Command
AI	1C_FC07	Zone Temp

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1C_FC07	Zone Setpoint
AOS	1C_FC07	Heating Valve Command
AOS	1C_FC07	Cooling Valve Command
BO	1C_FC07	Fan Command
BI	1C_FC07	Fan Status
BI	1C_FC07	Pan Alarm Status
CS	1C_FC07	Temp Occ.Status C.S.
BO	1D_FC01	Occupied Command
AI	1D_FC01	Zone Temp
AI	1D_FC01	Zone Setpoint
AOS	1D_FC01	Heating Valve Command
AOS	1D_FC01	Cooling Valve Command
BO	1D_FC01	Fan Command
BI	1D_FC01	Fan Status
BI	1D_FC01	Pan Alarm Status
CS	1D_FC01	Temp Occ.Status C.S.
BO	1D_FC02	Occupied Command
AI	1D_FC02	Zone Temp
AI	1D_FC02	Zone Setpoint
AOS	1D_FC02	Heating Valve Command
AOS	1D_FC02	Cooling Valve Command
BO	1D_FC02	Fan Command
BI	1D_FC02	Fan Status
BI	1D_FC02	Pan Alarm Status
CS	1D_FC02	Temp Occ.Status C.S.
BO	1D_FC03	Occupied Command
AI	1D_FC03	Zone Temp
AI	1D_FC03	Zone Setpoint
AOS	1D_FC03	Heating Valve Command
AOS	1D_FC03	Cooling Valve Command
BO	1D_FC03	Fan Command
BI	1D_FC03	Fan Status
BI	1D_FC03	Pan Alarm Status
CS	1D_FC03	Temp Occ.Status C.S.
BO	1D_FC04	Occupied Command
AI	1D_FC04	Zone Temp
AI	1D_FC04	Zone Setpoint
AOS	1D_FC04	Heating Valve Command
AOS	1D_FC04	Cooling Valve Command
BO	1D_FC04	Fan Command
BI	1D_FC04	Fan Status
BI	1D_FC04	Pan Alarm Status
CS	1D_FC04	Temp Occ.Status C.S.
BO	1D_FC05	Occupied Command
AI	1D_FC05	Zone Temp
AI	1D_FC05	Zone Setpoint

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	1D_FC05	Heating Valve Command
AOS	1D_FC05	Cooling Valve Command
BO	1D_FC05	Fan Command
BI	1D_FC05	Fan Status
BI	1D_FC05	Pan Alarm Status
CS	1D_FC05	Temp Occ.Status C.S.
BO	1D_FC06	Occupied Command
AI	1D_FC06	Zone Temp
AI	1D_FC06	Zone Setpoint
AOS	1D_FC06	Heating Valve Command
AOS	1D_FC06	Cooling Valve Command
BO	1D_FC06	Fan Command
BI	1D_FC06	Fan Status
BI	1D_FC06	Pan Alarm Status
CS	1D_FC06	Temp Occ.Status C.S.
BO	1D_FC07	Occupied Command
AI	1D_FC07	Zone Temp
AI	1D_FC07	Zone Setpoint
AOS	1D_FC07	Heating Valve Command
AOS	1D_FC07	Cooling Valve Command
BO	1D_FC07	Fan Command
BI	1D_FC07	Fan Status
BI	1D_FC07	Pan Alarm Status
CS	1D_FC07	Temp Occ.Status C.S.
BO	1D_FC08	Occupied Command
AI	1D_FC08	Zone Temp
AI	1D_FC08	Zone Setpoint
AOS	1D_FC08	Heating Valve Command
AOS	1D_FC08	Cooling Valve Command
BO	1D_FC08	Fan Command
BI	1D_FC08	Fan Status
BI	1D_FC08	Pan Alarm Status
CS	1D_FC08	Temp Occ.Status C.S.
BO	1D_FC09	Occupied Command
AI	1D_FC09	Zone Temp
AI	1D_FC09	Zone Setpoint
AOS	1D_FC09	Heating Valve Command
AOS	1D_FC09	Cooling Valve Command
BO	1D_FC09	Fan Command
BI	1D_FC09	Fan Status
BI	1D_FC09	Pan Alarm Status
CS	1D_FC09	Temp Occ.Status C.S.
BO	1D_FC10	Occupied Command
AI	1D_FC10	Zone Temp
AI	1D_FC10	Zone Setpoint
AOS	1D_FC10	Heating Valve Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	1D_FC10	Cooling Valve Command
BO	1D_FC10	Fan Command
BI	1D_FC10	Fan Status
BI	1D_FC10	Pan Alarm Status
CS	1D_FC10	Temp Occ.Status C.S.
BO	1D_FC11	Occupied Command
AI	1D_FC11	Zone Temp
AI	1D_FC11	Zone Setpoint
AOS	1D_FC11	Heating Valve Command
AOS	1D_FC11	Cooling Valve Command
BO	1D_FC11	Fan Command
BI	1D_FC11	Fan Status
BI	1D_FC11	Pan Alarm Status
CS	1D_FC11	Temp Occ.Status C.S.
BO	1D_FC12	Occupied Command
AI	1D_FC12	Zone Temp
AI	1D_FC12	Zone Setpoint
AOS	1D_FC12	Heating Valve Command
AOS	1D_FC12	Cooling Valve Command
BO	1D_FC12	Fan Command
BI	1D_FC12	Fan Status
BI	1D_FC12	Pan Alarm Status
CS	1D_FC12	Temp Occ.Status C.S.
BO	1D_FC13	Occupied Command
AI	1D_FC13	Zone Temp
AI	1D_FC13	Zone Setpoint
AOS	1D_FC13	Heating Valve Command
AOS	1D_FC13	Cooling Valve Command
BO	1D_FC13	Fan Command
BI	1D_FC13	Fan Status
BI	1D_FC13	Pan Alarm Status
CS	1D_FC13	Temp Occ.Status C.S.
BO	2C_FC01	Occupied Command
AI	2C_FC01	Zone Temp
AI	2C_FC01	Zone Setpoint
AOS	2C_FC01	Heating Valve Command
AOS	2C_FC01	Cooling Valve Command
BO	2C_FC01	Fan Command
BI	2C_FC01	Fan Status
BI	2C_FC01	Pan Alarm Status
CS	2C_FC01	Temp Occ.Status C.S.
BO	2C_FC02	Occupied Command
AI	2C_FC02	Zone Temp
AI	2C_FC02	Zone Setpoint
AOS	2C_FC02	Heating Valve Command
AOS	2C_FC02	Cooling Valve Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
BO	2C_FC02	Fan Command
BI	2C_FC02	Fan Status
BI	2C_FC02	Pan Alarm Status
CS	2C_FC02	Temp Occ.Status C.S.
BO	2C_FC03	Occupied Command
AI	2C_FC03	Zone Temp
AI	2C_FC03	Zone Setpoint
AOS	2C_FC03	Heating Valve Command
AOS	2C_FC03	Cooling Valve Command
BO	2C_FC03	Fan Command
BI	2C_FC03	Fan Status
BI	2C_FC03	Pan Alarm Status
CS	2C_FC03	Temp Occ.Status C.S.
BO	2C_FC04	Occupied Command
AI	2C_FC04	Zone Temp
AI	2C_FC04	Zone Setpoint
AOS	2C_FC04	Heating Valve Command
AOS	2C_FC04	Cooling Valve Command
BO	2C_FC04	Fan Command
BI	2C_FC04	Fan Status
BI	2C_FC04	Pan Alarm Status
CS	2C_FC04	Temp Occ.Status C.S.
BO	2C_FC05	Occupied Command
AI	2C_FC05	Zone Temp
AI	2C_FC05	Zone Setpoint
AOS	2C_FC05	Heating Valve Command
AOS	2C_FC05	Cooling Valve Command
BO	2C_FC05	Fan Command
BI	2C_FC05	Fan Status
BI	2C_FC05	Pan Alarm Status
CS	2C_FC05	Temp Occ.Status C.S.
BO	2C_FC06	Occupied Command
AI	2C_FC06	Zone Temp
AI	2C_FC06	Zone Setpoint
AOS	2C_FC06	Heating Valve Command
AOS	2C_FC06	Cooling Valve Command
BO	2C_FC06	Fan Command
BI	2C_FC06	Fan Status
BI	2C_FC06	Pan Alarm Status
CS	2C_FC06	Temp Occ.Status C.S.
BO	2C_FC07	Occupied Command
AI	2C_FC07	Zone Temp
AI	2C_FC07	Zone Setpoint
AOS	2C_FC07	Heating Valve Command
AOS	2C_FC07	Cooling Valve Command
BO	2C_FC07	Fan Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
BI	2C_FC07	Fan Status
BI	2C_FC07	Pan Alarm Status
CS	2C_FC07	Temp Occ.Status C.S.
BO	2C_FC08	Occupied Command
AI	2C_FC08	Zone Temp
AI	2C_FC08	Zone Setpoint
AOS	2C_FC08	Heating Valve Command
AOS	2C_FC08	Cooling Valve Command
BO	2C_FC08	Fan Command
BI	2C_FC08	Fan Status
BI	2C_FC08	Pan Alarm Status
CS	2C_FC08	Temp Occ.Status C.S.
BO	2C_FC09	Occupied Command
AI	2C_FC09	Zone Temp
AI	2C_FC09	Zone Setpoint
AOS	2C_FC09	Heating Valve Command
AOS	2C_FC09	Cooling Valve Command
BO	2C_FC09	Fan Command
BI	2C_FC09	Fan Status
BI	2C_FC09	Pan Alarm Status
CS	2C_FC09	Temp Occ.Status C.S.
BO	2C_FC10	Occupied Command
AI	2C_FC10	Zone Temp
AI	2C_FC10	Zone Setpoint
AOS	2C_FC10	Heating Valve Command
AOS	2C_FC10	Cooling Valve Command
BO	2C_FC10	Fan Command
BI	2C_FC10	Fan Status
BI	2C_FC10	Pan Alarm Status
CS	2C_FC10	Temp Occ.Status C.S.
BO	2C_FC11	Occupied Command
AI	2C_FC11	Zone Temp
AI	2C_FC11	Zone Setpoint
AOS	2C_FC11	Heating Valve Command
AOS	2C_FC11	Cooling Valve Command
BO	2C_FC11	Fan Command
BI	2C_FC11	Fan Status
BI	2C_FC11	Pan Alarm Status
CS	2C_FC11	Temp Occ.Status C.S.
BO	2A_FC01	Occupied Command
AI	2A_FC01	Zone Temp
AI	2A_FC01	Zone Setpoint
AOS	2A_FC01	Heating Valve Command
AOS	2A_FC01	Cooling Valve Command
BO	2A_FC01	Fan Command
BI	2A_FC01	Fan Status

DRAFT

	BUILDING 1	
Location	Equipment	Type
BI	2A_FC01	Pan Alarm Status
CS	2A_FC01	Temp Occ.Status C.S.
BO	2A_FC02	Occupied Command
AI	2A_FC02	Zone Temp
AI	2A_FC02	Zone Setpoint
AOS	2A_FC02	Heating Valve Command
AOS	2A_FC02	Cooling Valve Command
BO	2A_FC02	Fan Command
BI	2A_FC02	Fan Status
BI	2A_FC02	Pan Alarm Status
CS	2A_FC02	Temp Occ.Status C.S.
BO	2A_FC03	Occupied Command
AI	2A_FC03	Zone Temp
AI	2A_FC03	Zone Setpoint
AOS	2A_FC03	Heating Valve Command
AOS	2A_FC03	Cooling Valve Command
BO	2A_FC03	Fan Command
BI	2A_FC03	Fan Status
BI	2A_FC03	Pan Alarm Status
CS	2A_FC03	Temp Occ.Status C.S.
BO	2A_FC04	Occupied Command
AI	2A_FC04	Zone Temp
AI	2A_FC04	Zone Setpoint
AOS	2A_FC04	Heating Valve Command
AOS	2A_FC04	Cooling Valve Command
BO	2A_FC04	Fan Command
BI	2A_FC04	Fan Status
BI	2A_FC04	Pan Alarm Status
CS	2A_FC04	Temp Occ.Status C.S.
BO	2A_FC06	Occupied Command
AI	2A_FC06	Zone Temp
AI	2A_FC06	Zone Setpoint
AOS	2A_FC06	Heating Valve Command
AOS	2A_FC06	Cooling Valve Command
BO	2A_FC06	Fan Command
BI	2A_FC06	Fan Status
BI	2A_FC06	Pan Alarm Status
CS	2A_FC06	Temp Occ.Status C.S.
BO	2A_FC07	Occupied Command
AI	2A_FC07	Zone Temp
AI	2A_FC07	Zone Setpoint
AOS	2A_FC07	Heating Valve Command
AOS	2A_FC07	Cooling Valve Command
BO	2A_FC07	Fan Command
BI	2A_FC07	Fan Status
BI	2A_FC07	Pan Alarm Status

DRAFT

	BUILDING 1	
Location	Equipment	Type
CS	2A_FC07	Temp Occ.Status C.S.
BO	2A_FC08	Occupied Command
AI	2A_FC08	Zone Temp
AI	2A_FC08	Zone Setpoint
AOS	2A_FC08	Heating Valve Command
AOS	2A_FC08	Cooling Valve Command
BO	2A_FC08	Fan Command
BI	2A_FC08	Fan Status
BI	2A_FC08	Pan Alarm Status
CS	2A_FC08	Temp Occ.Status C.S.
BO	2A_FC09	Occupied Command
AI	2A_FC09	Zone Temp
AI	2A_FC09	Zone Setpoint
AOS	2A_FC09	Heating Valve Command
AOS	2A_FC09	Cooling Valve Command
BO	2A_FC09	Fan Command
BI	2A_FC09	Fan Status
BI	2A_FC09	Pan Alarm Status
CS	2A_FC09	Temp Occ.Status C.S.
BO	2A_FC10	Occupied Command
AI	2A_FC10	Zone Temp
AI	2A_FC10	Zone Setpoint
AOS	2A_FC10	Heating Valve Command
AOS	2A_FC10	Cooling Valve Command
BO	2A_FC10	Fan Command
BI	2A_FC10	Fan Status
BI	2A_FC10	Pan Alarm Status
CS	2A_FC10	Temp Occ.Status C.S.
BO	2A_FC11	Occupied Command
AI	2A_FC11	Zone Temp
AI	2A_FC11	Zone Setpoint
AOS	2A_FC11	Heating Valve Command
AOS	2A_FC11	Cooling Valve Command
BO	2A_FC11	Fan Command
BI	2A_FC11	Fan Status
BI	2A_FC11	Pan Alarm Status
CS	2A_FC11	Temp Occ.Status C.S.
BO	2A_FC12	Occupied Command
AI	2A_FC12	Zone Temp
AI	2A_FC12	Zone Setpoint
AOS	2A_FC12	Heating Valve Command
AOS	2A_FC12	Cooling Valve Command
BO	2A_FC12	Fan Command
BI	2A_FC12	Fan Status
BI	2A_FC12	Pan Alarm Status
CS	2A_FC12	Temp Occ.Status C.S.

DRAFT

	BUILDING 1	
Location	Equipment	Type
BO	2A_FC13	Occupied Command
AI	2A_FC13	Zone Temp
AI	2A_FC13	Zone Setpoint
AOS	2A_FC13	Heating Valve Command
AOS	2A_FC13	Cooling Valve Command
BO	2A_FC13	Fan Command
BI	2A_FC13	Fan Status
BI	2A_FC13	Pan Alarm Status
CS	2A_FC13	Temp Occ.Status C.S.
BO	2A_FC14	Occupied Command
AI	2A_FC14	Zone Temp
AI	2A_FC14	Zone Setpoint
AOS	2A_FC14	Heating Valve Command
AOS	2A_FC14	Cooling Valve Command
BO	2A_FC14	Fan Command
BI	2A_FC14	Fan Status
BI	2A_FC14	Pan Alarm Status
CS	2A_FC14	Temp Occ.Status C.S.
BO	2A_FC15	Occupied Command
AI	2A_FC15	Zone Temp
AI	2A_FC15	Zone Setpoint
AOS	2A_FC15	Heating Valve Command
AOS	2A_FC15	Cooling Valve Command
BO	2A_FC15	Fan Command
BI	2A_FC15	Fan Status
BI	2A_FC15	Pan Alarm Status
CS	2A_FC15	Temp Occ.Status C.S.
BO	2A_FC16	Occupied Command
AI	2A_FC16	Zone Temp
AI	2A_FC16	Zone Setpoint
AOS	2A_FC16	Heating Valve Command
AOS	2A_FC16	Cooling Valve Command
BO	2A_FC16	Fan Command
BI	2A_FC16	Fan Status
BI	2A_FC16	Pan Alarm Status
CS	2A_FC16	Temp Occ.Status C.S.
BO	2A_FC17	Occupied Command
AI	2A_FC17	Zone Temp
AI	2A_FC17	Zone Setpoint
AOS	2A_FC17	Heating Valve Command
AOS	2A_FC17	Cooling Valve Command
BO	2A_FC17	Fan Command
BI	2A_FC17	Fan Status
BI	2A_FC17	Pan Alarm Status
CS	2A_FC17	Temp Occ.Status C.S.
BO	2B_FC01	Occupied Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	2B_FC01	Zone Temp
AI	2B_FC01	Zone Setpoint N/C
AOS	2B_FC01	Heating Valve Command
AOS	2B_FC01	Cooling Valve Command
BO	2B_FC01	Fan Command
BI	2B_FC01	Fan Status
BI	2B_FC01	Pan Alarm Status
CS	2B_FC01	Temp Occ.Status C.S.
BO	2B_FC02	Occupied Command
AI	2B_FC02	Zone Temp
AI	2B_FC02	Zone Setpoint
AOS	2B_FC02	Heating Valve Command
AOS	2B_FC02	Cooling Valve Command
BO	2B_FC02	Fan Command
BI	2B_FC02	Fan Status
BI	2B_FC02	Pan Alarm Status
CS	2B_FC02	Temp Occ.Status C.S.
BO	2B_FC03	Occupied Command
AI	2B_FC03	Zone Temp
AI	2B_FC03	Zone Setpoint
AOS	2B_FC03	Heating Valve Command
AOS	2B_FC03	Cooling Valve Command
BO	2B_FC03	Fan Command
BI	2B_FC03	Fan Status
BI	2B_FC03	Pan Alarm Status
CS	2B_FC03	Temp Occ.Status C.S.
BO	2B_FC04	Occupied Command
AI	2B_FC04	Zone Temp
AI	2B_FC04	Zone Setpoint
AOS	2B_FC04	Heating Valve Command
AOS	2B_FC04	Cooling Valve Command
BO	2B_FC04	Fan Command
BI	2B_FC04	Fan Status
BI	2B_FC04	Pan Alarm Status
CS	2B_FC04	Temp Occ.Status C.S.
BO	2B_FC05	Occupied Command
AI	2B_FC05	Zone Temp
AI	2B_FC05	Zone Setpoint
AOS	2B_FC05	Heating Valve Command
AOS	2B_FC05	Cooling Valve Command
BO	2B_FC05	Fan Command
BI	2B_FC05	Fan Status
BI	2B_FC05	Pan Alarm Status
CS	2B_FC05	Temp Occ.Status C.S.
BO	2B_FC06	Occupied Command
AI	2B_FC06	Zone Temp

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	2B_FC06	Zone Setpoint
AOS	2B_FC06	Heating Valve Command
AOS	2B_FC06	Cooling Valve Command
BO	2B_FC06	Fan Command
BI	2B_FC06	Fan Status
BI	2B_FC06	Pan Alarm Status
CS	2B_FC06	Temp Occ.Status C.S.
BO	2B_FC07	Occupied Command
AI	2B_FC07	Zone Temp
AI	2B_FC07	Zone Setpoint
AOS	2B_FC07	Heating Valve Command
AOS	2B_FC07	Cooling Valve Command
BO	2B_FC07	Fan Command
BI	2B_FC07	Fan Status
BI	2B_FC07	Pan Alarm Status
CS	2B_FC07	Temp Occ.Status C.S.
BO	2B_FC08	Occupied Command
AI	2B_FC08	Zone Temp
AI	2B_FC08	Zone Setpoint
AOS	2B_FC08	Heating Valve Command
AOS	2B_FC08	Cooling Valve Command
BO	2B_FC08	Fan Command
BI	2B_FC08	Fan Status
BI	2B_FC08	Pan Alarm Status
CS	2B_FC08	Temp Occ.Status C.S.
BO	2B_FC09	Occupied Command
AI	2B_FC09	Zone Temp
AI	2B_FC09	Zone Setpoint
AOS	2B_FC09	Heating Valve Command
AOS	2B_FC09	Cooling Valve Command
BO	2B_FC09	Fan Command
BI	2B_FC09	Fan Status
BI	2B_FC09	Pan Alarm Status
CS	2B_FC09	Temp Occ.Status C.S.
BO	2B_FC10	Occupied Command
AI	2B_FC10	Zone Temp
AI	2B_FC10	Zone Setpoint
AOS	2B_FC10	Heating Valve Command
AOS	2B_FC10	Cooling Valve Command
BO	2B_FC10	Fan Command
BI	2B_FC10	Fan Status
BI	2B_FC10	Pan Alarm Status
CS	2B_FC10	Temp Occ.Status C.S.
BO	2B_FC11	Occupied Command
AI	2B_FC11	Zone Temp
AI	2B_FC11	Zone Setpoint

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	2B_FC11	Heating Valve Command
AOS	2B_FC11	Cooling Valve Command
BO	2B_FC11	Fan Command
BI	2B_FC11	Fan Status
BI	2B_FC11	Pan Alarm Status
CS	2B_FC11	Temp Occ.Status C.S.
BO	2D_FC01	Occupied Command
AI	2D_FC01	Zone Temp
AI	2D_FC01	Zone Setpoint
AOS	2D_FC01	Heating Valve Command
AOS	2D_FC01	Cooling Valve Command
BO	2D_FC01	Fan Command
BI	2D_FC01	Fan Status
BI	2D_FC01	Pan Alarm Status
CS	2D_FC01	Temp Occ.Status C.S.
BO	2D_FC02	Occupied Command
AI	2D_FC02	Zone Temp
AI	2D_FC02	Zone Setpoint
AOS	2D_FC02	Heating Valve Command
AOS	2D_FC02	Cooling Valve Command
BO	2D_FC02	Fan Command
BI	2D_FC02	Fan Status
BI	2D_FC02	Pan Alarm Status
CS	2D_FC02	Temp Occ.Status C.S.
BO	2D_FC03	Occupied Command
AI	2D_FC03	Zone Temp
AI	2D_FC03	Zone Setpoint
AOS	2D_FC03	Heating Valve Command
AOS	2D_FC03	Cooling Valve Command
BO	2D_FC03	Fan Command
BI	2D_FC03	Fan Status
BI	2D_FC03	Pan Alarm Status
CS	2D_FC03	Temp Occ.Status C.S.
BO	2D_FC04	Occupied Command
AI	2D_FC04	Zone Temp
AI	2D_FC04	Zone Setpoint
AOS	2D_FC04	Heating Valve Command
AOS	2D_FC04	Cooling Valve Command
BO	2D_FC04	Fan Command
BI	2D_FC04	Fan Status
BI	2D_FC04	Pan Alarm Status
CS	2D_FC04	Temp Occ.Status C.S.
BO	2D_FC05	Occupied Command
AI	2D_FC05	Zone Temp
AI	2D_FC05	Zone Setpoint
AOS	2D_FC05	Heating Valve Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	2D_FC05	Cooling Valve Command
BO	2D_FC05	Fan Command
BI	2D_FC05	Fan Status
BI	2D_FC05	Pan Alarm Status
CS	2D_FC05	Temp Occ.Status C.S.
BO	2D_FC06	Occupied Command
AI	2D_FC06	Zone Temp
AI	2D_FC06	Zone Setpoint
AOS	2D_FC06	Heating Valve Command
AOS	2D_FC06	Cooling Valve Command
BO	2D_FC06	Fan Command
BI	2D_FC06	Fan Status
BI	2D_FC06	Pan Alarm Status
CS	2D_FC06	Temp Occ.Status C.S.
BO	2D_FC07	Occupied Command
AI	2D_FC07	Zone Temp
AI	2D_FC07	Zone Setpoint
AOS	2D_FC07	Heating Valve Command
AOS	2D_FC07	Cooling Valve Command
BO	2D_FC07	Fan Command
BI	2D_FC07	Fan Status
BI	2D_FC07	Pan Alarm Status
CS	2D_FC07	Temp Occ.Status C.S.
BO	2D_FC08	Occupied Command
AI	2D_FC08	Zone Temp
AI	2D_FC08	Zone Setpoint
AOS	2D_FC08	Heating Valve Command
AOS	2D_FC08	Cooling Valve Command
BO	2D_FC08	Fan Command
BI	2D_FC08	Fan Status
BI	2D_FC08	Pan Alarm Status
CS	2D_FC08	Temp Occ.Status C.S.
BO	2D_FC09	Occupied Command
AI	2D_FC09	Zone Temp
AI	2D_FC09	Zone Setpoint
AOS	2D_FC09	Heating Valve Command
AOS	2D_FC09	Cooling Valve Command
BO	2D_FC09	Fan Command
BI	2D_FC09	Fan Status
BI	2D_FC09	Pan Alarm Status
CS	2D_FC09	Temp Occ.Status C.S.
BO	2D_FC10	Occupied Command
AI	2D_FC10	Zone Temp
AI	2D_FC10	Zone Setpoint
AOS	2D_FC10	Heating Valve Command
AOS	2D_FC10	Cooling Valve Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
BO	2D_FC10	Fan Command
BI	2D_FC10	Fan Status
BI	2D_FC10	Pan Alarm Status
CS	2D_FC10	Temp Occ.Status C.S.
BO	2D_FC11	Occupied Command
AI	2D_FC11	Zone Temp
AI	2D_FC11	Zone Setpoint
AOS	2D_FC11	Heating Valve Command
AOS	2D_FC11	Cooling Valve Command
BO	2D_FC11	Fan Command
BI	2D_FC11	Fan Status
BI	2D_FC11	Pan Alarm Status
CS	2D_FC11	Temp Occ.Status C.S.
BO	2D_FC12	Occupied Command
AI	2D_FC12	Zone Temp
AI	2D_FC12	Zone Setpoint
AOS	2D_FC12	Heating Valve Command
AOS	2D_FC12	Cooling Valve Command
BO	2D_FC12	Fan Command
BI	2D_FC12	Fan Status
BI	2D_FC12	alPan Alarm Status
CS	2D_FC12	Temp Occ.Status C.S.
BO	2D_FC13	Occupied Command
AI	2D_FC13	Zone Temp
AI	2D_FC13	Zone Setpoint
AOS	2D_FC13	Heating Valve Command
AOS	2D_FC13	Cooling Valve Command
BO	2D_FC13	Fan Command
BI	2D_FC13	Fan Status
BI	2D_FC13	Pan Alarm Status
CS	2D_FC13	Temp Occ.Status C.S.
BO	1A_FC07	Occupied Command
AI	1A_FC07	Zone Temp
AI	1A_FC07	Zone Setpoint
AOS	1A_FC07	Heating Valve Command
AOS	1A_FC07	Cooling Valve Command
BO	1A_FC07	Fan Command
BI	1A_FC07	Fan Status
BI	1A_FC07	Pan Alarm Status
CS	1A_FC07	Temp Occ.Status C.S.
AI	1A_FC07	Zone Humdity
AD	1A_FC07	Zone Humdity Setpoint
BO	1A_FC05	Occupied Command
AI	1A_FC05	Zone Temp
AI	1A_FC05	Zone Setpoint
AOS	1A_FC05	Heating Valve Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	1A_FC05	Cooling Valve Command
BO	1A_FC05	Fan Command
BI	1A_FC05	Fan Status
BI	1A_FC05	Pan Alarm Status
CS	1A_FC05	Temp Occ.Status C.S.
AI	1A_FC05	Zone Humdity
AD	1A_FC05	Zone Humdity Setpoint
BO	1B_FC05	Occupied Command
AI	1B_FC05	Zone Temp
AI	1B_FC05	Zone Setpoint
AOS	1B_FC05	Heating Valve Command
AOS	1B_FC05	Cooling Valve Command
BO	1B_FC05	Fan Command
BI	1B_FC05	Fan Status
BI	1B_FC05	Pan Alarm Status
CS	1B_FC05	Temp Occ.Status C.S.
AI	1B_FC05	Zone Humdity
AD	1B_FC05	Zone Humdity Setpoint
BO	1B_FC06	Occupied Command
AI	1B_FC06	Zone Temp
AI	1B_FC06	Zone Setpoint
AOS	1B_FC06	Heating Valve Command
AOS	1B_FC06	Cooling Valve Command
BO	1B_FC06	Fan Command
BI	1B_FC06	Fan Status
BI	1B_FC06	Pan Alarm Status
CS	1B_FC06	Temp Occ.Status C.S.
AI	1B_FC06	Zone Humdity
AD	1B_FC06	Zone Humdity Setpoint
BO	1C_FC01	Occupied Command
AI	1C_FC01	Zone Temp
AI	1C_FC01	Zone Setpoint
AOS	1C_FC01	Heating Valve Command
AOS	1C_FC01	Cooling Valve Command
BO	1C_FC01	Fan Command
BI	1C_FC01	Fan Status
BI	1C_FC01	Pan Alarm Status
CS	1C_FC01	Temp Occ.Status C.S.
AI	1C_FC01	Zone Humdity
BO	1C_FC06	Occupied Command
AI	1C_FC06	Zone Temp
AI	1C_FC06	Zone Setpoint
AOS	1C_FC06	Heating Valve Command
AOS	1C_FC06	Cooling Valve Command
BO	1C_FC06	Fan Command
BI	1C_FC06	Fan Status

DRAFT

	BUILDING 1	
Location	Equipment	Type
BI	1C_FC06	Pan Alarm Status
CS	1C_FC06	Temp Occ.Status C.S.
AI	1C_FC06	Zone Humdity
AD	1C_FC06	Zone Humdity Setpoint
BO	1C_FC04	Occupied Command
AI	1C_FC04	Zone Temp
AI	1C_FC04	Zone Setpoint
AOS	1C_FC04	Heating Valve Command
AOS	1C_FC04	Cooling Valve Command
BO	1C_FC04	Fan Command
BI	1C_FC04	Fan Status
BI	1C_FC04	Pan Alarm Status
CS	1C_FC04	Temp Occ.Status C.S.
BO	1B_FC07	Occupied Command
AI	1B_FC07	Zone Temp
AI	1B_FC07	Zone Setpoint
AOS	1B_FC07	Cooling Valve Command
BO	1B_FC07	Fan Command
BI	1B_FC07	Fan Status
BI	1B_FC07	Pan Alarm Status
CS	1B_FC07	Temp Occ.Status C.S.
BO	2A_FC05	Occupied Command
AI	2A_FC05	Zone Temp
AI	2A_FC05	Zone Setpoint
AOS	2A_FC05	Cooling Valve Command
BO	2A_FC05	Fan Command
BI	2A_FC05	Fan Status
BI	2A_FC05	Pan Alarm Status
CS	2A_FC05	Temp Occ.Status C.S.
AI	EQUIPRM	Room Temp
BD	EQUIPRM	
BI	EQUIPRM	Exhaust Fan 10 Status
BO	EQUIPRM	Exhaust Fan 10 Command
BD	EQUIPRM	
ACM	EQUIPRM	Kilo Watt Hour Meter
AD	NC20-HRW	
CS	1A_FC14	Temp Occ-Status C.S.
AI	1A_FC14	Zone Temp
AI	1A_FC14	Zone Setpoint
AOS	1A_FC14	Heating Valve
AOS	1A_FC14	Cooling Valve
BO	1A_FC14	Fan Command
BI	1A_FC14	Fan Status
BI	1A_FC14	Pan Alarm
CS	1A_FC15	Temp Occ. Status C.S.
AI	1A_FC15	Zone Temperature

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1A_FC15	Zone Setpoint
AOS	1A_FC15	Heating Valve
AOS	1A_FC15	Cooling Valve
BO	1A_FC15	Fan Command
BI	1A_FC15	Fan Status
BI	1A_FC15	Pan Alarm
BO	2B_FC12	Occupied Command
AI	2B_FC12	Zone Temp
AI	2B_FC12	Zone Setpoint
AOS	2B_FC12	Cooling Valve Command
BO	2B_FC12	Fan Command
BI	2B_FC12	Fan Status
BI	2B_FC12	Pan Alarm Status
CS	2B_FC12	Temp Occ.Status C.S.
AOS	2B_FC12	Heating Valve Command
	Building 1	
Point	Equipment	Type
	NC-21	Network Controller
NC21-HRW	AH_3	19, 1, 3, AHU
NC21-HRW	AH_8	22, 1, 3, AHU
NC21-HRW	AH_7	21, 1, 3, AHU
NC21-HRW	AH_2	20, 1, 3, AHU
NC21-HRW	AH_9	24, 1, 3, AHU
NC21-HRW	AH_10	1, 1, 3, AHU
NC21-HRW	AH_11	254, 1, 3, AHU
NC21-HRW	AH_12	87, 1, 3, AHU
NC21-HRW	AH_13	88, 1, 3, AHU
NC21-HRW	AH_1	4, 1, 3, AHU
NC21-HRW	AH_4	78, 1, 3, AHU
NC21-HRW	AHU_5	5, 1, 3, AHU
NC21-HRW	AH_6	6, 1, 3, AHU
NC21-HRW	4A_FC01	7, 1, 3, VAV
NC21-HRW	4B_FC01	25, 1, 3, VAV
NC21-HRW	4C_FC01	8, 1, 3, VAV
NC21-HRW	4C_FC02	14, 1, 3, VAV
NC21-HRW	4C_FC03	33, 1, 3, VAV
NC21-HRW	4C_FC04	18, 1, 3, VAV
NC21-HRW	4C_FC05	17, 1, 3, VAV
NC21-HRW	4C_FC06	16, 1, 3, VAV
NC21-HRW	4C_FC07	13, 1, 3, VAV
NC21-HRW	4C_FC08	15, 1, 3, VAV
NC21-HRW	4C_FC09	11, 1, 3, VAV
NC21-HRW	4C_FC10	10, 1, 3, VAV
NC21-HRW	4C_FC11	9, 1, 3, VAV
NC21-HRW	4C_FC12	12, 1, 3, VAV
NC21-HRW	4D_FC01	26, 1, 3, VAV

DRAFT

	BUILDING 1	
Location	Equipment	Type
NC21-HRW	4D_FC02	27, 1, 3, VAV
NC21-HRW	4D_FC03	28, 1, 3, VAV
NC21-HRW	4D_FC04	32, 1, 3, VAV
NC21-HRW	4D_FC05	31, 1, 3, VAV
NC21-HRW	3A_FC01	46, 1, 3, VAV
NC21-HRW	3A_FC02	47, 1, 3, VAV
NC21-HRW	3A_FC03	68, 1, 3, VAV
NC21-HRW	3A_FC04	48, 1, 3, VAV
NC21-HRW	3A_FC05	57, 1, 3, VAV
NC21-HRW	3A_FC06	55, 1, 3, VAV
NC21-HRW	3A_FC07	56, 1, 3, VAV
NC21-HRW	3A_FC08	54, 1, 3, VAV
NC21-HRW	3A_FC09	53, 1, 3, VAV
NC21-HRW	3A_FC10	52, 1, 3, VAV
NC21-HRW	3A_FC11	51, 1, 3, VAV
NC21-HRW	3A_FC12	49, 1, 3, VAV
NC21-HRW	3A_FC13	50, 1, 3, VAV
NC21-HRW	3B_FC01	45, 1, 3, VAV
NC21-HRW	3B_FC02	44, 1, 3, VAV
NC21-HRW	3B_FC03	43, 1, 3, VAV
NC21-HRW	3B_FC04	42, 1, 3, VAV
NC21-HRW	3B_FC05	41, 1, 3, VAV
NC21-HRW	3B_FC06	38, 1, 3, VAV
NC21-HRW	3B_FC07	40, 1, 3, VAV
NC21-HRW	3B_FC08	39, 1, 3, VAV
NC21-HRW	3B_FC09	37, 1, 3, VAV
NC21-HRW	3B_FC10	36, 1, 3, VAV
NC21-HRW	3B_FC11	35, 1, 3, VAV
NC21-HRW	3B_FC12	84, 1, 3, VAV
NC21-HRW	3C_FC01	70, 1, 3, VAV
NC21-HRW	3C_FC02	69, 1, 3, VAV
NC21-HRW	3C_FC03	71, 1, 3, VAV
NC21-HRW	3C_FC04	66, 1, 3, VAV
NC21-HRW	3C_FC05	67, 1, 3, VAV
NC21-HRW	3C_FC06	65, 1, 3, VAV
NC21-HRW	3C_FC07	63, 1, 3, VAV
NC21-HRW	3C_FC08	64, 1, 3, VAV
NC21-HRW	3C_FC09	62, 1, 3, VAV
NC21-HRW	3C_FC10	61, 1, 3, VAV
NC21-HRW	3C_FC11	60, 1, 3, VAV
NC21-HRW	3C_FC12	59, 1, 3, VAV
NC21-HRW	3C_FC13	58, 1, 3, VAV
NC21-HRW	3D_FC01	85, 1, 3, VAV
NC21-HRW	3D_FC02	86, 1, 3, VAV
NC21-HRW	3D_FC03	75, 1, 3, VAV
NC21-HRW	3D_FC04	74, 1, 3, VAV

DRAFT

	BUILDING 1	
Location	Equipment	Type
NC21-HRW	3D_FC05	73, 1, 3, VAV
NC21-HRW	UNT-ACF	3, 1, 3, UNT
NC21-HRW	UNT-CHL	77, 1, 3, UNT
NC21-HRW	UNT-HOT	29, 1, 3, UNT
NC21-HRW	6A_FC01	2, 1, 3, VAV
NC21-HRW	6B_FC01	23, 1, 3, VAV
DCDR	Hotwater Dx9100 Add92	92, 1, 3, DX9100
N2OPEN	Hotwater VFD Add91	91, 1, 3, VND
DCDR	Chill Water DX9100 Add93	93, 1, 3, DX9100
N2OPEN	Chillwater VFD Add 90	90, 1, 3, VND
AD	NC21-HRW	Idle
BO	4D_FC01	Occupied Command
AI	4D_FC01	Zone Temp
AI	4D_FC01	Zone Setpoint
AOS	4D_FC01	Heating Valve Command
AOS	4D_FC01	Cooling Valve Command
BI	4D_FC01	Fan Status
BI	4D_FC01	Pan Alarm Status
CS	4D_FC01	Temp Occ.Status C.S.
BD	AH_4	Fan Coil Occupied Commad
BD	AH_4	
AI	AH_4	Preheat Temp
AOS	AH_4	Preheat Setpoint
AOS	AH_4	Preheat Valve Command
AI	AH_4	Preheat RetWtr Temp
BD	AH_4	
AI	AH_4	Outside Air Temp
AOS	AH_4	Preheat Face/Bypass
AOS	AH_4	F&B OA Sitchover Stpt
BD	AH_4	Setpoint
AI	AH_4	Discharge Air Temp
AOS	AH_4	Cooling Coil Setpoint
AOS	AH_4	Reheat Setpoint
AOS	AH_4	Cooling Valve Command
AOS	AH_4	Reheat Valve Command
BD	AH_4	
BD	AH_4	Cooling Enable OAT>56
BD	AH_4	Reheat Enable OAT<54
AI	AH_4	Cooiling RetWtr Temp
AI	AH_4	Reheat RetWtr Temp
BD	AH_4	
BO	AH_4	Supply Fan Command
BI	AH_4	Supply Airflow
BI	AH_4	Outside Air Damper Sts
BI	AH_4	Filter Status
BI	AH_4	Low Temp Alarm

DRAFT

	BUILDING 1	
Location	Equipment	Type
BI	AH_4	Supply Air Smk Detector
CS	AH_4	All Points
JCB	AH_4	AH_4OCC
BO	3C_FC05	Occupied Command
AI	3C_FC05	Zone Temp
AI	3C_FC05	Zone Setpoint
AOS	3C_FC05	Heating Valve Command
BO	3C_FC05	Fan Command
AOS	3C_FC05	Cooling Valve Command
BI	3C_FC05	Fan Status
BI	3C_FC05	Pan Alarm Status
CS	3C_FC05	Temp Occ.Status C.S.
AD	CHL_PUMP	Motor Speed
AD	CHL_PUMP	Motor Current
AOS	CHL_PUMP	VFD Output
AOS	CHL_PUMP	DP Pressure Setpoint
AI	CHL_PUMP	Attic-01
AI	CHL_PUMP	Attic-02
AI	CHL_PUMP	Floor 1 -01
AI	CHL_PUMP	Floor 1 -02
AI	CHL_PUMP	Flow Meter
BI	CHL_PUMP	Remote Local Status
BI	CHL_PUMP	Run Status
BI	CHL_PUMP	1M Contactor Status
BI	CHL_PUMP	2M Contactor Status
BI	CHL_PUMP	3M Contactor Status
BI	CHL_PUMP	4M Contactor Status
BI	CHL_PUMP	Pump 1 Status
BI	CHL_PUMP	Pump 2 Status
CS	CHL_PUMP	CS Object Chillwater VFD
BO	CHL_PUMP	Pump 1 Enable
BO	CHL_PUMP	Pump 2 Enable
BO	4C_FC07	Occupied Command
AI	4C_FC07	Zone Temp
AI	4C_FC07	Zone Setpoint
AOS	4C_FC07	Heating Valve Command
AOS	4C_FC07	Cooling Valve Command
BO	4C_FC07	Fan Command
BI	4C_FC07	Fan Status
BI	4C_FC07	Pan Alarm Status
CS	4C_FC07	Temp Occ.Status C.S.
CS	HW_PUMP	CS Object VFD
AD	HW_PUMP	Motor Speed
AD	HW_PUMP	Motor Current
BO	HW_PUMP	Remote Local Cmd
AI	HW_PUMP	Attic-01 Diff Press

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	HW_PUMP	Attic-02 Diff Press
AI	HW_PUMP	Flr1-01 Diff Press
AI	HW_PUMP	Flr1-02 Diff Press
AI	HW_PUMP	Flow Meter
BI	HW_PUMP	Remote Local Status
BI	HW_PUMP	Run Status
BI	HW_PUMP	1M Contactor Status
BI	HW_PUMP	2M Contactor Status
BI	HW_PUMP	3M Contactor Status
BI	HW_PUMP	4M Contactor Status
BI	HW_PUMP	Pump 2 Status
BI	HW_PUMP	Pump 1 Status
AOS	HW_PUMP	VFD Command
BO	HW_PUMP	Pump 1 Select
BO	HW_PUMP	Pump 2 Select
AOS	HW_PUMP	Hotwater Press Setpoint
BD	CHL_WTR	ACF Main Chill Water
AI	CHL_WTR	ACF Chill Water Supply T
AI	CHL_WTR	ACF Chill Water Return T
AOS	CHL_WTR	ACF Chil Wtr Return Stpt
BD	CHL_WTR	ACF Main Chill Water
AOS	CHL_WTR	Chill Water Return Valve
BD	CHL_WTR	Chill Water
AI	CHL_WTR	Chill Water Supply Temp
AI	CHL_WTR	Chill Water Return Temp
CS	CHL_WTR	All Points
JCB	CHL_WTR	WTR_STPT
AI	HOT_WTR	ACF Hot Water Supply
AI	HOT_WTR	ACF Hot Water Return
AD	HOT_WTR	ACF Ht Wtr Return Tem St
BD	HOT_WTR	
AOS	HOT_WTR	0=0 and 100=100 %Open
BD	HOT_WTR	
AI	HOT_WTR	Hot Water Supply
AI	HOT_WTR	Hot Water Return
CS	HOT_WTR	All Points
JCB	HOT_WTR	
BO	AH_8	Unoccupied Occupied Cmd
BD	AH_8	
AI	AH_8	Zone Temp
AI	AH_8	Zone Setpoint
AI	AH_8	Zone Humdity
AOS	AH_8	Dehumditify Setpoint
BD	AH_8	
AOS	AH_8	Cooling Valve Command
AOS	AH_8	Heating Valve Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
BD	AH_8	_____
AI	AH_8	Mixed Air Temp
AI	AH_8	Discharge Air Temp
AI	AH_8	Heating RetWtr Temp
AI	AH_8	Cooiling RetWtr Temp
BD	AH_8	
BO	AH_8	Supply Fan Command
BI	AH_8	Supply Airflow
BO	AH_8	OA Damper Command
BI	AH_8	Outside Air Damper Sts
BI	AH_8	Filter Status
BI	AH_8	Low Temp Alarm
BI	AH_8	Supply Air Smk Detector
CS	AH_8	All Points C.S.
AD	AH_8	Temperary Overide Time
JCB	AH_8	TEMPOVD
BO	AH_7	Unoccupied Occupied Cmd
BD	AH_7	__
AI	AH_7	Zone Temp
AI	AH_7	Zone Setpoint
AI	AH_7	Zone Humdity
AOS	AH_7	Dehumdication Setpoint
BD	AH_7	
AOS	AH_7	Cooling Valve Command
AOS	AH_7	Heating Valve Command
BD	AH_7	
AI	AH_7	Mixed Air Temp
AI	AH_7	Discharge Air Temp
AI	AH_7	Heating RetWtr Temp
AI	AH_7	Cooling RetWtr Temp
BD	AH_7	
BO	AH_7	Supply Fan Command
BI	AH_7	Supply Airflow
BO	AH_7	OA Damper Command
BI	AH_7	Outside Air Damper Sts
BI	AH_7	Filter Status
BI	AH_7	Low Temp Alarm
CS	AH_7	All Points C.S.
AD	AH_7	Temperary Overide Time
JCB	AH_7	TEMPOVD
BO	AH_6	Unoccupied Occupied Cmd
BD	AH_6	
AI	AH_6	Zone Temp
AI	AH_6	Zone Setpoint
AI	AH_6	Zone Humdity
AOS	AH_6	Dehumditify Setpoint

DRAFT

	BUILDING 1	
Location	Equipment	Type
BD	AH_6	
AOS	AH_6	Heating Valve Command
AOS	AH_6	Cooling Valve Command
BD	AH_6	
AI	AH_6	Mixed Air Temp
AI	AH_6	Discharge Air Temp
AI	AH_6	Heating RetWtr Temp
AI	AH_6	Cooling RetWtr Temp
BD	AH_6	
BO	AH_6	Supply Fan Command
BI	AH_6	Supply Airflow
BO	AH_6	Outside Air Dmpr Command
BI	AH_6	Outside Air Damper Sts
BI	AH_6	Filter Status
BI	AH_6	Low Temp Alarm
BI	AH_6	Supply Air Smk Detector
CS	AH_6	All Points C.S.
AD	AH_6	Temperary Overide Time
JCB	AH_6	TEMPOVD
BO	AHU_5	Unoccupied Occupied Cmd
BD	AHU_5	
AI	AHU_5	Zone Temp
AI	AHU_5	Zone Setpoint
AI	AHU_5	Zone Humdity
AOS	AHU_5	Dehumdifcation Setpoint
BD	AHU_5	
AOS	AHU_5	Heating Valve Command
AOS	AHU_5	Cooling Valve Command
BD	AHU_5	
AI	AHU_5	Mixed Air Temp
AI	AHU_5	Discharge Air Temp
AI	AHU_5	Heating RetWtr Temp
AI	AHU_5	Cooiling RetWtr Temp
BD	AHU_5	
BO	AHU_5	Supply Fan Command
BI	AHU_5	Supply Airflow
BO	AHU_5	Outside Air Dmpr Command
BI	AHU_5	Outside Air Damper Sts
BI	AHU_5	Filter Status
BI	AHU_5	Low Temp Alarm
BI	AHU_5	Supply Air Smk Detector
CS	AHU_5	All Points C.S.
AD	AHU_5	Temperary Overide Time
JCB	AHU_5	TEMPOVD
BO	AH_11	Unoccupied Occupied Cmd
BD	AH_11	

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	AH_11	Zone Temp
AI	AH_11	Zone Setpoint
BD	AH_11	
AOS	AH_11	Heating Valve Command
AOS	AH_11	Cooling Valve Command
BD	AH_11	
AI	AH_11	Mixed Air Temp
AI	AH_11	Discharge Air Temp
AI	AH_11	Heating Ret Wtr Temp
AI	AH_11	Outside Air Temp
AI	AH_11	Cooling RetWtr Temp
BD	AH_11	
BO	AH_11	Supply Fan Command
BI	AH_11	Supply Airflow
BO	AH_11	OA Damper Command
BI	AH_11	Outside Air Damper Sts
BI	AH_11	Filter Status
BI	AH_11	Low Temp Alarm
CS	AH_11	All Points C.S.
AD	AH_11	Temperary Overide Time
JCB	AH_11	TEMPOVD
BO	AH_10	Unoccupied Occupied Cmd
BD	AH_10	__
AI	AH_10	Zone Temp
AI	AH_10	Zone Setpoint
BD	AH_10	
AOS	AH_10	Heating Valve Command
AOS	AH_10	Cooling Valve Command
BD	AH_10	
AI	AH_10	Mixed Air Temp
AI	AH_10	Discharge Air Temp
AI	AH_10	Heating Ret Wtr Temp
AI	AH_10	Cooling RetWtr Temp
BD	AH_10	
BO	AH_10	Supply Fan Command
BI	AH_10	Supply Airflow
BO	AH_10	OA Damper Command
BI	AH_10	Outside Air Damper Sts
BI	AH_10	Filter Status
BI	AH_10	Low Temp Alarm
CS	AH_10	All Points C.S.
AD	AH_10	Temperary Overide Time
JCB	AH_10	TEMPOVD
BO	AH_13	Unoccupied Occupied Cmd
BD	AH_13	
AI	AH_13	Zone Temp

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	AH_13	Zone Setpoint
BD	AH_13	
AOS	AH_13	Heating Valve Command
AOS	AH_13	Cooling Valve Command
BD	AH_13	
AI	AH_13	Mixed Air Temp
AI	AH_13	Discharge Air Temp
AI	AH_13	Cooiling RetWtr Temp
AI	AH_13	Heating Ret Wtr Temp
BD	AH_13	
BO	AH_13	Supply Fan Command
BI	AH_13	Supply Airflow
BI	AH_13	Filter Status
CS	AH_13	All Points C.S.
AD	AH_13	Temperary Overide Time
JCB	AH_13	TEMPOVD
BO	AH_12	Unoccupied Occupied Cmd
BD	AH_12	
AI	AH_12	Zone Temp
AI	AH_12	Zone Setpoint
BD	AH_12	
AOS	AH_12	Heating Valve Command
AOS	AH_12	Cooling Valve Command
BD	AH_12	
AI	AH_12	Cooling RetWtr Temp
AI	AH_12	Discharge Air Temp
AI	AH_12	Mixed Air Temp
AI	AH_12	Heating Ret Wtr Temp
BD	AH_12	
BO	AH_12	Supply Fan Command
BI	AH_12	Supply Airflow
BI	AH_12	Filter Status
CS	AH_12	All Points C.S.
AD	AH_12	Temperary Overide Time
JCB	AH_12	TEMPOVD
BO	4B_FC01	Occupied Command
AI	4B_FC01	Zone Temp
AI	4B_FC01	Zone Setpoint
AOS	4B_FC01	Cooling Valve Command
BO	4B_FC01	Fan Command
BI	4B_FC01	Fan Status
BI	4B_FC01	Pan Alarm Status
CS	4B_FC01	Temp Occ.Status C.S.
BO	4A_FC01	Occupied Command
AI	4A_FC01	Zone Temp
AI	4A_FC01	Zone Setpoint

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	4A_FC01	Cooling Valve Command
BO	4A_FC01	Fan Command
BI	4A_FC01	Fan Status
BI	4A_FC01	Pan Alarm Status
CS	4A_FC01	Temp Occ.Status C.S.
BO	3B_FC11	Occupied Command
AI	3B_FC11	Zone Temp
AI	3B_FC11	Zone Setpoint
AOS	3B_FC11	Cooling Valve Command
BO	3B_FC11	Fan Command
BI	3B_FC11	Fan Status
BI	3B_FC11	Pan Alarm Status
CS	3B_FC11	Temp Occ.Status C.S.
BO	3A_FC05	Occupied Command
AI	3A_FC05	Zone Temp
AI	3A_FC05	Zone Setpoint
AOS	3A_FC05	Cooling Valve Command
BO	3A_FC05	Fan Command
BI	3A_FC05	Fan Status
BI	3A_FC05	Pan Alarm Status
CS	3A_FC05	Temp Occ.Status C.S.
BD	AH_1	Fan Coil Occupied Commad
BD	AH_1	
AI	AH_1	Preheat Temp
AOS	AH_1	Preheat Setpoint
AOS	AH_1	Preheat Valve Command
AI	AH_1	Preheat RetWtr Temp
BD	AH_1	
AI	AH_1	Outside Air Temp
AOS	AH_1	Preheat Face/Bypass
AOS	AH_1	F&B OA Sitchover Stpt
BD	AH_1	Setpoint
AI	AH_1	Discharge Air Temp
AOS	AH_1	Cooling Coil Setpoint
AOS	AH_1	Reheat Setpoint
AOS	AH_1	Cooling Valve Command
AOS	AH_1	Reheat Valve Command
BD	AH_1	
BD	AH_1	Cooling Enable OAT>56
BD	AH_1	Reheat Enable OAT<54
AI	AH_1	Cooling Ret Wtr Temp
AI	AH_1	Reheat RetWtr Temp
BD	AH_1	
BO	AH_1	Supply Fan Command
BI	AH_1	Supply Airflow
BI	AH_1	Outside Air Damper Sts

DRAFT

	BUILDING 1	
Location	Equipment	Type
BI	AH_1	Filter Status
BI	AH_1	Low Temp Alarm
BI	AH_1	Supply Air Smk Detector
CS	AH_1	All Points
JCB	AH_1	OCC-CMD
AI	AH_1	Zone Humdity Rm A304
JCB	AH_1	FCUZNHUM
BI	EF1-S	Exhaust Fan 1 Status
BO	EF1-CMD	Interlocked with AHU_11
BI	EF2-S	Exhaust Fan 2 Status
BO	EF2-CMD	Interlocked with AHU_1
BI	EF3-S	Exhaust Fan 3 Status
BO	EF3-CMD	Interlocked with AHU_2
BI	EF4-S	Exhaust Fan 4 Status
BO	EF4-CMD	Interlocked with AHU_10
BI	EF5-S	Exhaust Fan 5 Status
BO	EF5-CMD	Interlocked with AHU_3
BI	EF6-S	Exhaust Fan 6 Status
BO	EF6-CMD	Interlocked with AHU_4
BI	EF7-S	Exhaust Fan 7 Status
BO	EF7-CMD	Interlocked with AHU_3
BI	EF8-S	Exhaust Fan 8 Status
BO	EF8-CMD	Interlocked with AHU_4
BI	EF9-S	Exhaust Fan 9 Status
BO	EF9-CMD	Exhaust Fan 9 Command
BI	EF11-S	Exhaust Fan 11 Status
BO	EF11-CMD	Interlocked with AHU_4
BI	EF12-S	Exhaust Fan 12 Status
BO	EF12-CMD	Exhaust Fan 12 Command
BI	EF13-S	Exhaust Fan 13 Status
BO	EF13-CMD	Exhaust Fan 13 Command
BI	EF14-S	Exhaust Fan 14 Status
BO	EF14-CMD	Exhaust Fan 14 Command
JCB	EX_FANS	EXFANS
BO	6A_FC01	Occupied Command
AI	6A_FC01	Zone Temp
AI	6A_FC01	Zone Setpoint
AOS	6A_FC01	Heating Valve Command
AOS	6A_FC01	Cooling Valve Command
BO	6A_FC01	Fan Command
BI	6A_FC01	Fan Status
BI	6A_FC01	Pan Alarm Status
CS	6A_FC01	Temp Occ.Status C.S.
BO	6B_FC01	Occupied Command
AI	6B_FC01	Zone Temp
AI	6B_FC01	Zone Setpoint

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	6B_FC01	Heating Valve Command
AOS	6B_FC01	Cooling Valve Command
BO	6B_FC01	Fan Command
BI	6B_FC01	Fan Status
BI	6B_FC01	Pan Alarm Status
CS	6B_FC01	Temp Occ.Status C.S.
AI	DOM_HWTR	Domestic Hot Wtr Supply
AI	DOM_HWTR	Domestic Hot Wtr Return
BD	DOM_HWTR	_
AI	DOM_HWTR	City Water Temp
BD	DOM_HWTR	__
BO	DOM_HWTR	Domestic Hot Wtr Pmp S/S
BI	DOM_HWTR	Dom Hot Watr Pump Status
BO	AH_9	Unoccupied Occupied Cmd
BD	AH_9	__
AI	AH_9	Zone Temp
AI	AH_9	Zone Setpoint
AI	AH_9	Zone Humdity
AOS	AH_9	Dehumdification Setpoint
BD	AH_9	
AOS	AH_9	Heating Valve Command
AOS	AH_9	Cooling Valve Command
BD	AH_9	
AI	AH_9	Mixed Air Temp
AI	AH_9	Reheat Coil Temp
AI	AH_9	Heating Ret Wtr Temp
AI	AH_9	Cooiling RetWtr Temp
BD	AH_9	
BO	AH_9	Supply Fan Command
BI	AH_9	Supply Airflow
BO	AH_9	OA Damper Command
BI	AH_9	Outside Air Damper Sts
BI	AH_9	Filter Status
BI	AH_9	Low Temp Alarm
CS	AH_9	All Points C.S.
AD	AH_9	Temperary Overide Time
JCB	AH_9	TEMPOVD
BO	3C_FC01	Occupied Command
AI	3C_FC01	Zone Temp
AI	3C_FC01	Zone Setpoint
AOS	3C_FC01	Heating Valve Command
AOS	3C_FC01	Cooling Valve Command
BO	3C_FC01	Fan Command
BI	3C_FC01	Fan Status
BI	3C_FC01	Pan Alarm Status
CS	3C_FC01	Temp Occ.Status C.S.

DRAFT

	BUILDING 1	
Location	Equipment	Type
BO	3C_FC02	Occupied Command
AI	3C_FC02	Zone Temp
AI	3C_FC02	Zone Setpoint
AOS	3C_FC02	Heating Valve Command
AOS	3C_FC02	Cooling Valve Command
BO	3C_FC02	Fan Command
BI	3C_FC02	Fan Status
BI	3C_FC02	Pan Alarm Status
CS	3C_FC02	Temp Occ.Status C.S.
BO	3C_FC03	Occupied Command
AI	3C_FC03	Zone Temp
AI	3C_FC03	Zone Setpoint
AOS	3C_FC03	Heating Valve Command
AOS	3C_FC03	Cooling Valve Command
BO	3C_FC03	Fan Command
BI	3C_FC03	Fan Status
BI	3C_FC03	Pan Alarm Status
CS	3C_FC03	Temp Occ.Status C.S.
BO	3C_FC04	Occupied Command
AI	3C_FC04	Zone Temp
AI	3C_FC04	Zone Setpoint
AOS	3C_FC04	Heating Valve Command
AOS	3C_FC04	Cooling Valve Command
BO	3C_FC04	Fan Command
BI	3C_FC04	Fan Status
BI	3C_FC04	Pan Alarm Status
CS	3C_FC04	Temp Occ.Status C.S.
BO	3C_FC06	Occupied Command
AI	3C_FC06	Zone Temp
AI	3C_FC06	Zone Setpoint
AOS	3C_FC06	Heating Valve Command
AOS	3C_FC06	Cooling Valve Command
BO	3C_FC06	Fan Command
BI	3C_FC06	Fan Status
BI	3C_FC06	Pan Alarm Status
CS	3C_FC06	Temp Occ.Status C.S.
BO	3C_FC07	Occupied Command
AI	3C_FC07	Zone Temp
AI	3C_FC07	Zone Setpoint
AOS	3C_FC07	Heating Valve Command
AOS	3C_FC07	Cooling Valve Command
BO	3C_FC07	Fan Command
BI	3C_FC07	Fan Status
BI	3C_FC07	Pan Alarm Status
CS	3C_FC07	Temp Occ.Status C.S.
BO	3C_FC08	Occupied Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	3C_FC08	Zone Temp
AI	3C_FC08	Zone Setpoint
AOS	3C_FC08	Heating Valve Command
AOS	3C_FC08	Cooling Valve Command
BO	3C_FC08	Fan Command
BI	3C_FC08	Fan Status
BI	3C_FC08	Pan Alarm Status
CS	3C_FC08	Temp Occ.Status C.S.
BO	3C_FC09	Occupied Command
AI	3C_FC09	Zone Temp
AI	3C_FC09	Zone Setpoint
AOS	3C_FC09	Heating Valve Command
AOS	3C_FC09	Cooling Valve Command
BO	3C_FC09	Fan Command
BI	3C_FC09	Fan Status
BI	3C_FC09	Pan Alarm Status
CS	3C_FC09	Temp Occ.Status C.S.
BO	3C_FC10	Occupied Command
AI	3C_FC10	Zone Temp
AI	3C_FC10	Zone Setpoint
AOS	3C_FC10	Heating Valve Command
AOS	3C_FC10	Cooling Valve Command
BO	3C_FC10	Fan Command
BI	3C_FC10	Fan Status
BI	3C_FC10	Pan Alarm Status
CS	3C_FC10	Temp Occ.Status C.S.
BO	3C_FC11	Occupied Command
AI	3C_FC11	Zone Temp
AI	3C_FC11	Zone Setpoint
AOS	3C_FC11	Heating Valve Command
AOS	3C_FC11	Cooling Valve Command
BO	3C_FC11	Fan Command
BI	3C_FC11	Fan Status
BI	3C_FC11	Pan Alarm Status
CS	3C_FC11	Temp Occ.Status C.S.
BO	3C_FC12	Occupied Command
AI	3C_FC12	Zone Temp
AI	3C_FC12	Zone Setpoint
AOS	3C_FC12	Heating Valve Command
AOS	3C_FC12	Cooling Valve Command
BO	3C_FC12	Fan Command
BI	3C_FC12	Fan Status
BI	3C_FC12	Pan Alarm Status
CS	3C_FC12	Temp Occ.Status C.S.
BO	3C_FC13	Occupied Command
AI	3C_FC13	Zone Temp

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	3C_FC13	Zone Setpoint
AOS	3C_FC13	Heating Valve Command
AOS	3C_FC13	Cooling Valve Command
BO	3C_FC13	Fan Command
BI	3C_FC13	Fan Status
BI	3C_FC13	Pan Alarm Status
CS	3C_FC13	Temp Occ.Status C.S.
BO	4C_FC01	Occupied Command
AI	4C_FC01	Zone Temp
AI	4C_FC01	Zone Setpoint
AOS	4C_FC01	Heating Valve Command
AOS	4C_FC01	Cooling Valve Command
BO	4C_FC01	Fan Command
BI	4C_FC01	Fan Status
BI	4C_FC01	Pan Alarm Status
CS	4C_FC01	Temp Occ.Status C.S.
BO	4C_FC02	Occupied Command
AI	4C_FC02	Zone Temp
AI	4C_FC02	Zone Setpoint
AOS	4C_FC02	Heating Valve Command
AOS	4C_FC02	Cooling Valve Command
BO	4C_FC02	Fan Command
BI	4C_FC02	Fan Status
BI	4C_FC02	Pan Alarm Status
CS	4C_FC02	Temp Occ.Status C.S.
BO	4C_FC03	Occupied Command
AI	4C_FC03	Zone Temp
AI	4C_FC03	Zone Setpoint
AOS	4C_FC03	Heating Valve Command
AOS	4C_FC03	Cooling Valve Command
BO	4C_FC03	Fan Command
BI	4C_FC03	Fan Status
BI	4C_FC03	Pan Alarm Status
CS	4C_FC03	Temp Occ.Status C.S.
BO	4C_FC04	Occupied Command
AI	4C_FC04	Zone Temp
AI	4C_FC04	Zone Setpoint
AOS	4C_FC04	Heating Valve Command
AOS	4C_FC04	Cooling Valve Command
BO	4C_FC04	Fan Command
BI	4C_FC04	Fan Status
BI	4C_FC04	Pan Alarm Status
CS	4C_FC04	Temp Occ.Status C.S.
BO	4C_FC05	Occupied Command
AI	4C_FC05	Zone Temp
AI	4C_FC05	Zone Setpoint

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	4C_FC05	Heating Valve Command
AOS	4C_FC05	Cooling Valve Command
BO	4C_FC05	Fan Command
BI	4C_FC05	Fan Status
BI	4C_FC05	Pan Alarm Status
CS	4C_FC05	Temp Occ.Status C.S.
BO	4C_FC06	Occupied Command
AI	4C_FC06	Zone Temp
AI	4C_FC06	Zone Setpoint
AOS	4C_FC06	Heating Valve Command
AOS	4C_FC06	Cooling Valve Command
BO	4C_FC06	Fan Command
BI	4C_FC06	Fan Status
BI	4C_FC06	Pan Alarm Status
CS	4C_FC06	Temp Occ.Status C.S.
BO	4C_FC08	Occupied Command
AI	4C_FC08	Zone Temp
AI	4C_FC08	Zone Setpoint
AOS	4C_FC08	Heating Valve Command
AOS	4C_FC08	Cooling Valve Command
BO	4C_FC08	Fan Command
BI	4C_FC08	Fan Status
BI	4C_FC08	Pan Alarm Status
CS	4C_FC08	Temp Occ.Status C.S.
BO	4C_FC09	Occupied Command
AI	4C_FC09	Zone Temp
AI	4C_FC09	Zone Setpoint
AOS	4C_FC09	Heating Valve Command
AOS	4C_FC09	Cooling Valve Command
BO	4C_FC09	Fan Command
BI	4C_FC09	Fan Status
BI	4C_FC09	Pan Alarm Status
CS	4C_FC09	Temp Occ.Status C.S.
BO	4C_FC10	Occupied Command
AI	4C_FC10	Zone Temp
AI	4C_FC10	Zone Setpoint
AOS	4C_FC10	Heating Valve Command
AOS	4C_FC10	Cooling Valve Command
BO	4C_FC10	Fan Command
BI	4C_FC10	Fan Status
BI	4C_FC10	Pan Alarm Status
CS	4C_FC10	Temp Occ.Status C.S.
BO	4C_FC11	Occupied Command
AI	4C_FC11	Zone Temp
AI	4C_FC11	Zone Setpoint
AOS	4C_FC11	Heating Valve Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	4C_FC11	Cooling Valve Command
BO	4C_FC11	Fan Command
BI	4C_FC11	Fan Status
BI	4C_FC11	Pan Alarm Status
CS	4C_FC11	Temp Occ.Status C.S.
BO	4C_FC12	Occupied Command
AI	4C_FC12	Zone Temp
AI	4C_FC12	Zone Setpoint
AOS	4C_FC12	Heating Valve Command
AOS	4C_FC12	Cooling Valve Command
BO	4C_FC12	Fan Command
BI	4C_FC12	Fan Status
BI	4C_FC12	Pan Alarm Status
CS	4C_FC12	Temp Occ.Status C.S.
BO	4D_FC02	Occupied Command
AI	4D_FC02	Zone Temp
AI	4D_FC02	Zone Setpoint
AOS	4D_FC02	Heating Valve Command
AOS	4D_FC02	Cooling Valve Command
BO	4D_FC02	Fan Command
BI	4D_FC02	Fan Status
BI	4D_FC02	Pan Alarm Status
CS	4D_FC02	Temp Occ.Status C.S.
BO	4D_FC03	Occupied Command
AI	4D_FC03	Zone Temp
AI	4D_FC03	Zone Setpoint
AOS	4D_FC03	Heating Valve Command
AOS	4D_FC03	Cooling Valve Command
BO	4D_FC03	Fan Command
BI	4D_FC03	Fan Status
BI	4D_FC03	Pan Alarm Status
CS	4D_FC03	Temp Occ.Status C.S.
BO	4D_FC04	Occupied Command
AI	4D_FC04	Zone Temp
AI	4D_FC04	Zone Setpoint
AOS	4D_FC04	Heating Valve Command
AOS	4D_FC04	Cooling Valve Command
BO	4D_FC04	Fan Command
BI	4D_FC04	Fan Status
BI	4D_FC04	Pan Alarm Status
CS	4D_FC04	Temp Occ.Status C.S.
BO	4D_FC05	Occupied Command
AI	4D_FC05	Zone Temp
AI	4D_FC05	Zone Setpoint
AOS	4D_FC05	Heating Valve Command
AOS	4D_FC05	Cooling Valve Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
BO	4D_FC05	Fan Command
BI	4D_FC05	Fan Status
BI	4D_FC05	Pan Alarm Status
CS	4D_FC05	Temp Occ.Status C.S.
BO	3A_FC01	Occupied Command
AI	3A_FC01	Zone Temp
AI	3A_FC01	Zone Setpoint
AOS	3A_FC01	Heating Valve Command
AOS	3A_FC01	Cooling Valve Command
BO	3A_FC01	Fan Command
BI	3A_FC01	Wall unit FN STAT
BI	3A_FC01	Pan Alarm Status
CS	3A_FC01	Temp Occ.Status C.S.
BO	3A_FC02	Occupied Command
AI	3A_FC02	Zone Temp
AI	3A_FC02	Zone Setpoint
AOS	3A_FC02	Heating Valve Command
AOS	3A_FC02	Cooling Valve Command
BO	3A_FC02	Fan Command
BI	3A_FC02	Fan Status
BI	3A_FC02	Pan Alarm Status
CS	3A_FC02	Temp Occ.Status C.S.
BO	3A_FC03	Occupied Command
AI	3A_FC03	Zone Temp
AI	3A_FC03	Zone Setpoint
AOS	3A_FC03	Heating Valve Command
AOS	3A_FC03	Cooling Valve Command
BO	3A_FC03	Fan Command
BI	3A_FC03	Fan Status
BI	3A_FC03	Pan Alarm Status
CS	3A_FC03	Temp Occ.Status C.S.
BO	3A_FC04	Occupied Command
AI	3A_FC04	Zone Temp
AI	3A_FC04	Zone Setpoint
AOS	3A_FC04	Heating Valve Command
AOS	3A_FC04	Cooling Valve Command
BO	3A_FC04	Fan Command
BI	3A_FC04	Fan Status
BI	3A_FC04	Pan Alarm Status
CS	3A_FC04	Temp Occ.Status C.S.
BO	3A_FC06	Occupied Command
AI	3A_FC06	Zone Temp
AI	3A_FC06	Zone Setpoint
AOS	3A_FC06	Heating Valve Command
AOS	3A_FC06	Cooling Valve Command
BO	3A_FC06	Fan Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
BI	3A_FC06	Fan Status
BI	3A_FC06	Pan Alarm Status
CS	3A_FC06	Temp Occ.Status C.S.
BO	3A_FC07	Occupied Command
AI	3A_FC07	Zone Temp
AI	3A_FC07	Zone Setpoint
AOS	3A_FC07	Heating Valve Command
AOS	3A_FC07	Cooling Valve Command
BO	3A_FC07	Fan Command
BI	3A_FC07	Fan Status
BI	3A_FC07	Pan Alarm Status
CS	3A_FC07	Temp Occ.Status C.S.
BO	3A_FC08	Occupied Command
AI	3A_FC08	Zone Temp
AI	3A_FC08	Zone Setpoint
AOS	3A_FC08	Heating Valve Command
AOS	3A_FC08	Cooling Valve Command
BO	3A_FC08	Fan Command
BI	3A_FC08	Fan Status
BI	3A_FC08	Pan Alarm Status
CS	3A_FC08	Temp Occ.Status C.S.
BO	3A_FC09	Occupied Command
AI	3A_FC09	Zone Temp
AI	3A_FC09	Zone Setpoint
AOS	3A_FC09	Heating Valve Command
AOS	3A_FC09	Cooling Valve Command
BO	3A_FC09	Fan Command
BI	3A_FC09	Fan Status
BI	3A_FC09	Pan Alarm Status
CS	3A_FC09	Temp Occ.Status C.S.
BO	3A_FC10	Occupied Command
AI	3A_FC10	Zone Temp
AI	3A_FC10	Zone Setpoint
AOS	3A_FC10	Heating Valve Command
AOS	3A_FC10	Cooling Valve Command
BO	3A_FC10	Fan Command
BI	3A_FC10	Fan Status
BI	3A_FC10	Pan Alarm Status
CS	3A_FC10	Temp Occ.Status C.S.
BO	3A_FC11	Occupied Command
AI	3A_FC11	Zone Temp
AI	3A_FC11	Zone Setpoint
AOS	3A_FC11	Heating Valve Command
AOS	3A_FC11	Cooling Valve Command
BO	3A_FC11	Fan Command
BI	3A_FC11	Fan Status

DRAFT

	BUILDING 1	
Location	Equipment	Type
BI	3A_FC11	Pan Alarm Status
CS	3A_FC11	Temp Occ.Status C.S.
BO	3A_FC12	Occupied Command
AI	3A_FC12	Zone Temp
AI	3A_FC12	Zone Setpoint
AOS	3A_FC12	Heating Valve Command
AOS	3A_FC12	Cooling Valve Command
BO	3A_FC12	Fan Command
BI	3A_FC12	Fan Status
BI	3A_FC12	Pan Alarm Status
CS	3A_FC12	Temp Occ.Status C.S.
BO	3A_FC13	Occupied Command
AI	3A_FC13	Zone Temp
AI	3A_FC13	Zone Setpoint
AOS	3A_FC13	Heating Valve Command
AOS	3A_FC13	Cooling Valve Command
BO	3A_FC13	Fan Command
BI	3A_FC13	Fan Status
BI	3A_FC13	Pan Alarm Status
CS	3A_FC13	Temp Occ.Status C.S.
BO	3B_FC01	Occupied Command
AI	3B_FC01	Zone Temp
AI	3B_FC01	Zone Setpoint
AOS	3B_FC01	Heating Valve Command
AOS	3B_FC01	Cooling Valve Command
BO	3B_FC01	Fan Command
BI	3B_FC01	Fan Status
BI	3B_FC01	Pan Alarm Status
CS	3B_FC01	Temp Occ.Status C.S.
BO	3B_FC02	Occupied Command
AI	3B_FC02	Zone Temp
AI	3B_FC02	Zone Setpoint
AOS	3B_FC02	Heating Valve Command
AOS	3B_FC02	Cooling Valve Command
BO	3B_FC02	Fan Command
BI	3B_FC02	Fan Status
BI	3B_FC02	Pan Alarm Status
CS	3B_FC02	Temp Occ.Status C.S.
BO	3B_FC03	Occupied Command
AI	3B_FC03	Zone Temp
AI	3B_FC03	Zone Setpoint
AOS	3B_FC03	Heating Valve Command
AOS	3B_FC03	Cooling Valve Command
BO	3B_FC03	Fan Command
BI	3B_FC03	Fan Status
BI	3B_FC03	Pan Alarm Status

DRAFT

	BUILDING 1	
Location	Equipment	Type
CS	3B_FC03	Temp Occ.Status C.S.
BO	3B_FC04	Occupied Command
AI	3B_FC04	Zone Temp
AI	3B_FC04	Zone Setpoint
AOS	3B_FC04	Heating Valve Command
AOS	3B_FC04	Cooling Valve Command
BO	3B_FC04	Fan Command
BI	3B_FC04	Fan Status
BI	3B_FC04	Pan Alarm Status
CS	3B_FC04	Temp Occ.Status C.S.
BO	3B_FC05	Occupied Command
AI	3B_FC05	Zone Temp
AI	3B_FC05	Zone Setpoint
AOS	3B_FC05	Heating Valve Command
AOS	3B_FC05	Cooling Valve Command
BO	3B_FC05	Fan Command
BI	3B_FC05	Fan Status
BI	3B_FC05	Pan Alarm Status
CS	3B_FC05	Temp Occ.Status C.S.
BO	3B_FC06	Occupied Command
AI	3B_FC06	Zone Temp
AI	3B_FC06	Zone Setpoint
AOS	3B_FC06	Heating Valve Command
AOS	3B_FC06	Cooling Valve Command
BO	3B_FC06	Fan Command
BI	3B_FC06	Fan Status
BI	3B_FC06	Pan Alarm Status
CS	3B_FC06	Temp Occ.Status C.S.
BO	3B_FC07	Occupied Command
AI	3B_FC07	Zone Temp
AI	3B_FC07	Zone Setpoint
AOS	3B_FC07	Heating Valve Command
AOS	3B_FC07	Cooling Valve Command
BO	3B_FC07	Fan Command
BI	3B_FC07	Fan Status
BI	3B_FC07	Pan Alarm Status
CS	3B_FC07	Temp Occ.Status C.S.
BO	3B_FC08	Occupied Command
AI	3B_FC08	Zone Temp
AI	3B_FC08	Zone Setpoint
AOS	3B_FC08	Heating Valve Command
AOS	3B_FC08	Cooling Valve Command
BO	3B_FC08	Fan Command
BI	3B_FC08	Fan Status
BI	3B_FC08	Pan Alarm Status
CS	3B_FC08	Temp Occ.Status C.S.

DRAFT

	BUILDING 1	
Location	Equipment	Type
BO	3B_FC09	Occupied Command
AI	3B_FC09	Zone Temp
AI	3B_FC09	Zone Setpoint
AOS	3B_FC09	Heating Valve Command
AOS	3B_FC09	Cooling Valve Command
BO	3B_FC09	Fan Command
BI	3B_FC09	Fan Status
BI	3B_FC09	Pan Alarm Status
CS	3B_FC09	Temp Occ.Status C.S.
BO	3B_FC10	Occupied Command
AI	3B_FC10	Zone Temp
AI	3B_FC10	Zone Setpoint
AOS	3B_FC10	Heating Valve Command
AOS	3B_FC10	Cooling Valve Command
BO	3B_FC10	Fan Command
BI	3B_FC10	Fan Status
BI	3B_FC10	Pan Alarm Status
CS	3B_FC10	Temp Occ.Status C.S.
BO	3B_FC12	Occupied Command
AI	3B_FC12	Zone Temp
AI	3B_FC12	Zone Setpoint
AOS	3B_FC12	Heating Valve Command
AOS	3B_FC12	Cooling Valve Command
BO	3B_FC12	Fan Command
BI	3B_FC12	Fan Status
BI	3B_FC12	Pan Alarm Status
CS	3B_FC12	Temp Occ.Status C.S.
BO	3D_FC01	Occupied Command
AI	3D_FC01	Zone Temp
AI	3D_FC01	Zone Setpoint
AOS	3D_FC01	Heating Valve Command
AOS	3D_FC01	Cooling Valve Command
BO	3D_FC01	Fan Command
BI	3D_FC01	Fan Status
BI	3D_FC01	Pan Alarm Status
CS	3D_FC01	Temp Occ.Status C.S.
BO	3D_FC02	Occupied Command
AI	3D_FC02	Zone Temp
AI	3D_FC02	Zone Setpoint
AOS	3D_FC02	Heating Valve Command
AOS	3D_FC02	Cooling Valve Command
BO	3D_FC02	Fan Command
BI	3D_FC02	Fan Status
BI	3D_FC02	Pan Alarm Status
CS	3D_FC02	Temp Occ.Status C.S.
BO	3D_FC03	Occupied Command

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	3D_FC03	Zone Temp
AI	3D_FC03	Zone Setpoint
AOS	3D_FC03	Heating Valve Command
AOS	3D_FC03	Cooling Valve Command
BO	3D_FC03	Fan Command
BI	3D_FC03	Fan Status
BI	3D_FC03	Pan Alarm Status
CS	3D_FC03	Temp Occ.Status C.S.
BO	3D_FC04	Occupied Command
AI	3D_FC04	Zone Temp
AI	3D_FC04	Zone Setpoint
AOS	3D_FC04	Heating Valve Command
AOS	3D_FC04	Cooling Valve Command
BO	3D_FC04	Fan Command
BI	3D_FC04	Fan Status
BI	3D_FC04	Pan Alarm Status
CS	3D_FC04	Temp Occ.Status C.S.
BO	3D_FC05	Occupied Command
AI	3D_FC05	Zone Temp
AI	3D_FC05	Zone Setpoint
AOS	3D_FC05	Heating Valve Command
AOS	3D_FC05	Cooling Valve Command
BO	3D_FC05	Fan Command
BI	3D_FC05	Fan Status
BI	3D_FC05	Pan Alarm Status
CS	3D_FC05	Temp Occ.Status C.S.
BD	AH_3	Fan Coil Occupied Commad
BD	AH_3	__
AI	AH_3	Preheat Temp
AOS	AH_3	Preheat Setpoint
AOS	AH_3	Preheat Valve Command
AI	AH_3	Preheat RetWtr Temp
BD	AH_3	
AI	AH_3	Outside Air Temp
AOS	AH_3	Preheat Face/Bypass
AOS	AH_3	F&B OA Sitchover Stpt
BD	AH_3	Setpoint
AI	AH_3	Discharge Air Temp
AOS	AH_3	Cooling Coil Setpoint
AOS	AH_3	Reheat Setpoint
AOS	AH_3	Cooling Valve Command
AOS	AH_3	Reheat Valve Command
BD	AH_3	
BD	AH_3	Cooling Enable OAT>56
BD	AH_3	Reheat Enable OAT<54
AI	AH_3	Cooling RetWtr Temp

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	AH_3	Reheat RetWtr Temp
BD	AH_3	
BO	AH_3	Supply Fan Command
BI	AH_3	Supply Airflow
BI	AH_3	Outside Air Damper Sts
BI	AH_3	Filter Status
BI	AH_3	Low Temp Alarm
BI	AH_3	Supply Air Smk Detector
CS	AH_3	All Points
JCB	AH_3	AH_3OCC
AI	AH_3	Zone Humdity Rm C408
BD	AH_2	Fan Coil Occupied Commad
BD	AH_2	
AI	AH_2	Preheat Temp
AOS	AH_2	Preheat Setpoint
AOS	AH_2	Preheat Valve Command
AI	AH_2	Preheat RetWtr Temp
BD	AH_2	
AI	AH_2	Outside Air Temp
AOS	AH_2	Preheat Face/Bypass
AOS	AH_2	F&B OA Sitchover Stpt
BD	AH_2	Setpoint
AI	AH_2	Discharge Air Temp
AOS	AH_2	Cooling Coil Setpoint
AOS	AH_2	Reheat Setpoint
AOS	AH_2	Cooling Valve Command
AOS	AH_2	Reheat Valve Command
BD	AH_2	
BD	AH_2	Cooling Enable OAT>56
BD	AH_2	Reheat Enable OAT<54
AI	AH_2	Cooiling RetWtr Temp
AI	AH_2	Reheat RetWtr Temp
BD	AH_2	
BO	AH_2	Supply Fan Command
BI	AH_2	Supply Airflow
BI	AH_2	Outside Air Damper Sts
BI	AH_2	Filter Status
BI	AH_2	Low Temp Alarm
BI	AH_2	Supply Air Smk Detector
CS	AH_2	All Points
JCB	AH_2	AH_2OCC
AI	AH_2	Zone Humdity Rm B210
Building 2		

DRAFT

	BUILDING 1	
Location	Equipment	Type
Points	**Equipment**	**Type**
NC-1		**Network controller**
NC-1-HW	2, 1, 3, UNT	DC1-02
NC-1-HW	3, 1, 3, AHU	AHU-2102
NC-1-HW	4, 1, 3, UNT	DC1-04
NC-1-HW	5, 1, 3, UNT	DC1-05
NC-1-HW	6, 1, 3, UNT	DC1-06
NC-1-HW	7, 1, 3, UNT	DC1-07
NC-1-HW	8, 1, 3, UNT	DC1-08
NC-1-HW	92, 1, 3, AHU	AHU-2201
NC-1-HW	91, 1, 3, UNT	DC1-91
NC-1-HW	90, 1, 3, AHU	AHU-2202
NC-1-HW	89, 1, 3, UNT	DC1-89
NC-1-HW	9, 1, 3, VAV	2A-30
NC-1-HW	10, 1, 3, VAV	2A-29
NC-1-HW	11, 1, 3, VAV	2A-28
NC-1-HW	12, 1, 3, VAV	2A-27
NC-1-HW	13, 1, 3, VAV	2A-10
NC-1-HW	14, 1, 3, VAV	2A-09
NC-1-HW	15, 1, 3, VAV	2A-08
NC-1-HW	16, 1, 3, VAV	2A-07
NC-1-HW	17, 1, 3, VAV	2A-06
NC-1-HW	18, 1, 3, VAV	2A-05
NC-1-HW	19, 1, 3, VAV	2A-04
NC-1-HW	20, 1, 3, VAV	2A-03
NC-1-HW	21, 1, 3, VAV	2A-02
NC-1-HW	22, 1, 3, VAV	2A-11
NC-1-HW	23, 1, 3, VAV	2A-12
NC-1-HW	24, 1, 3, VAV	2A-13
NC-1-HW	25, 1, 3, VAV	2A-14
NC-1-HW	26, 1, 3, VAV	2A-15
NC-1-HW	27, 1, 3, VAV	2A-16
NC-1-HW	28, 1, 3, VAV	2A-01
NC-1-HW	29, 1, 3, VAV	2A-105
NC-1-HW	30, 1, 3, VAV	2A-104
NC-1-HW	31, 1, 3, VAV	2A-103
NC-1-HW	32, 1, 3, VAV	2A-102

	BUILDING 1	
Location	Equipment	Type
NC-1-HW	33, 1, 3, VAV	2A-101
NC-1-HW	34, 1, 3, VAV	2A-106
NC-1-HW	35, 1, 3, VAV	2A-107
NC-1-HW	36, 1, 3, VAV	2A-108
NC-1-HW	37, 1, 3, VAV	2A-109
NC-1-HW	38, 1, 3, VAV	2A-110
NC-1-HW	39, 1, 3, VAV	2A-111
NC-1-HW	40, 1, 3, VAV	2A-112
NC-1-HW	41, 1, 3, VAV	2A-114
NC-1-HW	42, 1, 3, VAV	2A-116
NC-1-HW	43, 1, 3, VAV	2A-118-2
NC-1-HW	44, 1, 3, VAV	2A-117
NC-1-HW	45, 1, 3, VAV	2A-115
NC-1-HW	46, 1, 3, VAV	2A-113
NC-1-HW	47, 1, 3, VAV	2A-140
NC-1-HW	48, 1, 3, VAV	2A-141
NC-1-HW	49, 1, 3, VAV	2A-142
NC-1-HW	50, 1, 3, VAV	2A-143
NC-1-HW	51, 1, 3, VAV	2A-144
NC-1-HW	52, 1, 3, VAV	2A-145
NC-1-HW	53, 1, 3, VAV	2A-138
NC-1-HW	54, 1, 3, VAV	2A-137
NC-1-HW	55, 1, 3, VAV	2A-136
NC-1-HW	56, 1, 3, VAV	2A-135
NC-1-HW	57, 1, 3, VAV	2A-131
NC-1-HW	58, 1, 3, VAV	2A-139
NC-1-HW	59, 1, 3, VAV	2A-134
NC-1-HW	60, 1, 3, VAV	2A-133
NC-1-HW	61, 1, 3, VAV	2A-132
NC-1-HW	62, 1, 3, VAV	2A-130
NC-1-HW	63, 1, 3, VAV	2A-129
NC-1-HW	64, 1, 3, VAV	2A-126
NC-1-HW	65, 1, 3, VAV	2A-125
NC-1-HW	66, 1, 3, VAV	2A-123
NC-1-HW	67, 1, 3, VAV	2A-119
NC-1-HW	68, 1, 3, VAV	2A-118
NC-1-HW	69, 1, 3, VAV	2A-120
NC-1-HW	70, 1, 3, VAV	2A-121
NC-1-HW	71, 1, 3, VAV	2A-122
NC-1-HW	72, 1, 3, VAV	2A-124

	BUILDING 1	
Location	Equipment	Type
NC-1-HW	73, 1, 3, VAV	2A-127
NC-1-HW	74, 1, 3, VAV	2A-128
NC-1-HW	75, 1, 3, VAV	2C-15
NC-1-HW	76, 1, 3, VAV	2C-14
NC-1-HW	77, 1, 3, VAV	2C-13
NC-1-HW	78, 1, 3, VAV	2C-12
NC-1-HW	79, 1, 3, VAV	2C-04
NC-1-HW	80, 1, 3, VAV	2C-03
NC-1-HW	81, 1, 3, VAV	2C-02
NC-1-HW	82, 1, 3, VAV	2C-01
NC-1-HW	83, 1, 3, VAV	2A-151
NC-1-HW	84, 1, 3, VAV	2A-150
NC-1-HW	85, 1, 3, VAV	2A-149
NC-1-HW	86, 1, 3, VAV	2A-148
NC-1-HW	87, 1, 3, VAV	2A-147
NC-1-HW	88, 1, 3, VAV	2A-146
NC-1-HW	210, 1, 3, VND	ISO-210
NC-1-HW	211, 1, 3, VND	ISO-211
NC-1-HW	100, 1, 3, UNT	CLNSTM
AI	2101	STM-P
AOS	2101	STM-STPT
AOS	2101	STM-VLV
AD	NC-1-HW	idle
AD	DAT-S	1201-DAT
AD	DAT-S	1301-DAT
AD	DAT-S	1302-DAT
AD	DAT-S	1401-DAT
AD	DAT-S	1501-DAT
AD	DAT-S	18-DAT
AD	DAT-S	2101-DAT
AD	DAT-S	2102-DAT
AD	DAT-S	2201-DAT
AD	DAT-S	2202-DAT
AD	DAT-S	2301-DAT
AD	DAT-S	2302-DAT
AD	DAT-S	2401-DAT
AD	DAT-S	2501-DAT
AD	DAT-S	2801-DAT
AD	DAT-S	2901-DAT
AD	DAT-S	3201-DAT

	BUILDING 1	
Location	Equipment	Type
AD	DAT-S	3202-DAT
AD	DAT-S	3301-DAT
AD	DAT-S	3302-DAT
AD	DAT-S	3303-DAT
AD	DAT-S	3304-DAT
AD	DAT-S	3305-DAT
AD	DAT-S	3601-DAT
AD	DAT-S	3602-DAT
AD	DAT-S	3603-DAT
AD	DAT-S	3604-DAT
AD	DAT-S	3605-DAT
AD	DAT-S	3701-DAT
AD	DAT-S	3702-DAT
AD	DAT-S	3703-DAT
AD	DAT-S	3704-DAT
AD	DAT-S	52-DAT
AD	DAT-S	5401-DAT
AD	DAT-S	5501-DAT
AD	DAT-S	58-DAT
AD	DAT-S	6301-DAT
AD	DAT-S	6302-DAT
JCB	JCB-NC01	2101-PMP
JCB	JCB-NC01	2102-PMP
JCB	JCB-NC01	2102-SMK
JCB	JCB-NC01	2101-SMK
JCB	JCB-NC01	21_01EF
JCB	JCB-NC01	22_02EF
JCB	JCB-NC01	2201-PMP
JCB	JCB-NC01	2202-PMP
JCB	JCB-NC01	22_01-TE
JCB	JCB-NC01	22_02-TE
JCB	JCB-NC01	2201-SMK
JCB	JCB-NC01	2201-OCC
JCB	JCB-NC01	2202-SMK
JCB	JCB-NC01	2202-OCC
JCB	JCB-NC01	2101AITB
JCB	JCB-NC01	2201AITB
JCB	JCB-NC01	2102AITB
JCB	JCB-NC01	2202AITB
JCB	JCB-NC01	21_02EF

	BUILDING 1	
Location	Equipment	Type
JCB	JCB-NC01	22_01EF
BD	JCB-NC01	TESTGEN
JCB	JCB-NC01	2101-OCC
JCB	JCB-NC01	2102-OCC
JCB	JCB-NC01	21_02-TE
JCB	JCB-NC01	21_01-TE
AD	HW-DP	1201-HDP
AD	HW-DP	1301-HDP
AD	HW-DP	1401-HDP
AD	HW-DP	1501-HDP
AD	HW-DP	18-HDP
AD	HW-DP	2101-HDP
AD	HW-DP	3701-HDP
AD	HW-DP	BLDG1-DP
BO	SHARE01	EF2_24-C
BI	SHARE01	EF2_24
BO	SHARE01	EF3_36-C
BI	SHARE01	EF3_36
AI	SHARE01	Bl1CW-DP
AI	SHARE01	Bl1HW-DP
BD	AHU-2201	OCC
BI	AHU-2201	SF-S
BI	AHU-2201	RF-S
AI	AHU-2201	DA-T
AD	AHU-2201	DA-STPT
AOS	AHU-2201	HTG-VLV
BD	AHU-2201	HTG-PMP
AOS	AHU-2201	CLG-VLV
AOS	AHU-2201	OA-DMPR
AI	AHU-2201	MA-T
AI	AHU-2201	RA-T
AI	AHU-2201	OA-T
BI	AHU-2201	LT-ALM
BI	AHU-2201	PURGE
BI	AHU-2201	SHTDWN
BD	AHU-2201	CLG-LOCK
BI	AHU-2201	HAND
AI	AHU-2201	RA-H
AOS	AHU-2201	HUM-VLV
AI	AHU-2201	PRE

	BUILDING 1	
Location	Equipment	Type
AI	AHU-2201	AFT
AI	AHU-2201	HWS
AI	AHU-2201	HWR
AI	AHU-2201	CWS
AI	AHU-2201	CWR
AD	AHU-2201	L-ZONE-T
AD	AHU-2201	H-ZONE-T
BO	AHU-2201	SF-C
BO	AHU-2201	RF-C
BD	AHU-2201	EF3_32
BO	AHU-2201	EF3_33-C
BI	AHU-2201	EF3_33
BD	AHU-2201	EF3_34
BD	AHU-2201	EF3_35
BD	AHU-2201	EF3_36
BD	AHU-2201	EF3_37
BD	AHU-2201	NITEPURG
CS	CS-NC-1	AHU2102
CS	CS-NC-1	AHU2201
CS	CS-NC-1	AHU2202
CS	CS-NC-1	AHU2101
CS	CS-NC-1	R-DPSTPT
AI	2A-149	Zone-T
AD	2A-149	ActHtgSP
AD	2A-149	CFM
CS	2A-149	CFM-stpt
AI	2A-149	Rm-Press
CS	2A-149	Mode
AD	2A-149	Alm-Stat
BD	2A-149	Filter-S
BD	2A-149	ALM
BD	AHU-2102	OCC
BI	AHU-2102	SF-S
BI	AHU-2102	RF-S
AI	AHU-2102	DA-T
AD	AHU-2102	DA-STPT
AOS	AHU-2102	HTG-VLV
BD	AHU-2102	HTG-PMP
AOS	AHU-2102	CLG-VLV
AOS	AHU-2102	OA-DMPR

	BUILDING 1	
Location	Equipment	Type
AI	AHU-2102	MA-T
AI	AHU-2102	RA-T
AI	AHU-2102	OA-T
BI	AHU-2102	LT-ALM
BI	AHU-2102	PURGE
BI	AHU-2102	SHTDWN
BD	AHU-2102	CLG-LOCK
BI	AHU-2102	HAND
AI	AHU-2102	RA-H
AOS	AHU-2102	HUM-VLV
AI	AHU-2102	PRE
AI	AHU-2102	AFT
AI	AHU-2102	HWS
AI	AHU-2102	HWR
AI	AHU-2102	CWS
AI	AHU-2102	CWR
AD	AHU-2102	L-ZONE-T
AD	AHU-2102	H-ZONE-T
AD	AHU-2102	A-ZONE-T
BO	AHU-2102	SF-C
BO	AHU-2102	RF-C
BO	AHU-2102	EF3_03-C
BI	AHU-2102	EF3_03
BO	AHU-2102	EF3_06-C
BI	AHU-2102	EF3_06
BO	AHU-2102	EF3_09-C
BI	AHU-2102	EF3_09
BO	AHU-2102	EF3_10-C
BI	AHU-2102	EF3_10
BO	AHU-2102	EF3_11-C
BI	AHU-2102	EF3_11
BO	AHU-2102	EF3_12-C
BI	AHU-2102	EF3_12
BO	AHU-2102	EF3_31-C
BI	AHU-2102	EF3_31
BO	AHU-2102	EF3_44-C
BI	AHU-2102	EF3_44
BD	AHU-2102	NITEPURG
BI	AHU-2102	WS-D
BD	AHU-2101	OCC

	BUILDING 1	
Location	Equipment	Type
BI	AHU-2101	SF-S
BI	AHU-2101	RF-S
AI	AHU-2101	DA-T
AD	AHU-2101	DA-STPT
AOS	AHU-2101	HTG-VLV
BD	AHU-2101	HTG-PMP
AOS	AHU-2101	CLG-VLV
AOS	AHU-2101	OA-DMPR
AI	AHU-2101	MA-T
AI	AHU-2101	RA-T
AI	AHU-2101	OA-T
BI	AHU-2101	LT-ALM
BI	AHU-2101	PURGE
BI	AHU-2101	SHTDWN
BD	AHU-2101	CLG-LOCK
BI	AHU-2101	HAND
AI	AHU-2101	RA-H
AOS	AHU-2101	HUM-VLV
AI	AHU-2101	PRE
AI	AHU-2101	AFT
AI	AHU-2101	HWS
AI	AHU-2101	HWR
AI	AHU-2101	CWS
AI	AHU-2101	CWR
AD	AHU-2101	L-ZONE-T
AD	AHU-2101	H-ZONE-T
AD	AHU-2101	A-ZONE-T
BO	AHU-2101	SF-C
BO	AHU-2101	RF-C
BI	AHU-2101	LO-STM
BI	AHU-2101	HI-STM
BO	AHU-2101	EF2_01-C
BI	AHU-2101	EF2_01
BO	AHU-2101	EF2_02-C
BI	AHU-2101	EF2_02
BD	AHU-2101	EF2_04
BD	AHU-2101	EF2_05
BD	AHU-2101	EF2_06
BD	AHU-2101	EF2_07
BD	AHU-2101	EF2_08

	BUILDING 1	
Location	Equipment	Type
BO	AHU-2101	EF2_09-C
BI	AHU-2101	EF2_09
BD	AHU-2101	EF2_22
BD	AHU-2101	EF2_31
BO	AHU-2101	EF3_63-C
BI	AHU-2101	EF3_63
BO	AHU-2101	EF3_64-C
BI	AHU-2101	EF3_64
BO	AHU-2101	EF3_65-C
BI	AHU-2101	EF3_65
AI	AHU-2101	CW-DP
AI	AHU-2101	MAU301-T
BI	AHU-2101	MAU301-S
AI	AHU-2101	MAU302-T
BI	AHU-2101	MAU302-S
AI	AHU-2101	HW-DP
AOS	AHU-2101	HWDP-VLV
BD	AHU-2101	NITEPURG
AI	2A-111	Zone-T
AD	2A-111	CFM
CS	2A-111	CFM-stpt
AI	2C-02	Zone-T
AD	2C-02	ActHtgSP
AD	2C-02	CFM
CS	2C-02	CFM-stpt
AI	2A-29	Zone-T
AD	2A-29	ActHtgSP
AD	2A-29	CFM
CS	2A-29	CFM-stpt
AI	2A-28	Zone-T
AD	2A-28	ActHtgSP
AD	2A-28	CFM
CS	2A-28	CFM-stpt
AI	2A-27	Zone-T
AD	2A-27	ActHtgSP
AD	2A-27	CFM
CS	2A-27	CFM-stpt
AI	2A-10	Zone-T
AD	2A-10	ActHtgSP
AD	2A-10	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2A-10	CFM-stpt
AI	2A-09	Zone-T
AD	2A-09	ActHtgSP
AD	2A-09	CFM
CS	2A-09	CFM-stpt
AI	2A-08	Zone-T
AD	2A-08	ActHtgSP
AD	2A-08	CFM
CS	2A-08	CFM-stpt
AI	2A-07	Zone-T
AD	2A-07	ActHtgSP
AD	2A-07	CFM
CS	2A-07	CFM-stpt
AI	2A-06	Zone-T
AD	2A-06	ActHtgSP
AD	2A-06	CFM
CS	2A-06	CFM-stpt
AI	2A-05	Zone-T
AD	2A-05	ActHtgSP
AD	2A-05	CFM
CS	2A-05	CFM-stpt
AI	2A-04	Zone-T
AD	2A-04	ActHtgSP
AD	2A-04	CFM
CS	2A-04	CFM-stpt
AI	2A-03	Zone-T
AD	2A-03	ActHtgSP
AD	2A-03	CFM
CS	2A-03	CFM-stpt
AI	2A-02	Zone-T
AD	2A-02	ActHtgSP
AD	2A-02	CFM
CS	2A-02	CFM-stpt
AI	2A-11	Zone-T
AD	2A-11	ActHtgSP
AD	2A-11	CFM
CS	2A-11	CFM-stpt
AI	2A-12	Zone-T
AD	2A-12	ActHtgSP
AD	2A-12	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2A-12	CFM-stpt
AI	2A-13	Zone-T
AD	2A-13	ActHtgSP
AD	2A-13	CFM
CS	2A-13	CFM-stpt
AI	2A-14	Zone-T
AD	2A-14	ActHtgSP
AD	2A-14	CFM
CS	2A-14	CFM-stpt
AI	2A-15	Zone-T
AD	2A-15	ActHtgSP
AD	2A-15	CFM
CS	2A-15	CFM-stpt
AI	2A-16	Zone-T
AD	2A-16	ActHtgSP
AD	2A-16	CFM
CS	2A-16	CFM-stpt
AI	2A-146	Zone-T
AD	2A-146	ActHtgSP
AD	2A-146	CFM
CS	2A-146	CFM-stpt
AI	2A-01	Zone-T
AD	2A-01	ActHtgSP
AD	2A-01	CFM
CS	2A-01	CFM-stpt
AI	2A-105	Zone-T
AD	2A-105	ActHtgSP
AD	2A-105	CFM
CS	2A-105	CFM-stpt
AI	2A-104	Zone-T
AD	2A-104	ActHtgSP
AD	2A-104	CFM
CS	2A-104	CFM-stpt
AI	2A-103	Zone-T
AD	2A-103	ActHtgSP
AD	2A-103	CFM
CS	2A-103	CFM-stpt
AI	2A-102	Zone-T
AD	2A-102	ActHtgSP
AD	2A-102	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2A-102	CFM-stpt
AI	2A-101	Zone-T
AD	2A-101	ActHtgSP
AD	2A-101	CFM
CS	2A-101	CFM-stpt
AI	2A-106	Zone-T
AD	2A-106	ActHtgSP
AD	2A-106	CFM
CS	2A-106	CFM-stpt
AI	2A-107	Zone-T
AD	2A-107	ActHtgSP
AD	2A-107	CFM
CS	2A-107	CFM-stpt
AI	2A-108	Zone-T
AD	2A-108	ActHtgSP
AD	2A-108	CFM
CS	2A-108	CFM-stpt
AI	2A-109	Zone-T
AD	2A-109	ActHtgSP
AD	2A-109	CFM
CS	2A-109	CFM-stpt
AI	2A-110	Zone-T
AD	2A-110	ActHtgSP
AD	2A-110	CFM
CS	2A-110	CFM-stpt
AI	2A-112	Zone-T
AD	2A-112	ActHtgSP
AD	2A-112	CFM
CS	2A-112	CFM-stpt
AI	2A-114	Zone-T
AD	2A-114	ActHtgSP
AD	2A-114	CFM
CS	2A-114	CFM-stpt
AI	2A-116	Zone-T
AD	2A-116	ActHtgSP
AD	2A-116	CFM
CS	2A-116	CFM-stpt
AI	2A-118-2	Zone-T
AD	2A-118-2	ActHtgSP
AD	2A-118-2	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2A-118-2	CFM-stpt
AI	2A-117	Zone-T
AD	2A-117	ActHtgSP
AD	2A-117	CFM
CS	2A-117	CFM-stpt
AI	2A-115	Zone-T
AD	2A-115	ActHtgSP
AD	2A-115	CFM
CS	2A-115	CFM-stpt
AI	2A-113	Zone-T
AD	2A-113	ActHtgSP
AD	2A-113	CFM
CS	2A-113	CFM-stpt
AI	2A-140	Zone-T
AD	2A-140	ActHtgSP
AD	2A-140	CFM
CS	2A-140	CFM-stpt
AI	2A-141	Zone-T
AD	2A-141	ActHtgSP
AD	2A-141	CFM
CS	2A-141	CFM-stpt
AI	2A-142	Zone-T
AD	2A-142	ActHtgSP
AD	2A-142	CFM
CS	2A-142	CFM-stpt
AI	2A-143	Zone-T
AD	2A-143	ActHtgSP
AD	2A-143	CFM
CS	2A-143	CFM-stpt
AI	2A-144	Zone-T
AD	2A-144	ActHtgSP
AD	2A-144	CFM
CS	2A-144	CFM-stpt
AI	2A-145	Zone-T
AD	2A-145	ActHtgSP
AD	2A-145	CFM
CS	2A-145	CFM-stpt
AI	2A-138	Zone-T
AD	2A-138	ActHtgSP
AD	2A-138	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2A-138	CFM-stpt
AI	2A-137	Zone-T
AD	2A-137	ActHtgSP
AD	2A-137	CFM
CS	2A-137	CFM-stpt
AI	2A-136	Zone-T
AD	2A-136	ActHtgSP
AD	2A-136	CFM
CS	2A-136	CFM-stpt
AI	2A-135	Zone-T
AD	2A-135	ActHtgSP
AD	2A-135	CFM
CS	2A-135	CFM-stpt
AI	2A-131	Zone-T
AD	2A-131	ActHtgSP
AD	2A-131	CFM
CS	2A-131	CFM-stpt
AI	2A-139	Zone-T
AD	2A-139	ActHtgSP
AD	2A-139	CFM
CS	2A-139	CFM-stpt
AI	2A-134	Zone-T
AD	2A-134	ActHtgSP
AD	2A-134	CFM
CS	2A-134	CFM-stpt
AI	2A-133	Zone-T
AD	2A-133	ActHtgSP
AD	2A-133	CFM
CS	2A-133	CFM-stpt
AI	2A-132	Zone-T
AD	2A-132	ActHtgSP
AD	2A-132	CFM
CS	2A-132	CFM-stpt
AI	2A-130	Zone-T
AD	2A-130	ActHtgSP
AD	2A-130	CFM
CS	2A-130	CFM-stpt
AI	2A-129	Zone-T
AD	2A-129	ActHtgSP
AD	2A-129	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2A-129	CFM-stpt
AI	2A-126	Zone-T
AD	2A-126	ActHtgSP
AD	2A-126	CFM
CS	2A-126	CFM-stpt
AI	2A-125	Zone-T
AD	2A-125	ActHtgSP
AD	2A-125	CFM
CS	2A-125	CFM-stpt
AI	2A-123	Zone-T
AD	2A-123	ActHtgSP
AD	2A-123	CFM
CS	2A-123	CFM-stpt
AI	2A-119	Zone-T
AD	2A-119	ActHtgSP
AD	2A-119	CFM
CS	2A-119	CFM-stpt
AI	2A-118	Zone-T
AD	2A-118	ActHtgSP
AD	2A-118	CFM
CS	2A-118	CFM-stpt
AI	2A-120	Zone-T
AD	2A-120	ActHtgSP
AD	2A-120	CFM
CS	2A-120	CFM-stpt
AI	2A-121	Zone-T
AD	2A-121	ActHtgSP
AD	2A-121	CFM
CS	2A-121	CFM-stpt
AI	2A-122	Zone-T
AD	2A-122	ActHtgSP
AD	2A-122	CFM
CS	2A-122	CFM-stpt
AI	2A-124	Zone-T
AD	2A-124	ActHtgSP
AD	2A-124	CFM
CS	2A-124	CFM-stpt
AI	2A-127	Zone-T
AD	2A-127	ActHtgSP
AD	2A-127	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2A-127	CFM-stpt
AI	2A-128	Zone-T
AD	2A-128	ActHtgSP
AD	2A-128	CFM
CS	2A-128	CFM-stpt
AI	2C-15	Zone-T
AD	2C-15	ActHtgSP
AD	2C-15	CFM
CS	2C-15	CFM-stpt
AI	2C-13	Zone-T
AD	2C-13	ActHtgSP
AD	2C-13	CFM
CS	2C-13	CFM-stpt
AI	2C-12	Zone-T
AD	2C-12	ActHtgSP
AD	2C-12	CFM
CS	2C-12	CFM-stpt
AI	2C-04	Zone-T
AD	2C-04	ActHtgSP
AD	2C-04	CFM
CS	2C-04	CFM-stpt
AI	2C-03	Zone-T
AD	2C-03	ActHtgSP
AD	2C-03	CFM
CS	2C-03	CFM-stpt
AI	2C-01	Zone-T
AD	2C-01	ActHtgSP
AD	2C-01	CFM
CS	2C-01	CFM-stpt
AI	2A-151	Zone-T
AD	2A-151	ActHtgSP
AD	2A-151	CFM
CS	2A-151	CFM-stpt
AI	2A-150	Zone-T
AD	2A-150	ActHtgSP
AD	2A-150	CFM
CS	2A-150	CFM-stpt
AI	2A-148	Zone-T
AD	2A-148	ActHtgSP
AD	2A-148	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2A-148	CFM-stpt
AI	2A-147	Zone-T
AD	2A-147	ActHtgSP
AD	2A-147	CFM
CS	2A-147	CFM-stpt
BD	AHU-2202	OCC
BI	AHU-2202	SF-S
BI	AHU-2202	RF-S
AI	AHU-2202	DA-T
AD	AHU-2202	DA-STPT
AOS	AHU-2202	HTG-VLV
BD	AHU-2202	HTG-PMP
AOS	AHU-2202	CLG-VLV
AOS	AHU-2202	OA-DMPR
AI	AHU-2202	MA-T
AI	AHU-2202	RA-T
AI	AHU-2202	OA-T
BI	AHU-2202	LT-ALM
BI	AHU-2202	PURGE
BI	AHU-2202	SHTDWN
BD	AHU-2202	CLG-LOCK
BI	AHU-2202	HAND
AI	AHU-2202	RA-H
AOS	AHU-2202	HUM-VLV
AI	AHU-2202	PRE
AI	AHU-2202	AFT
AI	AHU-2202	HWS
AI	AHU-2202	HWR
AI	AHU-2202	CWS
AI	AHU-2202	CWR
AD	AHU-2202	L-ZONE-T
AD	AHU-2202	H-ZONE-T
BO	AHU-2202	SF-C
BO	AHU-2202	RF-C
BD	AHU-2202	NITEPURG
BD	AHU-2202	EF4_06
BD	AHU-2202	EF4_25
AI	2C-14	Zone-T
AD	2C-14	ActHtgSP
AD	2C-14	CFM

	BUILDING 1	
Location	Equipment	Type
CS	2C-14	CFM-stpt
AI	2C-14	RM-Press
CS	2C-14	Mode
AD	2C-14	Alm-Stat
BD	2C-14	FILTER-S
AI	2A-30	Zone-T
AD	2A-30	ActHtgSP
AD	2A-30	CFM
CS	2A-30	CFM-stpt
Building 2		
Points	Equipment	Type
NC – 2		Network controller
NC-2-HW	AHU-1201	1, 1, 3, AHU
NC-2-HW	DC2-02	2, 1, 3, UNT
NC-2-HW	DC2-03	3, 1, 3, UNT
NC-2-HW	DC2-04	4, 1, 3, UNT
NC-2-HW	1A-01	68, 1, 3, VAV
NC-2-HW	1A-02	69, 1, 3, VAV
NC-2-HW	1A-03	70, 1, 3, VAV
NC-2-HW	1A-04	67, 1, 3, VAV
NC-2-HW	1A-05	66, 1, 3, VAV
NC-2-HW	1A-06	65, 1, 3, VAV
NC-2-HW	1A-07	64, 1, 3, VAV
NC-2-HW	1A-08	63, 1, 3, VAV
NC-2-HW	1A-09	62, 1, 3, VAV
NC-2-HW	1A-10	61, 1, 3, VAV
NC-2-HW	1A-11	71, 1, 3, VAV
NC-2-HW	1A-12	72, 1, 3, VAV
NC-2-HW	1A-13	73, 1, 3, VAV
NC-2-HW	1A-14	74, 1, 3, VAV
NC-2-HW	1A-15	75, 1, 3, VAV
NC-2-HW	1A-16	76, 1, 3, VAV
NC-2-HW	1A-17	77, 1, 3, VAV
NC-2-HW	1A-18	81, 1, 3, VAV
NC-2-HW	1A-19	80, 1, 3, VAV
NC-2-HW	1A-20	79, 1, 3, VAV
NC-2-HW	1A-21	78, 1, 3, VAV
NC-2-HW	1A-22	83, 1, 3, VAV

DRAFT

	BUILDING 1	
Location	Equipment	Type
NC-2-HW	1A-23A	85, 1, 3, VAV
NC-2-HW	1A-23	82, 1, 3, VAV
NC-2-HW	1A-24	84, 1, 3, VAV
NC-2-HW	1A-25	86, 1, 3, VAV
NC-2-HW	1A-26	87, 1, 3, VAV
NC-2-HW	1A-27	90, 1, 3, VAV
NC-2-HW	1A-28	89, 1, 3, VAV
NC-2-HW	1A-29	88, 1, 3, VAV
NC-2-HW	1A-30	96, 1, 3, VAV
NC-2-HW	1A-31	95, 1, 3, VAV
NC-2-HW	1A-32	94, 1, 3, VAV
NC-2-HW	1A-33	93, 1, 3, VAV
NC-2-HW	1A-34	91, 1, 3, VAV
NC-2-HW	1A-35	39, 1, 3, VAV
NC-2-HW	1A-36	40, 1, 3, VAV
NC-2-HW	1A-37	97, 1, 3, VAV
NC-2-HW	1A-101	12, 1, 3, VAV
NC-2-HW	1A-102	13, 1, 3, VAV
NC-2-HW	1A-103	14, 1, 3, VAV
NC-2-HW	1A-104	15, 1, 3, VAV
NC-2-HW	1A-105	16, 1, 3, VAV
NC-2-HW	1A-106	11, 1, 3, VAV
NC-2-HW	1A-107	10, 1, 3, VAV
NC-2-HW	1A-107A	18, 1, 3, VAV
NC-2-HW	1A-108	17, 1, 3, VAV
NC-2-HW	1A-109	9, 1, 3, VAV
NC-2-HW	1A-110	8, 1, 3, VAV
NC-2-HW	1A-112	19, 1, 3, VAV
NC-2-HW	1A-113	6, 1, 3, VAV
NC-2-HW	1A-113A	57, 1, 3, VAV
NC-2-HW	1A-114	7, 1, 3, VAV
NC-2-HW	1A-115	20, 1, 3, VAV
NC-2-HW	1A-116	21, 1, 3, VAV
NC-2-HW	1A-117	22, 1, 3, VAV
NC-2-HW	1C-03	23, 1, 3, VAV
NC-2-HW	1C-01	24, 1, 3, VAV
NC-2-HW	1C-02	25, 1, 3, VAV
NC-2-HW	1C-05	26, 1, 3, VAV
NC-2-HW	1C-06	27, 1, 3, VAV
NC-2-HW	1C-74	28, 1, 3, VAV

DRAFT

	BUILDING 1	
Location	Equipment	Type
NC-2-HW	1C-76	29, 1, 3, VAV
NC-2-HW	1C-04	30, 1, 3, VAV
NC-2-HW	1A-60	41, 1, 3, VAV
NC-2-HW	1A-122	32, 1, 3, VAV
NC-2-HW	1A-123	31, 1, 3, VAV
NC-2-HW	1A-124	50, 1, 3, VAV
NC-2-HW	1A-125	51, 1, 3, VAV
NC-2-HW	1A-126	47, 1, 3, VAV
NC-2-HW	1A-127	35, 1, 3, VAV
NC-2-HW	1A-128	34, 1, 3, VAV
NC-2-HW	1A-129	33, 1, 3, VAV
NC-2-HW	1A-130	49, 1, 3, VAV
NC-2-HW	1A-131	98, 1, 3, VAV
NC-2-HW	1A-132	52, 1, 3, VAV
NC-2-HW	1A-133	53, 1, 3, VAV
NC-2-HW	1A-134	54, 1, 3, VAV
NC-2-HW	1A-135	55, 1, 3, VAV
NC-2-HW	1A-136	36, 1, 3, VAV
NC-2-HW	1A-137	46, 1, 3, VAV
NC-2-HW	1A-138	45, 1, 3, VAV
NC-2-HW	1A-139	44, 1, 3, VAV
NC-2-HW	1A-140	37, 1, 3, VAV
NC-2-HW	1A-141	43, 1, 3, VAV
NC-2-HW	1A-142	38, 1, 3, VAV
NC-2-HW	1A-143	42, 1, 3, VAV
NC-2-HW	1A-144	56, 1, 3, VAV
NC-2-HW	DC2-58	58, 1, 3, UNT
NC-2-HW	DC2-59	59, 1, 3, UNT
NC-2-HW	DC2-60	60, 1, 3, UNT
NC-2-HW	1A-300	92, 1, 3, VAV
NC-2-HW	1A-200	200, 1, 3, VAV
NC-2-HW	DC2105	105, 1, 3, UNT
NC-2-HW	CLNSTM	100, 1, 3, UNT
NC-2-HW	PETSCAN	130, 1, 3, UNT
NC-2-HW	MIG-101	101, 1, 3, MIG
NC-2-HW	MIG-102	102, 1, 3, MIG
NC-2-HW	MIG-103	103, 1, 3, MIG
NC-2-HW	1A-104A	104, 1, 3, VAV
AI	1A-104A	ZN-T
AI	1A-104A	DA-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1A-104A	ZN-SP
BO	SHARE02	EF1_05-C
BI	SHARE02	EF1_05
BO	SHARE02	EF2_04-C
BI	SHARE02	EF2_04
BO	SHARE02	EF2_05-C
BI	SHARE02	EF2_05
BO	SHARE02	EF2_06-C
BI	SHARE02	EF2_06
BO	SHARE02	EF2_22-C
BI	SHARE02	EF2_22
BI	SHARE02	EF2_25
BI	SHARE02	EF2_26
BO	SHARE02	EF2_31-C
BI	SHARE02	EF2_31
AI	SHARE02	MAU201-T
BI	SHARE02	MAU201-S
AI	SHARE02	MAU202-T
BI	SHARE02	MAU202-S
BI	SHARE02	AIR-COMP
BI	SHARE02	VAC-PMP
AI	SHARE02	SW_North
BD	AHU-1201	OCC
BI	AHU-1201	SF-S
BI	AHU-1201	RF-S
AI	AHU-1201	DA-T
AD	AHU-1201	DA-STPT
AOS	AHU-1201	HTG-VLV
BD	AHU-1201	HTG-PMP
AOS	AHU-1201	CLG-VLV
AOS	AHU-1201	OA-DMPR
AI	AHU-1201	MA-T
AI	AHU-1201	RA-T
AI	AHU-1201	OA-T
BI	AHU-1201	LT-ALM
BI	AHU-1201	PURGE
BI	AHU-1201	SHTDWN
BI	AHU-1201	HAND
AI	AHU-1201	RA-H
AOS	AHU-1201	HUM-VLV

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	AHU-1201	PRE
AI	AHU-1201	AFT
AI	AHU-1201	HWS
AI	AHU-1201	HWR
AI	AHU-1201	CWS
AI	AHU-1201	CWR
AD	AHU-1201	L-ZONE-T
AD	AHU-1201	H-ZONE-T
AD	AHU-1201	A-ZONE-T
BO	AHU-1201	SF-C
BO	AHU-1201	RF-C
AI	AHU-1201	HW-DP
AOS	AHU-1201	HWDP-VLV
BI	AHU-1201	LO-STM
BI	AHU-1201	HI-STM
AOS	AHU-1201	HXCWS-SP
AI	AHU-1201	HXCWS-T
AI	AHU-1201	HXCWR-T
AOS	AHU-1201	V-80
BI	AHU-1201	P12_2-S
BO	AHU-1201	P12_2-C
BI	AHU-1201	P12_3-S
BO	AHU-1201	P12_3-C
BD	AHU-1201	EF2_24
BD	AHU-1201	EF5_56
BD	AHU-1201	EF5_57
BD	AHU-1201	EF6_24
BD	AHU-1201	NITEPURG
BD	AHU-1201	MESSAGE
BD	AHU-1201	CLG-LOCK
CS	CS-NC-2	R-DPTPT
CS	CS-NC-2	AHU1201
AI	PETSCAN	ZN-T
AI	PETSCAN	REM-ADJ
AI	PETSCAN	DA-T
BI	PETSCAN	FAN-ST
BI	PETSCAN	PAN-ALM
BO	PETSCAN	FAN-LOW
BO	PETSCAN	CLG-CMD
AOS	PETSCAN	CLG-STPT

DRAFT

	BUILDING 1	
Location	Equipment	Type
AOS	PETSCAN	HTG-STPT
AI	1201	STM-P
AOS	1201	STM-STPT
AOS	1201	STM-VLV
JCB	JCB-NC02	1201-PMP
JCB	JCB-NC02	1201-SMK
JCB	JCB-NC02	HX-1201
BD	JCB-NC02	OPT-ENA
AD	JCB-NC02	TEMP
AD	JCB-NC02	STPT
AD	JCB-NC02	HOWFAR
BD	JCB-NC02	SF-C
BD	JCB-NC02	OCC
JCB	JCB-NC02	12_01EF
JCB	JCB-NC02	1201AITB
JCB	JCB-NC02	1201-OCC
JCB	JCB-NC02	12_01-TE
BO	RM-NORTH	Pumps-En
BI	RM-NORTH	Pmps-Alm
BI	RM-NORTH	Pumps-St
AI	1A-27	Zone-T
AD	1A-27	CFM
CS	1A-27	CFM-stpt
AI	1A-02	Zone-T
AD	1A-02	ActHtgSP
AD	1A-02	CFM
CS	1A-02	CFM-stpt
AI	1A-03	Zone-T
AD	1A-03	ActHtgSP
AD	1A-03	CFM
CS	1A-03	CFM-stpt
AI	1A-04	Zone-T
AD	1A-04	ActHtgSP
AD	1A-04	CFM
CS	1A-04	CFM-stpt
AI	1A-05	Zone-T
AD	1A-05	ActHtgSP
AD	1A-05	CFM
CS	1A-05	CFM-stpt
AI	1A-06	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1A-06	ActHtgSP
AD	1A-06	CFM
CS	1A-06	CFM-stpt
AI	1A-07	Zone-T
AD	1A-07	ActHtgSP
AD	1A-07	CFM
CS	1A-07	CFM-stpt
AI	1A-08	Zone-T
AD	1A-08	ActHtgSP
AD	1A-08	CFM
CS	1A-08	CFM-stpt
AI	1A-09	Zone-T
AD	1A-09	ActHtgSP
AD	1A-09	CFM
CS	1A-09	CFM-stpt
AI	1A-10	Zone-T
AD	1A-10	ActHtgSP
AD	1A-10	CFM
CS	1A-10	CFM-stpt
AI	1A-11	Zone-T
AD	1A-11	ActHtgSP
AD	1A-11	CFM
CS	1A-11	CFM-stpt
AI	1A-12	Zone-T
AD	1A-12	ActHtgSP
AD	1A-12	CFM
CS	1A-12	CFM-stpt
AI	1A-14	Zone-T
AD	1A-14	ActHtgSP
AD	1A-14	CFM
CS	1A-14	CFM-stpt
AI	1A-15	Zone-T
AD	1A-15	ActHtgSP
AD	1A-15	CFM
CS	1A-15	CFM-stpt
AI	1A-16	Zone-T
AD	1A-16	ActHtgSP
AD	1A-16	CFM
CS	1A-16	CFM-stpt
AI	1A-17	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1A-17	ActHtgSP
AD	1A-17	CFM
CS	1A-17	CFM-stpt
AI	1A-18	Zone-T
AD	1A-18	ActHtgSP
AD	1A-18	CFM
CS	1A-18	CFM-stpt
AI	1A-19	Zone-T
AD	1A-19	ActHtgSP
AD	1A-19	CFM
CS	1A-19	CFM-stpt
AI	1A-20	Zone-T
AD	1A-20	ActHtgSP
AD	1A-20	CFM
CS	1A-20	CFM-stpt
AI	1A-21	Zone-T
AD	1A-21	ActHtgSP
AD	1A-21	CFM
CS	1A-21	CFM-stpt
AI	1A-22	Zone-T
AD	1A-22	ActHtgSP
AD	1A-22	CFM
CS	1A-22	CFM-stpt
AI	1A-23	Zone-T
AD	1A-23	ActHtgSP
AD	1A-23	CFM
CS	1A-23	CFM-stpt
AI	1A-23A	Zone-T
AD	1A-23A	ActHtgSP
AD	1A-23A	CFM
CS	1A-23A	CFM-stpt
AI	1A-24	Zone-T
AD	1A-24	ActHtgSP
AD	1A-24	CFM
CS	1A-24	CFM-stpt
AI	1A-25	Zone-T
AD	1A-25	ActHtgSP
AD	1A-25	CFM
CS	1A-25	CFM-stpt
AI	1A-26	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1A-26	ActHtgSP
AD	1A-26	CFM
CS	1A-26	CFM-stpt
AI	1A-28	Zone-T
AD	1A-28	ActHtgSP
AD	1A-28	CFM
CS	1A-28	CFM-stpt
AI	1A-29	Zone-T
AD	1A-29	ActHtgSP
AD	1A-29	CFM
CS	1A-29	CFM-stpt
AI	1A-30	Zone-T
AD	1A-30	ActHtgSP
AD	1A-30	CFM
CS	1A-30	CFM-stpt
AI	1A-31	Zone-T
AD	1A-31	ActHtgSP
AD	1A-31	CFM
CS	1A-31	CFM-stpt
AI	1A-32	Zone-T
AD	1A-32	ActHtgSP
AD	1A-32	CFM
CS	1A-32	CFM-stpt
AI	1A-33	Zone-T
AD	1A-33	ActHtgSP
AD	1A-33	CFM
CS	1A-33	CFM-stpt
AI	1A-34	Zone-T
AD	1A-34	ActHtgSP
AD	1A-34	CFM
CS	1A-34	CFM-stpt
AI	1A-35	Zone-T
AD	1A-35	ActHtgSP
AD	1A-35	CFM
CS	1A-35	CFM-stpt
AI	1A-36	Zone-T
AD	1A-36	ActHtgSP
AD	1A-36	CFM
CS	1A-36	CFM-stpt
AI	1A-37	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1A-37	ActHtgSP
AD	1A-37	CFM
CS	1A-37	CFM-stpt
AI	1A-60	Zone-T
AD	1A-60	ActHtgSP
AD	1A-60	CFM
CS	1A-60	CFM-stpt
AI	1A-101	Zone-T
AD	1A-101	ActHtgSP
AD	1A-101	CFM
CS	1A-101	CFM-stpt
AI	1A-102	Zone-T
AD	1A-102	ActHtgSP
AD	1A-102	CFM
CS	1A-102	CFM-stpt
AI	1A-103	Zone-T
AD	1A-103	ActHtgSP
AD	1A-103	CFM
CS	1A-103	CFM-stpt
AI	1A-104	Zone-T
AD	1A-104	ActHtgSP
AD	1A-104	CFM
CS	1A-104	CFM-stpt
AI	1A-105	Zone-T
AD	1A-105	ActHtgSP
AD	1A-105	CFM
CS	1A-105	CFM-stpt
AI	1A-106	Zone-T
AD	1A-106	ActHtgSP
AD	1A-106	CFM
CS	1A-106	CFM-stpt
AI	1A-107	Zone-T
AD	1A-107	ActHtgSP
AD	1A-107	CFM
CS	1A-107	CFM-stpt
AI	1A-107A	Zone-T
AD	1A-107A	ActHtgSP
AD	1A-107A	CFM
CS	1A-107A	CFM-stpt
AI	1A-108	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1A-108	ActHtgSP
AD	1A-108	CFM
CS	1A-108	CFM-stpt
AI	1A-109	Zone-T
AD	1A-109	ActHtgSP
AD	1A-109	CFM
CS	1A-109	CFM-stpt
AI	1A-110	Zone-T
AD	1A-110	ActHtgSP
AD	1A-110	CFM
CS	1A-110	CFM-stpt
AI	1A-112	Zone-T
AD	1A-112	ActHtgSP
AD	1A-112	CFM
CS	1A-112	CFM-stpt
AI	1A-113	Zone-T
AD	1A-113	ActHtgSP
AD	1A-113	CFM
CS	1A-113	CFM-stpt
AI	1A-113A	Zone-T
AD	1A-113A	ActHtgSP
AD	1A-113A	CFM
CS	1A-113A	CFM-stpt
AI	1A-114	Zone-T
AD	1A-114	ActHtgSP
AD	1A-114	CFM
CS	1A-114	CFM-stpt
AI	1A-115	Zone-T
AD	1A-115	ActHtgSP
AD	1A-115	CFM
CS	1A-115	CFM-stpt
AI	1A-116	Zone-T
AD	1A-116	ActHtgSP
AD	1A-116	CFM
CS	1A-116	CFM-stpt
AI	1A-117	Zone-T
AD	1A-117	ActHtgSP
AD	1A-117	CFM
CS	1A-117	CFM-stpt
AI	1A-122	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1A-122	ActHtgSP
AD	1A-122	CFM
CS	1A-122	CFM-stpt
AI	1A-123	Zone-T
AD	1A-123	ActHtgSP
AD	1A-123	CFM
CS	1A-123	CFM-stpt
AI	1A-124	Zone-T
AD	1A-124	ActHtgSP
AD	1A-124	CFM
CS	1A-124	CFM-stpt
AI	1A-125	Zone-T
AD	1A-125	ActHtgSP
AD	1A-125	CFM
CS	1A-125	CFM-stpt
AI	1A-126	Zone-T
AD	1A-126	ActHtgSP
AD	1A-126	CFM
CS	1A-126	CFM-stpt
AI	1A-127	Zone-T
AD	1A-127	ActHtgSP
AD	1A-127	CFM
CS	1A-127	CFM-stpt
AI	1A-128	Zone-T
AD	1A-128	ActHtgSP
AD	1A-128	CFM
CS	1A-128	CFM-stpt
AI	1A-129	Zone-T
AD	1A-129	ActHtgSP
AD	1A-129	CFM
CS	1A-129	CFM-stpt
AI	1A-130	Zone-T
AD	1A-130	ActHtgSP
AD	1A-130	CFM
CS	1A-130	CFM-stpt
AI	1A-131	Zone-T
AD	1A-131	ActHtgSP
AD	1A-131	CFM
CS	1A-131	CFM-stpt
AI	1A-132	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1A-132	ActHtgSP
AD	1A-132	CFM
CS	1A-132	CFM-stpt
AI	1A-133	Zone-T
AD	1A-133	ActHtgSP
AD	1A-133	CFM
CS	1A-133	CFM-stpt
AI	1A-134	Zone-T
AD	1A-134	ActHtgSP
AD	1A-134	CFM
CS	1A-134	CFM-stpt
AI	1A-135	Zone-T
AD	1A-135	ActHtgSP
AD	1A-135	CFM
CS	1A-135	CFM-stpt
AI	1A-136	Zone-T
AD	1A-136	ActHtgSP
AD	1A-136	CFM
CS	1A-136	CFM-stpt
AI	1A-137	Zone-T
AD	1A-137	ActHtgSP
AD	1A-137	CFM
CS	1A-137	CFM-stpt
AI	1A-138	Zone-T
AD	1A-138	ActHtgSP
AD	1A-138	CFM
CS	1A-138	CFM-stpt
AI	1A-139	Zone-T
AD	1A-139	ActHtgSP
AD	1A-139	CFM
CS	1A-139	CFM-stpt
AI	1A-140	Zone-T
AD	1A-140	ActHtgSP
AD	1A-140	CFM
CS	1A-140	CFM-stpt
AI	1A-141	Zone-T
AD	1A-141	ActHtgSP
AD	1A-141	CFM
CS	1A-141	CFM-stpt
AI	1A-142	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1A-142	ActHtgSP
AD	1A-142	CFM
CS	1A-142	CFM-stpt
AI	1A-143	Zone-T
AD	1A-143	ActHtgSP
AD	1A-143	CFM
CS	1A-143	CFM-stpt
AI	1A-144	Zone-T
AD	1A-144	ActHtgSP
AD	1A-144	CFM
CS	1A-144	CFM-stpt
AI	1C-03	Zone-T
AD	1C-03	ActHtgSP
AD	1C-03	CFM
CS	1C-03	CFM-stpt
AI	1C-04	Zone-T
AD	1C-04	ActHtgSP
AD	1C-04	CFM
CS	1C-04	CFM-stpt
AI	1C-76	Zone-T
AD	1C-76	ActHtgSP
AD	1C-76	CFM
CS	1C-76	CFM-stpt
AI	1C-74	Zone-T
AD	1C-74	ActHtgSP
AD	1C-74	CFM
CS	1C-74	CFM-stpt
AI	1C-06	Zone-T
AD	1C-06	ActHtgSP
AD	1C-06	CFM
CS	1C-06	CFM-stpt
AI	1C-05	Zone-T
AD	1C-05	ActHtgSP
AD	1C-05	CFM
CS	1C-05	CFM-stpt
AI	1C-02	Zone-T
AD	1C-02	ActHtgSP
AD	1C-02	CFM
CS	1C-02	CFM-stpt
AI	1C-01	Zone-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	1C-01	ActHtgSP
AD	1C-01	CFM
CS	1C-01	CFM-stpt
AI	1A-300	Zone-T
AD	1A-300	ActHtgSP
AD	1A-300	CFM
CS	1A-300	CFM-stpt
AI	1A-200	Zone-T
AD	1A-200	ActHtgSP
AD	1A-200	CFM
CS	1A-200	CFM-stpt
BD	FAN-STAT	1201-SF
BD	FAN-STAT	1201-RF
BD	FAN-STAT	1301-SF
BD	FAN-STAT	1301-RF
BD	FAN-STAT	1302-SF
BD	FAN-STAT	1302-RF
BD	FAN-STAT	1401-SF
BD	FAN-STAT	1401-RF
BD	FAN-STAT	1501-SF
BD	FAN-STAT	1501-RF
BD	FAN-STAT	1801-SF
BD	FAN-STAT	2101-SF
BD	FAN-STAT	2101-RF
BD	FAN-STAT	2102-SF
BD	FAN-STAT	2102-RF
BD	FAN-STAT	2201-SF
BD	FAN-STAT	2201-RF
BD	FAN-STAT	2202-SF
BD	FAN-STAT	2202-RF
BD	FAN-STAT	2301-SF
BD	FAN-STAT	2301-RF
BD	FAN-STAT	2302-SF
BD	FAN-STAT	2302-RF
BD	FAN-STAT	2401-SF
BD	FAN-STAT	2401-RF
BD	FAN-STAT	2501-SF
BD	FAN-STAT	2501-RF
BD	FAN-STAT	2801-SF
BD	FAN-STAT	2801-RF

DRAFT

	BUILDING 1	
Location	Equipment	Type
BD	FAN-STAT	2901-SF
BD	FAN-STAT	2901-RF
BD	FAN-STAT	3201-SF
BD	FAN-STAT	3201-RF
BD	FAN-STAT	3202-SF
BD	FAN-STAT	3202-RF
BD	FAN-STAT	3301-SF
BD	FAN-STAT	3301-RF
BD	FAN-STAT	3302-SF
BD	FAN-STAT	3302-RF
BD	FAN-STAT	3303-SF
BD	FAN-STAT	3303-RF
BD	FAN-STAT	3304-SF
BD	FAN-STAT	3304-RF
BD	FAN-STAT	3601-SF
BD	FAN-STAT	3601-RF
BD	FAN-STAT	3602-SF
BD	FAN-STAT	3602-RF
BD	FAN-STAT	3603-SF
BD	FAN-STAT	3603-RF
BD	FAN-STAT	3604-SF
BD	FAN-STAT	3604-RF
BD	FAN-STAT	3605-SF
BD	FAN-STAT	3605-RF
BD	FAN-STAT	3701-SF
BD	FAN-STAT	3701-RF
BD	FAN-STAT	3702-SF
BD	FAN-STAT	3702-RF
BD	FAN-STAT	3703-SF
BD	FAN-STAT	3703-RF
BD	FAN-STAT	3704-SF
BD	FAN-STAT	3704-RF
BD	FAN-STAT	5201-SF
BD	FAN-STAT	5201-RF
BD	FAN-STAT	5401-SF
BD	FAN-STAT	5401-RF
BD	FAN-STAT	5501-SF
BD	FAN-STAT	5501-RF
BD	FAN-STAT	5801-SF
BD	FAN-STAT	5801-RF

DRAFT

	BUILDING 1	
Location	Equipment	Type
BD	FAN-STAT	6301-SF
BD	FAN-STAT	6301-RF
BD	FAN-STAT	6302-SF
BD	FAN-STAT	6302-RF
AI	1A-01	Zone-T
AD	1A-01	ActHtgSP
AD	1A-01	CFM
CS	1A-01	CFM-stpt
BO	UNIT-1	UNIT_RUN
BI	UNIT-1	UNIT-S
AI	UNIT-1	HUM-RH
AOS	UNIT-1	HUM-SPT
AI	UNIT-1	RM-T
AOS	UNIT-1	TEMP-SPT
BI	UNIT-1	CLG-EN
BI	UNIT-1	HTG-EN
BI	UNIT-1	HUM
BI	UNIT-1	DEHUMD
BI	UNIT-1	ALM-PRES
BI	UNIT-1	HI-TEMP
BI	UNIT-1	LOW-TEMP
BI	UNIT-1	HI-HUM
BI	UNIT-1	LOW-HUM
CS	UNIT-1	CS-LIB1
BO	UNIT-2	UNIT-RUN
BI	UNIT-2	UNIT-S
AI	UNIT-2	HUM-RH
AOS	UNIT-2	HUM-SPT
AI	UNIT-2	RM-T
AOS	UNIT-2	TEMP-SPT
BI	UNIT-2	CLG-EN
BI	UNIT-2	HTG-EN
BI	UNIT-2	HUM
BI	UNIT-2	DEHUMD
BI	UNIT-2	ALM-PRES
BI	UNIT-2	HI-TEMP
BI	UNIT-2	LOW-TEMP
BI	UNIT-2	HI-HUM
BI	UNIT-2	LOW-HUM
CS	UNIT-2	CS-LIB2

DRAFT

	BUILDING 1	
Location	Equipment	Type
BO	UNIT-3	UNIT_RUN
BI	UNIT-3	UNIT-S
AI	UNIT-3	HUM-RH
AOS	UNIT-3	HUM-SPT
AI	UNIT-3	RM-T
AOS	UNIT-3	TEMP-SPT
BI	UNIT-3	CLG-EN
BI	UNIT-3	HTG-EN
BI	UNIT-3	HUM
BI	UNIT-3	DEUMD
BI	UNIT-3	ALM-PRES
BI	UNIT-3	HI-TEMP
BI	UNIT-3	LOW-TEMP
BI	UNIT-3	HI-HUM
BI	UNIT-3	LOW-HUM
CS	UNIT-3	CS-LIB3
AI	1A-13	Zone-T
AD	1A-13	CFM
AD	1A-13	ActHtgSP
CS	1A-13	CFM-stpt
Building 2		
Points	**Equipment**	**Type**
NC-3		**Network controller**
NC-3-HW	AHU-1301	113, 1, 3, AHU
NC-3-HW	DC3-114	114, 1, 3, UNT
NC-3-HW	AHU-1302	115, 1, 3, AHU
NC-3-HW	DC3-116	116, 1, 3, UNT
NC-3-HW	DC3-117	117, 1, 3, UNT
NC-3-HW	DC3-118	118, 1, 3, UNT
NC-3-HW	DC3-119	119, 1, 3, UNT
NC-3-HW	1C-33	1, 1, 3, VAV
NC-3-HW	1C-34	2, 1, 3, VAV
NC-3-HW	1C-35	3, 1, 3, VAV
NC-3-HW	1C-13	4, 1, 3, VAV
NC-3-HW	1C-12	5, 1, 3, VAV
NC-3-HW	1C-19	6, 1, 3, VAV
NC-3-HW	1C-20	7, 1, 3, VAV

DRAFT

	BUILDING 1	
Location	Equipment	Type
NC-3-HW	1C-27	8, 1, 3, VAV
NC-3-HW	1C-28	9, 1, 3, VAV
NC-3-HW	1C-29	10, 1, 3, VAV
NC-3-HW	1C-31	11, 1, 3, VAV
NC-3-HW	1C-38	12, 1, 3, VAV
NC-3-HW	1C-39	13, 1, 3, VAV
NC-3-HW	1C-08	14, 1, 3, VAV
NC-3-HW	1C-21	15, 1, 3, VAV
NC-3-HW	1C-24	16, 1, 3, VAV
NC-3-HW	1C-23	17, 1, 3, VAV
NC-3-HW	1C-09	18, 1, 3, VAV
NC-3-HW	1C-22	19, 1, 3, VAV
NC-3-HW	1C-75	20, 1, 3, VAV
NC-3-HW	1C-23A	21, 1, 3, VAV
NC-3-HW	1C-24A	22, 1, 3, VAV
NC-3-HW	1C-78	23, 1, 3, VAV
NC-3-HW	1C-25A	24, 1, 3, VAV
NC-3-HW	1C-30A	25, 1, 3, VAV
NC-3-HW	1C-31A	26, 1, 3, VAV
NC-3-HW	1C-26A	27, 1, 3, VAV
NC-3-HW	1C-32A	28, 1, 3, VAV
NC-3-HW	1C-77	29, 1, 3, VAV
NC-3-HW	1C-79	30, 1, 3, VAV
NC-3-HW	1C-33A	31, 1, 3, VAV
NC-3-HW	1C-34A	32, 1, 3, VAV
NC-3-HW	1C-35A	33, 1, 3, VAV
NC-3-HW	1C-36A	34, 1, 3, VAV
NC-3-HW	1C-38A	36, 1, 3, VAV
NC-3-HW	1C-40A	38, 1, 3, VAV
NC-3-HW	1C-27A	39, 1, 3, VAV
NC-3-HW	1C-80	40, 1, 3, VAV
NC-3-HW	1C-28A	41, 1, 3, VAV
NC-3-HW	1C-81	42, 1, 3, VAV
NC-3-HW	1C-29A	43, 1, 3, VAV
NC-3-HW	1C-82	44, 1, 3, VAV
NC-3-HW	1C-07	89, 1, 3, VAV
NC-3-HW	1C-14	90, 1, 3, VAV
NC-3-HW	1C-15	91, 1, 3, VAV
NC-3-HW	1C-16	92, 1, 3, VAV
NC-3-HW	1C-10	93, 1, 3, VAV

DRAFT

	BUILDING 1	
Location	Equipment	Type
NC-3-HW	1C-11	94, 1, 3, VAV
NC-3-HW	1C-17	95, 1, 3, VAV
NC-3-HW	1C-18	96, 1, 3, VAV
NC-3-HW	1C-26	97, 1, 3, VAV
NC-3-HW	1C-25	98, 1, 3, VAV
NC-3-HW	1C-32	99, 1, 3, VAV
NC-3-HW	1C-30	100, 1, 3, VAV
NC-3-HW	AHU1303	120, 1, 3, AHU
NC-3-HW	Zn1-RH	121, 1, 3, UNT
NC-3-HW	ZN2-RH	122, 1, 3, UNT
NC-3-HW	1303-1	123, 1, 3, UNT
NC-3-HW	LIEB-MIG	124, 1, 3, MIG
NC-3-HW	CLNSTM	50, 1, 3, UNT
BD	AHU1303	OCC
BO	AHU1303	HWRP-C
CS	AHU1303	CS-1303
BO	AHU1303	SF-C
BO	AHU1303	RF-C
BO	AHU1303	HIV-C
AOS	AHU1303	DPR-C
AOS	AHU1303	HTG-CMD
AOS	AHU1303	CLG-CMD
AOS	AHU1303	HUM-CMD
BI	AHU1303	VENT-CMD
BI	AHU1303	PURGE-C
BI	AHU1303	SHDN-CMD
BI	AHU1303	SF-S
BI	AHU1303	RF-S
BI	AHU1303	LT-ALM
BI	AHU1303	AHU-HAND
AI	AHU1303	OA-T
AI	AHU1303	MA-T
AI	AHU1303	DA-T
AI	AHU1303	OA-H
AI	AHU1303	RA-T
AI	AHU1303	RA-H
AI	AHU1303	PREFIL-P
AD	AHU1303	L-ZONE-T
AD	AHU1303	H-ZONE-T
AD	AHU1303	A-ZONE-T

DRAFT

	BUILDING 1	
Location	Equipment	Type
BD	AHU1303	NITEPURG
BD	AHU1303	----
BD	AHU1303	ZONE-1
AI	AHU1303	ZN-T
AI	AHU1303	REM-SP
AI	AHU1303	ZN1-H
BO	AHU1303	HIV1-CMD
AOS	AHU1303	RH-CMD
AOS	AHU1303	HUM-O
AOS	AHU1303	HUM1STPT
AOS	AHU1303	ZN1STPT
BD	AHU1303	--------
BD	AHU1303	ZONE2PTS
AI	AHU1303	ZN2-T
AI	AHU1303	REM-STP2
AI	AHU1303	ZN2-H
BO	AHU1303	HIV2-CMD
AOS	AHU1303	RH2-CMD
AOS	AHU1303	HUM2-CMD
AOS	AHU1303	HUM2STPT
AOS	AHU1303	ZN2STPT
BD	AHU1303	---
BD	AHU1303	WATERPTS
AI	AHU1303	HWS-T
AI	AHU1303	HWR-T
AI	AHU1303	CHS-T
AI	AHU1303	CHR-T
BI	AHU1303	ZN2-ST
BI	AHU1303	ZN1-INT
JCB	AHU1303	TMP_PRO
AI	1C-39	Zone-T
AD	1C-39	CFM
CS	1C-39	CFM-stpt
AI	1301	STM-P
AOS	1301	STM-STPT
AOS	1301	STM-VLV
CS	PACS	CS-LIEB
AD	PACS	Zn-T
AD	PACS	ZN-HUM
AD	PACS	Tmp-STPT

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	PACS	HUM-STPT
BD	PACS	HI-TEMP
BD	PACS	Lo-TMP
BD	PACS	HI-HUM
BD	PACS	LO-HUM
BD	PACS	CLG-STG
BD	PACS	HTG-STG
BD	PACS	HUMIDIFY
BD	PACS	DEHUM
BD	PACS	UNIT-RUN
BD	PACS	Water-Al
BO	PACS	UNIT-CMD
AI	1C-26A	Zone-T
AD	1C-26A	ActHtgSP
AD	1C-26A	CFM
CS	1C-26A	CFM-stpt
BI	1C-26A	WaterAla
JCB	JCB-NC03	1301-PMP
JCB	JCB-NC03	1302-PMP
JCB	JCB-NC03	13_01EF
JCB	JCB-NC03	1301-SMK
JCB	JCB-NC03	1302-SMK
JCB	JCB-NC03	HX-MRI
JCB	JCB-NC03	13_02EF
JCB	JCB-NC03	1301AITB
JCB	JCB-NC03	1302AITB
JCB	JCB-NC03	1301-OCC
JCB	JCB-NC03	1302-OCC
JCB	JCB-NC03	13_01-TE
JCB	JCB-NC03	13_02-TE
JCB	JCB-NC03	1303-SMK
JCB	JCB-NC03	1303-PMP
JCB	JCB-NC03	1303-OCC
AD	OP-ROOMS	ZONE-1
AD	OP-ROOMS	ZONE-2
AD	OP-ROOMS	ZONE-3
AD	OP-ROOMS	ZONE-4
AD	OP-ROOMS	ZONE-5
AD	OP-ROOMS	ZONE-6
AD	OP-ROOMS	ZONE-7

DRAFT

	BUILDING 1	
Location	Equipment	Type
AD	OP-ROOMS	ZONE-8
AD	OP-ROOMS	ZONE-9
AD	OP-ROOMS	ZONE-10
AD	OP-ROOMS	ZONE-11
AD	OP-ROOMS	ZONE-12
AD	OP-ROOMS	ZONE-13
AD	OP-ROOMS	ZONE-14
AD	OP-ROOMS	ZONE-15
AD	OP-ROOMS	ZONE-16
AD	OP-ROOMS	ZONE-17
CS	CS-NC-3	AHU1301
CS	CS-NC-3	AHU1302
CS	CS-NC-3	R-DPSTPT
AI	1C-15	Zone-T
AD	1C-15	CFM
CS	1C-15	CFM-stpt
BD	AHU-1301	OCC
BI	AHU-1301	SF-S
BI	AHU-1301	RF-S
AI	AHU-1301	DA-T
AD	AHU-1301	DA-STPT
AOS	AHU-1301	HTG-VLV
BD	AHU-1301	HTG-PMP
AOS	AHU-1301	CLG-VLV
AOS	AHU-1301	OA-DMPR
AI	AHU-1301	MA-T
AI	AHU-1301	RA-T
AI	AHU-1301	OA-T
BI	AHU-1301	LT-ALM
BI	AHU-1301	PURGE
BI	AHU-1301	SHTDWN
BD	AHU-1301	CLG-LOCK
BI	AHU-1301	HAND
AI	AHU-1301	RA-H
AOS	AHU-1301	HUM-VLV
AI	AHU-1301	PRE
AI	AHU-1301	AFT
AI	AHU-1301	HWS
AI	AHU-1301	HWR
AI	AHU-1301	CWS

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	AHU-1301	CWR
AD	AHU-1301	L-ZONE-T
AD	AHU-1301	H-ZONE-T
AD	AHU-1301	A-ZONE-T
BO	AHU-1301	SF-C
BO	AHU-1301	RF-C
AI	AHU-1301	HW-DP
AOS	AHU-1301	HWDP-VLV
AI	AHU-1301	HXCWS-T
AI	AHU-1301	HXCWR-T
BI	AHU-1301	P13_3-S
BO	AHU-1301	P13_3-C
BI	AHU-1301	P13_4-S
BO	AHU-1301	P13_4-C
AOS	AHU-1301	HX_VLV
BI	AHU-1301	LO-STM
BI	AHU-1301	HI-STM
BO	AHU-1301	EF1_01-C
BI	AHU-1301	EF1_01
BD	AHU-1301	EF1_05
BD	AHU-1301	EF3_68
BD	AHU-1301	EF3_69
BD	AHU-1301	EF5_55
BD	AHU-1301	EF7_10
BD	AHU-1301	NITEPURG
BD	AHU-1302	OCC
BI	AHU-1302	SF-S
BI	AHU-1302	RF-S
AI	AHU-1302	DA-T
AD	AHU-1302	DA-STPT
AOS	AHU-1302	HTG-VLV
BD	AHU-1302	HTG-PMP
AOS	AHU-1302	CLG-VLV
AOS	AHU-1302	OA-DMPR
AI	AHU-1302	MA-T
AI	AHU-1302	RA-T
AI	AHU-1302	OA-T
BI	AHU-1302	LT-ALM
BI	AHU-1302	PURGE
BI	AHU-1302	SHTDWN

DRAFT

	BUILDING 1	
Location	Equipment	Type
BD	AHU-1302	CLG-LOCK
BI	AHU-1302	HAND
AI	AHU-1302	RA-H
AOS	AHU-1302	HUM-VLV
AI	AHU-1302	PRE
AI	AHU-1302	AFT
AI	AHU-1302	HWS
AI	AHU-1302	HWR
AI	AHU-1302	CWS
AI	AHU-1302	CWR
AD	AHU-1302	L-ZONE-T
AD	AHU-1302	H-ZONE-T
AD	AHU-1302	A-ZONE-T
BO	AHU-1302	SF-C
BO	AHU-1302	RF-C
BO	AHU-1302	EF1_02-C
BI	AHU-1302	EF1_02
BO	AHU-1302	EF1_03-C
BI	AHU-1302	EF1_03
BO	AHU-1302	EF1_04-C
BI	AHU-1302	EF1_04
BD	AHU-1302	EF3_70
BD	AHU-1302	EF7_09
BD	AHU-1302	EF7_11
BD	AHU-1302	EF7_12
BD	AHU-1302	NITEPURG
AI	1C-81	Zone-T
AD	1C-81	CFM
CS	1C-81	CFM-stpt
AI	1C-38	Zone-T
AD	1C-38	CFM
CS	1C-38	CFM-stpt
AI	1C-07	Zone-T
AD	1C-07	ActHtgSP
AD	1C-07	CFM
CS	1C-07	CFM-stpt
AI	1C-08	Zone-T
AD	1C-08	ActHtgSP
AD	1C-08	CFM
CS	1C-08	CFM-stpt

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1C-09	Zone-T
AD	1C-09	ActHtgSP
AD	1C-09	CFM
CS	1C-09	CFM-stpt
AI	1C-10	Zone-T
AD	1C-10	ActHtgSP
AD	1C-10	CFM
CS	1C-10	CFM-stpt
AI	1C-11	Zone-T
AD	1C-11	ActHtgSP
AD	1C-11	CFM
CS	1C-11	CFM-stpt
AI	1C-12	Zone-T
AD	1C-12	ActHtgSP
AD	1C-12	CFM
CS	1C-12	CFM-stpt
AI	1C-13	Zone-T
AD	1C-13	ActHtgSP
AD	1C-13	CFM
CS	1C-13	CFM-stpt
AI	1C-14	Zone-T
AD	1C-14	ActHtgSP
AD	1C-14	CFM
CS	1C-14	CFM-stpt
AI	1C-16	Zone-T
AD	1C-16	ActHtgSP
AD	1C-16	CFM
CS	1C-16	CFM-stpt
AI	1C-17	Zone-T
AD	1C-17	ActHtgSP
AD	1C-17	CFM
CS	1C-17	CFM-stpt
AI	1C-18	Zone-T
AD	1C-18	ActHtgSP
AD	1C-18	CFM
CS	1C-18	CFM-stpt
AI	1C-19	Zone-T
AD	1C-19	ActHtgSP
AD	1C-19	CFM
CS	1C-19	CFM-stpt

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1C-20	Zone-T
AD	1C-20	ActHtgSP
AD	1C-20	CFM
CS	1C-20	CFM-stpt
AI	1C-21	Zone-T
AD	1C-21	ActHtgSP
AD	1C-21	CFM
CS	1C-21	CFM-stpt
AI	1C-22	Zone-T
AD	1C-22	ActHtgSP
AD	1C-22	CFM
CS	1C-22	CFM-stpt
AI	1C-23	Zone-T
AD	1C-23	ActHtgSP
AD	1C-23	CFM
CS	1C-23	CFM-stpt
AI	1C-24	Zone-T
AD	1C-24	ActHtgSP
AD	1C-24	CFM
CS	1C-24	CFM-stpt
AI	1C-25	Zone-T
AD	1C-25	ActHtgSP
AD	1C-25	CFM
CS	1C-25	CFM-stpt
AI	1C-26	Zone-T
AD	1C-26	ActHtgSP
AD	1C-26	CFM
CS	1C-26	CFM-stpt
AI	1C-27	Zone-T
AD	1C-27	ActHtgSP
AD	1C-27	CFM
CS	1C-27	CFM-stpt
AI	1C-28	Zone-T
AD	1C-28	ActHtgSP
AD	1C-28	CFM
CS	1C-28	CFM-stpt
AI	1C-29	Zone-T
AD	1C-29	ActHtgSP
AD	1C-29	CFM
CS	1C-29	CFM-stpt

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1C-30	Zone-T
AD	1C-30	ActHtgSP
AD	1C-30	CFM
CS	1C-30	CFM-stpt
AI	1C-31	Zone-T
AD	1C-31	ActHtgSP
AD	1C-31	CFM
CS	1C-31	CFM-stpt
AI	1C-32	Zone-T
AD	1C-32	ActHtgSP
AD	1C-32	CFM
CS	1C-32	CFM-stpt
AI	1C-33	Zone-T
AD	1C-33	ActHtgSP
AD	1C-33	CFM
CS	1C-33	CFM-stpt
AI	1C-34	Zone-T
AD	1C-34	ActHtgSP
AD	1C-34	CFM
CS	1C-34	CFM-stpt
AI	1C-35	Zone-T
AD	1C-35	ActHtgSP
AD	1C-35	CFM
CS	1C-35	CFM-stpt
AI	1C-23A	Zone-T
AD	1C-23A	ActHtgSP
AD	1C-23A	CFM
CS	1C-23A	CFM-stpt
AI	1C-24A	Zone-T
AD	1C-24A	ActHtgSP
AD	1C-24A	CFM
CS	1C-24A	CFM-stpt
AI	1C-25A	Zone-T
AD	1C-25A	ActHtgSP
AD	1C-25A	CFM
CS	1C-25A	CFM-stpt
AI	1C-27A	Zone-T
AD	1C-27A	ActHtgSP
AD	1C-27A	CFM
CS	1C-27A	CFM-stpt

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1C-28A	Zone-T
AD	1C-28A	ActHtgSP
AD	1C-28A	CFM
CS	1C-28A	CFM-stpt
AI	1C-29A	Zone-T
AD	1C-29A	ActHtgSP
AD	1C-29A	CFM
CS	1C-29A	CFM-stpt
AI	1C-30A	Zone-T
AD	1C-30A	ActHtgSP
AD	1C-30A	CFM
CS	1C-30A	CFM-stpt
AI	1C-31A	Zone-T
AD	1C-31A	ActHtgSP
AD	1C-31A	CFM
CS	1C-31A	CFM-stpt
AI	1C-32A	Zone-T
AD	1C-32A	ActHtgSP
AD	1C-32A	CFM
CS	1C-32A	CFM-stpt
AI	1C-33A	Zone-T
AD	1C-33A	ActHtgSP
AD	1C-33A	CFM
CS	1C-33A	CFM-stpt
AI	1C-34A	Zone-T
AD	1C-34A	ActHtgSP
AD	1C-34A	CFM
CS	1C-34A	CFM-stpt
AI	1C-35A	Zone-T
AD	1C-35A	ActHtgSP
AD	1C-35A	CFM
CS	1C-35A	CFM-stpt
AI	1C-36A	Zone-T
AD	1C-36A	ActHtgSP
AD	1C-36A	CFM
CS	1C-36A	CFM-stpt
AI	1C-38A	Zone-T
AD	1C-38A	ActHtgSP
AD	1C-38A	CFM
CS	1C-38A	CFM-stpt

DRAFT

	BUILDING 1	
Location	Equipment	Type
AI	1C-40A	Zone-T
AD	1C-40A	ActHtgSP
AD	1C-40A	CFM
CS	1C-40A	CFM-stpt
AI	1C-75	Zone-T
AD	1C-75	ActHtgSP
AD	1C-75	CFM
CS	1C-75	CFM-stpt
AI	1C-77	Zone-T
AD	1C-77	ActHtgSP
AD	1C-77	CFM
CS	1C-77	CFM-stpt
AI	1C-78	Zone-T
AD	1C-78	ActHtgSP
AD	1C-78	CFM
CS	1C-78	CFM-stpt
AI	1C-79	Zone-T
AD	1C-79	ActHtgSP
AD	1C-79	CFM
CS	1C-79	CFM-stpt
AI	1C-80	Zone-T
AD	1C-80	ActHtgSP
AD	1C-80	CFM
CS	1C-80	CFM-stpt
AI	1C-82	Zone-T
AD	1C-82	ActHtgSP
AD	1C-82	CFM
CS	1C-82	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
	NC-4	**Network Controller**
NC-4-HW	AHU-1401	114, 1, 3, AHU
NC-4-HW	DC4-115	115, 1, 3, UNT
NC-4-HW	DC4-116	116, 1, 3, UNT
NC-4-HW	DC4-117	117, 1, 3, UNT
NC-4-HW	dc4-120	120, 1, 3, UNT
NC-4-HW	DC4-121	121, 1, 3, UNT
NC-4-HW	DC4-122	122, 1, 3, UNT
NC-4-HW	DC4-123	123, 1, 3, UNT
NC-4-HW	CVR-01	1, 1, 3, VAV
NC-4-HW	CVR-02	2, 1, 3, VAV
NC-4-HW	CVR-03	3, 1, 3, VAV
NC-4-HW	CVR-04	4, 1, 3, VAV
NC-4-HW	CVR-05	5, 1, 3, VAV
NC-4-HW	CVR-06	6, 1, 3, VAV
NC-4-HW	CVR-08	8, 1, 3, VAV
NC-4-HW	CVR-09	9, 1, 3, VAV
NC-4-HW	CVR-10	10, 1, 3, VAV
NC-4-HW	CVR-11	11, 1, 3, VAV
NC-4-HW	CVR-12	12, 1, 3, VAV
NC-4-HW	CVR-13	13, 1, 3, VAV
NC-4-HW	CVR-14	14, 1, 3, VAV
NC-4-HW	CVR-15	15, 1, 3, VAV
NC-4-HW	CVR-16	16, 1, 3, VAV
NC-4-HW	CVR-17	17, 1, 3, VAV
NC-4-HW	CVR-18	18, 1, 3, VAV
NC-4-HW	CVR-19	19, 1, 3, VAV
NC-4-HW	CVR-20	20, 1, 3, VAV
NC-4-HW	CVR-21	21, 1, 3, VAV
NC-4-HW	CVR-22	22, 1, 3, VAV
NC-4-HW	CVR-23	23, 1, 3, VAV
NC-4-HW	CVR-24	24, 1, 3, VAV
NC-4-HW	CVR-25	25, 1, 3, VAV
NC-4-HW	CVR-26	26, 1, 3, VAV
NC-4-HW	CVR-27	27, 1, 3, VAV
NC-4-HW	CVR-28	28, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-4-HW	CVR-29	29, 1, 3, VAV
NC-4-HW	CVR-30	30, 1, 3, VAV
NC-4-HW	CVR-31	31, 1, 3, VAV
NC-4-HW	CVR-32	32, 1, 3, VAV
NC-4-HW	CVR-33	33, 1, 3, VAV
NC-4-HW	CVR-34	34, 1, 3, VAV
NC-4-HW	CVR-35	35, 1, 3, VAV
NC-4-HW	CVR-36	36, 1, 3, VAV
NC-4-HW	CVR-37	37, 1, 3, VAV
NC-4-HW	CVR-38	38, 1, 3, VAV
NC-4-HW	CVR-39	39, 1, 3, VAV
NC-4-HW	CVR-40	40, 1, 3, VAV
NC-4-HW	CVR-41	41, 1, 3, VAV
NC-4-HW	CVR-42	42, 1, 3, VAV
NC-4-HW	CVR-43	43, 1, 3, VAV
NC-4-HW	CVR-44	44, 1, 3, VAV
NC-4-HW	CVR-45	45, 1, 3, VAV
NC-4-HW	CVR-46	46, 1, 3, VAV
NC-4-HW	CVR-47	47, 1, 3, VAV
NC-4-HW	CVR-48	48, 1, 3, VAV
NC-4-HW	CVR-49	49, 1, 3, VAV
NC-4-HW	CVR-50	50, 1, 3, VAV
NC-4-HW	CVR-51	51, 1, 3, VAV
NC-4-HW	CVR-52	52, 1, 3, VAV
NC-4-HW	CVR-53	53, 1, 3, VAV
NC-4-HW	CVR-54	54, 1, 3, VAV
NC-4-HW	CVR-55	55, 1, 3, VAV
NC-4-HW	CVR-56	56, 1, 3, VAV
NC-4-HW	CVR-57	57, 1, 3, VAV
NC-4-HW	CVR-58	58, 1, 3, VAV
NC-4-HW	CVR-59	59, 1, 3, VAV
NC-4-HW	CVR-60	60, 1, 3, VAV
NC-4-HW	CVR-61	61, 1, 3, VAV
NC-4-HW	DC4-62	62, 1, 3, UNT
NC-4-HW	CVR-99	99, 1, 3, VAV
NC-4-HW	CVR-132	132, 1, 3, VAV
NC-4-HW	CVR-142	142, 1, 3, VAV
NC-4-HW	CVR-200	200, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-4-HW	CVR-201	201, 1, 3, VAV
NC-4-HW	CVR-202	202, 1, 3, VAV
NC-4-HW	CVR-255	255, 1, 3, VAV
NC-4-HW	DC4-124	124, 1, 3, UNT
NC-4-HW	ISO-118	118, 1, 3, VND
NC-4-HW	CLNSTM70	70, 1, 3, UNT
NC-4-HW	TEL1LIEB	162, 1, 3, MIG
NC-4-HW	TEL2LIEB	163, 1, 3, MIG
NC-4-HW	DC4-75	75, 1, 3, UNT
NC-4-HW	DC4-125	125, 1, 3, UNT
AD	TELE_RM	1E-201-T
BI	TELE_RM	LIB1-ALM
BI	TELE_RM	LIB2-ALM
BD	TELE_RM	SWOP
BO	TELE_RM	LIB1-C
BO	TELE_RM	LIB2-C
BI	TELE_RM	HP-A-S
BI	TELE_RM	HP-B-S
BI	TELE_RM	WTR-PNL
BO	TELE_RM	Lib1-Opn
BO	TELE_RM	Lib1-Cls
BO	TELE_RM	Lib2-Opn
BO	TELE_RM	Lib2-Cls
CS	LIEB-2	LIEB2CS
BD	LIEB-2	UNIT-RUN
AD	LIEB-2	Zn-T
AD	LIEB-2	TMP-STPT
AD	LIEB-2	ZN-HUM
AD	LIEB-2	HUM-STPT
BD	LIEB-2	CLG
BD	LIEB-2	HUM
BD	LIEB-2	DEHM
BD	LIEB-2	ALM-PRES
BD	LIEB-2	AIR-FLOW
BD	LIEB-2	CHNG-FLT
BD	LIEB-2	HI-TEMP
BD	LIEB-2	LOW-TEMP
BD	LIEB-2	HI-HUM

DRAFT

Building 2		
Points	Equipment	Type
BD	LIEB-2	LOW-HUM
CS	LIEB-1	LIEB1CS
BD	LIEB-1	UNIT-RUN
AD	LIEB-1	Zn-T
AD	LIEB-1	TMP-STPT
AD	LIEB-1	ZN-HUM
AD	LIEB-1	HUM-STPT
BD	LIEB-1	CLG
BD	LIEB-1	HUM
BD	LIEB-1	DEHUM
BD	LIEB-1	ALM-PRES
BD	LIEB-1	AIR-FLOW
BD	LIEB-1	CHNG-FLT
BD	LIEB-1	HI-TEMP
BD	LIEB-1	LOW-TEMP
BD	LIEB-1	HI-HUM
BD	LIEB-1	LOW-HUM
BO	RM-SOUTH	Pump-En
BI	RM-SOUTH	Pmp-Alm
BI	RM-SOUTH	Pmps-St
AI	1E-46	Zone-T
AD	1E-46	ActHtgSP
AD	1E-46	CFM
CS	1E-46	CFM-stpt
AI	1E-46	RM-PRESS
CS	1E-46	MODE
BD	1E-46	ALM
BD	1E-46	EF7_14
AI	1E-01	Zone-T
AD	1E-01	ActHtgSP
AD	1E-01	CFM
CS	1E-01	CFM-stpt
AI	1E-02	Zone-T
AD	1E-02	ActHtgSP
AD	1E-02	CFM
CS	1E-02	CFM-stpt
AI	1E-03	Zone-T
AD	1E-03	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1E-03	CFM
CS	1E-03	CFM-stpt
AI	1E-04	Zone-T
AD	1E-04	ActHtgSP
AD	1E-04	CFM
CS	1E-04	CFM-stpt
AI	1E-05	Zone-T
AD	1E-05	ActHtgSP
AD	1E-05	CFM
CS	1E-05	CFM-stpt
AI	1E-06	Zone-T
AD	1E-06	ActHtgSP
AD	1E-06	CFM
CS	1E-06	CFM-stpt
AI	1E-08	Zone-T
AD	1E-08	ActHtgSP
AD	1E-08	CFM
CS	1E-08	CFM-stpt
AI	1E-09	Zone-T
AD	1E-09	ActHtgSP
AD	1E-09	CFM
CS	1E-09	CFM-stpt
AI	1E-10	Zone-T
AD	1E-10	ActHtgSP
AD	1E-10	CFM
CS	1E-10	CFM-stpt
AI	1E-11	Zone-T
AD	1E-11	ActHtgSP
AD	1E-11	CFM
CS	1E-11	CFM-stpt
AI	1E-12	Zone-T
AD	1E-12	ActHtgSP
AD	1E-12	CFM
CS	1E-12	CFM-stpt
AI	1E-13	Zone-T
AD	1E-13	ActHtgSP
AD	1E-13	CFM
CS	1E-13	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1E-14	Zone-T
AD	1E-14	ActHtgSP
AD	1E-14	CFM
CS	1E-14	CFM-stpt
AI	1E-15	Zone-T
AD	1E-15	ActHtgSP
AD	1E-15	CFM
CS	1E-15	CFM-stpt
AI	1E-16	Zone-T
AD	1E-16	ActHtgSP
AD	1E-16	CFM
CS	1E-16	CFM-stpt
AI	1E-17	Zone-T
AD	1E-17	ActHtgSP
AD	1E-17	CFM
CS	1E-17	CFM-stpt
AI	1E-18	Zone-T
AD	1E-18	ActHtgSP
AD	1E-18	CFM
CS	1E-18	CFM-stpt
AI	1E-19	Zone-T
AD	1E-19	ActHtgSP
AD	1E-19	CFM
CS	1E-19	CFM-stpt
AI	1E-20	Zone-T
AD	1E-20	ActHtgSP
AD	1E-20	CFM
CS	1E-20	CFM-stpt
AI	1E-21	Zone-T
AD	1E-21	ActHtgSP
AD	1E-21	CFM
CS	1E-21	CFM-stpt
AI	1E-22	Zone-T
AD	1E-22	ActHtgSP
AD	1E-22	CFM
CS	1E-22	CFM-stpt
AI	1E-23	Zone-T
AD	1E-23	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1E-23	CFM
CS	1E-23	CFM-stpt
AI	1E-24	Zone-T
AD	1E-24	ActHtgSP
AD	1E-24	CFM
CS	1E-24	CFM-stpt
AI	1E-25	Zone-T
AD	1E-25	ActHtgSP
AD	1E-25	CFM
CS	1E-25	CFM-stpt
AI	1E-26	Zone-T
AD	1E-26	ActHtgSP
AD	1E-26	CFM
CS	1E-26	CFM-stpt
AI	1E-27	Zone-T
AD	1E-27	ActHtgSP
AD	1E-27	CFM
CS	1E-27	CFM-stpt
AI	1E-28	Zone-T
AD	1E-28	ActHtgSP
AD	1E-28	CFM
CS	1E-28	CFM-stpt
AI	1E-29	Zone-T
AD	1E-29	ActHtgSP
AD	1E-29	CFM
CS	1E-29	CFM-stpt
AI	1E-30	Zone-T
AD	1E-30	ActHtgSP
AD	1E-30	CFM
CS	1E-30	CFM-stpt
AI	1E-31	Zone-T
AD	1E-31	ActHtgSP
AD	1E-31	CFM
CS	1E-31	CFM-stpt
AI	1E-32A	Zone-T
AD	1E-32A	ActHtgSP
AD	1E-32A	CFM
CS	1E-32A	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1E-32	Zone-T
AD	1E-32	ActHtgSP
AD	1E-32	CFM
CS	1E-32	CFM-stpt
AI	1E-33	Zone-T
AD	1E-33	ActHtgSP
AD	1E-33	CFM
CS	1E-33	CFM-stpt
AI	1E-34	Zone-T
AD	1E-34	ActHtgSP
AD	1E-34	CFM
CS	1E-34	CFM-stpt
AI	1E-35	Zone-T
AD	1E-35	ActHtgSP
AD	1E-35	CFM
CS	1E-35	CFM-stpt
AI	1E-36	Zone-T
AD	1E-36	ActHtgSP
AD	1E-36	CFM
CS	1E-36	CFM-stpt
AI	1E-37	Zone-T
AD	1E-37	ActHtgSP
AD	1E-37	CFM
CS	1E-37	CFM-stpt
AI	1E-38	Zone-T
AD	1E-38	ActHtgSP
AD	1E-38	CFM
CS	1E-38	CFM-stpt
AI	1E-39	Zone-T
AD	1E-39	ActHtgSP
AD	1E-39	CFM
CS	1E-39	CFM-stpt
AI	1E-40	Zone-T
AD	1E-40	ActHtgSP
AD	1E-40	CFM
CS	1E-40	CFM-stpt
AI	1E-41	Zone-T
AD	1E-41	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1E-41	CFM
CS	1E-41	CFM-stpt
AI	1E-42A	Zone-T
AD	1E-42A	ActHtgSP
AD	1E-42A	CFM
CS	1E-42A	CFM-stpt
AI	1E-42	Zone-T
AD	1E-42	ActHtgSP
AD	1E-42	CFM
CS	1E-42	CFM-stpt
AI	1E-44	Zone-T
AD	1E-44	ActHtgSP
AD	1E-44	CFM
CS	1E-44	CFM-stpt
AI	1E-45	Zone-T
AD	1E-45	ActHtgSP
AD	1E-45	CFM
CS	1E-45	CFM-stpt
AI	1E-47	Zone-T
AD	1E-47	ActHtgSP
AD	1E-47	CFM
CS	1E-47	CFM-stpt
AI	1E-48	Zone-T
AD	1E-48	ActHtgSP
AD	1E-48	CFM
CS	1E-48	CFM-stpt
AI	1E-49	Zone-T
AD	1E-49	ActHtgSP
AD	1E-49	CFM
CS	1E-49	CFM-stpt
AI	1E-50	Zone-T
AD	1E-50	ActHtgSP
AD	1E-50	CFM
CS	1E-50	CFM-stpt
AI	1E-51	Zone-T
AD	1E-51	ActHtgSP
AD	1E-51	CFM
CS	1E-51	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1E-52	Zone-T
AD	1E-52	ActHtgSP
AD	1E-52	CFM
CS	1E-52	CFM-stpt
AI	1E-53	Zone-T
AD	1E-53	ActHtgSP
AD	1E-53	CFM
CS	1E-53	CFM-stpt
AI	1E-54	Zone-T
AD	1E-54	ActHtgSP
AD	1E-54	CFM
CS	1E-54	CFM-stpt
AI	1E-55	Zone-T
AD	1E-55	ActHtgSP
AD	1E-55	CFM
CS	1E-55	CFM-stpt
AI	1C-36	Zone-T
AD	1C-36	ActHtgSP
AD	1C-36	CFM
CS	1C-36	CFM-stpt
AI	1C-40	Zone-T
AD	1C-40	ActHtgSP
AD	1C-40	CFM
CS	1C-40	CFM-stpt
AI	1C-42	Zone-T
AD	1C-42	ActHtgSP
AD	1C-42	CFM
CS	1C-42	CFM-stpt
AI	1C-41A	Zone-T
AD	1C-41A	ActHtgSP
AD	1C-41A	CFM
CS	1C-41A	CFM-stpt
AI	1E-99	Zone-T
AD	1E-99	ActHtgSP
AD	1E-99	CFM
CS	1E-99	CFM-stpt
AI	1E-200	Zone-T
AD	1E-200	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1E-200	CFM
CS	1E-200	CFM-stpt
AI	1E-201	Zone-T
AD	1E-201	ActHtgSP
AD	1E-201	CFM
CS	1E-201	CFM-stpt
AI	1E-202	Zone-T
AD	1E-202	ActHtgSP
AD	1E-202	CFM
CS	1E-202	CFM-stpt
AI	1E-01A	Zone-T
AD	1E-01A	ActHtgSP
AD	1E-01A	CFM
CS	1E-01A	CFM-stpt
AI	1C-41	Zone-T
AD	1C-41	CFM
CS	1C-41	CFM-stpt
AI	1E-43	Zone-T
AD	1E-43	ActHtgSP
AD	1E-43	CFM
CS	1E-43	CFM-stpt
BI	1E-43	Filter-S
AI	1E-56	Zone-T
AD	1E-56	ActHtgSP
AD	1E-56	CFM
CS	1E-56	CFM-stpt
BI	1E-56	Filter-S
AI	BATT_RM	Rm-T
CS	BATT_RM	A-STPT
BI	BATT_RM	Fan_A-S
BO	BATT_RM	Fan_A-C
CS	BATT_RM	B-STPT
BI	BATT_RM	Fan_B-S
BO	BATT_RM	Fan_B-C
AOS	BATT_RM	Fan_A-V
AOS	BATT_RM	Fan_B-V
BI	BATT_RM	HP-C-S
BD	AHU-1401	OCC

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-1401	SF-S
BI	AHU-1401	RF-S
AI	AHU-1401	DA-T
AD	AHU-1401	DA-STPT
AOS	AHU-1401	HTG-VLV
BD	AHU-1401	HTG-PMP
AOS	AHU-1401	CLG-VLV
AOS	AHU-1401	OA-DMPR
AI	AHU-1401	MA-T
AI	AHU-1401	RA-T
AI	AHU-1401	OA-T
BI	AHU-1401	LT-ALM
BI	AHU-1401	PURGE
BI	AHU-1401	SHTDWN
BD	AHU-1401	CLG-LOCK
BI	AHU-1401	HAND
AI	AHU-1401	RA-H
AOS	AHU-1401	HUM-VLV
AI	AHU-1401	PRE
AI	AHU-1401	AFT
AI	AHU-1401	HWS
AI	AHU-1401	HWR
AI	AHU-1401	CWS
AI	AHU-1401	CWR
AD	AHU-1401	L-ZONE-T
AD	AHU-1401	H-ZONE-T
BO	AHU-1401	SF-C
BO	AHU-1401	RF-C
BO	AHU-1401	EF2_18-C
BI	AHU-1401	EF2_18
BO	AHU-1401	EF2_19-C
BI	AHU-1401	EF2_19
BO	AHU-1401	EF2_20-C
BI	AHU-1401	EF2_20
BO	AHU-1401	EF2_29-C
BI	AHU-1401	EF2_29
BD	AHU-1401	EF4_18
BD	AHU-1401	EF4_19

DRAFT

Building 2		
Points	Equipment	Type
BD	AHU-1401	EF4_20
BD	AHU-1401	NITEPURG
AI	AHU-1401	HW-DP
AOS	AHU-1401	HWDP-VLV
BI	AHU-1401	LO-STM
BI	AHU-1401	HI-STM
CS	CS-NC-4	AHU1401
CS	CS-NC-4	R-DPSTPT
CS	CS-NC-4	TEL-CHG
JCB	CS-NC-4	LOAD-RST
AI	1401	STM-P
AOS	1401	STM-VLV
AOS	1401	STM-STPT
JCB	JCB-NC04	14_01-TE
JCB	JCB-NC04	14_01EF
JCB	JCB-NC04	1401-OCC
JCB	JCB-NC04	1401-PMP
JCB	JCB-NC04	1401-SMK
JCB	JCB-NC04	BATT-FCU
JCB	JCB-NC04	LIEBSWOP
AI	CT_SCAN	RM-1-T
CS	CT_SCAN	RM-1STPT
AI	CT_SCAN	SA-T-1
AOS	CT_SCAN	Clg-Vlv1
AI	CT_SCAN	RA-T-1
BI	CT_SCAN	AHU_01_S
BO	CT_SCAN	AHU_01_C
BD	CT_SCAN	_
AI	CT_SCAN	RM-2-T
CS	CT_SCAN	RM-2STPT
AI	CT_SCAN	SA-T-2
AOS	CT_SCAN	Clg-Vlv2
AI	CT_SCAN	RA-T-2
BI	CT_SCAN	AHU_02_S
BO	CT_SCAN	AHU_02_C
AI	CT_SCAN	CWS-T-1
AI	CT_SCAN	CWR-T-1
AI	CT_SCAN	CWS-T-2

DRAFT

Building 2		
Points	Equipment	Type
AI	CT_SCAN	CWR-T-2
BD	CT_SCAN	____
AI	CT_SCAN	RM-3-T
CS	CT_SCAN	RM-3STPT
AI	CT_SCAN	SA-T-3
BI	CT_SCAN	AHU-03-S
BO	CT_SCAN	AHU-03-C
BI	CT_SCAN	FLT3-S
BI	CT_SCAN	PAN3-ALM
AOS	CT_SCAN	CLG-VLV3
AD	CT_SCAN	__
AI	CT_SCAN	RA-T
AI	CT_SCAN	SA-T
AOS	CT_SCAN	CLG-VLV4
AOS	CT_SCAN	RA-SPT
BO	CT_SCAN	SF-C
BI	CT_SCAN	SF-S
BO	CT_SCAN	SDWN-C
Building 2		
Points	**Equipment**	**Type**
	NC-5	**Network controller**
NC-5-HW	AHU-1501	115, 1, 3, AHU
NC-5-HW	DC5-116	116, 1, 3, UNT
NC-5-HW	DC5-117	117, 1, 3, UNT
NC-5-HW	DC5-118	118, 1, 3, UNT
NC-5-HW	DC5-119	119, 1, 3, AHU
NC-5-HW	CVR-01	1, 1, 3, VAV
NC-5-HW	CVR-02	2, 1, 3, VAV
NC-5-HW	CVR-03	3, 1, 3, VAV
NC-5-HW	CVR-04	4, 1, 3, VAV
NC-5-HW	CVR-05	5, 1, 3, VAV
NC-5-HW	CVR-06	6, 1, 3, VAV
NC-5-HW	CVR-07	7, 1, 3, VAV
NC-5-HW	CVR-08	8, 1, 3, VAV
NC-5-HW	CVR-09	9, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-5-HW	CVR-10	10, 1, 3, VAV
NC-5-HW	CVR-11	11, 1, 3, VAV
NC-5-HW	CVR-12	12, 1, 3, VAV
NC-5-HW	CVR-13	13, 1, 3, VAV
NC-5-HW	CVR-14	14, 1, 3, VAV
NC-5-HW	CVR-15	15, 1, 3, VAV
NC-5-HW	CVR-16	16, 1, 3, VAV
NC-5-HW	CVR-17	17, 1, 3, VAV
NC-5-HW	CVR-18	18, 1, 3, VAV
NC-5-HW	CVR-19	19, 1, 3, VAV
NC-5-HW	CVR-20	20, 1, 3, VAV
NC-5-HW	CVR-21	21, 1, 3, VAV
NC-5-HW	CVR-22	22, 1, 3, VAV
NC-5-HW	CVR-23	23, 1, 3, VAV
NC-5-HW	CVR-24	24, 1, 3, VAV
NC-5-HW	CVR-25	25, 1, 3, VAV
NC-5-HW	CVR-26	26, 1, 3, VAV
NC-5-HW	CVR-27	27, 1, 3, VAV
NC-5-HW	CVR-28	28, 1, 3, VAV
NC-5-HW	CVR-29	29, 1, 3, VAV
NC-5-HW	CVR-100	100, 1, 3, VAV
NC-5-HW	CVR-48	48, 1, 3, VAV
NC-5-HW	CVR-49	49, 1, 3, VAV
NC-5-HW	CVR-50	50, 1, 3, VAV
NC-5-HW	CVR-51	51, 1, 3, VAV
NC-5-HW	CVR-52	52, 1, 3, VAV
NC-5-HW	CVR-53	53, 1, 3, VAV
NC-5-HW	CVR-54	54, 1, 3, VAV
NC-5-HW	CVR-55	55, 1, 3, VAV
NC-5-HW	CVR-56	56, 1, 3, VAV
NC-5-HW	CVR-57	57, 1, 3, VAV
NC-5-HW	CVR-58	58, 1, 3, VAV
NC-5-HW	CVR-59	59, 1, 3, VAV
NC-5-HW	CVR-60	60, 1, 3, VAV
NC-5-HW	CVR-61	61, 1, 3, VAV
NC-5-HW	CVR-62	62, 1, 3, VAV
NC-5-HW	CVR-63	63, 1, 3, VAV
NC-5-HW	CVR-76	76, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-5-HW	CVR-77	77, 1, 3, VAV
NC-5-HW	CVR-78	78, 1, 3, VAV
NC-5-HW	CVR-79	79, 1, 3, VAV
NC-5-HW	CVR-80	80, 1, 3, VAV
NC-5-HW	CVR-81	81, 1, 3, VAV
NC-5-HW	CVR-82	82, 1, 3, VAV
NC-5-HW	CVR-182	182, 1, 3, VAV
NC-5-HW	CVR-83	83, 1, 3, VAV
NC-5-HW	CVR-84	84, 1, 3, VAV
NC-5-HW	CVR-85	85, 1, 3, VAV
NC-5-HW	CVR-86	86, 1, 3, VAV
NC-5-HW	CVR-87	87, 1, 3, VAV
NC-5-HW	CVR-88	88, 1, 3, VAV
NC-5-HW	CVR-89	89, 1, 3, VAV
NC-5-HW	CVR-90	90, 1, 3, VAV
NC-5-HW	CVR-91	91, 1, 3, VAV
NC-5-HW	CVR-92	92, 1, 3, VAV
NC-5-HW	CVR-93	93, 1, 3, VAV
NC-5-HW	CVR-94	94, 1, 3, VAV
NC-5-HW	CVR-95	95, 1, 3, VAV
NC-5-HW	DC5-120	120, 1, 3, VAV
NC-5-HW	DC5-121	121, 1, 3, UNT
NC-5-HW	DC5-122	122, 1, 3, VAV
NC-5-HW	CVR-42	142, 1, 3, VAV
NC-5-HW	CLNSTM70	70, 1, 3, UNT
BD	AHU-1501	OCC
BI	AHU-1501	SF-S
BI	AHU-1501	RF-S
AI	AHU-1501	DA-T
AD	AHU-1501	DA-STPT
AOS	AHU-1501	HTG-VLV
BD	AHU-1501	HTG-PMP
AOS	AHU-1501	CLG-VLV
AOS	AHU-1501	OA-DMPR
AI	AHU-1501	MA-T
AI	AHU-1501	RA-T
AI	AHU-1501	OA-T
BI	AHU-1501	LT-ALM

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-1501	PURGE
BI	AHU-1501	SHTDWN
BD	AHU-1501	CLG-LOCK
BI	AHU-1501	HAND
AI	AHU-1501	RA-H
AOS	AHU-1501	HUM-VLV
AI	AHU-1501	PRE
AI	AHU-1501	AFT
AI	AHU-1501	HWS
AI	AHU-1501	HWR
AI	AHU-1501	CWS
AI	AHU-1501	CWR
AD	AHU-1501	L-ZONE-T
AD	AHU-1501	H-ZONE-T
BO	AHU-1501	SF-C
BO	AHU-1501	RF-C
AI	AHU-1501	HW-DP
AOS	AHU-1501	HWDP-VLV
BI	AHU-1501	LO-STM
BI	AHU-1501	HI-STM
BD	AHU-1501	NITEPURG
BD	AHU-1501	EF3_48
BD	AHU-1501	EF3_49
BD	AHU-1501	EF3_52
BD	AHU-1501	EF3_54
AI	Ele_Temp	STORAGE
AI	Ele_Temp	SW_SOUTH
AD	Ele_Temp	SW_NORTH
AI	1501	STM-P
AOS	1501	STM-STPT
AOS	1501	STM-VLV
AI	1D-42	Zone-T
AD	1D-42	ActHtgSP
AD	1D-42	CFM
CS	1D-42	CFM-stpt
AI	1D-42	DA-T
AI	1D-85	Zone-T
AD	1D-85	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	1D-85	CFM-stpt
AI	1D-86	Zone-T
AD	1D-86	CFM
CS	1D-86	CFM-stpt
AI	1F-28	Zone-T
AD	1F-28	CFM
CS	1F-28	CFM-stpt
JCB	JCB-NC05	1501-OCC
JCB	JCB-NC05	1501-SMK
JCB	JCB-NC05	15_01EF
JCB	JCB-NC05	1501-PMP
JCB	JCB-NC05	15_01-TE
JCB	JCB-NC05	1501AITB
BO	SHARE05	EF2_21-C
BI	SHARE05	EF2_21
BO	SHARE05	EF2_23-C
BO	SHARE05	EF3_46-C
BI	SHARE05	EF3_46
BO	SHARE05	EF3_47-C
BI	SHARE05	EF3_47
CS	SHARE05	MED_GAS
BI	SHARE05	EF2_23
CS	CS-NC-5	AHU1501
CS	CS-NC-5	R-DPSTPT
AI	1D-95	Zone-T
AD	1D-95	ActHtgSP
AD	1D-95	CFM
CS	1D-95	CFM-stpt
AI	1D-94	Zone-T
AD	1D-94	ActHtgSP
AD	1D-94	CFM
CS	1D-94	CFM-stpt
AI	1D-93	Zone-T
AD	1D-93	ActHtgSP
AD	1D-93	CFM
CS	1D-93	CFM-stpt
AI	1D-92	Zone-T
AD	1D-92	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1D-92	CFM
CS	1D-92	CFM-stpt
AI	1D-91	Zone-T
AD	1D-91	ActHtgSP
AD	1D-91	CFM
CS	1D-91	CFM-stpt
AI	1D-90	Zone-T
AD	1D-90	ActHtgSP
AD	1D-90	CFM
CS	1D-90	CFM-stpt
AI	1D-89	Zone-T
AD	1D-89	ActHtgSP
AD	1D-89	CFM
CS	1D-89	CFM-stpt
AI	1D-88	Zone-T
AD	1D-88	ActHtgSP
AD	1D-88	CFM
CS	1D-88	CFM-stpt
AI	1D-87	Zone-T
AD	1D-87	ActHtgSP
AD	1D-87	CFM
CS	1D-87	CFM-stpt
AI	1D-84	Zone-T
AD	1D-84	ActHtgSP
AD	1D-84	CFM
CS	1D-84	CFM-stpt
AI	1D-83	Zone-T
AD	1D-83	ActHtgSP
AD	1D-83	CFM
CS	1D-83	CFM-stpt
AI	1D-82A	Zone-T
AD	1D-82A	ActHtgSP
AD	1D-82A	CFM
CS	1D-82A	CFM-stpt
AI	1D-82	Zone-T
AD	1D-82	ActHtgSP
AD	1D-82	CFM
CS	1D-82	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1D-81	Zone-T
AD	1D-81	ActHtgSP
AD	1D-81	CFM
CS	1D-81	CFM-stpt
AI	1D-80	Zone-T
AD	1D-80	ActHtgSP
AD	1D-80	CFM
CS	1D-80	CFM-stpt
AI	1D-79	Zone-T
AD	1D-79	ActHtgSP
AD	1D-79	CFM
CS	1D-79	CFM-stpt
AI	1D-78	Zone-T
AD	1D-78	ActHtgSP
AD	1D-78	CFM
CS	1D-78	CFM-stpt
AI	1D-77	Zone-T
AD	1D-77	ActHtgSP
AD	1D-77	CFM
CS	1D-77	CFM-stpt
AI	1D-76	Zone-T
AD	1D-76	ActHtgSP
AD	1D-76	CFM
CS	1D-76	CFM-stpt
AI	1D-63	Zone-T
AD	1D-63	ActHtgSP
AD	1D-63	CFM
CS	1D-63	CFM-stpt
AI	1D-62	Zone-T
AD	1D-62	ActHtgSP
AD	1D-62	CFM
CS	1D-62	CFM-stpt
AI	1D-61	Zone-T
AD	1D-61	ActHtgSP
AD	1D-61	CFM
CS	1D-61	CFM-stpt
AI	1D-60	Zone-T
AD	1D-60	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1D-60	CFM
CS	1D-60	CFM-stpt
AI	1D-59	Zone-T
AD	1D-59	ActHtgSP
AD	1D-59	CFM
CS	1D-59	CFM-stpt
AI	1D-58	Zone-T
AD	1D-58	ActHtgSP
AD	1D-58	CFM
CS	1D-58	CFM-stpt
AI	1D-57	Zone-T
AD	1D-57	ActHtgSP
AD	1D-57	CFM
CS	1D-57	CFM-stpt
AI	1D-56	Zone-T
AD	1D-56	ActHtgSP
AD	1D-56	CFM
CS	1D-56	CFM-stpt
AI	1D-55	Zone-T
AD	1D-55	ActHtgSP
AD	1D-55	CFM
CS	1D-55	CFM-stpt
AI	1D-54	Zone-T
AD	1D-54	ActHtgSP
AD	1D-54	CFM
CS	1D-54	CFM-stpt
AI	1D-53	Zone-T
AD	1D-53	ActHtgSP
AD	1D-53	CFM
CS	1D-53	CFM-stpt
AI	1D-52	Zone-T
AD	1D-52	ActHtgSP
AD	1D-52	CFM
CS	1D-52	CFM-stpt
AI	1D-51	Zone-T
AD	1D-51	ActHtgSP
AD	1D-51	CFM
CS	1D-51	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1D-49	Zone-T
AD	1D-49	ActHtgSP
AD	1D-49	CFM
CS	1D-49	CFM-stpt
AI	1D-48	Zone-T
AD	1D-48	ActHtgSP
AD	1D-48	CFM
CS	1D-48	CFM-stpt
AI	1F-29	Zone-T
AD	1F-29	ActHtgSP
AD	1F-29	CFM
CS	1F-29	CFM-stpt
AI	1F-27	Zone-T
AD	1F-27	ActHtgSP
AD	1F-27	CFM
CS	1F-27	CFM-stpt
AI	1F-26	Zone-T
AD	1F-26	ActHtgSP
AD	1F-26	CFM
CS	1F-26	CFM-stpt
AI	1F-25	Zone-T
AD	1F-25	ActHtgSP
AD	1F-25	CFM
CS	1F-25	CFM-stpt
AI	1F-24	Zone-T
AD	1F-24	ActHtgSP
AD	1F-24	CFM
CS	1F-24	CFM-stpt
AI	1F-23	Zone-T
AD	1F-23	ActHtgSP
AD	1F-23	CFM
CS	1F-23	CFM-stpt
AI	1F-22	Zone-T
AD	1F-22	ActHtgSP
AD	1F-22	CFM
CS	1F-22	CFM-stpt
AI	1F-21	Zone-T
AD	1F-21	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1F-21	CFM
CS	1F-21	CFM-stpt
AI	1F-20	Zone-T
AD	1F-20	ActHtgSP
AD	1F-20	CFM
CS	1F-20	CFM-stpt
AI	1F-19	Zone-T
AD	1F-19	ActHtgSP
AD	1F-19	CFM
CS	1F-19	CFM-stpt
AI	1F-18	Zone-T
AD	1F-18	ActHtgSP
AD	1F-18	CFM
CS	1F-18	CFM-stpt
AI	1F-17	Zone-T
AD	1F-17	ActHtgSP
AD	1F-17	CFM
CS	1F-17	CFM-stpt
AI	1F-16	Zone-T
AD	1F-16	ActHtgSP
AD	1F-16	CFM
CS	1F-16	CFM-stpt
AI	1F-15	Zone-T
AD	1F-15	ActHtgSP
AD	1F-15	CFM
CS	1F-15	CFM-stpt
AI	1F-14	Zone-T
AD	1F-14	ActHtgSP
AD	1F-14	CFM
CS	1F-14	CFM-stpt
AI	1F-13	Zone-T
AD	1F-13	ActHtgSP
AD	1F-13	CFM
CS	1F-13	CFM-stpt
AI	1F-12	Zone-T
AD	1F-12	ActHtgSP
AD	1F-12	CFM
CS	1F-12	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1F-11	Zone-T
AD	1F-11	ActHtgSP
AD	1F-11	CFM
CS	1F-11	CFM-stpt
AI	1F-10	Zone-T
AD	1F-10	ActHtgSP
AD	1F-10	CFM
CS	1F-10	CFM-stpt
AI	1F-09	Zone-T
AD	1F-09	ActHtgSP
AD	1F-09	CFM
CS	1F-09	CFM-stpt
AI	1F-08	Zone-T
AD	1F-08	ActHtgSP
AD	1F-08	CFM
CS	1F-08	CFM-stpt
AI	1F-07	Zone-T
AD	1F-07	ActHtgSP
AD	1F-07	CFM
CS	1F-07	CFM-stpt
AI	1F-06	Zone-T
AD	1F-06	ActHtgSP
AD	1F-06	CFM
CS	1F-06	CFM-stpt
AI	1F-05	Zone-T
AD	1F-05	ActHtgSP
AD	1F-05	CFM
CS	1F-05	CFM-stpt
AI	1F-04	Zone-T
AD	1F-04	ActHtgSP
AD	1F-04	CFM
CS	1F-04	CFM-stpt
AI	1F-03	Zone-T
AD	1F-03	ActHtgSP
AD	1F-03	CFM
CS	1F-03	CFM-stpt
AI	1F-02	Zone-T
AD	1F-02	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1F-02	CFM
CS	1F-02	CFM-stpt
AI	1F-01	Zone-T
AD	1F-01	ActHtgSP
AD	1F-01	CFM
CS	1F-01	CFM-stpt
AI	1D-50	Zone-T
AD	1D-50	ActHtgSP
AD	1D-50	CFM
CS	1D-50	CFM-stpt
AI	1F-100	Zone-T
AD	1F-100	ActHtgSP
AD	1F-100	CFM
CS	1F-100	CFM-stpt

Building 2		
Points	**Equipment**	**Type**
NC-6		**Network controller**
NC-6-HW	AHU-18	1, 1, 3, AHU
NC-6-HW	DC06-02	2, 1, 3, UNT
NC-6-HW	DC06-04	4, 1, 3, UNT
NC-6-HW	DC06-86	86, 1, 3, UNT
NC-6-HW	AHU-2901	87, 1, 3, AHU
NC-6-HW	DC06-88	88, 1, 3, UNT
NC-6-HW	1B-41	5, 1, 3, VAV
NC-6-HW	1B-42	6, 1, 3, VAV
NC-6-HW	1B-52	7, 1, 3, VAV
NC-6-HW	1B-46	8, 1, 3, VAV
NC-6-HW	1B-43	9, 1, 3, VAV
NC-6-HW	1B-44	10, 1, 3, VAV
NC-6-HW	1B-45	11, 1, 3, VAV
NC-6-HW	1B-48	12, 1, 3, VAV
NC-6-HW	1B-47	13, 1, 3, VAV
NC-6-HW	1B-49	14, 1, 3, VAV
NC-6-HW	1B-50	15, 1, 3, VAV
NC-6-HW	1B-51	16, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-6-HW	1D-70	17, 1, 3, VAV
NC-6-HW	1D-71	18, 1, 3, VAV
NC-6-HW	1D-72	19, 1, 3, VAV
NC-6-HW	1D-74	20, 1, 3, VAV
NC-6-HW	1D-73	21, 1, 3, VAV
NC-6-HW	1D-75	22, 1, 3, VAV
NC-6-HW	1D-69	23, 1, 3, VAV
NC-6-HW	1D-67	24, 1, 3, VAV
NC-6-HW	1D-66	25, 1, 3, VAV
NC-6-HW	1D-65	26, 1, 3, VAV
NC-6-HW	1D-64	27, 1, 3, VAV
NC-6-HW	1B-55	28, 1, 3, VAV
NC-6-HW	1B-54	29, 1, 3, VAV
NC-6-HW	1B-53	30, 1, 3, VAV
NC-6-HW	1B-52-1	31, 1, 3, VAV
NC-6-HW	1B-53-1	32, 1, 3, VAV
NC-6-HW	1B-54-1	33, 1, 3, VAV
NC-6-HW	1B-55-1	34, 1, 3, VAV
NC-6-HW	1B-56	35, 1, 3, VAV
NC-6-HW	1B-57	36, 1, 3, VAV
NC-6-HW	1B-58	37, 1, 3, VAV
NC-6-HW	1B-59	38, 1, 3, VAV
NC-6-HW	1B-60	39, 1, 3, VAV
NC-6-HW	1D-43	40, 1, 3, VAV
NC-6-HW	1D-44	41, 1, 3, VAV
NC-6-HW	1D-45	42, 1, 3, VAV
NC-6-HW	1D-46	43, 1, 3, VAV
NC-6-HW	1D-47	44, 1, 3, VAV
NC-6-HW	1B-40	45, 1, 3, VAV
NC-6-HW	1B-38	46, 1, 3, VAV
NC-6-HW	1B-39	47, 1, 3, VAV
NC-6-HW	1B-ADD48	48, 1, 3, VAV
NC-6-HW	1B-32	49, 1, 3, VAV
NC-6-HW	1B-29	50, 1, 3, VAV
NC-6-HW	1B-30	51, 1, 3, VAV
NC-6-HW	1B-26	52, 1, 3, VAV
NC-6-HW	1B-25	53, 1, 3, VAV
NC-6-HW	1B-25A	54, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-6-HW	1B-27	55, 1, 3, VAV
NC-6-HW	1B-24	56, 1, 3, VAV
NC-6-HW	1B-23	57, 1, 3, VAV
NC-6-HW	1B-70	58, 1, 3, VAV
NC-6-HW	1B-21	59, 1, 3, VAV
NC-6-HW	1B-20	60, 1, 3, VAV
NC-6-HW	1B-19	61, 1, 3, VAV
NC-6-HW	1B-18	62, 1, 3, VAV
NC-6-HW	1B-17	63, 1, 3, VAV
NC-6-HW	1B-16	64, 1, 3, VAV
NC-6-HW	1B-15	65, 1, 3, VAV
NC-6-HW	1B-14	66, 1, 3, VAV
NC-6-HW	1B-09	67, 1, 3, VAV
NC-6-HW	1B-12	68, 1, 3, VAV
NC-6-HW	1B-13	69, 1, 3, VAV
NC-6-HW	1B-10	70, 1, 3, VAV
NC-6-HW	1B-11	71, 1, 3, VAV
NC-6-HW	1B-31	72, 1, 3, VAV
NC-6-HW	1B-37	73, 1, 3, VAV
NC-6-HW	1B-35A	74, 1, 3, VAV
NC-6-HW	1B-35	75, 1, 3, VAV
NC-6-HW	1B-34	76, 1, 3, VAV
NC-6-HW	1B-08	78, 1, 3, VAV
NC-6-HW	1B-07	79, 1, 3, VAV
NC-6-HW	1B-06	80, 1, 3, VAV
NC-6-HW	1B-03	81, 1, 3, VAV
NC-6-HW	1B-02	82, 1, 3, VAV
NC-6-HW	1B-01	83, 1, 3, VAV
NC-6-HW	1B-04	84, 1, 3, VAV
NC-6-HW	1B-05	85, 1, 3, VAV
NC-6-HW	1B-28	89, 1, 3, VAV
NC-6-HW	1D-42	142, 1, 3, VAV
NC-6-HW	ISO-90	90, 1, 3, VND
NC-6-HW	ISO-91	91, 1, 3, VND
NC-6-HW	IB-33	77, 1, 3, VMA
AI	1B-33	ZN-T
AD	1B-33	ActHtgSP
AD	1B-33	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	1B-33	CFM-stpt
BD	1B-33	EF1TB-S
BD	1B-33	_____
AI	1B-33	RM-PRESS
CS	1B-33	Mode
BD	1B-33	ALM
BD	1B-33	_____
AI	1B-33	HW-PRESS
CS	1B-33	Mode2
BO	1B-33	EADPR-C
AOS	1B-33	SADPR-C
BI	1B-33	EMRG-SD
JCB	1B-33	TBLAB
BD	AHU-18	OCC
BI	AHU-18	SF-S
AI	AHU-18	DA-T
AD	AHU-18	DA-STPT
AI	AHU-18	PRE-T
AOS	AHU-18	PHTG-VLV
BD	AHU-18	PHTG-PMP
AOS	AHU-18	CLG-VLV
AI	AHU-18	ZN-T
AOS	AHU-18	HUM-VLV
AI	AHU-18	OA-T
BI	AHU-18	LT-ALM
BI	AHU-18	PURGE
BI	AHU-18	SHTDWN
BI	AHU-18	HAND
AI	AHU-18	PRE
AI	AHU-18	AFT
AI	AHU-18	HWS
AI	AHU-18	CWR
AI	AHU-18	HWR
AI	AHU-18	CWS
AD	AHU-18	L-ZONE-T
AD	AHU-18	H-ZONE-T
BO	AHU-18	SF-C
AI	AHU-18	HW-DP

DRAFT

Building 2		
Points	Equipment	Type
AOS	AHU-18	HWDP-VLV
AD	AHU-18	OA-H
AD	AHU-18	OADWPT
BO	AHU-18	EF2_30-C
BI	AHU-18	EF2_30
BD	AHU-18	EF3_59
BD	AHU-18	EF3_60
BD	AHU-18	EF3_61
BD	AHU-18	EF6_26
BD	AHU-18	EF6_30
BD	AHU-18	EF6_31
BD	AHU-18	EF7_04
BD	AHU-18	EF7_05
BD	AHU-18	EF7_06
BD	AHU-18	NITEPURG
AD	AHU-18	ZN-H
AI	1B-50	Zone-T
AD	1B-50	CFM
CS	1B-50	CFM-stpt
AI	1B-25	Zone-T
AD	1B-25	CFM
CS	1B-25	CFM-stpt
CS	CS-NC-6	AHU2901
CS	CS-NC-6	AHU1801
CS	CS-NC-6	R-DPSTPT
BD	AHU-2901	OCC
BI	AHU-2901	SF-S
BI	AHU-2901	RF-S
AI	AHU-2901	DA-T
AD	AHU-2901	DA-STPT
AOS	AHU-2901	HTG-VLV
BD	AHU-2901	HTG-PMP
AOS	AHU-2901	CLG-VLV
AOS	AHU-2901	OA-DMPR
AI	AHU-2901	MA-T
AI	AHU-2901	RA-T
AI	AHU-2901	OA-T
BI	AHU-2901	LT-ALM

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-2901	PURGE
BI	AHU-2901	SHTDWN
BD	AHU-2901	CLG-LOCK
BI	AHU-2901	HAND
AI	AHU-2901	RA-H
AOS	AHU-2901	HUM-VLV
AI	AHU-2901	PRE
AI	AHU-2901	AFT
AI	AHU-2901	HWS
AI	AHU-2901	HWR
AI	AHU-2901	CWS
AI	AHU-2901	CWR
AD	AHU-2901	L-ZONE-T
AD	AHU-2901	H-ZONE-T
BO	AHU-2901	SF-C
BO	AHU-2901	RF-C
AI	AHU-2901	CW-DP
BO	AHU-2901	EF2_10-C
BI	AHU-2901	EF2_10
BD	AHU-2901	NITEPURG
AI	1B-05	Zone-T
AD	1B-05	ActHtgSP
AD	1B-05	CFM
CS	1B-05	CFM-stpt
AI	1B-04	Zone-T
AD	1B-04	ActHtgSP
AD	1B-04	CFM
CS	1B-04	CFM-stpt
AI	1B-01	Zone-T
AD	1B-01	ActHtgSP
AD	1B-01	CFM
CS	1B-01	CFM-stpt
AI	1B-02	Zone-T
AD	1B-02	ActHtgSP
AD	1B-02	CFM
CS	1B-02	CFM-stpt
AI	1B-07	Zone-T
AD	1B-07	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1B-07	CFM
CS	1B-07	CFM-stpt
AI	1B-08	Zone-T
AD	1B-08	ActHtgSP
AD	1B-08	CFM
CS	1B-08	CFM-stpt
AI	1B-34	Zone-T
AD	1B-34	ActHtgSP
AD	1B-34	CFM
CS	1B-34	CFM-stpt
AI	1B-35	Zone-T
AD	1B-35	ActHtgSP
AD	1B-35	CFM
CS	1B-35	CFM-stpt
AI	1B-35A	Zone-T
AD	1B-35A	ActHtgSP
AD	1B-35A	CFM
CS	1B-35A	CFM-stpt
AI	1B-37	Zone-T
AD	1B-37	ActHtgSP
AD	1B-37	CFM
CS	1B-37	CFM-stpt
AI	1B-31	Zone-T
AD	1B-31	ActHtgSP
AD	1B-31	CFM
CS	1B-31	CFM-stpt
AI	1B-11	Zone-T
AD	1B-11	ActHtgSP
AD	1B-11	CFM
CS	1B-11	CFM-stpt
AI	1B-13	Zone-T
AD	1B-13	ActHtgSP
AD	1B-13	CFM
CS	1B-13	CFM-stpt
AI	1B-12	Zone-T
AD	1B-12	ActHtgSP
AD	1B-12	CFM
CS	1B-12	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1B-09	Zone-T
AD	1B-09	ActHtgSP
AD	1B-09	CFM
CS	1B-09	CFM-stpt
AI	1B-14	Zone-T
AD	1B-14	ActHtgSP
AD	1B-14	CFM
CS	1B-14	CFM-stpt
AI	1B-15	Zone-T
AD	1B-15	ActHtgSP
AD	1B-15	CFM
CS	1B-15	CFM-stpt
AI	1B-16	Zone-T
AD	1B-16	ActHtgSP
AD	1B-16	CFM
CS	1B-16	CFM-stpt
AI	1B-17	Zone-T
AD	1B-17	ActHtgSP
AD	1B-17	CFM
CS	1B-17	CFM-stpt
AI	1B-18	Zone-T
AD	1B-18	ActHtgSP
AD	1B-18	CFM
CS	1B-18	CFM-stpt
AI	1B-19	Zone-T
AD	1B-19	ActHtgSP
AD	1B-19	CFM
CS	1B-19	CFM-stpt
AI	1B-20	Zone-T
AD	1B-20	ActHtgSP
AD	1B-20	CFM
CS	1B-20	CFM-stpt
AI	1B-21	Zone-T
AD	1B-21	ActHtgSP
AD	1B-21	CFM
CS	1B-21	CFM-stpt
AI	1B-70	Zone-T
AD	1B-70	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1B-70	CFM
CS	1B-70	CFM-stpt
AI	1B-23	Zone-T
AD	1B-23	ActHtgSP
AD	1B-23	CFM
CS	1B-23	CFM-stpt
AI	1B-24	Zone-T
AD	1B-24	ActHtgSP
AD	1B-24	CFM
CS	1B-24	CFM-stpt
AI	1B-29	Zone-T
AD	1B-29	ActHtgSP
AD	1B-29	CFM
CS	1B-29	CFM-stpt
AI	1B-28	Zone-T
AD	1B-28	ActHtgSP
AD	1B-28	CFM
CS	1B-28	CFM-stpt
AI	1B-27	Zone-T
AD	1B-27	ActHtgSP
AD	1B-27	CFM
CS	1B-27	CFM-stpt
AI	1B-25A	Zone-T
AD	1B-25A	ActHtgSP
AD	1B-25A	CFM
CS	1B-25A	CFM-stpt
AI	1B-26	Zone-T
AD	1B-26	ActHtgSP
AD	1B-26	CFM
CS	1B-26	CFM-stpt
AI	1B-30	Zone-T
AD	1B-30	ActHtgSP
AD	1B-30	CFM
CS	1B-30	CFM-stpt
AI	1B-32	Zone-T
AD	1B-32	ActHtgSP
AD	1B-32	CFM
CS	1B-32	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1B-ADD48	Zone-T
AD	1B-ADD48	ActHtgSP
AD	1B-ADD48	CFM
CS	1B-ADD48	CFM-stpt
AI	1B-39	Zone-T
AD	1B-39	ActHtgSP
AD	1B-39	CFM
CS	1B-39	CFM-stpt
AI	1B-38	Zone-T
AD	1B-38	ActHtgSP
AD	1B-38	CFM
CS	1B-38	CFM-stpt
AI	1B-40	Zone-T
AD	1B-40	ActHtgSP
AD	1B-40	CFM
CS	1B-40	CFM-stpt
AI	1D-47	Zone-T
AD	1D-47	ActHtgSP
AD	1D-47	CFM
CS	1D-47	CFM-stpt
AI	1D-46	Zone-T
AD	1D-46	ActHtgSP
AD	1D-46	CFM
CS	1D-46	CFM-stpt
AI	1D-45	Zone-T
AD	1D-45	ActHtgSP
AD	1D-45	CFM
CS	1D-45	CFM-stpt
AI	1D-44	Zone-T
AD	1D-44	ActHtgSP
AD	1D-44	CFM
CS	1D-44	CFM-stpt
AI	1D-43	Zone-T
AD	1D-43	ActHtgSP
AD	1D-43	CFM
CS	1D-43	CFM-stpt
AI	1B-60	Zone-T
AD	1B-60	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1B-60	CFM
CS	1B-60	CFM-stpt
AI	1B-59	Zone-T
AD	1B-59	ActHtgSP
AD	1B-59	CFM
CS	1B-59	CFM-stpt
AI	1B-58	Zone-T
AD	1B-58	ActHtgSP
AD	1B-58	CFM
CS	1B-58	CFM-stpt
AI	1B-57	Zone-T
AD	1B-57	ActHtgSP
AD	1B-57	CFM
CS	1B-57	CFM-stpt
AI	1B-56	Zone-T
AD	1B-56	ActHtgSP
AD	1B-56	CFM
CS	1B-56	CFM-stpt
AI	1B-55	Zone-T
AD	1B-55	ActHtgSP
AD	1B-55	CFM
CS	1B-55	CFM-stpt
AI	1B-54	Zone-T
AD	1B-54	ActHtgSP
AD	1B-54	CFM
CS	1B-54	CFM-stpt
AI	1B-53	Zone-T
AD	1B-53	ActHtgSP
AD	1B-53	CFM
CS	1B-53	CFM-stpt
AI	1B-52	Zone-T
AD	1B-52	ActHtgSP
AD	1B-52	CFM
CS	1B-52	CFM-stpt
AI	1B-53-1	Zone-T
AD	1B-53-1	ActHtgSP
AD	1B-53-1	CFM
CS	1B-53-1	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1B-54-1	Zone-T
AD	1B-54-1	ActHtgSP
AD	1B-54-1	CFM
CS	1B-54-1	CFM-stpt
AI	1B-55-1	Zone-T
AD	1B-55-1	ActHtgSP
AD	1B-55-1	CFM
CS	1B-55-1	CFM-stpt
AI	1D-64	Zone-T
AD	1D-64	ActHtgSP
AD	1D-64	CFM
CS	1D-64	CFM-stpt
AI	1D-65	Zone-T
AD	1D-65	ActHtgSP
AD	1D-65	CFM
CS	1D-65	CFM-stpt
AI	1D-66	Zone-T
AD	1D-66	ActHtgSP
AD	1D-66	CFM
CS	1D-66	CFM-stpt
AI	1D-67	Zone-T
AD	1D-67	ActHtgSP
AD	1D-67	CFM
CS	1D-67	CFM-stpt
AI	1D-69	Zone-T
AD	1D-69	ActHtgSP
AD	1D-69	CFM
CS	1D-69	CFM-stpt
AI	1D-73	Zone-T
AD	1D-73	ActHtgSP
AD	1D-73	CFM
CS	1D-73	CFM-stpt
AI	1D-74	Zone-T
AD	1D-74	ActHtgSP
AD	1D-74	CFM
CS	1D-74	CFM-stpt
AI	1D-72	Zone-T
AD	1D-72	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	1D-72	CFM
CS	1D-72	CFM-stpt
AI	1D-71	Zone-T
AD	1D-71	ActHtgSP
AD	1D-71	CFM
CS	1D-71	CFM-stpt
AI	1D-70	Zone-T
AD	1D-70	ActHtgSP
AD	1D-70	CFM
CS	1D-70	CFM-stpt
AI	1B-51	Zone-T
AD	1B-51	ActHtgSP
AD	1B-51	CFM
CS	1B-51	CFM-stpt
AI	1B-49	Zone-T
AD	1B-49	ActHtgSP
AD	1B-49	CFM
CS	1B-49	CFM-stpt
AI	1B-47	Zone-T
AD	1B-47	ActHtgSP
AD	1B-47	CFM
CS	1B-47	CFM-stpt
AI	1B-48	Zone-T
AD	1B-48	ActHtgSP
AD	1B-48	CFM
CS	1B-48	CFM-stpt
AI	1B-45	Zone-T
AD	1B-45	ActHtgSP
AD	1B-45	CFM
CS	1B-45	CFM-stpt
AI	1B-44	Zone-T
AD	1B-44	ActHtgSP
AD	1B-44	CFM
CS	1B-44	CFM-stpt
AI	1B-43	Zone-T
AD	1B-43	ActHtgSP
AD	1B-43	CFM
CS	1B-43	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	1B-46	Zone-T
AD	1B-46	ActHtgSP
AD	1B-46	CFM
CS	1B-46	CFM-stpt
AI	1B-52-1	Zone-T
AD	1B-52-1	ActHtgSP
AD	1B-52-1	CFM
CS	1B-52-1	CFM-stpt
AI	1B-42	Zone-T
AD	1B-42	ActHtgSP
AD	1B-42	CFM
CS	1B-42	CFM-stpt
AI	1B-41	Zone-T
AD	1B-41	ActHtgSP
AD	1B-41	CFM
CS	1B-41	CFM-stpt
AI	1B-03	Zone-T
AD	1B-03	ActHtgSP
CS	1B-03	CFM-stpt
AD	1B-03	CFM
AI	1B-06	Zone-T
AD	1B-06	ActHtgSP
AD	1B-06	CFM
CS	1B-06	CFM-stpt
AI	1B-10	Zone-T
AD	1B-10	CFM
CS	1B-10	CFM-stpt
AI	1D-75	Zone-T
AD	1D-75	ActHtgSP
AD	1D-75	CFM
CS	1D-75	CFM-stpt
AI	1D-75	Z-HUM
BO	SHARE06	EF2_07-C
BI	SHARE06	EF2_07
BO	SHARE06	EF2_08-C
BI	SHARE06	EF2_08
BO	SHARE06	EF2_12-C
BI	SHARE06	EF2_12

DRAFT

Building 2		
Points	Equipment	Type
BO	SHARE06	EF2_13-C
BI	SHARE06	EF2_13
BO	SHARE06	EF2_14-C
BI	SHARE06	EF2_14
BO	SHARE06	EF2_15-C
BI	SHARE06	EF2_15
BO	SHARE06	EF2_32-C
AI	SHARE06	EF2_32-F
BI	SHARE06	EF2_32
JCB	JCB-NC06	2901-PMP
JCB	JCB-NC06	29_01EF
JCB	JCB-NC06	2901-SMK
JCB	JCB-NC06	1801-OCC
JCB	JCB-NC06	1801-PMP
JCB	JCB-NC06	18_01-TE
JCB	JCB-NC06	1801AITB
JCB	JCB-NC06	2901AITB
JCB	JCB-NC06	18_01-EF
JCB	JCB-NC06	DEWPT
JCB	JCB-NC06	OAH-GLB
JCB	JCB-NC06	2901-OCC
JCB	JCB-NC06	29_01TE
JCB	JCB-NC06	OAT-GLB

Building 2		
Points	**Equipment**	**Type**
	NC-7	**Network controller**
NC-7-HW	DC7-124	124, 1, 3, UNT
NC-7-HW	AHU-2302	125, 1, 3, AHU
NC-7-HW	DC7-126	126, 1, 3, UNT
NC-7-HW	DC7-129	129, 1, 3, UNT
NC-7-HW	AHU-2401	127, 1, 3, AHU
NC-7-HW	DC7-128	128, 1, 3, UNT
NC-7-HW	DC7-130	130, 1, 3, UNT
NC-7-HW	CVR-05	5, 1, 3, VAV
NC-7-HW	CVR-06	6, 1, 3, VAV
NC-7-HW	CVR-07	7, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-7-HW	CVR-08	8, 1, 3, VAV
NC-7-HW	CVR-09	9, 1, 3, VAV
NC-7-HW	CVR-10	10, 1, 3, VAV
NC-7-HW	CVR-11	11, 1, 3, VAV
NC-7-HW	CVR-16	16, 1, 3, VAV
NC-7-HW	CVR-17	17, 1, 3, VAV
NC-7-HW	CVR-18	18, 1, 3, VAV
NC-7-HW	CVR-19	19, 1, 3, VAV
NC-7-HW	CVR-20	20, 1, 3, VAV
NC-7-HW	CVR-21	21, 1, 3, VAV
NC-7-HW	CVR-22	22, 1, 3, VAV
NC-7-HW	CVR-23	23, 1, 3, VAV
NC-7-HW	CVR-24	24, 1, 3, VAV
NC-7-HW	CVR-25	25, 1, 3, VAV
NC-7-HW	CVR-26	26, 1, 3, VAV
NC-7-HW	CVR-27	27, 1, 3, VAV
NC-7-HW	CVR-28	28, 1, 3, VAV
NC-7-HW	CVR-29	29, 1, 3, VAV
NC-7-HW	CVR-30	30, 1, 3, VAV
NC-7-HW	CVR-31	31, 1, 3, VAV
NC-7-HW	CVR-32	32, 1, 3, VAV
NC-7-HW	CVR-33	33, 1, 3, VAV
NC-7-HW	CVR-34	34, 1, 3, VAV
NC-7-HW	CVR-35	35, 1, 3, VAV
NC-7-HW	CVR-36	36, 1, 3, VAV
NC-7-HW	CVR-37	37, 1, 3, VAV
NC-7-HW	CVR-38	38, 1, 3, VAV
NC-7-HW	CVR-39	39, 1, 3, VAV
NC-7-HW	CVR-40	40, 1, 3, VAV
NC-7-HW	CVR-41	41, 1, 3, VAV
NC-7-HW	CVR-42	42, 1, 3, VAV
NC-7-HW	CVR-43	43, 1, 3, VAV
NC-7-HW	CVR-44	44, 1, 3, VAV
NC-7-HW	CVR-45	45, 1, 3, VAV
NC-7-HW	CVR-46	46, 1, 3, VAV
NC-7-HW	CVR-47	47, 1, 3, VAV
NC-7-HW	CVR-48	48, 1, 3, VAV
NC-7-HW	CVR-49	49, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-7-HW	CVR-50	50, 1, 3, VAV
NC-7-HW	CVR-51	51, 1, 3, VAV
NC-7-HW	CVR-52	52, 1, 3, VAV
NC-7-HW	CVR-53	53, 1, 3, VAV
NC-7-HW	CVR-113	113, 1, 3, VAV
NC-7-HW	CVR-115	115, 1, 3, VAV
NC-7-HW	CVR-116	116, 1, 3, VAV
NC-7-HW	CVR-118	118, 1, 3, VAV
NC-7-HW	CVR-65	65, 1, 3, VAV
NC-7-HW	CVR-66	66, 1, 3, VAV
NC-7-HW	CVR-67	67, 1, 3, VAV
NC-7-HW	CVR-68	68, 1, 3, VAV
NC-7-HW	CVR-69	69, 1, 3, VAV
NC-7-HW	CVR-70	70, 1, 3, VAV
NC-7-HW	CVR-71	71, 1, 3, VAV
NC-7-HW	CVR-72	72, 1, 3, VAV
NC-7-HW	CVR-73	73, 1, 3, VAV
NC-7-HW	CVR-74	74, 1, 3, VAV
NC-7-HW	CVR-75	75, 1, 3, VAV
NC-7-HW	CVR-76	76, 1, 3, VAV
NC-7-HW	CVR-78	78, 1, 3, VAV
NC-7-HW	CVR-83	83, 1, 3, VAV
NC-7-HW	CVR-84	84, 1, 3, VAV
NC-7-HW	CVR-85	85, 1, 3, VAV
NC-7-HW	CVR-86	86, 1, 3, VAV
NC-7-HW	CVR-87	87, 1, 3, VAV
NC-7-HW	CVR-88	88, 1, 3, VAV
NC-7-HW	CVR-89	89, 1, 3, VAV
NC-7-HW	CVR-90	90, 1, 3, VAV
NC-7-HW	CVR-92	92, 1, 3, VAV
NC-7-HW	CVR-93	93, 1, 3, VAV
NC-7-HW	CVR-94	94, 1, 3, VAV
NC-7-HW	CVR-95	95, 1, 3, VAV
NC-7-HW	CVR-96	96, 1, 3, VAV
NC-7-HW	CVR-97	97, 1, 3, VAV
NC-7-HW	CVR-98	98, 1, 3, VAV
NC-7-HW	CVR-99	99, 1, 3, VAV
NC-7-HW	CVR-100	100, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-7-HW	CVR-255	255, 1, 3, VAV
BO	SHARE07	EF3_48-C
BI	SHARE07	EF3_48
BO	SHARE07	EF3_49-C
BI	SHARE07	EF3_49
BO	SHARE07	EF3_50-C
BI	SHARE07	EF3_50
BO	SHARE07	EF3_51-C
BI	SHARE07	EF3_51
BO	SHARE07	EF3_52-C
BI	SHARE07	EF3_52
BO	SHARE07	EF3_53-C
BI	SHARE07	EF3_53
BO	SHARE07	EF3_54-C
BI	SHARE07	EF3_54
AI	2E-43	Zone-T
AD	2E-43	ActHtgSP
AD	2E-43	CFM
BI	2E-43	ExhFan-S
BO	2E-43	ExhFan-C
CS	2E-43	CFM-stpt
CS	CS-NC-7	AHU2301
CS	CS-NC-7	AHU2302
CS	CS-NC-7	AHU2401
BD	AHU-2401	OCC
BI	AHU-2401	SF-S
BI	AHU-2401	RF-S
AI	AHU-2401	DA-T
AD	AHU-2401	DA-STPT
AOS	AHU-2401	HTG-VLV
BD	AHU-2401	HTG-PMP
AOS	AHU-2401	CLG-VLV
AOS	AHU-2401	OA-DMPR
AI	AHU-2401	MA-T
AI	AHU-2401	RA-T
AI	AHU-2401	OA-T
BI	AHU-2401	LL-ALM
BI	AHU-2401	PURGE

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-2401	SHTDWN
BD	AHU-2401	CLG-LOCK
BI	AHU-2401	HAND
AI	AHU-2401	RA-H
AOS	AHU-2401	HUM-VLV
AI	AHU-2401	PRE
AI	AHU-2401	AFT
AI	AHU-2401	HWS
AI	AHU-2401	HWR
AI	AHU-2401	CWS
AI	AHU-2401	CWR
AD	AHU-2401	L-ZONE-T
AD	AHU-2401	H-ZONE-T
BO	AHU-2401	SF-C
BO	AHU-2401	RF-C
BD	AHU-2401	EF2_21
BD	AHU-2401	EF3_01
BO	AHU-2401	EF3_02-C
BI	AHU-2401	EF3_02
BD	AHU-2401	EF3_04
BD	AHU-2401	EF3_05
BD	AHU-2401	EF3_07
BD	AHU-2401	EF3_45
BO	AHU-2401	EF3_73-C
BI	AHU-2401	EF3_73
BO	AHU-2401	EF3_74-C
BI	AHU-2401	EF3_74
BD	AHU-2401	NITEPURG
JCB	JCB-NC07	2301-SMK
JCB	JCB-NC07	2302-SMK
JCB	JCB-NC07	2401-SMK
JCB	JCB-NC07	2301-PMP
JCB	JCB-NC07	2302-PMP
JCB	JCB-NC07	2401-PMP
JCB	JCB-NC07	23_02EF
JCB	JCB-NC07	24_01EF
JCB	JCB-NC07	2301AITB
JCB	JCB-NC07	2302AITB

DRAFT

Building 2		
Points	Equipment	Type
JCB	JCB-NC07	2401AITB
JCB	JCB-NC07	23_01EF
JCB	JCB-NC07	2301-OCC
JCB	JCB-NC07	2302-OCC
JCB	JCB-NC07	2401-OCC
JCB	JCB-NC07	24_01-TE
JCB	JCB-NC07	23_02-TE
JCB	JCB-NC07	23_01-TE
BD	AHU-2302	OCC
BI	AHU-2302	SF-S
BI	AHU-2302	RF-S
AI	AHU-2302	DA-T
AD	AHU-2302	DA-STPT
AOS	AHU-2302	HTG-VLV
BD	AHU-2302	HTG-PMP
AOS	AHU-2302	CLG-VLV
AOS	AHU-2302	OA-DMPR
AI	AHU-2302	MA-T
AI	AHU-2302	RA-T
AI	AHU-2302	OA-T
BI	AHU-2302	LT-ALM
BI	AHU-2302	PURGE
BI	AHU-2302	SHTDWN
BD	AHU-2302	CLG-LOCK
BI	AHU-2302	HAND
AI	AHU-2302	RA-H
AOS	AHU-2302	HUM-VLV
AI	AHU-2302	PRE
AI	AHU-2302	AFT
AI	AHU-2302	HWS
AI	AHU-2302	HWR
AI	AHU-2302	CWS
AI	AHU-2302	CWR
AD	AHU-2302	L-ZONE-T
AD	AHU-2302	H-ZONE-T
BO	AHU-2302	SF-C
BO	AHU-2302	RF-C
BO	AHU-2302	EF3_26-C

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-2302	EF3_26
BO	AHU-2302	EF3_27-C
BI	AHU-2302	EF3_27
BD	AHU-2302	NITEPURG
BD	AHU-2301	OCC
BI	AHU-2301	SF-S
BI	AHU-2301	RF-S
AI	AHU-2301	DA-T
AD	AHU-2301	DA-STPT
AOS	AHU-2301	HTG-VLV
BD	AHU-2301	HTG-PMP
AOS	AHU-2301	CLG-VLV
AOS	AHU-2301	OA-DMPR
AI	AHU-2301	MA-T
AI	AHU-2301	RA-T
AI	AHU-2301	OA-T
BI	AHU-2301	LT-ALM
BI	AHU-2301	PURGE
BI	AHU-2301	SHTDWN
BD	AHU-2301	CLG-LOCK
BI	AHU-2301	HAND
AI	AHU-2301	RA-H
AOS	AHU-2301	HUM-VLV
AI	AHU-2301	PRE
AI	AHU-2301	AFT
AI	AHU-2301	HWS
AI	AHU-2301	HWR
AI	AHU-2301	CWS
AI	AHU-2301	CWR
AD	AHU-2301	L-ZONE-T
AD	AHU-2301	H-ZONE-T
BO	AHU-2301	SF-C
BO	AHU-2301	RF-C
BO	AHU-2301	EF3_29-C
BI	AHU-2301	EF3_29
BD	AHU-2301	NITEPURG
AI	2E-22	Zone-T
AD	2E-22	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2E-22	CFM-stpt
AI	2C-18	Zone-T
AD	2C-18	CFM
CS	2C-18	CFM-stpt
AI	2C-28	Zone-T
AD	2C-28	CFM
CS	2C-28	CFM-stpt
AI	2C-05	Zone-T
AD	2C-05	ActHtgSP
AD	2C-05	CFM
CS	2C-05	CFM-stpt
AI	2C-06	Zone-T
AD	2C-06	ActHtgSP
AD	2C-06	CFM
CS	2C-06	CFM-stpt
AI	2C-07	Zone-T
AD	2C-07	ActHtgSP
AD	2C-07	CFM
CS	2C-07	CFM-stpt
AI	2C-08	Zone-T
AD	2C-08	ActHtgSP
AD	2C-08	CFM
CS	2C-08	CFM-stpt
AI	2C-09	Zone-T
AD	2C-09	ActHtgSP
AD	2C-09	CFM
CS	2C-09	CFM-stpt
AI	2C-10	Zone-T
AD	2C-10	ActHtgSP
AD	2C-10	CFM
CS	2C-10	CFM-stpt
AI	2C-11	Zone-T
AD	2C-11	ActHtgSP
AD	2C-11	CFM
CS	2C-11	CFM-stpt
AI	2C-16	Zone-T
AD	2C-16	ActHtgSP
AD	2C-16	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2C-16	CFM-stpt
AI	2C-17	Zone-T
AD	2C-17	ActHtgSP
AD	2C-17	CFM
CS	2C-17	CFM-stpt
AI	2C-19	Zone-T
AD	2C-19	ActHtgSP
AD	2C-19	CFM
CS	2C-19	CFM-stpt
AI	2C-20	Zone-T
AD	2C-20	ActHtgSP
AD	2C-20	CFM
CS	2C-20	CFM-stpt
AI	2C-21	Zone-T
AD	2C-21	ActHtgSP
AD	2C-21	CFM
CS	2C-21	CFM-stpt
AI	2C-22	Zone-T
AD	2C-22	ActHtgSP
AD	2C-22	CFM
CS	2C-22	CFM-stpt
AI	2C-23	Zone-T
AD	2C-23	ActHtgSP
AD	2C-23	CFM
CS	2C-23	CFM-stpt
AI	2C-24	Zone-T
AD	2C-24	ActHtgSP
AD	2C-24	CFM
CS	2C-24	CFM-stpt
AI	2C-25	Zone-T
AD	2C-25	ActHtgSP
AD	2C-25	CFM
CS	2C-25	CFM-stpt
AI	2C-26	Zone-T
AD	2C-26	ActHtgSP
AD	2C-26	CFM
CS	2C-26	CFM-stpt
AI	2C-27	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2C-27	ActHtgSP
AD	2C-27	CFM
CS	2C-27	CFM-stpt
AI	2C-29	Zone-T
AD	2C-29	ActHtgSP
AD	2C-29	CFM
CS	2C-29	CFM-stpt
AI	2C-30	Zone-T
AD	2C-30	ActHtgSP
AD	2C-30	CFM
CS	2C-30	CFM-stpt
AI	2C-31	Zone-T
AD	2C-31	ActHtgSP
AD	2C-31	CFM
CS	2C-31	CFM-stpt
AI	2C-32	Zone-T
AD	2C-32	ActHtgSP
AD	2C-32	CFM
CS	2C-32	CFM-stpt
AI	2C-33	Zone-T
AD	2C-33	ActHtgSP
AD	2C-33	CFM
CS	2C-33	CFM-stpt
AI	2C-34	Zone-T
AD	2C-34	ActHtgSP
AD	2C-34	CFM
CS	2C-34	CFM-stpt
AI	2C-35	Zone-T
AD	2C-35	ActHtgSP
AD	2C-35	CFM
CS	2C-35	CFM-stpt
AI	2C-36	Zone-T
AD	2C-36	ActHtgSP
AD	2C-36	CFM
CS	2C-36	CFM-stpt
AI	2C-37	Zone-T
AD	2C-37	ActHtgSP
AD	2C-37	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2C-37	CFM-stpt
AI	2C-38	Zone-T
AD	2C-38	ActHtgSP
AD	2C-38	CFM
CS	2C-38	CFM-stpt
AI	2C-39	Zone-T
AD	2C-39	ActHtgSP
AD	2C-39	CFM
CS	2C-39	CFM-stpt
AI	2C-40	Zone-T
AD	2C-40	ActHtgSP
AD	2C-40	CFM
CS	2C-40	CFM-stpt
AI	2C-41	Zone-T
AD	2C-41	ActHtgSP
AD	2C-41	CFM
CS	2C-41	CFM-stpt
AI	2C-42	Zone-T
AD	2C-42	ActHtgSP
AD	2C-42	CFM
CS	2C-42	CFM-stpt
AI	2C-43	Zone-T
AD	2C-43	ActHtgSP
AD	2C-43	CFM
CS	2C-43	CFM-stpt
AI	2C-44	Zone-T
AD	2C-44	ActHtgSP
AD	2C-44	CFM
CS	2C-44	CFM-stpt
AI	2C-45	Zone-T
AD	2C-45	ActHtgSP
AD	2C-45	CFM
CS	2C-45	CFM-stpt
AI	2C-46	Zone-T
AD	2C-46	ActHtgSP
AD	2C-46	CFM
CS	2C-46	CFM-stpt
AI	2C-47	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2C-47	ActHtgSP
AD	2C-47	CFM
CS	2C-47	CFM-stpt
AI	2C-48	Zone-T
AD	2C-48	ActHtgSP
AD	2C-48	CFM
CS	2C-48	CFM-stpt
AI	2C-49	Zone-T
AD	2C-49	ActHtgSP
AD	2C-49	CFM
CS	2C-49	CFM-stpt
AI	2C-50	Zone-T
AD	2C-50	ActHtgSP
AD	2C-50	CFM
CS	2C-50	CFM-stpt
AI	2C-51	Zone-T
AD	2C-51	ActHtgSP
AD	2C-51	CFM
CS	2C-51	CFM-stpt
AI	2C-52	Zone-T
AD	2C-52	ActHtgSP
AD	2C-52	CFM
CS	2C-52	CFM-stpt
AI	2C-53	Zone-T
AD	2C-53	ActHtgSP
AD	2C-53	CFM
CS	2C-53	CFM-stpt
AI	2C-113	Zone-T
AD	2C-113	ActHtgSP
AD	2C-113	CFM
CS	2C-113	CFM-stpt
AI	2C-115	Zone-T
AD	2C-115	ActHtgSP
AD	2C-115	CFM
CS	2C-115	CFM-stpt
AI	2C-116	Zone-T
AD	2C-116	ActHtgSP
AD	2C-116	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2C-116	CFM-stpt
AI	2C-118	Zone-T
AD	2C-118	ActHtgSP
AD	2C-118	CFM
CS	2C-118	CFM-stpt
AI	2E-01	Zone-T
AD	2E-01	ActHtgSP
AD	2E-01	CFM
CS	2E-01	CFM-stpt
AI	2E-02	Zone-T
AD	2E-02	ActHtgSP
AD	2E-02	CFM
CS	2E-02	CFM-stpt
AI	2E-03	Zone-T
AD	2E-03	ActHtgSP
AD	2E-03	CFM
CS	2E-03	CFM-stpt
AI	2E-04	Zone-T
AD	2E-04	ActHtgSP
AD	2E-04	CFM
CS	2E-04	CFM-stpt
AI	2E-05	Zone-T
AD	2E-05	ActHtgSP
AD	2E-05	CFM
CS	2E-05	CFM-stpt
AI	2E-06	Zone-T
AD	2E-06	ActHtgSP
AD	2E-06	CFM
CS	2E-06	CFM-stpt
AI	2E-07	Zone-T
AD	2E-07	ActHtgSP
AD	2E-07	CFM
CS	2E-07	CFM-stpt
AI	2E-08	Zone-T
AD	2E-08	ActHtgSP
AD	2E-08	CFM
CS	2E-08	CFM-stpt
AI	2E-09	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2E-09	ActHtgSP
AD	2E-09	CFM
CS	2E-09	CFM-stpt
AI	2E-10	Zone-T
AD	2E-10	ActHtgSP
AD	2E-10	CFM
CS	2E-10	CFM-stpt
AI	2E-11	Zone-T
AD	2E-11	ActHtgSP
AD	2E-11	CFM
CS	2E-11	CFM-stpt
AI	2E-12	Zone-T
AD	2E-12	ActHtgSP
AD	2E-12	CFM
CS	2E-12	CFM-stpt
AI	2E-14	Zone-T
AD	2E-14	ActHtgSP
AD	2E-14	CFM
CS	2E-14	CFM-stpt
AI	2E-19	Zone-T
AD	2E-19	ActHtgSP
AD	2E-19	CFM
CS	2E-19	CFM-stpt
AI	2E-20	Zone-T
AD	2E-20	ActHtgSP
AD	2E-20	CFM
CS	2E-20	CFM-stpt
AI	2E-21	Zone-T
AD	2E-21	ActHtgSP
AD	2E-21	CFM
CS	2E-21	CFM-stpt
AI	2E-23	Zone-T
AD	2E-23	ActHtgSP
AD	2E-23	CFM
CS	2E-23	CFM-stpt
AI	2E-24	Zone-T
AD	2E-24	ActHtgSP
AD	2E-24	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2E-24	CFM-stpt
AI	2E-25	Zone-T
AD	2E-25	ActHtgSP
AD	2E-25	CFM
CS	2E-25	CFM-stpt
AI	2E-26	Zone-T
AD	2E-26	ActHtgSP
AD	2E-26	CFM
CS	2E-26	CFM-stpt
AI	2E-28	Zone-T
AD	2E-28	ActHtgSP
AD	2E-28	CFM
CS	2E-28	CFM-stpt
AI	2E-29	Zone-T
AD	2E-29	ActHtgSP
AD	2E-29	CFM
CS	2E-29	CFM-stpt
AI	2E-30	Zone-T
AD	2E-30	ActHtgSP
AD	2E-30	CFM
CS	2E-30	CFM-stpt
AI	2E-31	Zone-T
AD	2E-31	ActHtgSP
AD	2E-31	CFM
CS	2E-31	CFM-stpt
AI	2E-32	Zone-T
AD	2E-32	ActHtgSP
AD	2E-32	CFM
CS	2E-32	CFM-stpt
AI	2E-33	Zone-T
AD	2E-33	ActHtgSP
AD	2E-33	CFM
CS	2E-33	CFM-stpt
AI	2E-34	Zone-T
AD	2E-34	ActHtgSP
AD	2E-34	CFM
CS	2E-34	CFM-stpt
AI	2E-35	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2E-35	ActHtgSP
AD	2E-35	CFM
CS	2E-35	CFM-stpt
AI	2E-36	Zone-T
AD	2E-36	ActHtgSP
AD	2E-36	CFM
CS	2E-36	CFM-stpt
Building 2		
Points	**Equipment**	**Type**
	NC-8	**Network controller**
NC-8-HW	AHU-2501	125, 1, 3, AHU
NC-8-HW	DC8-126	126, 1, 3, UNT
NC-8-HW	DC8-127	127, 1, 3, UNT
NC-8-HW	DC8-128	128, 1, 3, UNT
NC-8-HW	CVR-01	1, 1, 3, VAV
NC-8-HW	CVR-02	2, 1, 3, VAV
NC-8-HW	CVR-03	3, 1, 3, VAV
NC-8-HW	CVR-04	4, 1, 3, VAV
NC-8-HW	CVR-05	5, 1, 3, VAV
NC-8-HW	CVR-06	6, 1, 3, VAV
NC-8-HW	CVR-07	7, 1, 3, VAV
NC-8-HW	CVR-08	8, 1, 3, VAV
NC-8-HW	CVR-09	9, 1, 3, VAV
NC-8-HW	CVR-10	10, 1, 3, VAV
NC-8-HW	CVR-11	11, 1, 3, VAV
NC-8-HW	CVR-12	12, 1, 3, VAV
NC-8-HW	CVR-13	13, 1, 3, VAV
NC-8-HW	CVR-14	14, 1, 3, VAV
NC-8-HW	CVR-15	15, 1, 3, VAV
NC-8-HW	CVR-16	16, 1, 3, VAV
NC-8-HW	CVR-17	17, 1, 3, VAV
NC-8-HW	CVR-18	18, 1, 3, VAV
NC-8-HW	CVR-19	19, 1, 3, VAV
NC-8-HW	CVR-20	20, 1, 3, VAV
NC-8-HW	CVR-21	21, 1, 3, VAV
NC-8-HW	CVR-22	22, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-8-HW	CVR-23	23, 1, 3, VAV
NC-8-HW	CVR-24	24, 1, 3, VAV
NC-8-HW	CVR-25	25, 1, 3, VAV
NC-8-HW	CVR-26	26, 1, 3, VAV
NC-8-HW	CVR-27	27, 1, 3, VAV
NC-8-HW	CVR-28	28, 1, 3, VAV
NC-8-HW	CVR-29	29, 1, 3, VAV
NC-8-HW	CVR-30	30, 1, 3, VAV
NC-8-HW	CVR-31	31, 1, 3, VAV
NC-8-HW	CVR-32	32, 1, 3, VAV
NC-8-HW	CVR-33	33, 1, 3, VAV
NC-8-HW	CVR-51	51, 1, 3, VAV
NC-8-HW	CVR-52	52, 1, 3, VAV
NC-8-HW	CVR-53	53, 1, 3, VAV
NC-8-HW	CVR-54	54, 1, 3, VAV
NC-8-HW	CVR-55	55, 1, 3, VAV
NC-8-HW	CVR-56	56, 1, 3, VAV
NC-8-HW	CVR-57	57, 1, 3, VAV
NC-8-HW	CVR-58	58, 1, 3, VAV
NC-8-HW	CVR-59	59, 1, 3, VAV
NC-8-HW	CVR-60	60, 1, 3, VAV
NC-8-HW	CVR-61	61, 1, 3, VAV
NC-8-HW	CVR-62	62, 1, 3, VAV
NC-8-HW	CVR-63	63, 1, 3, VAV
NC-8-HW	CVR-64	64, 1, 3, VAV
NC-8-HW	CVR-65	65, 1, 3, VAV
NC-8-HW	CVR-66	66, 1, 3, VAV
NC-8-HW	CVR-67	67, 1, 3, VAV
NC-8-HW	CVR-68	68, 1, 3, VAV
NC-8-HW	CVR-69	69, 1, 3, VAV
NC-8-HW	CVR-70	70, 1, 3, VAV
NC-8-HW	CVR-71	71, 1, 3, VAV
NC-8-HW	CVR-72	72, 1, 3, VAV
NC-8-HW	CVR-73	73, 1, 3, VAV
NC-8-HW	CVR-74	74, 1, 3, VAV
NC-8-HW	FCU-100	100, 1, 3, UNT
NC-8-HW	FCU101	101, 1, 3, UNT
NC-8-HW	FCU-102	102, 1, 3, UNT

DRAFT

Building 2		
Points	Equipment	Type
NC-8-HW	FCU-103	103, 1, 3, UNT
NC-8-HW	FCU-104	104, 1, 3, UNT
CS	CS-NC-8	AHU2501
AI	2F-74	Zone-T
AD	2F-74	ActHtgSP
AD	2F-74	CFM
CS	2F-74	CFM-stpt
AI	2F-73	Zone-T
AD	2F-73	ActHtgSP
AD	2F-73	CFM
CS	2F-73	CFM-stpt
AI	2F-72	Zone-T
AD	2F-72	ActHtgSP
AD	2F-72	CFM
CS	2F-72	CFM-stpt
AI	2F-71	Zone-T
AD	2F-71	ActHtgSP
AD	2F-71	CFM
CS	2F-71	CFM-stpt
AI	2F-70	Zone-T
AD	2F-70	ActHtgSP
AD	2F-70	CFM
CS	2F-70	CFM-stpt
AI	2F-69	Zone-T
AD	2F-69	ActHtgSP
AD	2F-69	CFM
CS	2F-69	CFM-stpt
AI	2F-68	Zone-T
AD	2F-68	ActHtgSP
AD	2F-68	CFM
CS	2F-68	CFM-stpt
AI	2F-66	Zone-T
AD	2F-66	ActHtgSP
AD	2F-66	CFM
CS	2F-66	CFM-stpt
AI	2F-65	Zone-T
AD	2F-65	ActHtgSP
AD	2F-65	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2F-65	CFM-stpt
AI	2F-64	Zone-T
AD	2F-64	ActHtgSP
AD	2F-64	CFM
CS	2F-64	CFM-stpt
AI	2F-63	Zone-T
AD	2F-63	ActHtgSP
AD	2F-63	CFM
CS	2F-63	CFM-stpt
AI	2F-62	Zone-T
AD	2F-62	ActHtgSP
AD	2F-62	CFM
CS	2F-62	CFM-stpt
AI	2F-61	Zone-T
AD	2F-61	ActHtgSP
AD	2F-61	CFM
CS	2F-61	CFM-stpt
AI	2F-60	Zone-T
AD	2F-60	ActHtgSP
AD	2F-60	CFM
CS	2F-60	CFM-stpt
AI	2F-59	Zone-T
AD	2F-59	ActHtgSP
AD	2F-59	CFM
CS	2F-59	CFM-stpt
AI	2F-58	Zone-T
AD	2F-58	ActHtgSP
AD	2F-58	CFM
CS	2F-58	CFM-stpt
AI	2F-57	Zone-T
AD	2F-57	ActHtgSP
AD	2F-57	CFM
CS	2F-57	CFM-stpt
AI	2F-56	Zone-T
AD	2F-56	ActHtgSP
AD	2F-56	CFM
CS	2F-56	CFM-stpt
AI	2F-55	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2F-55	ActHtgSP
AD	2F-55	CFM
CS	2F-55	CFM-stpt
AI	2F-54	Zone-T
AD	2F-54	ActHtgSP
AD	2F-54	CFM
CS	2F-54	CFM-stpt
AI	2F-53	Zone-T
AD	2F-53	ActHtgSP
AD	2F-53	CFM
CS	2F-53	CFM-stpt
AI	2F-33	Zone-T
AD	2F-33	ActHtgSP
AD	2F-33	CFM
CS	2F-33	CFM-stpt
AI	2F-32	Zone-T
AD	2F-32	ActHtgSP
AD	2F-32	CFM
CS	2F-32	CFM-stpt
AI	2F-31	Zone-T
AD	2F-31	ActHtgSP
AD	2F-31	CFM
CS	2F-31	CFM-stpt
AI	2F-30	Zone-T
AD	2F-30	ActHtgSP
AD	2F-30	CFM
CS	2F-30	CFM-stpt
AI	2F-29	Zone-T
AD	2F-29	ActHtgSP
AD	2F-29	CFM
CS	2F-29	CFM-stpt
AI	2F-28	Zone-T
AD	2F-28	ActHtgSP
AD	2F-28	CFM
CS	2F-28	CFM-stpt
AI	2F-27	Zone-T
AD	2F-27	ActHtgSP
AD	2F-27	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2F-27	CFM-stpt
AI	2F-26	Zone-T
AD	2F-26	ActHtgSP
AD	2F-26	CFM
CS	2F-26	CFM-stpt
AI	2F-25	Zone-T
AD	2F-25	ActHtgSP
AD	2F-25	CFM
CS	2F-25	CFM-stpt
AI	2F-24	Zone-T
AD	2F-24	ActHtgSP
AD	2F-24	CFM
CS	2F-24	CFM-stpt
AI	2F-23	Zone-T
AD	2F-23	ActHtgSP
AD	2F-23	CFM
CS	2F-23	CFM-stpt
AI	2F-22	Zone-T
AD	2F-22	ActHtgSP
AD	2F-22	CFM
CS	2F-22	CFM-stpt
AI	2F-21	Zone-T
AD	2F-21	ActHtgSP
AD	2F-21	CFM
CS	2F-21	CFM-stpt
AI	2F-20	Zone-T
AD	2F-20	ActHtgSP
AD	2F-20	CFM
CS	2F-20	CFM-stpt
AI	2F-19	Zone-T
AD	2F-19	ActHtgSP
AD	2F-19	CFM
CS	2F-19	CFM-stpt
AI	2F-18	Zone-T
AD	2F-18	ActHtgSP
AD	2F-18	CFM
CS	2F-18	CFM-stpt
AI	2F-17	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2F-17	ActHtgSP
AD	2F-17	CFM
CS	2F-17	CFM-stpt
AI	2F-16	Zone-T
AD	2F-16	ActHtgSP
AD	2F-16	CFM
CS	2F-16	CFM-stpt
AI	2F-15	Zone-T
AD	2F-15	ActHtgSP
AD	2F-15	CFM
CS	2F-15	CFM-stpt
AI	2F-14	Zone-T
AD	2F-14	ActHtgSP
AD	2F-14	CFM
CS	2F-14	CFM-stpt
AI	2F-13	Zone-T
AD	2F-13	ActHtgSP
AD	2F-13	CFM
CS	2F-13	CFM-stpt
AI	2F-12	Zone-T
AD	2F-12	ActHtgSP
AD	2F-12	CFM
CS	2F-12	CFM-stpt
AI	2F-11	Zone-T
AD	2F-11	ActHtgSP
AD	2F-11	CFM
CS	2F-11	CFM-stpt
AI	2F-10	Zone-T
AD	2F-10	ActHtgSP
AD	2F-10	CFM
CS	2F-10	CFM-stpt
AI	2F-09	Zone-T
AD	2F-09	ActHtgSP
AD	2F-09	CFM
CS	2F-09	CFM-stpt
AI	2F-08	Zone-T
AD	2F-08	ActHtgSP
AD	2F-08	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2F-08	CFM-stpt
AI	2F-07	Zone-T
AD	2F-07	ActHtgSP
AD	2F-07	CFM
CS	2F-07	CFM-stpt
AI	2F-06	Zone-T
AD	2F-06	ActHtgSP
AD	2F-06	CFM
CS	2F-06	CFM-stpt
AI	2F-05	Zone-T
AD	2F-05	ActHtgSP
AD	2F-05	CFM
CS	2F-05	CFM-stpt
AI	2F-04	Zone-T
AD	2F-04	ActHtgSP
AD	2F-04	CFM
CS	2F-04	CFM-stpt
AI	2F-03	Zone-T
AD	2F-03	ActHtgSP
AD	2F-03	CFM
CS	2F-03	CFM-stpt
AI	2F-02	Zone-T
AD	2F-02	ActHtgSP
AD	2F-02	CFM
CS	2F-02	CFM-stpt
AI	2F-01	Zone-T
AD	2F-01	ActHtgSP
AD	2F-01	CFM
CS	2F-01	CFM-stpt
AI	2F-67	Zone-T
AD	2F-67	CFM
CS	2F-67	CFM-stpt
AI	2F-52	Zone-T
AD	2F-52	ActHtgSP
AD	2F-52	CFM
CS	2F-52	CFM-stpt
AI	2F-52	Zone-H
CS	2F-52	Hum-stpt

DRAFT

Building 2		
Points	Equipment	Type
AOS	2F-52	Hum-vlv
BI	2F-52	Air-flow
BO	2F-52	Hum-iso
BD	AHU-2501	OCC
BI	AHU-2501	SF-S
BI	AHU-2501	RF-S
AI	AHU-2501	DA-T
AD	AHU-2501	DA-STPT
AOS	AHU-2501	HTG-VLV
BD	AHU-2501	HTG-PMP
AOS	AHU-2501	CLG-VLV
AOS	AHU-2501	OA-DMPR
AI	AHU-2501	MA-T
AI	AHU-2501	RA-T
AI	AHU-2501	OA-T
BI	AHU-2501	LT-ALM
BI	AHU-2501	PURGE
BI	AHU-2501	SHTDWN
BD	AHU-2501	CLG-LOCK
BI	AHU-2501	HAND
AI	AHU-2501	RA-H
AOS	AHU-2501	HUM-VLV
AI	AHU-2501	PRE
AI	AHU-2501	AFT
AI	AHU-2501	HWS
AI	AHU-2501	HWR
AI	AHU-2501	CWS
AI	AHU-2501	CWR
AD	AHU-2501	L-ZONE-T
AD	AHU-2501	H-ZONE-T
AD	AHU-2501	A-ZONE-T
BO	AHU-2501	SF-C
BO	AHU-2501	RF-C
BO	AHU-2501	EF3_39-C
BI	AHU-2501	EF3_39
BO	AHU-2501	EF3_40-C
BI	AHU-2501	EF3_40
BD	AHU-2501	EF3_41

DRAFT

Building 2		
Points	Equipment	Type
BO	AHU-2501	EF3_42-C
BI	AHU-2501	EF3_42
BD	AHU-2501	EF3_46
BD	AHU-2501	EF3_47
BO	AHU-2501	EF3_62-C
BI	AHU-2501	EF3_62
BD	AHU-2501	NITEPURG
BO	SHARE08	EF3_05-C
BI	SHARE08	EF3_05
BO	SHARE08	EF3_07-C
BI	SHARE08	EF3_07
BO	SHARE08	EF3_15-C
BI	SHARE08	EF3_15
BO	SHARE08	EF3_16-C
BI	SHARE08	EF3_16
BO	SHARE08	EF3_23-C
BI	SHARE08	EF3_23
BO	SHARE08	EF3_25-C
BI	SHARE08	EF3_25
JCB	JCB-NC08	2501-SMK
JCB	JCB-NC08	2501-PMP
JCB	JCB-NC08	2501AITB
JCB	JCB-NC08	25_01EF
JCB	JCB-NC08	HYPERB
JCB	JCB-NC08	2501-OCC
JCB	JCB-NC08	25_01-TE
AI	2F-51	Zone-T
AD	2F-51	CFM
CS	2F-51	CFM-stpt
AI	FCU-1	RA-T
AI	FCU-1	DA-T
AOS	FCU-1	Clg-CMD
AOS	FCU-1	HTG-CMD
BO	FCU-1	FCU-CMD
BI	FCU-1	FCU-S
AOS	FCU-1	HTG-STPT
AOS	FCU-1	CLG-STPT
AI	FCU-2	RA-T

DRAFT

Building 2		
Points	Equipment	Type
AI	FCU-2	DA-T
AOS	FCU-2	HTG-CMD
AOS	FCU-2	CLG-CMD
BO	FCU-2	FCU-CMD
BI	FCU-2	FCU-S
AOS	FCU-2	HTG-STPT
AOS	FCU-2	CLG-STPT
AI	FCU-4	RA-T
AI	FCU-4	DA-T
AOS	FCU-4	CLG-CMD
AOS	FCU-4	HTG-CMD
BO	FCU-4	FCU-CMD
BI	FCU-4	FCU-S
AOS	FCU-4	HTG-STPT
AOS	FCU-4	CLG-STPT
AI	FCU-5	RA-T
AI	FCU-5	DA-T
AOS	FCU-5	CLG-CMD
AOS	FCU-5	HTG-CMD
BO	FCU-5	FCU-CMD
BI	FCU-5	FCU-S
AOS	FCU-5	HTG-STPT
AOS	FCU-5	CLG-STPT
AI	FCU-6	RA-T
AI	FCU-6	DA-T
AOS	FCU-6	CLG-CMD
AOS	FCU-6	HTG-CMD
BO	FCU-6	FCU-CMD
BI	FCU-6	FCU-S
AOS	FCU-6	HTG-STPT
AOS	FCU-6	CLG-STPT
AI	FCU-7	RA-T
AI	FCU-7	DA-T
AOS	FCU-7	CLG-CMD
AOS	FCU-7	HTG-CMD
BO	FCU-7	FCU-CMD
BI	FCU-7	FCU-S
AOS	FCU-7	HTG-STPT

DRAFT

Building 2		
Points	Equipment	Type
AOS	FCU-7	CLG-STPT
AI	FCU-8	RA-T
AI	FCU-8	DA-T
AOS	FCU-8	CLG-CMD
AOS	FCU-8	HTG-CMD
BO	FCU-8	FCU-CMD
BI	FCU-8	FCU-S
AOS	FCU-8	HTG-STPT
AOS	FCU-8	CLG-STPT
AI	FCU-9	RA-T
AI	FCU-9	DA-T
AOS	FCU-9	CLG-CMD
AOS	FCU-9	HTG-CMD
BO	FCU-9	FCU-CMD
BI	FCU-9	FCU-S
AOS	FCU-9	HTG-STPT
AOS	FCU-9	CLG-STPT
AOS	FCU-3	HTG-STPT
AI	FCU-3	RA-T
AOS	FCU-3	CLG-STPT
BD	FCU-3	_
AI	FCU-3	DA-T
BD	FCU-3	__
AOS	FCU-3	CLG-CMD
AOS	FCU-3	HTG-CMD
BD	FCU-3	___
BO	FCU-3	FCU-CMD
BI	FCU-3	FCU-S

Building 2		
Points	**Equipment**	**Type**
NC-9		**Network controller**
NC-9-HW	CVR-13	13, 1, 3, VAV
NC-9-HW	CVR-14	14, 1, 3, VAV
NC-9-HW	CVR-15	15, 1, 3, VAV
NC-9-HW	CVR-16	16, 1, 3, VAV
NC-9-HW	CVR-17	17, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-9-HW	CVR-18	18, 1, 3, VAV
NC-9-HW	CVR-19	19, 1, 3, VAV
NC-9-HW	CVR-20	20, 1, 3, VAV
NC-9-HW	CVR-21	21, 1, 3, VAV
NC-9-HW	CVR-22	22, 1, 3, VAV
NC-9-HW	CVR-23	23, 1, 3, VAV
NC-9-HW	CVR-24	24, 1, 3, VAV
NC-9-HW	CVR-25	25, 1, 3, VAV
NC-9-HW	CVR-26	26, 1, 3, VAV
NC-9-HW	CVR-27	27, 1, 3, VAV
NC-9-HW	CVR-28	28, 1, 3, VAV
NC-9-HW	CVR-29	29, 1, 3, VAV
NC-9-HW	CVR-30	30, 1, 3, VAV
NC-9-HW	CVR-31	31, 1, 3, VAV
NC-9-HW	CVR-32	32, 1, 3, VAV
NC-9-HW	CVR-33	33, 1, 3, VAV
NC-9-HW	CVR-34	34, 1, 3, VAV
NC-9-HW	CVR-35	35, 1, 3, VAV
NC-9-HW	CVR-36	36, 1, 3, VAV
NC-9-HW	CVR-37	37, 1, 3, VAV
NC-9-HW	CVR-38	38, 1, 3, VAV
NC-9-HW	CVR-39	39, 1, 3, VAV
NC-9-HW	CVR-40	40, 1, 3, VAV
NC-9-HW	CVR-41	41, 1, 3, VAV
NC-9-HW	CVR-42	42, 1, 3, VAV
NC-9-HW	CVR-43	43, 1, 3, VAV
NC-9-HW	CVR-44	44, 1, 3, VAV
NC-9-HW	CVR-45	45, 1, 3, VAV
NC-9-HW	CVR-46	46, 1, 3, VAV
NC-9-HW	CVR-47	47, 1, 3, VAV
NC-9-HW	CVR-48	48, 1, 3, VAV
NC-9-HW	CVR-49	49, 1, 3, VAV
NC-9-HW	CVR-50	50, 1, 3, VAV
NC-9-HW	CVR-51	51, 1, 3, VAV
NC-9-HW	CVR-52	52, 1, 3, VAV
NC-9-HW	CVR-53	53, 1, 3, VAV
NC-9-HW	CVR-54	54, 1, 3, VAV
NC-9-HW	CVR-55	55, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-9-HW	CVR-56	56, 1, 3, VAV
NC-9-HW	CVR-57	57, 1, 3, VAV
NC-9-HW	CVR-58	58, 1, 3, VAV
NC-9-HW	CVR-59	59, 1, 3, VAV
NC-9-HW	CVR-60	60, 1, 3, VAV
NC-9-HW	CVR-61	61, 1, 3, VAV
NC-9-HW	CVR-62	62, 1, 3, VAV
NC-9-HW	CVR-63	63, 1, 3, VAV
NC-9-HW	CVR-98	98, 1, 3, VAV
NC-9-HW	CVR-99	99, 1, 3, VAV
NC-9-HW	CVR-100	100, 1, 3, VAV
NC-9-HW	CVR-101	101, 1, 3, VAV
NC-9-HW	CVR-102	102, 1, 3, VAV
NC-9-HW	CVR-103	103, 1, 3, VAV
NC-9-HW	CVR-104	104, 1, 3, VAV
NC-9-HW	CVR-105	105, 1, 3, VAV
NC-9-HW	CVR-106	106, 1, 3, VAV
NC-9-HW	CVR-107	107, 1, 3, VAV
NC-9-HW	CVR-108	108, 1, 3, VAV
NC-9-HW	CVR-109	109, 1, 3, VAV
NC-9-HW	CVR-110	110, 1, 3, VAV
NC-9-HW	CVR-111	111, 1, 3, VAV
NC-9-HW	CVR-112	112, 1, 3, VAV
NC-9-HW	CVR-113	113, 1, 3, VAV
NC-9-HW	CVR-114	114, 1, 3, VAV
NC-9-HW	DC9-128	128, 1, 3, UNT
NC-9-HW	ISO-205	205, 1, 3, VND
NC-9-HW	FCU-115	115, 1, 3, UNT
NC-9-HW	FCU-116	116, 1, 3, UNT
NC-9-HW	fcu-117	117, 1, 3, UNT
NC-9-HW	fcu-118	118, 1, 3, UNT
NC-9-HW	FCU-119	119, 1, 3, UNT
NC-9-HW	FCU-120	120, 1, 3, UNT
NC-9-HW	FCU-121	121, 1, 3, UNT
NC-9-HW	FCU-122	122, 1, 3, UNT
NC-9-HW	FCU-123	123, 1, 3, UNT
NC-9-HW	FCU-124	124, 1, 3, UNT
BD	CHKPT	CH1-S

DRAFT

Building 2		
Points	Equipment	Type
BD	CHKPT	CH2-S
BD	CHKPT	CH3-S
BD	CHKPT	CH4A-S
BD	CHKPT	CH4B-S
AD	CHKPT	CWS-T
AD	CHKPT	SYS_PRES
AD	CHKPT	CWBYP-FW
AD	CHKPT	CWBYP-R
AD	CHKPT	LOAD-#1
AD	CHKPT	LOAD-#2
AD	CHKPT	LOAD-#3
AD	CHKPT	LOAD-#4A
AD	CHKPT	LOAD-#4B
AD	CHKPT	#1CWS-T
AD	CHKPT	#2CWS-T
AD	CHKPT	#3CWS-T
AD	CHKPT	#4ACWS-T
AD	CHKPT	#4BCWS-T
AD	CHKPT	CTS-T
AD	CHKPT	CTR-T
BD	CHKPT	CTP1-S
BD	CHKPT	CTP2-S
BD	CHKPT	CTP3-S
BD	CHKPT	CTP4-S
AD	CHKPT	HWS-T
AD	CHKPT	HW_PRES
AD	CHKPT	HWS-T1
AD	CHKPT	HWS-T2
AD	CHKPT	HWS-T3
AD	CHKPT	HXCWS-T
AD	CHKPT	HXCWR-T
BD	CHKPT	P12_2-S
BD	CHKPT	P12_3-S
BD	CHKPT	P13_3-S
BD	CHKPT	P13_4-S
AD	CHKPT	HX_CWS-T
AD	CHKPT	1E-201-T
AD	CHKPT	RM-T

DRAFT

Building 2		
Points	Equipment	Type
AD	CHKPT	OA-Temp
BO	SHARE09	EF3_68-C
BI	SHARE09	EF3_68
AI	2D-13	Zone-T
AD	2D-13	ActHtgSP
AD	2D-13	CFM
CS	2D-13	CFM-stpt
AI	2D-14	Zone-T
AD	2D-14	ActHtgSP
AD	2D-14	CFM
CS	2D-14	CFM-stpt
AI	2D-15	Zone-T
AD	2D-15	ActHtgSP
AD	2D-15	CFM
CS	2D-15	CFM-stpt
AI	2D-16	Zone-T
AD	2D-16	ActHtgSP
AD	2D-16	CFM
CS	2D-16	CFM-stpt
AI	2D-17	Zone-T
AD	2D-17	ActHtgSP
AD	2D-17	CFM
CS	2D-17	CFM-stpt
AI	2D-18	Zone-T
AD	2D-18	ActHtgSP
AD	2D-18	CFM
CS	2D-18	CFM-stpt
AI	2D-19	Zone-T
AD	2D-19	ActHtgSP
AD	2D-19	CFM
CS	2D-19	CFM-stpt
AI	2D-20	Zone-T
AD	2D-20	ActHtgSP
AD	2D-20	CFM
CS	2D-20	CFM-stpt
AI	2D-21	Zone-T
AD	2D-21	ActHtgSP
AD	2D-21	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2D-21	CFM-stpt
AI	2D-22	Zone-T
AD	2D-22	ActHtgSP
AD	2D-22	CFM
CS	2D-22	CFM-stpt
AI	2D-23	Zone-T
AD	2D-23	ActHtgSP
AD	2D-23	CFM
CS	2D-23	CFM-stpt
AI	2D-24	Zone-T
AD	2D-24	ActHtgSP
AD	2D-24	CFM
CS	2D-24	CFM-stpt
AI	2D-25	Zone-T
AD	2D-25	ActHtgSP
AD	2D-25	CFM
CS	2D-25	CFM-stpt
AI	2D-26	Zone-T
AD	2D-26	ActHtgSP
AD	2D-26	CFM
CS	2D-26	CFM-stpt
AI	2D-27	Zone-T
AD	2D-27	ActHtgSP
AD	2D-27	CFM
CS	2D-27	CFM-stpt
AI	2D-28	Zone-T
AD	2D-28	ActHtgSP
AD	2D-28	CFM
CS	2D-28	CFM-stpt
AI	2D-29	Zone-T
AD	2D-29	ActHtgSP
AD	2D-29	CFM
CS	2D-29	CFM-stpt
AI	2D-30	Zone-T
AD	2D-30	ActHtgSP
AD	2D-30	CFM
CS	2D-30	CFM-stpt
AI	2D-31	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2D-31	ActHtgSP
AD	2D-31	CFM
CS	2D-31	CFM-stpt
AI	2D-32	Zone-T
AD	2D-32	ActHtgSP
AD	2D-32	CFM
CS	2D-32	CFM-stpt
AI	2D-33	Zone-T
AD	2D-33	ActHtgSP
AD	2D-33	CFM
CS	2D-33	CFM-stpt
AI	2D-34	Zone-T
AD	2D-34	ActHtgSP
AD	2D-34	CFM
CS	2D-34	CFM-stpt
AI	2D-35	Zone-T
AD	2D-35	ActHtgSP
AD	2D-35	CFM
CS	2D-35	CFM-stpt
AI	2D-36	Zone-T
AD	2D-36	ActHtgSP
AD	2D-36	CFM
CS	2D-36	CFM-stpt
AI	2D-37	Zone-T
AD	2D-37	ActHtgSP
AD	2D-37	CFM
CS	2D-37	CFM-stpt
AI	2D-38	Zone-T
AD	2D-38	ActHtgSP
AD	2D-38	CFM
CS	2D-38	CFM-stpt
AI	2D-39	Zone-T
AD	2D-39	ActHtgSP
AD	2D-39	CFM
CS	2D-39	CFM-stpt
AI	2D-40	Zone-T
AD	2D-40	ActHtgSP
AD	2D-40	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2D-40	CFM-stpt
AI	2D-41	Zone-T
AD	2D-41	ActHtgSP
AD	2D-41	CFM
CS	2D-41	CFM-stpt
AI	2D-42	Zone-T
AD	2D-42	ActHtgSP
AD	2D-42	CFM
CS	2D-42	CFM-stpt
AI	2D-43	Zone-T
AD	2D-43	ActHtgSP
AD	2D-43	CFM
CS	2D-43	CFM-stpt
AI	2D-44	Zone-T
AD	2D-44	ActHtgSP
AD	2D-44	CFM
CS	2D-44	CFM-stpt
AI	2D-45	Zone-T
AD	2D-45	ActHtgSP
AD	2D-45	CFM
CS	2D-45	CFM-stpt
AI	2D-46	Zone-T
AD	2D-46	ActHtgSP
AD	2D-46	CFM
CS	2D-46	CFM-stpt
AI	2D-47	Zone-T
AD	2D-47	ActHtgSP
AD	2D-47	CFM
CS	2D-47	CFM-stpt
AI	2D-48	Zone-T
AD	2D-48	ActHtgSP
AD	2D-48	CFM
CS	2D-48	CFM-stpt
AI	2D-49	Zone-T
AD	2D-49	ActHtgSP
AD	2D-49	CFM
CS	2D-49	CFM-stpt
AI	2D-50	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2D-50	ActHtgSP
AD	2D-50	CFM
CS	2D-50	CFM-stpt
AI	2D-51	Zone-T
AD	2D-51	ActHtgSP
AD	2D-51	CFM
CS	2D-51	CFM-stpt
AI	2D-52	Zone-T
AD	2D-52	ActHtgSP
AD	2D-52	CFM
CS	2D-52	CFM-stpt
AI	2D-53	Zone-T
AD	2D-53	ActHtgSP
AD	2D-53	CFM
CS	2D-53	CFM-stpt
AI	2D-54	Zone-T
AD	2D-54	ActHtgSP
AD	2D-54	CFM
CS	2D-54	CFM-stpt
AI	2D-56	Zone-T
AD	2D-56	ActHtgSP
AD	2D-56	CFM
CS	2D-56	CFM-stpt
AI	2D-57	Zone-T
AD	2D-57	ActHtgSP
AD	2D-57	CFM
CS	2D-57	CFM-stpt
AI	2D-58	Zone-T
AD	2D-58	ActHtgSP
AD	2D-58	CFM
CS	2D-58	CFM-stpt
AI	2D-59	Zone-T
AD	2D-59	ActHtgSP
AD	2D-59	CFM
CS	2D-59	CFM-stpt
AI	2D-60	Zone-T
AD	2D-60	ActHtgSP
AD	2D-60	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2D-60	CFM-stpt
AI	2D-61	Zone-T
AD	2D-61	ActHtgSP
AD	2D-61	CFM
CS	2D-61	CFM-stpt
AI	2D-62	Zone-T
AD	2D-62	ActHtgSP
AD	2D-62	CFM
CS	2D-62	CFM-stpt
AI	2D-63	Zone-T
AD	2D-63	ActHtgSP
AD	2D-63	CFM
CS	2D-63	CFM-stpt
AI	2F-34	Zone-T
AD	2F-34	ActHtgSP
AD	2F-34	CFM
CS	2F-34	CFM-stpt
AI	2F-36	Zone-T
AD	2F-36	ActHtgSP
AD	2F-36	CFM
CS	2F-36	CFM-stpt
AI	2F-37	Zone-T
AD	2F-37	ActHtgSP
AD	2F-37	CFM
CS	2F-37	CFM-stpt
AI	2F-38	Zone-T
AD	2F-38	ActHtgSP
AD	2F-38	CFM
CS	2F-38	CFM-stpt
AI	2F-39	Zone-T
AD	2F-39	ActHtgSP
AD	2F-39	CFM
CS	2F-39	CFM-stpt
AI	2F-40	Zone-T
AD	2F-40	ActHtgSP
AD	2F-40	CFM
CS	2F-40	CFM-stpt
AI	2F-41	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2F-41	ActHtgSP
AD	2F-41	CFM
CS	2F-41	CFM-stpt
AI	2F-42	Zone-T
AD	2F-42	ActHtgSP
AD	2F-42	CFM
CS	2F-42	CFM-stpt
AI	2F-43	Zone-T
AD	2F-43	ActHtgSP
AD	2F-43	CFM
CS	2F-43	CFM-stpt
AI	2F-44	Zone-T
AD	2F-44	ActHtgSP
AD	2F-44	CFM
CS	2F-44	CFM-stpt
AI	2F-45	Zone-T
AD	2F-45	ActHtgSP
AD	2F-45	CFM
CS	2F-45	CFM-stpt
AI	2F-46	Zone-T
AD	2F-46	ActHtgSP
AD	2F-46	CFM
CS	2F-46	CFM-stpt
AI	2F-47	Zone-T
AD	2F-47	ActHtgSP
AD	2F-47	CFM
CS	2F-47	CFM-stpt
AI	2F-48	Zone-T
AD	2F-48	ActHtgSP
AD	2F-48	CFM
CS	2F-48	CFM-stpt
AI	2F-49	Zone-T
AD	2F-49	ActHtgSP
AD	2F-49	CFM
CS	2F-49	CFM-stpt
AI	2F-50	Zone-T
AD	2F-50	ActHtgSP
AD	2F-50	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2F-50	CFM-stpt
AI	2D-55	Zone-T
AD	2D-55	ActHtgSP
AD	2D-55	CFM
CS	2D-55	CFM-stpt
AI	2D-55	RM-PRESS
CS	2D-55	MODE
BD	2D-55	ALM
BD	2D-55	EF7_14
BD	EF_1st	EF1_01
BD	EF_1st	EF1_02
BD	EF_1st	EF1_03
BD	EF_1st	EF1_04
BD	EF_1st	EF1_05
BD	EF_3rd	EF3_01
BD	EF_3rd	EF3_02
BD	EF_3rd	EF3_03
BD	EF_3rd	EF3_04
BD	EF_3rd	EF3_05
BD	EF_3rd	EF3_06
BD	EF_3rd	EF3_07
BD	EF_3rd	EF3_09
BD	EF_3rd	EF3_10
BD	EF_3rd	EF3_11
BD	EF_3rd	EF3_12
BD	EF_3rd	EF3_13
BD	EF_3rd	EF3_14
BD	EF_3rd	EF3_15
BD	EF_3rd	EF3_16
BD	EF_3rd	EF3_17
BD	EF_3rd	EF3_19
BD	EF_3rd	EF3_20
BD	EF_3rd	EF3_21
BD	EF_3rd	EF3_22
BD	EF_3rd	EF3_23
BD	EF_3rd	EF3_24
BD	EF_3rd	EF3_25
BD	EF_3rd	EF3_26

DRAFT

Building 2		
Points	Equipment	Type
BD	EF_3rd	EF3_27
BD	EF_3rd	EF3_28
BD	EF_3rd	EF3_29
BD	EF_3rd	EF3_30
BD	EF_3rd	EF3_31
BD	EF_3rd	EF3_32
BD	EF_3rd	EF3_33
BD	EF_3rd	EF3_34
BD	EF_3rd	EF3_35
BD	EF_4th	EF4_01
BD	EF_4th	EF4_02
BD	EF_4th	EF4_03
BD	EF_4th	EF4_04
BD	EF_4th	EF4_05
BD	EF_4th	EF4_06
BD	EF_4th	EF4_07
BD	EF_4th	EF4_08
BD	EF_4th	EF4_09
BD	EF_4th	EF4_10
BD	EF_4th	EF4_11
BD	EF_4th	EF4_12
BD	EF_4th	EF4_18
BD	EF_4th	EF4_19
BD	EF_4th	EF4_20
BD	EF_4th	EF4_22
BD	EF_4th	EF4_23
BD	EF_4th	EF4_24
BD	EF_4th	EF4_25
AD	EF_4th	EF4_26
BD	EF_5th	EF5_01
BD	EF_5th	EF5_02
BD	EF_5th	EF5_03
BD	EF_5th	EF5_04
BD	EF_5th	EF5_05
BD	EF_5th	EF5_06
BD	EF_5th	EF5_07
BD	EF_5th	EF5_09
BD	EF_5th	EF5_10

DRAFT

Building 2		
Points	Equipment	Type
BD	EF_5th	EF5_12
BD	EF_5th	EF5_13
BD	EF_5th	EF5_14
BD	EF_5th	EF5_16
BD	EF_5th	EF5_18
BD	EF_5th	EF5_20
BD	EF_5th	EF5_21
BD	EF_5th	EF5-23
BD	EF_5th	EF5_24
BD	EF_5th	EF5_26
BD	EF_5th	EF5_27
BD	EF_5th	EF5_28
BD	EF_5th	EF5_29
BD	EF_5th	EF5_30
BD	EF_5th	EF5_31
BD	EF-5th	EF5_32
BD	EF-5th	EF5_33
BD	EF-5th	EF5_34
BD	EF-5th	EF5_35
BD	EF-5th	EF5_36
BD	EF-5th	EF5_37
BD	EF-5th	EF5_38
BD	EF-5th	EF5_39
BD	EF-5th	EF5_40
BD	EF-5th	EF5_41
BD	EF-5th	EF5_42
BD	EF-5th	EF5_43
BD	EF-5th	EF5_44
BD	EF-5th	EF5_45
BD	EF-5th	EF5_49
BD	EF-5th	EF5_50
BD	EF-5th	EF5_52
BD	EF-5th	EF5_54
BD	EF-5th	EF5_55
BD	EF-5th	EF5_56
BD	EF-5th	EF5_57
BD	EF-5th	EF5_58
BD	EF-5th	EF5_59

DRAFT

Building 2		
Points	Equipment	Type
BD	EF-5th	EF5_60
BD	EF-5th	EF5_61
BD	EF-5th	EF5_62
BD	EF_5	EF55_02
BD	EF_5	EF55_03
BD	EF_8th	EF8_01
BD	EF-3rd	EF3_37
BD	EF-3rd	EF3_40
BD	EF-3rd	EF3_41
BD	EF-3rd	EF3_42
BD	EF-3rd	EF3_43
BD	EF-3rd	EF3_44
BD	EF-3rd	EF3_45
BD	EF-3rd	EF3_46
BD	EF-3rd	EF3_47
BD	EF-3rd	EF3_48
BD	EF-3rd	EF3_49
BD	EF-3rd	EF3_50
BD	EF-3rd	EF3_51
BD	EF-3rd	EF3_52
BD	EF-3rd	EF3_53
BD	EF-3rd	EF3_54
BD	EF-3rd	EF3_59
BD	EF-3rd	EF3_60
BD	EF-3rd	EF3_61
BD	EF-3rd	EF3_62
BD	EF-3rd	EF3_63
BD	EF-3rd	EF3_64
BD	EF-3rd	EF3_65
BD	EF-3rd	EF3_68
BD	EF-3rd	EF3_69
BD	EF-3rd	EF3_70
AD	EF-3rd	EF3_71
BD	EF-3rd	EF3_73
BD	EF-3rd	EF3_74
BD	EF-3rd	EF3_75
AI	FCU1	RA-T
AI	FCU1	DA-T

DRAFT

Building 2		
Points	Equipment	Type
AOS	FCU1	CLG-CMD
AOS	FCU1	HTG-CMD
BO	FCU1	FCU-CMD
BI	FCU1	FCU-S
AOS	FCU1	HTG-STPT
AOS	FCU1	CLG-STPT
AI	FCU2	RA-T
AI	FCU2	DA-T
AOS	FCU2	CLG-CMD
AOS	FCU2	HTG-CMD
BO	FCU2	FCU-CMD
BI	FCU2	FCU-S
AOS	FCU2	HTG-STPT
AOS	FCU2	CLG-STPT
AI	FCU3	RA-T
AI	FCU3	DA-T
AOS	FCU3	CLG-CMD
AOS	FCU3	HTG-CMD
BO	FCU3	FCU-CMD
BI	FCU3	FCU-S
AOS	FCU3	HTG-STPT
AOS	FCU3	CLG-STPT
AI	FCU4	RA-T
AI	FCU4	DA-T
AOS	FCU4	CLG-CMD
AOS	FCU4	HTG-CMD
BO	FCU4	FCU-CMD
BI	FCU4	FCU-S
AOS	FCU4	HTG-STPT
AOS	FCU4	CLG-STPT
AI	FCU5	RA-T
AI	FCU5	DA-T
AOS	FCU5	CLG-CMD
AOS	FCU5	HTG-CMD
BO	FCU5	FCU-CMD
BI	FCU5	FCU-S
AOS	FCU5	HTG-STPT
AOS	FCU5	CLG-STPT

DRAFT

Building 2		
Points	Equipment	Type
AI	FCU6	RA-T
AI	FCU6	DA-T
AOS	FCU6	HTG-CMD
AOS	FCU6	CLG-CMD
AOS	FCU6	HTG-STPT
AOS	FCU6	CLG-STPT
BO	FCU6	FCU-CMD
BI	FCU6	FCU-S
AI	FCU7	RA-T
AI	FCU7	DA-T
AOS	FCU7	CLG-CMD
AOS	FCU7	HTG-CMD
BO	FCU7	FCU-CMD
BI	FCU7	FCU-S
AOS	FCU7	HTG-STPT
AOS	FCU7	CLG-STPT
AI	FCU8	RA-T
AI	FCU8	DA-T
AOS	FCU8	CLG-CMD
AOS	FCU8	HTG-CMD
BO	FCU8	FCU-CMD
BI	FCU8	FCU-S
AOS	FCU8	HTG-STPT
AOS	FCU8	CLG-STPT
AI	FCU9	RA-T
AI	FCU9	DA-T
AOS	FCU9	CLG-CMD
AOS	FCU9	HTG-CMD
BO	FCU9	FCU-CMD
BI	FCU9	FCU-S
AOS	FCU9	HTG-STPT
AOS	FCU9	CLG-STPT
AI	FCU12	RA-T
AI	FCU12	DA-T
AOS	FCU12	CLG-CMD
AOS	FCU12	HTG-CMD
BO	FCU12	FCU-CMD
BI	FCU12	FCU-S

DRAFT

Building 2		
Points	Equipment	Type
AOS	FCU12	HTG-STPT
AOS	FCU12	CLG-STPT
AI	FCU11	RA-T
AI	FCU11	DA-T
AOS	FCU11	CLG-CMD
AOS	FCU11	HTG-CMD
BO	FCU11	FCU-CMD
BI	FCU11	FCU-S
AOS	FCU11	HTG-STPT
AOS	FCU11	CLG-STPT
AI	FCU13	RA-T
AI	FCU13	DA-T
AOS	FCU13	CLG-CMD
AOS	FCU13	HTG-CMD
BO	FCU13	FCU-CMD
BI	FCU13	FCU-S
AOS	FCU13	HTG-STPT
AOS	FCU13	CLG-STPT
AI	FCU14	RA-T
AI	FCU14	DA-T
AOS	FCU14	HTG-CMD
AOS	FCU14	CLG-CMD
AOS	FCU14	HTG-STPT
AOS	FCU14	CLG-STPT
BO	FCU14	FCU-CMD
BI	FCU14	FCU-S
AI	FCU15	RA-T
AI	FCU15	DA-T
AOS	FCU15	CLG-CMD
AOS	FCU15	HTG-CMD
BO	FCU15	FCU-CMD
BI	FCU15	FCU-S
AOS	FCU15	HTG-STPT
AOS	FCU15	CLG-STPT
AI	FCU16	RA-T
AI	FCU16	DA-T
AOS	FCU16	CLG-CMD
AOS	FCU16	HTG-CMD

DRAFT

Building 2		
Points	Equipment	Type
BO	FCU16	FCU-CMD
BI	FCU16	FCU-S
AOS	FCU16	HTG-STPT
AOS	FCU16	CLG-STPT
AI	FCU17	RA-T
AI	FCU17	DA-T
AOS	FCU17	CLG-CMD
AOS	FCU17	HTG-CMD
BO	FCU17	FCU-CMD
BI	FCU17	FCU-S
AOS	FCU17	HTG-STPT
AOS	FCU17	CLG-STPT
AI	FCU18	RA-T
AI	FCU18	DA-T
AOS	FCU18	HTG-CMD
AOS	FCU18	CLG-CMD
BO	FCU18	FCU-CMD
BI	FCU18	FCU-S
AOS	FCU18	HTG-STPT
AOS	FCU18	CLG-STPT
AI	FCU10	RA-T
AI	FCU10	DA-T
AOS	FCU10	HTG-CMD
AOS	FCU10	CLG-CMD
BO	FCU10	FCU-CMD
BI	FCU10	FCU-S
AOS	FCU10	HTG-STPT
AOS	FCU10	CLG-STPT
BD	EF_2nd	EF2_01
BD	EF_2nd	EF2_02
BD	EF_2nd	EF2_04
BD	EF_2nd	EF2_05
BD	EF_2nd	EF2_06
BD	EF_2nd	EF2_07
BD	EF_2nd	EF2_08
BD	EF_2nd	EF2_09
BD	EF_2nd	EF2_10
BD	EF_2nd	EF2_14

DRAFT

Building 2		
Points	Equipment	Type
BD	EF_2nd	EF2_15
BD	EF_2nd	EF2_18
BD	EF_2nd	EF2_19
BD	EF_2nd	EF2_20
BD	EF_2nd	EF2_21
BD	EF_2nd	EF2_22
BD	EF_2nd	EF2_24
BD	EF_2nd	EF2_25
BD	EF_2nd	EF2_26
BD	EF_2nd	EF2_29
BD	EF_2nd	EF2_30
BD	EF_2nd	EF2_31
BD	EF_2nd	EF2_32
AI	2F-35	Zone-T
AD	2F-35	ActHtgSP
AD	2F-35	CFM
CS	2F-35	CFM-stpt
BI	2F-35	AirFlow
AI	2F-35	ZN-H
AOS	2F-35	HUM-C
BD	EF_6th	EF6_01
BD	EF_6th	EF6_02
BD	EF_6th	EF6_03
BD	EF_6th	EF6_04
BD	EF_6th	EF6_05
BD	EF_6th	EF6_06
AD	EF_6th	EF-07DP
BD	EF_6th	EF6_08
BD	EF_6th	EF6_09
BD	EF_6th	EF6_10
BD	EF_6th	EF6_11
BD	EF_6th	EF6_12
BD	EF_6th	EF6_13
BD	EF_6th	EF6_14
BD	EF_6th	EF6_15
BD	EF_6th	EF6_16
BD	EF_6th	EF6_17
BD	EF_6th	EF6_18

DRAFT

Building 2		
Points	Equipment	Type
BD	EF_6th	EF6_19
BD	EF_6th	EF6_20
BD	EF_6th	EF6_21
BD	EF_6th	EF6_23
BD	EF_6th	EF6_24
BD	EF_6th	EF6_25
BD	EF_6th	EF6_26
BD	EF_6th	EF6_27
BD	EF_6th	EF6_28
BD	EF_6th	EF6_29
BD	EF_6th	EF6_30
BD	EF_6th	EF6_31
BD	EF_6th	EF6_32
AD	EF_6th	EF6_33
BD	EF_6th	EF6_34
BD	EF_6th	EF6_35
AD	EF_6th	EF6_36
BD	EF_6th	EF6_38
AD	EF_6th	EF6_39
BD	EF_7th	EF7_01
BD	EF_7th	EF7_03
BD	EF_7th	EF7_04
BD	EF_7th	EF7_05
BD	EF_7th	EF7_06
BD	EF_7th	EF7_07
BD	EF_7th	EF7_09
BD	EF_7th	EF7_10
BD	EF_7th	EF7_11
BD	EF_7th	EF7_12
BD	EF_7th	EF7_14
BD	EF_7th	EF7_15
AD	ISO-MODE	1E46-MOD
AD	ISO-MODE	2D-55MOD
AD	ISO-MODE	2C-14MOD
AD	ISO-MODE	2A-149MD
AD	ISO-MODE	2B-43MOD
AD	ISO-MODE	2B-22MOD
AD	ISO-MODE	3B-31MOD

DRAFT

Building 2		
Points	Equipment	Type
AD	ISO-MODE	3B-32MOD
AD	ISO-MODE	3C-76MOD
AD	ISO-MODE	3E-35MOD
AD	ISO-MODE	3E-36MOD
AD	ISO-MODE	3E-06MOD
AD	ISO-MODE	3E-16MOD
AD	ISO-MODE	3E-17AMD
AD	ISO-MODE	3F-05MOD
AD	ISO-MODE	3E-07MOD
AD	ISO-MODE	3F-06MOD
AD	ISO-MODE	3F-25MOD
AD	ISO-MODE	4F-31MOD
AD	ISO-MODE	4F-03MOD
AD	ISO-MODE	4F-04MOD
AD	ISO-MODE	4F-22MOD
AD	ISO-MODE	4C-70MOD
AD	ISO-MODE	4C-14MOD
AD	ISO-MODE	4C-56MOD
AD	ISO-MODE	4C-67MOD
AD	ISO-MODE	4A-19MOD
AD	ISO-MODE	4A-20MOD
AD	ISO-MODE	4A-38MOD
AD	ISO-MODE	4A-39MOD
AD	ISO-MODE	4B-20MOD
AD	ISO-MODE	4B-21MOD
AD	ISO-MODE	4B-44MOD
AD	ISO-MODE	4B-45MOD
AD	ISO-MODE	4F-16MOD
Building 2		
Points	**Equipment**	**Type**
NC-10	**Network controller**	VMA
NC-10-HW	AHU-2801	200, 1, 3, AHU
NC-10-HW	DC10-201	201, 1, 3, UNT
NC-10-HW	2B-37	255, 1, 3, VAV
NC-10-HW	2B-27	1, 1, 3, VAV
NC-10-HW	2B-26	2, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-10-HW	2B-36	103, 1, 3, VAV
NC-10-HW	2B-25	4, 1, 3, VAV
NC-10-HW	2B-24	5, 1, 3, VAV
NC-10-HW	2B-35	6, 1, 3, VAV
NC-10-HW	2B-06	7, 1, 3, VAV
NC-10-HW	2B-23	8, 1, 3, VAV
NC-10-HW	2B-05	9, 1, 3, VAV
NC-10-HW	2B-22	10, 1, 3, VAV
NC-10-HW	2B-34	11, 1, 3, VAV
NC-10-HW	2B-21	12, 1, 3, VAV
NC-10-HW	2B-02	13, 1, 3, VAV
NC-10-HW	2B-20	14, 1, 3, VAV
NC-10-HW	2B-19	15, 1, 3, VAV
NC-10-HW	2B-18	16, 1, 3, VAV
NC-10-HW	2B-17	17, 1, 3, VAV
NC-10-HW	2B-16	18, 1, 3, VAV
NC-10-HW	2B-15	19, 1, 3, VAV
NC-10-HW	2B-14	20, 1, 3, VAV
NC-10-HW	2D-01	41, 1, 3, VAV
NC-10-HW	2B-67	43, 1, 3, VAV
NC-10-HW	2B-55	44, 1, 3, VAV
NC-10-HW	2D-03	45, 1, 3, VAV
NC-10-HW	2B-54	46, 1, 3, VAV
NC-10-HW	2B-13	47, 1, 3, VAV
NC-10-HW	2B-66	48, 1, 3, VAV
NC-10-HW	2B-53	49, 1, 3, VAV
NC-10-HW	2D-04	50, 1, 3, VAV
NC-10-HW	2B-11	51, 1, 3, VAV
NC-10-HW	2B-65	52, 1, 3, VAV
NC-10-HW	2B-52	53, 1, 3, VAV
NC-10-HW	2D-05	54, 1, 3, VAV
NC-10-HW	2B-63	55, 1, 3, VAV
NC-10-HW	2D-06	56, 1, 3, VAV
NC-10-HW	2B-09	57, 1, 3, VAV
NC-10-HW	2B-61	58, 1, 3, VAV
NC-10-HW	2B-62	59, 1, 3, VAV
NC-10-HW	2B-99	60, 1, 3, VAV
NC-10-HW	2B-51	61, 1, 3, VAV
NC-10-HW	2B-50	62, 1, 3, VAV
NC-10-HW	2B-08	63, 1, 3, VAV
NC-10-HW	2B-07	64, 1, 3, VAV
NC-10-HW	2B-49	65, 1, 3, VAV
NC-10-HW	2B-48	66, 1, 3, VAV
NC-10-HW	2B-60	67, 1, 3, VAV
NC-10-HW	2D-07	68, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-10-HW	2B-59	69, 1, 3, VAV
NC-10-HW	2D-08	70, 1, 3, VAV
NC-10-HW	2B-04	71, 1, 3, VAV
NC-10-HW	2B-58	72, 1, 3, VAV
NC-10-HW	2D-09	73, 1, 3, VAV
NC-10-HW	2B-43	74, 1, 3, VAV
NC-10-HW	2D-10	75, 1, 3, VAV
NC-10-HW	2B-03	76, 1, 3, VAV
NC-10-HW	2B-57	77, 1, 3, VAV
NC-10-HW	2B-56	78, 1, 3, VAV
NC-10-HW	2B-45	79, 1, 3, VAV
NC-10-HW	2B-46	80, 1, 3, VAV
NC-10-HW	2B-44	81, 1, 3, VAV
NC-10-HW	2B-43-82	82, 1, 3, VAV
NC-10-HW	2D-11	83, 1, 3, VAV
NC-10-HW	2B-42	84, 1, 3, VAV
NC-10-HW	2D-12	85, 1, 3, VAV
NC-10-HW	2B-01	87, 1, 3, VAV
NC-10-HW	2B-41	88, 1, 3, VAV
NC-10-HW	2B-33	89, 1, 3, VAV
NC-10-HW	2B-40	90, 1, 3, VAV
NC-10-HW	2B-32	91, 1, 3, VAV
NC-10-HW	2B-31	92, 1, 3, VAV
NC-10-HW	2B-39	93, 1, 3, VAV
NC-10-HW	2B-12	94, 1, 3, VAV
NC-10-HW	2B-38	95, 1, 3, VAV
NC-10-HW	2B-30	96, 1, 3, VAV
NC-10-HW	2B-29	97, 1, 3, VAV
NC-10-HW	2B-10	98, 1, 3, VAV
NC-10-HW	2B-28	99, 1, 3, VAV
NC-10-HW	DC10-101	101, 1, 3, UNT
NC-10-HW	ISO-202	202, 1, 3, VND
NC-10-HW	ISO-203	203, 1, 3, VND
NC-10-HW	ISO-204	204, 1, 3, VND
NC-10-HW	CLNSTM	100, 1, 3, UNT
NC-10-HW	DC10-22	22, 1, 3, UNT
NC-10-HW	DC10-23	23, 1, 3, UNT
NC-10-HW	DC10-24	24, 1, 3, UNT
NC-10-HW	DC10-25	25, 1, 3, UNT
NC-10-HW	DC10-31	31, 1, 3, UNT
NC-10-HW	DC10-32	32, 1, 3, UNT
NC-10-HW	DC10-33	33, 1, 3, UNT
NC-10-HW	DC10-26	26, 1, 3, VND
NC-10-HW	DC10-27	27, 1, 3, VND
NC-10-HW	DC10-28	28, 1, 3, VND

DRAFT

Building 2		
Points	Equipment	Type
NC-10-HW	DC10-29	29, 1, 3, VND
AI	REHEAT	ZN1-T
AI	REHEAT	WC1-ADJ
CS	REHEAT	Z1HTG-SP
AI	REHEAT	ZN1-RH
AI	REHEAT	DA1-T
AOS	REHEAT	HTG1-O
AI	REHEAT	ZN2-T
AI	REHEAT	WC2-ADJ
CS	REHEAT	Z2HTG-SP
AI	REHEAT	ZN2-RH
AI	REHEAT	DA2-T
AOS	REHEAT	HTG2-O
AI	REHEAT	ZN3-T
AI	REHEAT	WC3-ADJ
CS	REHEAT	Z3HTG-SP
AI	REHEAT	ZN3-H
AI	REHEAT	DA3-T
AOS	REHEAT	HTG3-O
AI	REHEAT	ZN4-T
AI	REHEAT	WC4-ADJ
CS	REHEAT	Z4HTG-SP
AI	REHEAT	ZN4-H
AI	REHEAT	DA4-T
AOS	REHEAT	HTG4-O
AI	EAV	ZN1-P
AOS	EAV	ZN1-O
CS	EAV	ZN1-S
AI	EAV	ZN2-P
AOS	EAV	ZN2-O
CS	EAV	ZN2-S
AI	EAV	ZN3-P
AOS	EAV	ZN3-O
CS	EAV	ZN3-S
AI	EAV	ZN4-P
AOS	EAV	ZN4-O
CS	EAV	ZN4-S
BI	FILTERS	FILT1-A
BI	FILTERS	FILT2-A
BI	FILTERS	FILT3-A
BI	FILTERS	FILT4-A
BI	FILTERS	FILT5-A
BI	FILTERS	FILT6-A
BI	FILTERS	FILT7-A
BI	FILTERS	FILT8-A

DRAFT

Building 2		
Points	Equipment	Type
BI	FILTERS	FILT9-A
BI	FILTERS	FILT10-A
BI	FILTERS	FILT11-A
AI	FILTERS	HEPA1
AI	FILTERS	HEPA2
JCB	JCB-NC10	2801-PMP
JCB	JCB-NC10	2801-SMK
BD	JCB-NC10	2801-73
JCB	JCB-NC10	2801AITB
JCB	JCB-NC10	28_01EF
JCB	JCB-NC10	2801-OCC
JCB	JCB-NC10	28_01-TE
BD	AHU-2801	OCC
BI	AHU-2801	SF-S
BI	AHU-2801	RF-S
AI	AHU-2801	DA-T
AD	AHU-2801	DA-STPT
AOS	AHU-2801	HTG-VLV
BD	AHU-2801	HTG-PMP
AOS	AHU-2801	CLG-VLV
AOS	AHU-2801	OA-DMPR
AI	AHU-2801	MA-T
AI	AHU-2801	RA-T
AI	AHU-2801	OA-T
BI	AHU-2801	LT-ALM
BI	AHU-2801	PURGE
BI	AHU-2801	SHTDWN
BD	AHU-2801	CLG-LOCK
BI	AHU-2801	HAND
AI	AHU-2801	RA-H
AOS	AHU-2801	HUM-VLV
AI	AHU-2801	PRE
AI	AHU-2801	AFT
AI	AHU-2801	HWS
AI	AHU-2801	HWR
AI	AHU-2801	CWS
AI	AHU-2801	CWR
AI	AHU-2801	CW-DP
AD	AHU-2801	L-ZONE-T
AD	AHU-2801	H-ZONE-T
AD	AHU-2801	A-ZONE-T
BO	AHU-2801	SF-C
BO	AHU-2801	RF-C
BD	AHU-2801	EF2_12
BD	AHU-2801	EF2_13

DRAFT

Building 2		
Points	Equipment	Type
BD	AHU-2801	EF2_14
BD	AHU-2801	EF2_15
BO	AHU-2801	EF3_13-C
BI	AHU-2801	EF3_13
BO	AHU-2801	EF3_20-C
BI	AHU-2801	EF3_20
BO	AHU-2801	EF3_38-C
BI	AHU-2801	EF3_38
BO	AHU-2801	EF3_71-C
AI	AHU-2801	EF3_71DP
BD	AHU-2801	EF6_32
BD	AHU-2801	NITEPURG
BI	AHU-2801	HI-STM
BI	AHU-2801	LO-STM
BO	SHARE10	EF3_43-C
BI	SHARE10	EF3_43
BO	SHARE10	EF3_75-C
BI	SHARE10	EF3_75-S
BI	SHARE10	EF3_75-F
CS	CS-NC-10	AHU2801
AI	2D-01	Zone-T
AD	2D-01	ActHtgSP
AD	2D-01	CFM
CS	2D-01	CFM-stpt
AI	2D-03	Zone-T
AD	2D-03	ActHtgSP
AD	2D-03	CFM
CS	2D-03	CFM-stpt
AI	2D-04	Zone-T
AD	2D-04	ActHtgSP
AD	2D-04	CFM
CS	2D-04	CFM-stpt
AI	2D-05	Zone-T
AD	2D-05	ActHtgSP
AD	2D-05	CFM
CS	2D-05	CFM-stpt
AI	2D-06	Zone-T
AD	2D-06	ActHtgSP
AD	2D-06	CFM
CS	2D-06	CFM-stpt
AI	2D-07	Zone-T
AD	2D-07	ActHtgSP
AD	2D-07	CFM
CS	2D-07	CFM-stpt
AI	2D-08	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2D-08	ActHtgSP
AD	2D-08	CFM
CS	2D-08	CFM-stpt
AI	2D-09	Zone-T
AD	2D-09	ActHtgSP
AD	2D-09	CFM
CS	2D-09	CFM-stpt
AI	2D-10	Zone-T
AD	2D-10	ActHtgSP
AD	2D-10	CFM
CS	2D-10	CFM-stpt
AI	2D-11	Zone-T
AD	2D-11	ActHtgSP
AD	2D-11	CFM
CS	2D-11	CFM-stpt
AI	2D-12	Zone-T
AD	2D-12	ActHtgSP
AD	2D-12	CFM
CS	2D-12	CFM-stpt
AI	2B-01	Zone-T
AD	2B-01	ActHtgSP
AD	2B-01	CFM
CS	2B-01	CFM-stpt
AI	2B-02	Zone-T
AD	2B-02	ActHtgSP
AD	2B-02	CFM
CS	2B-02	CFM-stpt
AI	2B-03	Zone-T
AD	2B-03	ActHtgSP
AD	2B-03	CFM
CS	2B-03	CFM-stpt
AI	2B-04	Zone-T
AD	2B-04	ActHtgSP
AD	2B-04	CFM
CS	2B-04	CFM-stpt
AI	2B-05	Zone-T
AD	2B-05	ActHtgSP
AD	2B-05	CFM
CS	2B-05	CFM-stpt
AI	2B-06	Zone-T
AD	2B-06	ActHtgSP
AD	2B-06	CFM
CS	2B-06	CFM-stpt
AI	2B-07	Zone-T
AD	2B-07	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	2B-07	CFM
CS	2B-07	CFM-stpt
AI	2B-08	Zone-T
AD	2B-08	ActHtgSP
AD	2B-08	CFM
CS	2B-08	CFM-stpt
AI	2B-09	Zone-T
AD	2B-09	ActHtgSP
AD	2B-09	CFM
CS	2B-09	CFM-stpt
AI	2B-10	Zone-T
AD	2B-10	ActHtgSP
AD	2B-10	CFM
CS	2B-10	CFM-stpt
AI	2B-11	Zone-T
AD	2B-11	ActHtgSP
AD	2B-11	CFM
CS	2B-11	CFM-stpt
AI	2B-12	Zone-T
AD	2B-12	ActHtgSP
AD	2B-12	CFM
CS	2B-12	CFM-stpt
AI	2B-13	Zone-T
AD	2B-13	ActHtgSP
AD	2B-13	CFM
CS	2B-13	CFM-stpt
AI	2B-14	Zone-T
AD	2B-14	ActHtgSP
AD	2B-14	CFM
CS	2B-14	CFM-stpt
AI	2B-15	Zone-T
AD	2B-15	ActHtgSP
AD	2B-15	CFM
CS	2B-15	CFM-stpt
AI	2B-16	Zone-T
AD	2B-16	ActHtgSP
AD	2B-16	CFM
CS	2B-16	CFM-stpt
AI	2B-17	Zone-T
AD	2B-17	ActHtgSP
AD	2B-17	CFM
CS	2B-17	CFM-stpt
AI	2B-18	Zone-T
AD	2B-18	ActHtgSP
AD	2B-18	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2B-18	CFM-stpt
AI	2B-19	Zone-T
AD	2B-19	ActHtgSP
AD	2B-19	CFM
CS	2B-19	CFM-stpt
AI	2B-20	Zone-T
AD	2B-20	ActHtgSP
AD	2B-20	CFM
CS	2B-20	CFM-stpt
AI	2B-21	Zone-T
AD	2B-21	ActHtgSP
AD	2B-21	CFM
CS	2B-21	CFM-stpt
AI	2B-23	Zone-T
AD	2B-23	ActHtgSP
AD	2B-23	CFM
CS	2B-23	CFM-stpt
AI	2B-24	Zone-T
AD	2B-24	ActHtgSP
AD	2B-24	CFM
CS	2B-24	CFM-stpt
AI	2B-25	Zone-T
AD	2B-25	ActHtgSP
AD	2B-25	CFM
CS	2B-25	CFM-stpt
AI	2B-26	Zone-T
AD	2B-26	ActHtgSP
AD	2B-26	CFM
CS	2B-26	CFM-stpt
AI	2B-27	Zone-T
AD	2B-27	ActHtgSP
AD	2B-27	CFM
CS	2B-27	CFM-stpt
AI	2B-28	Zone-T
AD	2B-28	ActHtgSP
AD	2B-28	CFM
CS	2B-28	CFM-stpt
AI	2B-29	Zone-T
AD	2B-29	ActHtgSP
AD	2B-29	CFM
CS	2B-29	CFM-stpt
AI	2B-30	Zone-T
AD	2B-30	ActHtgSP
AD	2B-30	CFM
CS	2B-30	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	2B-31	Zone-T
AD	2B-31	ActHtgSP
AD	2B-31	CFM
CS	2B-31	CFM-stpt
AI	2B-32	Zone-T
AD	2B-32	ActHtgSP
AD	2B-32	CFM
CS	2B-32	CFM-stpt
AI	2B-33	Zone-T
AD	2B-33	ActHtgSP
AD	2B-33	CFM
CS	2B-33	CFM-stpt
AI	2B-34	Zone-T
AD	2B-34	ActHtgSP
AD	2B-34	CFM
CS	2B-34	CFM-stpt
AI	2B-35	Zone-T
AD	2B-35	ActHtgSP
AD	2B-35	CFM
CS	2B-35	CFM-stpt
AI	2B-36	Zone-T
AD	2B-36	ActHtgSP
AD	2B-36	CFM
CS	2B-36	CFM-stpt
AI	2B-37	Zone-T
AD	2B-37	ActHtgSP
AD	2B-37	CFM
CS	2B-37	CFM-stpt
AI	2B-38	Zone-T
AD	2B-38	ActHtgSP
AD	2B-38	CFM
CS	2B-38	CFM-stpt
AI	2B-39	Zone-T
AD	2B-39	ActHtgSP
AD	2B-39	CFM
CS	2B-39	CFM-stpt
AI	2B-40	Zone-T
AD	2B-40	ActHtgSP
AD	2B-40	CFM
CS	2B-40	CFM-stpt
AI	2B-41	Zone-T
AD	2B-41	ActHtgSP
AD	2B-41	CFM
CS	2B-41	CFM-stpt
AI	2B-43-82	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	2B-43-82	ActHtgSP
AD	2B-43-82	CFM
CS	2B-43-82	CFM-stpt
AI	2B-44	Zone-T
AD	2B-44	ActHtgSP
AD	2B-44	CFM
CS	2B-44	CFM-stpt
AI	2B-45	Zone-T
AD	2B-45	ActHtgSP
AD	2B-45	CFM
CS	2B-45	CFM-stpt
AI	2B-46	Zone-T
AD	2B-46	ActHtgSP
AD	2B-46	CFM
CS	2B-46	CFM-stpt
AI	2B-48	Zone-T
AD	2B-48	ActHtgSP
AD	2B-48	CFM
CS	2B-48	CFM-stpt
AI	2B-49	Zone-T
AD	2B-49	ActHtgSP
AD	2B-49	CFM
CS	2B-49	CFM-stpt
AI	2B-50	Zone-T
AD	2B-50	ActHtgSP
AD	2B-50	CFM
CS	2B-50	CFM-stpt
AI	2B-51	Zone-T
AD	2B-51	ActHtgSP
AD	2B-51	CFM
CS	2B-51	CFM-stpt
AI	2B-52	Zone-T
AD	2B-52	ActHtgSP
AD	2B-52	CFM
CS	2B-52	CFM-stpt
AI	2B-53	Zone-T
AD	2B-53	ActHtgSP
AD	2B-53	CFM
CS	2B-53	CFM-stpt
AI	2B-54	Zone-T
AD	2B-54	ActHtgSP
AD	2B-54	CFM
CS	2B-54	CFM-stpt
AI	2B-55	Zone-T
AD	2B-55	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	2B-55	CFM
CS	2B-55	CFM-stpt
AI	2B-56	Zone-T
AD	2B-56	ActHtgSP
AD	2B-56	CFM
CS	2B-56	CFM-stpt
AI	2B-57	Zone-T
AD	2B-57	ActHtgSP
AD	2B-57	CFM
CS	2B-57	CFM-stpt
AI	2B-58	Zone-T
AD	2B-58	ActHtgSP
AD	2B-58	CFM
CS	2B-58	CFM-stpt
AI	2B-59	Zone-T
AD	2B-59	ActHtgSP
AD	2B-59	CFM
CS	2B-59	CFM-stpt
AI	2B-60	Zone-T
AD	2B-60	ActHtgSP
AD	2B-60	CFM
CS	2B-60	CFM-stpt
AI	2B-61	Zone-T
AD	2B-61	ActHtgSP
AD	2B-61	CFM
CS	2B-61	CFM-stpt
AI	2B-62	Zone-T
AD	2B-62	ActHtgSP
AD	2B-62	CFM
CS	2B-62	CFM-stpt
AI	2B-63	Zone-T
AD	2B-63	ActHtgSP
AD	2B-63	CFM
CS	2B-63	CFM-stpt
AI	2B-65	Zone-T
AD	2B-65	ActHtgSP
AD	2B-65	CFM
CS	2B-65	CFM-stpt
AI	2B-66	Zone-T
AD	2B-66	ActHtgSP
AD	2B-66	CFM
CS	2B-66	CFM-stpt
AI	2B-67	Zone-T
AD	2B-67	ActHtgSP
AD	2B-67	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	2B-67	CFM-stpt
AI	2B-99	Zone-T
AD	2B-99	ActHtgSP
AD	2B-99	CFM
CS	2B-99	CFM-stpt
AI	2B-42	Zone-T
AD	2B-42	CFM
CS	2B-42	CFM-stpt
AI	2B-22	Zone-T
AD	2B-22	ActHtgSP
AD	2B-22	CFM
CS	2B-22	CFM-stpt
AI	2B-22	RM-PRESS
CS	2B-22	MODE
BD	2B-22	ALM
AI	2B-22	RM-PRES
CS	2B-22	MODE_
BD	2B-22	ALM_
BD	2B-22	Filter-S
BD	2B-22	EF3_75
AI	2B-43	Zone-T
AD	2B-43	ActHtgSP
AD	2B-43	CFM
CS	2B-43	CFM-stpt
AI	2B-43	RM-PRESS
CS	2B-43	MODE
BD	2B-43	ALM
BD	2B-43	EF3_75
BD	2B-43	Filter-S
AI	2801	STM-P
AOS	2801	STM-STPT
AOS	2801	STM-VLV

Building 2		
Points	**Equipment**	**Type**
NC-11		**Network controller**
NC-11-HW	AHU-3201	132, 1, 3, AHU
NC-11-HW	DC11-133	133, 1, 3, UNT
NC-11-HW	AHU-3202	134, 1, 3, AHU
NC-11-HW	DC11-135	135, 1, 3, UNT
NC-11-HW	DC11-101	101, 1, 3, UNT
NC-11-HW	DC11-105	105, 1, 3, UNT

DRAFT

Building 2		
Points	Equipment	Type
NC-11-HW	DC11-106	106, 1, 3, UNT
NC-11-HW	DC11-107	107, 1, 3, UNT
NC-11-HW	DC11-111	111, 1, 3, UNT
NC-11-HW	DC11-112	112, 1, 3, UNT
NC-11-HW	DC11-142	142, 1, 3, UNT
NC-11-HW	DC11-143	143, 1, 3, UNT
NC-11-HW	DC11-145	145, 1, 3, UNT
NC-11-HW	DC11-151	151, 1, 3, UNT
NC-11-HW	CVR-01	1, 1, 3, VAV
NC-11-HW	CVR-02	2, 1, 3, VAV
NC-11-HW	CVR-03	3, 1, 3, VAV
NC-11-HW	CVR-04	4, 1, 3, VAV
NC-11-HW	CVR-05	5, 1, 3, VAV
NC-11-HW	CVR-06	6, 1, 3, VAV
NC-11-HW	CVR-07	7, 1, 3, VAV
NC-11-HW	CVR-08	8, 1, 3, VAV
NC-11-HW	CVR-09	9, 1, 3, VAV
NC-11-HW	CVR-10	10, 1, 3, VAV
NC-11-HW	CVR-11	11, 1, 3, VAV
NC-11-HW	CVR-12	12, 1, 3, VAV
NC-11-HW	CVR-13	13, 1, 3, VAV
NC-11-HW	CVR-14	14, 1, 3, VAV
NC-11-HW	CVR-15	15, 1, 3, VAV
NC-11-HW	CVR-16	16, 1, 3, VAV
NC-11-HW	CVR-17	17, 1, 3, VAV
NC-11-HW	CVR-18	18, 1, 3, VAV
NC-11-HW	CVR-19	19, 1, 3, VAV
NC-11-HW	CVR-20	20, 1, 3, VAV
NC-11-HW	CVR-21	21, 1, 3, VAV
NC-11-HW	CVR-22	22, 1, 3, VAV
NC-11-HW	CVR-23	23, 1, 3, VAV
NC-11-HW	CVR-24	24, 1, 3, VAV
NC-11-HW	CVR-31	31, 1, 3, VAV
NC-11-HW	CVR-32	32, 1, 3, VAV
NC-11-HW	CVR-33	33, 1, 3, VAV
NC-11-HW	CVR-34	34, 1, 3, VAV
NC-11-HW	CVR-35	35, 1, 3, VAV
NC-11-HW	CVR-36	36, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-11-HW	CVR-37	37, 1, 3, VAV
NC-11-HW	CVR-38	38, 1, 3, VAV
NC-11-HW	CVR-39	39, 1, 3, VAV
NC-11-HW	CVR-40	40, 1, 3, VAV
NC-11-HW	CVR-41	41, 1, 3, VAV
NC-11-HW	CVR-42	42, 1, 3, VAV
NC-11-HW	CVR-43	43, 1, 3, VAV
NC-11-HW	CVR-44	44, 1, 3, VAV
NC-11-HW	CVR-45	45, 1, 3, VAV
NC-11-HW	CVR-46	46, 1, 3, VAV
NC-11-HW	CVR-47	47, 1, 3, VAV
NC-11-HW	CVR-48	48, 1, 3, VAV
NC-11-HW	CVR-49	49, 1, 3, VAV
NC-11-HW	CVR-50	50, 1, 3, VAV
NC-11-HW	CVR-51	51, 1, 3, VAV
NC-11-HW	CVR-400	255, 1, 3, VAV
NC-11-HW	FCU-125	125, 1, 3, UNT
NC-11-HW	FCU-126	126, 1, 3, UNT
NC-11-HW	FCU-123	123, 1, 3, UNT
NC-11-HW	FCU-124	124, 1, 3, UNT
JCB	JCB-NC11	3201-OCC
JCB	JCB-NC11	3201-SMK
JCB	JCB-NC11	3202-OCC
JCB	JCB-NC11	3202-SMK
JCB	JCB-NC11	3201-PMP
JCB	JCB-NC11	3202-PMP
JCB	JCB-NC11	32_01EF
JCB	JCB-NC11	32_02EF
JCB	JCB-NC11	32_02-TE
JCB	JCB-NC11	32_01-TE
JCB	JCB-NC11	3201AITB
JCB	JCB-NC11	3202AITB
JCB	JCB-NC11	3201ZHUM
JCB	JCB-NC11	3202ZHUM
AI	FC-4	RA-T
AI	FC-4	DA-T
AOS	FC-4	Clg-CMD
AOS	FC-4	HTG-CMD

DRAFT

Building 2		
Points	Equipment	Type
BO	FC-4	FCU-CMD
BI	FC-4	FCU-S
AOS	FC-4	HTG-STPT
AOS	FC-4	CLG-STPT
AI	FC-3	RA-T
AI	FC-3	DA-T
AOS	FC-3	CLG-CMD
AOS	FC-3	HTG-CMD
BO	FC-3	FCU-CMD
BI	FC-3	FCU-S
AOS	FC-3	HTG-STPT
AOS	FC-3	CLG-STPT
AI	FC-2	RA-T
AI	FC-2	DA-T
AOS	FC-2	CLG-CMD
AOS	FC-2	HTG-CMD
BO	FC-2	FCU-CMD
BI	FC-2	FCU-S
AOS	FC-2	HTG-STPT
AOS	FC-2	CLG-STPT
AI	FC-1	RA-T
AI	FC-1	DA-T
AOS	FC-1	CLG-CMD
AOS	FC-1	HTG-CMD
BO	FC-1	FCU-CMD
BI	FC-1	FCU-S
AOS	FC-1	HTG-STPT
AOS	FC-1	CLG-STPT
AD	ORS	OR-1
AD	ORS	OR-2
AD	ORS	OR-3
AD	ORS	OR-4
AD	ORS	OR-5
AD	ORS	OR-6
AD	ORS	OR-7
AD	ORS	OR-8
AD	ORS	OR-9
AD	ORS	OR-10

DRAFT

Building 2		
Points	Equipment	Type
AD	ORS	OR-11
AD	ORS	OR-12
AD	ORS	OR-13
AD	ORS	OR-14
AD	ORS	OR-15
AD	ORS	OR-17
BO	SHARE11	EF4_06-C
BI	SHARE11	EF4_06
BO	SHARE11	EF4_09-C
BI	SHARE11	EF4_09
BO	SHARE11	EF4_24-C
BI	SHARE11	EF4_24
BO	SHARE11	EF4_25-C
BI	SHARE11	EF4_25
BO	SHARE11	EF4_26-C
BI	SHARE11	EF4_26
BI	SHARE11	Filter-S
BD	AHU-3202	OCC
BI	AHU-3202	SF-S
BI	AHU-3202	RF-S
AI	AHU-3202	DA-T
AD	AHU-3202	DA-STPT
AOS	AHU-3202	HTG-VLV
BD	AHU-3202	HTG-PMP
AOS	AHU-3202	CLG-VLV
AOS	AHU-3202	OA-DMPR
AI	AHU-3202	MA-T
AI	AHU-3202	RA-T
AI	AHU-3202	OA-T
BI	AHU-3202	LT-ALM
BI	AHU-3202	PURGE
BI	AHU-3202	SHTDWN
BD	AHU-3202	CLG-LOCK
BI	AHU-3202	HAND
AI	AHU-3202	RA-H
AOS	AHU-3202	HUM-VLV
AI	AHU-3202	PRE
AI	AHU-3202	AFT

DRAFT

Building 2		
Points	Equipment	Type
AI	AHU-3202	HWS
AI	AHU-3202	HWR
AI	AHU-3202	CWS
AI	AHU-3202	CWR
AD	AHU-3202	L-ZONE-T
AD	AHU-3202	H-ZONE-T
BO	AHU-3202	SF-C
BO	AHU-3202	RF-C
BO	AHU-3202	EF4_03-C
BI	AHU-3202	EF4_03
BD	AHU-3202	NITEPURG
BD	AHU-3201	OCC
BI	AHU-3201	SF-S
BI	AHU-3201	RF-S
AI	AHU-3201	DA-T
AD	AHU-3201	DA-STPT
AOS	AHU-3201	HTG-VLV
BD	AHU-3201	HTG-PMP
AOS	AHU-3201	CLG-VLV
AOS	AHU-3201	OA-DMPR
AI	AHU-3201	MA-T
AI	AHU-3201	RA-T
AI	AHU-3201	OA-T
BI	AHU-3201	LT-ALM
BI	AHU-3201	PURGE
BI	AHU-3201	SHTDWN
BD	AHU-3201	CLG-LOCK
BI	AHU-3201	HAND
AI	AHU-3201	RA-H
AOS	AHU-3201	HUM-VLV
AI	AHU-3201	PRE
AI	AHU-3201	AFT
AI	AHU-3201	HWS
AI	AHU-3201	HWR
AI	AHU-3201	CWS
AI	AHU-3201	CWR
AD	AHU-3201	L-ZONE-T
AD	AHU-3201	H-ZONE-T

DRAFT

Building 2		
Points	Equipment	Type
BO	AHU-3201	SF-C
BO	AHU-3201	RF-C
BO	AHU-3201	EF4_10-C
BI	AHU-3201	EF4_10
BO	AHU-3201	EF4_11-C
BI	AHU-3201	EF4_11
BD	AHU-3201	NITEPURG
AI	3C-51	Zone-T
AD	3C-51	ActHtgSP
AD	3C-51	CFM
CS	3C-51	CFM-stpt
AI	3C-51	Zone-H
CS	3C-51	HUM-stpt
AOS	3C-51	Hum-vlv
BI	3C-51	Air-flow
BO	3C-51	Hum-iso
BI	3C-51	FILTER-S
AI	3A-06	Zone-T
AD	3A-06	ActHtgSP
AD	3A-06	CFM
CS	3A-06	CFM-stpt
AI	3A-06	Zone-H
CS	3A-06	HUM-stpt
AOS	3A-06	Hum-vlv
BI	3A-06	Air-flow
BO	3A-06	Hum-iso
BI	3A-06	Filter-S
AI	3A-01	Zone-T
AD	3A-01	ActHtgSP
AD	3A-01	CFM
CS	3A-01	CFM-stpt
AI	3A-01	Zone-H
CS	3A-01	HUM-stpt
AOS	3A-01	Hum-vlv
BI	3A-01	Air-flow
BO	3A-01	Hum-iso
BI	3A-01	Filter-S
CS	CS-NC-11	AHU3201

DRAFT

Building 2		
Points	Equipment	Type
CS	CS-NC-11	AHU3202
AI	3A-02	Zone-T
AD	3A-02	ActHtgSP
AD	3A-02	CFM
CS	3A-02	CFM-stpt
AI	3A-03	Zone-T
AD	3A-03	ActHtgSP
AD	3A-03	CFM
CS	3A-03	CFM-stpt
AI	3A-04	Zone-T
AD	3A-04	ActHtgSP
AD	3A-04	CFM
CS	3A-04	CFM-stpt
AI	3A-05	Zone-T
AD	3A-05	ActHtgSP
AD	3A-05	CFM
CS	3A-05	CFM-stpt
AI	3A-05	Zone-H
CS	3A-05	HUM-stpt
AOS	3A-05	Hum-vlv
BI	3A-05	Air-flow
BO	3A-05	Hum-iso
AI	3A-07	Zone-T
AD	3A-07	ActHtgSP
AD	3A-07	CFM
CS	3A-07	CFM-stpt
AI	3A-07	Zone-H
CS	3A-07	HUM-stpt
AOS	3A-07	Hum-vlv
BI	3A-07	Air-flow
BO	3A-07	Hum-iso
AI	3A-08	Zone-T
AD	3A-08	ActHtgSP
AD	3A-08	CFM
CS	3A-08	CFM-stpt
AI	3A-09	Zone-T
AD	3A-09	ActHtgSP
AD	3A-09	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	3A-09	CFM-stpt
AI	3A-10	Zone-T
AD	3A-10	ActHtgSP
AD	3A-10	CFM
CS	3A-10	CFM-stpt
AI	3A-11	Zone-T
AD	3A-11	ActHtgSP
AD	3A-11	CFM
CS	3A-11	CFM-stpt
AI	3A-11	Zone-H
CS	3A-11	HUM-stpt
AOS	3A-11	Hum-vlv
BI	3A-11	Air-flow
BO	3A-11	Hum-iso
AI	3A-12	Zone-T
AD	3A-12	ActHtgSP
AD	3A-12	CFM
CS	3A-12	CFM-stpt
AI	3A-12	Zone-H
CS	3A-12	HUM-stpt
AOS	3A-12	Hum-vlv
BI	3A-12	Air-flow
BO	3A-12	Hum-iso
AI	3A-13	Zone-T
AD	3A-13	ActHtgSP
AD	3A-13	CFM
CS	3A-13	CFM-stpt
AI	3A-14	Zone-T
AD	3A-14	ActHtgSP
AD	3A-14	CFM
CS	3A-14	CFM-stpt
AI	3A-15	Zone-T
AD	3A-15	ActHtgSP
AD	3A-15	CFM
CS	3A-15	CFM-stpt
AI	3A-16	Zone-T
AD	3A-16	ActHtgSP
AD	3A-16	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	3A-16	CFM-stpt
AI	3A-17	Zone-T
AD	3A-17	ActHtgSP
AD	3A-17	CFM
CS	3A-17	CFM-stpt
AI	3A-18	Zone-T
AD	3A-18	ActHtgSP
AD	3A-18	CFM
CS	3A-18	CFM-stpt
AI	3A-19	Zone-T
AD	3A-19	ActHtgSP
AD	3A-19	CFM
CS	3A-19	CFM-stpt
AI	3A-20	Zone-T
AD	3A-20	ActHtgSP
AD	3A-20	CFM
CS	3A-20	CFM-stpt
AI	3A-21	Zone-T
AD	3A-21	ActHtgSP
AD	3A-21	CFM
CS	3A-21	CFM-stpt
AI	3A-22	Zone-T
AD	3A-22	ActHtgSP
AD	3A-22	CFM
CS	3A-22	CFM-stpt
AI	3A-23	Zone-T
AD	3A-23	ActHtgSP
AD	3A-23	CFM
CS	3A-23	CFM-stpt
AI	3A-24	Zone-T
AD	3A-24	ActHtgSP
AD	3A-24	CFM
CS	3A-24	CFM-stpt
AI	3C-33	Zone-T
AD	3C-33	ActHtgSP
AD	3C-33	CFM
CS	3C-33	CFM-stpt
AI	3C-32	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	3C-32	ActHtgSP
AD	3C-32	CFM
CS	3C-32	CFM-stpt
AI	3C-31	Zone-T
AD	3C-31	ActHtgSP
AD	3C-31	CFM
CS	3C-31	CFM-stpt
AI	3A-34	Zone-T
AD	3A-34	ActHtgSP
AD	3A-34	CFM
CS	3A-34	CFM-stpt
AI	3A-35	Zone-T
AD	3A-35	ActHtgSP
AD	3A-35	CFM
CS	3A-35	CFM-stpt
AI	3A-36	Zone-T
AD	3A-36	ActHtgSP
AD	3A-36	CFM
CS	3A-36	CFM-stpt
AI	3A-37	Zone-T
AD	3A-37	ActHtgSP
AD	3A-37	CFM
CS	3A-37	CFM-stpt
AI	3A-38	Zone-T
AD	3A-38	ActHtgSP
AD	3A-38	CFM
CS	3A-38	CFM-stpt
AI	3A-39	Zone-T
AD	3A-39	ActHtgSP
AD	3A-39	CFM
CS	3A-39	CFM-stpt
AI	3A-40	Zone-T
AD	3A-40	ActHtgSP
AD	3A-40	CFM
CS	3A-40	CFM-stpt
AI	3A-41	Zone-T
AD	3A-41	ActHtgSP
AD	3A-41	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	3A-41	CFM-stpt
AI	3A-42	Zone-T
AD	3A-42	ActHtgSP
AD	3A-42	CFM
CS	3A-42	CFM-stpt
AI	3A-42	Zone-H
CS	3A-42	HUM-stpt
AOS	3A-42	Hum-vlv
BI	3A-42	Air-flow
BO	3A-42	Hum-iso
AI	3A-43	Zone-T
AD	3A-43	ActHtgSP
AD	3A-43	CFM
CS	3A-43	CFM-stpt
AI	3A-43	Zone-H
CS	3A-43	HUM-stpt
AOS	3A-43	Hum-vlv
BI	3A-43	Air-flow
BO	3A-43	Hum-iso
AI	3A-45	Zone-T
AD	3A-45	ActHtgSP
AD	3A-45	CFM
CS	3A-45	CFM-stpt
AI	3A-45	Zone-H
CS	3A-45	HUM-stpt
AOS	3A-45	Hum-vlv
BI	3A-45	Air-flow
BO	3A-45	Hum-iso
AI	3A-46	Zone-T
AD	3A-46	ActHtgSP
AD	3A-46	CFM
CS	3A-46	CFM-stpt
AI	3A-47	Zone-T
AD	3A-47	ActHtgSP
AD	3A-47	CFM
CS	3A-47	CFM-stpt
AI	3A-48	Zone-T
AD	3A-48	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3A-48	CFM
CS	3A-48	CFM-stpt
AI	3A-49	Zone-T
AD	3A-49	ActHtgSP
AD	3A-49	CFM
CS	3A-49	CFM-stpt
AI	3A-50	Zone-T
AD	3A-50	ActHtgSP
AD	3A-50	CFM
CS	3A-50	CFM-stpt
AI	3A-400	Zone-T
AD	3A-400	ActHtgSP
AD	3A-400	CFM
CS	3A-400	CFM-stpt
AI	3A-44	Zone-T
AD	3A-44	ActHtgSP
AD	3A-44	CFM
CS	3A-44	CFM-stpt

Building 2		
Points	**Equipment**	**Type**
NC-12		**Network controller**
NC-12-HW	AHU-3701	137, 1, 3, AHU
NC-12-HW	DC12-138	138, 1, 3, UNT
NC-12-HW	AHU-3702	139, 1, 3, AHU
NC-12-HW	DC12-140	140, 1, 3, UNT
NC-12-HW	AHU-3703	141, 1, 3, AHU
NC-12-HW	DC12-142	142, 1, 3, UNT
NC-12-HW	AHU-3704	143, 1, 3, AHU
NC-12-HW	DC12-144	144, 1, 3, UNT
NC-12-HW	DC12-145	145, 1, 3, UNT
NC-12-HW	DC12-146	146, 1, 3, UNT
NC-12-HW	CVR-01	1, 1, 3, VAV
NC-12-HW	CVR-02	2, 1, 3, VAV
NC-12-HW	CVR-04	4, 1, 3, VAV
NC-12-HW	CVR-05	5, 1, 3, VAV
NC-12-HW	CVR-06	6, 1, 3, VAV
NC-12-HW	CVR-07	7, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-12-HW	CVR-08	8, 1, 3, VAV
NC-12-HW	CVR-09	9, 1, 3, VAV
NC-12-HW	CVR-10	10, 1, 3, VAV
NC-12-HW	CVR-11	11, 1, 3, VAV
NC-12-HW	CVR-12	12, 1, 3, VAV
NC-12-HW	CVR-13	13, 1, 3, VAV
NC-12-HW	CVR-14	14, 1, 3, VAV
NC-12-HW	CVR-15	15, 1, 3, VAV
NC-12-HW	CVR-16	16, 1, 3, VAV
NC-12-HW	CVR-17	17, 1, 3, VAV
NC-12-HW	CVR-18	18, 1, 3, VAV
NC-12-HW	CVR-19	19, 1, 3, VAV
NC-12-HW	CVR-20	20, 1, 3, VAV
NC-12-HW	CVR-23	23, 1, 3, VAV
NC-12-HW	CVR-24	24, 1, 3, VAV
NC-12-HW	CVR-25	25, 1, 3, VAV
NC-12-HW	CVR-26	26, 1, 3, VAV
NC-12-HW	CVR-27	27, 1, 3, VAV
NC-12-HW	CVR-28	28, 1, 3, VAV
NC-12-HW	CVR-29	29, 1, 3, VAV
NC-12-HW	CVR-32	32, 1, 3, VAV
NC-12-HW	CVR-33	33, 1, 3, VAV
NC-12-HW	CVR-35	35, 1, 3, VAV
NC-12-HW	CVR-37	37, 1, 3, VAV
NC-12-HW	CVR-40	40, 1, 3, VAV
NC-12-HW	CVR-42	42, 1, 3, VAV
NC-12-HW	CVR-45	45, 1, 3, VAV
NC-12-HW	CVR-46	46, 1, 3, VAV
NC-12-HW	CVR-47	47, 1, 3, VAV
NC-12-HW	CVR-48	48, 1, 3, VAV
NC-12-HW	CVR-49	49, 1, 3, VAV
NC-12-HW	CVR-50	50, 1, 3, VAV
NC-12-HW	CVR-85	85, 1, 3, VAV
NC-12-HW	CVR-86	86, 1, 3, VAV
NC-12-HW	CVR-87	87, 1, 3, VAV
NC-12-HW	CVR-88	88, 1, 3, VAV
NC-12-HW	CVR-89	89, 1, 3, VAV
NC-12-HW	CVR-90	90, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-12-HW	CVR-91	91, 1, 3, VAV
NC-12-HW	CVR-92	92, 1, 3, VAV
NC-12-HW	CVR-93	93, 1, 3, VAV
NC-12-HW	CVR-94	94, 1, 3, VAV
NC-12-HW	CVR-95	95, 1, 3, VAV
NC-12-HW	CVR-96	96, 1, 3, VAV
NC-12-HW	ISO-210	210, 1, 3, VND
NC-12-HW	ISO-211	211, 1, 3, VND
NC-12-HW	CLNSTM	60, 1, 3, UNT
NC-12-HW	AHU-3705	51, 1, 3, AHU
NC-12-HW	CVR-43	160, 1, 3, VMA
NC-12-HW	CVR-30	161, 1, 3, VMA
NC-12-HW	CVR-38	162, 1, 3, VMA
NC-12-HW	CVR-39	163, 1, 3, VMA
NC-12-HW	CVR-21	164, 1, 3, VMA
NC-12-HW	CVR-22	165, 1, 3, VMA
NC-12-HW	CVR-31	166, 1, 3, VMA
NC-12-HW	CVR-34	167, 1, 3, VMA
NC-12-HW	CVR-36	168, 1, 3, VMA
NC-12-HW	CVR-03	170, 1, 3, VMA
NC-12-HW	CVR-41	172, 1, 3, VMA
AI	3B-22	Zone-T
AD	3B-22	ActHtgSP
AD	3B-22	CFM
CS	3B-22	CFM-stpt
AI	3B-22	RM-PRESS
CS	3B-22	Mode
BD	3B-22	ALM
BD	3B-22	EF5_52
AI	3B-21	Zone-T
AD	3B-21	ActHtgSP
AD	3B-21	CFM
CS	3B-21	CFM-stpt
AI	3B-21	RM-PRESS
CS	3B-21	Mode
BD	3B-21	ALM
BD	3B-21	EF5_52
AI	3B-32	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	3B-32	ActHtgSP
AD	3B-32	CFM
CS	3B-32	CFM-stpt
AI	3B-31	Zone-T
AD	3B-31	ActHtgSP
CS	3B-31	CFM-stpt
AD	3B-31	CFM
AI	3B-43	Zone-T
AD	3B-43	ActHtgSP
AD	3B-43	CFM
CS	3B-43	CFM-stpt
AI	3B-41	Zone-T
AD	3B-41	ActHtgSP
AD	3B-41	CFM
CS	3B-41	CFM-stpt
AI	3B-39	Zone-T
AD	3B-39	ActHtgSP
AD	3B-39	CFM
CS	3B-39	CFM-stpt
AI	3B-38	Zone-T
AD	3B-38	ActHtgSP
AD	3B-38	CFM
CS	3B-38	CFM-stpt
AI	3B-36	Zone-T
AD	3B-36	ActHtgSP
AD	3B-36	CFM
CS	3B-36	CFM-stpt
AI	3B-30	Zone-T
AD	3B-30	ActHtgSP
AD	3B-30	CFM
CS	3B-30	CFM-stpt
AI	3B-34	Zone-T
AD	3B-34	ActHtgSP
AD	3B-34	CFM
CS	3B-34	CFM-stpt
AI	3B-03	Zone-T
AD	3B-03	ActHtgSP
AD	3B-03	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	3B-03	CFM-stpt
BO	AHU-3705	SDWN-C
BO	AHU-3705	SF-C
BI	AHU-3705	SF-S
AI	AHU-3705	SA-T
AOS	AHU-3705	SAT-SP
AOS	AHU-3705	CLG-O
AI	AHU-3705	SA-P
AI	AHU-3705	SA-VP
CS	AHU-3705	SA-F
AOS	AHU-3705	SF-O
AI	AHU-3705	RA-T
AI	AHU-3705	RA-H
AOS	AHU-3705	RAH-SP
BO	AHU-3705	HUM-C
AOS	AHU-3705	HUM-O
AI	AHU-3705	PH-T
AOS	AHU-3705	PH-SP
AOS	AHU-3705	PH-O
BO	AHU-3705	ECON-C
AOS	AHU-3705	OAD-C
AOS	AHU-3705	SAD-O
AI	AHU-3705	FTLR-DP
BI	AHU-3705	LT-A
BI	AHU-3705	HP-A
AI	3701	STM-P
AOS	3701	STM-STPT
AOS	3701	STM-VLV
AI	3B-01	Zone-T
AD	3B-01	ActHtgSP
AD	3B-01	CFM
CS	3B-01	CFM-stpt
AI	3B-04	Zone-T
AD	3B-04	ActHtgSP
AD	3B-04	CFM
CS	3B-04	CFM-stpt
AI	3B-05	Zone-T
AD	3B-05	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3B-05	CFM
CS	3B-05	CFM-stpt
AI	3B-06	Zone-T
AD	3B-06	ActHtgSP
AD	3B-06	CFM
CS	3B-06	CFM-stpt
AI	3B-07	Zone-T
AD	3B-07	ActHtgSP
AD	3B-07	CFM
CS	3B-07	CFM-stpt
AI	3B-08	Zone-T
AD	3B-08	ActHtgSP
AD	3B-08	CFM
CS	3B-08	CFM-stpt
AI	3B-09	Zone-T
AD	3B-09	ActHtgSP
AD	3B-09	CFM
CS	3B-09	CFM-stpt
AI	3B-10	Zone-T
AD	3B-10	ActHtgSP
AD	3B-10	CFM
CS	3B-10	CFM-stpt
AI	3B-11	Zone-T
AD	3B-11	ActHtgSP
AD	3B-11	CFM
CS	3B-11	CFM-stpt
AI	3B-12	Zone-T
AD	3B-12	ActHtgSP
AD	3B-12	CFM
CS	3B-12	CFM-stpt
AI	3B-13	Zone-T
AD	3B-13	ActHtgSP
AD	3B-13	CFM
CS	3B-13	CFM-stpt
AI	3B-14	Zone-T
AD	3B-14	ActHtgSP
AD	3B-14	CFM
CS	3B-14	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	3B-15	Zone-T
AD	3B-15	ActHtgSP
AD	3B-15	CFM
CS	3B-15	CFM-stpt
AI	3B-16	Zone-T
AD	3B-16	ActHtgSP
AD	3B-16	CFM
CS	3B-16	CFM-stpt
AI	3B-17	Zone-T
AD	3B-17	ActHtgSP
AD	3B-17	CFM
CS	3B-17	CFM-stpt
AI	3B-18	Zone-T
AD	3B-18	ActHtgSP
AD	3B-18	CFM
CS	3B-18	CFM-stpt
AI	3B-19	Zone-T
AD	3B-19	ActHtgSP
AD	3B-19	CFM
CS	3B-19	CFM-stpt
AI	3B-20	Zone-T
AD	3B-20	ActHtgSP
AD	3B-20	CFM
CS	3B-20	CFM-stpt
AI	3B-23	Zone-T
AD	3B-23	ActHtgSP
AD	3B-23	CFM
CS	3B-23	CFM-stpt
AI	3B-24	Zone-T
AD	3B-24	ActHtgSP
AD	3B-24	CFM
CS	3B-24	CFM-stpt
AI	3B-25	Zone-T
AD	3B-25	ActHtgSP
AD	3B-25	CFM
CS	3B-25	CFM-stpt
AI	3B-26	Zone-T
AD	3B-26	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3B-26	CFM
CS	3B-26	CFM-stpt
AI	3B-27	Zone-T
AD	3B-27	ActHtgSP
AD	3B-27	CFM
CS	3B-27	CFM-stpt
AI	3B-28	Zone-T
AD	3B-28	ActHtgSP
AD	3B-28	CFM
CS	3B-28	CFM-stpt
AI	3B-29	Zone-T
AD	3B-29	ActHtgSP
AD	3B-29	CFM
CS	3B-29	CFM-stpt
AI	3B-33	Zone-T
AD	3B-33	ActHtgSP
AD	3B-33	CFM
CS	3B-33	CFM-stpt
AI	3B-35	Zone-T
AD	3B-35	ActHtgSP
AD	3B-35	CFM
CS	3B-35	CFM-stpt
AI	3B-37	Zone-T
AD	3B-37	ActHtgSP
AD	3B-37	CFM
CS	3B-37	CFM-stpt
AI	3B-40	Zone-T
AD	3B-40	ActHtgSP
AD	3B-40	CFM
CS	3B-40	CFM-stpt
AI	3B-45	Zone-T
AD	3B-45	ActHtgSP
AD	3B-45	CFM
CS	3B-45	CFM-stpt
AI	3B-46	Zone-T
AD	3B-46	ActHtgSP
AD	3B-46	CFM
CS	3B-46	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	3B-47	Zone-T
AD	3B-47	ActHtgSP
AD	3B-47	CFM
CS	3B-47	CFM-stpt
AI	3B-48	Zone-T
AD	3B-48	ActHtgSP
AD	3B-48	CFM
CS	3B-48	CFM-stpt
AI	3B-49	Zone-T
AD	3B-49	ActHtgSP
AD	3B-49	CFM
CS	3B-49	CFM-stpt
AI	3B-50	Zone-T
AD	3B-50	ActHtgSP
AD	3B-50	CFM
CS	3B-50	CFM-stpt
AI	3D-85	Zone-T
AD	3D-85	ActHtgSP
AD	3D-85	CFM
CS	3D-85	CFM-stpt
AI	3D-87	Zone-T
AD	3D-87	ActHtgSP
AD	3D-87	CFM
CS	3D-87	CFM-stpt
AI	3D-88	Zone-T
AD	3D-88	ActHtgSP
AD	3D-88	CFM
CS	3D-88	CFM-stpt
AI	3D-89	Zone-T
AD	3D-89	ActHtgSP
AD	3D-89	CFM
CS	3D-89	CFM-stpt
AI	3D-90	Zone-T
AD	3D-90	ActHtgSP
AD	3D-90	CFM
CS	3D-90	CFM-stpt
AI	3D-91	Zone-T
AD	3D-91	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3D-91	CFM
CS	3D-91	CFM-stpt
AI	3D-92	Zone-T
AD	3D-92	ActHtgSP
AD	3D-92	CFM
CS	3D-92	CFM-stpt
AI	3D-93	Zone-T
AD	3D-93	ActHtgSP
AD	3D-93	CFM
CS	3D-93	CFM-stpt
AI	3D-94	Zone-T
AD	3D-94	ActHtgSP
AD	3D-94	CFM
CS	3D-94	CFM-stpt
AI	3D-95	Zone-T
AD	3D-95	ActHtgSP
AD	3D-95	CFM
CS	3D-95	CFM-stpt
AI	3D-96	Zone-T
AD	3D-96	ActHtgSP
AD	3D-96	CFM
CS	3D-96	CFM-stpt
BD	AHU-3702	OCC
BI	AHU-3702	SF-S
BI	AHU-3702	RF-S
AI	AHU-3702	DA-T
AD	AHU-3702	DA-STPT
AOS	AHU-3702	HTG-VLV
BD	AHU-3702	HTG-PMP
AOS	AHU-3702	CLG-VLV
AOS	AHU-3702	OA-DMPR
AI	AHU-3702	MA-T
AI	AHU-3702	RA-T
AI	AHU-3702	OA-T
BI	AHU-3702	LT-ALM
BI	AHU-3702	PURGE
BI	AHU-3702	SHTDWN
BD	AHU-3702	CLG-LOCK

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-3702	HAND
AI	AHU-3702	RA-H
AOS	AHU-3702	HUM-VLV
AI	AHU-3702	PRE
AI	AHU-3702	AFT
AI	AHU-3702	HWS
AI	AHU-3702	HWR
AI	AHU-3702	CWS
AI	AHU-3702	CWR
AD	AHU-3702	L-ZONE-T
AD	AHU-3702	H-ZONE-T
BO	AHU-3702	SF-C
BO	AHU-3702	RF-C
BD	AHU-3702	NITEPURG
BD	AHU-3702	EF5_30
BD	AHU-3704	OCC
BI	AHU-3704	SF-S
BI	AHU-3704	RF-S
AI	AHU-3704	DA-T
AD	AHU-3704	DA-STPT
AOS	AHU-3704	HTG-VLV
BD	AHU-3704	HTG-PMP
AOS	AHU-3704	CLG-VLV
AOS	AHU-3704	OA-DMPR
AI	AHU-3704	MA-T
AI	AHU-3704	RA-T
AI	AHU-3704	OA-T
BI	AHU-3704	LT-ALM
BI	AHU-3704	PURGE
BI	AHU-3704	SHTDWN
BD	AHU-3704	CLG-LOCK
AI	AHU-3704	RA-H
AOS	AHU-3704	HUM-VLV
AI	AHU-3704	PRE
AI	AHU-3704	AFT
AI	AHU-3704	HWS
AI	AHU-3704	HWR
AI	AHU-3704	CWS

DRAFT

Building 2		
Points	Equipment	Type
AI	AHU-3704	CWR
AD	AHU-3704	L-ZONE-T
AD	AHU-3704	H-ZONE-T
BO	AHU-3704	SF-C
BO	AHU-3704	RF-C
BD	AHU-3704	NITEPURG
BD	AHU-3703	OCC
BI	AHU-3703	SF-S
BI	AHU-3703	RF-S
AI	AHU-3703	DA-T
AD	AHU-3703	DA-STPT
AOS	AHU-3703	HTG-VLV
BD	AHU-3703	HTG-PMP
AOS	AHU-3703	CLG-VLV
AOS	AHU-3703	OA-DMPR
AI	AHU-3703	MA-T
AI	AHU-3703	RA-T
AI	AHU-3703	OA-T
BI	AHU-3703	LT-ALM
BI	AHU-3703	PURGE
BI	AHU-3703	SHTDWN
BD	AHU-3703	CLG-LOCK
AI	AHU-3703	RA-H
AOS	AHU-3703	HUM-VLV
AI	AHU-3703	PRE
AI	AHU-3703	AFT
AI	AHU-3703	HWS
AI	AHU-3703	HWR
AI	AHU-3703	CWS
AI	AHU-3703	CWR
AD	AHU-3703	L-ZONE-T
AD	AHU-3703	H-ZONE-T
BO	AHU-3703	SF-C
BO	AHU-3703	RF-C
BO	AHU-3703	EF3_14-C
BI	AHU-3703	EF3_14
BO	AHU-3703	EF3_17-C
BI	AHU-3703	EF3_17

DRAFT

Building 2		
Points	Equipment	Type
BO	AHU-3703	EF3_19-C
BI	AHU-3703	EF3_19
BO	AHU-3703	EF3_21-C
BI	AHU-3703	EF3_21
BO	AHU-3703	EF3_22-C
BI	AHU-3703	EF3_22
BD	AHU-3703	NITEPURG
BO	SHARE12	EF3_32-C
BI	SHARE12	EF3_32
BO	SHARE12	EF3_34-C
BI	SHARE12	EF3_34
BO	SHARE12	EF3_35-C
BI	SHARE12	EF3_35
BO	SHARE12	EF3_37-C
BI	SHARE12	EF3_37
BO	SHARE12	EF3_59-C
BI	SHARE12	EF3_59
BO	SHARE12	EF3_60-C
BI	SHARE12	EF3_60
BO	SHARE12	EF3_61-C
BI	SHARE12	EF3_61
BO	SHARE12	EF3_69-C
BI	SHARE12	EF3_69
BO	SHARE12	EF4_07-C
BI	SHARE12	EF4_07
BO	SHARE12	EF4_08-C
BI	SHARE12	EF4_08
BO	SHARE12	EF5_27-C
BI	SHARE12	EF5_27
BO	SHARE12	EF5_43-C
BI	SHARE12	EF5_43
CS	CS-NC-12	AHU3701
CS	CS-NC-12	AHU3702
CS	CS-NC-12	AHU3703
CS	CS-NC-12	AHU3704
CS	CS-NC-12	R-DPSTPT
BD	AHU-3701	OCC
BI	AHU-3701	SF-S

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-3701	RF-S
AI	AHU-3701	DA-T
AD	AHU-3701	DA-STPT
AOS	AHU-3701	HTG-VLV
BD	AHU-3701	HTG-PMP
AOS	AHU-3701	CLG-VLV
AOS	AHU-3701	OA-DMPR
AI	AHU-3701	MA-T
AI	AHU-3701	RA-T
AI	AHU-3701	OA-T
BI	AHU-3701	LT-ALM
BI	AHU-3701	PURGE
BI	AHU-3701	SHTDWN
BD	AHU-3701	CLG-LOCK
AI	AHU-3701	RA-H
AOS	AHU-3701	HUM-VLV
AI	AHU-3701	PRE
AI	AHU-3701	AFT
AI	AHU-3701	HWS
AI	AHU-3701	HWR
AI	AHU-3701	CWS
AI	AHU-3701	CWR
AD	AHU-3701	L-ZONE-T
AD	AHU-3701	H-ZONE-T
BO	AHU-3701	SF-C
BO	AHU-3701	RF-C
BD	AHU-3701	NITEPURG
AI	AHU-3701	HW-DP
AOS	AHU-3701	HWDP-VLV
BI	AHU-3701	LO-STM
BI	AHU-3701	HI-STM
JCB	JCB-NC12	3701-PMP
JCB	JCB-NC12	3702-PMP
JCB	JCB-NC12	3703-PMP
JCB	JCB-NC12	3704-PMP
JCB	JCB-NC12	3703-SMK
JCB	JCB-NC12	3701-SMK
JCB	JCB-NC12	3702-SMK

DRAFT

Building 2		
Points	Equipment	Type
JCB	JCB-NC12	3704-SMK
JCB	JCB-NC12	3701-OCC
JCB	JCB-NC12	3702-OCC
JCB	JCB-NC12	3704-OCC
JCB	JCB-NC12	3703-OCC
JCB	JCB-NC12	37_02EF
JCB	JCB-NC12	37_01-TE
JCB	JCB-NC12	37_02-TE
JCB	JCB-NC12	3702AITB
JCB	JCB-NC12	3701AITB
JCB	JCB-NC12	3704AITB
JCB	JCB-NC12	37_03EF
JCB	JCB-NC12	3703AITB
JCB	JCB-NC12	37_03-TE
JCB	JCB-NC12	37_04-TE
AI	3B-42	Zone-T
AD	3B-42	CFM
CS	3B-42	CFM-stpt
AI	3D-86	Zone-T
AD	3D-86	CFM
CS	3D-86	CFM-stpt
AI	3B-02	Zone-T
AD	3B-02	CFM
CS	3B-02	CFM-stpt

Building 2		
Points	**Equipment**	**Type**
NC-13		**Network controller**
NC-13-HW	DC13-134	134, 1, 3, UNT
NC-13-HW	AHU-3302	135, 1, 3, AHU
NC-13-HW	DC13-136	136, 1, 3, UNT
NC-13-HW	AHU-3303	137, 1, 3, AHU
NC-13-HW	DC13-138	138, 1, 3, UNT
NC-13-HW	AHU-3304	139, 1, 3, AHU
NC-13-HW	DC13-140	140, 1, 3, UNT

DRAFT

Building 2		
Points	Equipment	Type
NC-13-HW	CVR-03	3, 1, 3, VAV
NC-13-HW	CVR-25	25, 1, 3, VAV
NC-13-HW	CVR-26	26, 1, 3, VAV
NC-13-HW	CVR-27	27, 1, 3, VAV
NC-13-HW	CVR-28	28, 1, 3, VAV
NC-13-HW	CVR-29	29, 1, 3, VAV
NC-13-HW	CVR-30	30, 1, 3, VAV
NC-13-HW	CVR-255	255, 1, 3, VAV
NC-13-HW	CVR-52	52, 1, 3, VAV
NC-13-HW	CVR-53	53, 1, 3, VAV
NC-13-HW	CVR-54	54, 1, 3, VAV
NC-13-HW	CVR-55	55, 1, 3, VAV
NC-13-HW	CVR-56	56, 1, 3, VAV
NC-13-HW	CVR-57	57, 1, 3, VAV
NC-13-HW	CVR-58	58, 1, 3, VAV
NC-13-HW	CVR-59	59, 1, 3, VAV
NC-13-HW	CVR-60	60, 1, 3, VAV
NC-13-HW	CVR-61	61, 1, 3, VAV
NC-13-HW	CVR-62	62, 1, 3, VAV
NC-13-HW	CVR-63	63, 1, 3, VAV
NC-13-HW	CVR-64	64, 1, 3, VAV
NC-13-HW	CVR-65	65, 1, 3, VAV
NC-13-HW	CVR-66	66, 1, 3, VAV
NC-13-HW	CVR-68	68, 1, 3, VAV
NC-13-HW	CVR-69	69, 1, 3, VAV
NC-13-HW	CVR-70	70, 1, 3, VAV
NC-13-HW	CVR-71	71, 1, 3, VAV
NC-13-HW	CVR-72	72, 1, 3, VAV
NC-13-HW	CVR-73	73, 1, 3, VAV
NC-13-HW	CVR-74	74, 1, 3, VAV
NC-13-HW	CVR-75	75, 1, 3, VAV
NC-13-HW	CVR-76	76, 1, 3, VAV
NC-13-HW	CVR-77	77, 1, 3, VAV
NC-13-HW	CVR-78	78, 1, 3, VAV
NC-13-HW	CVR-79	79, 1, 3, VAV
NC-13-HW	CVR-80	80, 1, 3, VAV
NC-13-HW	CVR-81	81, 1, 3, VAV
NC-13-HW	CVR-82	82, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-13-HW	CVR-97	97, 1, 3, VAV
NC-13-HW	CVR-98	98, 1, 3, VAV
NC-13-HW	CVR-99	99, 1, 3, VAV
NC-13-HW	CVR-100	100, 1, 3, VAV
NC-13-HW	CVR-101	101, 1, 3, VAV
NC-13-HW	CVR-102	102, 1, 3, VAV
NC-13-HW	CVR-103	103, 1, 3, VAV
NC-13-HW	CVR-104	104, 1, 3, VAV
NC-13-HW	CVR-105	105, 1, 3, VAV
NC-13-HW	CVR-106	106, 1, 3, VAV
NC-13-HW	CVR-107	107, 1, 3, VAV
NC-13-HW	CVR-108	108, 1, 3, VAV
NC-13-HW	CVR-109	109, 1, 3, VAV
NC-13-HW	ISO-219	219, 1, 3, VND
NC-13-HW	ISO-220	220, 1, 3, VND
NC-13-HW	AHU-3305	141, 1, 3, AHU
NC-13-HW	DC13-142	142, 1, 3, UNT
NC-13-HW	OR-CHLR	128, 1, 3, DX9100
BO	OR-CHLR	CHLR-ENB
BO	OR-CHLR	CHSYS-EN
BI	OR-CHLR	CHWP1-S
BI	OR-CHLR	CHWP2-S
BI	OR-CHLR	CHLR-S
AOS	OR-CHLR	CHW-SP
BD	OR-CHLR	CHLR-SCH
BO	OR-CHLR	AUX-VLV
JCB	OR-CHLR	ORCHILL
JCB	JCB-NC13	33_01-TE
JCB	JCB-NC13	3301-OCC
JCB	JCB-NC13	33_03-TE
JCB	JCB-NC13	3302-OCC
JCB	JCB-NC13	3301-PMP
JCB	JCB-NC13	3303-OCC
JCB	JCB-NC13	3304-OCC
JCB	JCB-NC13	3302-PMP
JCB	JCB-NC13	3303-PMP
JCB	JCB-NC13	3304-PMP
JCB	JCB-NC13	3301-SMK

DRAFT

Building 2		
Points	Equipment	Type
JCB	JCB-NC13	3302-SMK
JCB	JCB-NC13	3303-SMK
JCB	JCB-NC13	3304-SMK
JCB	JCB-NC13	33_01EF
JCB	JCB-NC13	33_02EF
JCB	JCB-NC13	33_03EF
JCB	JCB-NC13	33_04EF
JCB	JCB-NC13	3302AITB
JCB	JCB-NC13	3304AITB
JCB	JCB-NC13	3303AITB
JCB	JCB-NC13	3301AITB
JCB	JCB-NC13	3301ZHUM
JCB	JCB-NC13	33_02-TE
JCB	JCB-NC13	33_04-TE
JCB	JCB-NC13	3305-SMK
JCB	JCB-NC13	3305-PMP
JCB	JCB-NC13	3303ZHUM
CS	AHU-3305	AHU3305
AI	AHU-3305	RM-T
AOS	AHU-3305	RHT-VLV
AOS	AHU-3305	CLG-VLV
AOS	AHU-3305	HTG-VLV
AI	AHU-3305	DA-T
AD	AHU-3305	OA-T
AI	AHU-3305	OA-H
AI	AHU-3305	MA-T
AI	AHU-3305	RA-T
AI	AHU-3305	RET-H
AI	AHU-3305	RM-H
AI	AHU-3305	HWR-T
AI	AHU-3305	HWS-T
AI	AHU-3305	CWS-T
AI	AHU-3305	CWR-T
BI	AHU-3305	SF-S
BI	AHU-3305	RF-S
BO	AHU-3305	SF-C
BO	AHU-3305	RF-C
BI	AHU-3305	LL-ALM

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-3305	HWP-S
BO	AHU-3305	HTG-PMP
BI	AHU-3305	AHUHAND
AOS	AHU-3305	DMPR-CMD
AOS	AHU-3305	HUMID-V
BI	AHU-3305	PURGE
BI	AHU-3305	SHTDWN
BD	AHU-3305	NITEPURG
BO	AHU-3305	HUMISO-V
BD	AHU-3305	OCC
BD	AHU-3302	OCC
BI	AHU-3302	SF-S
BI	AHU-3302	RF-S
AI	AHU-3302	DA-T
AD	AHU-3302	DA-STPT
AOS	AHU-3302	HTG-VLV
BD	AHU-3302	HTG-PMP
AOS	AHU-3302	CLG-VLV
AOS	AHU-3302	OA-DMPR
AI	AHU-3302	MA-T
AI	AHU-3302	RA-T
AI	AHU-3302	OA-T
BI	AHU-3302	LT-ALM
BI	AHU-3302	PURGE
BI	AHU-3302	SHTDWN
BD	AHU-3302	CLG-LOCK
BI	AHU-3302	HAND
AI	AHU-3302	RA-H
AOS	AHU-3302	HUM-VLV
AI	AHU-3302	PRE
AI	AHU-3302	AFT
AI	AHU-3302	HWS
AI	AHU-3302	HWR
AI	AHU-3302	CWS
AI	AHU-3302	CWR
AD	AHU-3302	L-ZONE-T
AD	AHU-3302	H-ZONE-T
BO	AHU-3302	SF-C

DRAFT

Building 2		
Points	Equipment	Type
BO	AHU-3302	RF-C
BD	AHU-3302	NITEPURG
BD	AHU-3302	EF4_09
AI	3C-28	Zone-T
AD	3C-28	CFM
CS	3C-28	CFM-stpt
AI	3C-72	Zone-T
AD	3C-72	CFM
CS	3C-72	CFM-stpt
AI	3D-109	Zone-T
AD	3D-109	ActHtgSP
AD	3D-109	CFM
CS	3D-109	CFM-stpt
AI	3D-108	Zone-T
AD	3D-108	ActHtgSP
AD	3D-108	CFM
CS	3D-108	CFM-stpt
AI	3D-107	Zone-T
AD	3D-107	ActHtgSP
AD	3D-107	CFM
CS	3D-107	CFM-stpt
AI	3D-106	Zone-T
AD	3D-106	ActHtgSP
AD	3D-106	CFM
CS	3D-106	CFM-stpt
AI	3D-105	Zone-T
AD	3D-105	ActHtgSP
AD	3D-105	CFM
CS	3D-105	CFM-stpt
AI	3D-104	Zone-T
AD	3D-104	ActHtgSP
AD	3D-104	CFM
CS	3D-104	CFM-stpt
AI	3D-103	Zone-T
AD	3D-103	ActHtgSP
AD	3D-103	CFM
CS	3D-103	CFM-stpt
AI	3D-102	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	3D-102	ActHtgSP
AD	3D-102	CFM
CS	3D-102	CFM-stpt
AI	3D-101	Zone-T
AD	3D-101	ActHtgSP
AD	3D-101	CFM
CS	3D-101	CFM-stpt
AI	3D-100	Zone-T
AD	3D-100	ActHtgSP
AD	3D-100	CFM
CS	3D-100	CFM-stpt
AI	3D-99	Zone-T
AD	3D-99	ActHtgSP
AD	3D-99	CFM
CS	3D-99	CFM-stpt
AI	3D-98	Zone-T
AD	3D-98	ActHtgSP
AD	3D-98	CFM
CS	3D-98	CFM-stpt
AI	3D-97	Zone-T
AD	3D-97	ActHtgSP
AD	3D-97	CFM
CS	3D-97	CFM-stpt
AI	3C-82	Zone-T
AD	3C-82	ActHtgSP
AD	3C-82	CFM
CS	3C-82	CFM-stpt
AI	3C-81	Zone-T
AD	3C-81	ActHtgSP
AD	3C-81	CFM
CS	3C-81	CFM-stpt
AI	3C-80	Zone-T
AD	3C-80	ActHtgSP
AD	3C-80	CFM
CS	3C-80	CFM-stpt
AI	3C-79	Zone-T
AD	3C-79	ActHtgSP
AD	3C-79	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	3C-79	CFM-stpt
AI	3C-78	Zone-T
AD	3C-78	ActHtgSP
AD	3C-78	CFM
CS	3C-78	CFM-stpt
AI	3C-77	Zone-T
AD	3C-77	ActHtgSP
AD	3C-77	CFM
CS	3C-77	CFM-stpt
AI	3C-75	Zone-T
AD	3C-75	ActHtgSP
AD	3C-75	CFM
CS	3C-75	CFM-stpt
AI	3C-74	Zone-T
AD	3C-74	ActHtgSP
AD	3C-74	CFM
CS	3C-74	CFM-stpt
AI	3C-73	Zone-T
AD	3C-73	ActHtgSP
AD	3C-73	CFM
CS	3C-73	CFM-stpt
AI	3C-71	Zone-T
AD	3C-71	ActHtgSP
AD	3C-71	CFM
CS	3C-71	CFM-stpt
AI	3C-70	Zone-T
AD	3C-70	ActHtgSP
AD	3C-70	CFM
CS	3C-70	CFM-stpt
AI	3C-69	Zone-T
AD	3C-69	ActHtgSP
AD	3C-69	CFM
CS	3C-69	CFM-stpt
AI	3C-68	Zone-T
AD	3C-68	ActHtgSP
AD	3C-68	CFM
CS	3C-68	CFM-stpt
AI	3C-65	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	3C-65	ActHtgSP
AD	3C-65	CFM
CS	3C-65	CFM-stpt
AI	3C-65	Zone-H
CS	3C-65	HUM-stpt
AOS	3C-65	Hum-vlv
BI	3C-65	Air-flow
BO	3C-65	Hum-iso
AI	3C-64	Zone-T
AD	3C-64	ActHtgSP
AD	3C-64	CFM
CS	3C-64	CFM-stpt
AI	3C-64	Zone-H
CS	3C-64	HUM-stpt
AOS	3C-64	Hum-vlv
BI	3C-64	Air-flow
BO	3C-64	Hum-iso
AI	3C-63	Zone-T
AD	3C-63	ActHtgSP
AD	3C-63	CFM
CS	3C-63	CFM-stpt
AI	3C-62	Zone-T
AD	3C-62	ActHtgSP
AD	3C-62	CFM
CS	3C-62	CFM-stpt
AI	3C-61	Zone-T
AD	3C-61	ActHtgSP
AD	3C-61	CFM
CS	3C-61	CFM-stpt
AI	3C-60	Zone-T
AD	3C-60	ActHtgSP
AD	3C-60	CFM
CS	3C-60	CFM-stpt
AI	3C-59	Zone-T
AD	3C-59	ActHtgSP
AD	3C-59	CFM
CS	3C-59	CFM-stpt
AI	3C-58	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	3C-58	ActHtgSP
AD	3C-58	CFM
CS	3C-58	CFM-stpt
AI	3C-57	Zone-T
AD	3C-57	ActHtgSP
AD	3C-57	CFM
CS	3C-57	CFM-stpt
AI	3C-56	Zone-T
AD	3C-56	ActHtgSP
AD	3C-56	CFM
CS	3C-56	CFM-stpt
AI	3C-56	Zone-H
CS	3C-56	HUM-stpt
AOS	3C-56	Hum-vlv
BI	3C-56	Air-flow
BO	3C-56	Hum-iso
AI	3C-55	Zone-T
AD	3C-55	ActHtgSP
AD	3C-55	CFM
CS	3C-55	CFM-stpt
AI	3C-54	Zone-T
AD	3C-54	ActHtgSP
AD	3C-54	CFM
CS	3C-54	CFM-stpt
AI	3C-53	Zone-T
AD	3C-53	ActHtgSP
AD	3C-53	CFM
CS	3C-53	CFM-stpt
AI	3C-53	Zone-H
CS	3C-53	HUM-stpt
AOS	3C-53	Hum-vlv
BI	3C-53	Air-flow
BO	3C-53	Hum-iso
AI	3C-52	Zone-T
AD	3C-52	ActHtgSP
AD	3C-52	CFM
CS	3C-52	CFM-stpt
AI	3C-52	Zone-H

DRAFT

Building 2		
Points	Equipment	Type
CS	3C-52	HUM-stpt
AOS	3C-52	Hum-vlv
BI	3C-52	Air-flow
BO	3C-52	Hum-iso
AI	3C-30	Zone-T
AD	3C-30	ActHtgSP
AD	3C-30	CFM
CS	3C-30	CFM-stpt
AI	3C-29	Zone-T
AD	3C-29	ActHtgSP
AD	3C-29	CFM
CS	3C-29	CFM-stpt
AI	3C-27	Zone-T
AD	3C-27	ActHtgSP
AD	3C-27	CFM
CS	3C-27	CFM-stpt
AI	3C-26	Zone-T
AD	3C-26	ActHtgSP
AD	3C-26	CFM
CS	3C-26	CFM-stpt
AI	3C-25	Zone-T
AD	3C-25	ActHtgSP
AD	3C-25	CFM
CS	3C-25	CFM-stpt
AI	3C-03	Zone-T
AD	3C-03	ActHtgSP
AD	3C-03	CFM
CS	3C-03	CFM-stpt
BD	AHU-3301	OCC
BI	AHU-3301	SF-S
BI	AHU-3301	RF-S
AI	AHU-3301	DA-T
AD	AHU-3301	DA-STPT
AOS	AHU-3301	HTG-VLV
BD	AHU-3301	HTG-PMP
AOS	AHU-3301	CLG-VLV
AOS	AHU-3301	OA-DMPR
AI	AHU-3301	MA-T

DRAFT

Building 2		
Points	Equipment	Type
AI	AHU-3301	RA-T
AI	AHU-3301	OA-T
BI	AHU-3301	LT-ALM
BI	AHU-3301	PURGE
BI	AHU-3301	SHTDWN
BD	AHU-3301	CLG-LOCK
BI	AHU-3301	HAND
AI	AHU-3301	RA-H
AOS	AHU-3301	HUM-VLV
AI	AHU-3301	PRE
AI	AHU-3301	AFT
AI	AHU-3301	HWS
AI	AHU-3301	HWR
AI	AHU-3301	CWS
AI	AHU-3301	CWR
AD	AHU-3301	L-ZONE-T
AD	AHU-3301	H-ZONE-T
BO	AHU-3301	SF-C
BO	AHU-3301	RF-C
BD	AHU-3301	NITEPURG
BD	AHU-3301	EF5_43
AI	3E-42B	Zone-T
AD	3E-42B	ActHtgSP
AD	3E-42B	CFM
CS	3E-42B	CFm-stpt
AI	3C-76	Zone-T
AD	3C-76	ActHtgSP
AD	3C-76	CFM
CS	3C-76	CFM-stpt
AI	3C-76	RM-Press
CS	3C-76	Mode
BD	3C-76	ALM
AI	3C-76	RM-Pres
BD	3C-76	EF4_05
CS	3C-76	Modes
BD	3C-76	ALMS
AI	3C-66	Zone-T
AD	3C-66	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3C-66	CFM
CS	3C-66	CFM-stpt
AI	3C-66	Zone-H
CS	3C-66	HUM-stpt
AOS	3C-66	Hum-vlv
BI	3C-66	Air-flow
BO	3C-66	Hum-iso
BI	3C-66	Filter-S
BD	AHU-3303	OCC
BI	AHU-3303	SF-S
BI	AHU-3303	RF-S
AI	AHU-3303	DA-T
AD	AHU-3303	DA-STPT
AOS	AHU-3303	HTG-VLV
BD	AHU-3303	HTG-PMP
AOS	AHU-3303	CLG-VLV
AOS	AHU-3303	OA-DMPR
AI	AHU-3303	MA-T
AI	AHU-3303	RA-T
AI	AHU-3303	OA-T
BI	AHU-3303	LT-ALM
BI	AHU-3303	PURGE
BI	AHU-3303	SHTDWN
BD	AHU-3303	CLG-LOCK
BI	AHU-3303	HAND
AI	AHU-3303	RA-H
AOS	AHU-3303	HUM-VLV
AI	AHU-3303	PRE
AI	AHU-3303	AFT
AI	AHU-3303	HWS
AI	AHU-3303	HWR
AI	AHU-3303	CWS
AI	AHU-3303	CWR
AD	AHU-3303	L-ZONE-T
AD	AHU-3303	H-ZONE-T
BO	AHU-3303	SF-C
BO	AHU-3303	RF-C
BD	AHU-3303	NITEPURG

DRAFT

Building 2		
Points	Equipment	Type
BO	AHU-3303	EF4_01-C
BI	AHU-3303	EF4_01
BO	AHU-3303	EF4_02-C
BI	AHU-3303	EF4_02
BD	AHU-3304	OCC
BI	AHU-3304	SF-S
BI	AHU-3304	RF-S
AI	AHU-3304	DA-T
AD	AHU-3304	DA-STPT
AOS	AHU-3304	HTG-VLV
BD	AHU-3304	HTG-PMP
AOS	AHU-3304	CLG-VLV
AOS	AHU-3304	OA-DMPR
AI	AHU-3304	MA-T
AI	AHU-3304	RA-T
AI	AHU-3304	OA-T
BI	AHU-3304	LT-ALM
BI	AHU-3304	PURGE
BI	AHU-3304	SHTDWN
BD	AHU-3304	CLG-LOCK
BI	AHU-3304	HAND
AI	AHU-3304	RA-H
AOS	AHU-3304	HUM-VLV
AI	AHU-3304	PRE
AI	AHU-3304	AFT
AI	AHU-3304	HWS
AI	AHU-3304	HWR
AI	AHU-3304	CWS
AI	AHU-3304	CWR
AD	AHU-3304	L-ZONE-T
AD	AHU-3304	H-ZONE-T
BO	AHU-3304	SF-C
BO	AHU-3304	RF-C
BD	AHU-3304	NITEPURG
BO	AHU-3304	EF4_04-C
BI	AHU-3304	EF4_04
BO	AHU-3304	EF4_05-C
BI	AHU-3304	EF4_05

DRAFT

Building 2		
Points	Equipment	Type
BO	AHU-3304	EF4_22-C
BI	AHU-3304	EF4_22
BO	SHARE13	EF3_01-C
BI	SHARE13	EF3_01
BO	SHARE13	EF3_04-C
BI	SHARE13	EF3_04
BO	SHARE13	EF3_28-C
BI	SHARE13	EF3_28
BO	SHARE13	EF3_30-C
BI	SHARE13	EF3_30
BO	SHARE13	EF3_45-C
BI	SHARE13	EF3_45
BO	SHARE13	EF3_70-C
BI	SHARE13	EF3_70
BO	SHARE13	EF4_12-C
BI	SHARE13	EF4_12
BO	SHARE13	EF4_19-C
BI	SHARE13	EF4_19
BO	SHARE13	EF4_20-C
BI	SHARE13	EF4_20
BO	SHARE13	EF4_23-C
BI	SHARE13	EF4_23
CS	CS-NC-13	AHU3301
CS	CS-NC-13	AHU3302
CS	CS-NC-13	AHU3303
CS	CS-NC-13	AHU3304
JCB	CS-NC-13	OA-T
CS	CS-NC-13	AHU3305

Building 2		
Points	**Equipment**	**Type**
NC-14		**Network controller**
NC-14-HW	DC14-142	142, 1, 3, UNT
NC-14-HW	AHU-3602	143, 1, 3, AHU
NC-14-HW	DC14-144	144, 1, 3, UNT

DRAFT

Building 2		
Points	Equipment	Type
NC-14-HW	AHU-3603	145, 1, 3, AHU
NC-14-HW	DC14-146	146, 1, 3, UNT
NC-14-HW	AHU-3604	147, 1, 3, AHU
NC-14-HW	DC14-148	148, 1, 3, UNT
NC-14-HW	AHU-3605	149, 1, 3, AHU
NC-14-HW	DC14-150	150, 1, 3, UNT
NC-14-HW	CVR-01	1, 1, 3, VAV
NC-14-HW	CVR-02	2, 1, 3, VAV
NC-14-HW	CVR-04	4, 1, 3, VAV
NC-14-HW	CVR-05	5, 1, 3, VAV
NC-14-HW	CVR-06	6, 1, 3, VAV
NC-14-HW	CVR-07	7, 1, 3, VAV
NC-14-HW	CVR-08	8, 1, 3, VAV
NC-14-HW	CVR-09	9, 1, 3, VAV
NC-14-HW	CVR-10	10, 1, 3, VAV
NC-14-HW	CVR-11	11, 1, 3, VAV
NC-14-HW	CVR-12	12, 1, 3, VAV
NC-14-HW	CVR-13	13, 1, 3, VAV
NC-14-HW	CVR-14	14, 1, 3, VAV
NC-14-HW	CVR-15	15, 1, 3, VAV
NC-14-HW	CVR-16	16, 1, 3, VAV
NC-14-HW	CVR-117	117, 1, 3, VAV
NC-14-HW	CVR-118	118, 1, 3, VAV
NC-14-HW	CVR-18	18, 1, 3, VAV
NC-14-HW	CVR-19	19, 1, 3, VAV
NC-14-HW	CVR-20	20, 1, 3, VAV
NC-14-HW	CVR-21	21, 1, 3, VAV
NC-14-HW	CVR-22	22, 1, 3, VAV
NC-14-HW	CVR-23	23, 1, 3, VAV
NC-14-HW	CVR-24	24, 1, 3, VAV
NC-14-HW	CVR-25	25, 1, 3, VAV
NC-14-HW	CVR-26	26, 1, 3, VAV
NC-14-HW	CVR-27	27, 1, 3, VAV
NC-14-HW	CVR-28	28, 1, 3, VAV
NC-14-HW	CVR-29	29, 1, 3, VAV
NC-14-HW	CVR-30	30, 1, 3, VAV
NC-14-HW	CVR-31	31, 1, 3, VAV
NC-14-HW	CVR-32	32, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-14-HW	CVR-33	33, 1, 3, VAV
NC-14-HW	CVR-34	34, 1, 3, VAV
NC-14-HW	CVR-35	35, 1, 3, VAV
NC-14-HW	CVR-36	36, 1, 3, VAV
NC-14-HW	CVR-37	37, 1, 3, VAV
NC-14-HW	CVR-38	38, 1, 3, VAV
NC-14-HW	CVR-39	39, 1, 3, VAV
NC-14-HW	CVR-40	40, 1, 3, VAV
NC-14-HW	CVR-41	41, 1, 3, VAV
NC-14-HW	CVR-42	42, 1, 3, VAV
NC-14-HW	CVR-43	43, 1, 3, VAV
NC-14-HW	CVR-44	44, 1, 3, VAV
NC-14-HW	CVR-45	45, 1, 3, VAV
NC-14-HW	CVR-46	46, 1, 3, VAV
NC-14-HW	CVR-47	47, 1, 3, VAV
NC-14-HW	CVR-48	48, 1, 3, VAV
NC-14-HW	CVR-49	49, 1, 3, VAV
NC-14-HW	CVR-65	65, 1, 3, VAV
NC-14-HW	CVR-66	66, 1, 3, VAV
NC-14-HW	CVR-67	67, 1, 3, VAV
NC-14-HW	CVR-68	68, 1, 3, VAV
NC-14-HW	CVR-69	69, 1, 3, VAV
NC-14-HW	CVR-70	70, 1, 3, VAV
NC-14-HW	CVR-71	71, 1, 3, VAV
NC-14-HW	CVR-72	72, 1, 3, VAV
NC-14-HW	CVR-73	73, 1, 3, VAV
NC-14-HW	CVR-74	74, 1, 3, VAV
NC-14-HW	CVR-75	75, 1, 3, VAV
NC-14-HW	CVR-76	76, 1, 3, VAV
NC-14-HW	CVR-77	77, 1, 3, VAV
NC-14-HW	CVR-78	78, 1, 3, VAV
NC-14-HW	CVR-79	79, 1, 3, VAV
NC-14-HW	CVR-80	80, 1, 3, VAV
NC-14-HW	CVR-81	81, 1, 3, VAV
NC-14-HW	CVR-82	82, 1, 3, VAV
NC-14-HW	CVR-83	83, 1, 3, VAV
NC-14-HW	CVR-84	84, 1, 3, VAV
NC-14-HW	CVR-85	85, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-14-HW	CVR-86	86, 1, 3, VAV
NC-14-HW	CVR-87	87, 1, 3, VAV
NC-14-HW	CVR-88	88, 1, 3, VAV
NC-14-HW	CVR-89	89, 1, 3, VAV
NC-14-HW	CVR-90	90, 1, 3, VAV
NC-14-HW	CVR-91	91, 1, 3, VAV
NC-14-HW	CVR-92	92, 1, 3, VAV
NC-14-HW	CVR-93	93, 1, 3, VAV
NC-14-HW	CVR-94	94, 1, 3, VAV
NC-14-HW	CVR-95	95, 1, 3, VAV
NC-14-HW	CVR-96	96, 1, 3, VAV
NC-14-HW	CVR-97	97, 1, 3, VAV
NC-14-HW	CVR-98	98, 1, 3, VAV
NC-14-HW	CVR-99	99, 1, 3, VAV
NC-14-HW	CVR-100	100, 1, 3, VAV
NC-14-HW	CVR-101	101, 1, 3, VAV
NC-14-HW	CVR-102	102, 1, 3, VAV
NC-14-HW	CVR-103	103, 1, 3, VAV
NC-14-HW	CVR-104	104, 1, 3, VAV
NC-14-HW	CVR-105	105, 1, 3, VAV
NC-14-HW	CVR-106	106, 1, 3, VAV
NC-14-HW	DC14-64	64, 1, 3, VAV
NC-14-HW	ISO-210	210, 1, 3, VND
NC-14-HW	ISO-211	211, 1, 3, VND
NC-14-HW	ISO-212	212, 1, 3, VND
NC-14-HW	ISO-213	213, 1, 3, VND
NC-14-HW	ISO-214	214, 1, 3, VND
NC-14-HW	ISO-215	215, 1, 3, VND
NC-14-HW	ISO-216	216, 1, 3, VND
NC-14-HW	ISO-217	217, 1, 3, VND
NC-14-HW	ISO-218	218, 1, 3, VND
NC-14-HW	DC-50	50, 1, 3, VAV
NC-14-HW	CVR-03	3, 1, 3, VAV
JCB	JCB-NC14	3602-OCC
JCB	JCB-NC14	3605-OCC
JCB	JCB-NC14	3601-SMK
JCB	JCB-NC14	3602-SMK
JCB	JCB-NC14	3603-SMK

DRAFT

Building 2		
Points	Equipment	Type
JCB	JCB-NC14	3604-SMK
JCB	JCB-NC14	3605-SMK
JCB	JCB-NC14	36_05-TE
JCB	JCB-NC14	3603-PMP
JCB	JCB-NC14	3601-PMP
JCB	JCB-NC14	3602-PMP
JCB	JCB-NC14	3604-PMP
JCB	JCB-NC14	3605-PMP
JCB	JCB-NC14	36_04EF
JCB	JCB-NC14	36_01-TE
JCB	JCB-NC14	36_02EF
JCB	JCB-NC14	3601AITB
JCB	JCB-NC14	3602AITB
JCB	JCB-NC14	3603AITB
JCB	JCB-NC14	3604AITB
JCB	JCB-NC14	3605AITB
JCB	JCB-NC14	36_03EF
JCB	JCB-NC14	3605ZHUM
JCB	JCB-NC14	36_02-TE
JCB	JCB-NC14	3603-OCC
JCB	JCB-NC14	3604-OCC
JCB	JCB-NC14	36_03-TE
JCB	JCB-NC14	36_04-TE
JCB	JCB-NC14	36_01EF
BD	AHU-3602	OCC
BI	AHU-3602	SF-S
BI	AHU-3602	RF-S
AI	AHU-3602	DA-T
AD	AHU-3602	DA-STPT
AOS	AHU-3602	HTG-VLV
BD	AHU-3602	HTG-PMP
AOS	AHU-3602	CLG-VLV
AOS	AHU-3602	OA-DMPR
AI	AHU-3602	MA-T
AI	AHU-3602	RA-T
AI	AHU-3602	OA-T
BI	AHU-3602	LT-ALM
BI	AHU-3602	PURGE

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-3602	SHTDWN
BD	AHU-3602	CLG-LOCK
BI	AHU-3602	HAND
AI	AHU-3602	RA-H
AOS	AHU-3602	HUM-VLV
AI	AHU-3602	PRE
AI	AHU-3602	AFT
AI	AHU-3602	HWS
AI	AHU-3602	HWR
AI	AHU-3602	CWS
AI	AHU-3602	CWR
AD	AHU-3602	L-ZONE-T
AD	AHU-3602	H-ZONE-T
BO	AHU-3602	SF-C
BO	AHU-3602	RF-C
BD	AHU-3602	EF4_23
BD	AHU-3602	EF4_24
BD	AHU-3602	EF5_27
BD	AHU-3602	EF5_32
BD	AHU-3602	EF8_01
BD	AHU-3602	NITEPURG
BD	AHU-3602	EF4_07
BD	AHU-3602	EF_08
BO	SHARE14	EF3_24-C
BI	SHARE14	EF3_24
BO	SHARE14	EF3_41-C
BI	SHARE14	EF3_41
BO	SHARE14	EF4_18-C
BI	SHARE14	EF4_18
AI	3E-07	Zone-T
AD	3E-07	ActHtgSP
AD	3E-07	CFM
CS	3E-07	CFM-stpt
AI	3E-07	RM-Press
CS	3E-07	Mode
BD	3E-07	ALM
BD	3E-07	EF5_06
AI	3E-06	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	3E-06	ActHtgSP
AD	3E-06	CFM
CS	3E-06	CFM-stpt
AI	3E-06	RM-Press
CS	3E-06	Mode
BD	3E-06	ALM
BD	3E-06	EF5_06
AI	3E-35	Zone-T
AD	3E-35	ActHtgSP
AD	3E-35	CFM
CS	3E-35	CFM-stpt
AI	3E-35	RM-Press
AD	3E-35	Alm-Stat
CS	3E-35	Mode
BD	3E-35	ALM
BD	3E-35	EF5_12
AI	3E-36	Zone-T
AD	3E-36	ActHtgSP
AD	3E-36	CFM
CS	3E-36	CFM-stpt
AI	3E-36	RM-Press
AD	3E-36	Alm-Stat
CS	3E-36	Mode
BD	3E-36	ALM
BD	3E-36	EF5_12
BD	AHU-3603	OCC
BI	AHU-3603	SF-S
BI	AHU-3603	RF-S
AI	AHU-3603	DA-T
AD	AHU-3603	DA-STPT
AOS	AHU-3603	HTG-VLV
BD	AHU-3603	HTG-PMP
AOS	AHU-3603	CLG-VLV
AOS	AHU-3603	OA-DMPR
AI	AHU-3603	MA-T
AI	AHU-3603	RA-T
AI	AHU-3603	OA-T
BI	AHU-3603	LT-ALM

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-3603	PURGE
BI	AHU-3603	SHTDWN
BD	AHU-3603	CLG-LOCK
BI	AHU-3603	HAND
AI	AHU-3603	RA-H
AOS	AHU-3603	HUM-VLV
AI	AHU-3603	PRE
AI	AHU-3603	AFT
AI	AHU-3603	HWS
AI	AHU-3603	HWR
AI	AHU-3603	CWS
AI	AHU-3603	CWR
AD	AHU-3603	L-ZONE-T
AD	AHU-3603	H-ZONE-T
AD	AHU-3603	A-ZONE-T
BO	AHU-3603	SF-C
BO	AHU-3603	RF-C
BD	AHU-3603	EF3_15
BD	AHU-3603	EF3_16
BD	AHU-3603	EF3_23
BD	AHU-3603	EF3_24
BD	AHU-3603	EF3_25
BD	AHU-3603	NITEPURG
AI	3F-25	Zone-T
AD	3F-25	ActHtgSP
AD	3F-25	CFM
CS	3F-25	CFM-stpt
AI	3F-25	RM-Press
BD	3F-25	EF5_50
CS	3F-25	Mode
BD	3F-25	ALM
AI	3F-06	Zone-T
AD	3F-06	ActHtgSP
AD	3F-06	CFM
CS	3F-06	CFM-stpt
AI	3F-06	RM-Press
BD	3F-06	EF5_34
CS	3F-06	Mode

DRAFT

Building 2		
Points	Equipment	Type
BD	3F-06	ALM
AI	3F-05	Zone-T
AD	3F-05	ActHtgSP
AD	3F-05	CFM
CS	3F-05	CFM-stpt
AI	3F-05	RM-Press
BD	3F-05	EF5_34
CS	3F-05	Mode
BD	3F-05	ALM
AI	3F-42	Zone-T
AD	3F-42	CFM
CS	3F-42	CFM-stpt
AI	3F-01	Zone-T
AD	3F-01	ActHtgSP
AD	3F-01	CFM
CS	3F-01	CFM-stpt
AI	3F-02	Zone-T
AD	3F-02	ActHtgSP
AD	3F-02	CFM
CS	3F-02	CFM-stpt
AI	3F-03	Zone-T
AD	3F-03	ActHtgSP
AD	3F-03	CFM
CS	3F-03	CFM-stpt
AI	3F-04	Zone-T
AD	3F-04	ActHtgSP
AD	3F-04	CFM
CS	3F-04	CFM-stpt
AI	3F-07	Zone-T
AD	3F-07	ActHtgSP
AD	3F-07	CFM
CS	3F-07	CFM-stpt
AI	3F-08	Zone-T
AD	3F-08	ActHtgSP
AD	3F-08	CFM
CS	3F-08	CFM-stpt
AI	3F-09	Zone-T
AD	3F-09	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3F-09	CFM
CS	3F-09	CFM-stpt
AI	3F-10	Zone-T
AD	3F-10	ActHtgSP
AD	3F-10	CFM
CS	3F-10	CFM-stpt
AI	3F-11	Zone-T
AD	3F-11	ActHtgSP
AD	3F-11	CFM
CS	3F-11	CFM-stpt
AI	3F-12	Zone-T
AD	3F-12	ActHtgSP
AD	3F-12	CFM
CS	3F-12	CFM-stpt
AI	3F-13	Zone-T
AD	3F-13	ActHtgSP
AD	3F-13	CFM
CS	3F-13	CFM-stpt
AI	3F-14	Zone-T
AD	3F-14	ActHtgSP
AD	3F-14	CFM
CS	3F-14	CFM-stpt
AI	3F-15	Zone-T
AD	3F-15	ActHtgSP
AD	3F-15	CFM
CS	3F-15	CFM-stpt
AI	3F-16	Zone-T
AD	3F-16	ActHtgSP
AD	3F-16	CFM
CS	3F-16	CFM-stpt
AI	3F-17	Zone-T
AD	3F-17	ActHtgSP
AD	3F-17	CFM
CS	3F-17	CFM-stpt
AI	3F-18	Zone-T
AD	3F-18	ActHtgSP
AD	3F-18	CFM
CS	3F-18	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	3F-19	Zone-T
AD	3F-19	ActHtgSP
AD	3F-19	CFM
CS	3F-19	CFM-stpt
AI	3F-21	Zone-T
AD	3F-21	ActHtgSP
AD	3F-21	CFM
CS	3F-21	CFM-stpt
AI	3F-22	Zone-T
AD	3F-22	ActHtgSP
AD	3F-22	CFM
CS	3F-22	CFM-stpt
AI	3F-23	Zone-T
AD	3F-23	ActHtgSP
AD	3F-23	CFM
CS	3F-23	CFM-stpt
AI	3F-24	Zone-T
AD	3F-24	ActHtgSP
AD	3F-24	CFM
CS	3F-24	CFM-stpt
AI	3F-26	Zone-T
AD	3F-26	ActHtgSP
AD	3F-26	CFM
CS	3F-26	CFM-stpt
AI	3F-27	Zone-T
AD	3F-27	ActHtgSP
AD	3F-27	CFM
CS	3F-27	CFM-stpt
AI	3F-28	Zone-T
AD	3F-28	ActHtgSP
AD	3F-28	CFM
CS	3F-28	CFM-stpt
AI	3F-29	Zone-T
AD	3F-29	ActHtgSP
AD	3F-29	CFM
CS	3F-29	CFM-stpt
AI	3F-30	Zone-T
AD	3F-30	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3F-30	CFM
CS	3F-30	CFM-stpt
AI	3F-31	Zone-T
AD	3F-31	ActHtgSP
AD	3F-31	CFM
CS	3F-31	CFM-stpt
AI	3F-32	Zone-T
AD	3F-32	ActHtgSP
AD	3F-32	CFM
CS	3F-32	CFM-stpt
AI	3F-33	Zone-T
AD	3F-33	ActHtgSP
AD	3F-33	CFM
CS	3F-33	CFM-stpt
AI	3F-34	Zone-T
AD	3F-34	ActHtgSP
AD	3F-34	CFM
CS	3F-34	CFM-stpt
AI	3F-35	Zone-T
AD	3F-35	ActHtgSP
AD	3F-35	CFM
CS	3F-35	CFM-stpt
AI	3F-36	Zone-T
AD	3F-36	ActHtgSP
AD	3F-36	CFM
CS	3F-36	CFM-stpt
AI	3F-37	Zone-T
AD	3F-37	ActHtgSP
AD	3F-37	CFM
CS	3F-37	CFM-stpt
AI	3F-38	Zone-T
AD	3F-38	ActHtgSP
AD	3F-38	CFM
CS	3F-38	CFM-stpt
AI	3F-39	Zone-T
AD	3F-39	ActHtgSP
AD	3F-39	CFM
CS	3F-39	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	3F-40	Zone-T
AD	3F-40	ActHtgSP
AD	3F-40	CFM
CS	3F-40	CFM-stpt
AI	3F-41	Zone-T
AD	3F-41	ActHtgSP
AD	3F-41	CFM
CS	3F-41	CFM-stpt
AI	3E-01	Zone-T
AD	3E-01	ActHtgSP
AD	3E-01	CFM
CS	3E-01	CFM-stpt
AI	3E-02	Zone-T
AD	3E-02	ActHtgSP
AD	3E-02	CFM
CS	3E-02	CFM-stpt
AI	3E-04	Zone-T
AD	3E-04	ActHtgSP
AD	3E-04	CFM
CS	3E-04	CFM-stpt
AI	3E-05	Zone-T
AD	3E-05	ActHtgSP
AD	3E-05	CFM
CS	3E-05	CFM-stpt
AI	3E-08	Zone-T
AD	3E-08	ActHtgSP
AD	3E-08	CFM
CS	3E-08	CFM-stpt
AI	3E-09	Zone-T
AD	3E-09	ActHtgSP
AD	3E-09	CFM
CS	3E-09	CFM-stpt
AI	3E-10	Zone-T
AD	3E-10	ActHtgSP
AD	3E-10	CFM
CS	3E-10	CFM-stpt
AI	3E-11	Zone-T
AD	3E-11	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3E-11	CFM
CS	3E-11	CFM-stpt
AI	3E-12	Zone-T
AD	3E-12	ActHtgSP
AD	3E-12	CFM
CS	3E-12	CFM-stpt
AI	3E-13	Zone-T
AD	3E-13	ActHtgSP
AD	3E-13	CFM
CS	3E-13	CFM-stpt
AI	3E-14	Zone-T
AD	3E-14	ActHtgSP
AD	3E-14	CFM
CS	3E-14	CFM-stpt
AI	3E-15	Zone-T
AD	3E-15	ActHtgSP
AD	3E-15	CFM
CS	3E-15	CFM-stpt
AI	3E-18	Zone-T
AD	3E-18	ActHtgSP
AD	3E-18	CFM
CS	3E-18	CFM-stpt
AI	3E-19	Zone-T
AD	3E-19	ActHtgSP
AD	3E-19	CFM
CS	3E-19	CFM-stpt
AI	3E-20	Zone-T
AD	3E-20	ActHtgSP
AD	3E-20	CFM
CS	3E-20	CFM-stpt
AI	3E-21	Zone-T
AD	3E-21	ActHtgSP
AD	3E-21	CFM
CS	3E-21	CFM-stpt
AI	3E-22	Zone-T
AD	3E-22	ActHtgSP
AD	3E-22	CFM
CS	3E-22	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	3E-23	Zone-T
AD	3E-23	ActHtgSP
AD	3E-23	CFM
CS	3E-23	CFM-stpt
AI	3E-24	Zone-T
AD	3E-24	ActHtgSP
AD	3E-24	CFM
CS	3E-24	CFM-stpt
AI	3E-25	Zone-T
AD	3E-25	ActHtgSP
AD	3E-25	CFM
CS	3E-25	CFM-stpt
AI	3E-26	Zone-T
AD	3E-26	ActHtgSP
AD	3E-26	CFM
CS	3E-26	CFM-stpt
AI	3E-27	Zone-T
AD	3E-27	ActHtgSP
AD	3E-27	CFM
CS	3E-27	CFM-stpt
AI	3E-28	Zone-T
AD	3E-28	ActHtgSP
AD	3E-28	CFM
CS	3E-28	CFM-stpt
AI	3E-29	Zone-T
AD	3E-29	ActHtgSP
AD	3E-29	CFM
CS	3E-29	CFM-stpt
AI	3E-30	Zone-T
AD	3E-30	ActHtgSP
AD	3E-30	CFM
CS	3E-30	CFM-stpt
AI	3E-31	Zone-T
AD	3E-31	ActHtgSP
AD	3E-31	CFM
CS	3E-31	CFM-stpt
AI	3E-32	Zone-T
AD	3E-32	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	3E-32	CFM
CS	3E-32	CFM-stpt
AI	3E-33	Zone-T
AD	3E-33	ActHtgSP
AD	3E-33	CFM
CS	3E-33	CFM-stpt
AI	3E-34	Zone-T
AD	3E-34	ActHtgSP
AD	3E-34	CFM
CS	3E-34	CFM-stpt
AI	3E-37	Zone-T
AD	3E-37	ActHtgSP
AD	3E-37	CFM
CS	3E-37	CFM-stpt
AI	3E-38	Zone-T
AD	3E-38	ActHtgSP
AD	3E-38	CFM
CS	3E-38	CFM-stpt
AI	3E-39	Zone-T
AD	3E-39	ActHtgSP
AD	3E-39	CFM
CS	3E-39	CFM-stpt
AI	3E-40	Zone-T
AD	3E-40	ActHtgSP
AD	3E-40	CFM
CS	3E-40	CFM-stpt
AI	3E-41	Zone-T
AD	3E-41	ActHtgSP
AD	3E-41	CFM
CS	3E-41	CFM-stpt
AI	3E-42	Zone-T
AD	3E-42	ActHtgSP
AD	3E-42	CFM
CS	3E-42	CFM-stpt
AI	3E-43	Zone-T
AD	3E-43	ActHtgSP
AD	3E-43	CFM
CS	3E-43	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	3E-44	Zone-T
AD	3E-44	ActHtgSP
AD	3E-44	CFM
CS	3E-44	CFM-stpt
AI	3E-45	Zone-T
AD	3E-45	ActHtgSP
AD	3E-45	CFM
CS	3E-45	CFM-stpt
AI	3E-46	Zone-T
AD	3E-46	ActHtgSP
AD	3E-46	CFM
CS	3E-46	CFM-stpt
AI	3E-47	Zone-T
AD	3E-47	ActHtgSP
AD	3E-47	CFM
CS	3E-47	CFM-stpt
AI	3E-48	Zone-T
AD	3E-48	ActHtgSP
AD	3E-48	CFM
CS	3E-48	CFM-stpt
AI	3E-49	Zone-T
AD	3E-49	ActHtgSP
AD	3E-49	CFM
CS	3E-49	CFM-stpt
CS	CS-NC-14	AHU3601
CS	CS-NC-14	AHU3602
CS	CS-NC-14	AHU3603
CS	CS-NC-14	AHU3604
CS	CS-NC-14	AHU3605
BD	AHU-3604	OCC
BI	AHU-3604	SF-S
BI	AHU-3604	RF-S
AI	AHU-3604	DA-T
AD	AHU-3604	DA-STPT
AOS	AHU-3604	HTG-VLV
BD	AHU-3604	HTG-PMP
AOS	AHU-3604	CLG-VLV
AOS	AHU-3604	OA-DMPR

DRAFT

Building 2		
Points	Equipment	Type
AI	AHU-3604	MA-T
AI	AHU-3604	RA-T
AI	AHU-3604	OA-T
BI	AHU-3604	LT-ALM
BI	AHU-3604	PURGE
BI	AHU-3604	SHTDWN
BD	AHU-3604	CLG-LOCK
BI	AHU-3604	HAND
AI	AHU-3604	RA-H
AOS	AHU-3604	HUM-VLV
AI	AHU-3604	PRE
AI	AHU-3604	AFT
AI	AHU-3604	HWS
AI	AHU-3604	HWR
AI	AHU-3604	CWS
AI	AHU-3604	CWR
AD	AHU-3604	L-ZONE-T
AD	AHU-3604	H-ZONE-T
BO	AHU-3604	SF-C
BO	AHU-3604	RF-C
BD	AHU-3604	EF3_50
BD	AHU-3604	EF3_51
BD	AHU-3604	EF3_53
BD	AHU-3604	NITEPURG
BD	AHU-3605	OCC
BI	AHU-3605	SF-S
BI	AHU-3605	RF-S
AI	AHU-3605	DA-T
AD	AHU-3605	DA-STPT
AOS	AHU-3605	HTG-VLV
BD	AHU-3605	HTG-PMP
AOS	AHU-3605	CLG-VLV
AOS	AHU-3605	OA-DMPR
AI	AHU-3605	MA-T
AI	AHU-3605	RA-T
AI	AHU-3605	OA-T
BI	AHU-3605	LT-ALM
BI	AHU-3605	PURGE

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-3605	SHTDWN
BD	AHU-3605	CLG-LOCK
BI	AHU-3605	HAND
AI	AHU-3605	RA-H
AOS	AHU-3605	HUM-VLV
AI	AHU-3605	PRE
AI	AHU-3605	AFT
AI	AHU-3605	HWS
AI	AHU-3605	HWR
AI	AHU-3605	CWS
AI	AHU-3605	CWR
AD	AHU-3605	L-ZONE-T
AD	AHU-3605	H-ZONE-T
BO	AHU-3605	SF-C
BO	AHU-3605	RF-C
BD	AHU-3605	NITEPURG
BD	AHU-3601	OCC
BI	AHU-3601	SF-S
BI	AHU-3601	RF-S
AI	AHU-3601	DA-T
AD	AHU-3601	DA-STPT
AOS	AHU-3601	HTG-VLV
BD	AHU-3601	HTG-PMP
AOS	AHU-3601	CLG-VLV
AOS	AHU-3601	OA-DMPR
AI	AHU-3601	MA-T
AI	AHU-3601	RA-T
AI	AHU-3601	OA-T
BI	AHU-3601	LT-ALM
BI	AHU-3601	PURGE
BI	AHU-3601	SHTDWN
BD	AHU-3601	CLG-LOCK
BI	AHU-3601	HAND
AI	AHU-3601	RA-H
AOS	AHU-3601	HUM-VLV
AI	AHU-3601	PRE
AI	AHU-3601	AFT
AI	AHU-3601	HWS

DRAFT

Building 2		
Points	Equipment	Type
AI	AHU-3601	HWR
AI	AHU-3601	CWS
AI	AHU-3601	CWR
AD	AHU-3601	L-ZONE-T
AD	AHU-3601	H-ZONE-T
BO	AHU-3601	SF-C
BO	AHU-3601	RF-C
BD	AHU-3601	NITEPURG
BD	AHU-3601	EF5_23
BD	AHU-3601	EF5_31
BD	AHU-3601	EF5_36
AI	AHU-3601	CW-DP
AI	3E-17B	Zone-T
AD	3E-17B	ActHtgSP
CS	3E-17B	CFM-stpt
AD	3E-17B	CFM
AI	3E-17A	Zone-T
AD	3E-17A	ActHtgSP
CS	3E-17A	CFM-stpt
AD	3E-17A	CFM
AI	3E-17A	RM-Press
BD	3E-17A	EF5_05
CS	3E-17A	Mode
BD	3E-17A	ALM
AI	3E-16	Zone-T
AD	3E-16	ActHtgSP
AD	3E-16	CFM
CS	3E-16	CFM-stpt
AI	3E-16	RM-Press
BD	3E-16	EF5_05
CS	3E-16	Mode
BD	3E-16	ALM
AD	3E-16	ALM-STAT
AI	3F-20	Zone-T
AD	3F-20	ActHtgSP
AD	3F-20	CFM
CS	3F-20	CFM-stpt
AI	CARDIOV	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AI	CARDIOV	Z-StPt
AI	CARDIOV	Zone-H
AI	CARDIOV	DA-T
AOS	CARDIOV	HW-VLV

Building 2		
Points	**Equipment**	**Type**
NC-15		**Network controller**
NC-15-HW	DC-153	152, 1, 3, AHU
NC-15-HW	DC-154	153, 1, 3, UNT
NC-15-HW	CVR-01	154, 1, 3, UNT
NC-15-HW	CVR-02	1, 1, 3, VAV
NC-15-HW	CVR-03	2, 1, 3, VAV
NC-15-HW	CVR-04	3, 1, 3, VAV
NC-15-HW	CVR-05	4, 1, 3, VAV
NC-15-HW	CVR-06	5, 1, 3, VAV
NC-15-HW	CVR-07	6, 1, 3, VAV
NC-15-HW	CVR-08	7, 1, 3, VAV
NC-15-HW	CVR-09	8, 1, 3, VAV
NC-15-HW	CVR-10	9, 1, 3, VAV
NC-15-HW	CVR-11	10, 1, 3, VAV
NC-15-HW	CVR-12	11, 1, 3, VAV
NC-15-HW	CVR-13	12, 1, 3, VAV
NC-15-HW	CVR-14	13, 1, 3, VAV
NC-15-HW	CVR-15	14, 1, 3, VAV
NC-15-HW	CVR-16	15, 1, 3, VAV
NC-15-HW	CVR-17	16, 1, 3, VAV
NC-15-HW	CVR-18	17, 1, 3, VAV
NC-15-HW	CVR-19	18, 1, 3, VAV
NC-15-HW	CVR-20	19, 1, 3, VAV
NC-15-HW	CVR-21	20, 1, 3, VAV
NC-15-HW	CVR-22	21, 1, 3, VAV
NC-15-HW	CVR-23	22, 1, 3, VAV
NC-15-HW	CVR-24	23, 1, 3, VAV
NC-15-HW	CVR-25	24, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-15-HW	CVR-26	25, 1, 3, VAV
NC-15-HW	CVR-27	26, 1, 3, VAV
NC-15-HW	CVR-28	27, 1, 3, VAV
NC-15-HW	CVR-29	28, 1, 3, VAV
NC-15-HW	CVR-30	29, 1, 3, VAV
NC-15-HW	CVR-38	30, 1, 3, VAV
NC-15-HW	CVR-39	38, 1, 3, VAV
NC-15-HW	CVR-40	39, 1, 3, VAV
NC-15-HW	CVR-41	40, 1, 3, VAV
NC-15-HW	CVR-42	41, 1, 3, VAV
NC-15-HW	CVR-45	42, 1, 3, VAV
NC-15-HW	CVR-46	45, 1, 3, VAV
NC-15-HW	CVR-47	46, 1, 3, VAV
NC-15-HW	CVR-48	47, 1, 3, VAV
NC-15-HW	CVR-49	48, 1, 3, VAV
NC-15-HW	CVR-49A	37, 1, 3, VAV
NC-15-HW	CVR-51	150, 1, 3, VAV
NC-15-HW	CVR-52	51, 1, 3, VAV
NC-15-HW	CVR-53	52, 1, 3, VAV
NC-15-HW	CVR-54	53, 1, 3, VAV
NC-15-HW	CVR-55	54, 1, 3, VAV
NC-15-HW	CVR-56	55, 1, 3, VAV
NC-15-HW	CVR-57	56, 1, 3, VAV
NC-15-HW	CVR-61	57, 1, 3, VAV
NC-15-HW	CVR-62	61, 1, 3, VAV
NC-15-HW	CVR-63	62, 1, 3, VAV
NC-15-HW	CVR-64	63, 1, 3, VAV
NC-15-HW	CVR-65	64, 1, 3, VAV
NC-15-HW	CVR-165	65, 1, 3, VAV
NC-15-HW	CVR-166	165, 1, 3, VAV
NC-15-HW	CVR-66	166, 1, 3, VAV
NC-15-HW	CVR-67	66, 1, 3, VAV
NC-15-HW	CVR-68	67, 1, 3, VAV
NC-15-HW	CVR-69	68, 1, 3, VAV
NC-15-HW	CVR-70	69, 1, 3, VAV
NC-15-HW	CVR-71	70, 1, 3, VAV
NC-15-HW	CVR-72	71, 1, 3, VAV
NC-15-HW	CVR-73	72, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-15-HW	CVR-74	73, 1, 3, VAV
NC-15-HW	CVR-75	74, 1, 3, VAV
NC-15-HW	CVR-76	75, 1, 3, VAV
NC-15-HW	CVR-77	76, 1, 3, VAV
NC-15-HW	CVR-78	77, 1, 3, VAV
NC-15-HW	CVR-79	78, 1, 3, VAV
NC-15-HW	CVR-80	79, 1, 3, VAV
NC-15-HW	CVR-81	80, 1, 3, VAV
NC-15-HW	CVR-82	81, 1, 3, VAV
NC-15-HW	CVR-83	82, 1, 3, VAV
NC-15-HW	CVR-84	83, 1, 3, VAV
NC-15-HW	CVR-85	84, 1, 3, VAV
NC-15-HW	CVR-86	85, 1, 3, VAV
NC-15-HW	CVR-87	86, 1, 3, VAV
NC-15-HW	CVR-187	87, 1, 3, VAV
NC-15-HW	CVR-191	187, 1, 3, VAV
NC-15-HW	CVR-192	191, 1, 3, VAV
NC-15-HW	CVR-193	192, 1, 3, VAV
NC-15-HW	CVR-194	193, 1, 3, VAV
NC-15-HW	CVR-195	194, 1, 3, VAV
NC-15-HW	CVR-196	195, 1, 3, VAV
NC-15-HW	CVR-209	196, 1, 3, VAV
NC-15-HW	ISO-210	209, 1, 3, VAV
NC-15-HW	ISO-211	210, 1, 3, VND
NC-15-HW	ISO-212	211, 1, 3, VND
NC-15-HW	ISO-213	212, 1, 3, VND
NC-15-HW	ISO-215	213, 1, 3, VND
NC-15-HW	ISO-216	215, 1, 3, VND
JCB	JCB-NC15	216, 1, 3, VND
JCB	JCB-NC15	5201-PMP
JCB	JCB-NC15	5201-SMK
JCB	JCB-NC15	52_01EF
JCB	JCB-NC15	5201AITB
AI	4A-06	Zone-T
AD	4A-06	CFM
CS	4A-06	CFM-stpt
AI	4A-01	Zone-T
AD	4A-01	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	4A-01	CFM-stpt
CS	CS-NC-15	AHU5201
AI	4A-02	Zone-T
AD	4A-02	ActHtgSP
AD	4A-02	CFM
CS	4A-02	CFM-stpt
AI	4A-03	Zone-T
AD	4A-03	ActHtgSP
AD	4A-03	CFM
CS	4A-03	CFM-stpt
AI	4A-04	Zone-T
AD	4A-04	ActHtgSP
AD	4A-04	CFM
CS	4A-04	CFM-stpt
AI	4A-05	Zone-T
AD	4A-05	ActHtgSP
AD	4A-05	CFM
CS	4A-05	CFM-stpt
AI	4A-07	Zone-T
AD	4A-07	ActHtgSP
AD	4A-07	CFM
CS	4A-07	CFM-stpt
AI	4A-08	Zone-T
AD	4A-08	ActHtgSP
AD	4A-08	CFM
CS	4A-08	CFM-stpt
AI	4A-09	Zone-T
AD	4A-09	ActHtgSP
AD	4A-09	CFM
CS	4A-09	CFM-stpt
AI	4A-10	Zone-T
AD	4A-10	ActHtgSP
AD	4A-10	CFM
CS	4A-10	CFM-stpt
AI	4A-11	Zone-T
AD	4A-11	ActHtgSP
AD	4A-11	CFM
CS	4A-11	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4A-12	Zone-T
AD	4A-12	ActHtgSP
AD	4A-12	CFM
CS	4A-12	CFM-stpt
AI	4A-13	Zone-T
AD	4A-13	ActHtgSP
AD	4A-13	CFM
CS	4A-13	CFM-stpt
AI	4A-14	Zone-T
AD	4A-14	ActHtgSP
AD	4A-14	CFM
CS	4A-14	CFM-stpt
AI	4A-15	Zone-T
AD	4A-15	ActHtgSP
AD	4A-15	CFM
CS	4A-15	CFM-stpt
AI	4A-16	Zone-T
AD	4A-16	ActHtgSP
AD	4A-16	CFM
CS	4A-16	CFM-stpt
AI	4A-17	Zone-T
AD	4A-17	ActHtgSP
AD	4A-17	CFM
CS	4A-17	CFM-stpt
AI	4A-18	Zone-T
AD	4A-18	ActHtgSP
AD	4A-18	CFM
CS	4A-18	CFM-stpt
AI	4A-21	Zone-T
AD	4A-21	ActHtgSP
AD	4A-21	CFM
CS	4A-21	CFM-stpt
AI	4A-22	Zone-T
AD	4A-22	ActHtgSP
AD	4A-22	CFM
CS	4A-22	CFM-stpt
AI	4A-23	Zone-T
AD	4A-23	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4A-23	CFM
CS	4A-23	CFM-stpt
AI	4A-24	Zone-T
AD	4A-24	ActHtgSP
AD	4A-24	CFM
CS	4A-24	CFM-stpt
AI	4A-25	Zone-T
AD	4A-25	ActHtgSP
AD	4A-25	CFM
CS	4A-25	CFM-stpt
AI	4A-26	Zone-T
AD	4A-26	ActHtgSP
AD	4A-26	CFM
CS	4A-26	CFM-stpt
AI	4A-27	Zone-T
AD	4A-27	ActHtgSP
AD	4A-27	CFM
CS	4A-27	CFM-stpt
AI	4A-28	Zone-T
AD	4A-28	ActHtgSP
AD	4A-28	CFM
CS	4A-28	CFM-stpt
AI	4A-29	Zone-T
AD	4A-29	ActHtgSP
AD	4A-29	CFM
CS	4A-29	CFM-stpt
AI	4A-30	Zone-T
AD	4A-30	ActHtgSP
AD	4A-30	CFM
CS	4A-30	CFM-stpt
AI	4A-40	Zone-T
AD	4A-40	ActHtgSP
AD	4A-40	CFM
CS	4A-40	CFM-stpt
AI	4A-41	Zone-T
AD	4A-41	ActHtgSP
AD	4A-41	CFM
CS	4A-41	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4A-42	Zone-T
AD	4A-42	ActHtgSP
AD	4A-42	CFM
CS	4A-42	CFM-stpt
AI	4A-45	Zone-T
AD	4A-45	ActHtgSP
AD	4A-45	CFM
CS	4A-45	CFM-stpt
AI	4A-46	Zone-T
AD	4A-46	ActHtgSP
AD	4A-46	CFM
CS	4A-46	CFM-stpt
AI	4A-47	Zone-T
AD	4A-47	ActHtgSP
AD	4A-47	CFM
CS	4A-47	CFM-stpt
AI	4A-48	Zone-T
AD	4A-48	ActHtgSP
AD	4A-48	CFM
CS	4A-48	CFM-stpt
AI	4A-49A	Zone-T
AD	4A-49A	ActHtgSP
AD	4A-49A	CFM
CS	4A-49A	CFM-stpt
AI	4A-49	Zone-T
AD	4A-49	ActHtgSP
AD	4A-49	CFM
CS	4A-49	CFM-stpt
AI	4A-51	Zone-T
AD	4A-51	ActHtgSP
AD	4A-51	CFM
CS	4A-51	CFM-stpt
AI	4A-52	Zone-T
AD	4A-52	ActHtgSP
AD	4A-52	CFM
CS	4A-52	CFM-stpt
AI	4A-53	Zone-T
AD	4A-53	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4A-53	CFM
CS	4A-53	CFM-stpt
AI	4A-54	Zone-T
AD	4A-54	ActHtgSP
AD	4A-54	CFM
CS	4A-54	CFM-stpt
AI	4A-55	Zone-T
AD	4A-55	ActHtgSP
AD	4A-55	CFM
CS	4A-55	CFM-stpt
AI	4A-56	Zone-T
AD	4A-56	ActHtgSP
AD	4A-56	CFM
CS	4A-56	CFM-stpt
AI	4A-57	Zone-T
AD	4A-57	ActHtgSP
AD	4A-57	CFM
CS	4A-57	CFM-stpt
AI	4A-61	Zone-T
AD	4A-61	ActHtgSP
AD	4A-61	CFM
CS	4A-61	CFM-stpt
AI	4A-62	Zone-T
AD	4A-62	ActHtgSP
AD	4A-62	CFM
CS	4A-62	CFM-stpt
AI	4A-63	Zone-T
AD	4A-63	ActHtgSP
AD	4A-63	CFM
CS	4A-63	CFM-stpt
AI	4A-64	Zone-T
AD	4A-64	ActHtgSP
AD	4A-64	CFM
CS	4A-64	CFM-stpt
AI	4A-65	Zone-T
AD	4A-65	ActHtgSP
AD	4A-65	CFM
CS	4A-65	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4C-01A	Zone-T
AD	4C-01A	ActHtgSP
AD	4C-01A	CFM
CS	4C-01A	CFM-stpt
AI	4C-01	Zone-T
AD	4C-01	ActHtgSP
AD	4C-01	CFM
CS	4C-01	CFM-stpt
AI	4C-03	Zone-T
AD	4C-03	ActHtgSP
AD	4C-03	CFM
CS	4C-03	CFM-stpt
AI	4C-04	Zone-T
AD	4C-04	ActHtgSP
AD	4C-04	CFM
CS	4C-04	CFM-stpt
AI	4C-05	Zone-T
AD	4C-05	ActHtgSP
AD	4C-05	CFM
CS	4C-05	CFM-stpt
AI	4C-06	Zone-T
AD	4C-06	ActHtgSP
AD	4C-06	CFM
CS	4C-06	CFM-stpt
AI	4C-07	Zone-T
AD	4C-07	ActHtgSP
AD	4C-07	CFM
CS	4C-07	CFM-stpt
AI	4C-08	Zone-T
AD	4C-08	ActHtgSP
AD	4C-08	CFM
CS	4C-08	CFM-stpt
AI	4C-09	Zone-T
AD	4C-09	ActHtgSP
AD	4C-09	CFM
CS	4C-09	CFM-stpt
AI	4C-10	Zone-T
AD	4C-10	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4C-10	CFM
CS	4C-10	CFM-stpt
AI	4C-11	Zone-T
AD	4C-11	ActHtgSP
AD	4C-11	CFM
CS	4C-11	CFM-stpt
AI	4C-12	Zone-T
AD	4C-12	ActHtgSP
AD	4C-12	CFM
CS	4C-12	CFM-stpt
AI	4C-13	Zone-T
AD	4C-13	ActHtgSP
AD	4C-13	CFM
CS	4C-13	CFM-stpt
AI	4C-15	Zone-T
AD	4C-15	ActHtgSP
AD	4C-15	CFM
CS	4C-15	CFM-stpt
AI	4C-16	Zone-T
AD	4C-16	ActHtgSP
AD	4C-16	CFM
CS	4C-16	CFM-stpt
AI	4C-17	Zone-T
AD	4C-17	ActHtgSP
AD	4C-17	CFM
CS	4C-17	CFM-stpt
AI	4C-18	Zone-T
AD	4C-18	ActHtgSP
AD	4C-18	CFM
CS	4C-18	CFM-stpt
AI	4C-19	Zone-T
AD	4C-19	ActHtgSP
AD	4C-19	CFM
CS	4C-19	CFM-stpt
AI	4C-20	Zone-T
AD	4C-20	ActHtgSP
AD	4C-20	CFM
CS	4C-20	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4C-21	Zone-T
AD	4C-21	ActHtgSP
AD	4C-21	CFM
CS	4C-21	CFM-stpt
AI	4C-22	Zone-T
AD	4C-22	ActHtgSP
AD	4C-22	CFM
CS	4C-22	CFM-stpt
AI	4C-23	Zone-T
AD	4C-23	ActHtgSP
AD	4C-23	CFM
CS	4C-23	CFM-stpt
AI	4C-59	Zone-T
AD	4C-59	ActHtgSP
AD	4C-59	CFM
CS	4C-59	CFM-stpt
AI	4C-63	Zone-T
AD	4C-63	ActHtgSP
AD	4C-63	CFM
CS	4C-63	CFM-stpt
AI	4C-64	Zone-T
AD	4C-64	ActHtgSP
AD	4C-64	CFM
CS	4C-64	CFM-stpt
AI	4C-65	Zone-T
AD	4C-65	ActHtgSP
AD	4C-65	CFM
CS	4C-65	CFM-stpt
AI	4C-66	Zone-T
AD	4C-66	ActHtgSP
AD	4C-66	CFM
CS	4C-66	CFM-stpt
AI	4C-68	Zone-T
AD	4C-68	ActHtgSP
AD	4C-68	CFM
CS	4C-68	CFM-stpt
AI	4C-69	Zone-T
AD	4C-69	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4C-69	CFM
CS	4C-69	CFM-stpt
AI	4C-81	Zone-T
AD	4C-81	ActHtgSP
AD	4C-81	CFM
CS	4C-81	CFM-stpt
AI	4C-67	Zone-T
AD	4C-67	ActHtgSP
AD	4C-67	CFM
CS	4C-67	CFM-stpt
AI	4C-67	RM-Press
CS	4C-67	Mode
AD	4C-67	Alm-Stat
BD	4C-67	EF6_13-S
AI	4C-14	Zone-T
AD	4C-14	ActHtgSP
AD	4C-14	CFM
CS	4C-14	CFM-stpt
AI	4C-14	RM-Press
CS	4C-14	Mode
AD	4C-14	Alm-Stat
BD	4C-14	EF6_12-S
AI	4A-19	Zone-T
AD	4A-19	ActHtgSP
AD	4A-19	CFM
CS	4A-19	CFM-stpt
AI	4A-19	RM-Press
AD	4A-19	Alm-Stat
BD	4A-19	EF5_13_S
CS	4A-19	Mode
BD	4A-19	ALM
AI	4A-39	Zone-T
AD	4A-39	ActHtgSP
AD	4A-39	CFM
CS	4A-39	CFM-stpt
AI	4A-39	RM-Press
BD	4A-39	EF5_01-S
CS	4A-39	Mode

DRAFT

Building 2		
Points	Equipment	Type
BD	4A-39	ALM
AI	4A-38	Zone-T
AD	4A-38	ActHtgSP
AD	4A-38	CFM
CS	4A-38	CFM-stpt
AI	4A-38	RM-Press
BD	4A-38	EF5_01-S
CS	4A-38	Mode
BD	4A-38	ALM
BD	AHU-52	OCC
BI	AHU-52	SF-S
BI	AHU-52	RF-S
AI	AHU-52	DA-T
AD	AHU-52	DA-STPT
AOS	AHU-52	HTG-VLV
BD	AHU-52	HTG-PMP
AOS	AHU-52	CLG-VLV
AOS	AHU-52	OA-DMPR
AI	AHU-52	MA-T
AI	AHU-52	RA-T
AI	AHU-52	OA-T
BI	AHU-52	LT-ALM
BI	AHU-52	PURGE
BI	AHU-52	SHTDWN
BD	AHU-52	CLG-LOCK
BI	AHU-52	HAND
AI	AHU-52	RA-H
AOS	AHU-52	HUM-VLV
AI	AHU-52	PRE
AI	AHU-52	AFT
AI	AHU-52	HWS
AI	AHU-52	HWR
AI	AHU-52	CWS
AI	AHU-52	CWR
AD	AHU-52	L-ZONE-T
AD	AHU-52	H-ZONE-T
BO	AHU-52	SF-C
BO	AHU-52	RF-C

DRAFT

Building 2		
Points	Equipment	Type
BO	AHU-52	EF5_01-C
BI	AHU-52	EF5_01
BO	AHU-52	EF5_04-C
BI	AHU-52	EF5_04
BO	AHU-52	EF5_08-C
BI	AHU-52	EF5_08
BO	AHU-52	EF5_13-C
BI	AHU-52	EF5_13
BO	AHU-52	EF5_16-C
BI	AHU-52	EF5_16
BO	AHU-52	EF5_18-C
BI	AHU-52	EF5_18
BD	AHU-52	EF5_21
BD	AHU-52	EF6_35
AI	AHU-52	CW-DP
BD	AHU-52	NITEPURG
BO	SHARE15	EF5_55-C
BI	SHARE15	EF5_55
BO	SHARE15	EF5_57-C
BI	SHARE15	EF5_57
AI	SHARE15	ELV-RM-A
AI	4A-20	Zone-T
AD	4A-20	ActHtgSP
AD	4A-20	CFM
CS	4A-20	CFM-stpt
AI	4A-20	RM-Press
AD	4A-20	Alm-Stat
BD	4A-20	EF5_13_S
CS	4A-20	Mode
BD	4A-20	ALM

Building 2		
Points	**Equipment**	**Type**
NC-16		**Network controller**
NC-16-HW	DC-159	159, 1, 3, UNT
NC-16-HW	DC-160	160, 1, 3, UNT
NC-16-HW	DC-161	161, 1, 3, UNT

DRAFT

Building 2		
Points	Equipment	Type
NC-16-HW	DC-162	162, 1, 3, AHU
NC-16-HW	CVR-01	1, 1, 3, VAV
NC-16-HW	CVR-02	2, 1, 3, VAV
NC-16-HW	CVR-03	3, 1, 3, VAV
NC-16-HW	CVR-04	4, 1, 3, VAV
NC-16-HW	CVR-05	5, 1, 3, VAV
NC-16-HW	CVR-06	6, 1, 3, VAV
NC-16-HW	CVR-07	7, 1, 3, VAV
NC-16-HW	CVR-08	8, 1, 3, VAV
NC-16-HW	CVR-09	9, 1, 3, VAV
NC-16-HW	CVR-10	10, 1, 3, VAV
NC-16-HW	CVR-11	11, 1, 3, VAV
NC-16-HW	CVR-12	12, 1, 3, VAV
NC-16-HW	CVR-13	13, 1, 3, VAV
NC-16-HW	CVR-14	14, 1, 3, VAV
NC-16-HW	CVR-15	15, 1, 3, VAV
NC-16-HW	CVR-16	16, 1, 3, VAV
NC-16-HW	CVR-17	17, 1, 3, VAV
NC-16-HW	CVR-18	18, 1, 3, VAV
NC-16-HW	CVR-19	19, 1, 3, VAV
NC-16-HW	CVR-20	20, 1, 3, VAV
NC-16-HW	CVR-21	21, 1, 3, VAV
NC-16-HW	CVR-22	22, 1, 3, VAV
NC-16-HW	CVR-23	23, 1, 3, VAV
NC-16-HW	CVR-24	24, 1, 3, VAV
NC-16-HW	CVR-25	25, 1, 3, VAV
NC-16-HW	CVR-26	26, 1, 3, VAV
NC-16-HW	CVR-27	27, 1, 3, VAV
NC-16-HW	CVR-29	29, 1, 3, VAV
NC-16-HW	CVR-30	30, 1, 3, VAV
NC-16-HW	CVR-31	31, 1, 3, VAV
NC-16-HW	CVR-32	32, 1, 3, VAV
NC-16-HW	CVR-33	33, 1, 3, VAV
NC-16-HW	CVR-34	34, 1, 3, VAV
NC-16-HW	CVR-35	35, 1, 3, VAV
NC-16-HW	CVR-36	36, 1, 3, VAV
NC-16-HW	CVR-37	37, 1, 3, VAV
NC-16-HW	CVR-38	38, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-16-HW	CVR-39	39, 1, 3, VAV
NC-16-HW	CVR-40	40, 1, 3, VAV
NC-16-HW	CVR-41	41, 1, 3, VAV
NC-16-HW	CVR-42	42, 1, 3, VAV
NC-16-HW	CVR-43	43, 1, 3, VAV
NC-16-HW	CVR-44	44, 1, 3, VAV
NC-16-HW	CVR-45	45, 1, 3, VAV
NC-16-HW	CVR-46	46, 1, 3, VAV
NC-16-HW	CVR-47	47, 1, 3, VAV
NC-16-HW	CVR-48	48, 1, 3, VAV
NC-16-HW	CVR-49	49, 1, 3, VAV
NC-16-HW	CVR-50	50, 1, 3, VAV
NC-16-HW	CVR-51	51, 1, 3, VAV
NC-16-HW	CVR-52	52, 1, 3, VAV
NC-16-HW	CVR-53	53, 1, 3, VAV
NC-16-HW	CVR-54	54, 1, 3, VAV
NC-16-HW	CVR-55	55, 1, 3, VAV
NC-16-HW	CVR-56	56, 1, 3, VAV
NC-16-HW	CVR-57	57, 1, 3, VAV
NC-16-HW	CVR-58	58, 1, 3, VAV
NC-16-HW	CVR-59	59, 1, 3, VAV
NC-16-HW	CVR-60	60, 1, 3, VAV
NC-16-HW	CVR-61	61, 1, 3, VAV
NC-16-HW	CVR-64	64, 1, 3, VAV
NC-16-HW	CVR-65	65, 1, 3, VAV
NC-16-HW	CVR-66	66, 1, 3, VAV
NC-16-HW	CVR-129	129, 1, 3, VAV
NC-16-HW	CVR-153	153, 1, 3, VAV
NC-16-HW	CVR-4A60	255, 1, 3, VAV
NC-16-HW	CVR-229	229, 1, 3, VAV
NC-16-HW	CVR-130	130, 1, 3, VAV
NC-16-HW	CVR-131	131, 1, 3, VAV
NC-16-HW	CVR-132	132, 1, 3, VAV
NC-16-HW	CVR-133	133, 1, 3, VAV
NC-16-HW	CVR-134	134, 1, 3, VAV
NC-16-HW	CVR-135	135, 1, 3, VAV
NC-16-HW	CVR-136	136, 1, 3, VAV
NC-16-HW	CVR-137	137, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-16-HW	CVR-138	138, 1, 3, VAV
NC-16-HW	CVR-139	139, 1, 3, VAV
NC-16-HW	CVR-190	190, 1, 3, VAV
NC-16-HW	CVR-191	191, 1, 3, VAV
NC-16-HW	CVR-192	192, 1, 3, VAV
NC-16-HW	CVR-193	193, 1, 3, VAV
NC-16-HW	CVR-194	194, 1, 3, VAV
NC-16-HW	CVR-198	198, 1, 3, VAV
NC-16-HW	CVR-199	199, 1, 3, VAV
NC-16-HW	CVR-200	200, 1, 3, VAV
NC-16-HW	CVR-201	201, 1, 3, VAV
NC-16-HW	CVR-202	202, 1, 3, VAV
NC-16-HW	CVR-203	203, 1, 3, VAV
NC-16-HW	CVR-207	207, 1, 3, VAV
NC-16-HW	CVR-208	208, 1, 3, VAV
NC-16-HW	CVR-209	209, 1, 3, VAV
NC-16-HW	ISO-210	210, 1, 3, VND
NC-16-HW	ISO-211	211, 1, 3, VND
NC-16-HW	ISO-212	212, 1, 3, VND
NC-16-HW	ISO-213	213, 1, 3, VND
NC-16-HW	CVR-62	62, 1, 3, VAV
AI	4D-06	Zone-T
AD	4D-06	CFM
CS	4D-06	CFM-stpt
AI	4B-38	Zone-T
AD	4B-38	CFM
CS	4B-38	CFM-stpt
AI	4B-45	Zone-T
AD	4B-45	ActHtgSP
AD	4B-45	CFM
CS	4B-45	CFM-stpt
AI	4B-45	RM-Press
CS	4B-45	Mode
AD	4B-45	Alm-Stat
BD	4B-45	EFS_54_S
AI	4B-21	Zone-T
AD	4B-21	ActHtgSP
AD	4B-21	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	4B-21	CFM-stpt
AI	4B-21	RM-Press
CS	4B-21	Mode
AD	4B-21	Alm-Stat
BD	4B-21	EF5_59_S
AI	4B-20	Zone-T
AD	4B-20	ActHtgSP
AD	4B-20	CFM
CS	4B-20	CFM-stpt
AI	4B-20	RM-Press
CS	4B-20	Mode
AD	4B-20	Alm-Stat
BD	4B-20	EF5_59_S
AI	4B-44	Zone-T
AD	4B-44	ActHtgSP
AD	4B-44	CFM
CS	4B-44	CFM-stpt
AI	4B-44	RM-Press
CS	4B-44	Mode
AD	4B-44	Alm-Stat
BD	4B-44	EF5_54_S
AI	4B-19	Zone-T
AD	4B-19	ActHtgSP
AD	4B-19	CFM
CS	4B-19	CFM-stpt
AI	4B-23	Zone-T
AD	4B-23	CFM
CS	4B-23	CFM-stpt
AI	4D-79	Zone-T
AD	4D-79	CFM
CS	4D-79	CFM-stpt
CS	CS-NC-16	AHU5801
AI	4D-01	Zone-T
AD	4D-01	ActHtgSP
AD	4D-01	CFM
CS	4D-01	CFM-stpt
AI	4D-02	Zone-T
AD	4D-02	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4D-02	CFM
CS	4D-02	CFM-stpt
AI	4D-03	Zone-T
AD	4D-03	ActHtgSP
AD	4D-03	CFM
CS	4D-03	CFM-stpt
AI	4D-04	Zone-T
AD	4D-04	ActHtgSP
AD	4D-04	CFM
CS	4D-04	CFM-stpt
AI	4D-05	Zone-T
AD	4D-05	ActHtgSP
AD	4D-05	CFM
CS	4D-05	CFM-stpt
AI	4D-07	Zone-T
AD	4D-07	ActHtgSP
AD	4D-07	CFM
CS	4D-07	CFM-stpt
AI	4D-08	Zone-T
AD	4D-08	ActHtgSP
AD	4D-08	CFM
CS	4D-08	CFM-stpt
AI	4D-09	Zone-T
AD	4D-09	ActHtgSP
AD	4D-09	CFM
CS	4D-09	CFM-stpt
AI	4D-10	Zone-T
AD	4D-10	ActHtgSP
AD	4D-10	CFM
CS	4D-10	CFM-stpt
AI	4D-11	Zone-T
AD	4D-11	ActHtgSP
AD	4D-11	CFM
CS	4D-11	CFM-stpt
AI	4D-62	Zone-T
AD	4D-62	ActHtgSP
AD	4D-62	CFM
CS	4D-62	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4D-63	Zone-T
AD	4D-63	ActHtgSP
AD	4D-63	CFM
CS	4D-63	CFM-stpt
AI	4D-64	Zone-T
AD	4D-64	ActHtgSP
AD	4D-64	CFM
CS	4D-64	CFM-stpt
AI	4D-65	Zone-T
AD	4D-65	ActHtgSP
AD	4D-65	CFM
CS	4D-65	CFM-stpt
AI	4D-66	Zone-T
AD	4D-66	ActHtgSP
AD	4D-66	CFM
CS	4D-66	CFM-stpt
AI	4D-70	Zone-T
AD	4D-70	ActHtgSP
AD	4D-70	CFM
CS	4D-70	CFM-stpt
AI	4D-71	Zone-T
AD	4D-71	ActHtgSP
AD	4D-71	CFM
CS	4D-71	CFM-stpt
AI	4D-72	Zone-T
AD	4D-72	ActHtgSP
AD	4D-72	CFM
CS	4D-72	CFM-stpt
AI	4D-73	Zone-T
AD	4D-73	ActHtgSP
AD	4D-73	CFM
CS	4D-73	CFM-stpt
AI	4D-74	Zone-T
AD	4D-74	ActHtgSP
AD	4D-74	CFM
CS	4D-74	CFM-stpt
AI	4D-75	Zone-T
AD	4D-75	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4D-75	CFM
CS	4D-75	CFM-stpt
AI	4D-80	Zone-T
AD	4D-80	ActHtgSP
AD	4D-80	CFM
CS	4D-80	CFM-stpt
AI	4D-81	Zone-T
AD	4D-81	ActHtgSP
AD	4D-81	CFM
CS	4D-81	CFM-stpt
AI	4B-01	Zone-T
AD	4B-01	ActHtgSP
AD	4B-01	CFM
CS	4B-01	CFM-stpt
AI	4B-02	Zone-T
AD	4B-02	ActHtgSP
AD	4B-02	CFM
CS	4B-02	CFM-stpt
AI	4B-03	Zone-T
AD	4B-03	ActHtgSP
AD	4B-03	CFM
CS	4B-03	CFM-stpt
AI	4B-04	Zone-T
AD	4B-04	ActHtgSP
AD	4B-04	CFM
CS	4B-04	CFM-stpt
AI	4B-05	Zone-T
AD	4B-05	ActHtgSP
AD	4B-05	CFM
CS	4B-05	CFM-stpt
AI	4B-06	Zone-T
AD	4B-06	ActHtgSP
AD	4B-06	CFM
CS	4B-06	CFM-stpt
AI	4B-07	Zone-T
AD	4B-07	ActHtgSP
AD	4B-07	CFM
CS	4B-07	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4B-08	Zone-T
AD	4B-08	ActHtgSP
AD	4B-08	CFM
CS	4B-08	CFM-stpt
AI	4B-09	Zone-T
AD	4B-09	ActHtgSP
AD	4B-09	CFM
CS	4B-09	CFM-stpt
AI	4B-10	Zone-T
AD	4B-10	ActHtgSP
AD	4B-10	CFM
CS	4B-10	CFM-stpt
AI	4B-11	Zone-T
AD	4B-11	ActHtgSP
AD	4B-11	CFM
CS	4B-11	CFM-stpt
AI	4B-12	Zone-T
AD	4B-12	ActHtgSP
AD	4B-12	CFM
CS	4B-12	CFM-stpt
AI	4B-13	Zone-T
AD	4B-13	ActHtgSP
AD	4B-13	CFM
CS	4B-13	CFM-stpt
AI	4B-14	Zone-T
AD	4B-14	ActHtgSP
AD	4B-14	CFM
CS	4B-14	CFM-stpt
AI	4B-15	Zone-T
AD	4B-15	ActHtgSP
AD	4B-15	CFM
CS	4B-15	CFM-stpt
AI	4B-16	Zone-T
AD	4B-16	ActHtgSP
AD	4B-16	CFM
CS	4B-16	CFM-stpt
AI	4B-17	Zone-T
AD	4B-17	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4B-17	CFM
CS	4B-17	CFM-stpt
AI	4B-18	Zone-T
AD	4B-18	ActHtgSP
AD	4B-18	CFM
CS	4B-18	CFM-stpt
AI	4B-22	Zone-T
AD	4B-22	ActHtgSP
AD	4B-22	CFM
CS	4B-22	CFM-stpt
AI	4B-24	Zone-T
AD	4B-24	ActHtgSP
AD	4B-24	CFM
CS	4B-24	CFM-stpt
AI	4B-25	Zone-T
AD	4B-25	ActHtgSP
AD	4B-25	CFM
CS	4B-25	CFM-stpt
AI	4B-26	Zone-T
AD	4B-26	ActHtgSP
AD	4B-26	CFM
CS	4B-26	CFM-stpt
AI	4B-27	Zone-T
AD	4B-27	ActHtgSP
AD	4B-27	CFM
CS	4B-27	CFM-stpt
AI	4B-29A	Zone-T
AD	4B-29A	ActHtgSP
AD	4B-29A	CFM
CS	4B-29A	CFM-stpt
AI	4B-29	Zone-T
AD	4B-29	ActHtgSP
AD	4B-29	CFM
CS	4B-29	CFM-stpt
AI	4B-30	Zone-T
AD	4B-30	ActHtgSP
AD	4B-30	CFM
CS	4B-30	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4B-31	Zone-T
AD	4B-31	ActHtgSP
AD	4B-31	CFM
CS	4B-31	CFM-stpt
AI	4B-32	Zone-T
AD	4B-32	ActHtgSP
AD	4B-32	CFM
CS	4B-32	CFM-stpt
AI	4B-33	Zone-T
AD	4B-33	ActHtgSP
AD	4B-33	CFM
CS	4B-33	CFM-stpt
AI	4B-34	Zone-T
AD	4B-34	ActHtgSP
AD	4B-34	CFM
CS	4B-34	CFM-stpt
AI	4B-35	Zone-T
AD	4B-35	ActHtgSP
AD	4B-35	CFM
CS	4B-35	CFM-stpt
AI	4B-36	Zone-T
AD	4B-36	ActHtgSP
AD	4B-36	CFM
CS	4B-36	CFM-stpt
AI	4B-37	Zone-T
AD	4B-37	ActHtgSP
AD	4B-37	CFM
CS	4B-37	CFM-stpt
AI	4B-39	Zone-T
AD	4B-39	ActHtgSP
AD	4B-39	CFM
CS	4B-39	CFM-stpt
AI	4B-40	Zone-T
AD	4B-40	ActHtgSP
AD	4B-40	CFM
CS	4B-40	CFM-stpt
AI	4B-41	Zone-T
AD	4B-41	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4B-41	CFM
CS	4B-41	CFM-stpt
AI	4B-42	Zone-T
AD	4B-42	ActHtgSP
AD	4B-42	CFM
CS	4B-42	CFM-stpt
AI	4B-43	Zone-T
AD	4B-43	ActHtgSP
AD	4B-43	CFM
CS	4B-43	CFM-stpt
AI	4B-46	Zone-T
AD	4B-46	ActHtgSP
AD	4B-46	CFM
CS	4B-46	CFM-stpt
AI	4B-47	Zone-T
AD	4B-47	ActHtgSP
AD	4B-47	CFM
CS	4B-47	CFM-stpt
AI	4B-48	Zone-T
AD	4B-48	ActHtgSP
AD	4B-48	CFM
CS	4B-48	CFM-stpt
AI	4B-49	Zone-T
AD	4B-49	ActHtgSP
AD	4B-49	CFM
CS	4B-49	CFM-stpt
AI	4B-50	Zone-T
AD	4B-50	ActHtgSP
AD	4B-50	CFM
CS	4B-50	CFM-stpt
AI	4B-51	Zone-T
AD	4B-51	ActHtgSP
AD	4B-51	CFM
CS	4B-51	CFM-stpt
AI	4B-52	Zone-T
AD	4B-52	ActHtgSP
AD	4B-52	CFM
CS	4B-52	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4B153	Zone-T
AD	4B153	ActHtgSP
AD	4B153	CFM
CS	4B153	CFM-stpt
AI	4B-53	Zone-T
AD	4B-53	ActHtgSP
AD	4B-53	CFM
CS	4B-53	CFM-stpt
AI	4B-54	Zone-T
AD	4B-54	ActHtgSP
AD	4B-54	CFM
CS	4B-54	CFM-stpt
AI	4B-55	Zone-T
AD	4B-55	ActHtgSP
AD	4B-55	CFM
CS	4B-55	CFM-stpt
AI	4B-56	Zone-T
AD	4B-56	ActHtgSP
AD	4B-56	CFM
CS	4B-56	CFM-stpt
AI	4B-57	Zone-T
AD	4B-57	ActHtgSP
AD	4B-57	CFM
CS	4B-57	CFM-stpt
AI	4B-58	Zone-T
AD	4B-58	ActHtgSP
AD	4B-58	CFM
CS	4B-58	CFM-stpt
AI	4B-59	Zone-T
AD	4B-59	ActHtgSP
AD	4B-59	CFM
CS	4B-59	CFM-stpt
AI	4B-60	Zone-T
AD	4B-60	ActHtgSP
AD	4B-60	CFM
CS	4B-60	CFM-stpt
AI	4A-60	Zone-T
AD	4A-60	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4A-60	CFM
CS	4A-60	CFM-stpt
AI	4A-59	Zone-T
AD	4A-59	ActHtgSP
AD	4A-59	CFM
CS	4A-59	CFM-stpt
AI	4A-58	Zone-T
AD	4A-58	ActHtgSP
AD	4A-58	CFM
CS	4A-58	CFM-stpt
AI	4A-66	Zone-T
AD	4A-66	ActHtgSP
AD	4A-66	CFM
CS	4A-66	CFM-stpt
AI	4B-61	Zone-T
AD	4B-61	ActHtgSP
AD	4B-61	CFM
CS	4B-61	CFM-stpt
BD	AHU-58	OCC
BI	AHU-58	SF-S
BI	AHU-58	RF-S
AI	AHU-58	DA-T
AD	AHU-58	DA-STPT
AOS	AHU-58	HTG-VLV
BD	AHU-58	HTG-PMP
AOS	AHU-58	CLG-VLV
AOS	AHU-58	OA-DMPR
AI	AHU-58	MA-T
AI	AHU-58	RA-T
AI	AHU-58	OA-T
BI	AHU-58	LT-ALM
BI	AHU-58	PURGE
BI	AHU-58	SHTDWN
BD	AHU-58	CLG-LOCK
BI	AHU-58	HAND
AI	AHU-58	RA-H
AOS	AHU-58	HUM-VLV
AI	AHU-58	PRE

DRAFT

Building 2		
Points	Equipment	Type
AI	AHU-58	AFT
AI	AHU-58	HWS
AI	AHU-58	HWR
AI	AHU-58	CWS
AI	AHU-58	CWR
AD	AHU-58	L-ZONE-T
AD	AHU-58	H-ZONE-T
BO	AHU-58	SF-C
BO	AHU-58	RF-C
AI	AHU-58	CW-DP
BO	AHU-58	EF5_20-C
BI	AHU-58	EF5_20
BO	AHU-58	EF5_35-C
BI	AHU-58	EF5_35
BO	AHU-58	EF5_40-C
BI	AHU-58	EF5_40
BO	AHU-58	EF5_41-C
BI	AHU-58	EF5_41
BO	AHU-58	EF5_44-C
BI	AHU-58	EF5_44
BO	AHU-58	EF5_45-C
BI	AHU-58	EF5_45
BO	AHU-58	EF5_52-C
BI	AHU-58	EF5_52
BO	AHU-58	EF5_54-C
BI	AHU-58	EF5_54
BO	AHU-58	EF5_58-C
BI	AHU-58	EF5_58
BO	AHU-58	EF5_59-C
BI	AHU-58	EF5_59
BD	AHU-58	NITEPURG
BO	SHARE16	EF5_21-C
BI	SHARE16	EF5_21
BO	SHARE16	EF5_30-C
BI	SHARE16	EF5_30
BO	SHARE16	EF5_56-C
BI	SHARE16	EF5_56
AI	SHARE16	ELV-RM-B

DRAFT

Building 2		
Points	Equipment	Type
JCB	JCB-NC16	5801-PMP
JCB	JCB-NC16	5801-SMK
JCB	JCB-NC16	58-OCC
JCB	JCB-NC16	5801AITB
JCB	JCB-NC16	58_01EF
JCB	JCB-NC16	58_01-TE
AI	4B-62	Zone-T
AD	4B-62	ActHtgSP
AD	4B-62	CFM
CS	4B-62	CFM-stpt
AI	4B-62	DA-T

Building 2		
Points	**Equipment**	**Type**
NC-17		**Network controller**
NC-17-HW	CVR-13	13, 1, 3, VAV
NC-17-HW	CVR-14	14, 1, 3, VAV
NC-17-HW	CVR-15	15, 1, 3, VAV
NC-17-HW	CVR-16	16, 1, 3, VAV
NC-17-HW	CVR-17	17, 1, 3, VAV
NC-17-HW	CVR-18	18, 1, 3, VAV
NC-17-HW	CVR-19	19, 1, 3, VAV
NC-17-HW	CVR-20	20, 1, 3, VAV
NC-17-HW	CVR-21	21, 1, 3, VAV
NC-17-HW	CVR-23	23, 1, 3, VAV
NC-17-HW	CVR-123	123, 1, 3, VAV
NC-17-HW	CVR-24	24, 1, 3, VAV
NC-17-HW	CVR-25	25, 1, 3, VAV
NC-17-HW	CVR-26	26, 1, 3, VAV
NC-17-HW	CVR-27	27, 1, 3, VAV
NC-17-HW	CVR-29	29, 1, 3, VAV
NC-17-HW	CVR-30	30, 1, 3, VAV
NC-17-HW	CVR-31	31, 1, 3, VAV
NC-17-HW	CVR-32	32, 1, 3, VAV
NC-17-HW	CVR-33	33, 1, 3, VAV
NC-17-HW	CVR-34	34, 1, 3, VAV
NC-17-HW	CVR-35	35, 1, 3, VAV
NC-17-HW	CVR-36	36, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-17-HW	CVR-37	37, 1, 3, VAV
NC-17-HW	CVR-137	137, 1, 3, VAV
NC-17-HW	CVR-38	38, 1, 3, VAV
NC-17-HW	CVR-39	39, 1, 3, VAV
NC-17-HW	CVR-40	40, 1, 3, VAV
NC-17-HW	CVR-41	41, 1, 3, VAV
NC-17-HW	CVR-42	42, 1, 3, VAV
NC-17-HW	CVR-43	43, 1, 3, VAV
NC-17-HW	CVR-44	44, 1, 3, VAV
NC-17-HW	CVR-45	45, 1, 3, VAV
NC-17-HW	CVR-46	46, 1, 3, VAV
NC-17-HW	CVR-47	47, 1, 3, VAV
NC-17-HW	CVR-48	48, 1, 3, VAV
NC-17-HW	CVR-49	49, 1, 3, VAV
NC-17-HW	CVR-50	50, 1, 3, VAV
NC-17-HW	CVR-51	51, 1, 3, VAV
NC-17-HW	CVR-52	52, 1, 3, VAV
NC-17-HW	CVR-53	53, 1, 3, VAV
NC-17-HW	CVR-54	54, 1, 3, VAV
NC-17-HW	CVR-55	55, 1, 3, VAV
NC-17-HW	CVR-56	56, 1, 3, VAV
NC-17-HW	CVR-57	57, 1, 3, VAV
NC-17-HW	CVR-58	58, 1, 3, VAV
NC-17-HW	CVR-59	59, 1, 3, VAV
NC-17-HW	CVR-60	60, 1, 3, VAV
NC-17-HW	CVR-61	61, 1, 3, VAV
NC-17-HW	CVR-67	67, 1, 3, VAV
NC-17-HW	CVR-68	68, 1, 3, VAV
NC-17-HW	CVR-69	69, 1, 3, VAV
NC-17-HW	CVR-76	76, 1, 3, VAV
NC-17-HW	CVR-77	77, 1, 3, VAV
NC-17-HW	CVR-78	78, 1, 3, VAV
NC-17-HW	CVR-82	82, 1, 3, VAV
NC-17-HW	CVR-101	101, 1, 3, VAV
NC-17-HW	CVR-103	103, 1, 3, VAV
NC-17-HW	CVR-89	89, 1, 3, VAV
NC-17-HW	CVR-88	88, 1, 3, VAV
NC-17-HW	CVR-90	90, 1, 3, VAV
NC-17-HW	CVR-91	91, 1, 3, VAV
NC-17-HW	CVR-92	92, 1, 3, VAV
NC-17-HW	CVR-93	93, 1, 3, VAV
NC-17-HW	CVR-94	94, 1, 3, VAV
NC-17-HW	CVR-171	171, 1, 3, VAV
AI	4C-28	Zone-T
AD	4C-28	ActHtgSP
CS	4C-28	CFM-stpt
AI	4D-18	Zone-T
AD	4D-18	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4D-18	CFM
CS	4D-18	CFM-stpt
AI	4D-18	Zone-H
CS	4D-18	HUM-stpt
AOS	4D-18	Hum-vlv
BO	4D-18	Hum-iso
JCB	JCB-NC17	3704ZHUM
JCB	JCB-NC17	3702ZHUM
JCB	JCB-NC17	3601ZHUM
AI	4D-26	Zone-T
AD	4D-26	ActHtgSP
AD	4D-26	CFM
CS	4D-26	CFM-stpt
AI	4D-103	Zone-T
AD	4D-103	ActHtgSP
AD	4D-103	CFM
CS	4D-103	CFM-stpt
AI	4D-101	Zone-T
AD	4D-101	ActHtgSP
AD	4D-101	CFM
CS	4D-101	CFM-stpt
AI	4D-101	Zone-H
CS	4D-101	HUM-stpt
AOS	4D-101	Hum-vlv
BI	4D-101	Air-flow
BO	4D-101	Hum-iso
AI	4D-82	Zone-T
AD	4D-82	ActHtgSP
AD	4D-82	CFM
CS	4D-82	CFM-stpt
AI	4D-78	Zone-T
AD	4D-78	ActHtgSP
AD	4D-78	CFM
CS	4D-78	CFM-stpt
AI	4D-77	Zone-T
AD	4D-77	ActHtgSP
AD	4D-77	CFM
CS	4D-77	CFM-stpt
AI	4D-76	Zone-T
AD	4D-76	ActHtgSP
AD	4D-76	CFM
CS	4D-76	CFM-stpt
AI	4D-69	Zone-T
AD	4D-69	ActHtgSP
AD	4D-69	CFM
CS	4D-69	CFM-stpt
AI	4D-68	Zone-T
AD	4D-68	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4D-68	CFM
CS	4D-68	CFM-stpt
AI	4D-67	Zone-T
AD	4D-67	ActHtgSP
AD	4D-67	CFM
CS	4D-67	CFM-stpt
AI	4D-61	Zone-T
AD	4D-61	ActHtgSP
AD	4D-61	CFM
CS	4D-61	CFM-stpt
AI	4D-60	Zone-T
AD	4D-60	ActHtgSP
AD	4D-60	CFM
CS	4D-60	CFM-stpt
AI	4D-59	Zone-T
AD	4D-59	ActHtgSP
AD	4D-59	CFM
CS	4D-59	CFM-stpt
AI	4D-58	Zone-T
AD	4D-58	ActHtgSP
AD	4D-58	CFM
CS	4D-58	CFM-stpt
AI	4D-58	Zone-H
CS	4D-58	HUM-stpt
AOS	4D-58	Hum-vlv
BI	4D-58	Air-flow
BO	4D-58	Hum-iso
AI	4D-57	Zone-T
AD	4D-57	ActHtgSP
AD	4D-57	CFM
CS	4D-57	CFM-stpt
AI	4D-56	Zone-T
AD	4D-56	ActHtgSP
AD	4D-56	CFM
CS	4D-56	CFM-stpt
AI	4D-55	Zone-T
AD	4D-55	ActHtgSP
AD	4D-55	CFM
CS	4D-55	CFM-stpt
AI	4D-54	Zone-T
AD	4D-54	ActHtgSP
AD	4D-54	CFM
CS	4D-54	CFM-stpt
AI	4D-53	Zone-T
AD	4D-53	ActHtgSP
AD	4D-53	CFM
CS	4D-53	CFM-stpt
AI	4D-52	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4D-52	ActHtgSP
AD	4D-52	CFM
CS	4D-52	CFM-stpt
AI	4D-51	Zone-T
AD	4D-51	ActHtgSP
AD	4D-51	CFM
CS	4D-51	CFM-stpt
AI	4D-50	Zone-T
AD	4D-50	ActHtgSP
AD	4D-50	CFM
CS	4D-50	CFM-stpt
AI	4D-49	Zone-T
AD	4D-49	ActHtgSP
AD	4D-49	CFM
CS	4D-49	CFM-stpt
AI	4D-48	Zone-T
AD	4D-48	ActHtgSP
AD	4D-48	CFM
CS	4D-48	CFM-stpt
AI	4D-48	Zone-H
CS	4D-48	HUM-stpt
AOS	4D-48	Hum-vlv
BI	4D-48	Air-flow
BO	4D-48	Hum-iso
AI	4D-47	Zone-T
AD	4D-47	ActHtgSP
AD	4D-47	CFM
CS	4D-47	CFM-stpt
AI	4D-47	Zone-H
CS	4D-47	HUM-stpt
AOS	4D-47	Hum-vlv
BI	4D-47	Air-flow
BO	4D-47	Hum-iso
AI	4D-46	Zone-T
AD	4D-46	ActHtgSP
AD	4D-46	CFM
CS	4D-46	CFM-stpt
AI	4D-46	Zone-H
CS	4D-46	HUM-stpt
AOS	4D-46	Hum-vlv
BI	4D-46	Air-flow
BO	4D-46	Hum-iso
AI	4D-45	Zone-T
AD	4D-45	ActHtgSP
AD	4D-45	CFM
CS	4D-45	CFM-stpt
AI	4D-45	Zone-H
CS	4D-45	HUM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AOS	4D-45	Hum-vlv
BI	4D-45	Air-flow
BO	4D-45	Hum-iso
AI	4D-44	Zone-T
AD	4D-44	ActHtgSP
AD	4D-44	CFM
CS	4D-44	CFM-stpt
AI	4D-43	Zone-T
AD	4D-43	ActHtgSP
AD	4D-43	CFM
CS	4D-43	CFM-stpt
AI	4D-42	Zone-T
AD	4D-42	ActHtgSP
AD	4D-42	CFM
CS	4D-42	CFM-stpt
AI	4D-42	Zone-H
CS	4D-42	HUM-stpt
AOS	4D-42	Hum-vlv
BI	4D-42	Air-flow
BO	4D-42	Hum-iso
AI	4D-41	Zone-T
AD	4D-41	ActHtgSP
AD	4D-41	CFM
CS	4D-41	CFM-stpt
AI	4D-41	Zone-H
CS	4D-41	HUM-stpt
AOS	4D-41	Hum-vlv
BI	4D-41	Air-flow
BO	4D-41	Hum-iso
AI	4D-40	Zone-T
AD	4D-40	ActHtgSP
AD	4D-40	CFM
CS	4D-40	CFM-stpt
AI	4D-40	Zone-H
CS	4D-40	HUM-stpt
AOS	4D-40	Hum-vlv
BI	4D-40	Air-flow
BO	4D-40	Hum-iso
AI	4D-39	Zone-T
AD	4D-39	ActHtgSP
AD	4D-39	CFM
CS	4D-39	CFM-stpt
AI	4D-39	Zone-H
CS	4D-39	HUM-stpt
AOS	4D-39	Hum-vlv
BI	4D-39	Air-flow
BO	4D-39	Hum-iso
AI	4D-38	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4D-38	ActHtgSP
AD	4D-38	CFM
CS	4D-38	CFM-stpt
AI	4D-38	Zone-H
CS	4D-38	HUM-stpt
AOS	4D-38	Hum-vlv
BI	4D-38	Air-flow
BO	4D-38	Hum-iso
AI	4D-37A	Zone-T
AD	4D-37A	ActHtgSP
AD	4D-37A	CFM
CS	4D-37A	CFM-stpt
AI	4D-37	Zone-T
AD	4D-37	ActHtgSP
AD	4D-37	CFM
CS	4D-37	CFM-stpt
AI	4D-36	Zone-T
AD	4D-36	ActHtgSP
AD	4D-36	CFM
CS	4D-36	CFM-stpt
AI	4D-35	Zone-T
AD	4D-35	ActHtgSP
AD	4D-35	CFM
CS	4D-35	CFM-stpt
AI	4D-35	Zone-H
CS	4D-35	HUM-stpt
AOS	4D-35	Hum-vlv
BI	4D-35	Air-flow
BO	4D-35	Hum-iso
AI	4D-34	Zone-T
AD	4D-34	ActHtgSP
AD	4D-34	CFM
CS	4D-34	CFM-stpt
AI	4D-34	Zone-H
CS	4D-34	HUM-stpt
AOS	4D-34	Hum-vlv
BI	4D-34	Air-flow
BO	4D-34	Hum-iso
AI	4D-33	Zone-T
AD	4D-33	ActHtgSP
AD	4D-33	CFM
CS	4D-33	CFM-stpt
AI	4D-33	Zone-H
CS	4D-33	HUM-stpt
AOS	4D-33	Hum-vlv
BI	4D-33	Air-flow
BO	4D-33	Hum-iso
AI	4D-32	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4D-32	ActHtgSP
AD	4D-32	CFM
CS	4D-32	CFM-stpt
AI	4D-31	Zone-T
AD	4D-31	ActHtgSP
AD	4D-31	CFM
CS	4D-31	CFM-stpt
AI	4D-31	Zone-H
CS	4D-31	HUM-stpt
AOS	4D-31	Hum-vlv
BI	4D-31	Air-flow
BO	4D-31	Hum-iso
AI	4D-30	Zone-T
AD	4D-30	ActHtgSP
AD	4D-30	CFM
CS	4D-30	CFM-stpt
AI	4D-29	Zone-T
AD	4D-29	ActHtgSP
AD	4D-29	CFM
CS	4D-29	CFM-stpt
AI	4D-29	Zone-H
CS	4D-29	HUM-stpt
AOS	4D-29	Hum-vlv
BI	4D-29	Air-flow
BO	4D-29	Hum-iso
AI	4D-27	Zone-T
AD	4D-27	ActHtgSP
AD	4D-27	CFM
CS	4D-27	CFM-stpt
AI	4D-25	Zone-T
AD	4D-25	ActHtgSP
AD	4D-25	CFM
CS	4D-25	CFM-stpt
AI	4D-25	Zone-H
CS	4D-25	HUM-stpt
AOS	4D-25	Hum-vlv
BI	4D-25	Air-flow
BO	4D-25	Hum-iso
AI	4D-24	Zone-T
AD	4D-24	ActHtgSP
AD	4D-24	CFM
CS	4D-24	CFM-stpt
AI	4D-24	Zone-H
CS	4D-24	HUM-stpt
AOS	4D-24	Hum-vlv
BI	4D-24	Air-flow
BO	4D-24	Hum-iso
AI	4D-23A	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4D-23A	ActHtgSP
AD	4D-23A	CFM
CS	4D-23A	CFM-stpt
AI	4D-23A	Zone-H
CS	4D-23A	HUM-stpt
AOS	4D-23A	Hum-vlv
BI	4D-23A	Air-flow
BO	4D-23A	Hum-iso
AI	4D-21	Zone-T
AD	4D-21	ActHtgSP
AD	4D-21	CFM
CS	4D-21	CFM-stpt
AI	4D-20	Zone-T
AD	4D-20	ActHtgSP
AD	4D-20	CFM
CS	4D-20	CFM-stpt
AI	4D-19	Zone-T
AD	4D-19	ActHtgSP
AD	4D-19	CFM
CS	4D-19	CFM-stpt
AI	4D-17	Zone-T
AD	4D-17	ActHtgSP
AD	4D-17	CFM
CS	4D-17	CFM-stpt
AI	4D-17	Zone-H
CS	4D-17	HUM-stpt
AOS	4D-17	Hum-vlv
BI	4D-17	Air-flow
BO	4D-17	Hum-iso
AI	4D-16	Zone-T
AD	4D-16	ActHtgSP
AD	4D-16	CFM
CS	4D-16	CFM-stpt
AI	4D-15	Zone-T
AD	4D-15	ActHtgSP
AD	4D-15	CFM
CS	4D-15	CFM-stpt
AI	4D-15	Zone-H
CS	4D-15	HUM-stpt
AOS	4D-15	Hum-vlv
BI	4D-15	Air-flow
BO	4D-15	Hum-iso
AI	4D-14	Zone-T
AD	4D-14	ActHtgSP
AD	4D-14	CFM
CS	4D-14	CFM-stpt
AI	4D-14	Zone-H
CS	4D-14	HUM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AOS	4D-14	Hum-vlv
BI	4D-14	Air-flow
BO	4D-14	Hum-iso
AI	4D-13	Zone-T
AD	4D-13	ActHtgSP
AD	4D-13	CFM
CS	4D-13	CFM-stpt
AI	4D-12	Zone-T
AD	4D-12	ActHtgSP
AD	4D-12	CFM
CS	4D-12	CFM-stpt
AI	4C-43	Zone-T
AD	4C-43	ActHtgSP
AD	4C-43	CFM
CS	4C-43	CFM-stpt
AI	4C-30	Zone-T
AD	4C-30	ActHtgSP
AD	4C-30	CFM
CS	4C-30	CFM-stpt
AI	4C-29	Zone-T
AD	4C-29	ActHtgSP
AD	4C-29	CFM
CS	4C-29	CFM-stpt
AI	4C-27	Zone-T
AD	4C-27	ActHtgSP
AD	4C-27	CFM
CS	4C-27	CFM-stpt
AI	4C-26	Zone-T
AD	4C-26	ActHtgSP
AD	4C-26	CFM
CS	4C-26	CFM-stpt
AI	4C-25A	Zone-T
AD	4C-25A	ActHtgSP
AD	4C-25A	CFM
CS	4C-25A	CFM-stpt
AI	4C-24	Zone-T
AD	4C-24	ActHtgSP
AD	4C-24	CFM
CS	4C-24	CFM-stpt
AI	4D-23	Zone-T
AD	4D-23	ActHtgSP
AD	4D-23	CFM
CS	4D-23	CFM-stpt
AI	4D-23	Zone-H
CS	4D-23	Hum-stpt
AOS	4D-23	HUM-VLV
BI	4D-23	Air-flow
BO	4D-23	HUM-ISO

DRAFT

Building 2		
Points	Equipment	Type
BO	SHARE17	EF5_23-C
BI	SHARE17	EF5_23
BO	SHARE17	EF5_31-C
BI	SHARE17	EF5_31
BO	SHARE17	EF5_36-C
BI	SHARE17	EF5_36

Building 2		
Points	**Equipment**	**Type**
NC-18		**Network controller**
NC-18-HW	AHU-5502	150, 1, 3, AHU
NC-18-HW	DC18-156	156, 1, 3, UNT
NC-18-HW	DC18-157	157, 1, 3, UNT
NC-18-HW	DC18-158	158, 1, 3, AHU
NC-18-HW	DC18-159	159, 1, 3, UNT
NC-18-HW	CVR-01	255, 1, 3, VAV
NC-18-HW	CVR-02	2, 1, 3, VAV
NC-18-HW	CVR-03	3, 1, 3, VAV
NC-18-HW	CVR-04	4, 1, 3, VAV
NC-18-HW	CVR-05	5, 1, 3, VAV
NC-18-HW	CVR-06	6, 1, 3, VAV
NC-18-HW	CVR-07	7, 1, 3, VAV
NC-18-HW	CVR-08	8, 1, 3, VAV
NC-18-HW	CVR-09	9, 1, 3, VAV
NC-18-HW	CVR-10	10, 1, 3, VAV
NC-18-HW	CVR-11	11, 1, 3, VAV
NC-18-HW	CVR-12	12, 1, 3, VAV
NC-18-HW	CVR-13	13, 1, 3, VAV
NC-18-HW	CVR-14	14, 1, 3, VAV
NC-18-HW	CVR-15	15, 1, 3, VAV
NC-18-HW	CVR-16	16, 1, 3, VAV
NC-18-HW	CVR-116	116, 1, 3, VAV
NC-18-HW	CVR-17	17, 1, 3, VAV
NC-18-HW	CVR-18	18, 1, 3, VAV
NC-18-HW	CVR-19	19, 1, 3, VAV
NC-18-HW	CVR-20	20, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-18-HW	CVR-21	21, 1, 3, VAV
NC-18-HW	CVR-22	22, 1, 3, VAV
NC-18-HW	CVR-23	23, 1, 3, VAV
NC-18-HW	CVR-25	25, 1, 3, VAV
NC-18-HW	CVR-26	26, 1, 3, VAV
NC-18-HW	CVR-27	27, 1, 3, VAV
NC-18-HW	CVR-28	28, 1, 3, VAV
NC-18-HW	CVR-29	29, 1, 3, VAV
NC-18-HW	CVR-30	30, 1, 3, VAV
NC-18-HW	CVR-31	31, 1, 3, VAV
NC-18-HW	CVR-32	32, 1, 3, VAV
NC-18-HW	CVR-33	33, 1, 3, VAV
NC-18-HW	CVR-34	34, 1, 3, VAV
NC-18-HW	CVR-134	134, 1, 3, VAV
NC-18-HW	CVR-35	35, 1, 3, VAV
NC-18-HW	CVR-36	36, 1, 3, VAV
NC-18-HW	CVR-37	37, 1, 3, VAV
NC-18-HW	CVR-38	38, 1, 3, VAV
NC-18-HW	CVR-39	39, 1, 3, VAV
NC-18-HW	CVR-40	40, 1, 3, VAV
NC-18-HW	CVR-41	41, 1, 3, VAV
NC-18-HW	CVR-42	42, 1, 3, VAV
NC-18-HW	CVR-43	43, 1, 3, VAV
NC-18-HW	CVR-44	44, 1, 3, VAV
NC-18-HW	CVR-45	45, 1, 3, VAV
NC-18-HW	CVR-46	46, 1, 3, VAV
NC-18-HW	CVR-47	47, 1, 3, VAV
NC-18-HW	CVR-70	70, 1, 3, VAV
NC-18-HW	CVR-71	71, 1, 3, VAV
NC-18-HW	CVR-72	72, 1, 3, VAV
NC-18-HW	CVR-73	73, 1, 3, VAV
NC-18-HW	CVR-173	173, 1, 3, VAV
NC-18-HW	CVR-174	174, 1, 3, VAV
NC-18-HW	CVR-100	100, 1, 3, VAV
NC-18-HW	ISO-210	210, 1, 3, VND
NC-18-HW	ISO-211	211, 1, 3, VND
NC-18-HW	ISO-212	212, 1, 3, VND
NC-18-HW	ISO-213	213, 1, 3, VND

DRAFT

Building 2		
Points	Equipment	Type
NC-18-HW	ISO-214	214, 1, 3, VND
AI	4F-70	Zone-T
AD	4F-70	ActHtgSP
AD	4F-70	CFM
CS	4F-70	CFM-stpt
AI	4F-70	OBGYN
AI	4F-16	Zone-T
AD	4F-16	ActHtgSP
AD	4F-16	CFM
CS	4F-16	CFM-stpt
AI	4F-16	RM-Press
BD	4F-16	EF5_50_S
CS	4F-16	Mode
BD	4F-16	ALM
AI	4F-16A	Zone-T
AD	4F-16A	ActHtgSP
AD	4F-16A	CFM
CS	4F-16A	CFM-stpt
BO	AHU-5502	SF-C
BO	AHU-5502	RF-C
BI	AHU-5502	SF-S
BI	AHU-5502	RF-S
AI	AHU-5502	DA-T
AD	AHU-5502	DA-STPT
AOS	AHU-5502	HTG-VLV
BO	AHU-5502	HTGPMP-C
BI	AHU-5502	HTGPMP-S
AOS	AHU-5502	CLG-VLV
AI	AHU-5502	MA-T
AOS	AHU-5502	OA-DMPR
AI	AHU-5502	OA-T
AI	AHU-5502	RA-T
AI	AHU-5502	RA-H
AOS	AHU-5502	HUM-VLV
BI	AHU-5502	LT-ALM
CS	CS-NC-18	AHU5501
CS	CS-NC-18	AHU5502
AI	4F-18	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4F-18	CFM
CS	4F-18	CFM-stpt
AI	4F-14	Zone-T
AD	4F-14	CFM
CS	4F-14	CFM-stpt
BO	SHARE18	EF5_24-C
BI	SHARE18	EF5_24
BO	SHARE18	EF5_28-C
BI	SHARE18	EF5_28
BO	SHARE18	EF5_29-C
BI	SHARE18	EF5_29
BO	SHARE18	EF5_32-C
BI	SHARE18	EF5_32
AI	SHARE18	ELV-RM-F
BD	AHU-5501	OCC
BI	AHU-5501	SF-S
BI	AHU-5501	RF-S
AI	AHU-5501	DA-T
AD	AHU-5501	DA-STPT
AOS	AHU-5501	HTG-VLV
BD	AHU-5501	HTG-PMP
AOS	AHU-5501	CLG-VLV
AOS	AHU-5501	OA-DMPR
AI	AHU-5501	MA-T
AI	AHU-5501	RA-T
AI	AHU-5501	OA-T
BI	AHU-5501	LT-ALM
BI	AHU-5501	PURGE
BI	AHU-5501	SHTDWN
BD	AHU-5501	CLG-LOCK
BI	AHU-5501	HAND
AI	AHU-5501	RA-H
AOS	AHU-5501	HUM-VLV
AI	AHU-5501	PRE
AI	AHU-5501	AFT
AI	AHU-5501	HWS
AI	AHU-5501	HWR
AI	AHU-5501	CWS

DRAFT

Building 2		
Points	Equipment	Type
AI	AHU-5501	CWR
AI	AHU-5501	CW-DP
AD	AHU-5501	L-ZONE-T
AD	AHU-5501	H-ZONE-T
AD	AHU-5501	A-ZONE-T
BO	AHU-5501	SF-C
BO	AHU-5501	RF-C
BO	AHU-5501	EF5_33-C
BI	AHU-5501	EF5_33
BO	AHU-5501	EF5_34-C
BI	AHU-5501	EF5_34
BO	AHU-5501	EF5_37-C
BI	AHU-5501	EF5_37
BO	AHU-5501	EF5_38-C
BI	AHU-5501	EF5_38
BO	AHU-5501	EF5_39-C
BI	AHU-5501	EF5_39
BO	AHU-5501	EF5_42-C
BI	AHU-5501	EF5_42
BO	AHU-5501	EF5_49-C
BI	AHU-5501	EF5_49
BO	AHU-5501	EF5_50-C
BI	AHU-5501	EF5_50
BO	AHU-5501	EF5_60-C
BI	AHU-5501	EF5_60
BO	AHU-5501	EF5_61-C
BI	AHU-5501	EF5_61
BO	AHU-5501	EF5_62-C
BI	AHU-5501	EF5_62
BO	AHU-5501	EF55_02C
BI	AHU-5501	EF55_02
BO	AHU-5501	EF55_03C
BI	AHU-5501	EF55_03
BD	AHU-5501	NITEPURG
AI	4F-31	Zone-T
AD	4F-31	ActHtgSP
AD	4F-31	CFM
CS	4F-31	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4F-31	RM-Press
BD	4F-31	EF5_39_S
CS	4F-31	Mode
BD	4F-31	ALM
AI	4F-04	Zone-T
AD	4F-04	ActHtgSP
AD	4F-04	CFM
CS	4F-04	CFM-stpt
AI	4F-04	RM-Press
BD	4F-04	EF5_37_S
CS	4F-04	Mode
BD	4F-04	ALM
AI	4F-03	Zone-T
AD	4F-03	ActHtgSP
AD	4F-03	CFM
CS	4F-03	CFM-stpt
AI	4F-03	RM-Press
BD	4F-03	EF5_37_S
CS	4F-03	Mode
BD	4F-03	ALM
AI	4F-22	Zone-T
AD	4F-22	ActHtgSP
AD	4F-22	CFM
CS	4F-22	CFM-stpt
AI	4F-22	RM-Press
BD	4F-22	EF5_49_S
BD	4F-22	ALM
CS	4F-22	Mode
AI	4F-01	Zone-T
AD	4F-01	ActHtgSP
AD	4F-01	CFM
CS	4F-01	CFM-stpt
AI	4F-02	Zone-T
AD	4F-02	ActHtgSP
AD	4F-02	CFM
CS	4F-02	CFM-stpt
AI	4F-05	Zone-T
AD	4F-05	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4F-05	CFM
CS	4F-05	CFM-stpt
AI	4F-06	Zone-T
AD	4F-06	ActHtgSP
AD	4F-06	CFM
CS	4F-06	CFM-stpt
AI	4F-07	Zone-T
AD	4F-07	ActHtgSP
AD	4F-07	CFM
CS	4F-07	CFM-stpt
AI	4F-08	Zone-T
AD	4F-08	ActHtgSP
AD	4F-08	CFM
CS	4F-08	CFM-stpt
AI	4F-09	Zone-T
AD	4F-09	ActHtgSP
AD	4F-09	CFM
CS	4F-09	CFM-stpt
AI	4F-10	Zone-T
AD	4F-10	ActHtgSP
AD	4F-10	CFM
CS	4F-10	CFM-stpt
AI	4F-11	Zone-T
AD	4F-11	ActHtgSP
AD	4F-11	CFM
CS	4F-11	CFM-stpt
AI	4F-12	Zone-T
AD	4F-12	ActHtgSP
AD	4F-12	CFM
CS	4F-12	CFM-stpt
AI	4F-13	Zone-T
AD	4F-13	ActHtgSP
AD	4F-13	CFM
CS	4F-13	CFM-stpt
AI	4F-15	Zone-T
AD	4F-15	ActHtgSP
AD	4F-15	CFM
CS	4F-15	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4F-17	Zone-T
AD	4F-17	ActHtgSP
AD	4F-17	CFM
CS	4F-17	CFM-stpt
AI	4F-19	Zone-T
AD	4F-19	ActHtgSP
AD	4F-19	CFM
CS	4F-19	CFM-stpt
AI	4F-20	Zone-T
AD	4F-20	ActHtgSP
AD	4F-20	CFM
CS	4F-20	CFM-stpt
AI	4F-21	Zone-T
AD	4F-21	ActHtgSP
AD	4F-21	CFM
CS	4F-21	CFM-stpt
AI	4F-23	Zone-T
AD	4F-23	ActHtgSP
AD	4F-23	CFM
CS	4F-23	CFM-stpt
AI	4F-25	Zone-T
AD	4F-25	ActHtgSP
AD	4F-25	CFM
CS	4F-25	CFM-stpt
AI	4F-26	Zone-T
AD	4F-26	ActHtgSP
AD	4F-26	CFM
CS	4F-26	CFM-stpt
AI	4F-27	Zone-T
AD	4F-27	ActHtgSP
AD	4F-27	CFM
CS	4F-27	CFM-stpt
AI	4F-28	Zone-T
AD	4F-28	ActHtgSP
AD	4F-28	CFM
CS	4F-28	CFM-stpt
AI	4F-29	Zone-T
AD	4F-29	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4F-29	CFM
CS	4F-29	CFM-stpt
AI	4F-30	Zone-T
AD	4F-30	ActHtgSP
AD	4F-30	CFM
CS	4F-30	CFM-stpt
AI	4F-32	Zone-T
AD	4F-32	ActHtgSP
AD	4F-32	CFM
CS	4F-32	CFM-stpt
AI	4F-33	Zone-T
AD	4F-33	ActHtgSP
AD	4F-33	CFM
CS	4F-33	CFM-stpt
AI	4F-34	Zone-T
AD	4F-34	ActHtgSP
AD	4F-34	CFM
CS	4F-34	CFM-stpt
AI	4F-34A	Zone-T
AD	4F-34A	ActHtgSP
AD	4F-34A	CFM
CS	4F-34A	CFM-stpt
AI	4F-35	Zone-T
AD	4F-35	ActHtgSP
AD	4F-35	CFM
CS	4F-35	CFM-stpt
AI	4F-36	Zone-T
AD	4F-36	ActHtgSP
AD	4F-36	CFM
CS	4F-36	CFM-stpt
AI	4F-37	Zone-T
AD	4F-37	ActHtgSP
AD	4F-37	CFM
CS	4F-37	CFM-stpt
AI	4F-38	Zone-T
AD	4F-38	ActHtgSP
AD	4F-38	CFM
CS	4F-38	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	4F-39	Zone-T
AD	4F-39	ActHtgSP
AD	4F-39	CFM
CS	4F-39	CFM-stpt
AI	4F-40	Zone-T
AD	4F-40	ActHtgSP
AD	4F-40	CFM
CS	4F-40	CFM-stpt
AI	4F-41	Zone-T
AD	4F-41	ActHtgSP
AD	4F-41	CFM
CS	4F-41	CFM-stpt
AI	4F-42	Zone-T
AD	4F-42	ActHtgSP
AD	4F-42	CFM
CS	4F-42	CFM-stpt
AI	4F-43	Zone-T
AD	4F-43	ActHtgSP
AD	4F-43	CFM
CS	4F-43	CFM-stpt
AI	4F-44	Zone-T
AD	4F-44	ActHtgSP
AD	4F-44	CFM
CS	4F-44	CFM-stpt
AI	4F-45	Zone-T
AD	4F-45	ActHtgSP
AD	4F-45	CFM
CS	4F-45	CFM-stpt
AI	4F-46	Zone-T
AD	4F-46	ActHtgSP
AD	4F-46	CFM
CS	4F-46	CFM-stpt
AI	4F-47	Zone-T
AD	4F-47	ActHtgSP
AD	4F-47	CFM
CS	4F-47	CFM-stpt
AI	4F-71	Zone-T
AD	4F-71	ActHtgSP

DRAFT

Building 2		
Points	Equipment	Type
AD	4F-71	CFM
CS	4F-71	CFM-stpt
AI	4F-72	Zone-T
AD	4F-72	ActHtgSP
AD	4F-72	CFM
CS	4F-72	CFM-stpt
AI	4F-73	Zone-T
AD	4F-73	ActHtgSP
AD	4F-73	CFM
CS	4F-73	CFM-stpt
AI	4F-73A	Zone-T
AD	4F-73A	ActHtgSP
AD	4F-73A	CFM
CS	4F-73A	CFM-stpt
AI	4F-73B	Zone-T
AD	4F-73B	ActHtgSP
AD	4F-73B	CFM
CS	4F-73B	CFM-stpt
AI	4E-100	Zone-T
AD	4E-100	ActHtgSP
AD	4E-100	CFM
CS	4E-100	CFM-stpt
JCB	JCB-NC18	5501-PMP
JCB	JCB-NC18	5501-OCC
JCB	JCB-NC18	5501-SMK
JCB	JCB-NC18	55_01EF
JCB	JCB-NC18	5501AITB
JCB	JCB-NC18	55_01-TE

Building 2		
Points	**Equipment**	**Type**
NC-19		**Network controller**
NC-19-HW	DC19-155	155, 1, 3, UNT
NC-19-HW	DC19-156	156, 1, 3, UNT
NC-19-HW	DC19-157	157, 1, 3, UNT

DRAFT

Building 2		
Points	Equipment	Type
NC-19-HW	CVR-01	1, 1, 3, VAV
NC-19-HW	CVR-101	101, 1, 3, VAV
NC-19-HW	CVR-02	2, 1, 3, VAV
NC-19-HW	CVR-03	3, 1, 3, VAV
NC-19-HW	CVR-103	103, 1, 3, VAV
NC-19-HW	CVR-04	4, 1, 3, VAV
NC-19-HW	CVR-05	5, 1, 3, VAV
NC-19-HW	CVR-06	6, 1, 3, VAV
NC-19-HW	CVR-07	7, 1, 3, VAV
NC-19-HW	CVR-08	8, 1, 3, VAV
NC-19-HW	CVR-09	9, 1, 3, VAV
NC-19-HW	CVR-10	10, 1, 3, VAV
NC-19-HW	CVR-13	13, 1, 3, VAV
NC-19-HW	CVR-14	14, 1, 3, VAV
NC-19-HW	CVR-15	15, 1, 3, VAV
NC-19-HW	CVR-16	16, 1, 3, VAV
NC-19-HW	CVR-17	17, 1, 3, VAV
NC-19-HW	CVR-18	18, 1, 3, VAV
NC-19-HW	CVR-118	118, 1, 3, VAV
NC-19-HW	CVR-19	19, 1, 3, VAV
NC-19-HW	CVR-20	20, 1, 3, VAV
NC-19-HW	CVR-21	21, 1, 3, VAV
NC-19-HW	CVR-22	22, 1, 3, VAV
NC-19-HW	CVR-23	23, 1, 3, VAV
NC-19-HW	CVR-24	24, 1, 3, VAV
NC-19-HW	CVR-25	25, 1, 3, VAV
NC-19-HW	CVR-26	26, 1, 3, VAV
NC-19-HW	CVR-27	27, 1, 3, VAV
NC-19-HW	CVR-28	28, 1, 3, VAV
NC-19-HW	CVR-128	128, 1, 3, VAV
NC-19-HW	CVR-29	29, 1, 3, VAV
NC-19-HW	CVR-30	30, 1, 3, VAV
NC-19-HW	CVR-31	31, 1, 3, VAV
NC-19-HW	CVR-32	32, 1, 3, VAV
NC-19-HW	CVR-33	33, 1, 3, VAV
NC-19-HW	CVR-34	34, 1, 3, VAV
NC-19-HW	CVR-35	35, 1, 3, VAV
NC-19-HW	CVR-36	36, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-19-HW	CVR-37	37, 1, 3, VAV
NC-19-HW	CVR-38	38, 1, 3, VAV
NC-19-HW	CVR-41	41, 1, 3, VAV
NC-19-HW	CVR-42	42, 1, 3, VAV
NC-19-HW	CVR-43	43, 1, 3, VAV
NC-19-HW	CVR-44	44, 1, 3, VAV
NC-19-HW	CVR-45	45, 1, 3, VAV
NC-19-HW	CVR-46	46, 1, 3, VAV
NC-19-HW	CVR-47	47, 1, 3, VAV
NC-19-HW	CVR-48	48, 1, 3, VAV
NC-19-HW	CVR-49	49, 1, 3, VAV
NC-19-HW	CVR-50	50, 1, 3, VAV
NC-19-HW	CVR-51	51, 1, 3, VAV
NC-19-HW	CVR-52	52, 1, 3, VAV
NC-19-HW	CVR-53	53, 1, 3, VAV
NC-19-HW	CVR-54	54, 1, 3, VAV
NC-19-HW	CVR-159	159, 1, 3, VAV
NC-19-HW	CVR-160	160, 1, 3, VAV
NC-19-HW	CVR-161	161, 1, 3, VAV
NC-19-HW	CVR-164	164, 1, 3, VAV
NC-19-HW	CVR-165	165, 1, 3, VAV
NC-19-HW	CVR-166	166, 1, 3, VAV
NC-19-HW	CVR-167	167, 1, 3, VAV
NC-19-HW	CVR-169	169, 1, 3, VAV
NC-19-HW	CVR-170	170, 1, 3, VAV
NC-19-HW	CVR-177	177, 1, 3, VAV
NC-19-HW	CVR-178	178, 1, 3, VAV
NC-19-HW	CVR-179	179, 1, 3, VAV
NC-19-HW	CVR-180	180, 1, 3, VAV
NC-19-HW	CVR-181	181, 1, 3, VAV
NC-19-HW	CVR-183	183, 1, 3, VAV
NC-19-HW	CVR-184	184, 1, 3, VAV
NC-19-HW	CVR-185	185, 1, 3, VAV
NC-19-HW	CVR-186	186, 1, 3, VAV
NC-19-HW	CVR-188	188, 1, 3, VAV
NC-19-HW	CVR-190	190, 1, 3, VAV
NC-19-HW	CVR-198	198, 1, 3, VAV
NC-19-HW	CVR-199	199, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-19-HW	CVR-200	200, 1, 3, VAV
NC-19-HW	CVR-201	201, 1, 3, VAV
NC-19-HW	CVR-202	202, 1, 3, VAV
NC-19-HW	CVR-203	203, 1, 3, VAV
NC-19-HW	CVR-204	204, 1, 3, VAV
NC-19-HW	CVR-252	252, 1, 3, VAV
NC-19-HW	CVR-253	253, 1, 3, VAV
NC-19-HW	CVR-254	254, 1, 3, VAV
NC-19-HW	CVR-255	255, 1, 3, VAV
NC-19-HW	ISO-210	210, 1, 3, VND
NC-19-HW	ISO-211	211, 1, 3, VND
AI	4E-34	Zone-T
AD	4E-34	ActHtgSP
AD	4E-34	CFM
CS	4E-34	CFM-stpt
AI	4E-46	ZN-T
AD	4E-46	ActHtgSP
AD	4E-46	CFM
CS	4E-46	CFM-stpt
AI	4C-56	Zone-T
AD	4C-56	ActHtgSP
AD	4C-56	CFM
CS	4C-56	CFM-stpt
AI	4C-56	RM-Press
CS	4C-56	Mode
AD	4C-56	Alm-Stat
BD	4C-56	EF6_11-S
AI	4C-70	Zone-T
AD	4C-70	ActHtgSP
AD	4C-70	CFM
CS	4C-70	CFM-stpt
AI	4C-70	RM-Press
CS	4C-70	Mode
AD	4C-70	Alm-Stat
BD	4C-70	EF6_04_S
AI	4E-54	Zone-T
AD	4E-54	ActHtgSP
AD	4E-54	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	4E-54	CFM-stpt
AI	4E-53	Zone-T
AD	4E-53	ActHtgSP
AD	4E-53	CFM
CS	4E-53	CFM-stpt
AI	4E-52	Zone-T
AD	4E-52	ActHtgSP
AD	4E-52	CFM
CS	4E-52	CFM-stpt
AI	4E-51	Zone-T
AD	4E-51	ActHtgSP
AD	4E-51	CFM
CS	4E-51	CFM-stpt
AI	4E-50	Zone-T
AD	4E-50	ActHtgSP
AD	4E-50	CFM
CS	4E-50	CFM-stpt
AI	4E-49	Zone-T
AD	4E-49	ActHtgSP
AD	4E-49	CFM
CS	4E-49	CFM-stpt
AI	4E-48	Zone-T
AD	4E-48	ActHtgSP
AD	4E-48	CFM
CS	4E-48	CFM-stpt
AI	4E-47	Zone-T
AD	4E-47	ActHtgSP
AD	4E-47	CFM
CS	4E-47	CFM-stpt
AI	4E-45	Zone-T
AD	4E-45	ActHtgSP
AD	4E-45	CFM
CS	4E-45	CFM-stpt
AI	4E-44	Zone-T
AD	4E-44	ActHtgSP
AD	4E-44	CFM
CS	4E-44	CFM-stpt
AI	4E-43	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4E-43	ActHtgSP
AD	4E-43	CFM
CS	4E-43	CFM-stpt
AI	4E-42	Zone-T
AD	4E-42	ActHtgSP
AD	4E-42	CFM
CS	4E-42	CFM-stpt
AI	4E-41	Zone-T
AD	4E-41	ActHtgSP
AD	4E-41	CFM
CS	4E-41	CFM-stpt
AI	4E-38	Zone-T
AD	4E-38	ActHtgSP
AD	4E-38	CFM
CS	4E-38	CFM-stpt
AI	4E-37	Zone-T
AD	4E-37	ActHtgSP
AD	4E-37	CFM
CS	4E-37	CFM-stpt
AI	4E-36	Zone-T
AD	4E-36	ActHtgSP
AD	4E-36	CFM
CS	4E-36	CFM-stpt
AI	4E-35	Zone-T
AD	4E-35	ActHtgSP
AD	4E-35	CFM
CS	4E-35	CFM-stpt
AI	4E-33	Zone-T
AD	4E-33	ActHtgSP
AD	4E-33	CFM
CS	4E-33	CFM-stpt
AI	4E-32	Zone-T
AD	4E-32	ActHtgSP
AD	4E-32	CFM
CS	4E-32	CFM-stpt
AI	4E-31	Zone-T
AD	4E-31	ActHtgSP
AD	4E-31	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	4E-31	CFM-stpt
AI	4E-30	Zone-T
AD	4E-30	ActHtgSP
AD	4E-30	CFM
CS	4E-30	CFM-stpt
AI	4E-29	Zone-T
AD	4E-29	ActHtgSP
AD	4E-29	CFM
CS	4E-29	CFM-stpt
AI	4E-28A	Zone-T
AD	4E-28A	ActHtgSP
AD	4E-28A	CFM
CS	4E-28A	CFM-stpt
AI	4E-28	Zone-T
AD	4E-28	ActHtgSP
AD	4E-28	CFM
CS	4E-28	CFM-stpt
AI	4E-27	Zone-T
AD	4E-27	ActHtgSP
AD	4E-27	CFM
CS	4E-27	CFM-stpt
AI	4E-26	Zone-T
AD	4E-26	ActHtgSP
AD	4E-26	CFM
CS	4E-26	CFM-stpt
AI	4E-25	Zone-T
AD	4E-25	ActHtgSP
AD	4E-25	CFM
CS	4E-25	CFM-stpt
AI	4E-24	Zone-T
AD	4E-24	ActHtgSP
AD	4E-24	CFM
CS	4E-24	CFM-stpt
AI	4E-23	Zone-T
AD	4E-23	ActHtgSP
AD	4E-23	CFM
CS	4E-23	CFM-stpt
AI	4E-22	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4E-22	ActHtgSP
AD	4E-22	CFM
CS	4E-22	CFM-stpt
AI	4E-21	Zone-T
AD	4E-21	ActHtgSP
AD	4E-21	CFM
CS	4E-21	CFM-stpt
AI	4E-20	Zone-T
AD	4E-20	ActHtgSP
AD	4E-20	CFM
CS	4E-20	CFM-stpt
AI	4E-19	Zone-T
AD	4E-19	ActHtgSP
AD	4E-19	CFM
CS	4E-19	CFM-stpt
AI	4E-18A	Zone-T
AD	4E-18A	ActHtgSP
AD	4E-18A	CFM
CS	4E-18A	CFM-stpt
AI	4E-18	Zone-T
AD	4E-18	ActHtgSP
AD	4E-18	CFM
CS	4E-18	CFM-stpt
AI	4E-17	Zone-T
AD	4E-17	ActHtgSP
AD	4E-17	CFM
CS	4E-17	CFM-stpt
AI	4E-16	Zone-T
AD	4E-16	ActHtgSP
AD	4E-16	CFM
CS	4E-16	CFM-stpt
AI	4E-15	Zone-T
AD	4E-15	ActHtgSP
AD	4E-15	CFM
CS	4E-15	CFM-stpt
AI	4E-14	Zone-T
AD	4E-14	ActHtgSP
AD	4E-14	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	4E-14	CFM-stpt
AI	4E-13	Zone-T
AD	4E-13	ActHtgSP
AD	4E-13	CFM
CS	4E-13	CFM-stpt
AI	4E-10	Zone-T
AD	4E-10	ActHtgSP
AD	4E-10	CFM
CS	4E-10	CFM-stpt
AI	4E-09	Zone-T
AD	4E-09	ActHtgSP
AD	4E-09	CFM
CS	4E-09	CFM-stpt
AI	4E-08	Zone-T
AD	4E-08	ActHtgSP
AD	4E-08	CFM
CS	4E-08	CFM-stpt
AI	4E-07	Zone-T
AD	4E-07	ActHtgSP
AD	4E-07	CFM
CS	4E-07	CFM-stpt
AI	4E-06	Zone-T
AD	4E-06	ActHtgSP
AD	4E-06	CFM
CS	4E-06	CFM-stpt
AI	4E-05	Zone-T
AD	4E-05	ActHtgSP
AD	4E-05	CFM
CS	4E-05	CFM-stpt
AI	4E-04	Zone-T
AD	4E-04	ActHtgSP
AD	4E-04	CFM
CS	4E-04	CFM-stpt
AI	4E-03A	Zone-T
AD	4E-03A	ActHtgSP
AD	4E-03A	CFM
CS	4E-03A	CFM-stpt
AI	4E-03	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4E-03	ActHtgSP
AD	4E-03	CFM
CS	4E-03	CFM-stpt
AI	4E-02	Zone-T
AD	4E-02	ActHtgSP
AD	4E-02	CFM
CS	4E-02	CFM-stpt
AI	4E-01A	Zone-T
AD	4E-01A	ActHtgSP
AD	4E-01A	CFM
CS	4E-01A	CFM-stpt
AI	4E-01	Zone-T
AD	4E-01	ActHtgSP
AD	4E-01	CFM
CS	4E-01	CFM-stpt
AI	4C-76	Zone-T
AD	4C-76	ActHtgSP
AD	4C-76	CFM
CS	4C-76	CFM-stpt
AI	4C-75	Zone-T
AD	4C-75	ActHtgSP
AD	4C-75	CFM
CS	4C-75	CFM-stpt
AI	4C-74	Zone-T
AD	4C-74	ActHtgSP
AD	4C-74	CFM
CS	4C-74	CFM-stpt
AI	4C-73	Zone-T
AD	4C-73	ActHtgSP
AD	4C-73	CFM
CS	4C-73	CFM-stpt
AI	4C-72	Zone-T
AD	4C-72	ActHtgSP
AD	4C-72	CFM
CS	4C-72	CFM-stpt
AI	4C-71	Zone-T
AD	4C-71	ActHtgSP
AD	4C-71	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	4C-71	CFM-stpt
AI	4C-69A	Zone-T
AD	4C-69A	ActHtgSP
AD	4C-69A	CFM
CS	4C-69A	CFM-stpt
AI	4C-62	Zone-T
AD	4C-62	ActHtgSP
AD	4C-62	CFM
CS	4C-62	CFM-stpt
AI	4C-60	Zone-T
AD	4C-60	ActHtgSP
AD	4C-60	CFM
CS	4C-60	CFM-stpt
AI	4C-58	Zone-T
AD	4C-58	ActHtgSP
AD	4C-58	CFM
CS	4C-58	CFM-stpt
AI	4C-57	Zone-T
AD	4C-57	ActHtgSP
AD	4C-57	CFM
CS	4C-57	CFM-stpt
AI	4C-55	Zone-T
AD	4C-55	ActHtgSP
AD	4C-55	CFM
CS	4C-55	CFM-stpt
AI	4C-53	Zone-T
AD	4C-53	ActHtgSP
AD	4C-53	CFM
CS	4C-53	CFM-stpt
AI	4C-52	Zone-T
AD	4C-52	ActHtgSP
AD	4C-52	CFM
CS	4C-52	CFM-stpt
AI	4C-51	Zone-T
AD	4C-51	ActHtgSP
AD	4C-51	CFM
CS	4C-51	CFM-stpt
AI	4C-50	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	4C-50	ActHtgSP
AD	4C-50	CFM
CS	4C-50	CFM-stpt
AI	4C-49	Zone-T
AD	4C-49	ActHtgSP
AD	4C-49	CFM
CS	4C-49	CFM-stpt
AI	4C-42	Zone-T
AD	4C-42	ActHtgSP
AD	4C-42	CFM
CS	4C-42	CFM-stpt
AI	4C-41	Zone-T
AD	4C-41	ActHtgSP
AD	4C-41	CFM
CS	4C-41	CFM-stpt
AI	4C-39	Zone-T
AD	4C-39	ActHtgSP
AD	4C-39	CFM
CS	4C-39	CFM-stpt
AI	4C-38	Zone-T
AD	4C-38	ActHtgSP
AD	4C-38	CFM
CS	4C-38	CFM-stpt
AI	4C-37A	Zone-T
AD	4C-37A	ActHtgSP
AD	4C-37A	CFM
CS	4C-37A	CFM-stpt
AI	4C-37	Zone-T
AD	4C-37	ActHtgSP
AD	4C-37	CFM
CS	4C-37	CFM-stpt
AI	4C-36	Zone-T
AD	4C-36	ActHtgSP
AD	4C-36	CFM
CS	4C-36	CFM-stpt
AI	4C-34A	Zone-T
AD	4C-34A	ActHtgSP
AD	4C-34A	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	4C-34A	CFM-stpt
AI	4C-33	Zone-T
AD	4C-33	ActHtgSP
AD	4C-33	CFM
CS	4C-33	CFM-stpt
AI	4C-32	Zone-T
AD	4C-32	ActHtgSP
AD	4C-32	CFM
CS	4C-32	CFM-stpt
AI	4C-25	Zone-T
AD	4C-25	ActHtgSP
AD	4C-25	CFM
CS	4C-25	CFM-stpt
CS	CS-NC-19	AHU5401
AI	4C-31	Zone-T
AD	4C-31	CFM
CS	4C-31	CFM-stpt
BO	SHARE19	EF5_26-C
BI	SHARE19	EF5_26
AI	SHARE19	ELV-RM-E
BD	AHU-5401	OCC
BI	AHU-5401	SF-S
BI	AHU-5401	RF-S
AI	AHU-5401	DA-T
AD	AHU-5401	DA-STPT
AOS	AHU-5401	HTG-VLV
BD	AHU-5401	HTG-PMP
AOS	AHU-5401	CLG-VLV
AOS	AHU-5401	OA-DMPR
AI	AHU-5401	MA-T
AI	AHU-5401	RA-T
AI	AHU-5401	OA-T
BI	AHU-5401	LT-ALM
BI	AHU-5401	PURGE
BI	AHU-5401	SHTDWN
BD	AHU-5401	CLG-LOCK
BI	AHU-5401	HAND
AI	AHU-5401	RA-H

DRAFT

Building 2		
Points	Equipment	Type
AOS	AHU-5401	HUM-VLV
AI	AHU-5401	PRE
AI	AHU-5401	AFT
AI	AHU-5401	HWS
AI	AHU-5401	HWR
AI	AHU-5401	CWS
AI	AHU-5401	CWR
AD	AHU-5401	L-ZONE-T
AD	AHU-5401	H-ZONE-T
BO	AHU-5401	SF-C
BO	AHU-5401	RF-C
BO	AHU-5401	EF5_02-C
BI	AHU-5401	EF5_02
BO	AHU-5401	EF5_03-C
BI	AHU-5401	EF5_03
BO	AHU-5401	EF5_05-C
BI	AHU-5401	EF5_05
BO	AHU-5401	EF5_06-C
BI	AHU-5401	EF5_06
BO	AHU-5401	EF5_07-C
BI	AHU-5401	EF5_07
BO	AHU-5401	EF5_09-C
BI	AHU-5401	EF5_09
BO	AHU-5401	EF5_10-C
BI	AHU-5401	EF5_10
BO	AHU-5401	EF5_12-C
BI	AHU-5401	EF5_12
BO	AHU-5401	EF5_14-C
BI	AHU-5401	EF5_14
BD	AHU-5401	EF5_24
BD	AHU-5401	EF5_28
BD	AHU-5401	EF5_29
BO	AHU-5401	EF7_15-C
BI	AHU-5401	EF7_15
AI	AHU-5401	CW-DP
BD	AHU-5401	NITEPURG
JCB	JCB-NC19	5401-PMP
JCB	JCB-NC19	5401-OCC

DRAFT

Building 2		
Points	Equipment	Type
JCB	JCB-NC19	5401-SMK
JCB	JCB-NC19	54_01-TE
JCB	JCB-NC19	5401AITB
JCB	JCB-NC19	54_01EF

Building 2		
Points	**Equipment**	**Type**
NC-21		**Network controller**
NC-21-HW	DC21-164	164, 1, 3, UNT
NC-21-HW	AHU-6302	165, 1, 3, AHU
NC-21-HW	DC21-166	166, 1, 3, UNT
NC-21-HW	DC21-167	167, 1, 3, AHU
NC-21-HW	DC21-168	168, 1, 3, AHU
NC-21-HW	DC21-170	170, 1, 3, UNT
NC-21-HW	DC21-171	171, 1, 3, UNT
NC-21-HW	DC21-172	172, 1, 3, AHU
NC-21-HW	DC21-173	173, 1, 3, AHU
NC-21-HW	DC21-174	174, 1, 3, UNT
NC-21-HW	DC21-175	175, 1, 3, AHU
NC-21-HW	DC21-176	176, 1, 3, AHU
NC-21-HW	CVR-01	1, 1, 3, VAV
NC-21-HW	CVR-02	2, 1, 3, VAV
NC-21-HW	CVR-03	3, 1, 3, VAV
NC-21-HW	CVR-04	4, 1, 3, VAV
NC-21-HW	CVR-05	5, 1, 3, VAV
NC-21-HW	CVR-06	6, 1, 3, VAV
NC-21-HW	CVR-07	7, 1, 3, VAV
NC-21-HW	CVR-08	8, 1, 3, VAV
NC-21-HW	CVR-09	9, 1, 3, VAV
NC-21-HW	CVR-10	10, 1, 3, VAV
NC-21-HW	CVR-11	11, 1, 3, VAV
NC-21-HW	CVR-12	12, 1, 3, VAV
NC-21-HW	CVR-13	13, 1, 3, VAV
NC-21-HW	CVR-14	255, 1, 3, VAV
NC-21-HW	CVR-15	15, 1, 3, VAV
NC-21-HW	CVR-16	16, 1, 3, VAV
NC-21-HW	CVR-17	17, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-21-HW	CVR-19	19, 1, 3, VAV
NC-21-HW	CVR-20	20, 1, 3, VAV
NC-21-HW	CVR-21	21, 1, 3, VAV
NC-21-HW	CVR-22	22, 1, 3, VAV
NC-21-HW	CVR-23	23, 1, 3, VAV
NC-21-HW	CVR-24	24, 1, 3, VAV
NC-21-HW	CVR-25	25, 1, 3, VAV
NC-21-HW	CVR-26	26, 1, 3, VAV
NC-21-HW	CVR-27	27, 1, 3, VAV
NC-21-HW	CVR-28	28, 1, 3, VAV
NC-21-HW	CVR-29	29, 1, 3, VAV
NC-21-HW	CVR-30	30, 1, 3, VAV
NC-21-HW	CVR-31	31, 1, 3, VAV
NC-21-HW	CVR-32	32, 1, 3, VAV
NC-21-HW	CVR-33	33, 1, 3, VAV
NC-21-HW	CVR-34	34, 1, 3, VAV
NC-21-HW	CVR-35	35, 1, 3, VAV
NC-21-HW	CVR-36	36, 1, 3, VAV
NC-21-HW	CVR-37	37, 1, 3, VAV
NC-21-HW	CVR-38	38, 1, 3, VAV
NC-21-HW	CVR-39	39, 1, 3, VAV
NC-21-HW	CVR-40	40, 1, 3, VAV
NC-21-HW	CVR-41	41, 1, 3, VAV
NC-21-HW	CVR-42	42, 1, 3, VAV
NC-21-HW	CVR-43	43, 1, 3, VAV
NC-21-HW	CVR-44	44, 1, 3, VAV
NC-21-HW	CVR-45	45, 1, 3, VAV
NC-21-HW	CVR-46	46, 1, 3, VAV
NC-21-HW	CVR-47	47, 1, 3, VAV
NC-21-HW	CVR-48	48, 1, 3, VAV
NC-21-HW	CVR-49	49, 1, 3, VAV
NC-21-HW	CVR-50	50, 1, 3, VAV
NC-21-HW	CVR-51	51, 1, 3, VAV
NC-21-HW	CVR-52	52, 1, 3, VAV
NC-21-HW	CVR-53	53, 1, 3, VAV
NC-21-HW	CVR-54	54, 1, 3, VAV
NC-21-HW	CVR-55	55, 1, 3, VAV
NC-21-HW	CVR-56	56, 1, 3, VAV

DRAFT

Building 2		
Points	Equipment	Type
NC-21-HW	CVR-57	57, 1, 3, VAV
NC-21-HW	CVR-58	58, 1, 3, VAV
NC-21-HW	CVR-59	59, 1, 3, VAV
NC-21-HW	CVR-60	60, 1, 3, VAV
NC-21-HW	CVR-61	61, 1, 3, VAV
NC-21-HW	CVR-62	62, 1, 3, VAV
NC-21-HW	CVR-63	63, 1, 3, VAV
NC-21-HW	CVR-64	64, 1, 3, VAV
NC-21-HW	CVR-65	65, 1, 3, VAV
NC-21-HW	CVR-66	66, 1, 3, VAV
NC-21-HW	CVR-67	67, 1, 3, VAV
NC-21-HW	CVR-68	68, 1, 3, VAV
NC-21-HW	CVR-69	69, 1, 3, VAV
NC-21-HW	CVR-70	70, 1, 3, VAV
NC-21-HW	CVR-101	101, 1, 3, VAV
NC-21-HW	DC21-177	177, 1, 3, UNT
NC-21-HW	DC21-71	71, 1, 3, UNT
NC-21-HW	DC21-178	178, 1, 3, UNT
BD	ISO-EXH	EF3_75
BD	ISO-EXH	EF3-75
BD	ISO-EXH	EF4_05
AD	ISO-EXH	EF4_26
AD	ISO-EXH	EF4-26
BD	ISO-EXH	EF5_01
BD	ISO-EXH	EF5_05
BD	ISO-EXH	EF5_06
BD	ISO-EXH	EF5_12
BD	ISO-EXH	EF5_13
BD	ISO-EXH	EF5_34
BD	ISO-EXH	EF5_35
BD	ISO-EXH	EF5_37
BD	ISO-EXH	EF5_39
BD	ISO-EXH	EF5_49
BD	ISO-EXH	EF5_50
BD	ISO-EXH	EF5_54
BD	ISO-EXH	EF5_59
BD	ISO-EXH	EF5_61
BD	ISO-EXH	EF6_04

DRAFT

Building 2		
Points	Equipment	Type
BD	ISO-EXH	EF6_11
BD	ISO-EXH	EF6_12
BD	ISO-EXH	EF6_13
BD	ISO-EXH	EF7_14
BD	ISO-EXH	EF5_52
BI	ISO-EXH	EF1TB-S
BO	BIO-SAFE	EF6_07-C
BI	BIO-SAFE	EF6_07
AI	BIO-SAFE	EF6_07DP
BO	BIO-SAFE	EF6_25-C
BI	BIO-SAFE	EF6_25
AI	BIO-SAFE	EF6_25DP
BO	BIO-SAFE	EF6_27-C
BI	BIO-SAFE	EF6_27
AI	BIO-SAFE	EF6_27DP
BO	BIO-SAFE	EF6_29-C
BI	BIO-SAFE	EF6_29
AI	BIO-SAFE	EF6_29DP
BO	BIO-SAFE	EF6_34-C
BI	BIO-SAFE	EF6_34
AI	BIO-SAFE	EF6_34DP
BO	BIO-SAFE	EF7_01-C
BI	BIO-SAFE	EF7_01
BO	BIO-SAFE	EF7_02-C
BI	BIO-SAFE	EF7_02
BO	BIO-SAFE	EF7_03-C
BI	BIO-SAFE	EF7_03
BO	BIO-SAFE	EF7_07-C
BI	BIO-SAFE	EF7_07
AI	BIO-SAFE	EF7-7-P
AI	BIO-SAFE	EF7-7-VP
BI	BIO-SAFE	EF7-7-HS
AD	BIO-SAFE	EF7-07-F
BD	BIO-SAFE	EF7-7A
BD	AHU-6302	OCC
BI	AHU-6302	SF-S
BI	AHU-6302	RF-S
AI	AHU-6302	DA-T

DRAFT

Building 2		
Points	Equipment	Type
AD	AHU-6302	DA-STPT
AOS	AHU-6302	HTG-VLV
BD	AHU-6302	HTG-PMP
AOS	AHU-6302	CLG-VLV
AOS	AHU-6302	OA-DMPR
AI	AHU-6302	MA-T
AI	AHU-6302	RA-T
AI	AHU-6302	OA-T
BI	AHU-6302	LT-ALM
BI	AHU-6302	PURGE
BI	AHU-6302	SHTDWN
BD	AHU-6302	CLG-LOCK
BI	AHU-6302	HAND
AI	AHU-6302	RA-H
AOS	AHU-6302	HUM-VLV
AI	AHU-6302	PRE
AI	AHU-6302	AFT
AI	AHU-6302	HWS
AI	AHU-6302	HWR
AI	AHU-6302	CWS
AI	AHU-6302	CWR
AD	AHU-6302	L-ZONE-T
AD	AHU-6302	H-ZONE-T
BO	AHU-6302	SF-C
BO	AHU-6302	RF-C
BD	AHU-6302	EF5_26
BO	AHU-6302	EF6_01-C
BI	AHU-6302	EF6_01
BO	AHU-6302	EF6_02-C
BI	AHU-6302	EF6_02
BO	AHU-6302	EF6_03-C
BI	AHU-6302	EF6_03
BO	AHU-6302	EF6_04-C
BI	AHU-6302	EF6_04
BO	AHU-6302	EF6_05-c
BI	AHU-6302	EF6_05
BO	AHU-6302	EF6_06-C
BI	AHU-6302	EF6_06

DRAFT

Building 2		
Points	Equipment	Type
BO	AHU-6302	EF6_20-C
BI	AHU-6302	EF6_20
BO	AHU-6302	EF6_23-C
BI	AHU-6302	EF6_23
BD	AHU-6302	NITEPURG
BO	SHARE21	EF6_24-C
BI	SHARE21	EF6_24
BO	SHARE21	EF6_30-C
BI	SHARE21	EF6_30
BO	SHARE21	EF6_31-C
BI	SHARE21	EF6_31
BO	SHARE21	EF6_32-C
BI	SHARE21	EF6_32
BO	SHARE21	EF6_35-C
BI	SHARE21	EF6_35
BO	SHARE21	EF7_04-C
BI	SHARE21	EF7_04
BO	SHARE21	EF7_05-C
BI	SHARE21	EF7_05
BO	SHARE21	EF7_06-C
BI	SHARE21	EF7_06
BO	SHARE21	EF7_09-C
BI	SHARE21	EF7_09
BO	SHARE21	EF7_10-C
BI	SHARE21	EF7_10
BO	SHARE21	EF7_11-C
BI	SHARE21	EF7_11
BO	SHARE21	EF7_12-C
BI	SHARE21	EF7_12
BO	SHARE21	EF8_01-C
BI	SHARE21	EF8_01
AI	SHARE21	EV-RM-AB
AI	SHARE21	EV-RM-CD
AI	SHARE21	EV-RM-EF
BD	AHU-6301	OCC
BI	AHU-6301	SF-S
BI	AHU-6301	RF-S
AI	AHU-6301	DA-T

DRAFT

Building 2		
Points	Equipment	Type
AD	AHU-6301	DA-STPT
AOS	AHU-6301	HTG-VLV
BD	AHU-6301	HTG-PMP
AOS	AHU-6301	CLG-VLV
AOS	AHU-6301	OA-DMPR
AI	AHU-6301	MA-T
AI	AHU-6301	RA-T
AI	AHU-6301	OA-T
BI	AHU-6301	LT-ALM
BI	AHU-6301	PURGE
BI	AHU-6301	SHTDWN
BD	AHU-6301	CLG-LOCK
BI	AHU-6301	HAND
AI	AHU-6301	RA-H
AOS	AHU-6301	HUM-VLV
AI	AHU-6301	PRE
AI	AHU-6301	AFT
AI	AHU-6301	HWS
AI	AHU-6301	HWR
AI	AHU-6301	CWS
AI	AHU-6301	CWR
AD	AHU-6301	L-ZONE-T
AD	AHU-6301	H-ZONE-T
BO	AHU-6301	SF-C
BO	AHU-6301	RF-C
BO	AHU-6301	EF6_08-C
BI	AHU-6301	EF6_08
BO	AHU-6301	EF6_09-C
BI	AHU-6301	EF6_09
BO	AHU-6301	EF6_10-C
BI	AHU-6301	EF6_10
BO	AHU-6301	EF6_11-C
BI	AHU-6301	EF6_11
BO	AHU-6301	EF6_12-C
BI	AHU-6301	EF6_12
BO	AHU-6301	EF6_13-C
BI	AHU-6301	EF6_13
BO	AHU-6301	EF6_14-C

DRAFT

Building 2		
Points	Equipment	Type
BI	AHU-6301	EF6_14
BO	AHU-6301	EF6_15-C
BI	AHU-6301	Ef6_15
BO	AHU-6301	EF6_16-C
BI	AHU-6301	EF6_16
BO	AHU-6301	EF6_17-C
BI	AHU-6301	EF6_17
BO	AHU-6301	EF6_18-C
BI	AHU-6301	EF6_18
BO	AHU-6301	EF6_19-c
BI	AHU-6301	EF6_19
BO	AHU-6301	EF6_21-C
BI	AHU-6301	EF6_21
BD	AHU-6301	NITEPURG
AI	AHU-6301	CW-DP
AD	FUMEHOOD	EF3_71DP
BO	FUMEHOOD	EF6_26-C
BI	FUMEHOOD	EF6_26
BO	FUMEHOOD	EF6_28-C
BI	FUMEHOOD	EF6_28
AI	FUMEHOOD	EF6_28DP
BO	FUMEHOOD	EF6_33-C
AI	FUMEHOOD	EF6_33DP
BO	FUMEHOOD	EF6_36-C
AI	FUMEHOOD	EF6_36DP
BO	FUMEHOOD	EF6_38-C
BI	FUMEHOOD	EF6_38
AI	FUMEHOOD	EF6_38DP
BO	FUMEHOOD	EF6_39-C
AI	FUMEHOOD	EF6_39DP
BI	FUMEHOOD	EF6_39FS
BO	FUMEHOOD	EF7_14-C
BI	FUMEHOOD	EF7_14
AI	FUMEHOOD	EF7_14DP
AI	5C-101	Zone-T
AD	5C-101	ActHtgSP
AD	5C-101	CFM
CS	5C-101	CFM-stpt

DRAFT

Building 2		
Points	Equipment	Type
AI	CONF_RM	RET-TEMP
CS	CONF_RM	RET-STPT
AOS	CONF_RM	CLG-VLV
BI	CONF_RM	FAN-STAT
BO	CONF_RM	FAN-SS
AI	5C-63	Zone-T
AD	5C-63	ActHtgSP
AD	5C-63	CFM
CS	5C-63	CFM-stpt
AI	5C-64	Zone-T
AD	5C-64	ActHtgSP
AD	5C-64	CFM
CS	5C-64	CFM-stpt
AI	5C-65	Zone-T
AD	5C-65	ActHtgSP
AD	5C-65	CFM
CS	5C-65	CFM-stpt
AI	5C-66	Zone-T
AD	5C-66	ActHtgSP
AD	5C-66	CFM
CS	5C-66	CFM-stpt
AI	5C-67	Zone-T
AD	5C-67	ActHtgSP
AD	5C-67	CFM
CS	5C-67	CFM-stpt
AI	5C-69	Zone-T
AD	5C-69	ActHtgSP
AD	5C-69	CFM
CS	5C-69	CFM-stpt
AI	5C-70	Zone-T
AD	5C-70	ActHtgSP
AD	5C-70	CFM
CS	5C-70	CFM-stpt
AI	5C-61	Zone-T
AD	5C-61	ActHtgSP
AD	5C-61	CFM
CS	5C-61	CFM-stpt
AI	5C-60	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	5C-60	ActHtgSP
AD	5C-60	CFM
CS	5C-60	CFM-stpt
AI	5C-59	Zone-T
AD	5C-59	ActHtgSP
AD	5C-59	CFM
CS	5C-59	CFM-stpt
AI	5C-58	Zone-T
AD	5C-58	ActHtgSP
AD	5C-58	CFM
CS	5C-58	CFM-stpt
AI	5C-57	Zone-T
AD	5C-57	ActHtgSP
AD	5C-57	CFM
CS	5C-57	CFM-stpt
AI	5C-56	Zone-T
AD	5C-56	ActHtgSP
AD	5C-56	CFM
CS	5C-56	CFM-stpt
AI	5C-55	Zone-T
AD	5C-55	ActHtgSP
AD	5C-55	CFM
CS	5C-55	CFM-stpt
AI	5C-54	Zone-T
AD	5C-54	ActHtgSP
AD	5C-54	CFM
CS	5C-54	CFM-stpt
AI	5C-53	Zone-T
AD	5C-53	ActHtgSP
AD	5C-53	CFM
CS	5C-53	CFM-stpt
AI	5C-52	Zone-T
AD	5C-52	ActHtgSP
AD	5C-52	CFM
CS	5C-52	CFM-stpt
AI	5C-50	Zone-T
AD	5C-50	ActHtgSP
AD	5C-50	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	5C-50	CFM-stpt
AI	5C-49	Zone-T
AD	5C-49	ActHtgSP
AD	5C-49	CFM
CS	5C-49	CFM-stpt
AI	5C-48	Zone-T
AD	5C-48	ActHtgSP
AD	5C-48	CFM
CS	5C-48	CFM-stpt
AI	5C-47	Zone-T
AD	5C-47	ActHtgSP
AD	5C-47	CFM
CS	5C-47	CFM-stpt
AI	5C-46	Zone-T
AD	5C-46	ActHtgSP
AD	5C-46	CFM
CS	5C-46	CFM-stpt
AI	5C-45	Zone-T
AD	5C-45	ActHtgSP
AD	5C-45	CFM
CS	5C-45	CFM-stpt
AI	5C-44	Zone-T
AD	5C-44	ActHtgSP
AD	5C-44	CFM
CS	5C-44	CFM-stpt
AI	5C-43	Zone-T
AD	5C-43	ActHtgSP
AD	5C-43	CFM
CS	5C-43	CFM-stpt
AI	5C-42	Zone-T
AD	5C-42	ActHtgSP
AD	5C-42	CFM
CS	5C-42	CFM-stpt
AI	5C-41	Zone-T
AD	5C-41	ActHtgSP
AD	5C-41	CFM
CS	5C-41	CFM-stpt
AI	5C-40	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	5C-40	ActHtgSP
AD	5C-40	CFM
CS	5C-40	CFM-stpt
AI	5C-39	Zone-T
AD	5C-39	ActHtgSP
AD	5C-39	CFM
CS	5C-39	CFM-stpt
AI	5C-38	Zone-T
AD	5C-38	ActHtgSP
AD	5C-38	CFM
CS	5C-38	CFM-stpt
AI	5C-37	Zone-T
AD	5C-37	ActHtgSP
AD	5C-37	CFM
CS	5C-37	CFM-stpt
AI	5C-36	Zone-T
AD	5C-36	ActHtgSP
AD	5C-36	CFM
CS	5C-36	CFM-stpt
AI	5C-35	Zone-T
AD	5C-35	ActHtgSP
AD	5C-35	CFM
CS	5C-35	CFM-stpt
AI	5C-34	Zone-T
AD	5C-34	ActHtgSP
AD	5C-34	CFM
CS	5C-34	CFM-stpt
AI	5C-33	Zone-T
AD	5C-33	ActHtgSP
AD	5C-33	CFM
CS	5C-33	CFM-stpt
AI	5C-31	Zone-T
AD	5C-31	ActHtgSP
AD	5C-31	CFM
CS	5C-31	CFM-stpt
AI	5C-30	Zone-T
AD	5C-30	ActHtgSP
AD	5C-30	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	5C-30	CFM-stpt
AI	5C-29	Zone-T
AD	5C-29	ActHtgSP
AD	5C-29	CFM
CS	5C-29	CFM-stpt
AI	5C-28	Zone-T
AD	5C-28	ActHtgSP
AD	5C-28	CFM
CS	5C-28	CFM-stpt
AI	5C-27	Zone-T
AD	5C-27	ActHtgSP
AD	5C-27	CFM
CS	5C-27	CFM-stpt
AI	5C-26	Zone-T
AD	5C-26	ActHtgSP
AD	5C-26	CFM
CS	5C-26	CFM-stpt
AI	5C-25	Zone-T
AD	5C-25	ActHtgSP
AD	5C-25	CFM
CS	5C-25	CFM-stpt
AI	5C-23	Zone-T
AD	5C-23	ActHtgSP
AD	5C-23	CFM
CS	5C-23	CFM-stpt
AI	5C-22	Zone-T
AD	5C-22	ActHtgSP
AD	5C-22	CFM
CS	5C-22	CFM-stpt
AI	5C-21	Zone-T
AD	5C-21	ActHtgSP
AD	5C-21	CFM
CS	5C-21	CFM-stpt
AI	5C-20	Zone-T
AD	5C-20	ActHtgSP
AD	5C-20	CFM
CS	5C-20	CFM-stpt
AI	5C-19	Zone-T

DRAFT

Building 2		
Points	Equipment	Type
AD	5C-19	ActHtgSP
AD	5C-19	CFM
CS	5C-19	CFM-stpt
AI	5C-17	Zone-T
AD	5C-17	ActHtgSP
AD	5C-17	CFM
CS	5C-17	CFM-stpt
AI	5C-16	Zone-T
AD	5C-16	ActHtgSP
AD	5C-16	CFM
CS	5C-16	CFM-stpt
AI	5C-15	Zone-T
AD	5C-15	ActHtgSP
AD	5C-15	CFM
CS	5C-15	CFM-stpt
AI	5C-14	Zone-T
AD	5C-14	ActHtgSP
AD	5C-14	CFM
CS	5C-14	CFM-stpt
AI	5C-13	Zone-T
AD	5C-13	ActHtgSP
AD	5C-13	CFM
CS	5C-13	CFM-stpt
AI	5C-12	Zone-T
AD	5C-12	ActHtgSP
AD	5C-12	CFM
CS	5C-12	CFM-stpt
AI	5C-11	Zone-T
AD	5C-11	ActHtgSP
AD	5C-11	CFM
CS	5C-11	CFM-stpt
AI	5C-10	Zone-T
AD	5C-10	ActHtgSP
AD	5C-10	CFM
CS	5C-10	CFM-stpt
AI	5C-09	Zone-T
AD	5C-09	ActHtgSP
AD	5C-09	CFM

DRAFT

Building 2		
Points	Equipment	Type
CS	5C-09	CFM-stpt
AI	5C-08	Zone-T
AD	5C-08	ActHtgSP
AD	5C-08	CFM
CS	5C-08	CFM-stpt
AI	5C-07	Zone-T
AD	5C-07	ActHtgSP
AD	5C-07	CFM
CS	5C-07	CFM-stpt
AI	5C-06	Zone-T
AD	5C-06	ActHtgSP
AD	5C-06	CFM
CS	5C-06	CFM-stpt
AI	5C-05	Zone-T
AD	5C-05	ActHtgSP
AD	5C-05	CFM
CS	5C-05	CFM-stpt
AI	5C-04	Zone-T
AD	5C-04	ActHtgSP
AD	5C-04	CFM
CS	5C-04	CFM-stpt
AI	5C-03	Zone-T
AD	5C-03	ActHtgSP
AD	5C-03	CFM
CS	5C-03	CFM-stpt
AI	5C-02	Zone-T
AD	5C-02	ActHtgSP
AD	5C-02	CFM
CS	5C-02	CFM-stpt
AI	5C-01	Zone-T
AD	5C-01	ActHtgSP
AD	5C-01	CFM
CS	5C-01	CFM-stpt
AI	5C-62	Zone-T
AD	5C-62	ActHtgSP
AD	5C-62	CFM
CS	5C-62	CFM-stpt
AD	ELEV-RM	ELV-RM-A

DRAFT

Building 2		
Points	Equipment	Type
AD	ELEV-RM	ELV-RM-B
AD	ELEV-RM	ELV-RM-E
AD	ELEV-RM	ELV-RM-F
AD	ELEV-RM	EV-RM-AB
AD	ELEV-RM	EV-RM-CD
AD	ELEV-RM	EV-RM-EF
AI	5C-24	Zone-T
AD	5C-24	CFM
CS	5C-24	CFM-stpt
AI	5C-51	Zone-T
AD	5C-51	CFM
CS	5C-51	CFM-stpt
AI	5C-68	Zone-T
AD	5C-68	ActHtgSP
AD	5C-68	CFM
CS	5C-68	CFM-stpt
AI	5C-32	ZN-T
AD	5C-32	ActHtgSP
AD	5C-32	CFM
CS	5C-32	CFM-stpt
JCB	JCB-NC21	6301-PMP
JCB	JCB-NC21	6302-PMP
JCB	JCB-NC21	6301-SMK
JCB	JCB-NC21	6302-SMK
JCB	JCB-NC21	63_01EF
JCB	JCB-NC21	63_02EF
JCB	JCB-NC21	6301AITB
JCB	JCB-NC21	6302AITB
JCB	JCB-NC21	6301-OCC
JCB	JCB-NC21	6302-OCC
JCB	JCB-NC21	63_02-TE
JCB	JCB-NC21	63_01-TE
AD	JCB-NC21	EF7-07-K
JCB	JCB-NC21	EF7_7_CF
JCB	JCB-NC21	FAN_HAND
CS	CS-NC-21	AHU6301
CS	CS-NC-21	AHU6302
CS	CS-NC-21	EF7-7

DRAFT

	Building 3	
Point	**Equipment**	**Type**
	NC-10	**Network controller**
NC10-HRW	HEAT	216, 1, 3, DX9100
NC10-HRW	TRANE1HW	210, 1, 1, MIG
NC10-HRW	TRANEHW2	211, 1, 1, MIG
NC10-HRW	12-121	1, 1, 3, VMA
NC10-HRW	12-119	2, 1, 3, VMA
NC10-HRW	12-132	3, 1, 3, VMA
NC10-HRW	12-134	4, 1, 3, VMA
NC10-HRW	16-105	5, 1, 3, VMA
NC10-HRW	16-107	6, 1, 3, VMA
NC10-HRW	16-108	7, 1, 3, VMA
NC10-HRW	16-110	8, 1, 3, VMA
NC10-HRW	16-116	9, 1, 3, VMA
NC10-HRW	16-113	10, 1, 3, VMA
NC10-HRW	16-122b	11, 1, 3, VMA
NC10-HRW	16-122a	12, 1, 3, VMA
NC10-HRW	16-117	13, 1, 3, VMA
NC10-HRW	16-119	14, 1, 3, VMA
NC10-HRW	16-141a	15, 1, 3, VMA
NC10-HRW	16-141b	16, 1, 3, VMA
NC10-HRW	15-163	17, 1, 3, VMA
NC10-HRW	15-162	18, 1, 3, VMA
NC10-HRW	15-160	19, 1, 3, VMA
NC10-HRW	15-153a	20, 1, 3, VMA
NC10-HRW	15-153b	21, 1, 3, VMA
NC10-HRW	15-149	22, 1, 3, VMA
NC10-HRW	15-152	23, 1, 3, VMA
NC10-HRW	15-148	24, 1, 3, VMA
NC10-HRW	15-145	25, 1, 3, VMA
NC10-HRW	15-129	26, 1, 3, VMA
NC10-HRW	15-131	27, 1, 3, VMA
NC10-HRW	15-133	28, 1, 3, VMA
NC10-HRW	15-136	29, 1, 3, VMA
NC10-HRW	15-135	30, 1, 3, VMA
NC10-HRW	15-137	31, 1, 3, VMA
NC10-HRW	15-140	32, 1, 3, VMA
NC10-HRW	15-125	33, 1, 3, VMA
NC10-HRW	15-124	34, 1, 3, VMA
NC10-HRW	15-123	35, 1, 3, VMA
NC10-HRW	15-134	36, 1, 3, VMA
NC10-HRW	15-116	37, 1, 3, VMA
NC10-HRW	15-120	38, 1, 3, VMA

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC10-HRW	15-118	39, 1, 3, VMA
NC10-HRW	15-111	40, 1, 3, VMA
NC10-HRW	15-102	41, 1, 3, VMA
NC10-HRW	15-106	42, 1, 3, VMA
NC10-HRW	15-101	43, 1, 3, VMA
NC10-HRW	15-168	44, 1, 3, VMA
NC10-HRW	14-119	45, 1, 3, VMA
NC10-HRW	14-105a	46, 1, 3, VMA
NC10-HRW	14-105b	47, 1, 3, VMA
NC10-HRW	14-104	48, 1, 3, VMA
NC10-HRW	14-102	49, 1, 3, VMA
NC10-HRW	14-101	50, 1, 3, VMA
NC10-HRW	14-108	51, 1, 3, VMA
NC10-HRW	AHU-2A	195, 1, 3, AHU
NC10-HRW	AHU-02	205, 1, 3, AHU
NC10-HRW	AHU-02C	206, 1, 3, AHU
NC10-HRW	AHU-02EW	203, 1, 3, AHU
NC10-HRW	AHU-01E	202, 1, 3, AHU
NC10-HRW	AHU-02AM	201, 1, 3, UNT
NC10-HRW	AHU-02CM	207, 1, 3, UNT
NC10-HRW	HV-UNIT	204, 1, 3, AHU
NC10-HRW	1-FCU-01	196, 1, 3, VAV
NC10-HRW	1-FCU-02	197, 1, 3, VAV
NC10-HRW	1-FCU-03	198, 1, 3, VAV
NC10-HRW	1-FCU-04	199, 1, 3, VAV
NC10-HRW	1-FCU-05	200, 1, 3, VAV
NC10-HRW	UNT-50	54, 1, 3, UNT
NC10-HRW	DC-208	208, 1, 3, DX9100
NC10-HRW	DC-217	217, 1, 3, DX9100
NC10-HRW	DC-218	218, 1, 3, DX9100
NC10-HRW	WTR-VFD	220, 1, 3, VND
NC10-HRW	P2-VFD	221, 1, 3, VND
NC10-HRW	PMP-ALM	222, 1, 3, UNT
NC10-HRW	PMP-ALM2	223, 1, 3, UNT
NC10-HRW	UNT-224	224, 1, 3, UNT
NC10-HRW	CHLR194	194, 1, 3, UNT
NC10-HRW	CHLR193	193, 1, 3, UNT
MSD	15-124	Occupied Command
AI	15-124	Zone Temp
AI	15-124	Zone Setpoint
AI	15-124	Zone Temp
AD	15-124	Supply Air CFM
AD	15-124	Supply Air CFM SP
AD	15-124	Damper Command
AD	15-124	Heating Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	15-124	All Points for 15-124
MC	AH-02A	AHU Occuipied Command
BO	AH-02A	Supply Fan Command
BI	AH-02A	Supply Airflow
BI	AH-02A	Outside Air Damper
MC	AH-02A	_
AI	AH-02A	Zone Temp
AI	AH-02A	Zone Humidity
MC	AH-02A	__
AI	AH-02A	Preheat Temp
AOS	AH-02A	Preheat Setpoint
AOS	AH-02A	Preheat Valve Command
AI	AH-02A	Preheat RetWtr Temp
MC	AH-02A	___
MC	AH-02A	____
AI	AH-02A	Outside Air Temp
AOS	AH-02A	Preheat Face/Bypass
AOS	AH-02A	Face And Bypass Setpoint
MC	AH-02A	_____
AI	AH-02A	Cooling Coil Temp
AOS	AH-02A	Cooling Coil Setpoint
AOS	AH-02A	Cooling Valve Command
AI	AH-02A	Cooling RetWtr Temp
MC	AH-02A	_____
AI	AH-02A	Reheat Air Temp
AOS	AH-02A	Reheat Setpoint
AOS	AH-02A	Reheat Valve Command
AI	AH-02A	Reheat RetWtr Temp
MC	AH-02A	_____
BI	AH-02A	Low Temp Alarm
BI	AH-02A	Supply Air Smk Detector
BI	AH-02A	Filter Status
MC	AH-02A	_____
CS	AH-02A	AHU CSO Space Temp
BD	CCHILLER	Enable 215 Chiller SYS
BD	CCHILLER	Enable Clg from Bldg20
BD	CCHILLER	Lead Chiller
BD	CCHILLER	Lead Primary Chw Pump
BD	CCHILLER	Lead Condenser Pump
BD	CCHILLER	-------
AI	CCHILLER	Bldg 215 Chil Wtr Supply
AI	CCHILLER	Bldg 215 Chil Wtr Return
AI	CCHILLER	Sec Chil Wtr Supply
AI	CCHILLER	Sec Chil Wtr Return
AI	CCHILLER	Cond Return to Tower

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	CCHILLER	Cond Supply to Chillers
BI	CCHILLER	Pri Chw Pmp 2 Status
BI	CCHILLER	Pri Chw Pmp 1 Status
BI	CCHILLER	Clg Twr Pmp 7 Status
BI	CCHILLER	Clg Twr Pmp 8 Status
BO	CCHILLER	Primary Chw P-2 S/S
BO	CCHILLER	Primary Chw P-1 S/S
BO	CCHILLER	Ch1 Isolation Valve S/S
BO	CCHILLER	Ch2 Isolation Valve S/S
BO	CCHILLER	CHW HX Isolation Vlv S/S
AI	CCHILLER	Secondary Chw Diff Press
BO	CCHILLER	Condenser P-7 S/S
BO	CCHILLER	Condenser P-8 S/S
BO	CCHILLER	Chw Hx Skid Enable
BO	CCHILLER	Sec Chw Skid Enable
BI	CCHILLER	Sec Chw Pump 3 Alarm
BI	CCHILLER	Sec Chw Pump 4 Alarm
AD	CCHILLER	Condenser Low Setpt=68.0
AD	CCHILLER	Condenser High Stpt=75.0
BD	CCHILLER	Low Differential Alarm
JCB	CCHILLER	COND-RST
BD	CCHILLER	-----Valve Status------
BI	CCHILLER	Chiller/Exchanger
BI	CCHILLER	Chiller/Exchanger A
BI	CCHILLER	Cond Water Vlv Status1
BI	CCHILLER	Cond Water Vlv Status1A
BI	CCHILLER	Chiled Water Vlv Status1
BI	CCHILLER	Chill Water Vlv Status1A
BI	CCHILLER	Chiled Water Vlv Status2
BI	CCHILLER	Chill Water Vlv Status2A
BI	CCHILLER	Cond Water Vlv Status2
BI	CCHILLER	Cond Water Vlv Status2A
JCB	JCB-NC10	CHILLER1
JCB	JCB-NC10	CDPUMPS
JCB	JCB-NC10	PRIPUMPS
JCB	JCB-NC10	CHILLER2
JCB	JCB-NC10	SEC-CHW
JCB	JCB-NC10	CHILLERS
JCB	JCB-NC10	HTG-STPT
JCB	JCB-NC10	ChwHx2
MSD	12-134	Occupied Command
AI	12-134	Zone Temp
AI	12-134	Zone Setpoint
AD	12-134	Supply Air CFM
AD	12-134	Supply Air CFM SP

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	12-134	Damper Command
BO	12-134	Series Fan Command
AD	12-134	Heating Command
CS	12-134	All Points for 12-134
MC	HV-UNIT	HV Occuipied Command
BO	HV-UNIT	Supply Fan Command
BI	HV-UNIT	Supply Airflow
BI	HV-UNIT	Outside Air Damper Sts
AI	HV-UNIT	Outside Air Temp
MC	HV-UNIT	_
AOS	HV-UNIT	Zone Setpoint
AI	HV-UNIT	Zone Temp
MC	HV-UNIT	__
AI	HV-UNIT	Preheat Temp
MC	HV-UNIT	___
AOS	HV-UNIT	Preheat Valve Command
AI	HV-UNIT	Preheat RetWtr Temp
MC	HV-UNIT	____
AOS	HV-UNIT	Preheat Face/Bypass
AOS	HV-UNIT	Face And Bypass Setpoint
MC	HV-UNIT	_____
BI	HV-UNIT	Low Temp Alarm
BI	HV-UNIT	Supply Air Smk Detector
BI	HV-UNIT	Filter Status
MC	HV-UNIT	_____
CS	HV-UNIT	HV CSO Space Temp
BO	DOM-WTR	Lead Lag Dom-P1,P2
AI	DOM-WTR	Domestic Water Pressure
AOS	DOM-WTR	Hours Setpoint
AOS	DOM-WTR	Dom. Wtr. Press. Stpt.
BD	DOM-WTR	Pump1 Data ----------
CS	DOM-WTR	Cs Object Pump 1
AD	DOM-WTR	Drive Current
AD	DOM-WTR	Drive Power in KW
AD	DOM-WTR	Drive Power in HP
AD	DOM-WTR	Drive Frequency
AOS	DOM-WTR	Dom-P1 Command %Out
AD	DOM-WTR	Drive Bus Ref
BD	DOM-WTR	Drive Current Alarm
BD	DOM-WTR	Drive Voltage Alarm
BI	DOM-WTR	Pump 1 Vfd Fault
BI	DOM-WTR	Pump 1 High Temp
BI	DOM-WTR	P1 Pressure Fail
BD	DOM-WTR	Drive Inverter Alarm
BD	DOM-WTR	Dom.-P1 Hardware Points

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	DOM-WTR	Dom.Pump1 Start Stop
BO	DOM-WTR	Dom.Pump1 Status
AD	DOM-WTR	Dom.- P1 Runtime
BD	DOM-WTR	Dom.-P1 Alarm
BD	DOM-WTR	Pump2 Data ----------
CS	DOM-WTR	Cs Object Pump 2
AD	DOM-WTR	Pump 2 Drive Frequency
AD	DOM-WTR	Pump 2 Current
AD	DOM-WTR	Pump 2 Power in KW
AD	DOM-WTR	Pump 2 Power in HP
AD	DOM-WTR	Pump 2 Bus Reference
BD	DOM-WTR	P2 Current Alarm
BD	DOM-WTR	P2 Voltage Alarm
BD	DOM-WTR	P2 Inverter Alarm
BI	DOM-WTR	P2 Pressure Fail
BI	DOM-WTR	Pump 2 Vfd Fault
BI	DOM-WTR	Pump 2 High Temp
AOS	DOM-WTR	Dom-P2 Command %Out
BD	DOM-WTR	Dom.-P2 Hardware Points
BD	DOM-WTR	Dom.-P2 Alarm
AD	DOM-WTR	Dom.- P2 Runtime
BO	DOM-WTR	Dom.Pump2 Status
BO	DOM-WTR	Dom.Pump2 Start Stop
BD	DOM-WTR	Pump Alarm Points-------
BI	DOM-WTR	Low System Pressure
BI	DOM-WTR	High System Shutdown
BI	DOM-WTR	Low Suction Shutdown
BI	DOM-WTR	High Suction Shutdown
CS	DOM-WTR	Dom-P1,P2 Alarms & RT
CS	DOM-WTR	GPL CS-Object
CS	DOM-WTR	LRS Switch For Lead/Lag
JCB	DOM-WTR	Dom-P1P2
AI	DOM-HW	Hot Water Tank 1 Sup Tmp
AI	DOM-HW	Hot Water Tank 2 Sup Tmp
AOS	DOM-HW	Hot Water Setpoint
AOS	DOM-HW	Steam Valve 1
AOS	DOM-HW	Steam Valve 2
AI	HEATXER	Hot Water Supply Temp
AI	HEATXER	Hot Water Return Temp
AOS	HEATXER	Hot Wtr Supply Setpoint
BI	HEATXER	Hot Water Pump Status
BO	HEATXER	Hot Wtr Pump Skid Comman
AOS	HEATXER	Steam Valve Command
AI	HEATXER	Steam Flow Meter

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	HEATXER	Diff Press -1
AI	HEATXER	Diff Press -2
AI	HEATXER	Diff Press -3
JCB	Heatxer	HWBYP-V
BI	HEATXER	Hot Water Pump9 Alarm
BI	HEATXER	Hot Water Pump10 Alarm
MC	AH-02EW	AHU Occuipied Command
BO	AH-02EW	Supply Fan Command
BI	AH-02EW	Supply Airflow
BO	AH-02EW	OA Damper Command
BI	AH-02EW	Outside Air Damper Sts
MC	AH-02EW	_
AI	AH-02EW	Cooling Coil Temp
AOS	AH-02EW	Cooling Coil Setpoint
AI	AH-02EW	Cooling RetWtr Temp
AOS	AH-02EW	Cooling Valve Command
MC	AH-02EW	__
AI	AH-02EW	Down Duct Static Press
AOS	AH-02EW	Down Duct Static Setpnt
MC	AH-02EW	___
AOS	AH-02EW	Supply Fan VFD
BI	AH-02EW	VSD Status
BI	AH-02EW	VSD Alarm
MC	AH-02EW	____
AI	AH-02EW	Mixed Air Temp
AI	AH-02EW	Return Air Temp
MC	AH-02EW	_____
AI	AH-02EW	Preheat Temp
AOS	AH-02EW	Preheat Setpoint
AI	AH-02EW	Preheat RetWtr Temp
AOS	AH-02EW	Preheat Valve Command
MC	AH-02EW	_____
AI	AH-02EW	OA Flow FPM
AOS	AH-02EW	OA Flow FPM Setpoint
MC	AH-02EW	_____
BI	AH-02EW	Low Temp Alarm
BI	AH-02EW	Supply Air Smk Detector
BI	AH-02EW	High Static Alarm
BI	AH-02EW	Filter Status
MC	AH-02EW	_____
CS	AH-02EW	AHU CSO
MC	AH-02	AHU Occuipied Command
BO	AH-02	Supply Fan Command
BI	AH-02	Supply Airflow
BO	AH-02	OA Damper Command
BI	AH-02	Outside Air Damper Sts

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MC	AH-02	_
AI	AH-02	Cooling Coil Temp
AOS	AH-02	Cooling Coil Setpoint
AI	AH-02	Cooling RetWtr Temp
AOS	AH-02	Cooling Valve Command
MC	AH-02	__
AI	AH-02	Down Duct Static Press
AOS	AH-02	Down Duct Static Setpnt
MC	AH-02	___
AOS	AH-02	Supply Fan VFD
BI	AH-02	VSD Status
BI	AH-02	VSD Alarm
MC	AH-02	____
AI	AH-02	Mixed Air Temp
AI	AH-02	Return Air Temp
MC	AH-02	_____
AI	AH-02	Preheat Temp
AOS	AH-02	Preheat Setpoint
AI	AH-02	Preheat RetWtr Temp
AOS	AH-02	Preheat Valve Command
MC	AH-02	_____
AI	AH-02	OA Flow FPM
AOS	AH-02	OA Flow FPM Setpoint
AOS	AH-02	Return Air Damper
MC	AH-02	_____
BI	AH-02	Low Temp Alarm
BI	AH-02	Supply Air Smk Detector
BI	AH-02	High Static Alarm
BI	AH-02	Filter Status
MC	AH-02	_____
CS	AH-02	AHU2-CSO
AOS	AH-02	FB-STPT
MC	AH-02C	AHU Occuipied Command
BO	AH-02C	Supply Fan Command
BI	AH-02C	Supply Airflow
BI	AH-02C	Outside Air Damper Sts
MC	AH-02C	_
AI	AH-02C	Zone Temp
AI	AH-02C	Zone Humidity
MC	AH-02C	__
AI	AH-02C	Preheat Temp
AOS	AH-02C	Preheat Setpoint
AOS	AH-02C	Preheat Valve Command
AI	AH-02C	Preheat RetWtr Temp
MC	AH-02C	___
MC	AH-02C	____

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	AH-02C	Outside Air Temp
AOS	AH-02C	Preheat Face/Bypass
AOS	AH-02C	Face And Bypass Setpoint
MC	AH-02C	_____
AI	AH-02C	Cooling Coil Temp
AOS	AH-02C	Cooling Coil Setpoint
AOS	AH-02C	Cooling Valve Command
AI	AH-02C	Cooling RetWtr Temp
MC	AH-02C	_____
AI	AH-02C	Reheat Air Temp
AOS	AH-02C	Reheat Setpoint
AOS	AH-02C	Reheat Valve Command
AI	AH-02C	Reheat RetWtr Temp
MC	AH-02C	_____
BI	AH-02C	Low Temp Alarm
BI	AH-02C	Supply Air Smk Detector
BI	AH-02C	Filter Status
MC	AH-02C	_____
CS	AH-02C	AHU CSO Zone Temp
MSD	15-125	Occupied Command
AI	15-125	Zone Temp
AI	15-125	Zone Setpoint
AI	15-125	Zone Temp
AD	15-125	Supply Air CFM
AD	15-125	Supply Air CFM SP
AD	15-125	Damper Command
BO	15-125	Series Fan Command
AD	15-125	Heating Command
CS	15-125	All Points for 15-125
BI	SUMP	Sump Pump 1 Stat
BI	SUMP	Sump Pump 2 Stat
BI	SUMP	General Sump Pump Alarm
BO	SUMP	Sump Pump 1 -Start Stop
BO	SUMP	Sump Pump 2 -Start Stop
BO	CHLR-2	Chiller Stop/Start
BI	CHLR-2	Chiller Status
BI	CHLR-2	Condenser Water Flow
BI	CHLR-2	Chilled Water Flow
AI	CHLR-2	Leaving Evaporater Temp
AI	CHLR-2	Entering Evaporater Temp
AI	CHLR-2	Leaving Cond Water Temp
AI	CHLR-2	Entering Cond Water Temp
AI	CHLR-2	Percent Running Load Amp
AI	CHLR-2	Evap Refrig Pressure
AI	CHLR-2	Cond Refrig Pressure
AI	CHLR-2	Comp Disch Refrig Pres

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	CHLR-2	Evap Refrig Temperature
AI	CHLR-2	Cond Refrig Temperature
AI	CHLR-2	Oil Temperature
AI	CHLR-2	Oil Pressure
BI	CHLR-2	Manual Reset Alarm
BI	CHLR-2	Auto Reset Alarm
BO	CHLR-1	Chiller Stop/Start
BI	CHLR-1	Chiller Status
BI	CHLR-1	Condenser Water Flow
BI	CHLR-1	Chilled Water Flow
AOS	CHLR-1	Chill Water Setpoint
AOS	CHLR-1	Demand Limit Setpoint
AI	CHLR-1	Leaving Evaporater Temp
AI	CHLR-1	Entering Evaporater Temp
AI	CHLR-1	Leaving Cond Wtr Temp
AI	CHLR-1	Entering Cond Wtr Temp
AI	CHLR-1	Percent Running Load Amp
AI	CHLR-1	Evap Refrig Pressure
AI	CHLR-1	Cond Refrig Pressure
AI	CHLR-1	Comp Disch Refrig Pres
AI	CHLR-1	Evap Refrig Temperature
AI	CHLR-1	Cond Refrig Temperature
AI	CHLR-1	Oil Temperature
AI	CHLR-1	Oil Press Differential
BI	CHLR-1	Manual Reset Alarm
BI	CHLR-1	Auto Reset Alarm
MSD	12-121	Occupied Command
AI	12-121	Zone Temp
AI	12-121	Zone Setpoint
AI	12-121	Zone Temp
AD	12-121	Supply Air CFM
AD	12-121	Supply Air CFM SP
AD	12-121	Damper Command
BO	12-121	Series Fan Command
AD	12-121	Heating Command
CS	12-121	All Points for 12-121
MSD	12-119	Occupied Command
AI	12-119	Zone Temp
AI	12-119	Zone Setpoint
AI	12-119	Zone Temp
AD	12-119	Supply Air CFM
AD	12-119	Supply Air CFM SP
AD	12-119	Damper Command
BO	12-119	Series Fan Command
AD	12-119	Heating Command
CS	12-119	All Points for 12-119

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MSD	12-132	Occupied Command
AI	12-132	Zone Temp
AI	12-132	Zone Setpoint
AI	12-132	Zone Temp
AD	12-132	Supply Air CFM
AD	12-132	Supply Air CFM SP
AD	12-132	Damper Command
BO	12-132	Series Fan Command
AD	12-132	Heating Command
CS	12-132	All Points for 12-132
MSD	14-119	Occupied Command
AI	14-119	Zone Temp
AI	14-119	Zone Setpoint
AI	14-119	Zone Temp
AD	14-119	Supply Air CFM
AD	14-119	Supply Air CFM SP
AD	14-119	Damper Command
BO	14-119	Series Fan Command
AD	14-119	Heating Command
CS	14-119	All Points for 14-119
MSD	14-105a	Occupied Command
AI	14-105a	Zone Temp
AI	14-105a	Zone Setpoint
AI	14-105a	Zone Temp
AD	14-105a	Supply Air CFM
AD	14-105a	Supply Air CFM SP
AD	14-105a	Damper Command
BO	14-105a	Series Fan Command
AD	14-105a	Heating Command
CS	14-105a	All Points for 14-105a
MSD	14-105b	Occupied Command
AI	14-105b	Zone Temp
AI	14-105b	Zone Setpoint
AI	14-105b	Zone Temp
AD	14-105b	Supply Air CFM
AD	14-105b	Supply Air CFM SP
AD	14-105b	Damper Command
BO	14-105b	Series Fan Command
AD	14-105b	Heating Command
CS	14-105b	All Points for 14-105b
MSD	14-104	Occupied Command
AI	14-104	Zone Temp
AI	14-104	Zone Setpoint
AI	14-104	Zone Temp
AD	14-104	Supply Air CFM
AD	14-104	Supply Air CFM SP

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	14-104	Damper Command
BO	14-104	Series Fan Command
AD	14-104	Heating Command
CS	14-104	All Points for 14-104
MSD	14-102	Occupied Command
AI	14-102	Zone Temp
AI	14-102	Zone Setpoint
AI	14-102	Zone Temp
AD	14-102	Supply Air CFM
AD	14-102	Supply Air CFM SP
AD	14-102	Damper Command
BO	14-102	Series Fan Command
AD	14-102	Heating Command
CS	14-102	All Points for 14-102
MSD	14-101	Occupied Command
AI	14-101	Zone Temp
AI	14-101	Zone Setpoint
AI	14-101	Zone Temp
AD	14-101	Supply Air CFM
AD	14-101	Supply Air CFM SP
AD	14-101	Damper Command
BO	14-101	Series Fan Command
AD	14-101	Heating Command
CS	14-101	All Points for 14-101
MSD	14-108	Occupied Command
AI	14-108	Zone Temp
AI	14-108	Zone Setpoint
AI	14-108	Zone Temp
AD	14-108	Supply Air CFM
AD	14-108	Supply Air CFM SP
AD	14-108	Damper Command
BO	14-108	Series Fan Command
AD	14-108	Heating Command
CS	14-108	All Points for 14-108
MC	AH-01E	AHU Occuipied Command
BO	AH-01E	Supply Fan Command
BI	AH-01E	Supply Airflow
BO	AH-01E	OA Damper Command
BI	AH-01E	Outside Air Damper Sts
MC	AH-01E	_
AI	AH-01E	Cooling Coil Temp
AOS	AH-01E	Cooling Coil Setpoint
AI	AH-01E	Cooling RetWtr Temp
AOS	AH-01E	Cooling Valve Command
MC	AH-01E	__
AI	AH-01E	Down Duct Static Press

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	AH-01E	Down Duct Static Setpnt
MC	AH-01E	___
AOS	AH-01E	Supply Fan VFD
BI	AH-01E	VSD Run Status
BI	AH-01E	VSD ALARM
MC	AH-01E	____
AI	AH-01E	Mixed Air Temp
AI	AH-01E	Return Air Temp
MC	AH-01E	_____
AI	AH-01E	Preheat Temp
AOS	AH-01E	Preheat Setpoint
AI	AH-01E	Preheat RetWtr Temp
AOS	AH-01E	Preheat Valve Command
MC	AH-01E	_____
AI	AH-01E	OA Flow FPM
AOS	AH-01E	OA Flow FPM Setpoint
AOS	AH-01E	Return Air Damper
MC	AH-01E	_____
BI	AH-01E	Low Temp Alarm
BI	AH-01E	Supply Air Smk Detector
BI	AH-01E	High Static Alarm
BI	AH-01E	Filter Status
MC	AH-01E	_____
CS	AH-01E	AHU CSO Supply Temp
MC	1-FCU-01	FCU Occupied Command
BO	1-FCU-01	FCU Fan Command
BI	1-FCU-01	FCU Fan Status
MC	1-FCU-01	_
AI	1-FCU-01	FCU Zone Temp
AOS	1-FCU-01	FCU Zone Setpoint
MC	1-FCU-01	__
AOS	1-FCU-01	FCU CW Valve
AOS	1-FCU-01	FCU HW Valve
MC	1-FCU-01	___
CS	1-FCU-01	FCU CSO Object
MC	1-FCU-02	FCU Occupied Command
BO	1-FCU-02	FCU Fan Command
BI	1-FCU-02	FCU Fan Status
MC	1-FCU-02	
AI	1-FCU-02	FCU Zone Temp
AOS	1-FCU-02	FCU Zone Setpoint
MC	1-FCU-02	
AOS	1-FCU-02	FCU CW Valve
AOS	1-FCU-02	FCU HW Valve
MC	1-FCU-02	
CS	1-FCU-02	FCU CSO Object

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MC	1-FCU-03	FCU Occupied Command
BO	1-FCU-03	FCU Fan Command
BI	1-FCU-03	FCU Fan Status
MC	1-FCU-03	
AI	1-FCU-03	FCU Zone Temp
AOS	1-FCU-03	FCU Zone Setpoint
MC	1-FCU-03	
AOS	1-FCU-03	FCU CW Valve
AOS	1-FCU-03	FCU HW Valve
MC	1-FCU-03	
CS	1-FCU-03	FCU CSO Object
MC	1-FCU-04	FCU Occupied Command
BO	1-FCU-04	FCU Fan Command
BI	1-FCU-04	FCU Fan Status
MC	1-FCU-04	
AI	1-FCU-04	FCU Zone Temp
AOS	1-FCU-04	FCU Zone Setpoint
MC	1-FCU-04	
AOS	1-FCU-04	FCU CW Valve
AOS	1-FCU-04	FCU HW Valve
MC	1-FCU-04	
CS	1-FCU-04	FCU CSO Object
MC	1-FCU-05	FCU Occupied Command
BO	1-FCU-05	FCU Fan Command
BI	1-FCU-05	FCU Fan Status
MC	1-FCU-05	
AI	1-FCU-05	FCU Zone Temp
AOS	1-FCU-05	FCU Zone Setpoint
MC	1-FCU-05	
AOS	1-FCU-05	FCU CW Valve
AOS	1-FCU-05	FCU HW Valve
MC	1-FCU-05	
CS	1-FCU-05	FCU CSO Object
MSD	16-105	Occupied Command
AI	16-105	Zone Temp
AI	16-105	Zone Setpoint
AI	16-105	Zone Temp
AD	16-105	Supply Air CFM
AD	16-105	Supply Air CFM SP
AD	16-105	Damper Command
BO	16-105	Series Fan Command
AD	16-105	Heating Command
CS	16-105	All Points for 16-105
MSD	16-107	Occupied Command
AI	16-107	Zone Temp
AI	16-107	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	16-107	Zone Temp
AD	16-107	Supply Air CFM
AD	16-107	Supply Air CFM SP
AD	16-107	Damper Command
BO	16-107	Series Fan Command
AD	16-107	Heating Command
CS	16-107	All Points for 16-107
MSD	16-108	Occupied Command
AI	16-108	Zone Temp
AI	16-108	Zone Setpoint
AI	16-108	Zone Temp
AD	16-108	Supply Air CFM
AD	16-108	Supply Air CFM SP
AD	16-108	Damper Command
BO	16-108	Series Fan Command
AD	16-108	Heating Command
CS	16-108	All Points for 16-108
MSD	16-110	Occupied Command
AI	16-110	Zone Temp
AI	16-110	Zone Setpoint
AI	16-110	Zone Temp
AD	16-110	Supply Air CFM
AD	16-110	Supply Air CFM SP
AD	16-110	Damper Command
BO	16-110	Series Fan Command
AD	16-110	Heating Command
CS	16-110	All Points for 16-110
MSD	16-116	Occupied Command
AI	16-116	Zone Temp
AI	16-116	Zone Setpoint
AI	16-116	Discharge Air Temp
AD	16-116	Supply Air CFM
AD	16-116	Supply Air CFM SP
AD	16-116	Damper Command
BO	16-116	Series Fan Command
AD	16-116	Heating Command
CS	16-116	All Points for 16-116
MSD	16-113	Occupied Command
AI	16-113	Zone Temp
AI	16-113	Zone Setpoint
AI	16-113	Zone Temp
AD	16-113	Supply Air CFM
AD	16-113	Supply Air CFM SP
AD	16-113	Damper Command
BO	16-113	Series Fan Command
AD	16-113	Heating Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	16-113	All Points for 16-113
MSD	16-122b	Occupied Command
AI	16-122b	Zone Temp
AI	16-122b	Zone Setpoint
AI	16-122b	Discharge Air Temp
AD	16-122b	Supply Air CFM
AD	16-122b	Supply Air CFM SP
AD	16-122b	Damper Command
BO	16-122b	Series Fan Command
AD	16-122b	Heating Command
CS	16-122b	All Points for 16-122b
MSD	16-122a	Occupied Command
AI	16-122a	Zone Temp
AI	16-122a	Zone Setpoint
AI	16-122a	Zone Temp
AD	16-122a	Supply Air CFM
AD	16-122a	Supply Air CFM SP
AD	16-122a	Damper Command
BO	16-122a	Series Fan Command
AD	16-122a	Heating Command
CS	16-122a	All Points for 16-122a
MSD	16-117	Occupied Command
AI	16-117	Zone Temp
AI	16-117	Zone Setpoint
AI	16-117	Zone Temp
AD	16-117	Supply Air CFM
AD	16-117	Supply Air CFM SP
AD	16-117	Damper Command
BO	16-117	Series Fan Command
AD	16-117	Heating Command
CS	16-117	All Points for 16-117
MSD	16-119	Occupied Command
AI	16-119	Zone Temp
AI	16-119	Zone Setpoint
AI	16-119	Zone Temp
AD	16-119	Supply Air CFM
AD	16-119	Supply Air CFM SP
AD	16-119	Damper Command
BO	16-119	Series Fan Command
AD	16-119	Heating Command
CS	16-119	All Points for 16-119
MSD	16-141a	Occupied Command
AI	16-141a	Zone Temp
AI	16-141a	Zone Setpoint
AI	16-141a	Zone Temp
AD	16-141a	Supply Air CFM

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	16-141a	Supply Air CFM SP
AD	16-141a	Damper Command
BO	16-141a	Series Fan Command
AD	16-141a	Heating Command
CS	16-141a	All Points for 16-141a
MSD	16-141b	Occupied Command
AI	16-141b	Zone Temp
AI	16-141b	Zone Setpoint
AI	16-141b	DA- Temp
AD	16-141b	Supply Air CFM
AD	16-141b	Supply Air CFM SP
AD	16-141b	Damper Command
BO	16-141b	Series Fan Command
AD	16-141b	Heating Command
CS	16-141b	All Points for 16-141A,B
MSD	15-163	Occupied Command
AI	15-163	Zone Temp
AI	15-163	Zone Setpoint
AI	15-163	Disch Air Temp
AD	15-163	Supply Air CFM
AD	15-163	Supply Air CFM SP
AD	15-163	Damper Command
BO	15-163	Series Fan Command
AD	15-163	Heating Command
CS	15-163	All Points for 15-163
MSD	15-162	Occupied Command
AI	15-162	Zone Temp
AI	15-162	Zone Setpoint
AI	15-162	Zone Temp
AD	15-162	Supply Air CFM
AD	15-162	Supply Air CFM SP
AD	15-162	Damper Command
BO	15-162	Series Fan Command
AD	15-162	Heating Command
CS	15-162	All Points for 15-162
MSD	15-160	Occupied Command
AI	15-160	Zone Temp
AI	15-160	Zone Setpoint
AI	15-160	Zone Temp
AD	15-160	Supply Air CFM
AD	15-160	Supply Air CFM SP
AD	15-160	Damper Command
BO	15-160	Series Fan Command
AD	15-160	Heating Command
CS	15-160	All Points for 15-160
MSD	15-153a	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	15-153a	Zone Temp
AI	15-153a	Zone Setpoint
AI	15-153a	DA Temp
AD	15-153a	Supply Air CFM
AD	15-153a	Supply Air CFM SP
AD	15-153a	Damper Command
BO	15-153a	Series Fan Command
AD	15-153a	Heating Command
CS	15-153a	All Points for 15-153a
MSD	15-153b	Occupied Command
AI	15-153b	Zone Temp
AI	15-153b	Zone Setpoint
AI	15-153b	DA Temp
AD	15-153b	Supply Air CFM
AD	15-153b	Supply Air CFM SP
AD	15-153b	Damper Command
BO	15-153b	Series Fan Command
AD	15-153b	Heating Command
CS	15-153b	All Points for 15-153b
MSD	15-149	Occupied Command
AI	15-149	Zone Temp
AI	15-149	Zone Setpoint
AI	15-149	DA Temp
AD	15-149	Supply Air CFM
AD	15-149	Supply Air CFM SP
AD	15-149	Damper Command
BO	15-149	Series Fan Command
AD	15-149	Heating Command
CS	15-149	All Points for 15-149
MSD	15-152	Occupied Command
AI	15-152	Zone Temp
AI	15-152	Zone Setpoint
AI	15-152	DA Temp
AD	15-152	Supply Air CFM
AD	15-152	Supply Air CFM SP
AD	15-152	Damper Command
BO	15-152	Series Fan Command
AD	15-152	Heating Command
CS	15-152	All Points for 15-152
MSD	15-148	Occupied Command
AI	15-148	Zone Temp
AI	15-148	Zone Setpoint
AI	15-148	DA Temp
AD	15-148	Supply Air CFM
AD	15-148	Supply Air CFM SP
AD	15-148	Damper Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	15-148	Series Fan Command
AD	15-148	Heating Command
CS	15-148	All Points for 15-148
MSD	15-145	Occupied Command
AI	15-145	Zone Temp
AI	15-145	Zone Setpoint
AI	15-145	Disch Air Temp
AD	15-145	Supply Air CFM
AD	15-145	Supply Air CFM SP
AD	15-145	Damper Command
BO	15-145	Series Fan Command
AD	15-145	Heating Command
CS	15-145	All Points for 15-145
MSD	15-129	Occupied Command
AI	15-129	Zone Temp
AI	15-129	Zone Setpoint
AI	15-129	Disch Air Temp
AD	15-129	Supply Air CFM
AD	15-129	Supply Air CFM SP
AD	15-129	Damper Command
BO	15-129	Series Fan Command
AD	15-129	Heating Command
CS	15-129	All Points for 15-129
MSD	15-131	Occupied Command
AI	15-131	Zone Temp
AI	15-131	Zone Setpoint
AI	15-131	Disch Air Temp
AD	15-131	Supply Air CFM
AD	15-131	Supply Air CFM SP
AD	15-131	Damper Command
BO	15-131	Series Fan Command
AD	15-131	Heating Command
CS	15-131	All Points for 15-131
MSD	15-133	Occupied Command
AI	15-133	Zone Temp
AI	15-133	Zone Setpoint
AI	15-133	Disch Air Temp
AD	15-133	Supply Air CFM
AD	15-133	Supply Air CFM SP
AD	15-133	Damper Command
BO	15-133	Series Fan Command
AD	15-133	Heating Command
CS	15-133	All Points for 15-133
MSD	15-136	Occupied Command
AI	15-136	Zone Temp
AI	15-136	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	15-136	Disch Air Temp
AD	15-136	Supply Air CFM
AD	15-136	Supply Air CFM SP
AD	15-136	Damper Command
BO	15-136	Series Fan Command
AD	15-136	Heating Command
CS	15-136	All Points for 15-136
MSD	15-135	Occupied Command
AI	15-135	Zone Temp
AI	15-135	Zone Setpoint
AI	15-135	Zone Temp
AD	15-135	Supply Air CFM
AD	15-135	Supply Air CFM SP
AD	15-135	Damper Command
BO	15-135	Series Fan Command
AD	15-135	Heating Command
CS	15-135	All Points for 15-135
MSD	15-137	Occupied Command
AI	15-137	Zone Temp
AI	15-137	Zone Setpoint
AI	15-137	Zone Temp
AD	15-137	Supply Air CFM
AD	15-137	Supply Air CFM SP
AD	15-137	Damper Command
BO	15-137	Series Fan Command
AD	15-137	Heating Command
CS	15-137	All Points for 15-137
MSD	15-140	Occupied Command
AI	15-140	Zone Temp
AI	15-140	Zone Setpoint
AI	15-140	Disch Air Temp
AD	15-140	Supply Air CFM
AD	15-140	Supply Air CFM SP
AD	15-140	Damper Command
BO	15-140	Series Fan Command
AD	15-140	Heating Command
CS	15-140	All Points for 15-140
MSD	15-123	Occupied Command
AI	15-123	Zone Temp
AI	15-123	Zone Setpoint
AI	15-123	Zone Temp
AD	15-123	Supply Air CFM
AD	15-123	Supply Air CFM SP
AD	15-123	Damper Command
BO	15-123	Series Fan Command
AD	15-123	Heating Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	15-123	All Points for 15-123
MSD	15-134	Occupied Command
AI	15-134	Zone Temp
AI	15-134	Zone Setpoint
AI	15-134	Zone Temp
AD	15-134	Supply Air CFM
AD	15-134	Supply Air CFM SP
AD	15-134	Damper Command
BO	15-134	Series Fan Command
AD	15-134	Heating Command
CS	15-134	All Points for 15-134
MSD	15-116	Occupied Command
AI	15-116	Zone Temp
AI	15-116	Zone Setpoint
AI	15-116	Zone Temp
AD	15-116	Supply Air CFM
AD	15-116	Supply Air CFM SP
AD	15-116	Damper Command
BO	15-116	Series Fan Command
AD	15-116	Heating Command
CS	15-116	All Points for 15-116
MSD	15-120	Occupied Command
AI	15-120	Zone Temp
AI	15-120	Zone Setpoint
AI	15-120	Zone Temp
AD	15-120	Supply Air CFM
AD	15-120	Supply Air CFM SP
AD	15-120	Damper Command
BO	15-120	Series Fan Command
AD	15-120	Heating Command
CS	15-120	All Points for 15-120
MSD	15-118	Occupied Command
AI	15-118	Zone Temp
AI	15-118	Zone Setpoint
AI	15-118	Zone Temp
AD	15-118	Supply Air CFM
AD	15-118	Supply Air CFM SP
AD	15-118	Damper Command
BO	15-118	Series Fan Command
AD	15-118	Heating Command
CS	15-118	All Points for 15-118
MSD	15-111	Occupied Command
AI	15-111	Zone Temp
AI	15-111	Zone Setpoint
AI	15-111	Zone Temp
AD	15-111	Supply Air CFM

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	15-111	Supply Air CFM SP
AD	15-111	Damper Command
BO	15-111	Series Fan Command
AD	15-111	Heating Command
CS	15-111	All Points for 15-111
MSD	15-102	Occupied Command
AI	15-102	Zone Temp
AI	15-102	Zone Setpoint
AI	15-102	Zone Temp
AD	15-102	Supply Air CFM
AD	15-102	Supply Air CFM SP
AD	15-102	Damper Command
BO	15-102	Series Fan Command
AD	15-102	Heating Command
CS	15-102	All Points for 15-102
MSD	15-106	Occupied Command
AI	15-106	Zone Temp
AI	15-106	Zone Setpoint
AI	15-106	Zone Temp
AD	15-106	Supply Air CFM
AD	15-106	Supply Air CFM SP
AD	15-106	Damper Command
BO	15-106	Series Fan Command
AD	15-106	Heating Command
CS	15-106	All Points for 15-106
MSD	15-101	Occupied Command
AI	15-101	Zone Temp
AI	15-101	Zone Setpoint
AI	15-101	Zone Temp
AD	15-101	Supply Air CFM
AD	15-101	Supply Air CFM SP
AD	15-101	Damper Command
BO	15-101	Series Fan Command
AD	15-101	Heating Command
CS	15-101	All Points for 15-101
MSD	15-168	Occupied Command
AI	15-168	Zone Temp
AI	15-168	Zone Setpoint
AI	15-168	Discharge Air Temp
AD	15-168	Supply Air CFM
AD	15-168	Supply Air CFM SP
AD	15-168	Damper Command
BO	15-168	Series Fan Command
AD	15-168	Heating Command
CS	15-168	All Points for 15-168
	Building 3	

DRAFT

	Building 3	
Point	**Equipment**	**Type**
point	Equipment	type
	NC-11	Network controller
NC11-HRW	VAV@1 - 25-109	1, 1, 3, VMA
NC11-HRW	VAV@2 - 25-104	2, 1, 3, VMA
NC11-HRW	VAV@3 - 25-106	3, 1, 3, VMA
NC11-HRW	VAV@4 - 25-117	4, 1, 3, VMA
NC11-HRW	VAV@5 - 25-118	5, 1, 3, VMA
NC11-HRW	VAV@6 - 25-119	6, 1, 3, VMA
NC11-HRW	VAV@7 - 25-121	7, 1, 3, VMA
NC11-HRW	VAV@8 - 25-122	8, 1, 3, VMA
NC11-HRW	VAV@9 - 25-123	9, 1, 3, VMA
NC11-HRW	VAV@10 - 25-130	10, 1, 3, VMA
NC11-HRW	VAV@11 - 25-133	11, 1, 3, VMA
NC11-HRW	VAV@12 - 25-134	12, 1, 3, VMA
NC11-HRW	VAV@14 - 25-135	14, 1, 3, VMA
NC11-HRW	VAV@15 - 25-136	15, 1, 3, VMA
NC11-HRW	VAV@16 - 25-137	16, 1, 3, VMA
NC11-HRW	VAV@17 - 26-141	17, 1, 3, VMA
NC11-HRW	VAV@18 - 26-139	18, 1, 3, VMA
NC11-HRW	VAV@19 - 26-139A	19, 1, 3, VMA
NC11-HRW	VAV@20 - 26-136	20, 1, 3, VMA
NC11-HRW	VAV@21 - 26-129	21, 1, 3, VMA
NC11-HRW	VAV@22 - 26-132	22, 1, 3, VMA
NC11-HRW	VAV@26 - 26-124	26, 1, 3, VMA
NC11-HRW	VAV@25 - 26-125	25, 1, 3, VMA
NC11-HRW	VAV@24 - 26-126	24, 1, 3, VMA
NC11-HRW	VAV@23 - 26-127	23, 1, 3, VMA
NC11-HRW	VAV@27 - 26-119	27, 1, 3, VMA
NC11-HRW	VAV@28 - 26-135	28, 1, 3, VMA
NC11-HRW	VAV@29 - 26-118	29, 1, 3, VMA
NC11-HRW	VAV@30 - 26-123	30, 1, 3, VMA
NC11-HRW	VAV@31 - 26-112	31, 1, 3, VMA
NC11-HRW	VAV@32 - 22-107	32, 1, 3, VMA
NC11-HRW	VAV@34 - 22-167	34, 1, 3, VMA
NC11-HRW	VAV@35 - 22-189	35, 1, 3, VMA
NC11-HRW	VAV@36 - 22-186	36, 1, 3, VMA
NC11-HRW	VAV@37 - 22-155	37, 1, 3, VMA
NC11-HRW	VAV@38 - 22-165	38, 1, 3, VMA
NC11-HRW	VAV@39 - 22-179	39, 1, 3, VMA
NC11-HRW	VAV@40 - 22-178	40, 1, 3, VMA
NC11-HRW	VAV@41 - 22-161	41, 1, 3, VMA
NC11-HRW	VAV@42 - 22-192	42, 1, 3, VMA
NC11-HRW	VAV@43 - 22-157	43, 1, 3, VMA
NC11-HRW	VAV@44 - 22-150	44, 1, 3, VMA
NC11-HRW	VAV@45 - 22-148	45, 1, 3, VMA
NC11-HRW	VAV@46 - 24-107	46, 1, 3, VMA

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC11-HRW	VAV@47 - 24-107A	47, 1, 3, VMA
NC11-HRW	VAV@48 - 24-108	48, 1, 3, VMA
NC11-HRW	VAV@49 - 22-117	49, 1, 3, VMA
NC11-HRW	VAV@50 - 22-117A	50, 1, 3, VMA
NC11-HRW	VAV@51 - 22-122	51, 1, 3, VMA
NC11-HRW	VAV@52 - 22-106	52, 1, 3, VMA
DCDR	NC11-HRW	13, 1, 3, XTM
NC11-HRW	EF 1G,2E,2F Chapel	55, 1, 3, UNT
NC11-HRW	VAV2.1-25-104B	56, 1, 3, VMA
MSD	26-132	Occupied Command
AI	26-132	Zone Temp
AI	26-132	Zone Setpoint
AI	26-132	Disch Air Temp (No Heat)
AD	26-132	Supply Air CFM
AD	26-132	Supply Air CFM SP
AD	26-132	Damper Command
BO	26-132	Series Fan Command
CS	26-132	All Points for 26-132
MSD	25-104B	Occupied Status
AI	25-104B	Zone Temp
AI	25-104B	Zone Setpoint
AI	25-104B	Discharge Air Temp
AD	25-104B	Supply Air CFM
AD	25-104B	Supply Air CFM Setpoint
AD	25-104B	Damper Command
BO	25-104B	Series Fan Command
AD	25-104B	Heating Command
CS	25-104B	All Points for 25-104B
BO	EX-Fans4	EF 1D Start/Stop
BI	EX-Fans4	EF 1D Fan Status
MC	EX-Fans4	
BO	EX-Fans4	EF 1E Start/Stop
BI	EX-Fans4	EF 1E Fan Status
MC	EX-Fans4	
BO	EX-Fans4	EF 1F Start/Stop
BI	EX-Fans4	EF 1F Fan Status
MC	EX-Fans4	
BO	EX-Fans4	EF 2C Start/Stop
BI	EX-Fans4	EF 1C Fan Status
MC	EX-Fans4	
BO	EX-Fans4	EF 2D Start/Stop
BI	EX-Fans4	EF 2D Fan Status
BO	EX-Fans3	EF 1G Start/Stop
BI	EX-Fans3	EF 1G Fan Status
MC	EX-Fans3	
BO	EX-Fans3	EF 2E Start/Stop

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	EX-Fans3	EF 2E Fan Status
MC	EX-Fans3	
BO	EX-Fans3	EF 2F Start/Stop
BI	EX-Fans3	EF 2F Fan Status
MSD	22-106	Occupied Command
AI	22-106	Zone Temp
AI	22-106	Zone Setpoint
AI	22-106	Discharge Air Temp
AD	22-106	Supply Air CFM
AD	22-106	Supply Air CFM SP
AD	22-106	Damper Command
BO	22-106	Series Fan Command
AD	22-106	Heating Command
CS	22-106	All Points for 22-106
MSD	22-122	Occupied Command
AI	22-122	Zone Temp
AI	22-122	Zone Setpoint
AI	22-122	Discharge Air Temp
AD	22-122	Supply Air CFM
AD	22-122	Supply Air CFM SP
AD	22-122	Damper Command
BO	22-122	Series Fan Command
AD	22-122	Heating Command
CS	22-122	All Points for 22-122
MSD	22-117A	Occupied Command
AI	22-117A	Zone Temp
AI	22-117A	Zone Setpoint
AI	22-117A	Discharge Air Temp
AD	22-117A	Supply Air CFM
AD	22-117A	Supply Air CFM SP
AD	22-117A	Damper Command
BO	22-117A	Series Fan Command
AD	22-117A	Heating Command
CS	22-117A	All Points for 22-117A
MSD	22-117	Occupied Command
AI	22-117	Zone Temp
AI	22-117	Zone Setpoint
AI	22-117	Discharge Air Temp
AD	22-117	Supply Air CFM
AD	22-117	Supply Air CFM SP
AD	22-117	Damper Command
BO	22-117	Series Fan Command
AD	22-117	Heating Command
CS	22-117	All Points for 22-117
MSD	24-108	Occupied Command
AI	24-108	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	24-108	Zone Setpoint
AI	24-108	Discharge Air Temp
AD	24-108	Supply Air CFM
AD	24-108	Supply Air CFM SP
AD	24-108	Damper Command
BO	24-108	Series Fan Command
AD	24-108	Heating Command
CS	24-108	All Points for 24-108
MSD	24-107A	Occupied Command
AI	24-107A	Zone Temp
AI	24-107A	Zone Setpoint
AI	24-107A	Discharge Air Temp
AD	24-107A	Supply Air CFM
AD	24-107A	Supply Air CFM SP
AD	24-107A	Damper Command
BO	24-107A	Series Fan Command
AD	24-107A	Heating Command
CS	24-107A	All Points for 24-107A
MSD	22-148	Occupied Command
AI	22-148	Zone Temp
AI	22-148	Zone Setpoint
AI	22-148	Discharge Air Temp
AD	22-148	Supply Air CFM
AD	22-148	Supply Air CFM SP
AD	22-148	Damper Command
BO	22-148	Series Fan Command
AD	22-148	Heating Command
CS	22-148	All Points for 22-148
MSD	22-150	Occupied Command
AI	22-150	Zone Temp
AI	22-150	Zone Setpoint
AI	22-150	Discharge Air Temp
AD	22-150	Supply Air CFM
AD	22-150	Supply Air CFM SP
AD	22-150	Damper Command
BO	22-150	Series Fan Command
AD	22-150	Heating Command
CS	22-150	All Points for 22-150
MSD	22-157	Occupied Command
AI	22-157	Zone Temp
AI	22-157	Zone Setpoint
AI	22-157	Discharge Air Temp
AD	22-157	Supply Air CFM
AD	22-157	Supply Air CFM SP
AD	22-157	Damper Command
BO	22-157	Series Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	22-157	Heating Command
CS	22-157	All Points for 22-157
MSD	22-192	Occupied Command
AI	22-192	Zone Temp
AI	22-192	Zone Setpoint
AI	22-192	Discharge Air Temp
AD	22-192	Supply Air CFM
AD	22-192	Supply Air CFM SP
AD	22-192	Damper Command
BO	22-192	Series Fan Command
AD	22-192	Heating Command
CS	22-192	All Points for 22-192
MSD	22-161	Occupied Command
AI	22-161	Zone Temp
AI	22-161	Zone Setpoint
AI	22-161	Discharge Air Temp
AD	22-161	Supply Air CFM
AD	22-161	Supply Air CFM SP
AD	22-161	Damper Command
BO	22-161	Series Fan Command
AD	22-161	Heating Command
CS	22-161	All Points for 22-161
MSD	22-178	Occupied Command
AI	22-178	Zone Temp
AI	22-178	Zone Setpoint
AI	22-178	Discharge Air Temp
AD	22-178	Supply Air CFM
AD	22-178	Supply Air CFM SP
AD	22-178	Damper Command
BO	22-178	Series Fan Command
AD	22-178	Heating Command
CS	22-178	All Points for 22-178
MSD	22-179	Occupied Command
AI	22-179	Zone Temp
AI	22-179	Zone Setpoint
AI	22-179	Discharge Air Temp
AD	22-179	Supply Air CFM
AD	22-179	Supply Air CFM SP
AD	22-179	Damper Command
BO	22-179	Series Fan Command
AD	22-179	Heating Command
CS	22-179	All Points for 22-179
MSD	22-165	Occupied Command
AI	22-165	Zone Temp
AI	22-165	Zone Setpoint
AI	22-165	Discharge Air Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	22-165	Supply Air CFM
AD	22-165	Supply Air CFM SP
AD	22-165	Damper Command
BO	22-165	Series Fan Command
AD	22-165	Heating Command
CS	22-165	All Points for 22-165
MSD	22-155	Occupied Command
AI	22-155	Zone Temp
AI	22-155	Zone Setpoint
AI	22-155	Discharge Air Temp
AD	22-155	Supply Air CFM
AD	22-155	Supply Air CFM SP
AD	22-155	Damper Command
BO	22-155	Series Fan Command
AD	22-155	Heating Command
CS	22-155	All Points for 22-155
MSD	22-186	Occupied Command
AI	22-186	Zone Temp
AI	22-186	Zone Setpoint
AI	22-186	Discharge Air Temp
AD	22-186	Supply Air CFM
AD	22-186	Supply Air CFM SP
AD	22-186	Damper Command
BO	22-186	Series Fan Command
AD	22-186	Heating Command
CS	22-186	All Points for 22-186
MSD	22-189	Occupied Command
AI	22-189	Zone Temp
AI	22-189	Zone Setpoint
AI	22-189	Discharge Air Temp
AD	22-189	Supply Air CFM
AD	22-189	Supply Air CFM SP
AD	22-189	Damper Command
BO	22-189	Series Fan Command
AD	22-189	Heating Command
CS	22-189	All Points for 22-189
MSD	22-167	Occupied Command
AI	22-167	Zone Temp
AI	22-167	Zone Setpoint
AI	22-167	Discharge Air Temp
AD	22-167	Supply Air CFM
AD	22-167	Supply Air CFM SP
AD	22-167	Damper Command
BO	22-167	Series Fan Command
AD	22-167	Heating Command
CS	22-167	All Points for 22-167

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MSD	22-107	Occupied Command
AI	22-107	Zone Temp
AI	22-107	Zone Setpoint
AI	22-107	Discharge Air Temp
AD	22-107	Supply Air CFM
AD	22-107	Supply Air CFM SP
AD	22-107	Damper Command
BO	22-107	Series Fan Command
AD	22-107	Heating Command
CS	22-107	All Points for 22-107
MSD	26-112	Occupied Command
AI	26-112	Zone Temp
AI	26-112	Zone Setpoint
AI	26-112	Discharge Air Temp
AD	26-112	Supply Air CFM
AD	26-112	Supply Air CFM SP
AD	26-112	Damper Command
BO	26-112	Series Fan Command
AD	26-112	Heating Command
CS	26-112	All Points for 26-112
MSD	26-123	Occupied Command
AI	26-123	Zone Temp
AI	26-123	Zone Setpoint
AI	26-123	Discharge Air Temp
AD	26-123	Supply Air CFM
AD	26-123	Supply Air CFM SP
AD	26-123	Damper Command
BO	26-123	Series Fan Command
AD	26-123	Heating Command
CS	26-123	All Points for 26-123
MSD	26-118	Occupied Command
AI	26-118	Zone Temp
AI	26-118	Zone Setpoint
AI	26-118	Discharge Air Temp
AD	26-118	Supply Air CFM
AD	26-118	Supply Air CFM SP
AD	26-118	Damper Command
BO	26-118	Series Fan Command
AD	26-118	Heating Command
CS	26-118	All Points for 26-118
MSD	26-135	Occupied Command
AI	26-135	Zone Temp
AI	26-135	Zone Setpoint
AI	26-135	Discharge Air Temp
AD	26-135	Supply Air CFM
AD	26-135	Supply Air CFM SP

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	26-135	Damper Command
BO	26-135	Series Fan Command
AD	26-135	Heating Command
CS	26-135	All Points for 26-135
MSD	26-119	Occupied Command
AI	26-119	Zone Temp
AI	26-119	Zone Setpoint
AI	26-119	Discharge Air Temp
AD	26-119	Supply Air CFM
AD	26-119	Supply Air CFM SP
AD	26-119	Damper Command
BO	26-119	Series Fan Command
AD	26-119	Heating Command
CS	26-119	All Points for 26-119
MSD	26-127	Occupied Command
AI	26-127	Zone Temp
AI	26-127	Zone Setpoint
AI	26-127	Discharge Air Temp
AD	26-127	Supply Air CFM
AD	26-127	Supply Air CFM SP
AD	26-127	Damper Command
BO	26-127	Series Fan Command
AD	26-127	Heating Command
CS	26-127	All Points for 26-127
MSD	26-126	Occupied Command
AI	26-126	Zone Temp
AI	26-126	Zone Setpoint
AI	26-126	Discharge Air Temp
AD	26-126	Supply Air CFM
AD	26-126	Supply Air CFM SP
AD	26-126	Damper Command
BO	26-126	Series Fan Command
AD	26-126	Heating Command
CS	26-126	All Points for 26-126
MSD	26-125	Occupied Command
AI	26-125	Zone Temp
AI	26-125	Zone Setpoint
AI	26-125	Discharge Air Temp
AD	26-125	Supply Air CFM
AD	26-125	Supply Air CFM SP
AD	26-125	Damper Command
BO	26-125	Series Fan Command
AD	26-125	Heating Command
CS	26-125	All Points for 26-125
MSD	26-124	Occupied Command
AI	26-124	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	26-124	Zone Setpoint
AI	26-124	Discharge Air Temp
AD	26-124	Supply Air CFM
AD	26-124	Supply Air CFM SP
AD	26-124	Damper Command
BO	26-124	Series Fan Command
AD	26-124	Heating Command
CS	26-124	All Points for 26-124
MSD	26-129	Occupied Command
AI	26-129	Zone Temp
AI	26-129	Zone Setpoint
AI	26-129	Discharge Air Temp
AD	26-129	Supply Air CFM
AD	26-129	Supply Air CFM SP
AD	26-129	Damper Command
BO	26-129	Series Fan Command
AD	26-129	Heating Command
CS	26-129	All Points for 26-129
MSD	26-136	Occupied Command
AI	26-136	Zone Temp
AI	26-136	Zone Setpoint
AI	26-136	Discharge Air Temp
AD	26-136	Supply Air CFM
AD	26-136	Supply Air CFM SP
AD	26-136	Damper Command
BO	26-136	Series Fan Command
AD	26-136	Heating Command
CS	26-136	All Points for 26-136
MSD	26-139A	Occupied Command
AI	26-139A	Zone Temp
AI	26-139A	Zone Setpoint
AI	26-139A	Discharge Air Temp
AD	26-139A	Supply Air CFM
AD	26-139A	Supply Air CFM SP
AD	26-139A	Damper Command
BO	26-139A	Series Fan Command
AD	26-139A	Heating Command
CS	26-139A	All Points for 26-139A
MSD	26-139	Occupied Command
AI	26-139	Zone Temp
AI	26-139	Zone Setpoint
AI	26-139	Discharge Air Temp
AD	26-139	Supply Air CFM
AD	26-139	Supply Air CFM SP
AD	26-139	Damper Command
BO	26-139	Series Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	26-139	Heating Command
CS	26-139	All Points for 26-139
MSD	26-141	Occupied Command
AI	26-141	Zone Temp
AI	26-141	Zone Setpoint
AI	26-141	Discharge Air Temp
AD	26-141	Supply Air CFM
AD	26-141	Supply Air CFM SP
AD	26-141	Damper Command
BO	26-141	Series Fan Command
AD	26-141	Heating Command
CS	26-141	All Points for 26-141
MSD	25-137	Occupied Command
AI	25-137	Zone Temp
AI	25-137	Zone Setpoint
AI	25-137	Discharge Air Temp
AD	25-137	Supply Air CFM
AD	25-137	Supply Air CFM SP
AD	25-137	Damper Command
BO	25-137	Series Fan Command
AD	25-137	Heating Command
CS	25-137	All Points for 25-137
MSD	25-136	Occupied Command
AI	25-136	Zone Temp
AI	25-136	Zone Setpoint
AI	25-136	Discharge Air Temp
AD	25-136	Supply Air CFM
AD	25-136	Supply Air CFM SP
AD	25-136	Damper Command
BO	25-136	Series Fan Command
AD	25-136	Heating Command
CS	25-136	All Points for 25-136
MSD	25-135	Occupied Command
AI	25-135	Zone Temp
AI	25-135	Zone Setpoint
AI	25-135	Discharge Air Temp
AD	25-135	Supply Air CFM
AD	25-135	Supply Air CFM SP
AD	25-135	Damper Command
BO	25-135	Series Fan Command
AD	25-135	Heating Command
CS	25-135	All Points for 25-135
MSD	25-134	Occupied Command
AI	25-134	Zone Temp
AI	25-134	Zone Setpoint
AI	25-134	Discharge Air Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	25-134	Supply Air CFM
AD	25-134	Supply Air CFM SP
AD	25-134	Damper Command
BO	25-134	Series Fan Command
AD	25-134	Heating Command
CS	25-134	All Points for 25-134
MSD	25-133	Occupied Command
AI	25-133	Zone Temp
AI	25-133	Zone Setpoint
AI	25-133	Discharge Air Temp
AD	25-133	Supply Air CFM
AD	25-133	Supply Air CFM SP
AD	25-133	Damper Command
BO	25-133	Series Fan Command
AD	25-133	Heating Command
CS	25-133	All Points for 25-133
MSD	25-130	Occupied Command
AI	25-130	Zone Temp
AI	25-130	Zone Setpoint
AI	25-130	Discharge Air Temp
AD	25-130	Supply Air CFM
AD	25-130	Supply Air CFM SP
AD	25-130	Damper Command
BO	25-130	Series Fan Command
AD	25-130	Heating Command
CS	25-130	All Points for 25-130
MSD	25-123	Occupied Command
AI	25-123	Zone Temp
AI	25-123	Zone Setpoint
AI	25-123	Discharge Air Temp
AD	25-123	Supply Air CFM
AD	25-123	Supply Air CFM SP
AD	25-123	Damper Command
BO	25-123	Series Fan Command
AD	25-123	Heating Command
CS	25-123	All Points for 25-123
MSD	25-122	Occupied Command
AI	25-122	Zone Temp
AI	25-122	Zone Setpoint
AI	25-122	Discharge Air Temp
AD	25-122	Supply Air CFM
AD	25-122	Supply Air CFM SP
AD	25-122	Damper Command
BO	25-122	Series Fan Command
AD	25-122	Heating Command
CS	25-122	All Points for 25-122

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MSD	25-121	Occupied Command
AI	25-121	Zone Temp
AI	25-121	Zone Setpoint
AI	25-121	Discharge Air Temp
AD	25-121	Supply Air CFM
AD	25-121	Supply Air CFM SP
AD	25-121	Damper Command
BO	25-121	Series Fan Command
AD	25-121	Heating Command
CS	25-121	All Points for 25-121
MSD	25-119	Occupied Command
AI	25-119	Zone Temp
AI	25-119	Zone Setpoint
AI	25-119	Discharge Air Temp
AD	25-119	Supply Air CFM
AD	25-119	Supply Air CFM SP
AD	25-119	Damper Command
BO	25-119	Series Fan Command
AD	25-119	Heating Command
CS	25-119	All Points for 25-119
MSD	25-118	Occupied Command
AI	25-118	Zone Temp
AI	25-118	Zone Setpoint
AI	25-118	Discharge Air Temp
AD	25-118	Supply Air CFM
AD	25-118	Supply Air CFM SP
AD	25-118	Damper Command
BO	25-118	Series Fan Command
AD	25-118	Heating Command
CS	25-118	All Points for 25-118
MSD	25-117	Occupied Command
AI	25-117	Zone Temp
AI	25-117	Zone Setpoint
AI	25-117	Discharge Air Temp
AD	25-117	Supply Air CFM
AD	25-117	Supply Air CFM SP
AD	25-117	Damper Command
BO	25-117	Series Fan Command
AD	25-117	Heating Command
CS	25-117	All Points for 25-117
MSD	25-106	Occupied Command
AI	25-106	Zone Temp
AI	25-106	Zone Setpoint
AI	25-106	Discharge Air Temp
AD	25-106	Supply Air CFM
AD	25-106	Supply Air CFM SP

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	25-106	Damper Command
BO	25-106	Series Fan Command
AD	25-106	Heating Command
CS	25-106	All Points for 25-106
MSD	25-104	Occupied Command
AI	25-104	Zone Temp
AI	25-104	Zone Setpoint
AI	25-104	Discharge NOT INSTALLED
AD	25-104	Supply Air CFM
AD	25-104	Supply Air CFM SP
AD	25-104	Damper Command
BO	25-104	Series Fan Command
AD	25-104	Heating Command
CS	25-104	All Points for 25-104
MSD	25-109	Occupied Command
AI	25-109	Zone Temp
AI	25-109	Zone Setpoint
AI	25-109	Discharge Air Temp
AD	25-109	Supply Air CFM
AD	25-109	Supply Air CFM SP
AD	25-109	Damper Command
BO	25-109	Series Fan Command
AD	25-109	Heating Command
CS	25-109	All Points for 25-109
AI	24-107	Zone Temp
AI	24-107	Zone Setpoint
AI	24-107	Discharge Air Temp
CS	24-107	All Points for 24-107
MSD	24-107	Occupied Command
BO	24-107	Series Fan Command
AD	24-107	Heating Command
AD	24-107	Supply Air CFM
	Building 3	
Point	Equipment	type
	NC-12	Network controller
NC12-HRW	VAV@53 - 22-121	53, 1, 3, VMA
NC12-HRW	VAV@54 - 22-129	54, 1, 3, VMA
NC12-HRW	VAV@55 - 22-112	55, 1, 3, VMA
NC12-HRW	VAV@56 - 22-130	56, 1, 3, VMA
NC12-HRW	VAV@57 - 22-185	57, 1, 3, VMA
NC12-HRW	VAV@58 - 22-184	58, 1, 3, VMA
NC12-HRW	VAV@59 - 22-183	59, 1, 3, VMA
NC12-HRW	VAV@60 - 21-139	60, 1, 3, VMA
NC12-HRW	VAV@61 - 21-127	61, 1, 3, VMA
NC12-HRW	VAV@62 - 21-138	62, 1, 3, VMA

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC12-HRW	VAV@63 - 21-135	63, 1, 3, VMA
NC12-HRW	VAV@64 - 21-134	64, 1, 3, VMA
NC12-HRW	VAV@65 - 21-133	65, 1, 3, VMA
NC12-HRW	VAV@66 - 21-130	66, 1, 3, VMA
NC12-HRW	VAV@67 - 21-122	67, 1, 3, VMA
NC12-HRW	VAV@68 - 21-125	68, 1, 3, VMA
NC12-HRW	VAV@70 - 21-123	70, 1, 3, VMA
NC12-HRW	VAV@71 - 21-124	71, 1, 3, VMA
NC12-HRW	VAV@72 - 21-103	72, 1, 3, VMA
NC12-HRW	VAV@73 - 21-105	73, 1, 3, VMA
NC12-HRW	VAV@74 - 21-104	74, 1, 3, VMA
NC12-HRW	VAV@75 - 21-102	75, 1, 3, VMA
NC12-HRW	VAV@76 - 21-107	76, 1, 3, VMA
NC12-HRW	VAV@78 - 21-112	78, 1, 3, VMA
NC12-HRW	VAV@79 - 21-101	79, 1, 3, VMA
NC12-HRW	VAV@80 - 21-101a	80, 1, 3, VMA
NC12-HRW	VAV@81 - 21-ad81	81, 1, 3, VMA
NC12-HRW	VAV@82 - XA-117	82, 1, 3, VMA
NC12-HRW	VAV@83 - XA-107	83, 1, 3, VMA
NC12-HRW	VAV@84 - XA-110	84, 1, 3, VMA
NC12-HRW	VAV@85 - XA-106a	85, 1, 3, VMA
NC12-HRW	VAV@86 - XA-106b	86, 1, 3, VMA
NC12-HRW	VAV@87 - XA-106c	87, 1, 3, VMA
NC12-HRW	VAV@88 - XA-106d	88, 1, 3, VMA
NC12-HRW	VAV@89 - XA-106e	89, 1, 3, VMA
NC12-HRW	VAV@90 - XA-106f	90, 1, 3, VMA
NC12-HRW	VAV@92 - XA-107a	92, 1, 3, VMA
NC12-HRW	VAV@93 - 21-107a	93, 1, 3, VMA
NC12-HRW	VAV@94 - XA-100	94, 1, 3, VMA
NC12-HRW	VAV@95 - XA-104a	95, 1, 3, VMA
NC12-HRW	VAV@96 - XA-105	96, 1, 3, VMA
NC12-HRW	VAV@97 - XA-104b	97, 1, 3, VMA
NC12-HRW	VAV@98 - XA-104c	98, 1, 3, VMA
NC12-HRW	VAV@99 - 24-105a	99, 1, 3, VMA
NC12-HRW	VAV@100 - 24-105b	100, 1, 3, VMA
NC12-HRW	VAV@101 - XA-104d	101, 1, 3, VMA
NC12-HRW	VAV@102 - 23-107c	102, 1, 3, VMA
NC12-HRW	VAV@103 - XA-101	103, 1, 3, VMA
NC12-HRW	VAV@104 - XA-104e	104, 1, 3, VMA
NC12-HRW	EF 1A-1B-2B UNT 69	69, 1, 3, UNT
NC12-HRW	EF X4,5,6 an 2G VAV 120	120, 1, 3, VAV
NC12-HRW	ACC1 n2=150 VAV	150, 1, 3, VAV
NC12-HRW	ACC1 n2=156 UNT	156, 1, 3, UNT
NC12-HRW	Liebert Unit 1	152, 1, 3, MIG
NC12-HRW	Liebert Unit 2	153, 1, 3, MIG
NC12-HRW	Liebert Unit 3	154, 1, 3, MIG

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC12-HRW	MID Liebert @155 UNT	155, 1, 3, UNT
NC12-HRW	3C-FC301	1, 1, 3, VAV
NC12-HRW	3C-FC302	2, 1, 3, VAV
NC12-HRW	3C-FC303	3, 1, 3, VAV
NC12-HRW	3C-FC304	4, 1, 3, VAV
NC12-HRW	3C-FC305	5, 1, 3, VAV
NC12-HRW	3C-FC306	6, 1, 3, VAV
NC12-HRW	3C-FC307	7, 1, 3, VAV
NC12-HRW	3C-FC308	8, 1, 3, VAV
NC12-HRW	3C-FC309	9, 1, 3, VAV
NC12-HRW	3C-FC310	10, 1, 3, VAV
NC12-HRW	3C-FC311	11, 1, 3, VAV
NC12-HRW	3C-FC312	12, 1, 3, VAV
NC12-HRW	3C-FC313	13, 1, 3, VAV
NC12-HRW	3C-FC314	14, 1, 3, VAV
NC12-HRW	3C-FC315	15, 1, 3, VAV
NC12-HRW	3C-FC316	16, 1, 3, VAV
NC12-HRW	3C-FC317	17, 1, 3, VAV
NC12-HRW	3C-FC318	18, 1, 3, VAV
NC12-HRW	3C-FC319	19, 1, 3, VAV
NC12-HRW	3C-FC320	20, 1, 3, VAV
NC12-HRW	3C-FC321	21, 1, 3, VAV
NC12-HRW	3C-FC322	22, 1, 3, VAV
NC12-HRW	3C-FC323	23, 1, 3, VAV
NC12-HRW	3C-FC324	24, 1, 3, VAV
NC12-HRW	3C-FC325	25, 1, 3, VAV
NC12-HRW	3C-FC326	26, 1, 3, VAV
NC12-HRW	3C-FC327	27, 1, 3, VAV
NC12-HRW	3C-FC328	28, 1, 3, VAV
NC12-HRW	3C-FC329	29, 1, 3, VAV
JCB	JCB-NC12	ACC1
BO	3C-FC305	Occupied Command
AI	3C-FC305	Zone Temp
AI	3C-FC305	Zone Setpoint
AOS	3C-FC305	Heating Valve Command
AOS	3C-FC305	Cooling Valve Command
BO	3C-FC305	Fan Command
BI	3C-FC305	Fan Status
BI	3C-FC305	Pan Alarm Status
CS	3C-FC305	Temp Occ.Status C.S.
BO	3C-FC305	Exhaust Fan 31 Command
BI	3C-FC305	Exhaust Fan 31 Status
BO	3C-FC326	Occupied Command
AI	3C-FC326	Zone Temp
AI	3C-FC326	Zone Setpoint
AOS	3C-FC326	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	3C-FC326	Cooling Valve Command
BO	3C-FC326	Fan Command
BI	3C-FC326	Fan Status
BI	3C-FC326	Pan Alarm Status
CS	3C-FC326	Temp Occ.Status C.S.
BO	3C-FC326	Exhaust Fan 30 Command
BI	3C-FC326	Exhaust Fan 30 Status
BO	3C-FC301	Occupied Command
AI	3C-FC301	Zone Temp
AI	3C-FC301	Zone Setpoint
AOS	3C-FC301	Heating Valve Command
AOS	3C-FC301	Cooling Valve Command
BO	3C-FC301	Fan Command
BI	3C-FC301	Fan Status
BI	3C-FC301	Pan Alarm Status
CS	3C-FC301	Temp Occ.Status C.S.
CS	LIEB-3	CS Liebert Unit #3 Satus
AD	LIEB-3	Room Temperature
AD	LIEB-3	Temperature Setpoint
AD	LIEB-3	Room Humidity
AD	LIEB-3	Humidity Setpoint
BD	LIEB-3	Cooling Enable
BD	LIEB-3	Heating Enable
BD	LIEB-3	Dehumidification Enable
BD	LIEB-3	Humidifier Enable
BD	LIEB-3	HI Temperature Alarm
BD	LIEB-3	LO Temperature Alarm
BD	LIEB-3	HI Humidity Alarm
BD	LIEB-3	LO Humidity Alarm
BI	LIEB-3	Under Floor Detector
CS	LIEB-2	CS Liebert Unit Start#2
AD	LIEB-2	Room Temperature
AD	LIEB-2	Temperature Setpoint
AD	LIEB-2	Room Humidity
AD	LIEB-2	Humidity Setpoint
BD	LIEB-2	Cooling Enable
BD	LIEB-2	Heating Enable
BD	LIEB-2	Dehumidification Enable
BD	LIEB-2	Humidity Enable
BD	LIEB-2	HI Temperature Alarm
BD	LIEB-2	LO Temperature Alarm
BD	LIEB-2	HI Humidity Alarm
BD	LIEB-2	LO Humidity Alarm
BI	LIEB-2	Under Floor Detector
CS	LIEB-1	CS Liebert Unit #1 Stat
AD	LIEB-1	Space Temperature

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	LIEB-1	Temperature Setpoint
AD	LIEB-1	Room Humidity
AD	LIEB-1	Humidity Setpoint
BD	LIEB-1	Cooling Enable
BD	LIEB-1	Heating Enable
BD	LIEB-1	Dehumdification Enable
BD	LIEB-1	Humidity Enable
BD	LIEB-1	HI Temperature Alarm
BD	LIEB-1	LO Temperature Alarm
BD	LIEB-1	HI Humidity Alarm
BD	LIEB-1	LO Humidity Alarm
BI	LIEB-1	Under Floor Detector
BD	ACC1	Reset Backup sequence
BD	ACC1	MainChlrFail
MC	ACC1	
BD	ACC1	RTU Chiller Sequence
BO	ACC1	Change/Over CL=MainChill
BO	ACC1	CRU ACC1 Pmp 11 Command
BI	ACC1	CRU ACC1 Pmp 11 Status
BI	ACC1	ACC1 Chiller Status
BO	ACC1	ACC1 Chiller Command
MC	ACC1	
AI	ACC1	CRU Space Temp
AI	ACC1	CRU Space Humidity
MC	ACC1	
BI	ACC1	CRU ACC1 Alarm
BI	ACC1	CRU 1 Alarm
BI	ACC1	CRU 2 Alarm
BI	ACC1	CRU 3 Alarm
MC	ACC1	
MC	ACC1	
BO	EX-Fans2	EF 1A Start/Stop
BI	EX-Fans2	EF 1A Fan Status
MC	EX-Fans2	
BO	EX-Fans2	EF 1B Start/Stop
BI	EX-Fans2	EF 1B Fan Status
MC	EX-Fans2	
BO	EX-Fans2	EF 2B Start/Stop
BI	EX-Fans2	EF 2B Fan Status
BO	EX-Fans1	Ef X1 Start/Stop XA-104B
BI	EX-Fans1	EF X1 Fan Status
MC	EX-Fans1	
BO	EX-Fans1	EF X2 Start/Stop XA-106A
BI	EX-Fans1	EF X2 Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MC	EX-Fans1	
BO	EX-Fans1	EF X3 Start/Stop XA-106A
BI	EX-Fans1	EF X3 Fan Status
MC	EX-Fans1	
BO	EX-Fans1	EF X4 Start/Stop
BI	EX-Fans1	EF X4 Fan Status
MC	EX-Fans1	
BO	EX-Fans1	EF X5 Start/Stop
BI	EX-Fans1	EF X5 Fan Status
MC	EX-Fans1	
BO	EX-Fans1	EF X6 Start/Stop
BI	EX-Fans1	EF X6 Fan Status
MC	EX-Fans1	
BO	EX-Fans1	EF 1c Start/Stop XA-106e
BI	EX-Fans1	EF 1C Fan Status
MC	EX-Fans1	
BO	EX-Fans1	EF 2A Start/Stop XA-106e
BI	EX-Fans1	EF 2A Fan Status
MC	EX-Fans1	
BO	EX-Fans1	EF 1J Start/Stop XA-106C
BI	EX-Fans1	EF 1J Fan Status
BO	EX-Fans1	EF 2G Start/Stop
BI	EX-Fans1	EF 2G Fan Status
MSD	XA-106c	Occupied Command
AI	XA-106c	Zone Temp
AI	XA-106c	Zone Setpoint
AI	XA-106c	Discharge Air Temp
AD	XA-106c	Supply Air CFM
AD	XA-106c	Supply Air CFM SP
AD	XA-106c	Damper Command
BO	XA-106c	Series Fan Command
AD	XA-106c	Heating Command
CS	XA-106c	All Points for XA-106c
MSD	XA-104b	Occupied Command
AI	XA-104b	Zone Temp
AI	XA-104b	Zone Setpoint
AI	XA-104b	Discharge Air Temp
AD	XA-104b	Supply Air CFM
AD	XA-104b	Supply Air CFM SP
AD	XA-104b	Damper Command
BO	XA-104b	Series Fan Command
AD	XA-104b	Heating Command
CS	XA-104b	All Points for xa-104b
MSD	XA-106a	Occupied Command
AI	XA-106a	Zone Temp
AI	XA-106a	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	XA-106a	Discharge Air Temp
AD	XA-106a	Supply Air CFM
AD	XA-106a	Supply Air CFM SP
AD	XA-106a	Damper Command
BO	XA-106a	Series Fan Command
AD	XA-106a	Heating Command
CS	XA-106a	All Points for XA-106a
MSD	XA-106e	Occupied Command
AI	XA-106e	Zone Temp
AI	XA-106e	Zone Setpoint
AI	XA-106e	Discharge Air Temp
AD	XA-106e	Supply Air CFM
AD	XA-106e	Supply Air CFM SP
AD	XA-106e	Damper Command
BO	XA-106e	Series Fan Command
AD	XA-106e	Heating Command
CS	XA-106e	All Points for XA-106e
MSD	XA-104e	Occupied Command
AI	XA-104e	Zone Temp
AI	XA-104e	Zone Setpoint
AI	XA-104e	Discharge Air Temp
AD	XA-104e	Supply Air CFM
AD	XA-104e	Supply Air CFM SP
AD	XA-104e	Damper Command
BO	XA-104e	Series Fan Command
AD	XA-104e	Heating Command
CS	XA-104e	All Points for XA-104e
MSD	XA-101	Occupied Command
AI	XA-101	Zone Temp
AI	XA-101	Zone Setpoint
AI	XA-101	Discharge Air Temp
AD	XA-101	Supply Air CFM
AD	XA-101	Supply Air CFM SP
AD	XA-101	Damper Command
BO	XA-101	Series Fan Command
AD	XA-101	Heating Command
CS	XA-101	All Points for XA-101
MSD	23-107c	Occupied Command
AI	23-107c	Zone Temp
AI	23-107c	Zone Setpoint
AI	23-107c	Discharge Air Temp
AD	23-107c	Supply Air CFM
AD	23-107c	Supply Air CFM SP
AD	23-107c	Damper Command
BO	23-107c	Series Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	23-107c	Heating Command
CS	23-107c	All Points for 23-107c
MSD	XA-104d	Occupied Command
AI	XA-104d	Zone Temp
AI	XA-104d	Zone Setpoint
AI	XA-104d	Discharge Air Temp
AD	XA-104d	Supply Air CFM
AD	XA-104d	Supply Air CFM SP
AD	XA-104d	Damper Command
BO	XA-104d	Series Fan Command
AD	XA-104d	Heating Command
CS	XA-104d	All Points for XA-104d
MSD	24-105b	Occupied Command
AI	24-105b	Zone Temp
AI	24-105b	Zone Setpoint
AI	24-105b	Discharge Air Temp
AD	24-105b	Supply Air CFM
AD	24-105b	Supply Air CFM SP
AD	24-105b	Damper Command
BO	24-105b	Series Fan Command
AD	24-105b	Heating Command
CS	24-105b	All Points for 24-105b
MSD	24-105a	Occupied Command
AI	24-105a	Zone Temp
AI	24-105a	Zone Setpoint
AI	24-105a	Discharge Air Temp
AD	24-105a	Supply Air CFM
AD	24-105a	Supply Air CFM SP
AD	24-105a	Damper Command
BO	24-105a	Series Fan Command
AD	24-105a	Heating Command
CS	24-105a	All Points for 24-105a
MSD	XA-104c	Occupied Command
AI	XA-104c	Zone Temp
AI	XA-104c	Zone Setpoint
AI	XA-104c	Discharge Air Temp
AD	XA-104c	Supply Air CFM
AD	XA-104c	Supply Air CFM SP
AD	XA-104c	Damper Command
BO	XA-104c	Series Fan Command
AD	XA-104c	Heating Command
CS	XA-104c	All Points for XA-104c
MSD	XA-105	Occupied Command
AI	XA-105	Zone Temp
AI	XA-105	Zone Setpoint
AI	XA-105	Discharge Air Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	XA-105	Supply Air CFM
AD	XA-105	Supply Air CFM SP
AD	XA-105	Damper Command
BO	XA-105	Series Fan Command
AD	XA-105	Heating Command
CS	XA-105	All Points for XA-105
MSD	XA-104a	Occupied Command
AI	XA-104a	Zone Temp
AI	XA-104a	Zone Setpoint
AI	XA-104a	Discharge Air Temp
AD	XA-104a	Supply Air CFM
AD	XA-104a	Supply Air CFM SP
AD	XA-104a	Damper Command
BO	XA-104a	Series Fan Command
AD	XA-104a	Heating Command
CS	XA-104a	All Points for XA-104a
MSD	XA-100	Occupied Command
AI	XA-100	Zone Temp
AI	XA-100	Zone Setpoint
AI	XA-100	Discharge Air Temp
AD	XA-100	Supply Air CFM
AD	XA-100	Supply Air CFM SP
AD	XA-100	Damper Command
BO	XA-100	Series Fan Command
AD	XA-100	Heating Command
CS	XA-100	All Points for XA-100
MSD	21-107a	Occupied Command
AI	21-107a	Zone Temp
AI	21-107a	Zone Setpoint
AI	21-107a	Discharge Air Temp
AD	21-107a	Supply Air CFM
AD	21-107a	Supply Air CFM SP
AD	21-107a	Damper Command
BO	21-107a	Series Fan Command
AD	21-107a	Heating Command
CS	21-107a	All Points for 21-107a
MSD	XA-107a	Occupied Command
AI	XA-107a	Zone Temp
AI	XA-107a	Zone Setpoint
AI	XA-107a	Discharge Air Temp
AD	XA-107a	Supply Air CFM
AD	XA-107a	Supply Air CFM SP
AD	XA-107a	Damper Command
BO	XA-107a	Series Fan Command
AD	XA-107a	Heating Command
CS	XA-107a	All Points for XA-107a

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MSD	XA-106f	Occupied Command
AI	XA-106f	Zone Temp
AI	XA-106f	Zone Setpoint
AI	XA-106f	Discharge Air Temp
AD	XA-106f	Supply Air CFM
AD	XA-106f	Supply Air CFM SP
AD	XA-106f	Damper Command
BO	XA-106f	Series Fan Command
AD	XA-106f	Heating Command
CS	XA-106f	All Points for XA-106f
MSD	XA-106d	Occupied Command
AI	XA-106d	Zone Temp
AI	XA-106d	Zone Setpoint
AI	XA-106d	Discharge Air Temp
AD	XA-106d	Supply Air CFM
AD	XA-106d	Supply Air CFM SP
AD	XA-106d	Damper Command
BO	XA-106d	Series Fan Command
AD	XA-106d	Heating Command
CS	XA-106d	All Points for XA-106d
MSD	XA-106b	Occupied Command
AI	XA-106b	Zone Temp
AI	XA-106b	Zone Setpoint
AI	XA-106b	Discharge Air Temp
AD	XA-106b	Supply Air CFM
AD	XA-106b	Supply Air CFM SP
AD	XA-106b	Damper Command
BO	XA-106b	Series Fan Command
AD	XA-106b	Heating Command
CS	XA-106b	All Points for XA-106b
MSD	XA-110	Occupied Command
AI	XA-110	Zone Temp
AI	XA-110	Zone Setpoint
AI	XA-110	Discharge Air Temp
AD	XA-110	Supply Air CFM
AD	XA-110	Supply Air CFM SP
AD	XA-110	Damper Command
BO	XA-110	Series Fan Command
AD	XA-110	Heating Command
CS	XA-110	All Points for XA-110
MSD	XA-107	Occupied Command
AI	XA-107	Zone Temp
AI	XA-107	Zone Setpoint
AI	XA-107	Discharge Air Temp
AD	XA-107	Supply Air CFM
AD	XA-107	Supply Air CFM SP

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	XA-107	Damper Command
BO	XA-107	Series Fan Command
AD	XA-107	Heating Command
CS	XA-107	All Points for XA-107
MSD	XA-117	Occupied Command
AI	XA-117	Zone Temp
AI	XA-117	Zone Setpoint
AI	XA-117	Discharge Air Temp
AD	XA-117	Supply Air CFM
AD	XA-117	Supply Air CFM SP
AD	XA-117	Damper Command
BO	XA-117	Series Fan Command
AD	XA-117	Heating Command
CS	XA-117	All Points for XA-117
MSD	21-ad81	Occupied Command
AI	21-ad81	Zone Temp
AI	21-ad81	Zone Setpoint
AI	21-ad81	Discharge Air Temp
AD	21-ad81	Supply Air CFM
AD	21-ad81	Supply Air CFM SP
AD	21-ad81	Damper Command
BO	21-ad81	Series Fan Command
AD	21-ad81	Heating Command
CS	21-ad81	All Points for 21-ad81
MSD	21-101a	Occupied Command
AI	21-101a	Zone Temp
AI	21-101a	Zone Setpoint
AI	21-101a	Discharge Air Temp
AD	21-101a	Supply Air CFM
AD	21-101a	Supply Air CFM SP
AD	21-101a	Damper Command
BO	21-101a	Series Fan Command
AD	21-101a	Heating Command
CS	21-101a	All Points for 21-101a
MSD	21-101	Occupied Command
AI	21-101	Zone Temp
AI	21-101	Zone Setpoint
AI	21-101	Discharge Air Temp
AD	21-101	Supply Air CFM
AD	21-101	Supply Air CFM SP
AD	21-101	Damper Command
BO	21-101	Series Fan Command
AD	21-101	Heating Command
CS	21-101	All Points for 21-101
MSD	21-112	Occupied Command
AI	21-112	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	21-112	Zone Setpoint
AI	21-112	Discharge Air Temp
AD	21-112	Supply Air CFM
AD	21-112	Supply Air CFM SP
AD	21-112	Damper Command
BO	21-112	Series Fan Command
AD	21-112	Heating Command
CS	21-112	All Points for 21-112
MSD	21-107	Occupied Command
AI	21-107	Zone Temp
AI	21-107	Zone Setpoint
AI	21-107	Discharge Air Temp
AD	21-107	Supply Air CFM
AD	21-107	Supply Air CFM SP
AD	21-107	Damper Command
BO	21-107	Series Fan Command
AD	21-107	Heating Command
CS	21-107	All Points for 21-107
MSD	21-102	Occupied Command
AI	21-102	Zone Temp
AI	21-102	Zone Setpoint
AI	21-102	Discharge Air Temp
AD	21-102	Supply Air CFM
AD	21-102	Supply Air CFM SP
AD	21-102	Damper Command
BO	21-102	Series Fan Command
AD	21-102	Heating Command
CS	21-102	All Points for 21-102
MSD	21-104	Occupied Command
AI	21-104	Zone Temp
AI	21-104	Zone Setpoint
AI	21-104	Discharge Air Temp
AD	21-104	Supply Air CFM
AD	21-104	Supply Air CFM SP
AD	21-104	Damper Command
BO	21-104	Series Fan Command
AD	21-104	Heating Command
CS	21-104	All Points for 21-104
MSD	21-105	Occupied Command
AI	21-105	Zone Temp
AI	21-105	Zone Setpoint
AI	21-105	Discharge Air Temp
AD	21-105	Supply Air CFM
AD	21-105	Supply Air CFM SP
AD	21-105	Damper Command
BO	21-105	Series Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	21-105	Heating Command
CS	21-105	All Points for 21-105
MSD	21-103	Occupied Command
AI	21-103	Zone Temp
AI	21-103	Zone Setpoint
AI	21-103	Discharge Air Temp
AD	21-103	Supply Air CFM
AD	21-103	Supply Air CFM SP
AD	21-103	Damper Command
BO	21-103	Series Fan Command
AD	21-103	Heating Command
CS	21-103	All Points for 21-103
MSD	21-124	Occupied Command
AI	21-124	Zone Temp
AI	21-124	Zone Setpoint
AI	21-124	Discharge Air Temp
AD	21-124	Supply Air CFM
AD	21-124	Supply Air CFM SP
AD	21-124	Damper Command
BO	21-124	Series Fan Command
AD	21-124	Heating Command
CS	21-124	All Points for 21-124
MSD	21-123	Occupied Command
AI	21-123	Zone Temp
AI	21-123	Zone Setpoint
AI	21-123	Discharge Air Temp
AD	21-123	Supply Air CFM
AD	21-123	Supply Air CFM SP
AD	21-123	Damper Command
BO	21-123	Series Fan Command
AD	21-123	Heating Command
CS	21-123	All Points for 21-123
MSD	21-125	Occupied Command
AI	21-125	Zone Temp
AI	21-125	Zone Setpoint
AI	21-125	Discharge Air Temp
AD	21-125	Supply Air CFM
AD	21-125	Supply Air CFM SP
AD	21-125	Damper Command
BO	21-125	Series Fan Command
AD	21-125	Heating Command
CS	21-125	All Points for 21-125
MSD	21-122	Occupied Command
AI	21-122	Zone Temp
AI	21-122	Zone Setpoint
AI	21-122	Discharge Air Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	21-122	Supply Air CFM
AD	21-122	Supply Air CFM SP
AD	21-122	Damper Command
BO	21-122	Series Fan Command
AD	21-122	Heating Command
CS	21-122	All Points for 21-122
MSD	21-130	Occupied Command
AI	21-130	Zone Temp
AI	21-130	Zone Setpoint
AI	21-130	Discharge Air Temp
AD	21-130	Supply Air CFM
AD	21-130	Supply Air CFM SP
AD	21-130	Damper Command
BO	21-130	Series Fan Command
AD	21-130	Heating Command
CS	21-130	All Points for 21-130
MSD	21-133	Occupied Command
AI	21-133	Zone Temp
AI	21-133	Zone Setpoint
AI	21-133	Discharge Air Temp
AD	21-133	Supply Air CFM
AD	21-133	Supply Air CFM SP
AD	21-133	Damper Command
BO	21-133	Series Fan Command
AD	21-133	Heating Command
CS	21-133	All Points for 21-133
MSD	21-134	Occupied Command
AI	21-134	Zone Temp
AI	21-134	Zone Setpoint
AI	21-134	Discharge Air Temp
AD	21-134	Supply Air CFM
AD	21-134	Supply Air CFM SP
AD	21-134	Damper Command
BO	21-134	Series Fan Command
AD	21-134	Heating Command
CS	21-134	All Points for 21-134
MSD	21-135	Occupied Command
AI	21-135	Zone Temp
AI	21-135	Zone Setpoint
AI	21-135	Discharge Air Temp
AD	21-135	Supply Air CFM
AD	21-135	Supply Air CFM SP
AD	21-135	Damper Command
BO	21-135	Series Fan Command
AD	21-135	Heating Command
CS	21-135	All Points for 21-135

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MSD	21-138	Occupied Command
AI	21-138	Zone Temp
AI	21-138	Zone Setpoint
AI	21-138	Discharge Air Temp
AD	21-138	Supply Air CFM
AD	21-138	Supply Air CFM SP
AD	21-138	Damper Command
BO	21-138	Series Fan Command
AD	21-138	Heating Command
CS	21-138	All Points for 21-138
MSD	21-127	Occupied Command
AI	21-127	Zone Temp
AI	21-127	Zone Setpoint
AI	21-127	Discharge Air Temp
AD	21-127	Supply Air CFM
AD	21-127	Supply Air CFM SP
AD	21-127	Damper Command
BO	21-127	Series Fan Command
AD	21-127	Heating Command
CS	21-127	All Points for 21-127
MSD	21-139	Occupied Command
AI	21-139	Zone Temp
AI	21-139	Zone Setpoint
AI	21-139	Discharge Air Temp
AD	21-139	Supply Air CFM
AD	21-139	Supply Air CFM SP
AD	21-139	Damper Command
BO	21-139	Series Fan Command
AD	21-139	Heating Command
CS	21-139	All Points for 21-139
MSD	22-183	Occupied Command
AI	22-183	Zone Temp
AI	22-183	Zone Setpoint
AI	22-183	Discharge Air Temp
AD	22-183	Supply Air CFM
AD	22-183	Supply Air CFM SP
AD	22-183	Damper Command
BO	22-183	Series Fan Command
AD	22-183	Heating Command
CS	22-183	All Points for 22-183
MSD	22-184	Occupied Command
AI	22-184	Zone Temp
AI	22-184	Zone Setpoint
AI	22-184	Discharge Air Temp
AD	22-184	Supply Air CFM
AD	22-184	Supply Air CFM SP

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	22-184	Damper Command
BO	22-184	Series Fan Command
AD	22-184	Heating Command
CS	22-184	All Points for 22-184
MSD	22-185	Occupied Command
AI	22-185	Zone Temp
AI	22-185	Zone Setpoint
AI	22-185	Discharge Air Temp
AD	22-185	Supply Air CFM
AD	22-185	Supply Air CFM SP
AD	22-185	Damper Command
BO	22-185	Series Fan Command
AD	22-185	Heating Command
CS	22-185	All Points for 22-185
MSD	22-130	Occupied Command
AI	22-130	Zone Temp
AI	22-130	Zone Setpoint
AI	22-130	Discharge Air Temp
AD	22-130	Supply Air CFM
AD	22-130	Supply Air CFM SP
AD	22-130	Damper Command
BO	22-130	Series Fan Command
AD	22-130	Heating Command
CS	22-130	All Points for 22-130
MSD	22-112	Occupied Command
AI	22-112	Zone Temp
AI	22-112	Zone Setpoint
AI	22-112	Discharge Air Temp
AD	22-112	Supply Air CFM
AD	22-112	Supply Air CFM SP
AD	22-112	Damper Command
BO	22-112	Series Fan Command
AD	22-112	Heating Command
CS	22-112	All Points for 22-112
MSD	22-129	Occupied Command
AI	22-129	Zone Temp
AI	22-129	Zone Setpoint
AI	22-129	Discharge Air Temp
AD	22-129	Supply Air CFM
AD	22-129	Supply Air CFM SP
AD	22-129	Damper Command
BO	22-129	Series Fan Command
AD	22-129	Heating Command
CS	22-129	AllPoints 22-129 AHU2EW
MSD	22-121	Occupied Command
AI	22-121	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	22-121	Zone Setpoint
AI	22-121	Discharge Air Temp
AD	22-121	Supply Air CFM
AD	22-121	Supply Air CFM SP
AD	22-121	Damper Command
BO	22-121	Series Fan Command
AD	22-121	Heating Command
CS	22-121	All Points for 22-121
BO	3C-FC302	Occupied Command
AI	3C-FC302	Zone Temp
AI	3C-FC302	Zone Setpoint
AOS	3C-FC302	Heating Valve Command
AOS	3C-FC302	Cooling Valve Command
BO	3C-FC302	Fan Command
BI	3C-FC302	Fan Status
BI	3C-FC302	Pan Alarm Status
CS	3C-FC302	Temp Occ.Status C.S.
BO	3C-FC303	Occupied Command
AI	3C-FC303	Zone Temp
AI	3C-FC303	Zone Setpoint
AOS	3C-FC303	Heating Valve Command
AOS	3C-FC303	Cooling Valve Command
BO	3C-FC303	Fan Command
BI	3C-FC303	Fan Status
BI	3C-FC303	Pan Alarm Status
CS	3C-FC303	Temp Occ.Status C.S.
BO	3C-FC304	Occupied Command
AI	3C-FC304	Zone Temp
AI	3C-FC304	Zone Setpoint
AOS	3C-FC304	Heating Valve Command
AOS	3C-FC304	Cooling Valve Command
BO	3C-FC304	Fan Command
BI	3C-FC304	Fan Status
BI	3C-FC304	Pan Alarm Status
CS	3C-FC304	Temp Occ.Status C.S.
BO	3C-FC306	Occupied Command
AI	3C-FC306	Zone Temp
AI	3C-FC306	Zone Setpoint
AOS	3C-FC306	Heating Valve Command
AOS	3C-FC306	Cooling Valve Command
BO	3C-FC306	Fan Command
BI	3C-FC306	Fan Status
BI	3C-FC306	Pan Alarm Status
CS	3C-FC306	Temp Occ.Status C.S.
BO	3C-FC307	Occupied Command
AI	3C-FC307	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	3C-FC307	Zone Setpoint
AOS	3C-FC307	Heating Valve Command
AOS	3C-FC307	Cooling Valve Command
BO	3C-FC307	Fan Command
BI	3C-FC307	Fan Status
BI	3C-FC307	Pan Alarm Status
CS	3C-FC307	Temp Occ.Status C.S.
BO	3C-FC308	Occupied Command
AI	3C-FC308	Zone Temp
AI	3C-FC308	Zone Setpoint
AOS	3C-FC308	Heating Valve Command
AOS	3C-FC308	Cooling Valve Command
BO	3C-FC308	Fan Command
BI	3C-FC308	Fan Status
BI	3C-FC308	Pan Alarm Status
CS	3C-FC308	Temp Occ.Status C.S.
BO	3C-FC309	Occupied Command
AI	3C-FC309	Zone Temp
AI	3C-FC309	Zone Setpoint
AOS	3C-FC309	Heating Valve Command
AOS	3C-FC309	Cooling Valve Command
BO	3C-FC309	Fan Command
BI	3C-FC309	Fan Status
BI	3C-FC309	Pan Alarm Status
CS	3C-FC309	Temp Occ.Status C.S.
BO	3C-FC310	Occupied Command
AI	3C-FC310	Zone Temp
AI	3C-FC310	Zone Setpoint
AOS	3C-FC310	Heating Valve Command
AOS	3C-FC310	Cooling Valve Command
BO	3C-FC310	Fan Command
BI	3C-FC310	Fan Status
BI	3C-FC310	Pan Alarm Status
CS	3C-FC310	Temp Occ.Status C.S.
BO	3C-FC311	Occupied Command
AI	3C-FC311	Zone Temp
AI	3C-FC311	Zone Setpoint
AOS	3C-FC311	Heating Valve Command
AOS	3C-FC311	Cooling Valve Command
BO	3C-FC311	Fan Command
BI	3C-FC311	Fan Status
BI	3C-FC311	Pan Alarm Status
CS	3C-FC311	Temp Occ.Status C.S.
BO	3C-FC312	Occupied Command
AI	3C-FC312	Zone Temp
AI	3C-FC312	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	3C-FC312	Heating Valve Command
AOS	3C-FC312	Cooling Valve Command
BO	3C-FC312	Fan Command
BI	3C-FC312	Fan Status
BI	3C-FC312	Pan Alarm Status
CS	3C-FC312	Temp Occ.Status C.S.
BO	3C-FC313	Occupied Command
AI	3C-FC313	Zone Temp
AI	3C-FC313	Zone Setpoint
AOS	3C-FC313	Heating Valve Command
AOS	3C-FC313	Cooling Valve Command
BO	3C-FC313	Fan Command
BI	3C-FC313	Fan Status
BI	3C-FC313	Pan Alarm Status
CS	3C-FC313	Temp Occ.Status C.S.
BO	3C-FC314	Occupied Command
AI	3C-FC314	Zone Temp
AI	3C-FC314	Zone Setpoint
AOS	3C-FC314	Heating Valve Command
AOS	3C-FC314	Cooling Valve Command
BO	3C-FC314	Fan Command
BI	3C-FC314	Fan Status
BI	3C-FC314	Pan Alarm Status
CS	3C-FC314	Temp Occ.Status C.S.
BO	3C-FC315	Occupied Command
AI	3C-FC315	Zone Temp
AI	3C-FC315	Zone Setpoint
AOS	3C-FC315	Heating Valve Command
AOS	3C-FC315	Cooling Valve Command
BO	3C-FC315	Fan Command
BI	3C-FC315	Fan Status
BI	3C-FC315	Pan Alarm Status
CS	3C-FC315	Temp Occ.Status C.S.
BO	3C-FC316	Occupied Command
AI	3C-FC316	Zone Temp
AI	3C-FC316	Zone Setpoint
AOS	3C-FC316	Heating Valve Command
AOS	3C-FC316	Cooling Valve Command
BO	3C-FC316	Fan Command
BI	3C-FC316	Fan Status
BI	3C-FC316	Pan Alarm Status
CS	3C-FC316	Temp Occ.Status C.S.
BO	3C-FC317	Occupied Command
AI	3C-FC317	Zone Temp
AI	3C-FC317	Zone Setpoint
AOS	3C-FC317	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	3C-FC317	Cooling Valve Command
BO	3C-FC317	Fan Command
BI	3C-FC317	Fan Status
BI	3C-FC317	Pan Alarm Status
CS	3C-FC317	Temp Occ.Status C.S.
BO	3C-FC318	Occupied Command
AI	3C-FC318	Zone Temp
AI	3C-FC318	Zone Setpoint
AOS	3C-FC318	Heating Valve Command
AOS	3C-FC318	Cooling Valve Command
BO	3C-FC318	Fan Command
BI	3C-FC318	Fan Status
BI	3C-FC318	Pan Alarm Status
CS	3C-FC318	Temp Occ.Status C.S.
BO	3C-FC319	Occupied Command
AI	3C-FC319	Zone Temp
AI	3C-FC319	Zone Setpoint
AOS	3C-FC319	Heating Valve Command
AOS	3C-FC319	Cooling Valve Command
BO	3C-FC319	Fan Command
BI	3C-FC319	Fan Status
BI	3C-FC319	Pan Alarm Status
CS	3C-FC319	Temp Occ.Status C.S.
BO	3C-FC320	Occupied Command
AI	3C-FC320	Zone Temp
AI	3C-FC320	Zone Setpoint
AOS	3C-FC320	Heating Valve Command
AOS	3C-FC320	Cooling Valve Command
BO	3C-FC320	Fan Command
BI	3C-FC320	Fan Status
BI	3C-FC320	Pan Alarm Status
CS	3C-FC320	Temp Occ.Status C.S.
BO	3C-FC321	Occupied Command
AI	3C-FC321	Zone Temp
AI	3C-FC321	Zone Setpoint
AOS	3C-FC321	Heating Valve Command
AOS	3C-FC321	Cooling Valve Command
BO	3C-FC321	Fan Command
BI	3C-FC321	Fan Status
BI	3C-FC321	Pan Alarm Status
CS	3C-FC321	Temp Occ.Status C.S.
BO	3C-FC323	Occupied Command
AI	3C-FC323	Zone Temp
AI	3C-FC323	Zone Setpoint
AOS	3C-FC323	Heating Valve Command
AOS	3C-FC323	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	3C-FC323	Fan Command
BI	3C-FC323	Fan Status
BI	3C-FC323	Pan Alarm Status
CS	3C-FC323	Temp Occ.Status C.S.
BO	3C-FC324	Occupied Command
AI	3C-FC324	Zone Temp
AI	3C-FC324	Zone Setpoint
AOS	3C-FC324	Heating Valve Command
AOS	3C-FC324	Cooling Valve Command
BO	3C-FC324	Fan Command
BI	3C-FC324	Fan Status
BI	3C-FC324	Pan Alarm Status
CS	3C-FC324	Temp Occ.Status C.S.
BO	3C-FC325	Occupied Command
AI	3C-FC325	Zone Temp
AI	3C-FC325	Zone Setpoint
AOS	3C-FC325	Heating Valve Command
AOS	3C-FC325	Cooling Valve Command
BO	3C-FC325	Fan Command
BI	3C-FC325	Fan Status
BI	3C-FC325	Pan Alarm Status
CS	3C-FC325	Temp Occ.Status C.S.
BO	3C-FC327	Occupied Command
AI	3C-FC327	Zone Temp
AI	3C-FC327	Zone Setpoint
AOS	3C-FC327	Heating Valve Command
AOS	3C-FC327	Cooling Valve Command
BO	3C-FC327	Fan Command
BI	3C-FC327	Fan Status
BI	3C-FC327	Pan Alarm Status
CS	3C-FC327	Temp Occ.Status C.S.
BO	3C-FC328	Occupied Command
AI	3C-FC328	Zone Temp
AI	3C-FC328	Zone Setpoint
AOS	3C-FC328	Heating Valve Command
AOS	3C-FC328	Cooling Valve Command
BO	3C-FC328	Fan Command
BI	3C-FC328	Fan Status
BI	3C-FC328	Pan Alarm Status
CS	3C-FC328	Temp Occ.Status C.S.
BO	3C-FC329	Occupied Command
AI	3C-FC329	Zone Temp
AI	3C-FC329	Zone Setpoint
AOS	3C-FC329	Heating Valve Command
AOS	3C-FC329	Cooling Valve Command
BO	3C-FC329	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	3C-FC329	Fan Status
BI	3C-FC329	Pan Alarm Status
CS	3C-FC329	Temp Occ.Status C.S.
BO	3C-FC322	Occupied Command
AI	3C-FC322	Zone Temp
AI	3C-FC322	Zone Setpoint
AOS	3C-FC322	Heating Valve Command
AOS	3C-FC322	Cooling Valve Command
BO	3C-FC322	Fan Command
BI	3C-FC322	Fan Status
CS	3C-FC322	Temp Occ.Status C.S.
BI	3C-FC322	Pan Alarm Status
	Building 3	
Point	Equipment	type
	NC-13	Network controller
NC13-HRW	AHU-06AB	107, 1, 3, AHU
NC13-HRW	AHU-06C	106, 1, 3, AHU
NC13-HRW	AHU-05AB	105, 1, 3, AHU
NC13-HRW	AHU-05C	104, 1, 3, AHU
NC13-HRW	AHU-4ABC	110, 1, 3, AHU
NC13-HRW	AHU-3ABC	108, 1, 3, AHU
NC13-HRW	AHU-03D	109, 1, 3, AHU
NC13-HRW	4A-FC01	50, 1, 3, VAV
NC13-HRW	4A-FC02	51, 1, 3, VAV
NC13-HRW	4A-FC03	52, 1, 3, VAV
NC13-HRW	4A-FC04	53, 1, 3, VAV
NC13-HRW	4A-FC05	54, 1, 3, VAV
NC13-HRW	4A-FC06	55, 1, 3, VAV
NC13-HRW	4A-FC07	56, 1, 3, VAV
NC13-HRW	4A-FC08	57, 1, 3, VAV
NC13-HRW	4A-FC09	58, 1, 3, VAV
NC13-HRW	4A-FC10	59, 1, 3, VAV
NC13-HRW	4A-FC11	60, 1, 3, VAV
NC13-HRW	4A-FC12	61, 1, 3, VAV
NC13-HRW	4A-FC13	62, 1, 3, VAV
NC13-HRW	4A-FC14	63, 1, 3, VAV
NC13-HRW	4A-FC15	64, 1, 3, VAV
NC13-HRW	4A-FC16	65, 1, 3, VAV
NC13-HRW	4B-FC01	66, 1, 3, VAV
NC13-HRW	4B-FC02	67, 1, 3, VAV
NC13-HRW	4B-FC03	68, 1, 3, VAV
NC13-HRW	4B-FC04	69, 1, 3, VAV
NC13-HRW	4B-FC05	70, 1, 3, VAV
NC13-HRW	4B-FC06	71, 1, 3, VAV
NC13-HRW	4B-FC07	72, 1, 3, VAV
NC13-HRW	4B-FC08	73, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC13-HRW	4B-FC09	74, 1, 3, VAV
NC13-HRW	4B-FC10	75, 1, 3, VAV
NC13-HRW	4B-FC11	76, 1, 3, VAV
NC13-HRW	4B-FC12	77, 1, 3, VAV
NC13-HRW	4B-FC13	78, 1, 3, VAV
NC13-HRW	4C-FC01	1, 1, 3, VAV
NC13-HRW	4C-FC02	2, 1, 3, VAV
NC13-HRW	4C-FC03	3, 1, 3, VAV
NC13-HRW	4C-FC04	4, 1, 3, VAV
NC13-HRW	4C-FC05	5, 1, 3, VAV
NC13-HRW	4C-FC06	6, 1, 3, VAV
NC13-HRW	4C-FC07	7, 1, 3, VAV
NC13-HRW	4C-FC08	8, 1, 3, VAV
NC13-HRW	4C-FC09	9, 1, 3, VAV
NC13-HRW	4C-FC10	10, 1, 3, VAV
NC13-HRW	4C-FC11	11, 1, 3, VAV
NC13-HRW	4C-FC12	12, 1, 3, VAV
NC13-HRW	4C-FC13	13, 1, 3, VAV
NC13-HRW	4C-FC14	14, 1, 3, VAV
NC13-HRW	4C-FC15	15, 1, 3, VAV
NC13-HRW	4C-FC16	16, 1, 3, VAV
NC13-HRW	4C-FC17	17, 1, 3, VAV
NC13-HRW	4C-FC18	18, 1, 3, VAV
NC13-HRW	4C-FC19	19, 1, 3, VAV
NC13-HRW	4C-FC20	20, 1, 3, VAV
NC13-HRW	4C-FC21	21, 1, 3, VAV
NC13-HRW	4C-FC22	22, 1, 3, VAV
NC13-HRW	4C-FC23	23, 1, 3, VAV
NC13-HRW	4C-FC24	24, 1, 3, VAV
NC13-HRW	4C-FC25	25, 1, 3, VAV
NC13-HRW	4C-FC26	26, 1, 3, VAV
NC13-HRW	4C-FC27	27, 1, 3, VAV
NC13-HRW	4C-FC28	28, 1, 3, VAV
NC13-HRW	4C-FC29	29, 1, 3, VAV
NC13-HRW	4C-FC30	30, 1, 3, VAV
NC13-HRW	4C-FC31	31, 1, 3, VAV
NC13-HRW	4C-FC32	32, 1, 3, VAV
NC13-HRW	4C-FC33	33, 1, 3, VAV
NC13-HRW	4C-FC34	34, 1, 3, VAV
NC13-HRW	4C-FC35	35, 1, 3, VAV
NC13-HRW	4C-FC36	36, 1, 3, VAV
NC13-HRW	4C-FC37	37, 1, 3, VAV
NC13-HRW	4C-FC38	38, 1, 3, VAV
NC13-HRW	4C-FC39	39, 1, 3, VAV
NC13-HRW	4C-FC41	41, 1, 3, VAV
NC13-HRW	4C-FC40	40, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC13-HRW	4C-FC42	42, 1, 3, VAV
NC13-HRW	4C-FC43	43, 1, 3, VAV
NC13-HRW	4C-FC44	44, 1, 3, VAV
NC13-HRW	4C-FC45	45, 1, 3, VAV
NC13-HRW	4C-FC46	46, 1, 3, VAV
NC13-HRW	4C-FC47	47, 1, 3, VAV
NC13-HRW	4C-FC48	48, 1, 3, VAV
NC13-HRW	4C-FC49	49, 1, 3, VAV
NC13-HRW	3C-FC01	120, 1, 3, VAV
NC13-HRW	3C-FC02	121, 1, 3, VAV
NC13-HRW	3C-FC03	122, 1, 3, VAV
NC13-HRW	3C-FC04	123, 1, 3, VAV
NC13-HRW	3C-FC05	124, 1, 3, VAV
NC13-HRW	3C-FC06	125, 1, 3, VAV
NC13-HRW	3C-FC07	126, 1, 3, VAV
NC13-HRW	3C-FC08	127, 1, 3, VAV
NC13-HRW	3C-FC09	128, 1, 3, VAV
NC13-HRW	3C-FC10	129, 1, 3, VAV
NC13-HRW	3C-FC11	130, 1, 3, VAV
NC13-HRW	3C-FC12	131, 1, 3, VAV
NC13-HRW	3C-FC13	132, 1, 3, VAV
NC13-HRW	3B-FC01	146, 1, 3, VAV
NC13-HRW	3B-FC02	158, 1, 3, VAV
NC13-HRW	3B-FC03	147, 1, 3, VAV
NC13-HRW	3B-FC04	148, 1, 3, VAV
NC13-HRW	3B-FC05	149, 1, 3, VAV
NC13-HRW	3B-FC06	150, 1, 3, VAV
NC13-HRW	3B-FC07	151, 1, 3, VAV
NC13-HRW	3B-FC08	152, 1, 3, VAV
NC13-HRW	3B-FC09	153, 1, 3, VAV
NC13-HRW	3B-FC10	154, 1, 3, VAV
NC13-HRW	3B-FC11	155, 1, 3, VAV
NC13-HRW	3B-FC12	156, 1, 3, VAV
NC13-HRW	3B-FC13	157, 1, 3, VAV
NC13-HRW	3B-FC14	145, 1, 3, VAV
NC13-HRW	3A-FC01	133, 1, 3, VAV
NC13-HRW	3A-FC02	134, 1, 3, VAV
NC13-HRW	3A-FC03	135, 1, 3, VAV
NC13-HRW	3A-FC04	136, 1, 3, VAV
NC13-HRW	3A-FC05	137, 1, 3, VAV
NC13-HRW	3A-FC06	138, 1, 3, VAV
NC13-HRW	3A-FC07	167, 1, 3, VAV
NC13-HRW	3A-FC08	139, 1, 3, VAV
NC13-HRW	3A-FC09	140, 1, 3, VAV
NC13-HRW	3A-FC10	160, 1, 3, VAV
NC13-HRW	3A-FC11	163, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC13-HRW	3A-FC12	164, 1, 3, VAV
NC13-HRW	3A-FC13	166, 1, 3, VAV
NC13-HRW	3A-FC14	165, 1, 3, VAV
NC13-HRW	3A-FC15	162, 1, 3, VAV
NC13-HRW	3A-FC16	161, 1, 3, VAV
NC13-HRW	3A-FC17	159, 1, 3, VAV
NC13-HRW	3A-FC18	168, 1, 3, VAV
NC13-HRW	3A-FC19	141, 1, 3, VAV
NC13-HRW	3A-FC20	142, 1, 3, VAV
NC13-HRW	3A-FC21	143, 1, 3, VAV
NC13-HRW	3A-FC144	144, 1, 3, VAV
BO	4B-FC13	Occupied Command
AI	4B-FC13	Zone Temp
AI	4B-FC13	Zone Setpoint
BO	4B-FC13	Fan Command
BI	4B-FC13	Fan Status
BI	4B-FC13	Pan Alarm Status
CS	4B-FC13	Temp Occ. Status C.S.
BO	4A-FC12	Occupied Command
AI	4A-FC12	Zone Temp
AI	4A-FC12	Zone Setpoint
AOS	4A-FC12	Cooling Valve Command
BO	4A-FC12	Fan Command
BI	4A-FC12	Fan Status
BI	4A-FC12	Pan Alarm Status
AOS	4A-FC12	Heating Valve Command
CS	4A-FC12	Temp Occ Status C.S.
BO	3A-FC07	Occupied Command
AI	3A-FC07	Zone Temp
AI	3A-FC07	Zone Setpoint
AOS	3A-FC07	Cooling Valve Command
AOS	3A-FC07	Heating Valve Command
BO	3A-FC07	Fan Command
BI	3A-FC07	Fan Status
BI	3A-FC07	Pan Alarm Status
CS	3A-FC07	Temp Occ.Status C.S.
BO	3B-FC07	Occupied Command
AI	3B-FC07	Zone Temp
AI	3B-FC07	Zone Setpoint
AOS	3B-FC07	Heating Valve Command
BO	3B-FC07	Fan Command
BI	3B-FC07	Fan Status
BI	3B-FC07	Pan Alarm Status
CS	3B-FC07	Temp. Occ. Status CS
BO	4A-FC13	Occupied Command
AI	4A-FC13	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	4A-FC13	Zone Setpoint
AOS	4A-FC13	Cooling Valve Command
BO	4A-FC13	Fan Command
BI	4A-FC13	Fan Status
BI	4A-FC13	Pan Alarm Status
AOS	4A-FC13	Heating Valve Command
CS	4A-FC13	Temp Occ. Status C.S.
BO	4B-FC04	Occupied Command
AI	4B-FC04	Zone Temp
AI	4B-FC04	Zone Setpoint
AOS	4B-FC04	Cooling Valve Command
BO	4B-FC04	Fan Command
BI	4B-FC04	Fan Status
BI	4B-FC04	Pan Alarm Status
AOS	4B-FC04	Heating Valve Command
CS	4B-FC04	Temp Occ.Status C.S.
BO	3C-FC08	Occupied Command
AI	3C-FC08	Zone Temp
AI	3C-FC08	Zone Setpoint
AOS	3C-FC08	Heating Valve Command
AOS	3C-FC08	Cooling Valve Command
BO	3C-FC08	Fan Command
BI	3C-FC08	Fan Status
BI	3C-FC08	Pan Alarm Status
CS	3C-FC08	Temp Occ.Status C.S.
BO	3C-FC07	Occupied Command
AI	3C-FC07	Zone Temp
AI	3C-FC07	Zone Setpoint
AOS	3C-FC07	Cooling Valve Command
AOS	3C-FC07	Heating Valve Command
BO	3C-FC07	Fan Command
BI	3C-FC07	Fan Status
BI	3C-FC07	Pan Alarm Status
CS	3C-FC07	Temp Occ.Status C.S.
BO	3C-FC05	Occupied Command
AI	3C-FC05	Zone Temp
AI	3C-FC05	Zone Setpoint
AOS	3C-FC05	Cooling Valve Command
AOS	3C-FC05	Heating Valve Command
BO	3C-FC05	Fan Command
BI	3C-FC05	Fan Status
BI	3C-FC05	Pan Alarm Status
CS	3C-FC05	Temp Occ.Status C.S.
BO	4A-FC06	Occupied Command
AI	4A-FC06	Zone Temp
AI	4A-FC06	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	4A-FC06	Heating Valve Command
AOS	4A-FC06	Cooling Valve Command
BO	4A-FC06	Fan Command
BI	4A-FC06	Fan Status
BI	4A-FC06	Pan Alarm Status
CS	4A-FC06	Temp Occ.Status C.S.
BO	3A-FC01	Occupied Command
AI	3A-FC01	Zone Temp
AI	3A-FC01	Zone Setpoint
AOS	3A-FC01	Heating Valve Command
AOS	3A-FC01	Cooling Valve Command
BO	3A-FC01	Fan Command
BI	3A-FC01	Fan Status
BI	3A-FC01	Pan Alarm Status
CS	3A-FC01	Temp Occ.Status C.S.
BO	3B-FC08	Occupied Command
AI	3B-FC08	Zone Temp
AI	3B-FC08	Zone Setpoint
AOS	3B-FC08	Cooling Valve Command
BO	3B-FC08	Fan Command
BI	3B-FC08	Fan Status
BI	3B-FC08	Pan Alarm Status
AOS	3B-FC08	Heating Valve Command
CS	3B-FC08	Temp Occ.Status C.S.
BO	3A-FC19	Occupied Command
AI	3A-FC19	Zone Temp
AI	3A-FC19	Zone Setpoint
AOS	3A-FC19	Heating Valve Command
AOS	3A-FC19	Cooling Valve Command
BO	3A-FC19	Fan Command
BI	3A-FC19	Fan Status
BI	3A-FC19	Pan Alarm Status
CS	3A-FC19	Temp Occ.Status C.S.
BO	3A-FC18	Occupied Command
AI	3A-FC18	Zone Temp
AI	3A-FC18	Zone Setpoint
AOS	3A-FC18	Heating Valve Command
AOS	3A-FC18	Cooling Valve Command
BO	3A-FC18	Fan Command
BI	3A-FC18	Fan Status
BI	3A-FC18	Pan Alarm Status
CS	3A-FC18	Temp Occ.Status C.S.
BO	3A-FC17	Occupied Command
AI	3A-FC17	Zone Temp
AI	3A-FC17	Zone Setpoint
AOS	3A-FC17	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	3A-FC17	Cooling Valve Command
BO	3A-FC17	Fan Command
BI	3A-FC17	Fan Status
BI	3A-FC17	Pan Alarm Status
CS	3A-FC17	Temp Occ.Status C.S.
BO	3A-FC16	Occupied Command
AI	3A-FC16	Zone Temp
AI	3A-FC16	Zone Setpoint
AOS	3A-FC16	Heating Valve Command
AOS	3A-FC16	Cooling Valve Command
BO	3A-FC16	Fan Command
BI	3A-FC16	Fan Status
BI	3A-FC16	Pan Alarm Status
CS	3A-FC16	Temp Occ.Status C.S.
BO	3A-FC15	Occupied Command
AI	3A-FC15	Zone Temp
AI	3A-FC15	Zone Setpoint
AOS	3A-FC15	Heating Valve Command
AOS	3A-FC15	Cooling Valve Command
BO	3A-FC15	Fan Command
BI	3A-FC15	Fan Status
BI	3A-FC15	Pan Alarm Status
CS	3A-FC15	Temp Occ.Status C.S.
BD	AHU-4ABC	Fan Coil Occupied Commad
BD	AHU-4ABC	
AI	AHU-4ABC	Preheat Temp
AOS	AHU-4ABC	Preheat Setpoint
AOS	AHU-4ABC	Preheat Valve Command
AOS	AHU-4ABC	Preheat Face/Bypass
AI	AHU-4ABC	Preheat RetWtr Temp
BD	AHU-4ABC	
AI	AHU-4ABC	Outside Air Temp
AOS	AHU-4ABC	Face&Bypass C\O Setpoint
BD	AHU-4ABC	Setpoint
AI	AHU-4ABC	Cooling Coil Temp
AOS	AHU-4ABC	Cooling Coil Setpoint
AOS	AHU-4ABC	Cooling Valve Command
AI	AHU-4ABC	Cooiling RetWtr Temp
BD	AHU-4ABC	
AI	AHU-4ABC	Reheat Temp
AOS	AHU-4ABC	Reheat Setpoint
AOS	AHU-4ABC	Reheat Valve Command
AI	AHU-4ABC	Reheat RetWtr Temp
BD	AHU-4ABC	
BO	AHU-4ABC	Supply Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	AHU-4ABC	Supply Airflow
BI	AHU-4ABC	Outside Air Damper Sts
BI	AHU-4ABC	Filter Status
BI	AHU-4ABC	Low Temp Alarm
BI	AHU-4ABC	Supply Air Smk Detector
CS	AHU-4ABC	All Points C.S.
JCB	AHU-4ABC	4COCCMD
JCB	AHU-4ABC	4AOCCMD
JCB	AHU-4ABC	4BOCCMD
BD	AHU-3ABC	Fan Coil Occupied Commad
BD	AHU-3ABC	
AI	AHU-3ABC	Preheat Temp
AOS	AHU-3ABC	Preheat Setpoint
AOS	AHU-3ABC	Preheat Valve Command
AOS	AHU-3ABC	Preheat Face/Bypass
AI	AHU-3ABC	Preheat RetWtr Temp
BD	AHU-3ABC	
AI	AHU-3ABC	Outside Air Temp
AOS	AHU-3ABC	Face&Bypass C\O Setpoint
BD	AHU-3ABC	
AI	AHU-3ABC	Cooling Coil Temp
AOS	AHU-3ABC	Cooling Coil Setpoint
AOS	AHU-3ABC	Cooling Valve Command
AI	AHU-3ABC	Cooiling RetWtr Temp
BD	AHU-3ABC	
AI	AHU-3ABC	Reheat Temp
AOS	AHU-3ABC	Reheat Setpoint
AOS	AHU-3ABC	Reheat Valve Command
AI	AHU-3ABC	Reheat RetWtr Temp
BD	AHU-3ABC	
BO	AHU-3ABC	Supply Fan Command
BI	AHU-3ABC	Supply Airflow
BI	AHU-3ABC	Outside Air Damper Sts
BI	AHU-3ABC	Filter Status
BI	AHU-3ABC	Low Temp Alarm
BI	AHU-3ABC	Supply Air Smk Detector
CS	AHU-3ABC	All Points C.S.
BD	AHU-03D	Fan Coil Occupied Commad
BD	AHU-03D	
AI	AHU-03D	Preheat Temp
AOS	AHU-03D	Preheat Setpoint
AOS	AHU-03D	Preheat Valve Command
AOS	AHU-03D	Preheat Face/Bypass
AI	AHU-03D	Preheat RetWtr Temp
BD	AHU-03D	

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	AHU-03D	Outside Air Temp
AOS	AHU-03D	Face&Bypass C\O Setpoint
BD	AHU-03D	
AI	AHU-03D	Cooling Coil Temp
AOS	AHU-03D	Cooling Coil Setpoint
AOS	AHU-03D	Cooling Valve Command
AI	AHU-03D	Cooiling RetWtr Temp
BD	AHU-03D	
AI	AHU-03D	Reheat Temp
AOS	AHU-03D	Reheat Setpoint
AOS	AHU-03D	Reheat Valve Command
AI	AHU-03D	Reheat RetWtr Temp
BD	AHU-03D	
BO	AHU-03D	Supply Fan Command
BI	AHU-03D	Supply Airflow
BI	AHU-03D	Outside Air Damper Sts
BI	AHU-03D	Filter Status
BI	AHU-03D	Low Temp Alarm
BI	AHU-03D	Supply Air Smk Detector
CS	AHU-03D	All Points C.S.
BO	3A-FC02	Occupied Command
AI	3A-FC02	Zone Temp
AI	3A-FC02	Zone Setpoint
AOS	3A-FC02	Heating Valve Command
AOS	3A-FC02	Cooling Valve Command
BO	3A-FC02	Fan Command
BI	3A-FC02	Fan Status
BI	3A-FC02	Pan Alarm Status
CS	3A-FC02	Temp Occ.Status C.S.
BO	3A-FC03	Occupied Command
AI	3A-FC03	Zone Temp
AI	3A-FC03	Zone Setpoint
AOS	3A-FC03	Heating Valve Command
AOS	3A-FC03	Cooling Valve Command
BO	3A-FC03	Fan Command
BI	3A-FC03	Fan Status
BI	3A-FC03	Pan Alarm Status
CS	3A-FC03	Temp Occ.Status C.S.
BO	3A-FC04	Occupied Command
AI	3A-FC04	Zone Temp
AI	3A-FC04	Zone Setpoint
AOS	3A-FC04	Heating Valve Command
AOS	3A-FC04	Cooling Valve Command
BO	3A-FC04	Fan Command
BI	3A-FC04	Fan Status
BI	3A-FC04	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	3A-FC04	Temp Occ.Status C.S.
BO	3A-FC05	Occupied Command
AI	3A-FC05	Zone Temp
AI	3A-FC05	Zone Setpoint
AOS	3A-FC05	Cooling (only) Vlv Cmd
BO	3A-FC05	Fan Command
BI	3A-FC05	Fan Status
BI	3A-FC05	Pan Alarm Status
CS	3A-FC05	Temp Occ.Status C.S.
BO	3A-FC06	Occupied Command
AI	3A-FC06	Zone Temp
AI	3A-FC06	Zone Setpoint
AOS	3A-FC06	Heating Valve Command
AOS	3A-FC06	Cooling Valve Command
BO	3A-FC06	Fan Command
BI	3A-FC06	Fan Status
BI	3A-FC06	Pan Alarm Status
CS	3A-FC06	Temp Occ.Status C.S.
BO	3A-FC10	Occupied Command
AI	3A-FC10	Zone Temp
AI	3A-FC10	Zone Setpoint
AOS	3A-FC10	Heating Valve Command
AOS	3A-FC10	Cooling Valve Command
BO	3A-FC10	Fan Command
BI	3A-FC10	Fan Status
BI	3A-FC10	Pan Alarm Status
CS	3A-FC10	Temp Occ.Status C.S.
BO	3A-FC11	Occupied Command
AI	3A-FC11	Zone Temp
AI	3A-FC11	Zone Setpoint
AOS	3A-FC11	Heating Valve Command
AOS	3A-FC11	Cooling Valve Command
BO	3A-FC11	Fan Command
BI	3A-FC11	Fan Status
BI	3A-FC11	Pan Alarm Status
CS	3A-FC11	Temp Occ.Status C.S.
BO	3A-FC12	Occupied Command
AI	3A-FC12	Zone Temp
AI	3A-FC12	Zone Setpoint
AOS	3A-FC12	Heating Valve Command
AOS	3A-FC12	Cooling Valve Command
BO	3A-FC12	Fan Command
BI	3A-FC12	Fan Status
BI	3A-FC12	Pan Alarm Status
CS	3A-FC12	Temp Occ.Status C.S.
BO	3A-FC13	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	3A-FC13	Zone Temp
AI	3A-FC13	Zone Setpoint
AOS	3A-FC13	Heating Valve Command
AOS	3A-FC13	Cooling Valve Command
BO	3A-FC13	Fan Command
BI	3A-FC13	Fan Status
BI	3A-FC13	Pan Alarm Status
CS	3A-FC13	Temp Occ.Status C.S.
BO	3A-FC14	Occupied Command
AI	3A-FC14	Zone Temp
AI	3A-FC14	Zone Setpoint
AOS	3A-FC14	Heating Valve Command
AOS	3A-FC14	Cooling Valve Command
BO	3A-FC14	Fan Command
BI	3A-FC14	Fan Status
BI	3A-FC14	Pan Alarm Status
CS	3A-FC14	Temp Occ.Status C.S.
BO	3A-FC20	Occupied Command
AI	3A-FC20	Zone Temp
AI	3A-FC20	Zone Setpoint
AOS	3A-FC20	Heating Valve Command
AOS	3A-FC20	Cooling Valve Command
BO	3A-FC20	Fan Command
BI	3A-FC20	Fan Status
BI	3A-FC20	Pan Alarm Status
BO	3A-FC21	Occupied Command
AI	3A-FC21	Zone Temp
AI	3A-FC21	Zone Setpoint
AOS	3A-FC21	Heating Valve Command
AOS	3A-FC21	Cooling Valve Command
BO	3A-FC21	Fan Command
BI	3A-FC21	Fan Status
BI	3A-FC21	Pan Alarm Status
BO	3B-FC01	Occupied Command
AI	3B-FC01	Zone Temp
AI	3B-FC01	Zone Setpoint
AOS	3B-FC01	Heating Valve Command
AOS	3B-FC01	Cooling Valve Command
BO	3B-FC01	Fan Command
BI	3B-FC01	Fan Status
BI	3B-FC01	Pan Alarm Status
CS	3B-FC01	Temp Occ.Status C.S.
BO	3B-FC02	Occupied Command
AI	3B-FC02	Zone Temp
AI	3B-FC02	Zone Setpoint
AOS	3B-FC02	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	3B-FC02	Cooling Valve Command
BO	3B-FC02	Fan Command
BI	3B-FC02	Fan Status
BI	3B-FC02	Pan Alarm Status
CS	3B-FC02	Temp Occ.Status C.S.
BO	3B-FC03	Occupied Command
AI	3B-FC03	Zone Temp
AI	3B-FC03	Zone Setpoint
AOS	3B-FC03	Heating Valve Command
AOS	3B-FC03	Cooling Valve Command
BO	3B-FC03	Fan Command
BI	3B-FC03	Fan Status
BI	3B-FC03	Pan Alarm Status
CS	3B-FC03	Temp Occ.Status C.S.
BO	3B-FC04	Occupied Command
AI	3B-FC04	Zone Temp
AI	3B-FC04	Zone Setpoint
AOS	3B-FC04	Heating Valve Command
AOS	3B-FC04	Cooling Valve Command
BO	3B-FC04	Fan Command
BI	3B-FC04	Fan Status
BI	3B-FC04	Pan Alarm Status
CS	3B-FC04	Temp Occ.Status C.S.
BO	3B-FC05	Occupied Command
AI	3B-FC05	Zone Temp
AI	3B-FC05	Zone Setpoint
AOS	3B-FC05	Cooling Valve Command
BO	3B-FC05	Fan Command
BI	3B-FC05	Fan Status
BI	3B-FC05	Pan Alarm Status
CS	3B-FC05	Temp Occ.Status C.S.
BO	3B-FC06	Occupied Command
AI	3B-FC06	Zone Temp
AI	3B-FC06	Zone Setpoint
AOS	3B-FC06	Heating Valve Command
AOS	3B-FC06	Cooling Valve Command
BO	3B-FC06	Fan Command
BI	3B-FC06	Fan Status
BI	3B-FC06	Pan Alarm Status
CS	3B-FC06	Temp Occ.Status C.S.
BO	3B-FC09	Occupied Command
AI	3B-FC09	Zone Temp
AI	3B-FC09	Zone Setpoint
AOS	3B-FC09	Heating Valve Command
AOS	3B-FC09	Cooling Valve Command
BO	3B-FC09	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	3B-FC09	Fan Status
BI	3B-FC09	Pan Alarm Status
CS	3B-FC09	Temp Occ.Status C.S.
BO	3B-FC10	Occupied Command
AI	3B-FC10	Zone Temp
AI	3B-FC10	Zone Setpoint
AOS	3B-FC10	Heating Valve Command
AOS	3B-FC10	Cooling Valve Command
BO	3B-FC10	Fan Command
BI	3B-FC10	Fan Status
BI	3B-FC10	Pan Alarm Status
CS	3B-FC10	Temp Occ.Status C.S.
BO	3B-FC11	Occupied Command
AI	3B-FC11	Zone Temp
AI	3B-FC11	Zone Setpoint
AOS	3B-FC11	Heating Valve Command
AOS	3B-FC11	Cooling Valve Command
BO	3B-FC11	Fan Command
BI	3B-FC11	Fan Status
BI	3B-FC11	Pan Alarm Status
CS	3B-FC11	Temp Occ.Status C.S.
BO	3B-FC12	Occupied Command
AI	3B-FC12	Zone Temp
AI	3B-FC12	Zone Setpoint
AOS	3B-FC12	Heating Valve Command
AOS	3B-FC12	Cooling Valve Command
BO	3B-FC12	Fan Command
BI	3B-FC12	Fan Status
BI	3B-FC12	Pan Alarm Status
CS	3B-FC12	Temp Occ.Status C.S.
BO	3B-FC13	Occupied Command
AI	3B-FC13	Zone Temp
AI	3B-FC13	Zone Setpoint
AOS	3B-FC13	Heating Valve Command
AOS	3B-FC13	Cooling Valve Command
BO	3B-FC13	Fan Command
BI	3B-FC13	Fan Status
BI	3B-FC13	Pan Alarm Status
CS	3B-FC13	Temp Occ.Status C.S.
BO	3B-FC14	Occupied Command
AI	3B-FC14	Zone Temp
AI	3B-FC14	Zone Setpoint
AOS	3B-FC14	Heating Valve Command
AOS	3B-FC14	Cooling Valve Command
BO	3B-FC14	Fan Command
BI	3B-FC14	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	3B-FC14	Pan Alarm Status
CS	3B-FC14	Temp Occ.Status C.S.
BO	3C-FC01	Occupied Command
AI	3C-FC01	Zone Temp
AI	3C-FC01	Zone Setpoint
AOS	3C-FC01	Heating Valve Command
AOS	3C-FC01	Cooling Valve Command
BO	3C-FC01	Fan Command
BI	3C-FC01	Fan Status
BI	3C-FC01	Pan Alarm Status
CS	3C-FC01	Temp Occ.Status C.S.
BO	3C-FC02	Occupied Command
AI	3C-FC02	Zone Temp
AI	3C-FC02	Zone Setpoint
AOS	3C-FC02	Heating Valve Command
AOS	3C-FC02	Cooling Valve Command
BO	3C-FC02	Fan Command
BI	3C-FC02	Fan Status
BI	3C-FC02	Pan Alarm Status
CS	3C-FC02	Temp Occ.Status C.S.
BO	3C-FC03	Occupied Command
AI	3C-FC03	Zone Temp
AI	3C-FC03	Zone Setpoint
AOS	3C-FC03	Heating Valve Command
AOS	3C-FC03	Cooling Valve Command
BO	3C-FC03	Fan Command
BI	3C-FC03	Fan Status
BI	3C-FC03	Pan Alarm Status
CS	3C-FC03	Temp Occ.Status C.S.
BO	3C-FC04	Occupied Command
AI	3C-FC04	Zone Temp
AI	3C-FC04	Zone Setpoint
AOS	3C-FC04	Heating Valve Command
AOS	3C-FC04	Cooling Valve Command
BO	3C-FC04	Fan Command
BI	3C-FC04	Fan Status
BI	3C-FC04	Pan Alarm Status
CS	3C-FC04	Temp Occ.Status C.S.
BO	3C-FC06	Occupied Command
AI	3C-FC06	Zone Temp
AI	3C-FC06	Zone Setpoint
AOS	3C-FC06	Heating Valve Command
AOS	3C-FC06	Cooling Valve Command
BO	3C-FC06	Fan Command
BI	3C-FC06	Fan Status
BI	3C-FC06	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	3C-FC06	Temp Occ.Status C.S.
BO	3C-FC09	Occupied Command
AI	3C-FC09	Zone Temp
AI	3C-FC09	Zone Setpoint
AOS	3C-FC09	Heating Valve Command
AOS	3C-FC09	Cooling Valve Command
BO	3C-FC09	Fan Command
BI	3C-FC09	Fan Status
BI	3C-FC09	Pan Alarm Status
CS	3C-FC09	Temp Occ.Status C.S.
BO	3C-FC10	Occupied Command
AI	3C-FC10	Zone Temp
AI	3C-FC10	Zone Setpoint
AOS	3C-FC10	Heating Valve Command
AOS	3C-FC10	Cooling Valve Command
BO	3C-FC10	Fan Command
BI	3C-FC10	Fan Status
BI	3C-FC10	Pan Alarm Status
CS	3C-FC10	Temp Occ.Status C.S.
BO	3C-FC11	Occupied Command
AI	3C-FC11	Zone Temp
AI	3C-FC11	Zone Setpoint
AOS	3C-FC11	Heating Valve Command
AOS	3C-FC11	Cooling Valve Command
BO	3C-FC11	Fan Command
BI	3C-FC11	Fan Status
BI	3C-FC11	Pan Alarm Status
CS	3C-FC11	Temp Occ.Status C.S.
BO	3C-FC12	Occupied Command
AI	3C-FC12	Zone Temp
AI	3C-FC12	Zone Setpoint
AOS	3C-FC12	Heating Valve Command
AOS	3C-FC12	Cooling Valve Command
BO	3C-FC12	Fan Command
BI	3C-FC12	Fan Status
BI	3C-FC12	Pan Alarm Status
CS	3C-FC12	Temp Occ.Status C.S.
BO	3C-FC13	Occupied Command
AI	3C-FC13	Zone Temp
AI	3C-FC13	Zone Setpoint
AOS	3C-FC13	Heating Valve Command
AOS	3C-FC13	Cooling Valve Command
BO	3C-FC13	Fan Command
BI	3C-FC13	Fan Status
BI	3C-FC13	Pan Alarm Status
CS	3C-FC13	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	4B-FC08	Occupied Command
AI	4B-FC08	Zone Temp
AI	4B-FC08	Zone Setpoint
AOS	4B-FC08	Cooling Valve Command
AOS	4B-FC08	Heating Valve Command
BO	4B-FC08	Fan Command
BI	4B-FC08	Fan Status
BI	4B-FC08	Pan Alarm Status
CS	4B-FC08	Temp Occ.Status C.S.
BO	4C-FC08	Occupied Command
AI	4C-FC08	Zone Temp
AI	4C-FC08	Zone Setpoint
AOS	4C-FC08	Cooling Valve Command
AOS	4C-FC08	Heating Valve Command
BO	4C-FC08	Fan Command
BI	4C-FC08	Fan Status
BI	4C-FC08	Pan Alarm Status
CS	4C-FC08	Temp Occ.Status C.S.
BO	4C-FC05	Occupied Command
AI	4C-FC05	Zone Temp
AI	4C-FC05	Zone Setpoint
AOS	4C-FC05	Cooling Valve Command
AOS	4C-FC05	Heating Valve Command
BO	4C-FC05	Fan Command
BI	4C-FC05	Fan Status
BI	4C-FC05	Pan Alarm Status
CS	4C-FC05	Temp Occ.Status C.S.
BD	AHU-06AB	Fan Coil Occupied Commad
BD	AHU-06AB	
AI	AHU-06AB	Preheat Temp
AOS	AHU-06AB	Preheat Setpoint
AOS	AHU-06AB	Preheat Valve Command
AI	AHU-06AB	Preheat RetWtr Temp
BD	AHU-06AB	
AI	AHU-06AB	Outside Air Temp
AOS	AHU-06AB	Preheat Face/Bypass
AOS	AHU-06AB	Face And Bypass Setpoint
BD	AHU-06AB	Setpoint
AI	AHU-06AB	Cooling Coil Temp
AOS	AHU-06AB	Cooling Coil Setpoint
AOS	AHU-06AB	Cooling Valve Command
AI	AHU-06AB	Cooiling RetWtr Temp
BD	AHU-06AB	
AI	AHU-06AB	Reheat Temp
AOS	AHU-06AB	Reheat Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	AHU-06AB	Reheat Valve Command
AI	AHU-06AB	Reheat RetWtr Temp
BD	AHU-06AB	
BO	AHU-06AB	Supply Fan Command
BI	AHU-06AB	Supply Airflow
BI	AHU-06AB	Outside Air Damper Sts
BI	AHU-06AB	Filter Status
BI	AHU-06AB	Low Temp Alarm
BI	AHU-06AB	Supply Air Smk Detector
CS	AHU-06AB	All Points C.S.
BD	AHU-05AB	Fan Coil Occupied Commad
BD	AHU-05AB	
AI	AHU-05AB	Preheat Temp
AOS	AHU-05AB	Preheat Setpoint
AOS	AHU-05AB	Preheat Valve Command
AI	AHU-05AB	Preheat RetWtr Temp
BD	AHU-05AB	
AI	AHU-05AB	Outside Air Temp
AOS	AHU-05AB	Preheat Face/Bypass
AOS	AHU-05AB	Face And Bypass Setpoint
BD	AHU-05AB	Setpoint
AI	AHU-05AB	Cooling Coil Temp
AOS	AHU-05AB	Cooling Coil Setpoint
AOS	AHU-05AB	Cooling Valve Command
AI	AHU-05AB	Cooiling RetWtr Temp
BD	AHU-05AB	
AI	AHU-05AB	Reheat Temp
AOS	AHU-05AB	Reheat Setpoint
AOS	AHU-05AB	Reheat Valve Command
AI	AHU-05AB	Reheat RetWtr Temp
BD	AHU-05AB	
BO	AHU-05AB	Supply Fan Command
BI	AHU-05AB	Supply Airflow
BI	AHU-05AB	Outside Air Damper Sts
BI	AHU-05AB	Filter Status
BI	AHU-05AB	Low Temp Alarm
BI	AHU-05AB	Supply Air Smk Detector
CS	AHU-05AB	All Points C.S.
JCB	AHU-05AB	
BD	AHU-05C	Fan Coil Occupied Commad
BD	AHU-05C	
AI	AHU-05C	Preheat Temp
AOS	AHU-05C	Preheat Setpoint
AOS	AHU-05C	Preheat Valve Command
AI	AHU-05C	Preheat RetWtr Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BD	AHU-05C	
AI	AHU-05C	Outside Air Temp
AOS	AHU-05C	Preheat Face/Bypass
AOS	AHU-05C	Face And Bypass Setpoint
BD	AHU-05C	Setpoint
AI	AHU-05C	Cooling Coil Temp
AOS	AHU-05C	Cooling Coil Setpoint
AOS	AHU-05C	Cooling Valve Command
AI	AHU-05C	Cooiling RetWtr Temp
BD	AHU-05C	
AI	AHU-05C	Reheat Temp
AOS	AHU-05C	Reheat Setpoint
AOS	AHU-05C	Reheat Valve Command
AI	AHU-05C	Reheat RetWtr Temp
BD	AHU-05C	
BO	AHU-05C	Supply Fan Command
BI	AHU-05C	Supply Airflow
BI	AHU-05C	Outside Air Damper Sts
BI	AHU-05C	Filter Status
BI	AHU-05C	Low Temp Alarm
BI	AHU-05C	Supply Air Smk Detector
CS	AHU-05C	All Points C.S.
BO	4A-FC10	Occupied Command
AI	4A-FC10	Zone Temp
AI	4A-FC10	Zone Setpoint
AOS	4A-FC10	Cooling Valve Command
BO	4A-FC10	Fan Command
BI	4A-FC10	Fan Status
BI	4A-FC10	Pan Alarm Status
CS	4A-FC10	Temp Occ.Status C.S.
AOS	4A-FC10	HEATING Valve Command
BO	4A-FC16	Occupied Command
AI	4A-FC16	Zone Temp
AI	4A-FC16	Zone Setpoint
AOS	4A-FC16	Cooling Valve Command
BO	4A-FC16	Fan Command
BI	4A-FC16	Fan Status
BI	4A-FC16	Pan Alarm Status
CS	4A-FC16	Temp Occ.Status C.S.
AOS	4A-FC16	Heating Valve Command
BO	4A-FC11	Occupied Command
AI	4A-FC11	Zone Temp
AI	4A-FC11	Zone Setpoint
AOS	4A-FC11	Cooling Valve Command
BO	4A-FC11	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	4A-FC11	Fan Status
BI	4A-FC11	Pan Alarm Status
CS	4A-FC11	Temp Occ.Status C.S.
AOS	4A-FC11	Heating Valve Command
BO	4C-FC07	Occupied Command
AI	4C-FC07	Zone Temp
AI	4C-FC07	Zone Setpoint
AOS	4C-FC07	Cooling Valve Command
AOS	4C-FC07	Heating Valve Command
BO	4C-FC07	Fan Command
BI	4C-FC07	Fan Status
BI	4C-FC07	Pan Alarm Status
CS	4C-FC07	Temp Occ.Status C.S.
BO	4C-FC49	Occupied Command
AI	4C-FC49	Zone Temp
AI	4C-FC49	Zone Setpoint
AOS	4C-FC49	Heating Valve Command
AOS	4C-FC49	Cooling Valve Command
BO	4C-FC49	Fan Command
BI	4C-FC49	Fan Status
BI	4C-FC49	Pan Alarm Status
CS	4C-FC49	Temp Occ.Status C.S.
BO	4C-FC48	Occupied Command
AI	4C-FC48	Zone Temp
AI	4C-FC48	Zone Setpoint
AOS	4C-FC48	Heating Valve Command
AOS	4C-FC48	Cooling Valve Command
BO	4C-FC48	Fan Command
BI	4C-FC48	Fan Status
BI	4C-FC48	Pan Alarm Status
CS	4C-FC48	Temp Occ.Status C.S.
BO	4C-FC47	Occupied Command
AI	4C-FC47	Zone Temp
AI	4C-FC47	Zone Setpoint
AOS	4C-FC47	Heating Valve Command
AOS	4C-FC47	Cooling Valve Command
BO	4C-FC47	Fan Command
BI	4C-FC47	Fan Status
BI	4C-FC47	Pan Alarm Status
CS	4C-FC47	Temp Occ.Status C.S.
BO	4C-FC46	Occupied Command
AI	4C-FC46	Zone Temp
AI	4C-FC46	Zone Setpoint
AOS	4C-FC46	Heating Valve Command
AOS	4C-FC46	Cooling Valve Command
BO	4C-FC46	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	4C-FC46	Fan Status
BI	4C-FC46	Pan Alarm Status
CS	4C-FC46	Temp Occ.Status C.S.
BO	4C-FC45	Occupied Command
AI	4C-FC45	Zone Temp
AI	4C-FC45	Zone Setpoint
AOS	4C-FC45	Heating Valve Command
AOS	4C-FC45	Cooling Valve Command
BO	4C-FC45	Fan Command
BI	4C-FC45	Fan Status
BI	4C-FC45	Pan Alarm Status
CS	4C-FC45	Temp Occ.Status C.S.
BO	4C-FC44	Occupied Command
AI	4C-FC44	Zone Temp
AI	4C-FC44	Zone Setpoint
AOS	4C-FC44	Heating Valve Command
AOS	4C-FC44	Cooling Valve Command
BO	4C-FC44	Fan Command
BI	4C-FC44	Fan Status
BI	4C-FC44	Pan Alarm Status
CS	4C-FC44	Temp Occ.Status C.S.
BO	4C-FC43	Occupied Command
AI	4C-FC43	Zone Temp
AI	4C-FC43	Zone Setpoint
AOS	4C-FC43	Heating Valve Command
AOS	4C-FC43	Cooling Valve Command
BO	4C-FC43	Fan Command
BI	4C-FC43	Fan Status
BI	4C-FC43	Pan Alarm Status
CS	4C-FC43	Temp Occ.Status C.S.
BO	4C-FC42	Occupied Command
AI	4C-FC42	Zone Temp
AI	4C-FC42	Zone Setpoint
AOS	4C-FC42	Heating Valve Command
AOS	4C-FC42	Cooling Valve Command
BO	4C-FC42	Fan Command
BI	4C-FC42	Fan Status
BI	4C-FC42	Pan Alarm Status
CS	4C-FC42	Temp Occ.Status C.S.
BO	4C-FC41	Occupied Command
AI	4C-FC41	Zone Temp
AI	4C-FC41	Zone Setpoint
AOS	4C-FC41	Heating Valve Command
AOS	4C-FC41	Cooling Valve Command
BO	4C-FC41	Fan Command
BI	4C-FC41	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	4C-FC41	Pan Alarm Status
CS	4C-FC41	Temp Occ.Status C.S.
BO	4C-FC40	Occupied Command
AI	4C-FC40	Zone Temp
AI	4C-FC40	Zone Setpoint
AOS	4C-FC40	Heating Valve Command
AOS	4C-FC40	Cooling Valve Command
BO	4C-FC40	Fan Command
BI	4C-FC40	Fan Status
BI	4C-FC40	Pan Alarm Status
CS	4C-FC40	Temp Occ.Status C.S.
BO	4C-FC39	Occupied Command
AI	4C-FC39	Zone Temp
AI	4C-FC39	Zone Setpoint
AOS	4C-FC39	Heating Valve Command
AOS	4C-FC39	Cooling Valve Command
BO	4C-FC39	Fan Command
BI	4C-FC39	Fan Status
BI	4C-FC39	Pan Alarm Status
CS	4C-FC39	Temp Occ.Status C.S.
BO	4C-FC38	Occupied Command
AI	4C-FC38	Zone Temp
AI	4C-FC38	Zone Setpoint
AOS	4C-FC38	Heating Valve Command
AOS	4C-FC38	Cooling Valve Command
BO	4C-FC38	Fan Command
BI	4C-FC38	Fan Status
BI	4C-FC38	Pan Alarm Status
CS	4C-FC38	Temp Occ.Status C.S.
BO	4C-FC37	Occupied Command
AI	4C-FC37	Zone Temp
AI	4C-FC37	Zone Setpoint
AOS	4C-FC37	Heating Valve Command
AOS	4C-FC37	Cooling Valve Command
BO	4C-FC37	Fan Command
BI	4C-FC37	Fan Status
BI	4C-FC37	Pan Alarm Status
CS	4C-FC37	Temp Occ.Status C.S.
BO	4C-FC36	Occupied Command
AI	4C-FC36	Zone Temp
AI	4C-FC36	Zone Setpoint
AOS	4C-FC36	Heating Valve Command
AOS	4C-FC36	Cooling Valve Command
BO	4C-FC36	Fan Command
BI	4C-FC36	Fan Status
BI	4C-FC36	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	4C-FC36	Temp Occ.Status C.S.
BO	4C-FC35	Occupied Command
AI	4C-FC35	Zone Temp
AI	4C-FC35	Zone Setpoint
AOS	4C-FC35	Heating Valve Command
AOS	4C-FC35	Cooling Valve Command
BO	4C-FC35	Fan Command
BI	4C-FC35	Fan Status
BI	4C-FC35	Pan Alarm Status
CS	4C-FC35	Temp Occ.Status C.S.
BO	4C-FC34	Occupied Command
AI	4C-FC34	Zone Temp
AI	4C-FC34	Zone Setpoint
AOS	4C-FC34	Heating Valve Command
AOS	4C-FC34	Cooling Valve Command
BO	4C-FC34	Fan Command
BI	4C-FC34	Fan Status
BI	4C-FC34	Pan Alarm Status
CS	4C-FC34	Temp Occ.Status C.S.
BO	4C-FC33	Occupied Command
AI	4C-FC33	Zone Temp
AI	4C-FC33	Zone Setpoint
AOS	4C-FC33	Heating Valve Command
AOS	4C-FC33	Cooling Valve Command
BO	4C-FC33	Fan Command
BI	4C-FC33	Fan Status
BI	4C-FC33	Pan Alarm Status
CS	4C-FC33	Temp Occ.Status C.S.
BO	4C-FC32	Occupied Command
AI	4C-FC32	Zone Temp
AI	4C-FC32	Zone Setpoint
AOS	4C-FC32	Heating Valve Command
AOS	4C-FC32	Cooling Valve Command
BO	4C-FC32	Fan Command
BI	4C-FC32	Fan Status
BI	4C-FC32	Pan Alarm Status
CS	4C-FC32	Temp Occ.Status C.S.
BO	4C-FC31	Occupied Command
AI	4C-FC31	Zone Temp
AI	4C-FC31	Zone Setpoint
AOS	4C-FC31	Heating Valve Command
AOS	4C-FC31	Cooling Valve Command
BO	4C-FC31	Fan Command
BI	4C-FC31	Fan Status
BI	4C-FC31	Pan Alarm Status
CS	4C-FC31	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	4C-FC30	Occupied Command
AI	4C-FC30	Zone Temp
AI	4C-FC30	Zone Setpoint
AOS	4C-FC30	Heating Valve Command
AOS	4C-FC30	Cooling Valve Command
BO	4C-FC30	Fan Command
BI	4C-FC30	Fan Status
BI	4C-FC30	Pan Alarm Status
CS	4C-FC30	Temp Occ.Status C.S.
BO	4C-FC29	Occupied Command
AI	4C-FC29	Zone Temp
AI	4C-FC29	Zone Setpoint
AOS	4C-FC29	Heating Valve Command
AOS	4C-FC29	Cooling Valve Command
BO	4C-FC29	Fan Command
BI	4C-FC29	Fan Status
BI	4C-FC29	Pan Alarm Status
CS	4C-FC29	Temp Occ.Status C.S.
BO	4C-FC28	Occupied Command
AI	4C-FC28	Zone Temp
AI	4C-FC28	Zone Setpoint
AOS	4C-FC28	Heating Valve Command
AOS	4C-FC28	Cooling Valve Command
BO	4C-FC28	Fan Command
BI	4C-FC28	Fan Status
BI	4C-FC28	Pan Alarm Status
CS	4C-FC28	Temp Occ.Status C.S.
BO	4C-FC27	Occupied Command
AI	4C-FC27	Zone Temp
AI	4C-FC27	Zone Setpoint
AOS	4C-FC27	Heating Valve Command
AOS	4C-FC27	Cooling Valve Command
BO	4C-FC27	Fan Command
BI	4C-FC27	Fan Status
BI	4C-FC27	Pan Alarm Status
CS	4C-FC27	Temp Occ.Status C.S.
BO	4C-FC26	Occupied Command
AI	4C-FC26	Zone Temp
AI	4C-FC26	Zone Setpoint
AOS	4C-FC26	Heating Valve Command
AOS	4C-FC26	Cooling Valve Command
BO	4C-FC26	Fan Command
BI	4C-FC26	Fan Status
BI	4C-FC26	Pan Alarm Status
CS	4C-FC26	Temp Occ.Status C.S.
BO	4C-FC25	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	4C-FC25	Zone Temp
AI	4C-FC25	Zone Setpoint
AOS	4C-FC25	Heating Valve Command
AOS	4C-FC25	Cooling Valve Command
BO	4C-FC25	Fan Command
BI	4C-FC25	Fan Status
BI	4C-FC25	Pan Alarm Status
CS	4C-FC25	Temp Occ.Status C.S.
BO	4C-FC24	Occupied Command
AI	4C-FC24	Zone Temp
AI	4C-FC24	Zone Setpoint
AOS	4C-FC24	Heating Valve Command
AOS	4C-FC24	Cooling Valve Command
BO	4C-FC24	Fan Command
BI	4C-FC24	Fan Status
BI	4C-FC24	Pan Alarm Status
CS	4C-FC24	Temp Occ.Status C.S.
BO	4C-FC23	Occupied Command
AI	4C-FC23	Zone Temp
AI	4C-FC23	Zone Setpoint
AOS	4C-FC23	Heating Valve Command
AOS	4C-FC23	Cooling Valve Command
BO	4C-FC23	Fan Command
BI	4C-FC23	Fan Status
BI	4C-FC23	Pan Alarm Status
CS	4C-FC23	Temp Occ.Status C.S.
BO	4C-FC22	Occupied Command
AI	4C-FC22	Zone Temp
AI	4C-FC22	Zone Setpoint
AOS	4C-FC22	Heating Valve Command
AOS	4C-FC22	Cooling Valve Command
BO	4C-FC22	Fan Command
BI	4C-FC22	Fan Status
BI	4C-FC22	Pan Alarm Status
CS	4C-FC22	Temp Occ.Status C.S.
BO	4C-FC21	Occupied Command
AI	4C-FC21	Zone Temp
AI	4C-FC21	Zone Setpoint
AOS	4C-FC21	Heating Valve Command
AOS	4C-FC21	Cooling Valve Command
BO	4C-FC21	Fan Command
BI	4C-FC21	Fan Status
BI	4C-FC21	Pan Alarm Status
CS	4C-FC21	Temp Occ.Status C.S.
BO	4C-FC20	Occupied Command
AI	4C-FC20	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	4C-FC20	Zone Setpoint
AOS	4C-FC20	Heating Valve Command
AOS	4C-FC20	Cooling Valve Command
BO	4C-FC20	Fan Command
BI	4C-FC20	Fan Status
BI	4C-FC20	Pan Alarm Status
CS	4C-FC20	Temp Occ.Status C.S.
BO	4C-FC19	Occupied Command
AI	4C-FC19	Zone Temp
AI	4C-FC19	Zone Setpoint
AOS	4C-FC19	Heating Valve Command
AOS	4C-FC19	Cooling Valve Command
BO	4C-FC19	Fan Command
BI	4C-FC19	Fan Status
BI	4C-FC19	Pan Alarm Status
CS	4C-FC19	Temp Occ.Status C.S.
BO	4C-FC18	Occupied Command
AI	4C-FC18	Zone Temp
AI	4C-FC18	Zone Setpoint
AOS	4C-FC18	Heating Valve Command
AOS	4C-FC18	Cooling Valve Command
BO	4C-FC18	Fan Command
BI	4C-FC18	Fan Status
BI	4C-FC18	Pan Alarm Status
CS	4C-FC18	Temp Occ.Status C.S.
BO	4C-FC17	Occupied Command
AI	4C-FC17	Zone Temp
AI	4C-FC17	Zone Setpoint
AOS	4C-FC17	Heating Valve Command
AOS	4C-FC17	Cooling Valve Command
BO	4C-FC17	Fan Command
BI	4C-FC17	Fan Status
BI	4C-FC17	Pan Alarm Status
CS	4C-FC17	Temp Occ.Status C.S.
BO	4C-FC16	Occupied Command
AI	4C-FC16	Zone Temp
AI	4C-FC16	Zone Setpoint
AOS	4C-FC16	Heating Valve Command
AOS	4C-FC16	Cooling Valve Command
BO	4C-FC16	Fan Command
BI	4C-FC16	Fan Status
BI	4C-FC16	Pan Alarm Status
CS	4C-FC16	Temp Occ.Status C.S.
BO	4C-FC15	Occupied Command
AI	4C-FC15	Zone Temp
AI	4C-FC15	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	4C-FC15	Heating Valve Command
AOS	4C-FC15	Cooling Valve Command
BO	4C-FC15	Fan Command
BI	4C-FC15	Fan Status
BI	4C-FC15	Pan Alarm Status
CS	4C-FC15	Temp Occ.Status C.S.
BO	4C-FC14	Occupied Command
AI	4C-FC14	Zone Temp
AI	4C-FC14	Zone Setpoint
AOS	4C-FC14	Heating Valve Command
AOS	4C-FC14	Cooling Valve Command
BO	4C-FC14	Fan Command
BI	4C-FC14	Fan Status
BI	4C-FC14	Pan Alarm Status
CS	4C-FC14	Temp Occ.Status C.S.
BO	4C-FC13	Occupied Command
AI	4C-FC13	Zone Temp
AI	4C-FC13	Zone Setpoint
AOS	4C-FC13	Heating Valve Command
AOS	4C-FC13	Cooling Valve Command
BO	4C-FC13	Fan Command
BI	4C-FC13	Fan Status
BI	4C-FC13	Pan Alarm Status
CS	4C-FC13	Temp Occ.Status C.S.
BO	4C-FC12	Occupied Command
AI	4C-FC12	Zone Temp
AI	4C-FC12	Zone Setpoint
AOS	4C-FC12	Heating Valve Command
AOS	4C-FC12	Cooling Valve Command
BO	4C-FC12	Fan Command
BI	4C-FC12	Fan Status
BI	4C-FC12	Pan Alarm Status
CS	4C-FC12	Temp Occ.Status C.S.
BO	4C-FC11	Occupied Command
AI	4C-FC11	Zone Temp
AI	4C-FC11	Zone Setpoint
AOS	4C-FC11	Heating Valve Command
AOS	4C-FC11	Cooling Valve Command
BO	4C-FC11	Fan Command
BI	4C-FC11	Fan Status
BI	4C-FC11	Pan Alarm Status
CS	4C-FC11	Temp Occ.Status C.S.
BO	4C-FC10	Occupied Command
AI	4C-FC10	Zone Temp
AI	4C-FC10	Zone Setpoint
AOS	4C-FC10	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	4C-FC10	Cooling Valve Command
BO	4C-FC10	Fan Command
BI	4C-FC10	Fan Status
BI	4C-FC10	Pan Alarm Status
CS	4C-FC10	Temp Occ.Status C.S.
BO	4C-FC09	Occupied Command
AI	4C-FC09	Zone Temp
AI	4C-FC09	Zone Setpoint
AOS	4C-FC09	Heating Valve Command
AOS	4C-FC09	Cooling Valve Command
BO	4C-FC09	Fan Command
BI	4C-FC09	Fan Status
BI	4C-FC09	Pan Alarm Status
CS	4C-FC09	Temp Occ.Status C.S.
BO	4C-FC06	Occupied Command
AI	4C-FC06	Zone Temp
AI	4C-FC06	Zone Setpoint
AOS	4C-FC06	Heating Valve Command
AOS	4C-FC06	Cooling Valve Command
BO	4C-FC06	Fan Command
BI	4C-FC06	Fan Status
BI	4C-FC06	Pan Alarm Status
CS	4C-FC06	Temp Occ.Status C.S.
BO	4C-FC04	Occupied Command
AI	4C-FC04	Zone Temp
AI	4C-FC04	Zone Setpoint
AOS	4C-FC04	Heating Valve Command
AOS	4C-FC04	Cooling Valve Command
BO	4C-FC04	Fan Command
BI	4C-FC04	Fan Status
BI	4C-FC04	Pan Alarm Status
CS	4C-FC04	Temp Occ.Status C.S.
BO	4C-FC03	Occupied Command
AI	4C-FC03	Zone Temp
AI	4C-FC03	Zone Setpoint
AOS	4C-FC03	Heating Valve Command
AOS	4C-FC03	Cooling Valve Command
BO	4C-FC03	Fan Command
BI	4C-FC03	Fan Status
BI	4C-FC03	Pan Alarm Status
CS	4C-FC03	Temp Occ.Status C.S.
BO	4C-FC02	Occupied Command
AI	4C-FC02	Zone Temp
AI	4C-FC02	Zone Setpoint
AOS	4C-FC02	Heating Valve Command
AOS	4C-FC02	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	4C-FC02	Fan Command
BI	4C-FC02	Fan Status
BI	4C-FC02	Pan Alarm Status
CS	4C-FC02	Temp Occ.Status C.S.
BO	4C-FC01	Occupied Command
AI	4C-FC01	Zone Temp
AI	4C-FC01	Zone Setpoint
AOS	4C-FC01	Heating Valve Command
AOS	4C-FC01	Cooling Valve Command
BO	4C-FC01	Fan Command
BI	4C-FC01	Fan Status
BI	4C-FC01	Pan Alarm Status
CS	4C-FC01	Temp Occ.Status C.S.
BO	4B-FC12	Occupied Command
AI	4B-FC12	Zone Temp
AI	4B-FC12	Zone Setpoint
AOS	4B-FC12	Heating Valve Command
AOS	4B-FC12	Cooling Valve Command
BO	4B-FC12	Fan Command
BI	4B-FC12	Fan Status
BI	4B-FC12	Pan Alarm Status
CS	4B-FC12	Temp Occ.Status C.S.
BO	4B-FC11	Occupied Command
AI	4B-FC11	Zone Temp
AI	4B-FC11	Zone Setpoint
AOS	4B-FC11	Heating Valve Command
AOS	4B-FC11	Cooling Valve Command
BO	4B-FC11	Fan Command
BI	4B-FC11	Fan Status
BI	4B-FC11	Pan Alarm Status
CS	4B-FC11	Temp Occ.Status C.S.
BO	4B-FC10	Occupied Command
AI	4B-FC10	Zone Temp
AI	4B-FC10	Zone Setpoint
AOS	4B-FC10	Heating Valve Command
AOS	4B-FC10	Cooling Valve Command
BO	4B-FC10	Fan Command
BI	4B-FC10	Fan Status
BI	4B-FC10	Pan Alarm Status
CS	4B-FC10	Temp Occ.Status C.S.
BO	4B-FC09	Occupied Command
AI	4B-FC09	Zone Temp
AI	4B-FC09	Zone Setpoint
AOS	4B-FC09	Heating Valve Command
AOS	4B-FC09	Cooling Valve Command
BO	4B-FC09	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	4B-FC09	Fan Status
BI	4B-FC09	Pan Alarm Status
CS	4B-FC09	Temp Occ.Status C.S.
BO	4B-FC07	Occupied Command
AI	4B-FC07	Zone Temp
AI	4B-FC07	Zone Setpoint
AOS	4B-FC07	Heating Valve Command
AOS	4B-FC07	Cooling Valve Command
BO	4B-FC07	Fan Command
BI	4B-FC07	Fan Status
BI	4B-FC07	Pan Alarm Status
CS	4B-FC07	Temp Occ.Status C.S.
BO	4B-FC06	Occupied Command
AI	4B-FC06	Zone Temp
AI	4B-FC06	Zone Setpoint
AOS	4B-FC06	Heating Valve Command
AOS	4B-FC06	Cooling Valve Command
BO	4B-FC06	Fan Command
BI	4B-FC06	Fan Status
BI	4B-FC06	Pan Alarm Status
CS	4B-FC06	Temp Occ.Status C.S.
BO	4B-FC05	Occupied Command
AI	4B-FC05	Zone Temp
AI	4B-FC05	Zone Setpoint
AOS	4B-FC05	Heating Valve Command
AOS	4B-FC05	Cooling Valve Command
BO	4B-FC05	Fan Command
BI	4B-FC05	Fan Status
BI	4B-FC05	Pan Alarm Status
CS	4B-FC05	Temp Occ.Status C.S.
BO	4B-FC03	Occupied Command
AI	4B-FC03	Zone Temp
AI	4B-FC03	Zone Setpoint
AOS	4B-FC03	Heating Valve Command
AOS	4B-FC03	Cooling Valve Command
BO	4B-FC03	Fan Command
BI	4B-FC03	Fan Status
BI	4B-FC03	Pan Alarm Status
CS	4B-FC03	Temp Occ.Status C.S.
BO	4B-FC02	Occupied Command
AI	4B-FC02	Zone Temp
AI	4B-FC02	Zone Setpoint
AOS	4B-FC02	Heating Valve Command
AOS	4B-FC02	Cooling Valve Command
BO	4B-FC02	Fan Command
BI	4B-FC02	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	4B-FC02	Pan Alarm Status
CS	4B-FC02	Temp Occ.Status C.S.
BO	4B-FC01	Occupied Command
AI	4B-FC01	Zone Temp
AI	4B-FC01	Zone Setpoint
AOS	4B-FC01	Heating Valve Command
AOS	4B-FC01	Cooling Valve Command
BO	4B-FC01	Fan Command
BI	4B-FC01	Fan Status
BI	4B-FC01	Pan Alarm Status
CS	4B-FC01	Temp Occ.Status C.S.
BO	4A-FC09	Occupied Command
AI	4A-FC09	Zone Temp
AI	4A-FC09	Zone Setpoint
AOS	4A-FC09	Heating Valve Command
AOS	4A-FC09	Cooling Valve Command
BO	4A-FC09	Fan Command
BI	4A-FC09	Fan Status
BI	4A-FC09	Pan Alarm Status
CS	4A-FC09	Temp Occ.Status C.S.
BO	4A-FC08	Occupied Command
AI	4A-FC08	Zone Temp
AI	4A-FC08	Zone Setpoint
AOS	4A-FC08	Heating Valve Command
AOS	4A-FC08	Cooling Valve Command
BO	4A-FC08	Fan Command
BI	4A-FC08	Fan Status
BI	4A-FC08	Pan Alarm Status
CS	4A-FC08	Temp Occ.Status C.S.
BO	4A-FC07	Occupied Command
AI	4A-FC07	Zone Temp
AI	4A-FC07	Zone Setpoint
AOS	4A-FC07	Heating Valve Command
AOS	4A-FC07	Cooling Valve Command
BO	4A-FC07	Fan Command
BI	4A-FC07	Fan Status
BI	4A-FC07	Pan Alarm Status
CS	4A-FC07	Temp Occ.Status C.S.
BO	4A-FC05	Occupied Command
AI	4A-FC05	Zone Temp
AI	4A-FC05	Zone Setpoint
AOS	4A-FC05	Heating Valve Command
AOS	4A-FC05	Cooling Valve Command
BO	4A-FC05	Fan Command
BI	4A-FC05	Fan Status
BI	4A-FC05	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	4A-FC05	Temp Occ.Status C.S.
BO	4A-FC04	Occupied Command
AI	4A-FC04	Zone Temp
AI	4A-FC04	Zone Setpoint
AOS	4A-FC04	Heating Valve Command
AOS	4A-FC04	Cooling Valve Command
BO	4A-FC04	Fan Command
BI	4A-FC04	Fan Status
BI	4A-FC04	Pan Alarm Status
CS	4A-FC04	Temp Occ.Status C.S.
BO	4A-FC03	Occupied Command
AI	4A-FC03	Zone Temp
AI	4A-FC03	Zone Setpoint
AOS	4A-FC03	Heating Valve Command
AOS	4A-FC03	Cooling Valve Command
BO	4A-FC03	Fan Command
BI	4A-FC03	Fan Status
BI	4A-FC03	Pan Alarm Status
CS	4A-FC03	Temp Occ.Status C.S.
BO	4A-FC02	Occupied Command
AI	4A-FC02	Zone Temp
AI	4A-FC02	Zone Setpoint
AOS	4A-FC02	Heating Valve Command
AOS	4A-FC02	Cooling Valve Command
BO	4A-FC02	Fan Command
BI	4A-FC02	Fan Status
BI	4A-FC02	Pan Alarm Status
CS	4A-FC02	Temp Occ.Status C.S.
BO	4A-FC01	Occupied Command
AI	4A-FC01	Zone Temp
AI	4A-FC01	Zone Setpoint
AOS	4A-FC01	Heating Valve Command
AOS	4A-FC01	Cooling Valve Command
BO	4A-FC01	Fan Command
BI	4A-FC01	Fan Status
BI	4A-FC01	Pan Alarm Status
CS	4A-FC01	Temp Occ.Status C.S.
BO	MISC-4	ExFan 4C Command
BI	MISC-4	ExFan 4C Status
BD	MISC-4	4AOCCMD
BD	MISC-4	4BOCCMD
BD	AHU-06C	Fan Coil Occupied Commad
BD	AHU-06C	
AI	AHU-06C	Preheat Temp
AOS	AHU-06C	Preheat Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	AHU-06C	Preheat Valve Command
AI	AHU-06C	Preheat RetWtr Temp
BD	AHU-06C	
AI	AHU-06C	Outside Air Temp
AOS	AHU-06C	Preheat Face/Bypass
AOS	AHU-06C	Face And Bypass Setpoint
BD	AHU-06C	Setpoint
AI	AHU-06C	Cooling Coil Temp
AOS	AHU-06C	Cooling Coil Setpoint
AOS	AHU-06C	Cooling Valve Command
AI	AHU-06C	Cooiling RetWtr Temp
BD	AHU-06C	
AI	AHU-06C	Reheat Temp
AOS	AHU-06C	Reheat Setpoint
AOS	AHU-06C	Reheat Valve Command
AI	AHU-06C	Reheat RetWtr Temp
BD	AHU-06C	
BO	AHU-06C	Supply Fan Command
BI	AHU-06C	Supply Airflow
BI	AHU-06C	Outside Air Damper Sts
BI	AHU-06C	Filter Status
BI	AHU-06C	Low Temp Alarm
BI	AHU-06C	Supply Air Smk Detector
CS	AHU-06C	All Points C.S.
JCB	AHU-06C	6COCCMD
BO	4A-FC15	Occupied Command
AI	4A-FC15	Zone Temp
AI	4A-FC15	Zone Setpoint
AOS	4A-FC15	Cooling Vlv Cmd (ONLY)
BO	4A-FC15	Fan Command
BI	4A-FC15	Fan Status
BI	4A-FC15	Pan Alarm Status
CS	4A-FC15	Temp Occ.Status C.S.
BO	4A-FC14	Occupied Command
AI	4A-FC14	Zone Temp
AI	4A-FC14	Zone Setpoint
AOS	4A-FC14	Cooling Vlv Cmd (ONLY)
BO	4A-FC14	Fan Command
BI	4A-FC14	Fan Status
BI	4A-FC14	Pan Alarm Status
CS	4A-FC14	Temp Occ.Status C.S.
	Building 3	
Point	Equipment	Type
	NC-14	Network controller
NC14-HRW	5A-FC01	42, 1, 3, VAV
NC14-HRW	5A-FC02	45, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC14-HRW	6B-FC08	153, 1, 3, VAV
NC14-HRW	5A-FC03	50, 1, 3, VAV
NC14-HRW	5A-FC04	53, 1, 3, VAV
NC14-HRW	5A-FC05	54, 1, 3, VAV
NC14-HRW	5A-FC06	57, 1, 3, VAV
NC14-HRW	5A-FC07	59, 1, 3, VAV
NC14-HRW	5A-FC08	63, 1, 3, VAV
NC14-HRW	5A-FC09	65, 1, 3, VAV
NC14-HRW	5A-FC10	69, 1, 3, VAV
NC14-HRW	5B-FC01	100, 1, 3, VAV
NC14-HRW	5B-FC02	73, 1, 3, VAV
NC14-HRW	5B-FC03	77, 1, 3, VAV
NC14-HRW	5B-FC04	85, 1, 3, VAV
NC14-HRW	5B-FC05	88, 1, 3, VAV
NC14-HRW	5B-FC06	90, 1, 3, VAV
NC14-HRW	5B-FC07	92, 1, 3, VAV
NC14-HRW	5B-FC08	98, 1, 3, VAV
NC14-HRW	5B-FC09	104, 1, 3, VAV
NC14-HRW	5B-FC10	106, 1, 3, VAV
NC14-HRW	5B-FC11	108, 1, 3, VAV
NC14-HRW	5B-FC12	109, 1, 3, VAV
NC14-HRW	5B-FC13	112, 1, 3, VAV
NC14-HRW	5C-FC01	1, 1, 3, VAV
NC14-HRW	5C-FC02	2, 1, 3, VAV
NC14-HRW	5C-FC03	3, 1, 3, VAV
NC14-HRW	5C-FC04	4, 1, 3, VAV
NC14-HRW	5C-FC05	5, 1, 3, VAV
NC14-HRW	5C-FC06	6, 1, 3, VAV
NC14-HRW	5C-FC07	7, 1, 3, VAV
NC14-HRW	5C-FC08	8, 1, 3, VAV
NC14-HRW	5C-FC09	9, 1, 3, VAV
NC14-HRW	5C-FC10	10, 1, 3, VAV
NC14-HRW	5C-FC11	11, 1, 3, VAV
NC14-HRW	5C-FC12	12, 1, 3, VAV
NC14-HRW	5C-FC13	13, 1, 3, VAV
NC14-HRW	5C-FC14	14, 1, 3, VAV
NC14-HRW	5C-FC15	15, 1, 3, VAV
NC14-HRW	5C-FC16	16, 1, 3, VAV
NC14-HRW	5C-FC17	17, 1, 3, VAV
NC14-HRW	5C-FC18	18, 1, 3, VAV
NC14-HRW	5C-FC19	19, 1, 3, VAV
NC14-HRW	5C-FC20	20, 1, 3, VAV
NC14-HRW	5C-FC21	21, 1, 3, VAV
NC14-HRW	5C-FC22	22, 1, 3, VAV
NC14-HRW	5C-FC23	23, 1, 3, VAV
NC14-HRW	5C-FC24	24, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC14-HRW	5C-FC25	25, 1, 3, VAV
NC14-HRW	5C-FC26	26, 1, 3, VAV
NC14-HRW	5C-FC27	27, 1, 3, VAV
NC14-HRW	5C-FC28	28, 1, 3, VAV
NC14-HRW	5C-FC29	29, 1, 3, VAV
NC14-HRW	5C-FC30	30, 1, 3, VAV
NC14-HRW	5C-FC31	31, 1, 3, VAV
NC14-HRW	5C-FC32	32, 1, 3, VAV
NC14-HRW	5C-FC33	33, 1, 3, VAV
NC14-HRW	5C-FC34	34, 1, 3, VAV
NC14-HRW	5C-FC35	35, 1, 3, VAV
NC14-HRW	5C-FC36	36, 1, 3, VAV
NC14-HRW	5C-FC37	37, 1, 3, VAV
NC14-HRW	5C-FC38	38, 1, 3, VAV
NC14-HRW	5C-FC39	39, 1, 3, VAV
NC14-HRW	5C-FC40	40, 1, 3, VAV
NC14-HRW	6C-FC01	113, 1, 3, VAV
NC14-HRW	6C-FC02	114, 1, 3, VAV
NC14-HRW	6C-FC03	115, 1, 3, VAV
NC14-HRW	6C-FC04	116, 1, 3, VAV
NC14-HRW	6C-FC05	117, 1, 3, VAV
NC14-HRW	6C-FC06	118, 1, 3, VAV
NC14-HRW	6C-FC07	119, 1, 3, VAV
NC14-HRW	6C-FC08	120, 1, 3, VAV
NC14-HRW	6C-FC09	121, 1, 3, VAV
NC14-HRW	6C-FC10	122, 1, 3, VAV
NC14-HRW	6C-FC11	123, 1, 3, VAV
NC14-HRW	6C-FC12	124, 1, 3, VAV
NC14-HRW	6C-FC13	125, 1, 3, VAV
NC14-HRW	6C-FC14	126, 1, 3, VAV
NC14-HRW	6C-FC15	127, 1, 3, VAV
NC14-HRW	6C-FC16	128, 1, 3, VAV
NC14-HRW	6C-FC17	129, 1, 3, VAV
NC14-HRW	6C-FC18	130, 1, 3, VAV
NC14-HRW	6C-FC19	131, 1, 3, VAV
NC14-HRW	6B-FC01	160, 1, 3, VAV
NC14-HRW	6B-FC02	159, 1, 3, VAV
NC14-HRW	6B-FC03	158, 1, 3, VAV
NC14-HRW	6B-FC04	157, 1, 3, VAV
NC14-HRW	6B-FC05	156, 1, 3, VAV
NC14-HRW	6B-FC06	155, 1, 3, VAV
NC14-HRW	6B-FC07	154, 1, 3, VAV
NC14-HRW	6B-FC09	152, 1, 3, VAV
NC14-HRW	6B-FC10	151, 1, 3, VAV
NC14-HRW	6B-FC11	150, 1, 3, VAV
NC14-HRW	6B-FC12	149, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC14-HRW	6B-FC13	148, 1, 3, VAV
NC14-HRW	6B-FC14	147, 1, 3, VAV
NC14-HRW	6B-FC15	146, 1, 3, VAV
NC14-HRW	6B-FC16	145, 1, 3, VAV
NC14-HRW	6B-FC17	144, 1, 3, VAV
NC14-HRW	6B-FC18	143, 1, 3, VAV
NC14-HRW	6B-FC19	142, 1, 3, VAV
NC14-HRW	6B-FC20	141, 1, 3, VAV
NC14-HRW	6B-FC21	140, 1, 3, VAV
NC14-HRW	6B-FC22	139, 1, 3, VAV
NC14-HRW	6B-FC23	138, 1, 3, VAV
NC14-HRW	6B-FC24	137, 1, 3, VAV
NC14-HRW	6B-FC25	136, 1, 3, VAV
NC14-HRW	6B-FC26	135, 1, 3, VAV
NC14-HRW	6B-FC27	134, 1, 3, VAV
NC14-HRW	6B-FC28	133, 1, 3, VAV
NC14-HRW	6B-FC29	132, 1, 3, VAV
NC14-HRW	6A-FC01	189, 1, 3, VAV
NC14-HRW	6A-FC02	188, 1, 3, VAV
NC14-HRW	6A-FC03	187, 1, 3, VAV
NC14-HRW	6A-FC04	192, 1, 3, VAV
NC14-HRW	6A-FC05	193, 1, 3, VAV
NC14-HRW	6A-FC06	203, 1, 3, VAV
NC14-HRW	6A-FC07	202, 1, 3, VAV
NC14-HRW	6A-FC08	201, 1, 3, VAV
NC14-HRW	6A-FC09	200, 1, 3, VAV
NC14-HRW	6A-FC10	199, 1, 3, VAV
NC14-HRW	6A-FC11	198, 1, 3, VAV
NC14-HRW	6A-FC12	197, 1, 3, VAV
NC14-HRW	6A-FC13	196, 1, 3, VAV
NC14-HRW	6A-FC14	195, 1, 3, VAV
NC14-HRW	6A-FC15	194, 1, 3, VAV
NC14-HRW	6A-FC16	191, 1, 3, VAV
NC14-HRW	6A-FC17	190, 1, 3, VAV
NC14-HRW	6A-FC18	169, 1, 3, VAV
NC14-HRW	6A-FC19	168, 1, 3, VAV
NC14-HRW	6A-FC20	167, 1, 3, VAV
NC14-HRW	6A-FC21	166, 1, 3, VAV
NC14-HRW	6A-FC22	165, 1, 3, VAV
NC14-HRW	6A-FC23	164, 1, 3, VAV
NC14-HRW	6A-FC24	163, 1, 3, VAV
NC14-HRW	6A-FC25	162, 1, 3, VAV
NC14-HRW	6A-FC26	161, 1, 3, VAV
NC14-HRW	CHLR-4	205, 1, 3, UNT
NC14-HRW	MEDGAS1	170, 1, 3, UNT
NC14-HRW	MEDGAS4	171, 1, 3, UNT

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC14-HRW	MEDGAS2	172, 1, 3, UNT
NC14-HRW	MEDGAS3	173, 1, 3, UNT
NC14-HRW	6A-FC27	52, 1, 3, VAV
BO	6A-FC22	Occupied Command
AI	6A-FC22	Zone Temp
AI	6A-FC22	Zone Setpoint
AOS	6A-FC22	Heating Valve Command
AOS	6A-FC22	Cooling Valve Command
BO	6A-FC22	Fan Command
BI	6A-FC22	Fan Status
CS	6A-FC22	Temp Occ.Status C.S.
BO	6A-FC21	Occupied Command
AI	6A-FC21	Zone Temp
AI	6A-FC21	Zone Setpoint
AOS	6A-FC21	Heating Valve Command
AOS	6A-FC21	Cooling Valve Command
BO	6A-FC21	Fan Command
BI	6A-FC21	Fan Status
CS	6A-FC21	Temp Occ.Status C.S.
BO	6A-FC20	Occupied Command
AI	6A-FC20	Zone Temp
AI	6A-FC20	Zone Setpoint
AOS	6A-FC20	Heating Valve Command
AOS	6A-FC20	Cooling Valve Command
BO	6A-FC20	Fan Command
BI	6A-FC20	Fan Status
CS	6A-FC20	Temp Occ.Status C.S.
BO	6B-FC17	Occupied Command
AI	6B-FC17	Zone Temp
AI	6B-FC17	Zone Setpoint
AOS	6B-FC17	Heating Valve Command
AOS	6B-FC17	Cooling Valve Command
BO	6B-FC17	Fan Command
BI	6B-FC17	Fan Status
CS	6B-FC17	Temp Occ.Status C.S.
BO	6B-FC15	Occupied Command
AI	6B-FC15	Zone Temp
AI	6B-FC15	Zone Setpoint
AOS	6B-FC15	Heating Valve Command
AOS	6B-FC15	Cooling Valve Command
BO	6B-FC15	Fan Command
BI	6B-FC15	Fan Status
CS	6B-FC15	Temp Occ.Status C.S.
BO	6B-FC25	Occupied Command
AI	6B-FC25	Zone Temp
AI	6B-FC25	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	6B-FC25	Heating Valve Command
AOS	6B-FC25	Cooling Valve Command
BO	6B-FC25	Fan Command
BI	6B-FC25	Fan Status
CS	6B-FC25	Temp Occ.Status C.S.
BO	6B-FC08	Occupied Command
AI	6B-FC08	Zone Temp
AI	6B-FC08	Zone Setpoint
AOS	6B-FC08	Heating Valve Command
AOS	6B-FC08	Cooling Valve Command
BO	6B-FC08	Fan Command
BI	6B-FC08	Fan Status
CS	6B-FC08	Temp Occ.Status C.S.
BO	6B-FC07	Occupied Command
AI	6B-FC07	Zone Temp
AI	6B-FC07	Zone Setpoint
AOS	6B-FC07	Heating Valve Command
AOS	6B-FC07	Cooling Valve Command
BO	6B-FC07	Fan Command
BI	6B-FC07	Fan Status
CS	6B-FC07	Temp Occ.Status C.S.
BO	6B-FC05	Occupied Command
AI	6B-FC05	Zone Temp
AI	6B-FC05	Zone Setpoint
AOS	6B-FC05	Heating Valve Command
AOS	6B-FC05	Cooling Valve Command
BO	6B-FC05	Fan Command
BI	6B-FC05	Fan Status
CS	6B-FC05	Temp Occ.Status C.S.
BO	6A-FC08	Occupied Command
AI	6A-FC08	Zone Temp
AI	6A-FC08	Zone Temp Setpoint
BO	6A-FC08	Fan Command
BI	6A-FC08	Fan Status
AOS	6A-FC08	Heating Valve Command
AOS	6A-FC08	Cooling Valve Command
CS	6A-FC08	Temp Occ.Status c.s.
BO	6A-FC09	Occupied Command
AI	6A-FC09	Zone Temp
AI	6A-FC09	Zone Temp Setpoint
BO	6A-FC09	Fan Command
BI	6A-FC09	Fan Status
AOS	6A-FC09	Heating Valve Command
AOS	6A-FC09	Cooling Valve Command
CS	6A-FC09	Temp Occ.Status c.s.
BO	6A-FC07	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	6A-FC07	Zone Temp
AI	6A-FC07	Zone Temp Setpoint
BO	6A-FC07	Fan Command
BI	6A-FC07	Fan Status
AOS	6A-FC07	Heating Valve Command
AOS	6A-FC07	Cooling Valve Command
CS	6A-FC07	Temp Occ.Status c.s.
BO	6A-FC06	Occupied Command
AI	6A-FC06	Zone Temp
AI	6A-FC06	Zone Setpoint
BO	6A-FC06	Fan Command
BI	6A-FC06	Fan Status
AOS	6A-FC06	Heating Valve Command
AOS	6A-FC06	Cooling Valve Command
CS	6A-FC06	Temp Occ.Status c.s.
BO	6A-FC04	Occupied Command
AI	6A-FC04	Zone Temp
AI	6A-FC04	Zone Setpoint
BO	6A-FC04	Fan Command
BI	6A-FC04	Fan Status
AOS	6A-FC04	Heating Valve Command
AOS	6A-FC04	Cooling Valve Command
CS	6A-FC04	Temp Occ.Status c.s.
BO	6A-FC03	Occupied Command
AI	6A-FC03	Zone Temp
AI	6A-FC03	Zone Setpoint
AOS	6A-FC03	Heating Valve Command
AOS	6A-FC03	Cooling Valve Command
BO	6A-FC03	Fan Command
BI	6A-FC03	Fan Staus
CS	6A-FC03	Temp Occ.Status c.s.
BO	6A-FC01	Occupied Command
AI	6A-FC01	Zone Temp
AI	6A-FC01	Zone Setpoint
AOS	6A-FC01	Heating Valve Command
AOS	6A-FC01	Cooling Valve Command
BO	6A-FC01	FAN Command
BI	6A-FC01	Fan Status
CS	6A-FC01	Temp Occ.Status c.s.
BO	6A-FC02	Occupied Command
AI	6A-FC02	Zone Temp
AI	6A-FC02	ZONE Setpoint
AOS	6A-FC02	Heating Valve
AOS	6A-FC02	Cooling Valve Command
BO	6A-FC02	Fan Command
BI	6A-FC02	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	6A-FC02	Temp Occ.Status c.s.
AI	CHLR-4	Chill Water Return Temp
AI	CHLR-4	Chill Water Supply Temp
BI	CHLR-4	Chiller Status
BI	CHLR-4	Chiller Alarm
BO	CHLR-4	Chiller Command
BO	CHLR-4	Isolation Valve Command
BO	5C-FC08	Occupied Command
AI	5C-FC08	Zone Temp
AI	5C-FC08	Zone Setpoint
AOS	5C-FC08	Cooling Valve Command
BO	5C-FC08	Fan Command
BI	5C-FC08	Fan Status
BI	5C-FC08	Pan Alarm Status
CS	5C-FC08	Temp Occ.Status C.S.
AOS	5C-FC08	Cooling Valve Command
BO	5C-FC05	Occupied Command
AI	5C-FC05	Zone Temp
AI	5C-FC05	Zone Setpoint
AOS	5C-FC05	Cooling Valve Command
BO	5C-FC05	Fan Command
BI	5C-FC05	Fan Status
BI	5C-FC05	Pan Alarm Status
CS	5C-FC05	Temp Occ.Status C.S.
AOS	5C-FC05	Cooling Valve Command
BO	6C-FC01	Occupied Command
AI	6C-FC01	Zone Temp
AI	6C-FC01	Zone Setpoint
AOS	6C-FC01	Heating Valve Command
AOS	6C-FC01	Cooling Valve Command
BO	6C-FC01	Fan Command
BI	6C-FC01	Fan Status
BI	6C-FC01	Pan Alarm Status
CS	6C-FC01	Temp Occ.Status C.S.
BO	6C-FC02	Occupied Command
AI	6C-FC02	Zone Temp
AI	6C-FC02	Zone Setpoint
AOS	6C-FC02	Heating Valve Command
AOS	6C-FC02	Cooling Valve Command
BO	6C-FC02	Fan Command
BI	6C-FC02	Fan Status
BI	6C-FC02	Pan Alarm Status
CS	6C-FC02	Temp Occ.Status C.S.
BO	6C-FC03	Occupied Command
AI	6C-FC03	Zone Temp
AI	6C-FC03	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	6C-FC03	Heating Valve Command
AOS	6C-FC03	Cooling Valve Command
BO	6C-FC03	Fan Command
BI	6C-FC03	Fan Status
BI	6C-FC03	Pan Alarm Status
CS	6C-FC03	Temp Occ.Status C.S.
BO	6C-FC04	Occupied Command
AI	6C-FC04	Zone Temp
AI	6C-FC04	Zone Setpoint
AOS	6C-FC04	Heating Valve Command
AOS	6C-FC04	Cooling Valve Command
BO	6C-FC04	Fan Command
BI	6C-FC04	Fan Status
BI	6C-FC04	Pan Alarm Status
CS	6C-FC04	Temp Occ.Status C.S.
BO	6C-FC06	Occupied Command
AI	6C-FC06	Zone Temp
AI	6C-FC06	Zone Setpoint
AOS	6C-FC06	Heating Valve Command
AOS	6C-FC06	Cooling Valve Command
BO	6C-FC06	Fan Command
BI	6C-FC06	Fan Status
BI	6C-FC06	Pan Alarm Status
CS	6C-FC06	Temp Occ.Status C.S.
BO	6C-FC09	Occupied Command
AI	6C-FC09	Zone Temp
AI	6C-FC09	Zone Setpoint
AOS	6C-FC09	Heating Valve Command
AOS	6C-FC09	Cooling Valve Command
BO	6C-FC09	Fan Command
BI	6C-FC09	Fan Status
BI	6C-FC09	Pan Alarm Status
CS	6C-FC09	Temp Occ.Status C.S.
BO	6C-FC10	Occupied Command
AI	6C-FC10	Zone Temp
AI	6C-FC10	Zone Setpoint
AOS	6C-FC10	Heating Valve Command
AOS	6C-FC10	Cooling Valve Command
BO	6C-FC10	Fan Command
BI	6C-FC10	Fan Status
BI	6C-FC10	Pan Alarm Status
CS	6C-FC10	Temp Occ.Status C.S.
BO	6C-FC11	Occupied Command
AI	6C-FC11	Zone Temp
AI	6C-FC11	Zone Setpoint
AOS	6C-FC11	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	6C-FC11	Cooling Valve Command
BO	6C-FC11	Fan Command
BI	6C-FC11	Fan Status
BI	6C-FC11	Pan Alarm Status
CS	6C-FC11	Temp Occ.Status C.S.
BO	6C-FC12	Occupied Command
AI	6C-FC12	Zone Temp
AI	6C-FC12	Zone Setpoint
AOS	6C-FC12	Heating Valve Command
AOS	6C-FC12	Cooling Valve Command
BO	6C-FC12	Fan Command
BI	6C-FC12	Fan Status
BI	6C-FC12	Pan Alarm Status
CS	6C-FC12	Temp Occ.Status C.S.
BO	6C-FC13	Occupied Command
AI	6C-FC13	Zone Temp
AI	6C-FC13	Zone Setpoint
AOS	6C-FC13	Heating Valve Command
AOS	6C-FC13	Cooling Valve Command
BO	6C-FC13	Fan Command
BI	6C-FC13	Fan Status
BI	6C-FC13	Pan Alarm Status
CS	6C-FC13	Temp Occ.Status C.S.
BO	6C-FC14	Occupied Command
AI	6C-FC14	Zone Temp
AI	6C-FC14	Zone Setpoint
AOS	6C-FC14	Heating Valve Command
AOS	6C-FC14	Cooling Valve Command
BO	6C-FC14	Fan Command
BI	6C-FC14	Fan Status
BI	6C-FC14	Pan Alarm Status
CS	6C-FC14	Temp Occ.Status C.S.
BO	6C-FC15	Occupied Command
AI	6C-FC15	Zone Temp
AI	6C-FC15	Zone Setpoint
AOS	6C-FC15	Heating Valve Command
AOS	6C-FC15	Cooling Valve Command
BO	6C-FC15	Fan Command
BI	6C-FC15	Fan Status
BI	6C-FC15	Pan Alarm Status
CS	6C-FC15	Temp Occ.Status C.S.
BO	6C-FC16	Occupied Command
AI	6C-FC16	Zone Temp
AI	6C-FC16	Zone Setpoint N/C
AOS	6C-FC16	Heating Valve Command
AOS	6C-FC16	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	6C-FC16	Fan Command
BI	6C-FC16	Fan Status
BI	6C-FC16	Pan Alarm Status
CS	6C-FC16	Temp Occ.Status C.S.
BO	6C-FC17	Occupied Command
AI	6C-FC17	Zone Temp
AI	6C-FC17	Zone Setpoint
AOS	6C-FC17	Heating Valve Command
AOS	6C-FC17	Cooling Valve Command
BO	6C-FC17	Fan Command
BI	6C-FC17	Fan Status
BI	6C-FC17	Pan Alarm Status
CS	6C-FC17	Temp Occ.Status C.S.
BO	6C-FC18	Occupied Command
AI	6C-FC18	Zone Temp
AI	6C-FC18	Zone Setpoint
AOS	6C-FC18	Heating Valve Command
AOS	6C-FC18	Cooling Valve Command
BO	6C-FC18	Fan Command
BI	6C-FC18	Fan Status
BI	6C-FC18	Pan Alarm Status
CS	6C-FC18	Temp Occ.Status C.S.
BO	6C-FC19	Occupied Command
AI	6C-FC19	Zone Temp
AI	6C-FC19	Zone Setpoint
AOS	6C-FC19	Heating Valve Command
AOS	6C-FC19	Cooling Valve Command
BO	6C-FC19	Fan Command
BI	6C-FC19	Fan Status
BI	6C-FC19	Pan Alarm Status
CS	6C-FC19	Temp Occ.Status C.S.
BO	MISC-5	ExFan 5C Command
BI	MISC-5	ExFan 5C Status
BO	5A-FC01	Occupied Command
AI	5A-FC01	Zone Temp
AI	5A-FC01	Zone Setpoint
AOS	5A-FC01	Heating Valve Command
AOS	5A-FC01	Cooling Valve Command
BO	5A-FC01	Fan Command
BI	5A-FC01	Fan Status
BI	5A-FC01	Pan Alarm Status
CS	5A-FC01	Temp Occ.Status C.S.
BO	5A-FC02	Occupied Command
AI	5A-FC02	Zone Temp
AI	5A-FC02	Zone Setpoint
AOS	5A-FC02	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	5A-FC02	Cooling Valve Command
BO	5A-FC02	Fan Command
BI	5A-FC02	Fan Status
BI	5A-FC02	Pan Alarm Status
CS	5A-FC02	Temp Occ.Status C.S.
BO	5A-FC03	Occupied Command
AI	5A-FC03	Zone Temp
AI	5A-FC03	Zone Setpoint
AOS	5A-FC03	Heating Valve Command
AOS	5A-FC03	Cooling Valve Command
BO	5A-FC03	Fan Command
BI	5A-FC03	Fan Status
BI	5A-FC03	Pan Alarm Status
CS	5A-FC03	Temp Occ.Status C.S.
BO	5A-FC04	Occupied Command
AI	5A-FC04	Zone Temp
AI	5A-FC04	Zone Setpoint
AOS	5A-FC04	Heating Valve Command
AOS	5A-FC04	Cooling Valve Command
BO	5A-FC04	Fan Command
BI	5A-FC04	Fan Status
BI	5A-FC04	Pan Alarm Status
CS	5A-FC04	Temp Occ.Status C.S.
BO	5A-FC05	Occupied Command
AI	5A-FC05	Zone Temp
AI	5A-FC05	Zone Setpoint
AOS	5A-FC05	Heating Valve Command
AOS	5A-FC05	Cooling Valve Command
BO	5A-FC05	Fan Command
BI	5A-FC05	Fan Status
BI	5A-FC05	Pan Alarm Status
CS	5A-FC05	Temp Occ.Status C.S.
BO	5A-FC06	Occupied Command
AI	5A-FC06	Zone Temp
AI	5A-FC06	Zone Setpoint
AOS	5A-FC06	Cooling Valve Command
BO	5A-FC06	Fan Command
BI	5A-FC06	Fan Status
BI	5A-FC06	Pan Alarm Status
CS	5A-FC06	Temp Occ.Status C.S.
BO	5A-FC08	Occupied Command
AI	5A-FC08	Zone Temp
AI	5A-FC08	Zone Setpoint
AOS	5A-FC08	Heating Valve Command
AOS	5A-FC08	Cooling Valve Command
BO	5A-FC08	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	5A-FC08	Fan Status
BI	5A-FC08	Pan Alarm Status
CS	5A-FC08	Temp Occ.Status C.S.
BO	5A-FC09	Occupied Command
AI	5A-FC09	Zone Temp
AI	5A-FC09	Zone Setpoint
AOS	5A-FC09	Heating Valve Command
AOS	5A-FC09	Cooling Valve Command
BO	5A-FC09	Fan Command
BI	5A-FC09	Fan Status
BI	5A-FC09	Pan Alarm Status
CS	5A-FC09	Temp Occ.Status C.S.
BO	5B-FC01	Occupied Command
AI	5B-FC01	Zone Temp
AI	5B-FC01	Zone Setpoint
AOS	5B-FC01	Heating Valve Command
AOS	5B-FC01	Cooling Valve Command
BO	5B-FC01	Fan Command
BI	5B-FC01	Fan Status
BI	5B-FC01	Pan Alarm Status
CS	5B-FC01	Temp Occ.Status C.S.
BO	5B-FC02	Occupied Command
AI	5B-FC02	Zone Temp
AI	5B-FC02	Zone Setpoint
AOS	5B-FC02	Heating Valve Command
AOS	5B-FC02	Cooling Valve Command
BO	5B-FC02	Fan Command
BI	5B-FC02	Fan Status
BI	5B-FC02	Pan Alarm Status
CS	5B-FC02	Temp Occ.Status C.S.
BO	5B-FC03	Occupied Command
AI	5B-FC03	Zone Temp
AI	5B-FC03	Zone Setpoint
AOS	5B-FC03	Heating Valve Command
AOS	5B-FC03	Cooling Valve Command
BO	5B-FC03	Fan Command
BI	5B-FC03	Fan Status
BI	5B-FC03	Pan Alarm Status
CS	5B-FC03	Temp Occ.Status C.S.
BO	5B-FC04	Occupied Command
AI	5B-FC04	Zone Temp
AI	5B-FC04	Zone Setpoint
AOS	5B-FC04	Cooling Valve Command
BO	5B-FC04	Fan Command
BI	5B-FC04	Fan Status
BI	5B-FC04	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	5B-FC04	Temp Occ.Status C.S.
BO	5B-FC05	Occupied Command
AI	5B-FC05	Zone Temp
AI	5B-FC05	Zone Setpoint
AOS	5B-FC05	Heating Valve Command
AOS	5B-FC05	Cooling Valve Command
BO	5B-FC05	Fan Command
BI	5B-FC05	Fan Status
BI	5B-FC05	Pan Alarm Status
CS	5B-FC05	Temp Occ.Status C.S.
BO	5B-FC06	Occupied Command
AI	5B-FC06	Zone Temp
AI	5B-FC06	Zone Setpoint
AOS	5B-FC06	Heating Valve Command
AOS	5B-FC06	Cooling Valve Command
BO	5B-FC06	Fan Command
BI	5B-FC06	Fan Status
BI	5B-FC06	Pan Alarm Status
CS	5B-FC06	Temp Occ.Status C.S.
BO	5B-FC07	Occupied Command
AI	5B-FC07	Zone Temp
AI	5B-FC07	Zone Setpoint
AOS	5B-FC07	Heating Valve Command
AOS	5B-FC07	Cooling Valve Command
BO	5B-FC07	Fan Command
BI	5B-FC07	Fan Status
BI	5B-FC07	Pan Alarm Status
CS	5B-FC07	Temp Occ.Status C.S.
BO	5B-FC09	Occupied Command
AI	5B-FC09	Zone Temp
AI	5B-FC09	Zone Setpoint
AOS	5B-FC09	Heating Valve Command
AOS	5B-FC09	Cooling Valve Command
BO	5B-FC09	Fan Command
BI	5B-FC09	Fan Status
BI	5B-FC09	Pan Alarm Status
CS	5B-FC09	Temp Occ.Status C.S.
BO	5B-FC10	Occupied Command
AI	5B-FC10	Zone Temp
AI	5B-FC10	Zone Setpoint
AOS	5B-FC10	Heating Valve Command
AOS	5B-FC10	Cooling Valve Command
BO	5B-FC10	Fan Command
BI	5B-FC10	Fan Status
BI	5B-FC10	Pan Alarm Status
CS	5B-FC10	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	5B-FC11	Occupied Command
AI	5B-FC11	Zone Temp
AI	5B-FC11	Zone Setpoint
AOS	5B-FC11	Heating Valve Command
AOS	5B-FC11	Cooling Valve Command
BO	5B-FC11	Fan Command
BI	5B-FC11	Fan Status
BI	5B-FC11	Pan Alarm Status
CS	5B-FC11	Temp Occ.Status C.S.
BO	5B-FC12	Occupied Command
AI	5B-FC12	Zone Temp
AI	5B-FC12	Zone Setpoint
AOS	5B-FC12	Heating Valve Command
AOS	5B-FC12	Cooling Valve Command
BO	5B-FC12	Fan Command
BI	5B-FC12	Fan Status
BI	5B-FC12	Pan Alarm Status
CS	5B-FC12	Temp Occ.Status C.S.
BO	5B-FC13	Occupied Command
AI	5B-FC13	Zone Temp
AI	5B-FC13	Zone Setpoint
AOS	5B-FC13	Heating Valve Command
AOS	5B-FC13	Cooling Valve Command
BO	5B-FC13	Fan Command
BI	5B-FC13	Fan Status
BI	5B-FC13	Pan Alarm Status
CS	5B-FC13	Temp Occ.Status C.S.
BO	5C-FC01	Occupied Command
AI	5C-FC01	Zone Temp
AI	5C-FC01	Zone Setpoint
AOS	5C-FC01	Heating Valve Command
AOS	5C-FC01	Cooling Valve Command
BO	5C-FC01	Fan Command
BI	5C-FC01	Fan Status
BI	5C-FC01	Pan Alarm Status
CS	5C-FC01	Temp Occ.Status C.S.
BO	5C-FC02	Occupied Command
AI	5C-FC02	Zone Temp
AI	5C-FC02	Zone Setpoint
AOS	5C-FC02	Heating Valve Command
AOS	5C-FC02	Cooling Valve Command
BO	5C-FC02	Fan Command
BI	5C-FC02	Fan Status
BI	5C-FC02	Pan Alarm Status
CS	5C-FC02	Temp Occ.Status C.S.
BO	5C-FC03	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	5C-FC03	Zone Temp
AI	5C-FC03	Zone Setpoint
AOS	5C-FC03	Heating Valve Command
AOS	5C-FC03	Cooling Valve Command
BO	5C-FC03	Fan Command
BI	5C-FC03	Fan Status
BI	5C-FC03	Pan Alarm Status
CS	5C-FC03	Temp Occ.Status C.S.
BO	5C-FC04	Occupied Command
AI	5C-FC04	Zone Temp
AI	5C-FC04	Zone Setpoint
AOS	5C-FC04	Heating Valve Command
AOS	5C-FC04	Cooling Valve Command
BO	5C-FC04	Fan Command
BI	5C-FC04	Fan Status
BI	5C-FC04	Pan Alarm Status
CS	5C-FC04	Temp Occ.Status C.S.
BO	5C-FC06	Occupied Command
AI	5C-FC06	Zone Temp
AI	5C-FC06	Zone Setpoint
AOS	5C-FC06	Heating Valve Command
AOS	5C-FC06	Cooling Valve Command
BO	5C-FC06	Fan Command
BI	5C-FC06	Fan Status
BI	5C-FC06	Pan Alarm Status
CS	5C-FC06	Temp Occ.Status C.S.
BO	5C-FC09	Occupied Command
AI	5C-FC09	Zone Temp
AI	5C-FC09	Zone Setpoint
AOS	5C-FC09	Heating Valve Command
AOS	5C-FC09	Cooling Valve Command
BO	5C-FC09	Fan Command
BI	5C-FC09	Fan Status
BI	5C-FC09	Pan Alarm Status
CS	5C-FC09	Temp Occ.Status C.S.
BO	5C-FC10	Occupied Command
AI	5C-FC10	Zone Temp
AI	5C-FC10	Zone Setpoint
AOS	5C-FC10	Heating Valve Command
AOS	5C-FC10	Cooling Valve Command
BO	5C-FC10	Fan Command
BI	5C-FC10	Fan Status
BI	5C-FC10	Pan Alarm Status
CS	5C-FC10	Temp Occ.Status C.S.
BO	5C-FC11	Occupied Command
AI	5C-FC11	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	5C-FC11	Zone Setpoint
AOS	5C-FC11	Heating Valve Command
AOS	5C-FC11	Cooling Valve Command
BO	5C-FC11	Fan Command
BI	5C-FC11	Fan Status
BI	5C-FC11	Pan Alarm Status
CS	5C-FC11	Temp Occ.Status C.S.
BO	5C-FC12	Occupied Command
AI	5C-FC12	Zone Temp
AI	5C-FC12	Zone Setpoint
AOS	5C-FC12	Heating Valve Command
AOS	5C-FC12	Cooling Valve Command
BO	5C-FC12	Fan Command
BI	5C-FC12	Fan Status
BI	5C-FC12	Pan Alarm Status
CS	5C-FC12	Temp Occ.Status C.S.
BO	5C-FC13	Occupied Command
AI	5C-FC13	Zone Temp
AI	5C-FC13	Zone Setpoint
AOS	5C-FC13	Heating Valve Command
AOS	5C-FC13	Cooling Valve Command
BO	5C-FC13	Fan Command
BI	5C-FC13	Fan Status
BI	5C-FC13	Pan Alarm Status
CS	5C-FC13	Temp Occ.Status C.S.
BO	5C-FC14	Occupied Command
AI	5C-FC14	Zone Temp
AI	5C-FC14	Zone Setpoint
AOS	5C-FC14	Heating Valve Command
AOS	5C-FC14	Cooling Valve Command
BO	5C-FC14	Fan Command
BI	5C-FC14	Fan Status
BI	5C-FC14	Pan Alarm Status
CS	5C-FC14	Temp Occ.Status C.S.
BO	5C-FC15	Occupied Command
AI	5C-FC15	Zone Temp
AI	5C-FC15	Zone Setpoint
AOS	5C-FC15	Heating Valve Command
AOS	5C-FC15	Cooling Valve Command
BO	5C-FC15	Fan Command
BI	5C-FC15	Fan Status
BI	5C-FC15	Pan Alarm Status
CS	5C-FC15	Temp Occ.Status C.S.
BO	5C-FC16	Occupied Command
AI	5C-FC16	Zone Temp
AI	5C-FC16	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	5C-FC16	Heating Valve Command
AOS	5C-FC16	Cooling Valve Command
BO	5C-FC16	Fan Command
BI	5C-FC16	Fan Status
BI	5C-FC16	Pan Alarm Status
CS	5C-FC16	Temp Occ.Status C.S.
BO	5C-FC17	Occupied Command
AI	5C-FC17	Zone Temp
AI	5C-FC17	Zone Setpoint
AOS	5C-FC17	Heating Valve Command
AOS	5C-FC17	Cooling Valve Command
BO	5C-FC17	Fan Command
BI	5C-FC17	Fan Status
BI	5C-FC17	Pan Alarm Status
CS	5C-FC17	Temp Occ.Status C.S.
BO	5C-FC18	Occupied Command
AI	5C-FC18	Zone Temp
AI	5C-FC18	Zone Setpoint
AOS	5C-FC18	Heating Valve Command
AOS	5C-FC18	Cooling Valve Command
BO	5C-FC18	Fan Command
BI	5C-FC18	Fan Status
BI	5C-FC18	Pan Alarm Status
CS	5C-FC18	Temp Occ.Status C.S.
BO	5C-FC19	Occupied Command
AI	5C-FC19	Zone Temp
AI	5C-FC19	Zone Setpoint
AOS	5C-FC19	Heating Valve Command
AOS	5C-FC19	Cooling Valve Command
BO	5C-FC19	Fan Command
BI	5C-FC19	Fan Status
BI	5C-FC19	Pan Alarm Status
CS	5C-FC19	Temp Occ.Status C.S.
AI	5C-FC20	Zone Temp
AI	5C-FC20	Zone Setpoint
AOS	5C-FC20	Heating Valve Command
AOS	5C-FC20	Cooling Valve Command
BO	5C-FC20	Fan Command
BI	5C-FC20	Fan Status
BI	5C-FC20	Pan Alarm Status
CS	5C-FC20	Temp Occ.Status C.S.
BO	5C-FC20	Occupied Command
BO	5C-FC21	Occupied Command
AI	5C-FC21	Zone Temp
AI	5C-FC21	Zone Setpoint
AOS	5C-FC21	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	5C-FC21	Cooling Valve Command
BO	5C-FC21	Fan Command
BI	5C-FC21	Fan Status
BI	5C-FC21	Pan Alarm Status
CS	5C-FC21	Temp Occ.Status C.S.
BO	5C-FC22	Occupied Command
AI	5C-FC22	Zone Temp
AI	5C-FC22	Zone Setpoint
AOS	5C-FC22	Heating Valve Command
AOS	5C-FC22	Cooling Valve Command
BO	5C-FC22	Fan Command
BI	5C-FC22	Fan Status
BI	5C-FC22	Pan Alarm Status
CS	5C-FC22	Temp Occ.Status C.S.
BO	5C-FC23	Occupied Command
AI	5C-FC23	Zone Temp
AI	5C-FC23	Zone Setpoint
AOS	5C-FC23	Heating Valve Command
AOS	5C-FC23	Cooling Valve Command
BO	5C-FC23	Fan Command
BI	5C-FC23	Fan Status
BI	5C-FC23	Pan Alarm Status
CS	5C-FC23	Temp Occ.Status C.S.
BO	5C-FC24	Occupied Command
AI	5C-FC24	Zone Temp
AI	5C-FC24	Zone Setpoint
AOS	5C-FC24	Heating Valve Command
AOS	5C-FC24	Cooling Valve Command
BO	5C-FC24	Fan Command
BI	5C-FC24	Fan Status
BI	5C-FC24	Pan Alarm Status
CS	5C-FC24	Temp Occ.Status C.S.
BO	5C-FC25	Occupied Command
AI	5C-FC25	Zone Temp
AI	5C-FC25	Zone Setpoint
AOS	5C-FC25	Heating Valve Command
AOS	5C-FC25	Cooling Valve Command
BO	5C-FC25	Fan Command
BI	5C-FC25	Fan Status
BI	5C-FC25	Pan Alarm Status
CS	5C-FC25	Temp Occ.Status C.S.
BO	5C-FC26	Occupied Command
AI	5C-FC26	Zone Temp
AI	5C-FC26	Zone Setpoint
AOS	5C-FC26	Heating Valve Command
AOS	5C-FC26	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	5C-FC26	Fan Command
BI	5C-FC26	Fan Status
BI	5C-FC26	Pan Alarm Status
CS	5C-FC26	Temp Occ.Status C.S.
BO	5C-FC27	Occupied Command
AI	5C-FC27	Zone Temp
AI	5C-FC27	Zone Setpoint
AOS	5C-FC27	Heating Valve Command
AOS	5C-FC27	Cooling Valve Command
BO	5C-FC27	Fan Command
BI	5C-FC27	Fan Status
BI	5C-FC27	Pan Alarm Status
CS	5C-FC27	Temp Occ.Status C.S.
BO	5C-FC28	Occupied Command
AI	5C-FC28	Zone Temp
AI	5C-FC28	Zone Setpoint
AOS	5C-FC28	Heating Valve Command
AOS	5C-FC28	Cooling Valve Command
BO	5C-FC28	Fan Command
BI	5C-FC28	Fan Status
BI	5C-FC28	Pan Alarm Status
CS	5C-FC28	Temp Occ.Status C.S.
BO	5C-FC29	Occupied Command
AI	5C-FC29	Zone Temp
AI	5C-FC29	Zone Setpoint
AOS	5C-FC29	Heating Valve Command
AOS	5C-FC29	Cooling Valve Command
BO	5C-FC29	Fan Command
BI	5C-FC29	Fan Status
BI	5C-FC29	Pan Alarm Status
CS	5C-FC29	Temp Occ.Status C.S.
BO	5C-FC30	Occupied Command
AI	5C-FC30	Zone Temp
AI	5C-FC30	Zone Setpoint
AOS	5C-FC30	Heating Valve Command
AOS	5C-FC30	Cooling Valve Command
BO	5C-FC30	Fan Command
BI	5C-FC30	Fan Status
BI	5C-FC30	Pan Alarm Status
CS	5C-FC30	Temp Occ.Status C.S.
BO	5C-FC31	Occupied Command
AI	5C-FC31	Zone Temp
AI	5C-FC31	Zone Setpoint
AOS	5C-FC31	Heating Valve Command
AOS	5C-FC31	Cooling Valve Command
BO	5C-FC31	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	5C-FC31	Fan Status
BI	5C-FC31	Pan Alarm Status
CS	5C-FC31	Temp Occ.Status C.S.
BO	5C-FC32	Occupied Command
AI	5C-FC32	Zone Temp
AI	5C-FC32	Zone Setpoint
AOS	5C-FC32	Heating Valve Command
AOS	5C-FC32	Cooling Valve Command
BO	5C-FC32	Fan Command
BI	5C-FC32	Fan Status
BI	5C-FC32	Pan Alarm Status
CS	5C-FC32	Temp Occ.Status C.S.
BO	5C-FC33	Occupied Command
AI	5C-FC33	Zone Temp
AI	5C-FC33	Zone Setpoint
AOS	5C-FC33	Heating Valve Command
AOS	5C-FC33	Cooling Valve Command
BO	5C-FC33	Fan Command
BI	5C-FC33	Fan Status
BI	5C-FC33	Pan Alarm Status
CS	5C-FC33	Temp Occ.Status C.S.
BO	5C-FC34	Occupied Command
AI	5C-FC34	Zone Temp
AI	5C-FC34	Zone Setpoint
AOS	5C-FC34	Heating Valve Command
AOS	5C-FC34	Cooling Valve Command
BO	5C-FC34	Fan Command
BI	5C-FC34	Fan Status
BI	5C-FC34	Pan Alarm Status
CS	5C-FC34	Temp Occ.Status C.S.
BO	5C-FC35	Occupied Command
AI	5C-FC35	Zone Temp
AI	5C-FC35	Zone Setpoint
AOS	5C-FC35	Heating Valve Command
AOS	5C-FC35	Cooling Valve Command
BO	5C-FC35	Fan Command
BI	5C-FC35	Fan Status
BI	5C-FC35	Pan Alarm Status
CS	5C-FC35	Temp Occ.Status C.S.
BO	5C-FC36	Occupied Command
AI	5C-FC36	Zone Temp
AI	5C-FC36	Zone Setpoint
AOS	5C-FC36	Heating Valve Command
AOS	5C-FC36	Cooling Valve Command
BO	5C-FC36	Fan Command
BI	5C-FC36	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	5C-FC36	Pan Alarm Status
CS	5C-FC36	Temp Occ.Status C.S.
BO	5C-FC37	Occupied Command
AI	5C-FC37	Zone Temp
AI	5C-FC37	Zone Setpoint
AOS	5C-FC37	Heating Valve Command
AOS	5C-FC37	Cooling Valve Command
BO	5C-FC37	Fan Command
BI	5C-FC37	Fan Status
BI	5C-FC37	Pan Alarm Status
CS	5C-FC37	Temp Occ.Status C.S.
BO	5C-FC38	Occupied Command
AI	5C-FC38	Zone Temp
AI	5C-FC38	Zone Setpoint
AOS	5C-FC38	Heating Valve Command
AOS	5C-FC38	Cooling Valve Command
BO	5C-FC38	Fan Command
BI	5C-FC38	Fan Status
BI	5C-FC38	Pan Alarm Status
CS	5C-FC38	Temp Occ.Status C.S.
BO	5C-FC39	Occupied Command
AI	5C-FC39	Zone Temp
AI	5C-FC39	Zone Setpoint
AOS	5C-FC39	Heating Valve Command
AOS	5C-FC39	Cooling Valve Command
BO	5C-FC39	Fan Command
BI	5C-FC39	Fan Status
BI	5C-FC39	Pan Alarm Status
CS	5C-FC39	Temp Occ.Status C.S.
BO	5C-FC40	Occupied Command
AI	5C-FC40	Zone Temp
AI	5C-FC40	Zone Setpoint
AOS	5C-FC40	Heating Valve Command
AOS	5C-FC40	Cooling Valve Command
BO	5C-FC40	Fan Command
BI	5C-FC40	Fan Status
BI	5C-FC40	Pan Alarm Status
CS	5C-FC40	Temp Occ.Status C.S.
BO	5C-FC07	Occupied Command
AI	5C-FC07	Zone Temp
AI	5C-FC07	Zone Setpoint
AOS	5C-FC07	Cooling Valve Command
AOS	5C-FC07	Heating Valve Command
BO	5C-FC07	Fan Command
BI	5C-FC07	Fan Status
BI	5C-FC07	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	5C-FC07	Temp Occ.Status C.S.
BO	6B-FC06	Occupied Command
AI	6B-FC06	Zone Temp
AI	6B-FC06	Zone Setpoint
AOS	6B-FC06	Heating Valve Command
AOS	6B-FC06	Cooling Valve Command
BO	6B-FC06	Fan Command
BI	6B-FC06	Fan Status
CS	6B-FC06	Temp Occ.Status C.S.
BO	6B-FC24	Occupied Command
AI	6B-FC24	Zone Temp
AI	6B-FC24	Zone Setpoint
AOS	6B-FC24	Heating Valve Command
AOS	6B-FC24	Cooling Valve Command
BO	6B-FC24	Fan Command
BI	6B-FC24	Fan Status
CS	6B-FC24	Temp Occ.Status C.S.
BO	6B-FC23	Occupied Command
AI	6B-FC23	Zone Temp
AI	6B-FC23	Zone Setpoint
AOS	6B-FC23	Heating Valve Command
AOS	6B-FC23	Cooling Valve Command
BO	6B-FC23	Fan Command
BI	6B-FC23	Fan Status
CS	6B-FC23	Temp Occ.Status C.S.
BO	6B-FC22	Occupied Command
AI	6B-FC22	Zone Temp
AI	6B-FC22	Zone Setpoint
AOS	6B-FC22	Heating Valve Command
AOS	6B-FC22	Cooling Valve Command
BO	6B-FC22	Fan Command
BI	6B-FC22	Fan Status
CS	6B-FC22	Temp Occ.Status C.S.
BO	6B-FC21	Occupied Command
AI	6B-FC21	Zone Temp
AI	6B-FC21	Zone Setpoint
AOS	6B-FC21	Heating Valve Command
AOS	6B-FC21	Cooling Valve Command
BO	6B-FC21	Fan Command
BI	6B-FC21	Fan Status
CS	6B-FC21	Temp Occ.Status C.S.
BO	6B-FC20	Occupied Command
AI	6B-FC20	Zone Temp
AI	6B-FC20	Zone Setpoint
AOS	6B-FC20	Heating Valve Command
AOS	6B-FC20	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	6B-FC20	Fan Command
BI	6B-FC20	Fan Status
CS	6B-FC20	Temp Occ.Status C.S.
BO	6B-FC19	Occupied Command
AI	6B-FC19	Zone Temp
AI	6B-FC19	Zone Setpoint
AOS	6B-FC19	Heating Valve Command
AOS	6B-FC19	Cooling Valve Command
BO	6B-FC19	Fan Command
BI	6B-FC19	Fan Status
CS	6B-FC19	Temp Occ.Status C.S.
BO	6B-FC01	Occupied Command
AI	6B-FC01	Zone Temp
AI	6B-FC01	Zone Setpoint
AOS	6B-FC01	Heating Valve Command
AOS	6B-FC01	Cooling Valve Command
BO	6B-FC01	Fan Command
BI	6B-FC01	Fan Status
CS	6B-FC01	Temp Occ.Status C.S.
BO	6B-FC02	Occupied Command
AI	6B-FC02	Zone Temp
AI	6B-FC02	Zone Setpoint
AOS	6B-FC02	Heating Valve Command
AOS	6B-FC02	Cooling Valve Command
BO	6B-FC02	Fan Command
BI	6B-FC02	Fan Status
CS	6B-FC02	Temp Occ.Status C.S.
BO	6B-FC03	Occupied Command
AI	6B-FC03	Zone Temp
AI	6B-FC03	Zone Setpoint
AOS	6B-FC03	Heating Valve Command
AOS	6B-FC03	Cooling Valve Command
BO	6B-FC03	Fan Command
BI	6B-FC03	Fan Status
CS	6B-FC03	Temp Occ.Status C.S.
BO	6B-FC04	Occupied Command
AI	6B-FC04	Zone Temp
AI	6B-FC04	Zone Setpoint
AOS	6B-FC04	Heating Valve Command
AOS	6B-FC04	Cooling Valve Command
BO	6B-FC04	Fan Command
BI	6B-FC04	Fan Status
CS	6B-FC04	Temp Occ.Status C.S.
BO	6B-FC09	Occupied Command
AI	6B-FC09	Zone Temp
AI	6B-FC09	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	6B-FC09	Heating Valve Command
AOS	6B-FC09	Cooling Valve Command
BO	6B-FC09	Fan Command
BI	6B-FC09	Fan Status
CS	6B-FC09	Temp Occ.Status C.S.
BO	6B-FC10	Occupied Command
AI	6B-FC10	Zone Temp
AI	6B-FC10	Zone Setpoint
AOS	6B-FC10	Heating Valve Command
AOS	6B-FC10	Cooling Valve Command
BO	6B-FC10	Fan Command
BI	6B-FC10	Fan Status
CS	6B-FC10	Temp Occ.Status C.S.
BO	6B-FC11	Occupied Command
AI	6B-FC11	Zone Temp
AI	6B-FC11	Zone Setpoint
AOS	6B-FC11	Heating Valve Command
AOS	6B-FC11	Cooling Valve Command
BO	6B-FC11	Fan Command
BI	6B-FC11	Fan Status
CS	6B-FC11	Temp Occ.Status C.S.
BO	6B-FC12	Occupied Command
AI	6B-FC12	Zone Temp
AI	6B-FC12	Zone Setpoint
AOS	6B-FC12	Heating Valve Command
AOS	6B-FC12	Cooling Valve Command
BO	6B-FC12	Fan Command
BI	6B-FC12	Fan Status
CS	6B-FC12	Temp Occ.Status C.S.
BO	6B-FC13	Occupied Command
AI	6B-FC13	Zone Temp
AI	6B-FC13	Zone Setpoint
AOS	6B-FC13	Heating Valve Command
AOS	6B-FC13	Cooling Valve Command
BO	6B-FC13	Fan Command
BI	6B-FC13	Fan Status
CS	6B-FC13	Temp Occ.Status C.S.
BO	6B-FC14	Occupied Command
AI	6B-FC14	Zone Temp
AI	6B-FC14	Zone Setpoint
AOS	6B-FC14	Heating Valve Command
AOS	6B-FC14	Cooling Valve Command
BO	6B-FC14	Fan Command
BI	6B-FC14	Fan Status
CS	6B-FC14	Temp Occ.Status C.S.
BO	6B-FC16	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	6B-FC16	Zone Temp
AI	6B-FC16	Zone Setpoint
AOS	6B-FC16	Heating Valve Command
AOS	6B-FC16	Cooling Valve Command
BO	6B-FC16	Fan Command
BI	6B-FC16	Fan Status
CS	6B-FC16	Temp Occ.Status C.S.
BO	6A-FC05	Occupied Command
AI	6A-FC05	Zone Temp
AI	6A-FC05	Zone Setpoint
AOS	6A-FC05	Cooling Valve Command
AOS	6A-FC05	Heating Valve Command
BO	6A-FC05	Fan Command
BI	6A-FC05	Fan Status
CS	6A-FC05	Temp Occ.Status c.s.
BO	6B-FC18	Occupied Command
AI	6B-FC18	Zone Temp
AI	6B-FC18	Zone Setpoint
AOS	6B-FC18	Cooling Valve Command
AOS	6B-FC18	Heating Valve Command
BO	6B-FC18	Fan Command
BI	6B-FC18	Fan Status
CS	6B-FC18	Temp Occ.Status C.S.
BO	6A-FC10	Occupied Command
AI	6A-FC10	Zone Temp
AI	6A-FC10	Zone Setpoint
AOS	6A-FC10	Heating Valve Command
AOS	6A-FC10	Cooling Valve Command
BO	6A-FC10	Fan Command
BI	6A-FC10	Fan Status
CS	6A-FC10	Temp Occ.Status C.S.
BO	6A-FC11	Occupied Command
AI	6A-FC11	Zone Temp
AI	6A-FC11	Zone Setpoint
AOS	6A-FC11	Heating Valve Command
AOS	6A-FC11	Cooling Valve Command
BO	6A-FC11	Fan Command
BI	6A-FC11	Fan Status
CS	6A-FC11	Temp Occ.Status C.S.
BO	6A-FC12	Occupied Command
AI	6A-FC12	Zone Temp
AI	6A-FC12	Zone Setpoint
AOS	6A-FC12	Heating Valve Command
AOS	6A-FC12	Cooling Valve Command
BO	6A-FC12	Fan Command
BI	6A-FC12	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	6A-FC12	Temp Occ.Status C.S.
BO	6A-FC13	Occupied Command
AI	6A-FC13	Zone Temp
AI	6A-FC13	Zone Setpoint
AOS	6A-FC13	Heating Valve Command
AOS	6A-FC13	Cooling Valve Command
BO	6A-FC13	Fan Command
BI	6A-FC13	Fan Status
CS	6A-FC13	Temp Occ.Status C.S.
BO	6A-FC14	Occupied Command
AI	6A-FC14	Zone Temp
AI	6A-FC14	Zone Setpoint
AOS	6A-FC14	Heating Valve Command
AOS	6A-FC14	Cooling Valve Command
BO	6A-FC14	Fan Command
BI	6A-FC14	Fan Status
CS	6A-FC14	Temp Occ.Status C.S.
BO	6A-FC15	Occupied Command
AI	6A-FC15	Zone Temp
AI	6A-FC15	Zone Setpoint
AOS	6A-FC15	Heating Valve Command
AOS	6A-FC15	Cooling Valve Command
BO	6A-FC15	Fan Command
BI	6A-FC15	Fan Status
CS	6A-FC15	Temp Occ.Status C.S.
BO	6A-FC16	Occupied Command
AI	6A-FC16	Zone Temp
AI	6A-FC16	Zone Setpoint
AOS	6A-FC16	Heating Valve Command
AOS	6A-FC16	Cooling Valve Command
BO	6A-FC16	Fan Command
BI	6A-FC16	Fan Status
CS	6A-FC16	Temp Occ.Status C.S.
BO	6A-FC17	Occupied Command
AI	6A-FC17	Zone Temp
AI	6A-FC17	Zone Setpoint
AOS	6A-FC17	Heating Valve Command
AOS	6A-FC17	Cooling Valve Command
BO	6A-FC17	Fan Command
BI	6A-FC17	Fan Status
CS	6A-FC17	Temp Occ.Status C.S.
BO	6A-FC19	Occupied Command
AI	6A-FC19	Zone Temp
AI	6A-FC19	Zone Setpoint
AOS	6A-FC19	Heating Valve Command
AOS	6A-FC19	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	6A-FC19	Fan Command
BI	6A-FC19	Fan Status
CS	6A-FC19	Temp Occ.Status C.S.
BO	6A-FC18	Occupied Command
AI	6A-FC18	Zone Temp
AI	6A-FC18	Zone Setpoint
AOS	6A-FC18	Heating Valve Command
AOS	6A-FC18	Cooling Valve Command
BO	6A-FC18	Fan Command
BI	6A-FC18	Fan Status
CS	6A-FC18	Temp Occ.Status C.S.
BO	6C-FC07	Occupied Command
AI	6C-FC07	Zone Temp
AI	6C-FC07	Zone Setpoint
AOS	6C-FC07	Cooling Valve Command
AOS	6C-FC07	Heating Valve Command
BO	6C-FC07	Fan Command
BI	6C-FC07	Fan Status
BI	6C-FC07	Pan Alarm Status
CS	6C-FC07	Temp Occ.Status C.S.
BO	6C-FC05	Occupied Command
AI	6C-FC05	Zone Temp
AI	6C-FC05	Zone Setpoint
AOS	6C-FC05	Heating Valve Command
AOS	6C-FC05	Cooling Valve Command
BO	6C-FC05	Fan Command
BI	6C-FC05	Fan Status
BI	6C-FC05	Pan Alarm Status
CS	6C-FC05	Temp Occ.Status C.S.
BO	6C-FC08	Occupied Command
AI	6C-FC08	Zone Temp
AI	6C-FC08	Zone Setpoint
AOS	6C-FC08	Heating Valve Command
AOS	6C-FC08	Cooling Valve Command
BO	6C-FC08	Fan Command
BI	6C-FC08	Fan Status
BI	6C-FC08	Pan Alarm Status
CS	6C-FC08	Temp Occ.Status C.S.
BI	MEDGAS	Med Vacuum Lag In Use
BI	MEDGAS	Med Air Maint. Required
BI	MEDGAS	Med Air Line Pressure Hi
BI	MEDGAS	Med Air Lag In Use
BI	MEDGAS	Med Air Line Press. Low
BI	MEDGAS	Med Vacuum Low
BI	MEDGAS	Med Air Dew Point High
BI	MEDGAS	Carbon Monox. Level Hi

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	MEDGAS	Nitrogen Reserve In Use
BI	MEDGAS	Nitrogen Line Press. Low
BI	MEDGAS	Nit. Oxid Reserve In Use
BI	MEDGAS	Nit Oxid Line Press. Low
BI	MEDGAS	Nit Oxid Line Press High
BI	MEDGAS	Nitrogen Line Pressur Hi
BO	5A-FC07	Occupied Command
AI	5A-FC07	Zone Temp
AI	5A-FC07	Zone Setpoint
AOS	5A-FC07	Heating Valve Command
AOS	5A-FC07	COOLING COMMAND
BO	5A-FC07	Fan Command
BI	5A-FC07	Fan Status
BI	5A-FC07	Pan Alarm Status
CS	5A-FC07	Temp Occ.Status C.S.
BO	5B-FC08	Occupied Command
AI	5B-FC08	Zone Temp
AI	5B-FC08	Zone Setpoint
AOS	5B-FC08	Cooling Valve Command
BO	5B-FC08	Fan Command
BI	5B-FC08	Fan Status
BI	5B-FC08	Pan Alarm Status
CS	5B-FC08	Temp Occ.Status C.S.
AOS	5B-FC08	Heating Valve Command
BO	5A-FC10	Occupied Command
AI	5A-FC10	Zone Temp
AI	5A-FC10	Zone Setpoint
AOS	5A-FC10	Cooling Valve Command
BO	5A-FC10	Fan Command
BI	5A-FC10	Fan Status
BI	5A-FC10	Pan Alarm Status
CS	5A-FC10	Temp Occ.Status C.S.
AOS	5A-FC10	Heating Valve Command
CS	6A-FC24	Temp Occ.Status C.S.
CS	6A-FC25	Temp Occ.Status C.S.
CS	6A-FC23	Temp Occ.Status C.S.
CS	6B-FC26	Temp Occ. Status C.S.
BO	6B-FC26	Occupied Command
AI	6B-FC26	Zone Temperature
AI	6B-FC26	Zone Setpoint
AOS	6B-FC26	Heating Valve Command
AOS	6B-FC26	Cooling Valve Command
BI	6B-FC26	Fan Status
BO	6B-FC26	Fan Command
CS	6B-FC27	Temp Occ. Status C.S.
BO	6B-FC27	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	6B-FC27	Zone Temperature
AI	6B-FC27	Zone Setpoint
AOS	6B-FC27	Heating Valve Command
AOS	6B-FC27	Cooling Valve Command
BO	6B-FC27	Fan command
BI	6B-FC27	Fan Status
CS	6B-FC28	Occupied Command
AI	6B-FC28	Zone Temperature
AI	6B-FC28	Zone Setpoint
AOS	6B-FC28	Heating Valve Command
AOS	6B-FC28	Cooling Valve Command
BO	6B-FC28	Fan Command
BI	6B-FC28	Fan Status
CS	6B-FC29	Temp Occ. Status C.S.
BO	6B-FC29	Occupied Command
AI	6B-FC29	Zone Temperature
AI	6B-FC29	Zone Setpoint
AOS	6B-FC29	Heating Valve Command
AOS	6B-FC29	Cooling Valve Command
BO	6B-FC29	Fan Command
BI	6B-FC29	Fan Status
CS	6A-FC27	Temp Occ.Status c.s.
BO	MISC-6	ExFan 6C Command
BI	MISC-6	ExFan 6C Status
	Building 3	
Points	Equipment	Type
	NC-15	Network controller
NC15-HRW	8C-FC01	7, 1, 3, VAV
NC15-HRW	8C-FC02	8, 1, 3, VAV
NC15-HRW	8C-FC03	9, 1, 3, VAV
NC15-HRW	8C-FC04	10, 1, 3, VAV
NC15-HRW	8C-FC05	11, 1, 3, VAV
NC15-HRW	8C-FC06	12, 1, 3, VAV
NC15-HRW	8C-FC101	101, 1, 3, VAV
NC15-HRW	8C-FC102	102, 1, 3, VAV
NC15-HRW	8C-FC103	103, 1, 3, VAV
NC15-HRW	8C-FC104	104, 1, 3, VAV
NC15-HRW	8C-FC105	105, 1, 3, VAV
NC15-HRW	8C-FC106	106, 1, 3, VAV
NC15-HRW	8C-FC107	107, 1, 3, VAV
NC15-HRW	8C-FC108	108, 1, 3, VAV
NC15-HRW	8C-FC109	109, 1, 3, VAV
NC15-HRW	8C-FC110	110, 1, 3, VAV
NC15-HRW	8C-FC111	111, 1, 3, VAV
NC15-HRW	8C-FC112	112, 1, 3, VAV
NC15-HRW	9C-FC01	13, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC15-HRW	9C-FC02	14, 1, 3, VAV
NC15-HRW	9C-FC03	15, 1, 3, VAV
NC15-HRW	9C-FC04	16, 1, 3, VAV
NC15-HRW	9C-FC05	17, 1, 3, VAV
NC15-HRW	9C-FC06	18, 1, 3, VAV
NC15-HRW	7C-FC01	1, 1, 3, VAV
NC15-HRW	7C-FC02	2, 1, 3, VAV
NC15-HRW	7C-FC03	3, 1, 3, VAV
NC15-HRW	7C-FC04	4, 1, 3, VAV
NC15-HRW	7C-FC05	5, 1, 3, VAV
NC15-HRW	7C-FC06	6, 1, 3, VAV
NC15-HRW	6A-201	201, 1, 3, VMA
NC15-HRW	6A-202	202, 1, 3, VMA
NC15-HRW	6A-203	203, 1, 3, VMA
NC15-HRW	6A-204	204, 1, 3, VMA
NC15-HRW	6A-205	205, 1, 3, VMA
NC15-HRW	7A-UNT	206, 1, 3, UNT
NC15-HRW	7A-AHU1	200, 1, 3, AHU
NC15-HRW	9C-FC1	20, 1, 3, VAV
NC15-HRW	9C-FC2	21, 1, 3, VAV
NC15-HRW	9C-FC3	22, 1, 3, VAV
NC15-HRW	9C-FC4	23, 1, 3, VAV
NC15-HRW	9C-FC5	24, 1, 3, VAV
NC15-HRW	9C-FC6	25, 1, 3, VAV
NC15-HRW	9C-FC7	26, 1, 3, VAV
NC15-HRW	9C-FC8	27, 1, 3, VAV
NC15-HRW	9C-FC9	28, 1, 3, VAV
NC15-HRW	9C-FC10	29, 1, 3, VAV
NC15-HRW	9C-FC11	30, 1, 3, VAV
NC15-HRW	9C-FC12	31, 1, 3, VAV
NC15-HRW	9C-FC13	32, 1, 3, VAV
MC	AHU1-OR	AM_OVR
SLAVE		BO, AHU1-OR, PMP-EN, AHU1-OR, AM_OVR
SLAVE		BO, CHLR-4, CHLR-C, AHU1-OR, AM_OVR
SLAVE		BO, CHLR-4, ISOVLV-C, AHU1-OR, AM_OVR
BD	AHU1-OR	----------
CS	AHU1-OR	Ahu 1 CS Object
AI	AHU1-OR	Outside Air Temp
AI	AHU1-OR	Return Air Humidity
AI	AHU1-OR	Return Air Temperature
AI	AHU1-OR	Outside Air Humidity
AI	AHU1-OR	Discharge Air Temp
AI	AHU1-OR	Mixed Air Temperature
AOS	AHU1-OR	Damper Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	AHU1-OR	Heating Valve Command
AOS	AHU1-OR	Cooling Valve Command
AOS	AHU1-OR	Humidity Command
BI	AHU1-OR	Supply Fan Status
BI	AHU1-OR	Low Temp Alarm
BO	AHU1-OR	Supply Fan Command
BO	AHU1-OR	Humidity Enable
BO	AHU1-OR	OR Hum Interlock
AI	AHU1-OR	Chilled Water Supply T
AI	AHU1-OR	Chilled Water Return T
AI	AHU1-OR	P2 Chill Water Return
AI	AHU1-OR	P1 Chill Water Return
BI	AHU1-OR	Pump1 Status
BI	AHU1-OR	Pump2 Status
BO	AHU1-OR	Pump 1 Enable
BO	AHU1-OR	Pump 2 Enable
BO	AHU1-OR	Lead/Lag Pump Enable
BO	8C-FC05	Occupied Command
AI	8C-FC05	Zone Temp
AI	8C-FC05	Zone Setpoint
AOS	8C-FC05	Heating Valve Command
AOS	8C-FC05	Cooling Valve Command
BO	8C-FC05	Fan Command
BI	8C-FC05	Fan Status
CS	8C-FC05	Temp Occ.Status C.S.
BI	8C-FC05	Pan Alarm Status
BO	8C-FC112	Occupied Command
AI	8C-FC112	Zone Temp
AI	8C-FC112	Zone Setpoint
AOS	8C-FC112	Heating Valve Command
AOS	8C-FC112	Cooling Valve Command
AI	8C-FC112	Discharge Temp
BO	8C-FC112	Fan Command
BI	8C-FC112	Fan Status
BI	8C-FC112	Pan Alarm Status
CS	8C-FC112	Temp Occ.Status C.S.
BO	8C-FC111	Occupied Command
AI	8C-FC111	Zone Temp
AI	8C-FC111	Zone Setpoint
AOS	8C-FC111	Heating Valve Command
AOS	8C-FC111	Cooling Valve Command
AI	8C-FC111	Discharge Temp
BO	8C-FC111	Fan Command
BI	8C-FC111	Fan Status
BI	8C-FC111	Pan Alarm Status
CS	8C-FC111	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	8C-FC110	Occupied Command
AI	8C-FC110	Zone Temp
AI	8C-FC110	Zone Setpoint
AOS	8C-FC110	Heating Valve Command
AOS	8C-FC110	Cooling Valve Command
AI	8C-FC110	Discharge Temp
BO	8C-FC110	Fan Command
BI	8C-FC110	Fan Status
BI	8C-FC110	Pan Alarm Status
CS	8C-FC110	Temp Occ.Status C.S.
BO	8C-FC109	Occupied Command
AI	8C-FC109	Zone Temp
AI	8C-FC109	Zone Setpoint
AOS	8C-FC109	Heating Valve Command
AOS	8C-FC109	Cooling Valve Command
AI	8C-FC109	Discharge Temp
BO	8C-FC109	Fan Command
BI	8C-FC109	Fan Status
BI	8C-FC109	Pan Alarm Status
CS	8C-FC109	Temp Occ.Status C.S.
BO	8C-FC108	Occupied Command
AI	8C-FC108	Zone Temp
AI	8C-FC108	Zone Setpoint
AOS	8C-FC108	Heating Valve Command
AOS	8C-FC108	Cooling Valve Command
AI	8C-FC108	Discharge Temp
BO	8C-FC108	Fan Command
BI	8C-FC108	Fan Status
BI	8C-FC108	Pan Alarm Status
CS	8C-FC108	Temp Occ.Status C.S.
BO	8C-FC107	Occupied Command
AI	8C-FC107	Zone Temp
AI	8C-FC107	Zone Setpoint
AOS	8C-FC107	Heating Valve Command
AOS	8C-FC107	Cooling Valve Command
AI	8C-FC107	Discharge Temp
BO	8C-FC107	Fan Command
BI	8C-FC107	Fan Status
BI	8C-FC107	Pan Alarm Status
CS	8C-FC107	Temp Occ.Status C.S.
BO	8C-FC106	Occupied Command
AI	8C-FC106	Zone Temp
AI	8C-FC106	Zone Setpoint
AOS	8C-FC106	Heating Valve Command
AOS	8C-FC106	Cooling Valve Command
AI	8C-FC106	Discharge Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	8C-FC106	Fan Command
BI	8C-FC106	Fan Status
BI	8C-FC106	Pan Alarm Status
CS	8C-FC106	Temp Occ.Status C.S.
BO	8C-FC105	Occupied Command
AI	8C-FC105	Zone Temp
AI	8C-FC105	Zone Setpoint
AOS	8C-FC105	Heating Valve Command
AOS	8C-FC105	Cooling Valve Command
AI	8C-FC105	Discharge Temp
BO	8C-FC105	Fan Command
BI	8C-FC105	Fan Status
BI	8C-FC105	Pan Alarm Status
CS	8C-FC105	Temp Occ.Status C.S.
BO	8C-FC104	Occupied Command
AI	8C-FC104	Zone Temp
AI	8C-FC104	Zone Setpoint
AOS	8C-FC104	Heating Valve Command
AOS	8C-FC104	Cooling Valve Command
AI	8C-FC104	Dicharge Temp
BO	8C-FC104	Fan Command
BI	8C-FC104	Fan Status
BI	8C-FC104	Pan Alarm Status
CS	8C-FC104	Temp Occ.Status C.S.
BO	8C-FC103	Occupied Command
AI	8C-FC103	Zone Temp
AI	8C-FC103	Zone Setpoint
AOS	8C-FC103	Heating Valve Command
AOS	8C-FC103	Cooling Valve Command
AI	8C-FC103	Discharge Temp
BO	8C-FC103	Fan Command
BI	8C-FC103	Fan Status
BI	8C-FC103	Pan Alarm Status
CS	8C-FC103	Temp Occ.Status C.S.
BO	8C-FC102	Occupied Command
AI	8C-FC102	Zone Temp
AI	8C-FC102	Zone Setpoint
AOS	8C-FC102	Heating Valve Command
AOS	8C-FC102	Cooling Valve Command
AI	8C-FC102	Discharge Temp
BO	8C-FC102	Fan Command
BI	8C-FC102	Fan Status
BI	8C-FC102	Pan Alarm Status
CS	8C-FC102	Temp Occ.Status C.S.
BO	8C-FC101	Occupied Command
AI	8C-FC101	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	8C-FC101	Zone Setpoint
AOS	8C-FC101	Heating Valve Command
AOS	8C-FC101	Cooling Valve Command
AI	8C-FC101	Discharge Temp
BO	8C-FC101	Fan Command
BI	8C-FC101	Fan Status
BI	8C-FC101	Pan Alarm Status
CS	8C-FC101	Temp Occ.Status C.S.
BO	7C-FC01	Occupied Command
AI	7C-FC01	Zone Temp
AI	7C-FC01	Zone Setpoint
AOS	7C-FC01	Heating Valve Command
AOS	7C-FC01	Cooling Valve Command
BO	7C-FC01	Fan Command
BI	7C-FC01	Fan Status
BI	7C-FC01	Pan Alarm Status
CS	7C-FC01	Temp Occ.Status C.S.
BO	7C-FC02	Occupied Command
AI	7C-FC02	Zone Temp
AI	7C-FC02	Zone Setpoint
AOS	7C-FC02	Heating Valve Command
AOS	7C-FC02	Cooling Valve Command
BO	7C-FC02	Fan Command
BI	7C-FC02	Fan Status
BI	7C-FC02	Pan Alarm Status
CS	7C-FC02	Temp Occ.Status C.S.
BO	7C-FC03	Occupied Command
AI	7C-FC03	Zone Temp
AI	7C-FC03	Zone Setpoint
AOS	7C-FC03	Heating Valve Command
AOS	7C-FC03	Cooling Valve Command
BO	7C-FC03	Fan Command
BI	7C-FC03	Fan Status
BI	7C-FC03	Pan Alarm Status
CS	7C-FC03	Temp Occ.Status C.S.
BO	7C-FC04	Occupied Command
AI	7C-FC04	Zone Temp
AI	7C-FC04	Zone Setpoint
AOS	7C-FC04	Heating Valve Command
AOS	7C-FC04	Cooling Valve Command
BO	7C-FC04	Fan Command
BI	7C-FC04	Fan Status
BI	7C-FC04	Pan Alarm Status
CS	7C-FC04	Temp Occ.Status C.S.
BO	7C-FC05	Occupied Command
AI	7C-FC05	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	7C-FC05	Zone Setpoint
AOS	7C-FC05	Heating Valve Command
AOS	7C-FC05	Cooling Valve Command
BO	7C-FC05	Fan Command
BI	7C-FC05	Fan Status
BI	7C-FC05	Pan Alarm Status
CS	7C-FC05	Temp Occ.Status C.S.
BO	7C-FC06	Occupied Command
AI	7C-FC06	Zone Temp
AI	7C-FC06	Zone Setpoint
AOS	7C-FC06	Heating Valve Command
AOS	7C-FC06	Cooling Valve Command
BO	7C-FC06	Fan Command
BI	7C-FC06	Fan Status
BI	7C-FC06	Pan Alarm Status
CS	7C-FC06	Temp Occ.Status C.S.
BO	8C-FC01	Occupied Command
AI	8C-FC01	Zone Temp
AI	8C-FC01	Zone Setpoint
AOS	8C-FC01	Heating Valve Command
AOS	8C-FC01	Cooling Valve Command
BO	8C-FC01	Fan Command
BI	8C-FC01	Fan Status
BI	8C-FC01	Pan Alarm Status
CS	8C-FC01	Temp Occ.Status C.S.
BO	8C-FC02	Occupied Command
AI	8C-FC02	Zone Temp
AI	8C-FC02	Zone Setpoint
AOS	8C-FC02	Heating Valve Command
AOS	8C-FC02	Cooling Valve Command
BO	8C-FC02	Fan Command
BI	8C-FC02	Fan Status
BI	8C-FC02	Pan Alarm Status
CS	8C-FC02	Temp Occ.Status C.S.
BO	8C-FC03	Occupied Command
AI	8C-FC03	Zone Temp
AI	8C-FC03	Zone Setpoint
AOS	8C-FC03	Heating Valve Command
AOS	8C-FC03	Cooling Valve Command
BO	8C-FC03	Fan Command
BI	8C-FC03	Fan Status
BI	8C-FC03	Pan Alarm Status
CS	8C-FC03	Temp Occ.Status C.S.
BO	8C-FC04	Occupied Command
AI	8C-FC04	Zone Temp
AI	8C-FC04	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	8C-FC04	Heating Valve Command
AOS	8C-FC04	Cooling Valve Command
BO	8C-FC04	Fan Command
BI	8C-FC04	Fan Status
BI	8C-FC04	Pan Alarm Status
CS	8C-FC04	Temp Occ.Status C.S.
BO	8C-FC06	Occupied Command
AI	8C-FC06	Zone Temp
AI	8C-FC06	Zone Setpoint
AOS	8C-FC06	Heating Valve Command
AOS	8C-FC06	Cooling Valve Command
BO	8C-FC06	Fan Command
BI	8C-FC06	Fan Status
BI	8C-FC06	Pan Alarm Status
CS	8C-FC06	Temp Occ.Status C.S.
BO	9C-FC01	Occupied Command
AI	9C-FC01	Zone Temp
AI	9C-FC01	Zone Setpoint
AOS	9C-FC01	Heating Valve Command
AOS	9C-FC01	Cooling Valve Command
BO	9C-FC01	Fan Command
BI	9C-FC01	Fan Status
BI	9C-FC01	Pan Alarm Status
CS	9C-FC01	Temp Occ.Status C.S.
BO	9C-FC02	Occupied Command
AI	9C-FC02	Zone Temp
AI	9C-FC02	Zone Setpoint
AOS	9C-FC02	Heating Valve Command
AOS	9C-FC02	Cooling Valve Command
BO	9C-FC02	Fan Command
BI	9C-FC02	Fan Status
BI	9C-FC02	Pan Alarm Status
CS	9C-FC02	Temp Occ.Status C.S.
BO	9C-FC03	Occupied Command
AI	9C-FC03	Zone Temp
AI	9C-FC03	Zone Setpoint
AOS	9C-FC03	Heating Valve Command
AOS	9C-FC03	Cooling Valve Command
BO	9C-FC03	Fan Command
BI	9C-FC03	Fan Status
BI	9C-FC03	Pan Alarm Status
CS	9C-FC03	Temp Occ.Status C.S.
BO	9C-FC04	Occupied Command
AI	9C-FC04	Zone Temp
AI	9C-FC04	Zone Setpoint
AOS	9C-FC04	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	9C-FC04	Cooling Valve Command
BO	9C-FC04	Fan Command
BI	9C-FC04	Fan Status
BI	9C-FC04	Pan Alarm Status
CS	9C-FC04	Temp Occ.Status C.S.
BO	9C-FC05	Occupied Command
AI	9C-FC05	Zone Temp
AI	9C-FC05	Zone Setpoint
AOS	9C-FC05	Heating Valve Command
AOS	9C-FC05	Cooling Valve Command
BO	9C-FC05	Fan Command
BI	9C-FC05	Fan Status
BI	9C-FC05	Pan Alarm Status
CS	9C-FC05	Temp Occ.Status C.S.
BO	9C-FC06	Occupied Command
AI	9C-FC06	Zone Temp
AI	9C-FC06	Zone Setpoint
AOS	9C-FC06	Heating Valve Command
AOS	9C-FC06	Cooling Valve Command
BO	9C-FC06	Fan Command
BI	9C-FC06	Fan Status
BI	9C-FC06	Pan Alarm Status
CS	9C-FC06	Temp Occ.Status C.S.
BO	MISC-7	Exhaust Fan 7C Command
BI	MISC-7	Exhaust Fan 7C Status
BO	MISC-8	Ehaust Fan 8C Command
BI	MISC-8	Exhaust Fan 8C Status
BO	MISC-9	Exhaust Fan 9C Command
BI	MISC-9	Exhaust Fan 9C Staus
AI	6A-OR1	Zone Temperature
AD	6A-OR1	Actual Heating Setpoint
AD	6A-OR1	Supply Cfm
AI	6A-OR1	Zone Humidity
AOS	6A-OR1	Humidity Vlv Feedback
CS	6A-OR1	Cfm Setpoint CS
AI	6A-BLOCK	Zone Temperature
AD	6A-BLOCK	Actual Heating Setpoint
AD	6A-BLOCK	Supply Cfm
AI	6A-BLOCK	Zone Humidity
AOS	6A-BLOCK	Humidity Valve Feedback
CS	6A-BLOCK	Center Area
AI	6A-OR3	Zone Temperature
AD	6A-OR3	Actual Heating Setpoint
AD	6A-OR3	Supply Cfm
AI	6A-OR3	Zone Humidity
AOS	6A-OR3	Humidity Valve Feedback

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	6A-OR3	Cfm Setpoint CS
AI	6A-OR4	Zone Temperature
AD	6A-OR4	Actual Heating Setpoint
AD	6A-OR4	Supply Cfm
AI	6A-OR4	Zone Humidity
AOS	6A-OR4	Humidity Valve Feedback
CS	6A-OR4	Cfm Setpoint CS
AI	6A-OR2	Zone Temperature
AD	6A-OR2	Actual Heating Setpoint
AD	6A-OR2	Supply Cfm
AI	6A-OR2	Zone Humidity
AOS	6A-OR2	Humidity Valve Feedback
CS	6A-OR2	CFM Setpoint CS
BO	9C-FCU1	Occupied Command
AI	9C-FCU1	Zone Temp
AI	9C-FCU1	Supply Air Temp
AI	9C-FCU1	Zone Setpoint
AOS	9C-FCU1	Heating Valve Command
AOS	9C-FCU1	Cooling Valve Command
BO	9C-FCU1	Fan Command
BI	9C-FCU1	Fan Status
BI	9C-FCU1	Pan Alarm Status
CS	9C-FCU1	Temp Occ.Status C.S.
BO	9C-FCU2	Occupied Command
AI	9C-FCU2	Zone Temp
AI	9C-FCU2	Supply Air Temp
AI	9C-FCU2	Zone Setpoint
AOS	9C-FCU2	Heating Valve Command
AOS	9C-FCU2	Cooling Valve Command
BO	9C-FCU2	Fan Command
BI	9C-FCU2	Fan Status
BI	9C-FCU2	Pan Alarm Status
CS	9C-FCU2	Temp Occ.Status C.S.
BO	9C-FCU3	Occupied Command
AI	9C-FCU3	Zone Temp
AI	9C-FCU3	Supply Air Temp
AI	9C-FCU3	Zone Setpoint
AOS	9C-FCU3	Heating Valve Command
AOS	9C-FCU3	Cooling Valve Command
BO	9C-FCU3	Fan Command
BI	9C-FCU3	Fan Status
BI	9C-FCU3	Pan Alarm Status
CS	9C-FCU3	Temp Occ.Status C.S.
BO	9C-FCU4	Occupied Command
AI	9C-FCU4	Zone Temp
AI	9C-FCU4	Supply Air Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	9C-FCU4	Zone Setpoint
AOS	9C-FCU4	Heating Valve Command
AOS	9C-FCU4	Cooling Valve Command
BO	9C-FCU4	Fan Command
BI	9C-FCU4	Fan Status
BI	9C-FCU4	Pan Alarm Status
CS	9C-FCU4	Temp Occ.Status C.S.
BO	9C-FCU5	Occupied Command
AI	9C-FCU5	Zone Temp
AI	9C-FCU5	Supply Air Temp
AI	9C-FCU5	Zone Setpoint
AOS	9C-FCU5	Heating Valve Command
AOS	9C-FCU5	Cooling Valve Command
BO	9C-FCU5	Fan Command
BI	9C-FCU5	Fan Status
BI	9C-FCU5	Pan Alarm Status
CS	9C-FCU5	Temp Occ.Status C.S.
BO	9C-FCU6	Occupied Command
AI	9C-FCU6	Zone Temp
AI	9C-FCU6	Supply Air Temp
AI	9C-FCU6	Zone Setpoint
AOS	9C-FCU6	Heating Valve Command
AOS	9C-FCU6	Cooling Valve Command
BO	9C-FCU6	Fan Command
BI	9C-FCU6	Fan Status
BI	9C-FCU6	Pan Alarm Status
CS	9C-FCU6	Temp Occ.Status C.S.
BO	9C-FCU6	Exhaust Fan Command
BI	9C-FCU6	Exhaust Fan Status
JCB	9C-FCU6	EF-C
BO	9C-FCU7	Occupied Command
AI	9C-FCU7	Zone Temp
AI	9C-FCU7	Supply Air Temp
AI	9C-FCU7	Zone Setpoint
AOS	9C-FCU7	Heating Valve Command
AOS	9C-FCU7	Cooling Valve Command
BO	9C-FCU7	Fan Command
BI	9C-FCU7	Fan Status
BI	9C-FCU7	Pan Alarm Status
CS	9C-FCU7	Temp Occ.Status C.S.
BO	9C-FCU8	Occupied Command
AI	9C-FCU8	Zone Temp
AI	9C-FCU8	Supply Air Temp
AI	9C-FCU8	Zone Setpoint
AOS	9C-FCU8	Heating Valve Command
AOS	9C-FCU8	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	9C-FCU8	Fan Command
BI	9C-FCU8	Fan Status
BI	9C-FCU8	Pan Alarm Status
CS	9C-FCU8	Temp Occ.Status C.S.
BO	9C-FCU9	Occupied Command
AI	9C-FCU9	Zone Temp
AI	9C-FCU9	Supply Air Temp
AI	9C-FCU9	Zone Setpoint
AOS	9C-FCU9	Heating Valve Command
AOS	9C-FCU9	Cooling Valve Command
BO	9C-FCU9	Fan Command
BI	9C-FCU9	Fan Status
BI	9C-FCU9	Pan Alarm Status
CS	9C-FCU9	Temp Occ.Status C.S.
BO	9C-FCU10	Occupied Command
AI	9C-FCU10	Zone Temp
AI	9C-FCU10	Supply Air Temp
AI	9C-FCU10	Zone Setpoint
AOS	9C-FCU10	Heating Valve Command
AOS	9C-FCU10	Cooling Valve Command
BO	9C-FCU10	Fan Command
BI	9C-FCU10	Fan Status
BI	9C-FCU10	Pan Alarm Status
CS	9C-FCU10	Temp Occ.Status C.S.
BO	9C-FCU11	Occupied Command
AI	9C-FCU11	Zone Temp
AI	9C-FCU11	Supply Air Temp
AI	9C-FCU11	Zone Setpoint
AOS	9C-FCU11	Heating Valve Command
AOS	9C-FCU11	Cooling Valve Command
BO	9C-FCU11	Fan Command
BI	9C-FCU11	Fan Status
BI	9C-FCU11	Pan Alarm Status
CS	9C-FCU11	Temp Occ.Status C.S.
BO	9C-FCU12	Occupied Command
AI	9C-FCU12	Zone Temp
AI	9C-FCU12	Supply Air Temp
AI	9C-FCU12	Zone Setpoint
AOS	9C-FCU12	Heating Valve Command
AOS	9C-FCU12	Cooling Valve Command
BO	9C-FCU12	Fan Command
BI	9C-FCU12	Fan Status
BI	9C-FCU12	Pan Alarm Status
CS	9C-FCU12	Temp Occ.Status C.S.
BO	9C-FCU13	Occupied Command
AI	9C-FCU13	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	9C-FCU13	Supply Air Temp
AI	9C-FCU13	Zone Setpoint
AOS	9C-FCU13	Heating Valve Command
AOS	9C-FCU13	Cooling Valve Command
BO	9C-FCU13	Fan Command
BI	9C-FCU13	Fan Status
BI	9C-FCU13	Pan Alarm Status
CS	9C-FCU13	Temp Occ.Status C.S.
	Building 3	
Point	Equipment	Type
	NC-16	Network controller
NC16-HRW	10A-FC01	18, 1, 3, VAV
NC16-HRW	10A-FC02	19, 1, 3, VAV
NC16-HRW	10A-FC03	98, 1, 3, VAV
NC16-HRW	10A-FC04	20, 1, 3, VAV
NC16-HRW	10A-FC05	21, 1, 3, VAV
NC16-HRW	10A-FC06	22, 1, 3, VAV
NC16-HRW	10A-FC07	23, 1, 3, VAV
NC16-HRW	10A-FC08	24, 1, 3, VAV
NC16-HRW	10A-FC09	25, 1, 3, VAV
NC16-HRW	10A-FC10	26, 1, 3, VAV
NC16-HRW	10A-FC11	99, 1, 3, VAV
NC16-HRW	10A-FC12	27, 1, 3, VAV
NC16-HRW	10B-FC01	28, 1, 3, VAV
NC16-HRW	10B-FC02	29, 1, 3, VAV
NC16-HRW	10B-FC03	30, 1, 3, VAV
NC16-HRW	10B-FC04	31, 1, 3, VAV
NC16-HRW	10B-FC05	32, 1, 3, VAV
NC16-HRW	10B-FC06	33, 1, 3, VAV
NC16-HRW	10B-FC07	34, 1, 3, VAV
NC16-HRW	10B-FC08	35, 1, 3, VAV
NC16-HRW	10B-FC09	36, 1, 3, VAV
NC16-HRW	10B-FC10	37, 1, 3, VAV
NC16-HRW	10B-FC11	38, 1, 3, VAV
NC16-HRW	10B-FC12	39, 1, 3, VAV
NC16-HRW	10B-FC13	40, 1, 3, VAV
NC16-HRW	10C-FC01	1, 1, 3, VAV
NC16-HRW	10C-FC02	2, 1, 3, VAV
NC16-HRW	10C-FC03	3, 1, 3, VAV
NC16-HRW	10C-FC04	4, 1, 3, VAV
NC16-HRW	10C-FC05	5, 1, 3, VAV
NC16-HRW	10C-FC06	6, 1, 3, VAV
NC16-HRW	10C-FC07	7, 1, 3, VAV
NC16-HRW	10C-FC08	8, 1, 3, VAV
NC16-HRW	10C-FC09	9, 1, 3, VAV
NC16-HRW	10C-FC10	10, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC16-HRW	10C-FC11	11, 1, 3, VAV
NC16-HRW	10C-FC12	12, 1, 3, VAV
NC16-HRW	10C-FC13	13, 1, 3, VAV
NC16-HRW	10C-FC14	14, 1, 3, VAV
NC16-HRW	10C-FC15	15, 1, 3, VAV
NC16-HRW	10C-FC16	16, 1, 3, VAV
NC16-HRW	10C-FC17	17, 1, 3, VAV
NC16-HRW	11A-FC01	59, 1, 3, VAV
NC16-HRW	11A-FC02	60, 1, 3, VAV
NC16-HRW	11A-FC03	61, 1, 3, VAV
NC16-HRW	11A-FC05	63, 1, 3, VAV
NC16-HRW	11A-FC06	64, 1, 3, VAV
NC16-HRW	11A-FC07	65, 1, 3, VAV
NC16-HRW	11A-FC08	66, 1, 3, VAV
NC16-HRW	11A-FC09	67, 1, 3, VAV
NC16-HRW	11A-FC10	68, 1, 3, VAV
NC16-HRW	11A-FC11	69, 1, 3, VAV
NC16-HRW	11A-FC12	70, 1, 3, VAV
NC16-HRW	11A-FC13	71, 1, 3, VAV
NC16-HRW	11B-FC01	72, 1, 3, VAV
NC16-HRW	11B-FC02	73, 1, 3, VAV
NC16-HRW	11B-FC03	74, 1, 3, VAV
NC16-HRW	11B-FC04	75, 1, 3, VAV
NC16-HRW	11B-FC05	76, 1, 3, VAV
NC16-HRW	11B-FC06	77, 1, 3, VAV
NC16-HRW	11B-FC07	78, 1, 3, VAV
NC16-HRW	11B-FC08	79, 1, 3, VAV
NC16-HRW	11B-FC09	80, 1, 3, VAV
NC16-HRW	11B-FC10	81, 1, 3, VAV
NC16-HRW	11B-FC11	82, 1, 3, VAV
NC16-HRW	11B-FC12	83, 1, 3, VAV
NC16-HRW	11C-FC01	43, 1, 3, VAV
NC16-HRW	11C-FC02	44, 1, 3, VAV
NC16-HRW	11C-FC03	45, 1, 3, VAV
NC16-HRW	11C-FC04	46, 1, 3, VAV
NC16-HRW	11C-FC05	47, 1, 3, VAV
NC16-HRW	11C-FC06	48, 1, 3, VAV
NC16-HRW	11C-FC07	49, 1, 3, VAV
NC16-HRW	11C-FC08	50, 1, 3, VAV
NC16-HRW	11C-FC09	51, 1, 3, VAV
NC16-HRW	11C-FC10	52, 1, 3, VAV
NC16-HRW	11C-FC11	53, 1, 3, VAV
NC16-HRW	11C-FC12	54, 1, 3, VAV
NC16-HRW	11C-FC13	55, 1, 3, VAV
NC16-HRW	11C-FC14	56, 1, 3, VAV
NC16-HRW	11C-FC15	57, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC16-HRW	11C-FC16	58, 1, 3, VAV
NC16-HRW	11B-EXFN	127, 1, 3, UNT
NC16-HRW	LSM-LIEB	128, 1, 3, MIG
NC16-HRW	DAP	130, 1, 3, VND
BO	EF11A-CM	Exhaust FAN 11 A Command
BI	EF11A-ST	Exhaust Fan 11 A Status
BO	EF11B-CM	Exhaust FAN 11 B Command
BI	EF11B-ST	Exhaust Fan 11 B Status
BO	EF11-CMD	Exhaust FAN 11 Command
BI	EF11-STS	Exhaust Fan 11 Status
BD	___	Exhaust Fan 11E
BO	EF11EF-C	Exhaust FAN 11 E Command
BI	EF11EF-S	Exhaust Fan 11E Status
AOS	EF11ED-C	Exh Fan 11E Var Spd Dr
BO	EF11ED-S	Exhaust Fan 11E VSD Stat
BI	EF11ED-A	Exhaust Fan 11E Alarm
AI	EF11E-F	11E Air Flow
AOS	E11EF-ST	Exhaust Fan 11E Flow Stp
BD	__	Exhaust Fan 11F
BO	EF11FF-C	Exhaust FAN 11 F Command
BI	EF11FF-S	Exhaust Fan 11E Status
AOS	EF11FD-C	Exh Fan 11D Var Spd Dr
BI	EF11FD-A	Exhaust Fan 11F Alarm
BO	EF11FD-S	Exhaust FAN 11F VSD Stat
AI	EF11F-F	11E Air Flow
AOS	E11FF-ST	Exhaust Fan 11F Flow Stp
BD	___	MISC
BD	ACLG-OVD	A Wing Clg Valve Overide
BD	AHTG-OVD	A Wing Htg Valve Overide
BD	BCLG-OVD	B Wing Clg Valve Overide
BD	BHTG-OVD	B Wing Htg Valve Overide
BD	CCLG-OVD	C Wing Clg Valve Overide
BD	CHTGVLV	C Wing Htg Valve Overide
BO	EF10A-CM	Exhaust FAN 10 A Command
BI	EF10A-ST	Exhaust Fan 10 A Status
BO	EF10B-CM	Exhaust FAN 10 B Command
BI	EF10B-ST	Exhaust Fan 10 B Status
BO	EF10-CMD	Exhaust FAN 10 Command
BI	EF10-STS	Exhaust Fan 10 Status
BD	ACLG-OVD	A Wing Clg Valve Overide
BD	AHTG-OVD	A Wing Htg Valve Overide

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BD	BHTG-OVD	B Wing Htg Valve Overide
BD	BCLG-OVD	B Wing Clg Valve Overide
BD	CCLG-OVD	C Wing Clg Valve Overide
BD	CHTG-OVD	C Wing Htg Valve Overide
BO	10A-FC01	Occupied Command
AI	10A-FC01	Zone Temp
AI	10A-FC01	Zone Setpoint
AOS	10A-FC01	Heating Valve Command
AOS	10A-FC01	Cooling Valve Command
BO	10A-FC01	Fan Command
BI	10A-FC01	Fan Status
BI	10A-FC01	Pan Alarm Status
CS	10A-FC01	Temp Occ.Status C.S.
BO	10A-FC02	Occupied Command
AI	10A-FC02	Zone Temp
AI	10A-FC02	Zone Setpoint
AOS	10A-FC02	Heating Valve Command
AOS	10A-FC02	Cooling Valve Command
BO	10A-FC02	Fan Command
BI	10A-FC02	Fan Status
BI	10A-FC02	Pan Alarm Status
CS	10A-FC02	Temp Occ.Status C.S.
BO	10A-FC03	Occupied Command
AI	10A-FC03	Zone Temp
AI	10A-FC03	Zone Setpoint
AOS	10A-FC03	Heating Valve Command
AOS	10A-FC03	Cooling Valve Command
BO	10A-FC03	Fan Command
BI	10A-FC03	Fan Status
BI	10A-FC03	Pan Alarm Status
CS	10A-FC03	Temp Occ.Status C.S.
BO	10A-FC04	Occupied Command
AI	10A-FC04	Zone Temp
AI	10A-FC04	Zone Setpoint
AOS	10A-FC04	Heating Valve Command
AOS	10A-FC04	Cooling Valve Command
BO	10A-FC04	Fan Command
BI	10A-FC04	Fan Status
BI	10A-FC04	Pan Alarm Status
CS	10A-FC04	Temp Occ.Status C.S.
BO	10A-FC05	Occupied Command
AI	10A-FC05	Zone Temp
AI	10A-FC05	Zone Setpoint
AOS	10A-FC05	Heating Valve Command
AOS	10A-FC05	Cooling Valve Command
BO	10A-FC05	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	10A-FC05	Fan Status
BI	10A-FC05	Pan Alarm Status
CS	10A-FC05	Temp Occ.Status C.S.
BO	10A-FC06	Occupied Command
AI	10A-FC06	Zone Temp
AI	10A-FC06	Zone Setpoint
AOS	10A-FC06	Heating Valve Command
AOS	10A-FC06	Cooling Valve Command
BO	10A-FC06	Fan Command
BI	10A-FC06	Fan Status
BI	10A-FC06	Pan Alarm Status
CS	10A-FC06	Temp Occ.Status C.S.
BO	10A-FC07	Occupied Command
AI	10A-FC07	Zone Temp
AI	10A-FC07	Zone Setpoint
AOS	10A-FC07	Heating Valve Command
AOS	10A-FC07	Cooling Valve Command
BO	10A-FC07	Fan Command
BI	10A-FC07	Fan Status
BI	10A-FC07	Pan Alarm Status
CS	10A-FC07	Temp Occ.Status C.S.
BO	10A-FC08	Occupied Command
AI	10A-FC08	Zone Temp
AI	10A-FC08	Zone Setpoint
AOS	10A-FC08	Heating Valve Command
AOS	10A-FC08	Cooling Valve Command
BO	10A-FC08	Fan Command
BI	10A-FC08	Fan Status
BI	10A-FC08	Pan Alarm Status
CS	10A-FC08	Temp Occ.Status C.S.
BO	10A-FC09	Occupied Command
AI	10A-FC09	Zone Temp
AI	10A-FC09	Zone Setpoint
AOS	10A-FC09	Heating Valve Command
AOS	10A-FC09	Cooling Valve Command
BO	10A-FC09	Fan Command
BI	10A-FC09	Fan Status
BI	10A-FC09	Pan Alarm Status
CS	10A-FC09	Temp Occ.Status C.S.
BO	10A-FC10	Occupied Command
AI	10A-FC10	Zone Temp
AI	10A-FC10	Zone Setpoint
AOS	10A-FC10	Heating Valve Command
AOS	10A-FC10	Cooling Valve Command
BO	10A-FC10	Fan Command
BI	10A-FC10	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	10A-FC10	Pan Alarm Status
CS	10A-FC10	Temp Occ.Status C.S.
BO	10A-FC11	Occupied Command
AI	10A-FC11	Zone Temp
AI	10A-FC11	Zone Setpoint
AOS	10A-FC11	Heating Valve Command
AOS	10A-FC11	Cooling Valve Command
BO	10A-FC11	Fan Command
BI	10A-FC11	Fan Status
BI	10A-FC11	Pan Alarm Status
CS	10A-FC11	Temp Occ.Status C.S.
BO	10A-FC12	Occupied Command
AI	10A-FC12	Zone Temp
AI	10A-FC12	Zone Setpoint
AOS	10A-FC12	Heating Valve Command
AOS	10A-FC12	Cooling Valve Command
BO	10A-FC12	Fan Command
BI	10A-FC12	Fan Status
BI	10A-FC12	Pan Alarm Status
CS	10A-FC12	Temp Occ.Status C.S.
BO	10B-FC01	Occupied Command
AI	10B-FC01	Zone Temp
AI	10B-FC01	Zone Setpoint
AOS	10B-FC01	Heating Valve Command
AOS	10B-FC01	Cooling Valve Command
BO	10B-FC01	Fan Command
BI	10B-FC01	Fan Status
BI	10B-FC01	Pan Alarm Status
CS	10B-FC01	Temp Occ.Status C.S.
BO	10B-FC02	Occupied Command
AI	10B-FC02	Zone Temp
AI	10B-FC02	Zone Setpoint
AOS	10B-FC02	Heating Valve Command
AOS	10B-FC02	Cooling Valve Command
BO	10B-FC02	Fan Command
BI	10B-FC02	Fan Status
BI	10B-FC02	Pan Alarm Status
CS	10B-FC02	Temp Occ.Status C.S.
BO	10B-FC03	Occupied Command
AI	10B-FC03	Zone Temp
AI	10B-FC03	Zone Setpoint
AOS	10B-FC03	Heating Valve Command
AOS	10B-FC03	Cooling Valve Command
BO	10B-FC03	Fan Command
BI	10B-FC03	Fan Status
BI	10B-FC03	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	10B-FC03	Temp Occ.Status C.S.
BO	10B-FC04	Occupied Command
AI	10B-FC04	Zone Temp
AI	10B-FC04	Zone Setpoint
AOS	10B-FC04	Heating Valve Command
AOS	10B-FC04	Cooling Valve Command
BO	10B-FC04	Fan Command
BI	10B-FC04	Fan Status
BI	10B-FC04	Pan Alarm Status
CS	10B-FC04	Temp Occ.Status C.S.
BO	10B-FC05	Occupied Command
AI	10B-FC05	Zone Temp
AI	10B-FC05	Zone Setpoint
AOS	10B-FC05	Heating Valve Command
AOS	10B-FC05	Cooling Valve Command
BO	10B-FC05	Fan Command
BI	10B-FC05	Fan Status
BI	10B-FC05	Pan Alarm Status
CS	10B-FC05	Temp Occ.Status C.S.
BO	10B-FC06	Occupied Command
AI	10B-FC06	Zone Temp
AI	10B-FC06	Zone Setpoint
AOS	10B-FC06	Heating Valve Command
AOS	10B-FC06	Cooling Valve Command
BO	10B-FC06	Fan Command
BI	10B-FC06	Fan Status
BI	10B-FC06	Pan Alarm Status
CS	10B-FC06	Temp Occ.Status C.S.
BO	10B-FC07	Occupied Command
AI	10B-FC07	Zone Temp
AI	10B-FC07	Zone Setpoint
AOS	10B-FC07	Heating Valve Command
AOS	10B-FC07	Cooling Valve Command
BO	10B-FC07	Fan Command
BI	10B-FC07	Fan Status
BI	10B-FC07	Pan Alarm Status
CS	10B-FC07	Temp Occ.Status C.S.
BO	10B-FC08	Occupied Command
AI	10B-FC08	Zone Temp
AI	10B-FC08	Zone Setpoint
AOS	10B-FC08	Heating Valve Command
AOS	10B-FC08	Cooling Valve Command
BO	10B-FC08	Fan Command
BI	10B-FC08	Fan Status
BI	10B-FC08	Pan Alarm Status
CS	10B-FC08	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	10B-FC09	Occupied Command
AI	10B-FC09	Zone Temp
AI	10B-FC09	Zone Setpoint
AOS	10B-FC09	Heating Valve Command
AOS	10B-FC09	Cooling Valve Command
BO	10B-FC09	Fan Command
BI	10B-FC09	Fan Status
BI	10B-FC09	Pan Alarm Status
CS	10B-FC09	Temp Occ.Status C.S.
BO	10B-FC10	Occupied Command
AI	10B-FC10	Zone Temp
AI	10B-FC10	Zone Setpoint
AOS	10B-FC10	Heating Valve Command
AOS	10B-FC10	Cooling Valve Command
BO	10B-FC10	Fan Command
BI	10B-FC10	Fan Status
BI	10B-FC10	Pan Alarm Status
CS	10B-FC10	Temp Occ.Status C.S.
BO	10B-FC11	Occupied Command
AI	10B-FC11	Zone Temp
AI	10B-FC11	Zone Setpoint
AOS	10B-FC11	Heating Valve Command
AOS	10B-FC11	Cooling Valve Command
BO	10B-FC11	Fan Command
BI	10B-FC11	Fan Status
BI	10B-FC11	Pan Alarm Status
CS	10B-FC11	Temp Occ.Status C.S.
BO	10B-FC12	Occupied Command
AI	10B-FC12	Zone Temp
AI	10B-FC12	Zone Setpoint
AOS	10B-FC12	Heating Valve Command
AOS	10B-FC12	Cooling Valve Command
BO	10B-FC12	Fan Command
BI	10B-FC12	Fan Status
BI	10B-FC12	Pan Alarm Status
CS	10B-FC12	Temp Occ.Status C.S.
BO	10B-FC13	Occupied Command
AI	10B-FC13	Zone Temp
AI	10B-FC13	Zone Setpoint
AOS	10B-FC13	Heating Valve Command
AOS	10B-FC13	Cooling Valve Command
BO	10B-FC13	Fan Command
BI	10B-FC13	Fan Status
BI	10B-FC13	Pan Alarm Status
CS	10B-FC13	Temp Occ.Status C.S.
BO	10C-FC01	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	10C-FC01	Zone Temp
AI	10C-FC01	Zone Setpoint
AOS	10C-FC01	Heating Valve Command
AOS	10C-FC01	Cooling Valve Command
BO	10C-FC01	Fan Command
BI	10C-FC01	Fan Status
BI	10C-FC01	Pan Alarm Status
CS	10C-FC01	Temp Occ.Status C.S.
BO	10C-FC02	Occupied Command
AI	10C-FC02	Zone Temp
AI	10C-FC02	Zone Setpoint
AOS	10C-FC02	Heating Valve Command
AOS	10C-FC02	Cooling Valve Command
BO	10C-FC02	Fan Command
BI	10C-FC02	Fan Status
BI	10C-FC02	Pan Alarm Status
CS	10C-FC02	Temp Occ.Status C.S.
BO	10C-FC03	Occupied Command
AI	10C-FC03	Zone Temp
AI	10C-FC03	Zone Setpoint
AOS	10C-FC03	Heating Valve Command
AOS	10C-FC03	Cooling Valve Command
BO	10C-FC03	Fan Command
BI	10C-FC03	Fan Status
BI	10C-FC03	Pan Alarm Status
CS	10C-FC03	Temp Occ.Status C.S.
BO	10C-FC04	Occupied Command
AI	10C-FC04	Zone Temp
AI	10C-FC04	Zone Setpoint
AOS	10C-FC04	Heating Valve Command
AOS	10C-FC04	Cooling Valve Command
BO	10C-FC04	Fan Command
BI	10C-FC04	Fan Status
BI	10C-FC04	Pan Alarm Status
CS	10C-FC04	Temp Occ.Status C.S.
BO	10C-FC05	Occupied Command
AI	10C-FC05	Zone Temp
AI	10C-FC05	Zone Setpoint
AOS	10C-FC05	Heating Valve Command
AOS	10C-FC05	Cooling Valve Command
BO	10C-FC05	Fan Command
BI	10C-FC05	Fan Status
BI	10C-FC05	Pan Alarm Status
CS	10C-FC05	Temp Occ.Status C.S.
BO	10C-FC06	Occupied Command
AI	10C-FC06	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	10C-FC06	Zone Setpoint
AOS	10C-FC06	Heating Valve Command
AOS	10C-FC06	Cooling Valve Command
BO	10C-FC06	Fan Command
BI	10C-FC06	Fan Status
BI	10C-FC06	Pan Alarm Status
CS	10C-FC06	Temp Occ.Status C.S.
BO	10C-FC07	Occupied Command
AI	10C-FC07	Zone Temp
AI	10C-FC07	Zone Setpoint
AOS	10C-FC07	Heating Valve Command
AOS	10C-FC07	Cooling Valve Command
BO	10C-FC07	Fan Command
BI	10C-FC07	Fan Status
BI	10C-FC07	Pan Alarm Status
CS	10C-FC07	Temp Occ.Status C.S.
BO	10C-FC08	Occupied Command
AI	10C-FC08	Zone Temp
AI	10C-FC08	Zone Setpoint
AOS	10C-FC08	Heating Valve Command
AOS	10C-FC08	Cooling Valve Command
BO	10C-FC08	Fan Command
BI	10C-FC08	Fan Status
BI	10C-FC08	Pan Alarm Status
CS	10C-FC08	Temp Occ.Status C.S.
BO	10C-FC09	Occupied Command
AI	10C-FC09	Zone Temp
AI	10C-FC09	Zone Setpoint
AOS	10C-FC09	Heating Valve Command
AOS	10C-FC09	Cooling Valve Command
BO	10C-FC09	Fan Command
BI	10C-FC09	Fan Status
BI	10C-FC09	Pan Alarm Status
CS	10C-FC09	Temp Occ.Status C.S.
BO	10C-FC10	Occupied Command
AI	10C-FC10	Zone Temp
AI	10C-FC10	Zone Setpoint
AOS	10C-FC10	Heating Valve Command
AOS	10C-FC10	Cooling Valve Command
BO	10C-FC10	Fan Command
BI	10C-FC10	Fan Status
BI	10C-FC10	Pan Alarm Status
CS	10C-FC10	Temp Occ.Status C.S.
BO	10C-FC11	Occupied Command
AI	10C-FC11	Zone Temp
AI	10C-FC11	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	10C-FC11	Heating Valve Command
AOS	10C-FC11	Cooling Valve Command
BO	10C-FC11	Fan Command
BI	10C-FC11	Fan Status
BI	10C-FC11	Pan Alarm Status
CS	10C-FC11	Temp Occ.Status C.S.
BO	10C-FC12	Occupied Command
AI	10C-FC12	Zone Temp
AI	10C-FC12	Zone Setpoint
AOS	10C-FC12	Heating Valve Command
AOS	10C-FC12	Cooling Valve Command
BO	10C-FC12	Fan Command
BI	10C-FC12	Fan Status
BI	10C-FC12	Pan Alarm Status
CS	10C-FC12	Temp Occ.Status C.S.
BO	10C-FC13	Occupied Command
AI	10C-FC13	Zone Temp
AI	10C-FC13	Zone Setpoint
AOS	10C-FC13	Heating Valve Command
AOS	10C-FC13	Cooling Valve Command
BO	10C-FC13	Fan Command
BI	10C-FC13	Fan Status
BI	10C-FC13	Pan Alarm Status
CS	10C-FC13	Temp Occ.Status C.S.
BO	10C-FC14	Occupied Command
AI	10C-FC14	Zone Temp
AI	10C-FC14	Zone Setpoint
AOS	10C-FC14	Heating Valve Command
AOS	10C-FC14	Cooling Valve Command
BO	10C-FC14	Fan Command
BI	10C-FC14	Fan Status
BI	10C-FC14	Pan Alarm Status
CS	10C-FC14	Temp Occ.Status C.S.
BO	10C-FC15	Occupied Command
AI	10C-FC15	Zone Temp
AI	10C-FC15	Zone Setpoint
AOS	10C-FC15	Heating Valve Command
AOS	10C-FC15	Cooling Valve Command
BO	10C-FC15	Fan Command
BI	10C-FC15	Fan Status
BI	10C-FC15	Pan Alarm Status
CS	10C-FC15	Temp Occ.Status C.S.
BO	10C-FC16	Occupied Command
AI	10C-FC16	Zone Temp
AI	10C-FC16	Zone Setpoint
AOS	10C-FC16	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	10C-FC16	Cooling Valve Command
BO	10C-FC16	Fan Command
BI	10C-FC16	Fan Status
BI	10C-FC16	Pan Alarm Status
CS	10C-FC16	Temp Occ.Status C.S.
BO	10C-FC17	Occupied Command
AI	10C-FC17	Zone Temp
AI	10C-FC17	Zone Setpoint
AOS	10C-FC17	Heating Valve Command
AOS	10C-FC17	Cooling Valve Command
BO	10C-FC17	Fan Command
BI	10C-FC17	Fan Status
BI	10C-FC17	Pan Alarm Status
CS	10C-FC17	Temp Occ.Status C.S.
BO	11A-FC01	Occupied Command
AI	11A-FC01	Zone Temp
AI	11A-FC01	Zone Setpoint
AOS	11A-FC01	Heating Valve Command
AOS	11A-FC01	Cooling Valve Command
BO	11A-FC01	Fan Command
BI	11A-FC01	Fan Status
BI	11A-FC01	Pan Alarm Status
CS	11A-FC01	Temp Occ.Status C.S.
BO	11A-FC02	Occupied Command
AI	11A-FC02	Zone Temp
AI	11A-FC02	Zone Setpoint
AOS	11A-FC02	Heating Valve Command
AOS	11A-FC02	Cooling Valve Command
BO	11A-FC02	Fan Command
BI	11A-FC02	Fan Status
BI	11A-FC02	Pan Alarm Status
CS	11A-FC02	Temp Occ.Status C.S.
BO	11A-FC03	Occupied Command
AI	11A-FC03	Zone Temp
AI	11A-FC03	Zone Setpoint
AOS	11A-FC03	Heating Valve Command
AOS	11A-FC03	Cooling Valve Command
BO	11A-FC03	Fan Command
BI	11A-FC03	Fan Status
BI	11A-FC03	Pan Alarm Status
CS	11A-FC03	Temp Occ.Status C.S.
BO	11A-FC05	Occupied Command
AI	11A-FC05	Zone Temp
AI	11A-FC05	Zone Setpoint
AOS	11A-FC05	Heating Valve Command
AOS	11A-FC05	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	11A-FC05	Fan Command
BI	11A-FC05	Fan Status
BI	11A-FC05	Pan Alarm Status
CS	11A-FC05	Temp Occ.Status C.S.
BO	11A-FC06	Occupied Command
AI	11A-FC06	Zone Temp
AI	11A-FC06	Zone Setpoint
AOS	11A-FC06	Heating Valve Command
AOS	11A-FC06	Cooling Valve Command
BO	11A-FC06	Fan Command
BI	11A-FC06	Fan Status
BI	11A-FC06	Pan Alarm Status
CS	11A-FC06	Temp Occ.Status C.S.
BO	11A-FC07	Occupied Command
AI	11A-FC07	Zone Temp
AI	11A-FC07	Zone Stpt. N/C
AOS	11A-FC07	Heating Valve Command
AOS	11A-FC07	Cooling Valve Command
BO	11A-FC07	Fan Command
BI	11A-FC07	Fan Status
BI	11A-FC07	Pan Alarm Status
CS	11A-FC07	Temp Occ.Status C.S.
BO	11A-FC08	Occupied Command
AI	11A-FC08	Zone Temp
AI	11A-FC08	Zone Setpoint
AOS	11A-FC08	Heating Valve Command
AOS	11A-FC08	Cooling Valve Command
BO	11A-FC08	Fan Command
BI	11A-FC08	Fan Status
BI	11A-FC08	Pan Alarm Status
CS	11A-FC08	Temp Occ.Status C.S.
BO	11A-FC09	Occupied Command
AI	11A-FC09	Zone Temp
AI	11A-FC09	Zone Setpoint
AOS	11A-FC09	Heating Valve Command
AOS	11A-FC09	Cooling Valve Command
BO	11A-FC09	Fan Command
BI	11A-FC09	Fan Status
BI	11A-FC09	Pan Alarm Status
CS	11A-FC09	Temp Occ.Status C.S.
BO	11A-FC10	Occupied Command
AI	11A-FC10	Zone Temp
AI	11A-FC10	Zone Setpoint
AOS	11A-FC10	Heating Valve Command
AOS	11A-FC10	Cooling Valve Command
BO	11A-FC10	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	11A-FC10	Fan Status
BI	11A-FC10	Pan Alarm Status
CS	11A-FC10	Temp Occ.Status C.S.
BO	11A-FC11	Occupied Command
AI	11A-FC11	Zone Temp
AI	11A-FC11	Zone Setpoint
AOS	11A-FC11	Heating Valve Command
AOS	11A-FC11	Cooling Valve Command
BO	11A-FC11	Fan Command
BI	11A-FC11	Fan Status
BI	11A-FC11	Pan Alarm Status
CS	11A-FC11	Temp Occ.Status C.S.
BO	11A-FC12	Occupied Command
AI	11A-FC12	Zone Temp
AI	11A-FC12	Zone Setpoint
AOS	11A-FC12	Heating Valve Command
AOS	11A-FC12	Cooling Valve Command
BO	11A-FC12	Fan Command
BI	11A-FC12	Fan Status
BI	11A-FC12	Pan Alarm Status
CS	11A-FC12	Temp Occ.Status C.S.
BO	11A-FC13	Occupied Command
AI	11A-FC13	Zone Temp
AI	11A-FC13	Zone Setpoint
AOS	11A-FC13	Heating Valve Command
AOS	11A-FC13	Cooling Valve Command
BO	11A-FC13	Fan Command
BI	11A-FC13	Fan Status
BI	11A-FC13	Pan Alarm Status
CS	11A-FC13	Temp Occ.Status C.S.
BO	11B-FC01	Occupied Command
AI	11B-FC01	Zone Temp
AI	11B-FC01	Zone Setpoint
AOS	11B-FC01	Heating Valve Command
AOS	11B-FC01	Cooling Valve Command
BO	11B-FC01	Fan Command
BI	11B-FC01	Fan Status
BI	11B-FC01	Pan Alarm Status
CS	11B-FC01	Temp Occ.Status C.S.
BO	11B-FC02	Occupied Command
AI	11B-FC02	Zone Temp
AI	11B-FC02	Zone Setpoint
AOS	11B-FC02	Heating Valve Command
AOS	11B-FC02	Cooling Valve Command
BO	11B-FC02	Fan Command
BI	11B-FC02	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	11B-FC02	Pan Alarm Status
CS	11B-FC02	Temp Occ.Status C.S.
BO	11B-FC03	Occupied Command
AI	11B-FC03	Zone Temp
AI	11B-FC03	Zone Setpoint
AOS	11B-FC03	Heating Valve Command
AOS	11B-FC03	Cooling Valve Command
BO	11B-FC03	Fan Command
BI	11B-FC03	Fan Status
BI	11B-FC03	Pan Alarm Status
CS	11B-FC03	Temp Occ.Status C.S.
BO	11B-FC04	Occupied Command
AI	11B-FC04	Zone Temp
AI	11B-FC04	Zone Setpoint
AOS	11B-FC04	Heating Valve Command
AOS	11B-FC04	Cooling Valve Command
BO	11B-FC04	Fan Command
BI	11B-FC04	Fan Status
BI	11B-FC04	Pan Alarm Status
CS	11B-FC04	Temp Occ.Status C.S.
BO	11B-FC05	Occupied Command
AI	11B-FC05	Zone Temp
AI	11B-FC05	Zone Setpoint
AOS	11B-FC05	Heating Valve Command
AOS	11B-FC05	Cooling Valve Command
BO	11B-FC05	Fan Command
BI	11B-FC05	Fan Status
BI	11B-FC05	Pan Alarm Status
CS	11B-FC05	Temp Occ.Status C.S.
BO	11B-FC06	Occupied Command
AI	11B-FC06	Zone Temp
AI	11B-FC06	Zone Setpoint
AOS	11B-FC06	Heating Valve Command
AOS	11B-FC06	Cooling Valve Command
BO	11B-FC06	Fan Command
BI	11B-FC06	Fan Status
BI	11B-FC06	Pan Alarm Status
CS	11B-FC06	Temp Occ.Status C.S.
BO	11B-FC07	Occupied Command
AI	11B-FC07	Zone Temp
AI	11B-FC07	Zone Setpoint
AOS	11B-FC07	Heating Valve Command
AOS	11B-FC07	Cooling Valve Command
BO	11B-FC07	Fan Command
BI	11B-FC07	Fan Status
BI	11B-FC07	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	11B-FC07	Temp Occ.Status C.S.
BO	11B-FC08	Occupied Command
AI	11B-FC08	Zone Temp
AI	11B-FC08	Zone Setpoint
AOS	11B-FC08	Heating Valve Command
AOS	11B-FC08	Cooling Valve Command
BO	11B-FC08	Fan Command
BI	11B-FC08	Fan Status
BI	11B-FC08	Pan Alarm Status
CS	11B-FC08	Temp Occ.Status C.S.
BO	11B-FC09	Occupied Command
AI	11B-FC09	Zone Temp
AI	11B-FC09	Zone Setpoint
AOS	11B-FC09	Heating Valve Command
AOS	11B-FC09	Cooling Valve Command
BO	11B-FC09	Fan Command
BI	11B-FC09	Fan Status
BI	11B-FC09	Pan Alarm Status
CS	11B-FC09	Temp Occ.Status C.S.
BO	11B-FC10	Occupied Command
AI	11B-FC10	Zone Temp
AI	11B-FC10	Zone Setpoint
AOS	11B-FC10	Heating Valve Command
AOS	11B-FC10	Cooling Valve Command
BO	11B-FC10	Fan Command
BI	11B-FC10	Fan Status
BI	11B-FC10	Pan Alarm Status
CS	11B-FC10	Temp Occ.Status C.S.
BO	11B-FC11	Occupied Command
AI	11B-FC11	Zone Temp
AI	11B-FC11	Zone Setpoint
AOS	11B-FC11	Heating Valve Command
AOS	11B-FC11	Cooling Valve Command
BO	11B-FC11	Fan Command
BI	11B-FC11	Fan Status
BI	11B-FC11	Pan Alarm Status
CS	11B-FC11	Temp Occ.Status C.S.
BO	11B-FC12	Occupied Command
AI	11B-FC12	Zone Temp
AI	11B-FC12	Zone Setpoint
AOS	11B-FC12	Heating Valve Command
AOS	11B-FC12	Cooling Valve Command
BO	11B-FC12	Fan Command
BI	11B-FC12	Fan Status
BI	11B-FC12	Pan Alarm Status
CS	11B-FC12	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	11C-FC01	Occupied Command
AI	11C-FC01	Zone Temp
AI	11C-FC01	Zone Setpoint
AOS	11C-FC01	Heating Valve Command
AOS	11C-FC01	Cooling Valve Command
BO	11C-FC01	Fan Command
BI	11C-FC01	Fan Status
BI	11C-FC01	Pan Alarm Status
CS	11C-FC01	Temp Occ.Status C.S.
BO	11C-FC02	Occupied Command
AI	11C-FC02	Zone Temp
AI	11C-FC02	Zone Setpoint
AOS	11C-FC02	Heating Valve Command
AOS	11C-FC02	Cooling Valve Command
BO	11C-FC02	Fan Command
BI	11C-FC02	Fan Status
BI	11C-FC02	Pan Alarm Status
CS	11C-FC02	Temp Occ.Status C.S.
BO	11C-FC03	Occupied Command
AI	11C-FC03	Zone Temp
AI	11C-FC03	Zone Setpoint
AOS	11C-FC03	Heating Valve Command
AOS	11C-FC03	Cooling Valve Command
BO	11C-FC03	Fan Command
BI	11C-FC03	Fan Status
BI	11C-FC03	Pan Alarm Status
CS	11C-FC03	Temp Occ.Status C.S.
BO	11C-FC04	Occupied Command
AI	11C-FC04	Zone Temp
AI	11C-FC04	Zone Setpoint
AOS	11C-FC04	Heating Valve Command
AOS	11C-FC04	Cooling Valve Command
BO	11C-FC04	Fan Command
BI	11C-FC04	Fan Status
BI	11C-FC04	Pan Alarm Status
CS	11C-FC04	Temp Occ.Status C.S.
BO	11C-FC05	Occupied Command
AI	11C-FC05	Zone Temp
AI	11C-FC05	Zone Setpoint
AOS	11C-FC05	Heating Valve Command
AOS	11C-FC05	Cooling Valve Command
BO	11C-FC05	Fan Command
BI	11C-FC05	Fan Status
BI	11C-FC05	Pan Alarm Status
CS	11C-FC05	Temp Occ.Status C.S.
BO	11C-FC06	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	11C-FC06	Zone Temp
AI	11C-FC06	Zone Setpoint
AOS	11C-FC06	Heating Valve Command
AOS	11C-FC06	Cooling Valve Command
BO	11C-FC06	Fan Command
BI	11C-FC06	Fan Status
BI	11C-FC06	Pan Alarm Status
CS	11C-FC06	Temp Occ.Status C.S.
BO	11C-FC07	Occupied Command
AI	11C-FC07	Zone Temp
AI	11C-FC07	Zone Setpoint
AOS	11C-FC07	Heating Valve Command
AOS	11C-FC07	Cooling Valve Command
BO	11C-FC07	Fan Command
BI	11C-FC07	Fan Status
BI	11C-FC07	Pan Alarm Status
CS	11C-FC07	Temp Occ.Status C.S.
BO	11C-FC08	Occupied Command
AI	11C-FC08	Zone Temp
AI	11C-FC08	Zone Setpoint
AOS	11C-FC08	Heating Valve Command
AOS	11C-FC08	Cooling Valve Command
BO	11C-FC08	Fan Command
BI	11C-FC08	Fan Status
BI	11C-FC08	Pan Alarm Status
CS	11C-FC08	Temp Occ.Status C.S.
BO	11C-FC09	Occupied Command
AI	11C-FC09	Zone Temp
AI	11C-FC09	Zone Setpoint
AOS	11C-FC09	Heating Valve Command
AOS	11C-FC09	Cooling Valve Command
BO	11C-FC09	Fan Command
BI	11C-FC09	Fan Status
BI	11C-FC09	Pan Alarm Status
CS	11C-FC09	Temp Occ.Status C.S.
BO	11C-FC10	Occupied Command
AI	11C-FC10	Zone Temp
AI	11C-FC10	Zone Setpoint
AOS	11C-FC10	Heating Valve Command
AOS	11C-FC10	Cooling Valve Command
BO	11C-FC10	Fan Command
BI	11C-FC10	Fan Status
BI	11C-FC10	Pan Alarm Status
CS	11C-FC10	Temp Occ.Status C.S.
BO	11C-FC11	Occupied Command
AI	11C-FC11	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	11C-FC11	Zone Setpoint
AOS	11C-FC11	Heating Valve Command
AOS	11C-FC11	Cooling Valve Command
BO	11C-FC11	Fan Command
BI	11C-FC11	Fan Status
BI	11C-FC11	Pan Alarm Status
CS	11C-FC11	Temp Occ.Status C.S.
BO	11C-FC12	Occupied Command
AI	11C-FC12	Zone Temp
AI	11C-FC12	Zone Setpoint
AOS	11C-FC12	Heating Valve Command
AOS	11C-FC12	Cooling Valve Command
BO	11C-FC12	Fan Command
BI	11C-FC12	Fan Status
BI	11C-FC12	Pan Alarm Status
CS	11C-FC12	Temp Occ.Status C.S.
BO	11C-FC13	Occupied Command
AI	11C-FC13	Zone Temp
AI	11C-FC13	Zone Setpoint
AOS	11C-FC13	Heating Valve Command
AOS	11C-FC13	Cooling Valve Command
BO	11C-FC13	Fan Command
BI	11C-FC13	Fan Status
BI	11C-FC13	Pan Alarm Status
CS	11C-FC13	Temp Occ.Status C.S.
BO	11C-FC14	Occupied Command
AI	11C-FC14	Zone Temp
AI	11C-FC14	Zone Setpoint
AOS	11C-FC14	Heating Valve Command
AOS	11C-FC14	Cooling Valve Command
BO	11C-FC14	Fan Command
BI	11C-FC14	Fan Status
BI	11C-FC14	Pan Alarm Status
CS	11C-FC14	Temp Occ.Status C.S.
BO	11C-FC15	Occupied Command
AI	11C-FC15	Zone Temp
AI	11C-FC15	Zone Setpoint
AOS	11C-FC15	Heating Valve Command
AOS	11C-FC15	Cooling Valve Command
BO	11C-FC15	Fan Command
BI	11C-FC15	Fan Status
BI	11C-FC15	Pan Alarm Status
CS	11C-FC15	Temp Occ.Status C.S.
BO	11C-FC16	Occupied Command
AI	11C-FC16	Zone Temp
AI	11C-FC16	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	11C-FC16	Heating Valve Command
AOS	11C-FC16	Cooling Valve Command
BO	11C-FC16	Fan Command
BI	11C-FC16	Fan Status
BI	11C-FC16	Pan Alarm Status
CS	11C-FC16	Temp Occ.Status C.S.
AI	CALLAB	Temperature
AI	CALLAB	Humidity
AI	CALLAB	Stages
AI	CALLAB	Capacity
AI	CALLAB	High Temp Setpoint
AI	CALLAB	Low Temp Setpoint
AOS	CALLAB	Temperature Setpoint
AOS	CALLAB	Humidity Setpoint
AD	DAP_II	Return Air temp
AD	DAP_II	Return Air Humidity
BD	DAP_II	Compresser Cycle Alarm
BD	DAP_II	High Humidity Alarm
BD	DAP_II	High Temperature Alarm
BD	DAP_II	No Air Flow
BD	DAP_II	Filter Status
CS	DAP_II	CS OBJECT DAP II
	Building 3	
Point	Equipment	Type
	NC-17	Network controller
NC17-HRW	12C-FC01	1, 1, 3, VAV
NC17-HRW	12C-FC02	2, 1, 3, VAV
NC17-HRW	12C-FC03	3, 1, 3, VAV
NC17-HRW	12C-FC04	4, 1, 3, VAV
NC17-HRW	12C-FC05	5, 1, 3, VAV
NC17-HRW	12C-FC06	6, 1, 3, VAV
NC17-HRW	12C-FC07	7, 1, 3, VAV
NC17-HRW	12C-FC08	8, 1, 3, VAV
NC17-HRW	12C-FC09	9, 1, 3, VAV
NC17-HRW	12C-FC10	10, 1, 3, VAV
NC17-HRW	12C-FC11	11, 1, 3, VAV
NC17-HRW	12C-FC12	12, 1, 3, VAV
NC17-HRW	12C-FC13	13, 1, 3, VAV
NC17-HRW	12C-FC14	14, 1, 3, VAV
NC17-HRW	12C-FC15	15, 1, 3, VAV
NC17-HRW	12C-FC16	16, 1, 3, VAV
NC17-HRW	12C-FC17	17, 1, 3, VAV
NC17-HRW	12C-FC18	18, 1, 3, VAV
NC17-HRW	12C-FC20	20, 1, 3, VAV
NC17-HRW	12C-FC21	21, 1, 3, VAV
NC17-HRW	12C-FC22	22, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC17-HRW	13C-FC01	23, 1, 3, VAV
NC17-HRW	13C-FC02	24, 1, 3, VAV
NC17-HRW	13C-FC03	25, 1, 3, VAV
NC17-HRW	13C-FC04	26, 1, 3, VAV
NC17-HRW	13C-FC05	27, 1, 3, VAV
NC17-HRW	13C-FC06	28, 1, 3, VAV
NC17-HRW	13C-FC07	29, 1, 3, VAV
NC17-HRW	13C-FC08	30, 1, 3, VAV
NC17-HRW	13C-FC09	31, 1, 3, VAV
NC17-HRW	13C-FC10	32, 1, 3, VAV
NC17-HRW	13C-FC11	33, 1, 3, VAV
NC17-HRW	13C-FC12	34, 1, 3, VAV
NC17-HRW	13C-FC13	35, 1, 3, VAV
NC17-HRW	13C-FC14	36, 1, 3, VAV
NC17-HRW	13C-FC15	37, 1, 3, VAV
NC17-HRW	13C-FC16	38, 1, 3, VAV
NC17-HRW	13C-FC17	39, 1, 3, VAV
NC17-HRW	13C-FC18	40, 1, 3, VAV
NC17-HRW	13C-FC19	41, 1, 3, VAV
NC17-HRW	13C-FC20	42, 1, 3, VAV
NC17-HRW	13C-FC21	43, 1, 3, VAV
NC17-HRW	13C-FC22	44, 1, 3, VAV
BO	12C-FC05	Occupied Command
AI	12C-FC05	Zone Temp (No Heat)
AI	12C-FC05	Zone Setpoint
AOS	12C-FC05	Cooling Valve Command
BO	12C-FC05	Fan Command
BI	12C-FC05	Fan Status
BI	12C-FC05	Pan Alarm Status
CS	12C-FC05	Temp Occ.Status C.S.
BO	MISC-13	Exhaust FAN 13 Command
BI	MISC-13	Exhaust Fan 13 Status
BO	13C-FC22	Occupied Command
AI	13C-FC22	Zone Temp
AI	13C-FC22	Zone Setpoint
AOS	13C-FC22	Heating Valve Command
AOS	13C-FC22	Cooling Valve Command
BO	13C-FC22	Fan Command
BI	13C-FC22	Fan Status
BI	13C-FC22	Pan Alarm Status
CS	13C-FC22	Temp Occ.Status C.S.
BO	13C-FC21	Occupied Command
AI	13C-FC21	Zone Temp
AI	13C-FC21	Zone Setpoint
AOS	13C-FC21	Heating Valve Command
AOS	13C-FC21	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	13C-FC21	Fan Command
BI	13C-FC21	Fan Status
BI	13C-FC21	Pan Alarm Status
CS	13C-FC21	Temp Occ.Status C.S.
BO	13C-FC20	Occupied Command
AI	13C-FC20	Zone Temp
AI	13C-FC20	Zone Setpoint
AOS	13C-FC20	Heating Valve Command
AOS	13C-FC20	Cooling Valve Command
BO	13C-FC20	Fan Command
BI	13C-FC20	Fan Status
BI	13C-FC20	Pan Alarm Status
CS	13C-FC20	Temp Occ.Status C.S.
BO	13C-FC19	Occupied Command
AI	13C-FC19	Zone Temp
AI	13C-FC19	Zone Setpoint
AOS	13C-FC19	Heating Valve Command
AOS	13C-FC19	Cooling Valve Command
BO	13C-FC19	Fan Command
BI	13C-FC19	Fan Status
BI	13C-FC19	Pan Alarm Status
CS	13C-FC19	Temp Occ.Status C.S.
BO	13C-FC18	Occupied Command
AI	13C-FC18	Zone Temp
AI	13C-FC18	Zone Setpoint
AOS	13C-FC18	Cooling Valve Command
BO	13C-FC18	Fan Command
BI	13C-FC18	Fan Status
BI	13C-FC18	Pan Alarm Status
CS	13C-FC18	Temp Occ.Status C.S.
BO	13C-FC17	Occupied Command
AI	13C-FC17	Zone Temp
AI	13C-FC17	Zone Setpoint
AOS	13C-FC17	Heating Valve Command
AOS	13C-FC17	Cooling Valve Command
BO	13C-FC17	Fan Command
BI	13C-FC17	Fan Status
BI	13C-FC17	Pan Alarm Status
CS	13C-FC17	Temp Occ.Status C.S.
BO	13C-FC16	Occupied Command
AI	13C-FC16	Zone Temp
AI	13C-FC16	Zone Setpoint
AOS	13C-FC16	Heating Valve Command
AOS	13C-FC16	Cooling Valve Command
BO	13C-FC16	Fan Command
BI	13C-FC16	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	13C-FC16	Pan Alarm Status
CS	13C-FC16	Temp Occ.Status C.S.
BO	13C-FC15	Occupied Command
AI	13C-FC15	Zone Temp
AI	13C-FC15	Zone Setpoint
AOS	13C-FC15	Cooling Valve Command
BO	13C-FC15	Fan Command
BI	13C-FC15	Fan Status
BI	13C-FC15	Pan Alarm Status
CS	13C-FC15	Temp Occ.Status C.S.
BO	13C-FC14	Occupied Command
AI	13C-FC14	Zone Temp
AI	13C-FC14	Zone Setpoint
AOS	13C-FC14	Heating Valve Command
AOS	13C-FC14	Cooling Valve Command
BO	13C-FC14	Fan Command
BI	13C-FC14	Fan Status
BI	13C-FC14	Pan Alarm Status
CS	13C-FC14	Temp Occ.Status C.S.
BO	13C-FC13	Occupied Command
AI	13C-FC13	Zone Temp
AI	13C-FC13	Zone Setpoint
AOS	13C-FC13	Heating Valve Command
AOS	13C-FC13	Cooling Valve Command
BO	13C-FC13	Fan Command
BI	13C-FC13	Fan Status
BI	13C-FC13	Pan Alarm Status
CS	13C-FC13	Temp Occ.Status C.S.
BO	13C-FC12	Occupied Command
AI	13C-FC12	Zone Temp
AI	13C-FC12	Zone Setpoint
AOS	13C-FC12	Heating Valve Command
AOS	13C-FC12	Cooling Valve Command
BO	13C-FC12	Fan Command
BI	13C-FC12	Fan Status
BI	13C-FC12	Pan Alarm Status
CS	13C-FC12	Temp Occ.Status C.S.
BO	13C-FC11	Occupied Command
AI	13C-FC11	Zone Temp
AI	13C-FC11	Zone Setpoint
AOS	13C-FC11	Heating Valve Command
AOS	13C-FC11	Cooling Valve Command
BO	13C-FC11	Fan Command
BI	13C-FC11	Fan Status
BI	13C-FC11	Pan Alarm Status
CS	13C-FC11	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	13C-FC10	Occupied Command
AI	13C-FC10	Zone Temp
AI	13C-FC10	Zone Setpoint
AOS	13C-FC10	Heating Valve Command
AOS	13C-FC10	Cooling Valve Command
BO	13C-FC10	Fan Command
BI	13C-FC10	Fan Status
BI	13C-FC10	Pan Alarm Status
CS	13C-FC10	Temp Occ.Status C.S.
BO	13C-FC09	Occupied Command
AI	13C-FC09	Zone Temp
AI	13C-FC09	Zone Setpoint
AOS	13C-FC09	Heating Valve Command
AOS	13C-FC09	Cooling Valve Command
BO	13C-FC09	Fan Command
BI	13C-FC09	Fan Status
BI	13C-FC09	Pan Alarm Status
CS	13C-FC09	Temp Occ.Status C.S.
BO	13C-FC08	Occupied Command
AI	13C-FC08	Zone Temp
AI	13C-FC08	Zone Setpoint
AOS	13C-FC08	Cooling Valve Command
BO	13C-FC08	Fan Command
BI	13C-FC08	Fan Status
BI	13C-FC08	Pan Alarm Status
CS	13C-FC08	Temp Occ.Status C.S.
BO	13C-FC07	Occupied Command
AI	13C-FC07	Zone Temp
AI	13C-FC07	Zone Setpoint
AOS	13C-FC07	Cooling Valve Command
BO	13C-FC07	Fan Command
BI	13C-FC07	Fan Status
BI	13C-FC07	Pan Alarm Status
CS	13C-FC07	Temp Occ.Status C.S.
BO	13C-FC06	Occupied Command
AI	13C-FC06	Zone Temp
AI	13C-FC06	Zone Setpoint
AOS	13C-FC06	Heating Valve Command
AOS	13C-FC06	Cooling Valve Command
BO	13C-FC06	Fan Command
BI	13C-FC06	Fan Status
BI	13C-FC06	Pan Alarm Status
CS	13C-FC06	Temp Occ.Status C.S.
BO	13C-FC05	Occupied Command
AI	13C-FC05	Zone Temp
AI	13C-FC05	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	13C-FC05	Cooling Valve Command
BO	13C-FC05	Fan Command
BI	13C-FC05	Fan Status
BI	13C-FC05	Pan Alarm Status
CS	13C-FC05	Temp Occ.Status C.S.
BO	13C-FC04	Occupied Command
AI	13C-FC04	Zone Temp
AI	13C-FC04	Zone Setpoint
AOS	13C-FC04	Heating Valve Command
AOS	13C-FC04	Cooling Valve Command
BO	13C-FC04	Fan Command
BI	13C-FC04	Fan Status
BI	13C-FC04	Pan Alarm Status
CS	13C-FC04	Temp Occ.Status C.S.
BO	13C-FC03	Occupied Command
AI	13C-FC03	Zone Temp
AI	13C-FC03	Zone Setpoint
AOS	13C-FC03	Heating Valve Command
AOS	13C-FC03	Cooling Valve Command
BO	13C-FC03	Fan Command
BI	13C-FC03	Fan Status
BI	13C-FC03	Pan Alarm Status
CS	13C-FC03	Temp Occ.Status C.S.
BO	13C-FC02	Occupied Command
AI	13C-FC02	Zone Temp
AI	13C-FC02	Zone Setpoint
AOS	13C-FC02	Heating Valve Command
AOS	13C-FC02	Cooling Valve Command
BO	13C-FC02	Fan Command
BI	13C-FC02	Fan Status
BI	13C-FC02	Pan Alarm Status
CS	13C-FC02	Temp Occ.Status C.S.
BO	13C-FC01	Occupied Command
AI	13C-FC01	Zone Temp
AI	13C-FC01	Zone Setpoint
AOS	13C-FC01	Heating Valve Command
AOS	13C-FC01	Cooling Valve Command
BO	13C-FC01	Fan Command
BI	13C-FC01	Fan Status
BI	13C-FC01	Pan Alarm Status
CS	13C-FC01	Temp Occ.Status C.S.
BO	MISC-12	Exhaust FAN 12 Command
BI	MISC-12	Exhaust Fan 12 Status
BO	12C-FC22	Occupied Command
AI	12C-FC22	Zone Temp
AI	12C-FC22	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	12C-FC22	Heating Valve Command
AOS	12C-FC22	Cooling Valve Command
BO	12C-FC22	Fan Command
BI	12C-FC22	Fan Status
BI	12C-FC22	Pan Alarm Status
CS	12C-FC22	Temp Occ.Status C.S.
BO	12C-FC21	Occupied Command
AI	12C-FC21	Zone Temp
AI	12C-FC21	Zone Setpoint
AOS	12C-FC21	Heating Valve Command
AOS	12C-FC21	Cooling Valve Command
BO	12C-FC21	Fan Command
BI	12C-FC21	Fan Status
BI	12C-FC21	Pan Alarm Status
CS	12C-FC21	Temp Occ.Status C.S.
BO	12C-FC20	Occupied Command
AI	12C-FC20	Zone Temp
AI	12C-FC20	Zone Setpoint
AOS	12C-FC20	Heating Valve Command
AOS	12C-FC20	Cooling Valve Command
BO	12C-FC20	Fan Command
BI	12C-FC20	Fan Status
BI	12C-FC20	Pan Alarm Status
CS	12C-FC20	Temp Occ.Status C.S.
BO	12C-FC18	Occupied Command
AI	12C-FC18	Zone Temp
AI	12C-FC18	Zone Setpoint
AOS	12C-FC18	Heating Valve Command
AOS	12C-FC18	Cooling Valve Command
BO	12C-FC18	Fan Command
BI	12C-FC18	Fan Status
BI	12C-FC18	Pan Alarm Status
CS	12C-FC18	Temp Occ.Status C.S.
BO	12C-FC17	Occupied Command
AI	12C-FC17	Zone Temp
AI	12C-FC17	Zone Setpoint
AOS	12C-FC17	Cooling Valve Command
BO	12C-FC17	Fan Command
BI	12C-FC17	Fan Status
BI	12C-FC17	Pan Alarm Status
CS	12C-FC17	Temp Occ.Status C.S.
BO	12C-FC16	Occupied Command
AI	12C-FC16	Zone Temp
AI	12C-FC16	Zone Setpoint
AOS	12C-FC16	Heating Valve Command
AOS	12C-FC16	Cooling Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	12C-FC16	Fan Command
BI	12C-FC16	Fan Status
BI	12C-FC16	Pan Alarm Status
CS	12C-FC16	Temp Occ.Status C.S.
BO	12C-FC15	Occupied Command
AI	12C-FC15	Zone Temp
AI	12C-FC15	Zone Setpoint
AOS	12C-FC15	Cooling Valve Command
BO	12C-FC15	Fan Command
BI	12C-FC15	Fan Status
BI	12C-FC15	Pan Alarm Status
CS	12C-FC15	Temp Occ.Status C.S.
BO	12C-FC14	Occupied Command
AI	12C-FC14	Zone Temp
AI	12C-FC14	Zone Setpoint
AOS	12C-FC14	Heating Valve Command
AOS	12C-FC14	Cooling Valve Command
BO	12C-FC14	Fan Command
BI	12C-FC14	Fan Status
BI	12C-FC14	Pan Alarm Status
CS	12C-FC14	Temp Occ.Status C.S.
BO	12C-FC13	Occupied Command
AI	12C-FC13	Zone Temp
AI	12C-FC13	Zone Setpoint
AOS	12C-FC13	Heating Valve Command
AOS	12C-FC13	Cooling Valve Command
BO	12C-FC13	Fan Command
BI	12C-FC13	Fan Status
BI	12C-FC13	Pan Alarm Status
CS	12C-FC13	Temp Occ.Status C.S.
BO	12C-FC12	Occupied Command
AI	12C-FC12	Zone Temp
AI	12C-FC12	Zone Setpoint
AOS	12C-FC12	Heating Valve Command
AOS	12C-FC12	Cooling Valve Command
BO	12C-FC12	Fan Command
BI	12C-FC12	Fan Status
BI	12C-FC12	Pan Alarm Status
CS	12C-FC12	Temp Occ.Status C.S.
BO	12C-FC11	Occupied Command
AI	12C-FC11	Zone Temp
AI	12C-FC11	Zone Setpoint
AOS	12C-FC11	Heating Valve Command
AOS	12C-FC11	Cooling Valve Command
BO	12C-FC11	Fan Command
BI	12C-FC11	Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	12C-FC11	Pan Alarm Status
CS	12C-FC11	Temp Occ.Status C.S.
BO	12C-FC10	Occupied Command
AI	12C-FC10	Zone Temp
AI	12C-FC10	Zone Setpoint
AOS	12C-FC10	Heating Valve Command
AOS	12C-FC10	Cooling Valve Command
BO	12C-FC10	Fan Command
BI	12C-FC10	Fan Status
BI	12C-FC10	Pan Alarm Status
CS	12C-FC10	Temp Occ.Status C.S.
BO	12C-FC09	Occupied Command
AI	12C-FC09	Zone Temp
AI	12C-FC09	Zone Setpoint
AOS	12C-FC09	Heating Valve Command
AOS	12C-FC09	Cooling Valve Command
BO	12C-FC09	Fan Command
BI	12C-FC09	Fan Status
BI	12C-FC09	Pan Alarm Status
CS	12C-FC09	Temp Occ.Status C.S.
BO	12C-FC08	Occupied Command
AI	12C-FC08	Zone Temp
AI	12C-FC08	Zone Setpoint
AOS	12C-FC08	Heating Valve Command
AOS	12C-FC08	Cooling Valve Command
BO	12C-FC08	Fan Command
BI	12C-FC08	Fan Status
BI	12C-FC08	Pan Alarm Status
CS	12C-FC08	Temp Occ.Status C.S.
BO	12C-FC07	Occupied Command
AI	12C-FC07	Zone Temp
AI	12C-FC07	Zone Setpoint
AOS	12C-FC07	Heating Valve Command
AOS	12C-FC07	Cooling Valve Command
BO	12C-FC07	Fan Command
BI	12C-FC07	Fan Status
BI	12C-FC07	Pan Alarm Status
CS	12C-FC07	Temp Occ.Status C.S.
BO	12C-FC06	Occupied Command
AI	12C-FC06	Zone Temp
AI	12C-FC06	Zone Setpoint
AOS	12C-FC06	Heating Valve Command
AOS	12C-FC06	Cooling Valve Command
BO	12C-FC06	Fan Command
BI	12C-FC06	Fan Status
BI	12C-FC06	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	12C-FC06	Temp Occ.Status C.S.
BO	12C-FC04	Occupied Command
AI	12C-FC04	Zone Temp
AI	12C-FC04	Zone Setpoint
AOS	12C-FC04	Heating Valve Command
AOS	12C-FC04	Cooling Valve Command
BO	12C-FC04	Fan Command
BI	12C-FC04	Fan Status
BI	12C-FC04	Pan Alarm Status
CS	12C-FC04	Temp Occ.Status C.S.
BO	12C-FC03	Occupied Command
AI	12C-FC03	Zone Temp
AI	12C-FC03	Zone Setpoint
AOS	12C-FC03	Heating Valve Command
AOS	12C-FC03	Cooling Valve Command
BO	12C-FC03	Fan Command
BI	12C-FC03	Fan Status
BI	12C-FC03	Pan Alarm Status
CS	12C-FC03	Temp Occ.Status C.S.
BO	12C-FC02	Occupied Command
AI	12C-FC02	Zone Temp
AI	12C-FC02	Zone Setpoint
AOS	12C-FC02	Heating Valve Command
AOS	12C-FC02	Cooling Valve Command
BO	12C-FC02	Fan Command
BI	12C-FC02	Fan Status
BI	12C-FC02	Pan Alarm Status
CS	12C-FC02	Temp Occ.Status C.S.
BO	12C-FC01	Occupied Command
AI	12C-FC01	Zone Temp
AI	12C-FC01	Zone Setpoint
AOS	12C-FC01	Heating Valve Command
AOS	12C-FC01	Cooling Valve Command
BO	12C-FC01	Fan Command
BI	12C-FC01	Fan Status
BI	12C-FC01	Pan Alarm Status
CS	12C-FC01	Temp Occ.Status C.S.
	Building 3	
Point	Equipment	Type
	NC-18	Network controller
NC18-HRW	14C-FC01	1, 1, 3, VAV
NC18-HRW	14C-FC02	2, 1, 3, VAV
NC18-HRW	14C-FC03	3, 1, 3, VAV
NC18-HRW	14C-FC04	4, 1, 3, VAV
NC18-HRW	14C-FC05	5, 1, 3, VAV
NC18-HRW	14C-FC06	6, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC18-HRW	14C-FC07	7, 1, 3, VAV
NC18-HRW	14C-FC08	8, 1, 3, VAV
NC18-HRW	14C-FC09	9, 1, 3, VAV
NC18-HRW	14C-FC10	10, 1, 3, VAV
NC18-HRW	14C-FC11	11, 1, 3, VAV
NC18-HRW	14C-FC12	12, 1, 3, VAV
NC18-HRW	14C-FC13	13, 1, 3, VAV
NC18-HRW	14C-FC14	14, 1, 3, VAV
NC18-HRW	14C-FC15	15, 1, 3, VAV
NC18-HRW	14C-FC16	16, 1, 3, VAV
NC18-HRW	14C-FC17	17, 1, 3, VAV
NC18-HRW	14C-FC18	18, 1, 3, VAV
NC18-HRW	15C-FC01	19, 1, 3, VAV
NC18-HRW	15C-FC02	20, 1, 3, VAV
NC18-HRW	15C-FC03	21, 1, 3, VAV
NC18-HRW	15C-FC04	22, 1, 3, VAV
NC18-HRW	15C-FC05	23, 1, 3, VAV
NC18-HRW	15C-FC06	24, 1, 3, VAV
NC18-HRW	15C-FC07	25, 1, 3, VAV
NC18-HRW	15C-FC08	26, 1, 3, VAV
NC18-HRW	15C-FC09	27, 1, 3, VAV
NC18-HRW	15C-FC10	28, 1, 3, VAV
NC18-HRW	15C-FC11	29, 1, 3, VAV
NC18-HRW	15C-FC12	30, 1, 3, VAV
NC18-HRW	15C-FC13	31, 1, 3, VAV
NC18-HRW	15C-FC14	32, 1, 3, VAV
NC18-HRW	15C-FC15	33, 1, 3, VAV
NC18-HRW	15C-FC16	34, 1, 3, VAV
NC18-HRW	15C-FC17	35, 1, 3, VAV
NC18-HRW	15C-FC18	36, 1, 3, VAV
NC18-HRW	15C-FC19	37, 1, 3, VAV
NC18-HRW	15C-FC20	38, 1, 3, VAV
NC18-HRW	15C-FC21	39, 1, 3, VAV
BO	14C-FC11	Occupied Command
AI	14C-FC11	Zone Temp
AI	14C-FC11	Zone Setpoint
AOS	14C-FC11	Cooling Valve Command
BO	14C-FC11	Fan Command
BI	14C-FC11	Fan Status
BI	14C-FC11	Pan Alarm Status
CS	14C-FC11	Temp Occupied Sts CS
BO	14C-FC06	Occupied Command
AI	14C-FC06	Zone Temp
AI	14C-FC06	Zone Setpoint
AOS	14C-FC06	Cooling Valve Command
BO	14C-FC06	Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	14C-FC06	Fan Status
BI	14C-FC06	Pan Alarm Status
CS	14C-FC06	Temp Occupied Sts CS
BO	15C-FC18	Occupied Command
AI	15C-FC18	Zone Temp
AI	15C-FC18	Zone Setpoint
AOS	15C-FC18	Cooling Valve Command
BO	15C-FC18	Fan Command
BI	15C-FC18	Fan Status
BI	15C-FC18	Pan Alarm Status
CS	15C-FC18	Temp Occupied Status CS
BO	14C-FC01	Occupied Command
AI	14C-FC01	Zone Temp
AI	14C-FC01	Zone Setpoint
AOS	14C-FC01	Heating Valve Command
AOS	14C-FC01	Cooling Valve Command
BO	14C-FC01	Fan Command
BI	14C-FC01	Fan Status
BI	14C-FC01	Pan Alarm Status
CS	14C-FC01	Temp Occ.Status C.S.
BO	14C-FC02	Occupied Command
AI	14C-FC02	Zone Temp
AI	14C-FC02	Zone Setpoint
AOS	14C-FC02	Heating Valve Command
AOS	14C-FC02	Cooling Valve Command
BO	14C-FC02	Fan Command
BI	14C-FC02	Fan Status
BI	14C-FC02	Pan Alarm Status
CS	14C-FC02	Temp Occ.Status C.S.
BO	14C-FC03	Occupied Command
AI	14C-FC03	Zone Temp
AI	14C-FC03	Zone Setpoint
AOS	14C-FC03	Heating Valve Command
AOS	14C-FC03	Cooling Valve Command
BO	14C-FC03	Fan Command
BI	14C-FC03	Fan Status
BI	14C-FC03	Pan Alarm Status
CS	14C-FC03	Temp Occ.Status C.S.
BO	14C-FC04	Occupied Command
AI	14C-FC04	Zone Temp
AI	14C-FC04	Zone Setpoint
AOS	14C-FC04	Heating Valve Command
AOS	14C-FC04	Cooling Valve Command
BO	14C-FC04	Fan Command
BI	14C-FC04	Fan Status
BI	14C-FC04	Pan Alarm Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	14C-FC04	Temp Occ.Status C.S.
BO	14C-FC05	Occupied Command
AI	14C-FC05	Zone Temp
AI	14C-FC05	Zone Setpoint
AOS	14C-FC05	Heating Valve Command
AOS	14C-FC05	Cooling Valve Command
BO	14C-FC05	Fan Command
BI	14C-FC05	Fan Status
BI	14C-FC05	Pan Alarm Status
CS	14C-FC05	Temp Occ.Status C.S.
BO	14C-FC07	Occupied Command
AI	14C-FC07	Zone Temp
AI	14C-FC07	Zone Setpoint
AOS	14C-FC07	Heating Valve Command
AOS	14C-FC07	Cooling Valve Command
BO	14C-FC07	Fan Command
BI	14C-FC07	Fan Status
BI	14C-FC07	Pan Alarm Status
CS	14C-FC07	Temp Occ.Status C.S.
BO	14C-FC08	Occupied Command
AI	14C-FC08	Zone Temp
AI	14C-FC08	Zone Setpoint
AOS	14C-FC08	Heating Valve Command
AOS	14C-FC08	Cooling Valve Command
BO	14C-FC08	Fan Command
BI	14C-FC08	Fan Status
BI	14C-FC08	Pan Alarm Status
CS	14C-FC08	Temp Occ.Status C.S.
BO	14C-FC09	Occupied Command
AI	14C-FC09	Zone Temp
AI	14C-FC09	Zone Setpoint
AOS	14C-FC09	Heating Valve Command
AOS	14C-FC09	Cooling Valve Command
BO	14C-FC09	Fan Command
BI	14C-FC09	Fan Status
BI	14C-FC09	Pan Alarm Status
CS	14C-FC09	Temp Occ.Status C.S.
BO	14C-FC10	Occupied Command
AI	14C-FC10	Zone Temp
AI	14C-FC10	Zone Setpoint
AOS	14C-FC10	Heating Valve Command
AOS	14C-FC10	Cooling Valve Command
BO	14C-FC10	Fan Command
BI	14C-FC10	Fan Status
BI	14C-FC10	Pan Alarm Status
CS	14C-FC10	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	14C-FC12	Occupied Command
AI	14C-FC12	Zone Temp
AI	14C-FC12	Zone Setpoint
AOS	14C-FC12	Heating Valve Command
AOS	14C-FC12	Cooling Valve Command
BO	14C-FC12	Fan Command
BI	14C-FC12	Fan Status
BI	14C-FC12	Pan Alarm Status
CS	14C-FC12	Temp Occ.Status C.S.
BO	14C-FC13	Occupied Command
AI	14C-FC13	Zone Temp
AI	14C-FC13	Zone Setpoint
AOS	14C-FC13	Cooling Valve Command
BO	14C-FC13	Fan Command
BI	14C-FC13	Fan Status
BI	14C-FC13	Pan Alarm Status
CS	14C-FC13	Temp Occ.Status C.S.
BO	14C-FC14	Occupied Command
AI	14C-FC14	Zone Temp
AI	14C-FC14	Zone Setpoint
AOS	14C-FC14	Heating Valve Command
AOS	14C-FC14	Cooling Valve Command
BO	14C-FC14	Fan Command
BI	14C-FC14	Fan Status
BI	14C-FC14	Pan Alarm Status
CS	14C-FC14	Temp Occ.Status C.S.
BO	14C-FC15	Occupied Command
AI	14C-FC15	Zone Temp
AI	14C-FC15	Zone Setpoint
AOS	14C-FC15	Cooling Valve Command
BO	14C-FC15	Fan Command
BI	14C-FC15	Fan Status
BI	14C-FC15	Pan Alarm Status
CS	14C-FC15	Temp Occ.Status C.S.
BO	14C-FC16	Occupied Command
AI	14C-FC16	Zone Temp
AI	14C-FC16	Zone Setpoint
AOS	14C-FC16	Heating Valve Command
AOS	14C-FC16	Cooling Valve Command
BO	14C-FC16	Fan Command
BI	14C-FC16	Fan Status
BI	14C-FC16	Pan Alarm Status
CS	14C-FC16	Temp Occ.Status C.S.
BO	14C-FC17	Occupied Command
AI	14C-FC17	Zone Temp
AI	14C-FC17	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	14C-FC17	Heating Valve Command
AOS	14C-FC17	Cooling Valve Command
BO	14C-FC17	Fan Command
BI	14C-FC17	Fan Status
BI	14C-FC17	Pan Alarm Status
CS	14C-FC17	Temp Occ.Status C.S.
BO	14C-FC18	Occupied Command
AI	14C-FC18	Zone Temp
AI	14C-FC18	Zone Setpoint
AOS	14C-FC18	Heating Valve Command
AOS	14C-FC18	Cooling Valve Command
BO	14C-FC18	Fan Command
BI	14C-FC18	Fan Status
BI	14C-FC18	Pan Alarm Status
CS	14C-FC18	Temp Occ.Status C.S.
BO	MISC-14	Exhaust FAN 14 Command
BI	MISC-14	Exhaust Fan 14 Status
BD	MISC-14	Cooling Valve Overide
BD	MISC-14	Heating Valve Overide
BO	15C-FC02	Occupied Command
AI	15C-FC02	Zone Temp
AI	15C-FC02	Zone Setpoint
AOS	15C-FC02	Heating Valve Command
AOS	15C-FC02	Cooling Valve Command
BO	15C-FC02	Fan Command
BI	15C-FC02	Fan Status
BI	15C-FC02	Pan Alarm Status
CS	15C-FC02	Temp Occ.Status C.S.
BO	15C-FC03	Occupied Command
AI	15C-FC03	Zone Temp
AI	15C-FC03	Zone Setpoint
AOS	15C-FC03	Heating Valve Command
AOS	15C-FC03	Cooling Valve Command
BO	15C-FC03	Fan Command
BI	15C-FC03	Fan Status
BI	15C-FC03	Pan Alarm Status
CS	15C-FC03	Temp Occ.Status C.S.
BO	15C-FC04	Occupied Command
AI	15C-FC04	Zone Temp
AI	15C-FC04	Zone Setpoint
AOS	15C-FC04	Heating Valve Command
AOS	15C-FC04	Cooling Valve Command
BO	15C-FC04	Fan Command
BI	15C-FC04	Fan Status
BI	15C-FC04	Pan Alarm Status
CS	15C-FC04	Temp Occ.Status C.S.

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	15C-FC05	Occupied Command
AI	15C-FC05	Zone Temp
AI	15C-FC05	Zone Setpoint
AOS	15C-FC05	Heating Valve Command
AOS	15C-FC05	Cooling Valve Command
BO	15C-FC05	Fan Command
BI	15C-FC05	Fan Status
BI	15C-FC05	Pan Alarm Status
CS	15C-FC05	Temp Occ.Status C.S.
BO	15C-FC06	Occupied Command
AI	15C-FC06	Zone Temp
AI	15C-FC06	Zone Setpoint
AOS	15C-FC06	Heating Valve Command
AOS	15C-FC06	Cooling Valve Command
BO	15C-FC06	Fan Command
BI	15C-FC06	Fan Status
BI	15C-FC06	Pan Alarm Status
CS	15C-FC06	Temp Occ.Status C.S.
BO	15C-FC07	Occupied Command
AI	15C-FC07	Zone Temp
AI	15C-FC07	Zone Setpoint
AOS	15C-FC07	Heating Valve Command
AOS	15C-FC07	Cooling Valve Command
BO	15C-FC07	Fan Command
BI	15C-FC07	Fan Status
BI	15C-FC07	Pan Alarm Status
CS	15C-FC07	Temp Occ.Status C.S.
BO	15C-FC08	Occupied Command
AI	15C-FC08	Zone Temp
AI	15C-FC08	Zone Setpoint
AOS	15C-FC08	Heating Valve Command
AOS	15C-FC08	Cooling Valve Command
BO	15C-FC08	Fan Command
BI	15C-FC08	Fan Status
BI	15C-FC08	Pan Alarm Status
CS	15C-FC08	Temp Occ.Status C.S.
BO	15C-FC09	Occupied Command
AI	15C-FC09	Zone Temp
AI	15C-FC09	Zone Setpoint
AOS	15C-FC09	Heating Valve Command
AOS	15C-FC09	Cooling Valve Command
BO	15C-FC09	Fan Command
BI	15C-FC09	Fan Status
BI	15C-FC09	Pan Alarm Status
CS	15C-FC09	Temp Occ.Status C.S.
BO	15C-FC10	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	15C-FC10	Zone Temp
AI	15C-FC10	Zone Setpoint
AOS	15C-FC10	Heating Valve Command
AOS	15C-FC10	Cooling Valve Command
BO	15C-FC10	Fan Command
BI	15C-FC10	Fan Status
BI	15C-FC10	Pan Alarm Status
CS	15C-FC10	Temp Occ.Status C.S.
BO	15C-FC11	Occupied Command
AI	15C-FC11	Zone Temp
AI	15C-FC11	Zone Setpoint
AOS	15C-FC11	Heating Valve Command
AOS	15C-FC11	Cooling Valve Command
BO	15C-FC11	Fan Command
BI	15C-FC11	Fan Status
BI	15C-FC11	Pan Alarm Status
CS	15C-FC11	Temp Occ.Status C.S.
BO	15C-FC12	Occupied Command
AI	15C-FC12	Zone Temp
AI	15C-FC12	Zone Setpoint
AOS	15C-FC12	Heating Valve Command
AOS	15C-FC12	Cooling Valve Command
BO	15C-FC12	Fan Command
BI	15C-FC12	Fan Status
BI	15C-FC12	Pan Alarm Status
CS	15C-FC12	Temp Occ.Status C.S.
BO	15C-FC13	Occupied Command
AI	15C-FC13	Zone Temp
AI	15C-FC13	Zone Setpoint
AOS	15C-FC13	Heating Valve Command
AOS	15C-FC13	Cooling Valve Command
BO	15C-FC13	Fan Command
BI	15C-FC13	Fan Status
BI	15C-FC13	Pan Alarm Status
CS	15C-FC13	Temp Occ.Status C.S.
BO	15C-FC14	Occupied Command
AI	15C-FC14	Zone Temp
AI	15C-FC14	Zone Setpoint
AOS	15C-FC14	Heating Valve Command
AOS	15C-FC14	Cooling Valve Command
BO	15C-FC14	Fan Command
BI	15C-FC14	Fan Status
BI	15C-FC14	Pan Alarm Status
CS	15C-FC14	Temp Occ.Status C.S.
BO	15C-FC15	Occupied Command
AI	15C-FC15	Zone Temp

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	15C-FC15	Zone Setpoint
AOS	15C-FC15	Heating Valve Command
AOS	15C-FC15	Cooling Valve Command
BO	15C-FC15	Fan Command
BI	15C-FC15	Fan Status
BI	15C-FC15	Pan Alarm Status
CS	15C-FC15	Temp Occ.Status C.S.
BO	15C-FC16	Occupied Command
AI	15C-FC16	Zone Temp
AI	15C-FC16	Zone Setpoint
AOS	15C-FC16	Heating Valve Command
AOS	15C-FC16	Cooling Valve Command
BO	15C-FC16	Fan Command
BI	15C-FC16	Fan Status
BI	15C-FC16	Pan Alarm Status
CS	15C-FC16	Temp Occ.Status C.S.
BO	15C-FC17	Occupied Command
AI	15C-FC17	Zone Temp
AI	15C-FC17	Zone Setpoint
AOS	15C-FC17	Heating Valve Command
AOS	15C-FC17	Cooling Valve Command
BO	15C-FC17	Fan Command
BI	15C-FC17	Fan Status
BI	15C-FC17	Pan Alarm Status
CS	15C-FC17	Temp Occ.Status C.S.
BO	15C-FC19	Occupied Command
AI	15C-FC19	Zone Temp
AI	15C-FC19	Zone Setpoint
AOS	15C-FC19	Heating Valve Command
AOS	15C-FC19	Cooling Valve Command
BO	15C-FC19	Fan Command
BI	15C-FC19	Fan Status
BI	15C-FC19	Pan Alarm Status
CS	15C-FC19	Temp Occ.Status C.S.
BO	15C-FC20	Occupied Command
AI	15C-FC20	Zone Temp
AI	15C-FC20	Zone Setpoint
AOS	15C-FC20	Heating Valve Command
AOS	15C-FC20	Cooling Valve Command
BO	15C-FC20	Fan Command
BI	15C-FC20	Fan Status
BI	15C-FC20	Pan Alarm Status
CS	15C-FC20	Temp Occ.Status C.S.
BO	15C-FC21	Occupied Command
AI	15C-FC21	Zone Temp
AI	15C-FC21	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	15C-FC21	Heating Valve Command
AOS	15C-FC21	Cooling Valve Command
BI	15C-FC21	Fan Status
BI	15C-FC21	Pan Alarm Status
CS	15C-FC21	Temp Occ.Status C.S.
BO	15C-FC21	Fan Command
BO	MISC-15	Exhaust FAN 15 Command
BI	MISC-15	Exhaust Fan 15 Status
BD	MISC-15	Cooling Valve Overide
BD	MISC-15	Heating Valve Overide
BO	15C-FC01	Occupied Command
AI	15C-FC01	Zone Temp
AI	15C-FC01	Zone Setpoint
AOS	15C-FC01	Heating Valve Command
AOS	15C-FC01	Cooling Valve Command
BO	15C-FC01	Fan Command
BI	15C-FC01	Fan Status
BI	15C-FC01	Pan Alarm Status
CS	15C-FC01	Temp Occ.Status C.S.
	Building 3	
Point	Equipment	Type
	NC-19	Network controller
NC19-HRW	AHU-07	7, 1, 3, AHU
NC19-HRW	AHU-08	8, 1, 3, AHU
NC19-HRW	AHU-09	9, 1, 3, AHU
NC19-HRW	AHU-10	10, 1, 3, AHU
NC19-HRW	AHU-11	11, 1, 3, AHU
NC19-HRW	AHU-12	12, 1, 3, AHU
NC19-HRW	AHU-13	13, 1, 3, AHU
NC19-HRW	AHU-14	14, 1, 3, AHU
NC19-HRW	AHU-15	15, 1, 3, AHU
NC19-HRW	TOWERS	3, 1, 3, UNT
NC19-HRW	17BEXFAN	100, 1, 3, UNT
NC19-HRW	AHU-18	18, 1, 3, AHU
BD	AHU-18	_
AI	AHU-18	Room Temp
AOS	AHU-18	Room Setpoint
BD	AHU-18	
AI	AHU-18	Outside Air Temp
AI	AHU-18	Cooling Coil Temp
AI	AHU-18	Clg Coil Chil Wtr Ret Tp
AI	AHU-18	Htg Coil Discharge Temp
AI	AHU-18	Htg Hot Water Return Tmp
BD	AHU-18	
AOS	AHU-18	Supply Fan OA Enable Stp
BO	AHU-18	Supply Fan Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	AHU-18	Supply Fan Status
BD	AHU-18	
AOS	AHU-18	EF 18A OA Enable Stpt
BO	AHU-18	Exhaust Fan 18A Command
BI	AHU-18	Exhaust Fan 18A Sts
BI	AHU-18	Outside Air Dpr Sts 18A
BD	AHU-18	
AOS	AHU-18	EF 18B OA Enable Stpt
BO	AHU-18	Exhaust Fan 18B Command
BI	AHU-18	Exhaust Fan 18B Sts
BI	AHU-18	Outside Air Dpr Sts 18B
BD	AHU-18	
BI	AHU-18	Filter Status
BI	AHU-18	Low Temp Alarm
BD	AHU-18	
AOS	AHU-18	Heating Valve Command
AOS	AHU-18	Cooling Valve Command
BD	AHU-18	
CS	AHU-18	All Points CS
BD	AHU-15	Fan Coil Occupied Commad
BD	AHU-15	
AI	AHU-15	Preheat Temp
AOS	AHU-15	Preheat Setpoint
AOS	AHU-15	Preheat Valve Command
AI	AHU-15	Preheat RetWtr Temp
BD	AHU-15	Preheat Enable
BD	AHU-15	
AI	AHU-15	Outside Air Temp
AOS	AHU-15	Preheat Face/Bypass
AOS	AHU-15	Face And Bypass Setpoint
BD	AHU-15	Setpoint
AI	AHU-15	Cooling Coil Temp
AOS	AHU-15	Cooling Coil Setpoint
AOS	AHU-15	Cooling Valve Command
AI	AHU-15	Cooiling RetWtr Temp
BD	AHU-15	
AI	AHU-15	Reheat Temp
AOS	AHU-15	Reheat Setpoint
AOS	AHU-15	Reheat Valve Command
AI	AHU-15	Reheat RetWtr Temp
BD	AHU-15	
BO	AHU-15	Supply Fan Command
BI	AHU-15	Supply Airflow
BI	AHU-15	Outside Air Damper Sts
BI	AHU-15	Filter Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	AHU-15	Low Temp Alarm
BI	AHU-15	Supply Air Smk Detector
CS	AHU-15	All Points C.S.
JCB	AHU-15	OCCCMD
JCB	AHU-15	OAT-GOB
BO	16THFlr	Exhaust Fan 16A Command
BO	16THFlr	Exhaust Fan 16B Command
AI	16THFlr	Mechroom Temp
BD	AHU-07	Fan Coil Occupied Commad
BD	AHU-07	
AI	AHU-07	Preheat Temp
AOS	AHU-07	Preheat Setpoint
AOS	AHU-07	Preheat Valve Command
AI	AHU-07	Preheat RetWtr Temp
BD	AHU-07	Preheat Enable
BD	AHU-07	
AI	AHU-07	Outside Air Temp
AOS	AHU-07	Preheat Face/Bypass
AOS	AHU-07	Face And Bypass Setpoint
BD	AHU-07	Setpoint
AI	AHU-07	Cooling Coil Temp
AOS	AHU-07	Cooling Coil Setpoint
AOS	AHU-07	Cooling Valve Command
AI	AHU-07	Cooiling RetWtr Temp
BD	AHU-07	
AI	AHU-07	Reheat Temp
AOS	AHU-07	Reheat Setpoint
AOS	AHU-07	Reheat Valve Command
AI	AHU-07	Reheat RetWtr Temp
BD	AHU-07	
BO	AHU-07	Supply Fan Command
BI	AHU-07	Supply Airflow
BI	AHU-07	Outside Air Damper Sts
BI	AHU-07	Filter Status
BI	AHU-07	Low Temp Alarm
BI	AHU-07	Supply Air Smk Detector
CS	AHU-07	All Points C.S.
JCB	AHU-07	
BD	AHU-08	Fan Coil Occupied Commad
BD	AHU-08	
AI	AHU-08	Preheat Temp
AOS	AHU-08	Preheat Setpoint
AOS	AHU-08	Preheat Valve Command
AI	AHU-08	Preheat RetWtr Temp
BD	AHU-08	Preheat Enable

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BD	AHU-08	
AI	AHU-08	Outside Air Temp
AOS	AHU-08	Preheat Face/Bypass
AOS	AHU-08	Face And Bypass Setpoint
BD	AHU-08	Setpoint
AI	AHU-08	Cooling Coil Temp
AOS	AHU-08	Cooling Coil Setpoint
AOS	AHU-08	Cooling Valve Command
AI	AHU-08	Cooiling RetWtr Temp
BD	AHU-08	
AI	AHU-08	Reheat Temp
AOS	AHU-08	Reheat Setpoint
AOS	AHU-08	Reheat Valve Command
AI	AHU-08	Reheat RetWtr Temp
BD	AHU-08	
BO	AHU-08	Supply Fan Command
BI	AHU-08	Supply Airflow
BI	AHU-08	Outside Air Damper Sts
BI	AHU-08	Filter Status
BI	AHU-08	Low Temp Alarm
BI	AHU-08	Supply Air Smk Detector
CS	AHU-08	All Points C.S.
JCB	AHU-08	OCCCMD
BD	AHU-09	Fan Coil Occupied Commad
BD	AHU-09	
AI	AHU-09	Preheat Temp
AOS	AHU-09	Preheat Setpoint
AOS	AHU-09	Preheat Valve Command
AI	AHU-09	Preheat RetWtr Temp
BD	AHU-09	Preheat Enable
BD	AHU-09	
AI	AHU-09	Outside Air Temp
AOS	AHU-09	Preheat Face/Bypass
AOS	AHU-09	Face And Bypass Setpoint
BD	AHU-09	Setpoint
AI	AHU-09	Cooling Coil Temp
AOS	AHU-09	Cooling Coil Setpoint
AOS	AHU-09	Cooling Valve Command
AI	AHU-09	Cooiling RetWtr Temp
BD	AHU-09	
AI	AHU-09	Reheat Temp
AOS	AHU-09	Reheat Setpoint
AOS	AHU-09	Reheat Valve Command
AI	AHU-09	Reheat RetWtr Temp
BD	AHU-09	

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	AHU-09	Supply Fan Command
BI	AHU-09	Supply Airflow
BI	AHU-09	Outside Air Damper Sts
BI	AHU-09	Filter Status
BI	AHU-09	Low Temp Alarm
BI	AHU-09	Supply Air Smk Detector
CS	AHU-09	All Points C.S.
JCB	AHU-09	9OCCCMD
BD	AHU-14	Fan Coil Occupied Commad
BD	AHU-14	
AI	AHU-14	Preheat Temp
AOS	AHU-14	Preheat Setpoint
AOS	AHU-14	Preheat Valve Command
AI	AHU-14	Preheat RetWtr Temp
BD	AHU-14	Preheat Enable
BD	AHU-14	
AI	AHU-14	Outside Air Temp
AOS	AHU-14	Preheat Face/Bypass
AOS	AHU-14	Face And Bypass Setpoint
BD	AHU-14	Setpoint
AI	AHU-14	Cooling Coil Temp
AOS	AHU-14	Cooling Coil Setpoint
AOS	AHU-14	Cooling Valve Command
AI	AHU-14	Cooiling RetWtr Temp
BD	AHU-14	
AI	AHU-14	Reheat Temp
AOS	AHU-14	Reheat Setpoint
AOS	AHU-14	Reheat Valve Command
AI	AHU-14	Reheat RetWtr Temp
BD	AHU-14	
BO	AHU-14	Supply Fan Command
BI	AHU-14	Supply Airflow
BI	AHU-14	Outside Air Damper Sts
BI	AHU-14	Filter Status
BI	AHU-14	Low Temp Alarm
BI	AHU-14	Supply Air Smk Detector
CS	AHU-14	All Points C.S.
JCB	AHU-14	14COCCMD
BD	AHU-11	Fan Coil Occupied Commad
BD	AHU-11	
AI	AHU-11	Preheat Temp
AOS	AHU-11	Preheat Setpoint
AOS	AHU-11	Preheat Valve Command
AI	AHU-11	Preheat RetWtr Temp
BD	AHU-11	Preheat Enable

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BD	AHU-11	
AI	AHU-11	Outside Air Temp
AOS	AHU-11	Preheat Face/Bypass
AOS	AHU-11	Face And Bypass Setpoint
BD	AHU-11	Setpoint
AI	AHU-11	Cooling Coil Temp
AOS	AHU-11	Cooling Coil Setpoint
AOS	AHU-11	Cooling Valve Command
AI	AHU-11	Cooiling RetWtr Temp
BD	AHU-11	
AI	AHU-11	Reheat Temp
AOS	AHU-11	Reheat Setpoint
AOS	AHU-11	Reheat Valve Command
AI	AHU-11	Reheat RetWtr Temp
BD	AHU-11	
BO	AHU-11	Supply Fan Command
BI	AHU-11	Supply Airflow
BI	AHU-11	Outside Air Damper Sts
BI	AHU-11	Filter Status
BI	AHU-11	Low Temp Alarm
BI	AHU-11	Supply Air Smk Detector
CS	AHU-11	All Points C.S.
JCB	AHU-11	11OCCMD
BD	AHU-12	Fan Coil Occupied Commad
BD	AHU-12	
AI	AHU-12	Preheat Temp
AOS	AHU-12	Preheat Setpoint
AOS	AHU-12	Preheat Valve Command
AI	AHU-12	Preheat RetWtr Temp
BD	AHU-12	Preheat Enable
BD	AHU-12	
AI	AHU-12	Outside Air Temp
AOS	AHU-12	Preheat Face/Bypass
AOS	AHU-12	Face And Bypass Setpoint
BD	AHU-12	Setpoint
AI	AHU-12	Cooling Coil Temp
AOS	AHU-12	Cooling Coil Setpoint
AOS	AHU-12	Cooling Valve Command
AI	AHU-12	Cooiling RetWtr Temp
BD	AHU-12	
AI	AHU-12	Reheat Temp
AOS	AHU-12	Reheat Setpoint
AOS	AHU-12	Reheat Valve Command
AI	AHU-12	Reheat RetWtr Temp
BD	AHU-12	

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	AHU-12	Supply Fan Command
BI	AHU-12	Supply Airflow
BI	AHU-12	Outside Air Damper Sts
BI	AHU-12	Filter Status
BI	AHU-12	Low Temp Alarm
BI	AHU-12	Supply Air Smk Detector
CS	AHU-12	All Points C.S.
JCB	AHU-12	12OCCMD
BD	AHU-13	Fan Coil Occupied Commad
BD	AHU-13	
AI	AHU-13	Preheat Temp
AOS	AHU-13	Preheat Setpoint
AOS	AHU-13	Preheat Valve Command
AI	AHU-13	Preheat RetWtr Temp
BD	AHU-13	Preheat Enable
BD	AHU-13	
AI	AHU-13	Outside Air Temp
AOS	AHU-13	Preheat Face/Bypass
AOS	AHU-13	Face And Bypass Setpoint
BD	AHU-13	Setpoint
AI	AHU-13	Cooling Coil Temp
AOS	AHU-13	Cooling Coil Setpoint
AOS	AHU-13	Cooling Valve Command
AI	AHU-13	Cooiling RetWtr Temp
BD	AHU-13	
AI	AHU-13	Reheat Temp
AOS	AHU-13	Reheat Setpoint
AOS	AHU-13	Reheat Valve Command
AI	AHU-13	Reheat RetWtr Temp
BD	AHU-13	
BO	AHU-13	Supply Fan Command
BI	AHU-13	Supply Airflow
BI	AHU-13	Outside Air Damper Sts
BI	AHU-13	Filter Status
BI	AHU-13	Low Temp Alarm
BI	AHU-13	Supply Air Smk Detector
CS	AHU-13	All Points C.S.
JCB	AHU-13	OCC-CMD
BO	MISC-17	Exhaust Fan 17B Command
BI	MISC-17	Exhaust Fan 17B Status
BI	MISC-17	Exhaust Fan 17B Alarm
BI	MISC-17	Exhaust Fan 17B VFD Sts
AOS	MISC-17	Exhaust Fan 17B Output
BI	MISC-17	Ex Fan 17B OA Damper Sts
AI	MISC-17	17B Air Flow

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AOS	MISC-17	Exhaust Fan 17B CFM Stpt
JCB	JCB-NC19	OA-GLB
JCB	JCB-NC19	PMP-INTL
BD	AHU-10	Fan Coil Occupied Commad
BD	AHU-10	
AI	AHU-10	Preheat Temp
AOS	AHU-10	Preheat Setpoint
AOS	AHU-10	Preheat Valve Command
AI	AHU-10	Preheat RetWtr Temp
BD	AHU-10	Preheat Enable
BD	AHU-10	
AI	AHU-10	Outside Air Temp
AOS	AHU-10	Preheat Face/Bypass
AOS	AHU-10	Face And Bypass Setpoint
BD	AHU-10	Setpoint
AI	AHU-10	Cooling Coil Temp
AOS	AHU-10	Cooling Coil Setpoint
AOS	AHU-10	Cooling Valve Command
AI	AHU-10	Cooiling RetWtr Temp
BD	AHU-10	
AI	AHU-10	Reheat Temp
AOS	AHU-10	Reheat Setpoint
AOS	AHU-10	Reheat Valve Command
AI	AHU-10	Reheat RetWtr Temp
BD	AHU-10	_____
BO	AHU-10	Supply Fan Command
BI	AHU-10	Supply Airflow
BI	AHU-10	Outside Air Damper Sts
BI	AHU-10	Filter Status
BI	AHU-10	Low Temp Alarm
BI	AHU-10	Supply Air Smk Detector
CS	AHU-10	All Points C.S.
JCB	AHU-10	10OCCMD
AOS	AHU-10	Hot Water Bypass Valve
JCB	AHU-10	10ACLGVL
JCB	AHU-10	10AHTGVL
JCB	AHU-10	10BCLGVL
JCB	AHU-10	10BHTGVL
JCB	AHU-10	10CCLGVL
JCB	AHU-10	10CHTGVL
AI	TOWERS	Outside Air Temp
AOS	TOWERS	Condenser Water Setpoint
AI	TOWERS	Condenser Wtr Supply Tmp
BI	TOWERS	Pump Interlock from P7P8
BI	TOWERS	Tower 1 Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	TOWERS	Tower 2 Fan Status
AOS	TOWERS	Condenser Valve Command
BO	TOWERS	Tower1 Low Speed Command
BO	TOWERS	Tower2 Low Speed Command
BO	TOWERS	Tower1 High Speed Commad
BO	TOWERS	Tower2 High Speed Commad
AOS	TOWERS	17th Flr Chw Bypass Vlv
CS	TOWERS	Pump Interlock from P7P8
	Building 3	
Point	Equipment	Type
	NC-22	Network controller
NC22-HRW	VAV@52 - 13-107	52, 1, 3, VMA
NC22-HRW	VAV@53 - 13-106	53, 1, 3, VMA
NC22-HRW	VAV@54 - 13-109	54, 1, 3, VMA
NC22-HRW	VAV@55 - 13-104	55, 1, 3, VMA
NC22-HRW	VAV@56 - 13-102	56, 1, 3, VMA
NC22-HRW	VAV@57 - 13-101	57, 1, 3, VMA
NC22-HRW	VAV@58 - 13-100	58, 1, 3, VMA
NC22-HRW	VAV@59 - 13-115	59, 1, 3, VMA
NC22-HRW	VAV@60 - 13-121	60, 1, 3, VMA
NC22-HRW	VAV@61 - 13-123	61, 1, 3, VMA
NC22-HRW	VAV@62 - 13-126	62, 1, 3, VMA
NC22-HRW	VAV@63 - 13-118	63, 1, 3, VMA
NC22-HRW	VAV@64 - 14-110	64, 1, 3, VMA
NC22-HRW	VAV@65 - 14-120	65, 1, 3, VMA
NC22-HRW	VAV@66 - 14-123	66, 1, 3, VMA
NC22-HRW	VAV@67 - 14-113	67, 1, 3, VMA
NC22-HRW	VAV@68 - 14-125	68, 1, 3, VMA
NC22-HRW	VAV@69 - 14-117	69, 1, 3, VMA
NC22-HRW	VAV@70 - 14-118	70, 1, 3, VMA
NC22-HRW	VAV@71 - 14-141	71, 1, 3, VMA
NC22-HRW	VAV@72 - 14-148	72, 1, 3, VMA
NC22-HRW	VAV@73 - 14-147	73, 1, 3, VMA
NC22-HRW	VAV@74 - 14-146	74, 1, 3, VMA
NC22-HRW	VAV@75 - 14-145	75, 1, 3, VMA
NC22-HRW	VAV@76 - 14-143	76, 1, 3, VMA
NC22-HRW	VAV@77 - 14-131	77, 1, 3, VMA
NC22-HRW	VAV@78 - 14-132	78, 1, 3, VMA
NC22-HRW	VAV@79 - 14-136	79, 1, 3, VMA
NC22-HRW	VAV@80 - 14-128	80, 1, 3, VMA
NC22-HRW	VAV@81 - 14-126	81, 1, 3, VMA
NC22-HRW	VAV@82 - 13-134	82, 1, 3, VMA
NC22-HRW	VAV@83 - 13-141	83, 1, 3, VMA

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC22-HRW	VAV@84 - 13-137	84, 1, 3, VMA
NC22-HRW	VAV@85 - 13-136	85, 1, 3, VMA
NC22-HRW	VAV@86 - 11-107	86, 1, 3, VMA
NC22-HRW	VAV@87 - 11-105	87, 1, 3, VMA
NC22-HRW	VAV@88 - 11-108a	88, 1, 3, VMA
NC22-HRW	VAV@89 - 11-108b	89, 1, 3, VMA
NC22-HRW	VAV@90 - 11-109	90, 1, 3, VMA
NC22-HRW	VAV@91 - 12-105	91, 1, 3, VMA
NC22-HRW	VAV@92 - 12-102	92, 1, 3, VMA
NC22-HRW	VAV@93 - 11-103	93, 1, 3, VMA
NC22-HRW	VAV@94 - 12-101	94, 1, 3, VMA
NC22-HRW	VAV@95 - 12-107	95, 1, 3, VMA
NC22-HRW	VAV@96 - 12-111	96, 1, 3, VMA
NC22-HRW	VAV@97 - 12-114	97, 1, 3, VMA
NC22-HRW	VAV@98 - 11-122	98, 1, 3, VMA
NC22-HRW	VAV@99 - 11-121	99, 1, 3, VMA
NC22-HRW	VAV@100 - 11-124	100, 1, 3, VMA
NC22-HRW	VAV@101 - 11-127	101, 1, 3, VMA
NC22-HRW	VAV@102 - 11-126	102, 1, 3, VMA
NC22-HRW	VAV@103 - 11-130	103, 1, 3, VMA
NC22-HRW	VAV@104 - 11-123	104, 1, 3, VMA
NC22-HRW	VAV@105 - 11-127	105, 1, 3, VMA
NC22-HRW	VAV@106 - 12-128	106, 1, 3, VMA
NC22-HRW	AHU-02N n2=212	212, 1, 3, AHU
NC22-HRW	AHU-01 n2=208	208, 1, 3, AHU
NC22-HRW	AHU-01M n2=210	210, 1, 3, AHU
NC22-HRW	AHU-01W n2=209	209, 1, 3, AHU
NC22-HRW	AHU-01M Misc Points 211	211, 1, 3, UNT
NC22-HRW	FCU 06 Near Load DK 120	120, 1, 3, VAV
NC22-HRW	UNT@192	192, 1, 3, UNT
NC22-HRW	Chiller 2 VFD	213, 1, 3, VND
NC22-HRW	Chiller valve status1	194, 1, 3, UNT
NC22-HRW	Chiller valve status2	193, 1, 3, VAV
MC	1-FCU-06	FCU Occupied Command
BO	1-FCU-06	FCU Fan Command
BI	1-FCU-06	FCU Fan Status
MC	1-FCU-06	
AI	1-FCU-06	FCU SA Temp
AOS	1-FCU-06	FCU CW Valve
MC	1-FCU-06	
AI	1-FCU-06	FCU Zone Temp
AI	1-FCU-06	FCU Zone Setpoint
MC	1-FCU-06	
AI	1-FCU-06	FCU CW Temp
MC	1-FCU-06	
BI	1-FCU-06	FCU Filter Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	CWP2-DRV	CS Actual Frequency
AD	CWP2-DRV	Actual Speed
AD	CWP2-DRV	Motor Current
AD	CWP2-DRV	Energy Megawatts
MSD	13-134	Occupied Command
AI	13-134	Zone Temp
AI	13-134	Zone Setpoint
AI	13-134	Discharge Air Temp
AD	13-134	Supply Air CFM
AD	13-134	Supply Air CFM SP
AD	13-134	Damper Command
BO	13-134	Series Fan Command
AD	13-134	Heating Command
AI	13-134	Bio-Skills Laboratory
CS	13-134	All Points for 13-134
MC	AH-01	AHU Occupied Command
BO	AH-01	Supply Fan Command
BI	AH-01	Supply Airflow
BO	AH-01	OA Damper Command
BI	AH-01	Outside Air Damper Sts
MC	AH-01	
AI	AH-01	Cooling Coil Temp
AOS	AH-01	Cooling Coil Setpoint
AI	AH-01	Cooling RetWtr Temp
AOS	AH-01	Cooling Valve Command
MC	AH-01	
AI	AH-01	Down Duct Static Press
AOS	AH-01	Down Duct Static Setpnt
MC	AH-01	
AOS	AH-01	Supply Fan VFD
BI	AH-01	VSD Run Status
BI	AH-01	VSD Alarm
MC	AH-01	
AI	AH-01	Mixed Air Temp
AI	AH-01	Return Air Temp
MC	AH-01	
AI	AH-01	Pre Heat Temp
AOS	AH-01	Preheat Setpoint
AI	AH-01	Preheat RetWtr Temp
AOS	AH-01	Preheat Valve Command
MC	AH-01	
AI	AH-01	Outside Air Feet Per Min
AOS	AH-01	OA Flow FPM Setpoint
AOS	AH-01	Return Air Damper
MC	AH-01	
BI	AH-01	Low Temp Alarm

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	AH-01	Supply Air Smk Detector
BI	AH-01	High Static Alarm
BI	AH-01	Filter Status
MC	AH-01	
CS	AH-01	AHU CSO
JCB	AH-01	EF-INLK
MC	AH-02N	AHU Occupied Command
BO	AH-02N	Supply Fan Command
BI	AH-02N	Supply Airflow
BO	AH-02N	OA Damper Command
BI	AH-02N	Outside Air Damper Sts
MC	AH-02N	
AI	AH-02N	Cooling Coil Temp
AOS	AH-02N	Cooling Coil Setpoint
AI	AH-02N	Cooling RetWtr Temp
AOS	AH-02N	Cooling Valve Command
MC	AH-02N	
AI	AH-02N	Down Duct Static Press
AOS	AH-02N	Down Duct Static Setpnt
MC	AH-02N	
AOS	AH-02N	Supply Fan VFD
BI	AH-02N	VSD Status
BI	AH-02N	VSD Alarm
MC	AH-02N	
AI	AH-02N	Mixed Air Temp
AI	AH-02N	Return Air Temp
MC	AH-02N	
AI	AH-02N	Preheat Temp
AOS	AH-02N	Preheat Setpoint
AI	AH-02N	Preheat RetWtr Temp
AOS	AH-02N	Preheat Valve Command
MC	AH-02N	
AI	AH-02N	OA Flow FPM
AOS	AH-02N	OA Flow FPM Setpoint
AOS	AH-02N	Return Air Damper
MC	AH-02N	
BI	AH-02N	Low Temp Alarm
BI	AH-02N	Supply Air Smk Detector
BI	AH-02N	High Static Alarm
BI	AH-02N	Filter Status
MC	AH-02N	
CS	AH-02N	AHU CSO
MC	AH-01M	AHU Occuipied Command
BO	AH-01M	Supply Fan Command
BI	AH-01M	Supply Airflow
BI	AH-01M	Outside Air Damper Sts

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MC	AH-01M	
AI	AH-01M	Zone Temp
AI	AH-01M	Zone Humidity
MC	AH-01M	
AI	AH-01M	Preheat Temp
AOS	AH-01M	Preheat Setpoint
AOS	AH-01M	Preheat Valve Command
AI	AH-01M	Preheat RetWtr Temp
MC	AH-01M	
MC	AH-01M	
AI	AH-01M	Outside Air Temp
AOS	AH-01M	Preheat Face/Bypass
AOS	AH-01M	Face And Bypass Setpoint
MC	AH-01M	
AI	AH-01M	Cooling Coil Temp
AOS	AH-01M	Cooling Coil Setpoint
AOS	AH-01M	Cooling Valve Command
AI	AH-01M	Cooling RetWtr Temp
MC	AH-01M	
AI	AH-01M	Reheat Air Temp
AOS	AH-01M	Reheat Coil Setpoint
AOS	AH-01M	Reheat Valve Command
AI	AH-01M	Reheat RetWtr Temp
MC	AH-01M	
BI	AH-01M	Low Temp Alarm
BI	AH-01M	Supply Air Smk Detector
BI	AH-01M	Filter Status
MC	AH-01M	
CS	AH-01M	AHU CSO Zone Temp
MC	AH-01W	AHU Occuipied Command
BO	AH-01W	Supply Fan Command
BI	AH-01W	Supply Airflow
BO	AH-01W	OA Damper Command
BI	AH-01W	Outside Air Damper Sts
MC	AH-01W	
AI	AH-01W	Cooling Coil Temp
AOS	AH-01W	Cooling Coil Setpoint
AI	AH-01W	Cooling RetWtr Temp
AOS	AH-01W	Cooling Valve Command
MC	AH-01W	
AI	AH-01W	Down Duct Static Press
AOS	AH-01W	Down Duct Setpoint
MC	AH-01W	
AOS	AH-01W	Supply Fan VFD
BI	AH-01W	VSD Status
BI	AH-01W	VSD Alarm

DRAFT

	Building 3	
Point	**Equipment**	**Type**
MC	AH-01W	
AI	AH-01W	Mixed Air Temp
AI	AH-01W	Return Air Temp
MC	AH-01W	
AI	AH-01W	Preheat Temp
AOS	AH-01W	Preheat Setpoint
AI	AH-01W	Preheat RetWtr Temp
AOS	AH-01W	Preheat Valve Command
MC	AH-01W	
AI	AH-01W	OA Flow FPM
AOS	AH-01W	OA Flow FPM Setpoint
AOS	AH-01W	Return Air Damper
MC	AH-01W	
BI	AH-01W	Low Temp Alarm
BI	AH-01W	Supply Air Smk Detector
BI	AH-01W	High Static Alarm
BI	AH-01W	Filter Status
MC	AH-01W	
CS	AH-01W	AHU CSO Dis Air Temp
MSD	12-128	Occupied Command
AI	12-128	Zone Temp
AI	12-128	Zone Setpoint
AI	12-128	Discharge Air Temp
AD	12-128	Supply Air CFM
AD	12-128	Supply Air CFM SP
AD	12-128	Damper Command
BO	12-128	Series Fan Command
AD	12-128	Heating Command
CS	12-128	All Points for 12-128
MSD	12-127	Occupied Command
AI	12-127	Zone Temp
AI	12-127	Zone Setpoint
AI	12-127	Discharge Air Temp
AD	12-127	Supply Air CFM
AD	12-127	Supply Air CFM SP
AD	12-127	Damper Command
BO	12-127	Series Fan Command
AD	12-127	Heating Command
CS	12-127	All Points for 11-127
MSD	11-123	Occupied Command
AI	11-123	Zone Temp
AI	11-123	Zone Setpoint
AI	11-123	Discharge Air Temp
AD	11-123	Supply Air CFM
AD	11-123	Supply Air CFM SP
AD	11-123	Damper Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	11-123	Series Fan Command
AD	11-123	Heating Command
CS	11-123	All Points for 11-123
MSD	11-130	Occupied Command
AI	11-130	Zone Temp
AI	11-130	Zone Setpoint
AI	11-130	Discharge Air Temp
AD	11-130	Supply Air CFM
AD	11-130	Supply Air CFM SP
AD	11-130	Damper Command
BO	11-130	Series Fan Command
AD	11-130	Heating Command
CS	11-130	All Points for 11-130
MSD	11-126	Occupied Command
AI	11-126	Zone Temp
AI	11-126	Zone Setpoint
AI	11-126	Discharge Air Temp
AD	11-126	Supply Air CFM
AD	11-126	Supply Air CFM SP
AD	11-126	Damper Command
BO	11-126	Series Fan Command
AD	11-126	Heating Command
CS	11-126	All Points for 11-126
MSD	11-127	Occupied Command
AI	11-127	Zone Temp
AI	11-127	Zone Setpoint
AI	11-127	Discharge Air Temp
AD	11-127	Supply Air CFM
AD	11-127	Supply Air CFM SP
AD	11-127	Damper Command
BO	11-127	Series Fan Command
AD	11-127	Heating Command
CS	11-127	All Points for 11-127
MSD	11-124	Occupied Command
AI	11-124	Zone Temp
AI	11-124	Zone Setpoint
AI	11-124	Discharge Air Temp
AD	11-124	Supply Air CFM
AD	11-124	Supply Air CFM SP
AD	11-124	Damper Command
BO	11-124	Series Fan Command
AD	11-124	Heating Command
CS	11-124	All Points for 11-124
MSD	11-121	Occupied Command
AI	11-121	Zone Temp
AI	11-121	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	11-121	Discharge Air Temp
AD	11-121	Supply Air CFM
AD	11-121	Supply Air CFM SP
AD	11-121	Damper Command
BO	11-121	Series Fan Command
AD	11-121	Heating Command
CS	11-121	All Points for 11-121
MSD	11-122	Occupied Command
AI	11-122	Zone Temp
AI	11-122	Zone Setpoint
AI	11-122	Discharge Air Temp
AD	11-122	Supply Air CFM
AD	11-122	Supply Air CFM SP
AD	11-122	Damper Command
BO	11-122	Series Fan Command
AD	11-122	Heating Command
CS	11-122	All Points for 11-122
MSD	12-114	Occupied Command
AI	12-114	Zone Temp
AI	12-114	Zone Setpoint
AI	12-114	Discharge Air Temp
AD	12-114	Supply Air CFM
AD	12-114	Supply Air CFM SP
AD	12-114	Damper Command
BO	12-114	Series Fan Command
AD	12-114	Heating Command
CS	12-114	All Points for 12-114
MSD	12-111	Occupied Command
AI	12-111	Zone Temp
AI	12-111	Zone Setpoint
AI	12-111	Discharge Air Temp
AD	12-111	Supply Air CFM
AD	12-111	Supply Air CFM SP
AD	12-111	Damper Command
BO	12-111	Series Fan Command
AD	12-111	Heating Command
CS	12-111	All Points for 12-111
MSD	12-107	Occupied Command
AI	12-107	Zone Temp
AI	12-107	Zone Setpoint
AI	12-107	Discharge Air Temp
AD	12-107	Supply Air CFM
AD	12-107	Supply Air CFM SP
AD	12-107	Damper Command
BO	12-107	Series Fan Command
AD	12-107	Heating Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	12-107	All Points for 12-107
MSD	12-101	Occupied Command
AI	12-101	Zone Temp
AI	12-101	Zone Setpoint
AI	12-101	Discharge Air Temp
AD	12-101	Supply Air CFM
AD	12-101	Supply Air CFM SP
AD	12-101	Damper Command
BO	12-101	Series Fan Command
AD	12-101	Heating Command
CS	12-101	All Points for 12-101
MSD	11-103	Occupied Command
AI	11-103	Zone Temp
AI	11-103	Zone Setpoint
AI	11-103	Discharge Air Temp
AD	11-103	Supply Air CFM
AD	11-103	Supply Air CFM SP
AD	11-103	Damper Command
BO	11-103	Series Fan Command
AD	11-103	Heating Command
CS	11-103	All Points for 11-103
MSD	12-102	Occupied Command
AI	12-102	Zone Temp
AI	12-102	Zone Setpoint
AI	12-102	Discharge Air Temp
AD	12-102	Supply Air CFM
AD	12-102	Supply Air CFM SP
AD	12-102	Damper Command
BO	12-102	Series Fan Command
AD	12-102	Heating Command
CS	12-102	All Points for 12-102
MSD	12-105	Occupied Command
AI	12-105	Zone Temp
AI	12-105	Zone Setpoint
AI	12-105	Discharge Air Temp
AD	12-105	Supply Air CFM
AD	12-105	Supply Air CFM SP
AD	12-105	Damper Command
BO	12-105	Series Fan Command
AD	12-105	Heating Command
CS	12-105	All Points for 12-105
MSD	11-109	Occupied Command
AI	11-109	Zone Temp
AI	11-109	Zone Setpoint
AI	11-109	Discharge Air Temp
AD	11-109	Supply Air CFM

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	11-109	Supply Air CFM SP
AD	11-109	Damper Command
BO	11-109	Series Fan Command
AD	11-109	Heating Command
CS	11-109	All Points for 11-109
MSD	11-108b	Occupied Command
AI	11-108b	Zone Temp
AI	11-108b	Zone Setpoint
AI	11-108b	Discharge Air Temp
AD	11-108b	Supply Air CFM
AD	11-108b	Supply Air CFM SP
AD	11-108b	Damper Command
BO	11-108b	Series Fan Command
AD	11-108b	Heating Command
CS	11-108b	All Points for 11-108b
MSD	11-108a	Occupied Command
AI	11-108a	Zone Temp
AI	11-108a	Zone Setpoint
AI	11-108a	Discharge Air Temp
AD	11-108a	Supply Air CFM
AD	11-108a	Supply Air CFM SP
AD	11-108a	Damper Command
BO	11-108a	Series Fan Command
AD	11-108a	Heating Command
CS	11-108a	All Points for 11-108a
MSD	11-105	Occupied Command
AI	11-105	Zone Temp
AI	11-105	Zone Setpoint
AI	11-105	Discharge Air Temp
AD	11-105	Supply Air CFM
AD	11-105	Supply Air CFM SP
AD	11-105	Damper Command
BO	11-105	Series Fan Command
AD	11-105	Heating Command
CS	11-105	All Points for 11-105
MSD	11-107	Occupied Command
AI	11-107	Zone Temp
AI	11-107	Zone Setpoint
AI	11-107	Discharge Air Temp
AD	11-107	Supply Air CFM
AD	11-107	Supply Air CFM SP
AD	11-107	Damper Command
BO	11-107	Series Fan Command
AD	11-107	Heating Command
CS	11-107	All Points for 11-107
MSD	13-136	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	13-136	Zone Temp
AI	13-136	Zone Setpoint
AI	13-136	Discharge Air Temp
AD	13-136	Supply Air CFM
AD	13-136	Supply Air CFM SP
AD	13-136	Damper Command
BO	13-136	Series Fan Command
AD	13-136	Heating Command
CS	13-136	All Points for 13-136
MSD	13-137	Occupied Command
AI	13-137	Zone Temp
AI	13-137	Zone Setpoint
AI	13-137	Discharge Air Temp
AD	13-137	Supply Air CFM
AD	13-137	Supply Air CFM SP
AD	13-137	Damper Command
BO	13-137	Series Fan Command
AD	13-137	Heating Command
CS	13-137	All Points for 13-137
MSD	13-141	Occupied Command
AI	13-141	Zone Temp
AI	13-141	Zone Setpoint
AI	13-141	Discharge Air Temp
AD	13-141	Supply Air CFM
AD	13-141	Supply Air CFM SP
AD	13-141	Damper Command
BO	13-141	Series Fan Command
AD	13-141	Heating Command
CS	13-141	All Points for 13-141
MSD	14-126	Occupied Command
AI	14-126	Zone Temp
AI	14-126	Zone Setpoint
AI	14-126	Discharge Air Temp
AD	14-126	Supply Air CFM
AD	14-126	Supply Air CFM SP
AD	14-126	Damper Command
BO	14-126	Series Fan Command
AD	14-126	Heating Command
CS	14-126	All Points for 14-126
MSD	14-128	Occupied Command
AI	14-128	Zone Temp
AI	14-128	Zone Setpoint
AI	14-128	Discharge Air Temp
AD	14-128	Supply Air CFM
AD	14-128	Supply Air CFM SP
AD	14-128	Damper Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	14-128	Series Fan Command
AD	14-128	Heating Command
CS	14-128	All Points for 14-128
MSD	14-136	Occupied Command
AI	14-136	Zone Temp
AI	14-136	Zone Setpoint
AI	14-136	Discharge Air Temp
AD	14-136	Supply Air CFM
AD	14-136	Supply Air CFM SP
AD	14-136	Damper Command
BO	14-136	Series Fan Command
AD	14-136	Heating Command
CS	14-136	All Points for 14-136
MSD	14-132	Occupied Command
AI	14-132	Zone Temp
AI	14-132	Zone Setpoint
AI	14-132	Discharge Air Temp
AD	14-132	Supply Air CFM
AD	14-132	Supply Air CFM SP
AD	14-132	Damper Command
BO	14-132	Series Fan Command
AD	14-132	Heating Command
CS	14-132	All Points for 14-132
MSD	14-131	Occupied Command
AI	14-131	Zone Temp
AI	14-131	Zone Setpoint
AI	14-131	Discharge Air Temp
AD	14-131	Supply Air CFM
AD	14-131	Supply Air CFM SP
AD	14-131	Damper Command
BO	14-131	Series Fan Command
AD	14-131	Heating Command
CS	14-131	All Points for 14-131
MSD	14-143	Occupied Command
AI	14-143	Zone Temp
AI	14-143	Zone Setpoint
AI	14-143	Discharge Air Temp
AD	14-143	Supply Air CFM
AD	14-143	Supply Air CFM SP
AD	14-143	Damper Command
BO	14-143	Series Fan Command
AD	14-143	Heating Command
CS	14-143	All Points for 14-143
MSD	14-145	Occupied Command
AI	14-145	Zone Temp
AI	14-145	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	14-145	Discharge Air Temp
AD	14-145	Supply Air CFM
AD	14-145	Supply Air CFM SP
AD	14-145	Damper Command
BO	14-145	Series Fan Command
AD	14-145	Heating Command
CS	14-145	All Points for 14-145
MSD	14-146	Occupied Command
AI	14-146	Zone Temp
AI	14-146	Zone Setpoint
AI	14-146	Discharge Air Temp
AD	14-146	Supply Air CFM
AD	14-146	Supply Air CFM SP
AD	14-146	Damper Command
BO	14-146	Series Fan Command
AD	14-146	Heating Command
CS	14-146	All Points for 14-146
MSD	14-147	Occupied Command
AI	14-147	Zone Temp
AI	14-147	Zone Setpoint
AI	14-147	Discharge Air Temp
AD	14-147	Supply Air CFM
AD	14-147	Supply Air CFM SP
AD	14-147	Damper Command
BO	14-147	Series Fan Command
AD	14-147	Heating Command
CS	14-147	All Points for 14-147
MSD	14-148	Occupied Command
AI	14-148	Zone Temp
AI	14-148	Zone Setpoint
AI	14-148	Discharge Air Temp
AD	14-148	Supply Air CFM
AD	14-148	Supply Air CFM SP
AD	14-148	Damper Command
BO	14-148	Series Fan Command
AD	14-148	Heating Command
CS	14-148	All Points for 14-148
MSD	14-141	Occupied Command
AI	14-141	Zone Temp
AI	14-141	Zone Setpoint
AI	14-141	Discharge Air Temp
AD	14-141	Supply Air CFM
AD	14-141	Supply Air CFM SP
AD	14-141	Damper Command
BO	14-141	Series Fan Command
AD	14-141	Heating Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	14-141	All Points for 14-141
MSD	14-118	Occupied Command
AI	14-118	Zone Temp
AI	14-118	Zone Setpoint
AI	14-118	Discharge Air Temp
AD	14-118	Supply Air CFM
AD	14-118	Supply Air CFM SP
AD	14-118	Damper Command
BO	14-118	Series Fan Command
AD	14-118	Heating Command
CS	14-118	All Points for 14-118
MSD	14-117	Occupied Command
AI	14-117	Zone Temp
AI	14-117	Zone Setpoint
AI	14-117	Discharge Air Temp
AD	14-117	Supply Air CFM
AD	14-117	Supply Air CFM SP
AD	14-117	Damper Command
BO	14-117	Series Fan Command
AD	14-117	Heating Command
CS	14-117	All Points for 14-117
MSD	14-125	Occupied Command
AI	14-125	Zone Temp
AI	14-125	Zone Setpoint
AI	14-125	Discharge Air Temp
AD	14-125	Supply Air CFM
AD	14-125	Supply Air CFM SP
AD	14-125	Damper Command
BO	14-125	Series Fan Command
AD	14-125	Heating Command
CS	14-125	All Points for 14-125
MSD	14-113	Occupied Command
AI	14-113	Zone Temp
AI	14-113	Zone Setpoint
AI	14-113	Discharge Air Temp
AD	14-113	Supply Air CFM
AD	14-113	Supply Air CFM SP
AD	14-113	Damper Command
BO	14-113	Series Fan Command
AD	14-113	Heating Command
CS	14-113	All Points for 14-113
MSD	14-123	Occupied Command
AI	14-123	Zone Temp
AI	14-123	Zone Setpoint
AI	14-123	Discharge Air Temp
AD	14-123	Supply Air CFM

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	14-123	Supply Air CFM SP
AD	14-123	Damper Command
BO	14-123	Series Fan Command
AD	14-123	Heating Command
CS	14-123	All Points for 14-123
MSD	14-120	Occupied Command
AI	14-120	Zone Temp
AI	14-120	Zone Setpoint
AI	14-120	Discharge Air Temp
AD	14-120	Supply Air CFM
AD	14-120	Supply Air CFM SP
AD	14-120	Damper Command
BO	14-120	Series Fan Command
AD	14-120	Heating Command
CS	14-120	All Points for 14-120
MSD	14-110	Occupied Command
AI	14-110	Zone Temp
AI	14-110	Zone Setpoint
AI	14-110	Discharge Air Temp
AD	14-110	Supply Air CFM
AD	14-110	Supply Air CFM SP
AD	14-110	Damper Command
BO	14-110	Series Fan Command
AD	14-110	Heating Command
CS	14-110	All Points for 14-110
MSD	13-118	Occupied Command
AI	13-118	Zone Temp
AI	13-118	Zone Setpoint
AI	13-118	Discharge Air Temp
AD	13-118	Supply Air CFM
AD	13-118	Supply Air CFM SP
AD	13-118	Damper Command
BO	13-118	Series Fan Command
AD	13-118	Heating Command
CS	13-118	All Points for 13-118
MSD	13-126	Occupied Command
AI	13-126	Zone Temp
AI	13-126	Zone Setpoint
AI	13-126	Discharge Air Temp
AD	13-126	Supply Air CFM
AD	13-126	Supply Air CFM SP
AD	13-126	Damper Command
BO	13-126	Series Fan Command
AD	13-126	Heating Command
CS	13-126	All Points for 13-126
MSD	13-123	Occupied Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	13-123	Zone Temp
AI	13-123	Zone Setpoint
AI	13-123	Discharge Air Temp
AD	13-123	Supply Air CFM
AD	13-123	Supply Air CFM SP
AD	13-123	Damper Command
BO	13-123	Series Fan Command
AD	13-123	Heating Command
CS	13-123	All Points for 13-123
MSD	13-121	Occupied Command
AI	13-121	Zone Temp
AI	13-121	Zone Setpoint
AI	13-121	Discharge Air Temp
AD	13-121	Supply Air CFM
AD	13-121	Supply Air CFM SP
AD	13-121	Damper Command
BO	13-121	Series Fan Command
AD	13-121	Heating Command
CS	13-121	All Points for 13-121
MSD	13-115	Occupied Command
AI	13-115	Zone Temp
AI	13-115	Zone Setpoint
AI	13-115	Discharge Air Temp
AD	13-115	Supply Air CFM
AD	13-115	Supply Air CFM SP
AD	13-115	Damper Command
BO	13-115	Series Fan Command
AD	13-115	Heating Command
CS	13-115	All Points for 13-115
MSD	13-100	Occupied Command
AI	13-100	Zone Temp
AI	13-100	Zone Setpoint
AI	13-100	Discharge Air Temp
AD	13-100	Supply Air CFM
AD	13-100	Supply Air CFM SP
AD	13-100	Damper Command
BO	13-100	Series Fan Command
AD	13-100	Heating Command
CS	13-100	All Points for 13-100
MSD	13-101	Occupied Command
AI	13-101	Zone Temp
AI	13-101	Zone Setpoint
AI	13-101	Discharge Air Temp
AD	13-101	Supply Air CFM
AD	13-101	Supply Air CFM SP
AD	13-101	Damper Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	13-101	Series Fan Command
AD	13-101	Heating Command
CS	13-101	All Points for 13-101
MSD	13-102	Occupied Command
AI	13-102	Zone Temp
AI	13-102	Zone Setpoint
AI	13-102	Discharge Air Temp
AD	13-102	Supply Air CFM
AD	13-102	Supply Air CFM SP
AD	13-102	Damper Command
BO	13-102	Series Fan Command
AD	13-102	Heating Command
CS	13-102	All Points for 13-102
MSD	13-104	Occupied Command
AI	13-104	Zone Temp
AI	13-104	Zone Setpoint
AI	13-104	Discharge Air Temp
AD	13-104	Supply Air CFM
AD	13-104	Supply Air CFM SP
AD	13-104	Damper Command
BO	13-104	Series Fan Command
AD	13-104	Heating Command
CS	13-104	All Points for 13-104
MSD	13-109	Occupied Command
AI	13-109	Zone Temp
AI	13-109	Zone Setpoint
AI	13-109	Discharge Air Temp
AD	13-109	Supply Air CFM
AD	13-109	Supply Air CFM SP
AD	13-109	Damper Command
BO	13-109	Series Fan Command
AD	13-109	Heating Command
CS	13-109	All Points for 13-109
MSD	13-106	Occupied Command
AI	13-106	Zone Temp
AI	13-106	Zone Setpoint
AI	13-106	Discharge Air Temp
AD	13-106	Supply Air CFM
AD	13-106	Supply Air CFM SP
AD	13-106	Damper Command
BO	13-106	Series Fan Command
AD	13-106	Heating Command
CS	13-106	All Points for 13-106
MSD	13-107	Occupied Command
AI	13-107	Zone Temp
AI	13-107	Zone Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	13-107	Discharge Air Temp
AD	13-107	Supply Air CFM
AD	13-107	Supply Air CFM SP
AD	13-107	Damper Command
BO	13-107	Series Fan Command
AD	13-107	Heating Command
CS	13-107	All Points for 13-107
Building 20		
Points	**Equipment**	**Type**
NC-20		**Network controller**
NC20_HW	XRL1_2HW	2, 1, 3, 1
NC20_HW	XBN1_3HW	3, 1, 1, 1
NC20_HW	DCM2_4HW	4, 1, 1
NC20_HW	XRL2_5HW	5, 1, 3, 1
NC20_HW	XRL3_6HW	6, 1, 3, 1
NC20_HW	DCM3_7HW	7, 1, 1
NC20_HW	YORK1_HW	8, 1, 3, MIG
NC20_HW	YORK2_HW	9, 1, 3, MIG
NC20_HW	YORK3_HW	10, 1, 3, MIG
NC20_HW	DCM4HW11	21, 1, 1
NC20_HW	XBN2HW12	12, 1, 1, 1
NC20_HW	TRANE1HW	13, 1, 1, MIG
NC20_HW	TRANEHW2	14, 1, 1, MIG
NC20_HW	DX15	15, 1, 3, DX9100
NC20_HW	Dx16	16, 1, 3, DX9100
NC20_HW	DP-1	25, 1, 3, VND
NC20_HW	DP-2	26, 1, 3, VND
NC20_HW	DP-3	27, 1, 3, VND
NC20_HW	DP-4	28, 1, 3, VND
NC20_HW	HWP-1	29, 1, 3, VND
NC20_HW	HWP2	30, 1, 3, VND
NC20_HW	HWP3	31, 1, 3, VND
NC20_HW	DX-17	17, 1, 3, DX9100
NC20_HW	DX39	39, 1, 3, DX9100
NC20_HW	CT1-F1	40, 1, 3, VND
NC20_HW	CT1-F2	41, 1, 3, VND

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC20_HW	CT1-F3	42, 1, 3, VND
NC20_HW	CT2-F1	43, 1, 3, VND
NC20_HW	CT2-F2	44, 1, 3, VND
NC20_HW	CT2-F3	45, 1, 3, VND
NC20_HW	CT3-F1	46, 1, 3, VND
NC20_HW	CT3-F2	47, 1, 3, VND
NC20_HW	CT3-F3	48, 1, 3, VND
NC20_HW	CT4-F1	49, 1, 3, VND
NC20_HW	CT4-F2	50, 1, 3, VND
NC20_HW	CT4-F3	51, 1, 3, VND
NC20_HW	CT4-F4	52, 1, 3, VND
BD	HEATEXCH	HWPMPINT
BD	HEATEXCH	HX1_ENAB
AI	HEATEXCH	HWS-T1
PIDL	HEATEXCH	HX1_PIDL
AOD	HEATEXCH	HHX1-VLV
BD	HEATEXCH	HX2_ENAB
AI	HEATEXCH	HWS-T2
PIDL	HEATEXCH	HX2_PIDL
AOD	HEATEXCH	HHX2-VLV
BD	HEATEXCH	HX3_ENAB
AI	HEATEXCH	HWS-T3
PIDL	HEATEXCH	HX3_PIDL
AOD	HEATEXCH	HHX3-VLV
JCB	HEATEXCH	HX2_GPL
JCB	HEATEXCH	HX3_GPL
JCB	HEATEXCH	HX1_GPL
MC	HEATEXCH	ALM-DIS
SLAVE		
SLAVE		
AI	MAINCHWL	CWS-T
AI	MAINCHWL	CWR-T
BD	MAINCHWL	CHWS_ENA
AI	MAINCHWL	CWS-F
AOS	MAINCHWL	DP-SPT
BI	MAINCHWL	REF-TBL
BI	MAINCHWL	REF-ALM

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	MAINCHWL	CWBYP-FW
AI	MAINCHWL	CWBYP-R
BO	MAINCHWL	DP1-3-C
AD	MAINCHWL	CHS_LOAD
BO	MAINCHWL	VFD1-EN
BO	MAINCHWL	VFD2-EN
BO	MAINCHWL	VFD3-EN
BO	MAINCHWL	VFD4-EN
BO	MAINCHWL	Sec-En
BI	MAINCHWL	CWP1-ST
BI	MAINCHWL	CWP2-ST
BI	MAINCHWL	CWP3-ST
BI	MAINCHWL	CWP4-ST
AI	MAINCHWL	1FREQ-HZ
AI	MAINCHWL	2FREQ-HZ
AI	MAINCHWL	3FREQ-HZ
AI	MAINCHWL	4FREQ-HZ
AOS	MAINCHWL	VFD1-FBK
AOS	MAINCHWL	VFD2-FBK
AOS	MAINCHWL	VFD3-FBK
AOS	MAINCHWL	VFD4-FBK
AD	MAINCHWL	SYS_PRES
JCB	MainChwl	SecChwp
JCB	MAINCHWL	CHLR_PRO
AI	MAINCHWL	VFD-AC-T
BI	MAINCHWL	VFDAC-ST
BO	MAINCHWL	TEMP-RST
BO	CLNGTWR1	CT1ISOV
BI	CLNGTWR1	CT1ISOVC
AI	CLNGTWR1	CT1ASMPT
AI	CLNGTWR1	CT1BSMPT
BI	CLNGTWR1	CT1IVRSO
BI	CLNGTWR1	CT1IVRSC
BO	CLNGTWR1	CT1-ENA
JCB	CLNGTWR1	CT1FANS
BO	CLNGTWR4	CT4ISOV
BI	CLNGTWR4	CT4ISOVC

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	CLNGTWR4	CT4IVRCO
BI	CLNGTWR4	CT4IVRSC
BO	CLNGTWR4	CT4-ENA
JCB	CLNGTWR4	CT4-FANS
BO	CLNGTWR2	CT2ISOV
BI	CLNGTWR2	CT2ISOVC
BI	CLNGTWR2	CT2IVRSO
BI	CLNGTWR2	CT2ISVRC
AOD	CLNGTWR2	CT2BPVLV
BO	CLNGTWR2	CT2-ENA
JCB	CLNGTWR2	CT2-FANS
BO	CLNGTWR3	CT3ISOV
BI	CLNGTWR3	CT3ISOVC
AI	CLNGTWR3	CT3ASMPT
AI	CLNGTWR3	CT3BSMPT
BI	CLNGTWR3	CT3IVRSO
BI	CLNGTWR3	CT3IVRSC
BO	CLNGTWR3	CT3-ENA
JCB	CLNGTWR3	CT3-FANS
BD	CLNGTWRs	CALL_RUN
AI	CLNGTWRS	CTS-T
AI	CLNGTWRS	CTR-T
PIDL	CLNGTWRS	PID_LOOP
AOD	CLNGTWRS	PIDL_OUT
BO	CLNGTWRS	CTP1-C
BI	CLNGTWRS	CTP1-S
AD	CLNGTWRS	CTP1-RUN
BI	CLNGTWRS	CTP1-TRP
BO	CLNGTWRS	CTP2-C
BI	CLNGTWRS	CTP2-S
AD	CLNGTWRS	CTP2-RUN
BI	CLNGTWRS	CTP2-TRP
BO	CLNGTWRS	CTP3-C
BI	CLNGTWRS	CTP3-S
AD	CLNGTWRS	CTP3-RUN
BI	CLNGTWRS	CTP3-TRP
BO	CLNGTWRS	CTP4-C

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	CLNGTWRS	CTP4-S
AD	CLNGTWRS	CTP4-RUN
BI	CLNGTWRS	CTP4-TRP
AOD	CLNGTWRS	CTA-VLV
BI	CLNGTWRS	CTVA-OPN
BI	CLNGTWRS	CTVA-CLS
AOD	CLNGTWRS	CTB-VLV
BI	CLNGTWRS	CTVB-OPN
BI	CLNGTWRS	CTVB-CLS
AOD	CLNGTWRS	CTC-VLV
BI	CLNGTWRS	CTVC-OPN
BI	CLNGTWRS	CTVC-CLO
MC	CLNGTWRS	CTP4-MCO
SLAVE		
SLAVE		
PIDL	CLNGTWRS	CD_SUPID
JCB	CLNGTWRS	FAN_CNTR
AOS	CLNGTWRS	CTV5-AO
BO	CLNGTWRS	CH1-INT
BO	CLNGTWRS	CH2-INT
BO	CLNGTWRS	CH3-INT
BO	CLNGTWRS	CH4-INT
AI	CLNGTWRS	LVL-CT1
AI	CLNGTWRS	LVL-CT2
AI	CLNGTWRS	LVL-CT3
AI	CLNGTWRS	LVL-CT4
CS	CLNGTWRS	CS-VLVS
JCB	CLNGTWRS	TWICEDAY
JCB	CLNGTWRS	CT1-LVL
JCB	CLNGTWRS	CONDPROC
CS	CLNGTWRS	CT-CS
AOS	CLNGTWRS	CWS-T
AOS	CLNGTWRS	CWST-SP
JCB	CLNGTWRS	SHR-CWST
JCB	CLNGTWRS	NEW-COND
JCB	clngtwrs	C4MODE
BD	CHILLER1	CH1SYSEN

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	CHILLER1	CH1S-T
AI	CHILLER1	CH1R-T
BD	CHILLER1	CH1-C
BI	CHILLER1	CH1-S
BI	CHILLER1	CH1-FLT
BI	CHILLER1	CH1-ALM
BI	CHILLER1	CH1E-OPN
BI	CHILLER1	CH1C-OPN
BO	CHILLER1	CHP1-C
BI	CHILLER1	CHP1-S
BI	CHILLER1	CHP1-TRP
AI	CHILLER1	CH1CTS-T
AI	CHILLER1	CH1CTR-T
AI	CHILLER1	CH1CTR-F
AD	CHILLER1	CH1_CDLD
AI	CHILLER1	CH1R-F
AD	CHILLER1	CH1_LOAD
BO	CHILLER1	GEN1_ENA
MSD	CHILLER1	CH1-STAT
MC	CHILLER1	ALM-DIS
SLAVE		
SLAVE		
BD	CHILLER1	TEST123
CS	CS-NC-20	CS-CWP
CS	CS-NC-20	CS-HWP
CS	CS-NC-20	DP1-VFD
CS	CS-NC-20	DP2-VFD
CS	CS-NC-20	DP3-VFD
CS	CS-NC-20	DP4-VFD
CS	CS-NC-20	HWP1-VFD
CS	CS-NC-20	HWP2-VFD
CS	CS-NC-20	HWP3-VFD
BD	CS-NC-20	_____
CS	CS-NC-20	CT1-F1
CS	CS-NC-20	CT1-F2
CS	CS-NC-20	CT1-F3
BD	CS-NC-20	CT1-FLT

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BD	CS-NC-20	_____
CS	CS-NC-20	CT2-F1
CS	CS-NC-20	CT2-F2
CS	CS-NC-20	CT2-F3
BD	CS-NC-20	CT2-FLT
BD	CS-NC-20	_____
CS	CS-NC-20	CT3-F1
CS	CS-NC-20	CT3-F2
CS	CS-NC-20	CT3-F3
BD	CS-NC-20	CT3-FLT
BD	CS-NC-20	_____
CS	CS-NC-20	CT4-F1
CS	CS-NC-20	CT4-F2
CS	CS-NC-20	CT4-F3
CS	CS-NC-20	CT4-F4
BD	CS-NC-20	CT4-FLT
JCB	CS-NC-20	VFD-FLT
AD	NC20_HW	idle
BD	CHILLER4	CH4SYSEN
BO	CHILLER4	CHP4-C
BI	CHILLER4	CHP4-S
BI	CHILLER4	CHP4-TRP
BI	CHILLER4	CH4-FLT
BI	CHILLER4	CH4E-OPN
BI	CHILLER4	CH4E-CLS
BI	CHILLER4	CH4C-OPN
BI	CHILLER4	CH4C-CLS
AI	CHILLER4	CH4R-F
AI	CHILLER4	CH4CTR-F
AI	CHILLER4	CH4S-T
AI	CHILLER4	CH4R-T
AI	CHILLER4	CH4CTS-T
AI	CHILLER4	CH4CTR-T
AD	CHILLER4	CH4_LOAD
AD	CHILLER4	CH4_CDLD
BI	CHILLER4	GEN-STS
BI	CHILLER4	LOAD-SH

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	CHILLER4	LD-RST
JCB	CHILLER4	CH4-GEN
MC	CHILLER4	ALM-DIS
SLAVE		
SLAVE		
BD	CHILLER3	CH3SYSEN
AI	CHILLER3	CH3S-T
AI	CHILLER3	CH3R-T
BD	CHILLER3	CH3-C
BI	CHILLER3	CH3-S
BI	CHILLER3	CH3-FLT
BI	CHILLER3	CH3-ALM
BI	CHILLER3	CH3E-OPN
BI	CHILLER3	CH3C-OPN
BO	CHILLER3	CHP3-C
BI	CHILLER3	CHP3-S
BI	CHILLER3	CHP3-TRP
AI	CHILLER3	CH3CTS-T
AI	CHILLER3	CH3CTR-T
AI	CHILLER3	CH3CTR-F
AD	CHILLER3	CH3_CDLD
AI	CHILLER3	CH3R-F
AD	CHILLER3	CH3_LOAD
BO	CHILLER3	GEN3_ENA
MC	CHILLER3	Alm-Dis
SLAVE		
SLAVE		
AD	CW-DP	MER21-DP
AD	CW-DP	MER36-DP
AD	CW-DP	MER52-DP
AD	CW-DP	MER54-DP
AD	CW-DP	MER55-DP
AD	CW-DP	MER58-DP
AD	CW-DP	MER63-DP
AD	CW-DP	BLDG1-DP
AD	CW-DP	CWDP-LOW
AD	DP-4	Freq-Act

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	DP-4	Speed
AD	DP-4	Current
AD	DP-4	Energy
AD	HWP-3	Freq-Act
AD	HWP-3	Speed
AD	HWP-3	Current
AD	HWP-3	Energy
AD	HWP-2	Freq-Act
AD	HWP-2	Speed
AD	HWP-2	Current
AD	HWP-2	Energy
AD	HWP-1	Freq-Act
AD	HWP-1	Speed
AD	HWP-1	Current
AD	HWP-1	Energy
AD	DP-3	Freq-Act
AD	DP-3	Speed
AD	DP-3	Current
AD	DP-3	Energy
AD	DP-2	Freq-Act
AD	DP-2	Speed
AD	DP-2	Current
AD	DP-2	Energy
AD	DP-1	Freq-Act
AD	DP-1	SPEED
AD	DP-1	CURRENT
AD	DP-1	Energy
BO	CHL4AINT	CHLR-SS
BI	CHL4AINT	CHLR_STA
BI	CHL4AINT	COND_FLO
BI	CHL4AINT	CHLW_FLO
AOS	CHL4AINT	CHLW_SP
AOS	CHL4AINT	DEML_SP
AI	CHL4AINT	LEAVING
AI	CHL4AINT	RETURN
AI	CHL4AINT	LV_CDWT
AI	CHL4AINT	RT_CDWT

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	CHL4AINT	PCT_RLA
AI	CHL4AINT	EVAPRESS
AI	CHL4AINT	CONDPRES
AI	CHL4AINT	COMPRESS
AI	CHL4AINT	EVAPTEMP
AI	CHL4AINT	CONDTEMP
AI	CHL4AINT	OILTEMP
AI	CHL4AINT	OILPRESS
BI	CHL4AINT	MRST_ALM
BI	CHL4AINT	ARST_ALM
MC	CHL4AINT	CHL4A-MC
SLAVE		
AD	CHLR2INT	LEAVINGE
AD	CHLR2INT	ENTRINGE
AD	CHLR2INT	FULLLOAD
AD	CHLR2INT	CHWS_SET
BD	CHLR2INT	VALVES
AD	CHLR2INT	RECYCLTM
AD	CHLR2INT	RUNTIME
AD	CHLR2INT	NO_START
AD	CHLR2INT	SAFETY
AD	CHLR2INT	OPRATION
BD	CHLR2INT	COMPRESS
AD	CHLR2INT	OIL_TEMP
AD	CHLR2INT	OILPRDP
BD	CHLR2INT	VENT
AD	CHLR2INT	PURGEPRE
BD	CHLR2INT	STARTER
BD	CHLR2INT	FLWSWTCH
AD	CHLR2INT	EVAP_SAT
AD	CHLR2INT	EVAPRESS
AD	CHLR2INT	DISCTEMP
AD	CHLR2INT	LEAVINGC
AD	CHLR2INT	COND_SAT
AD	CHLR2INT	ENTRINGC
AD	CHLR2INT	CONDPRES
AD	CHLR2INT	CURR_LIM

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	CHLR2INT	KEY_POSI
AD	CHLR2INT	CYCLING
CS	CHLR2INT	CS_MODEL
BD	CHLR2INT	CHLR_SS
MC	CHLR2INT	CHLR2-MC
SLAVE		
SLAVE		
BD	CHILLERS	STRT_LAG
AD	CHILLERS	STRT_SET
AD	CHILLERS	CWBYP-R
BD	CHILLERS	STOP_LAG
AD	CHILLERS	STOP_SET
AD	CHILLERS	CWBYP-FW
BD	CHILLERS	CHLR1_ST
AD	CHILLERS	CHLR1_RT
BD	CHILLERS	CHLR2_ST
AD	CHILLERS	CHLR2_RT
BD	CHILLERS	CHLR3_ST
AD	CHILLERS	CHLR3_RT
JCB	CHILLERS	LAGSSGPL
BD	CHILLERS	CHLR4_ST
AD	CHILLERS	CHLR4_RT
JCB	CHILLERS	RUNTMGPL
BI	CHL4BINT	CHLR_STA
BI	CHL4BINT	COND_FLO
BI	CHL4BINT	CHLW_FLO
AI	CHL4BINT	LEAVING
AI	CHL4BINT	RETURN
AI	CHL4BINT	LV_CDWT
AI	CHL4BINT	RT_CDWT
AI	CHL4BINT	PCT_RLA
AI	CHL4BINT	EVAPRESS
AI	CHL4BINT	CONDPRES
AI	CHL4BINT	COMPRESS
AI	CHL4BINT	EVAPTEMP
AI	CHL4BINT	CONDTEMP
AI	CHL4BINT	OILTEMP

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	CHL4BINT	OILPRESS
BI	CHL4BINT	MRST_ALM
BI	CHL4BINT	ARST_ALM
AI	DOM_HWS	TPV1-T
AI	DOM_HWS	TPV2-T
AI	DOM_HWS	TPV3-T
AD	CHLR1INT	LEAVINGE
AD	CHLR1INT	ENTERNGE
AD	CHLR1INT	FULLLOAD
AD	CHLR1INT	CHWS_SET
BD	CHLR1INT	VALVES
AD	CHLR1INT	RECYCLTM
AD	CHLR1INT	RUNTIME
AD	CHLR1INT	NO_START
AD	CHLR1INT	SAFETY
AD	CHLR1INT	OPRATION
BD	CHLR1INT	COMPRESS
AD	CHLR1INT	OIL_TEMP
AD	CHLR1INT	OILPRDRP
BD	CHLR1INT	VENT
AD	CHLR1INT	PURGEPRE
BD	CHLR1INT	STARTER
BD	CHLR1INT	FLWSWTCH
AD	CHLR1INT	EVAP_SAT
AD	CHLR1INT	EVAPRESS
AD	CHLR1INT	DISCHTMP
AD	CHLR1INT	ENTERNGC
AD	CHLR1INT	LEAVINGC
AD	CHLR1INT	COND_SAT
AD	CHLR1INT	CONDPRES
AD	CHLR1INT	CURR_LIM
AD	CHLR1INT	KEY_POSI
AD	CHLR1INT	CYCLING
CS	CHLR1INT	CS_MODEL
BD	CHLR1INT	CHLR_SS
JCB	JCB-NC20	LOADSHED
JCB	JCB-NC20	HWDP-LOW

DRAFT

	Building 3	
Point	**Equipment**	**Type**
JCB	JCB-NC20	CWDP-LOW
AD	CHLR3INT	LEAVINGE
AD	CHLR3INT	ENTRINGE
AD	CHLR3INT	FULLLOAD
AD	CHLR3INT	CHWS_SET
BD	CHLR3INT	VALVES
AD	CHLR3INT	RECYCLTM
AD	CHLR3INT	RUNTIME
AD	CHLR3INT	NO_STRTS
AD	CHLR3INT	SAFETY
AD	CHLR3INT	OPRATION
BD	CHLR3INT	COMPRESS
AD	CHLR3INT	OIL_TEMP
AD	CHLR3INT	OILPRDP
BD	CHLR3INT	VENT
AD	CHLR3INT	PURGEPRE
BD	CHLR3INT	STARTER
BD	CHLR3INT	FLWSWTCH
AD	CHLR3INT	EVAP_SAT
AD	CHLR3INT	EVAPPRES
AD	CHLR3INT	DISCTEMP
AD	CHLR3INT	LEAVINGC
AD	CHLR3INT	COND_SAT
AD	CHLR3INT	ENTRINGC
AD	CHLR3INT	CONDPRES
AD	CHLR3INT	CURR_LIM
AD	CHLR3INT	KEY_POSI
AD	CHLR3INT	CYCLING
CS	CHLR3INT	CS_MODEL
BD	CHLR3INT	CHLR_SS
AI	MAINHWLP	HWS-T
AI	MAINHWLP	HWR-T
BD	MAINHWLP	HWS_ENAB
AD	MAINHWLP	AVG_PRES
AI	MAINHWLP	1FREQ_HZ
AI	MAINHWLP	2FREQ-HZ
AI	MAINHWLP	3FREQ-HZ

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	MAINHWLP	HWPD-C
AD	MAINHWLP	HWS_LOAD
AI	MAINHWLP	HWSTM-F
BI	MAINHWLP	HWP-TRB
BI	MAINHWLP	HWP1-FLT
BI	MAINHWLP	HWP2-FLT
BI	MAINHWLP	HWP3-FLT
AI	MAINHWLP	HWR-F
JCB	MAINHWLP	HWPMPGPL
JCB	MAINHWLP	TONS_GPL
BO	MAINHWLP	VFD1-EN
BO	MAINHWLP	VFD2-EN
BO	MAINHWLP	VFD3-EN
BO	MAINHWLP	HWSYS-EN
BD	MAINHWLP	HWP1-ST
BD	MAINHWLP	HWP2-ST
BD	MAINHWLP	HWP3-ST
AOS	MAINHWLP	HWP-VFD
JCB	MAINHWLP	AVG-HWP
JCB	MainHwlp	Hwtr-Pro
AD	MAINHWLP	SYS_PRES
AOS	MAINHWLP	VFD1-FBK
AOS	MAINHWLP	VFD2-FBK
AOS	MAINHWLP	VFD3-FBK
BD	CHILLER2	CH2SYSEN
AD	CHILLER2	CH2S-T
AI	CHILLER2	CH2R-T
BD	CHILLER2	CH2-C
BI	CHILLER2	CH2-S
BI	CHILLER2	CH2-FLT
BI	CHILLER2	CH2-ALM
BI	CHILLER2	CH2E-OPN
BI	CHILLER2	CH2C-OPN
BO	CHILLER2	CHP2-C
BI	CHILLER2	CHP2-S
BI	CHILLER2	CHP2-TRP
AI	CHILLER2	CH2CTS-T

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	CHILLER2	CH2CTR-T
AI	CHILLER2	CH2CTR-F
AD	CHILLER2	CH2_CDLD
AI	CHILLER2	CH2R-F
AD	CHILLER2	CH2_LOAD
BO	CHILLER2	GEN2_ENA
MC	CHILLER2	CHL-ALM
MC	CHILLER2	ALM-DIS
SLAVE		
SLAVE		
AD	CHILLER2	CH2S-T2

	Building 104	
Point	**Equipment**	**Type**
	NC-7	**network controller**
NC-07-HW	VAV-1-4	7, 1, 3, VAV
NC-07-HW	VAV-1-5	8, 1, 3, VAV
NC-07-HW	VAV-1-1	11, 1, 3, VAV
NC-07-HW	VAV-1-2	12, 1, 3, VAV
NC-07-HW	VAV-1-3	13, 1, 3, VAV
NC-07-HW	VAV-4-1	14, 1, 3, VAV
NC-07-HW	VAV-4-2	15, 1, 3, VAV
NC-07-HW	VAV-4-3	16, 1, 3, VAV
NC-07-HW	VAV-4-4	17, 1, 3, VAV
NC-07-HW	VAV-4-A	60, 1, 3, VAV
NC-07-HW	VAV-1-9	20, 1, 3, VAV
NC-07-HW	VAV-1-10	21, 1, 3, VAV
NC-07-HW	VAV-2-1	22, 1, 3, VAV
NC-07-HW	VAV-2-2	23, 1, 3, VAV
NC-07-HW	VAV-1-6	24, 1, 3, VAV
NC-07-HW	VAV-1-7	25, 1, 3, VAV
NC-07-HW	VAV-1-8	26, 1, 3, VAV
NC-07-HW	VAV-3-1	27, 1, 3, VAV
NC-07-HW	VAV-3-2	28, 1, 3, VAV
NC-07-HW	VAV-3-3	29, 1, 3, VAV
NC-07-HW	VAV-3-4	30, 1, 3, VAV
NC-07-HW	VAV-4-5	31, 1, 3, VAV

DRAFT

	Building 3	
Point	**Equipment**	**Type**
NC-07-HW	VAV-4-6	32, 1, 3, VAV
NC-07-HW	VAV-4-7	33, 1, 3, VAV
NC-07-HW	VAV-4-8	34, 1, 3, VAV
NC-07-HW	VAV-1-14	35, 1, 3, VAV
NC-07-HW	VAV-1-15	36, 1, 3, VAV
NC-07-HW	VAV-2-3	37, 1, 3, VAV
NC-07-HW	VAV-2-4	38, 1, 3, VAV
NC-07-HW	VAV-2-5	39, 1, 3, VAV
NC-07-HW	VAV-2-6	40, 1, 3, VAV
NC-07-HW	VAV-1-11	41, 1, 3, VAV
NC-07-HW	VAV-1-12	42, 1, 3, VAV
NC-07-HW	VAV-1-13	43, 1, 3, VAV
NC-07-HW	VAV-3-5	44, 1, 3, VAV
NC-07-HW	VAV-3-6	45, 1, 3, VAV
NC-07-HW	VAV-3-7	46, 1, 3, VAV
NC-07-HW	VAV-3-8	47, 1, 3, VAV
NC-07-HW	VAV-4-9	48, 1, 3, VAV
NC-07-HW	VAV-4-10	49, 1, 3, VAV
NC-07-HW	VAV-4-11	50, 1, 3, VAV
NC-07-HW	VAV-4-12	51, 1, 3, VAV
NC-07-HW	AHU-05	5, 1, 3, UNT
NC-07-HW	AHU-07	10, 1, 3, UNT
NC-07-HW	AHU-06	9, 1, 3, UNT
NC-07-HW	AHU-10	6, 1, 3, UNT
NC-07-HW	RTU-03	54, 1, 3, DX9100
NC-07-HW	Mech_RmDX	1, 1, 3, DX9100
NC-07-HW	RTU-04	55, 1, 3, DX9100
NC-07-HW	RTU-02	53, 1, 3, DX9100
NC-07-HW	RTU-01	52, 1, 3, DX9100
NC-07-HW	XT1	2, 1, 3, XT9100
NC-07-HW	XT2	3, 1, 3, XT9100
NC-07-HW	XT3	4, 1, 3, XT9100
NC-07-HW	DX61	61, 1, 3, DX9100
NC-07-HW	SEC_VFD	62, 1, 3, VND
BD	RTU-03	Supply Fan S/S Feedback
BI	RTU-03	B-104 RTU #3 Sply Fan
AD	RTU-03	Calculated Disch. STPT
AI	RTU-03	B-104 RTU #3 Disch. Air
AI	RTU-03	Return Air Temp
AI	RTU-03	Mixed Air Temp
AD	RTU-03	Cooling Valve Feedback
AD	RTU-03	Heating Valve Feedback
AD	RTU-03	OA Damper Feedback
AD	RTU-03	Supply Fan Signal Fedbck
BI	RTU-03	Supply Air Smoke Detect
BI	RTU-03	Return Air Smoke Detect

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BI	RTU-03	Low Limit Alarm
BI	RTU-03	High Pressure Alarm
AI	RTU-03	2nd Flr Static Pressure
AI	RTU-03	3rd Flr Static Pressure
AD	RTU-03	Static Pressure STPT
AD	RTU-03	Optimized Heating Setpnt
AD	RTU-03	1=Off 2=On 3=Idle
AD	RTU-03	Optimin Deadband in Min
AD	RTU-03	Minimum Preheat Time
AD	RTU-03	Optimin Constant
AD	RTU-03	Maximum Preheat Time
AD	RTU-03	OutsideAir Temperature
BD	RTU-03	Warm-Up BD
BO	RTU-03	OCC
JCB process	RTU-03	OPTZ-GPL
JCB process	RTU-03	WARM_GPL
BO	RTU-02	Unoccupied Occupied BO
BD	RTU-02	Supply Fan Com Feeback
BI	RTU-02	B-104 RTU #2 Sply Fan
AD	RTU-02	Discharge Air Setpoint
AI	RTU-02	B-104 RTU #2 Disch. Air
AI	RTU-02	Return Air Temp
AI	RTU-02	Mixed Air Temp
AD	RTU-02	Cooling Valve Feedback
AD	RTU-02	Heating Valve Feedback
AD	RTU-02	O.A.Damper Feedback
AD	RTU-02	Supply Fan Feedback
BI	RTU-02	Supply Air Smoke Detect
BI	RTU-02	Return Air Smoke Detect
BI	RTU-02	Low Limit Alarm
BI	RTU-02	High Pressure Alarm
AI	RTU-02	3rd Flr Static Pressure
AI	RTU-02	2nd Flr Static Pressure
AD	RTU-02	Static Pressure Setpoint
AD	RTU-02	OutsideAir Temperature
AD	RTU-02	Optimized Heating Setpnt
AD	RTU-02	1=Off 2=On 3=Idle
AD	RTU-02	Optimin Deadband in Min
AD	RTU-02	Minimum Preheat Time
AD	RTU-02	Optimin Constant
AD	RTU-02	Maximum Preheat Time
JCB process	RTU-02	OPTZ-GPL
AD	RTU-02	SP_STPT
BD	RTU-02	WARM-UP
JCB process	RTU-02	WARM_GPL
CS	VAV 3-1 CS-Object	

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	VAV 3-2 CS-Object	
CS	VAV 3-3 CS-Object	
CS	VAV 3-4 CS-Object	
CS	VAV 3-5 CS-Object	
CS	VAV 3-6 CS-Object	
CS	VAV 3-7 CS-Object	
CS	VAV 3-8 CS-Object	
CS	AHU-07	Air Handling Unit 7
CS	RTU-03	RTU-03
CS	AHU-06	Air Handler Unit
AD	CHILLERS	B-104 Main Chl Wtr Sply
AD	CHILLERS	B-104 Main Chl Wtr Rtrn
BO	CHILLERS	Lead Chiller Selector
BD	CHILLERS	CHILLER #1
AD	CHILLERS	B-104 #1 Chl Wtr Sply
AD	CHILLERS	B-104 #1 Chl Wtr Rtrn
BO	CHILLERS	Chllr #1 Command (West)
BI	CHILLERS	B-104 Compr #1 Status
BI	CHILLERS	B-104 Compr #2 Status
BD	CHILLERS	Chiller #1 Alarm
BD	CHILLERS	B-104 Chiller #1 Alarm
BD	CHILLERS	CHILLER #2
AD	CHILLERS	B-104 #2 Chl Wtr Sply
AD	CHILLERS	B-104 #2 Chl Wtr Rtrn
BO	CHILLERS	Chllr #2 Command (East)
BI	CHILLERS	B-104 Compr #1 Status
BI	CHILLERS	B-104 Compr #2 Status
BD	CHILLERS	Chiller #2 Alarm
BD	CHILLERS	B-104 Chiller #2 Alarm
BD	CHILLERS	CHILLER #3
AD	CHILLERS	B-104 #3 Chl Wtr Sply
AD	CHILLERS	B-104 #3 Chl Wtr Rtrn
BO	CHILLERS	Chllr #3 Command (Centr)
BI	CHILLERS	B-104 Compr #1 Status
BI	CHILLERS	B-104 Compr #2 Status
BD	CHILLERS	B-104 Chiller #3 Alarm
BD	CHILLERS	Chiller #3 Alarm
BO	CHILLERS	ChillWaterSystemShutdown
AD	CHILLERS	Max Chill Water Valve
AD	CHILLERS	Stdby Enable GPM Setpont
AD	CHILLERS	Stdby Disable GPM Setpnt
AD	CHILLERS	Main Chl Wtr Flow
AD	CHILLERS	Lag Enable GPM Setpoint
AD	CHILLERS	Lag Disable GPM Setpoint
JCB	CHILLERS	CHAR-GPL
BO	RM_303	Occupied \Unoccupied

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	RM_303	Zone Tempeture
AD	RM_303	Heating Setpoint
AD	RM_303	Actual Supply CFM
AD	RM_303	Act.CFM Setpoint
AD	RM_303	Damper Command
BI	RM_303	Supply Fan Status
BO	RM_303	Supply Fan Command
AI	RM_303	Discharge Air Tempeture
AD	RM_303	Heating Valve Command
BO	RM_320	Occupied \Unoccupied
AI	RM_320	Zone Tempeture
AD	RM_320	Heating Setpoint
AD	RM_320	Actual Supply CFM
AD	RM_320	Act.CFM Setpoint
AD	RM_320	Damper Command
BI	RM_320	Supply Fan Status
BO	RM_320	Supply Fan Command
AI	RM_320	Discharge Air Tempeture
AD	RM_320	Heating Valve Command
BO	RM_321	Occupied \Unoccupied
AI	RM_321	Zone Tempeture
AD	RM_321	Heating Setpoint
AD	RM_321	Actual Supply CFM
AD	RM_321	Act.CFM Setpoint
AD	RM_321	Damper Command
BI	RM_321	Supply Fan Status
BO	RM_321	Supply Fan Command
AI	RM_321	Discharge Air Tempeture
AD	RM_321	Heating Valve Command
BO	RM_203	Occupied \Unoccupied
AI	RM_203	Zone Tempeture
AD	RM_203	Heating Setpoint
AD	RM_203	Actual Supply CFM
AD	RM_203	Act.CFM Setpoint
AD	RM_203	Damper Command
BI	RM_203	Supply Fan Status
BO	RM_203	Supply Fan Command
AI	RM_203	Discharge Air Tempeture
AD	RM_203	Heating Valve Command
BO	RM_220	Occupied \Unoccupied
AI	RM_220	Zone Tempeture
AD	RM_220	Heating Setpoint
AD	RM_220	Actual Supply CFM
AD	RM_220	Act.CFM Setpoint
AD	RM_220	Damper Command
BI	RM_220	Supply Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	RM_220	Supply Fan Command
AI	RM_220	Discharge Air Tempeture
AD	RM_220	Heating Valve Command
BO	RM_101	Occupied \Unoccupied
AI	RM_101	Zone Temperature
AD	RM_101	Heating Setpoint
AD	RM_101	Actual Supply CFM
AD	RM_101	Act.CFM Setpoint
AD	RM_101	Damper Command
BI	RM_101	Supply Fan Status
BO	RM_101	Supply Fan Command
AI	RM_101	Discharge Air Tempeture
AD	RM_101	Heating Valve Command
BO	RM_114	Occupied \Unoccupied
AI	RM_114	Zone Temperature
AD	RM_114	Heating Setpoint
AD	RM_114	Actual Supply CFM
AD	RM_114	Act.CFM Setpoint
AD	RM_114	Damper Command
BI	RM_114	Supply Fan Status
BO	RM_114	Supply Fan Command
AI	RM_114	Discharge Air Tempeture
AD	RM_114	Heating Valve Command
BO	RM_115	Occupied \Unoccupied
AI	RM_115	Zone Temperature
AD	RM_115	Heating Setpoint
AD	RM_115	Actual Supply CFM
AD	RM_115	Act.CFM Setpoint
AD	RM_115	Damper Command
BI	RM_115	Supply Fan Status
BO	RM_115	Supply Fan Command
AI	RM_115	Discharge Air Tempeture
AD	RM_115	Heating Valve Command
BO	RM_113A	Occupied \Unoccupied
AI	RM_113A	Zone Temperature
AD	RM_113A	Heating Setpoint
AD	RM_113A	Actual Supply CFM
AD	RM_113A	Act.CFM Setpoint
AD	RM_113A	Damper Command
BI	RM_113A	Supply Fan Status
BO	RM_113A	Supply Fan Command
AI	RM_113A	Discharge Air Tempeture
AD	RM_113A	Heating Valve Command
BO	RM_113	Occupied \Unoccupied
AI	RM_113	Zone Temperature
AD	RM_113	Cooling Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	RM_113	Actual Supply CFM
AD	RM_113	Act.CFM Setpoint
AD	RM_113	Damper Command
BI	RM_113	Supply Fan Status
BO	RM_113	Supply Fan Command
AI	RM_113	Discharge Air Tempeture
AD	RM_113	Heating Valve Command
BO	RM_127	Occupied \Unoccupied
AI	RM_127	Zone Temperature
AD	RM_127	Heating Setpoint
AD	RM_127	Actual Supply CFM
AD	RM_127	Act.CFM Setpoint
AD	RM_127	Damper Command
BI	RM_127	Supply Fan Status
BO	RM_127	Supply Fan Command
AI	RM_127	Discharge Air Tempeture
AD	RM_127	Heating Valve Command
BO	RM_231	Occupied \Unoccupied
AI	RM_231	Zone Tempeture
AD	RM_231	Heating Setpoint
AD	RM_231	Actual Supply CFM
AD	RM_231	Act.CFM Setpoint
AD	RM_231	Damper Command
BI	RM_231	Supply Fan Status
BO	RM_231	Supply Fan Command
AI	RM_231	Discharge Air Tempeture
AD	RM_231	Heating Valve Command
BO	RM_341	Occupied \Unoccupied
AI	RM_341	Zone Tempeture
AD	RM_341	Heating Setpoint
AD	RM_341	Actual Supply CFM
AD	RM_341	Act.CFM Setpoint
AD	RM_341	Damper Command
BI	RM_341	Supply Fan Status
BO	RM_341	Supply Fan Command
AI	RM_341	Discharge Air Tempeture
AD	RM_341	Heating Valve Command
BO	RM_331	Occupied \Unoccupied
AI	RM_331	Zone Tempeture
AD	RM_331	Heating Setpoint
AD	RM_331	Actual Supply CFM
AD	RM_331	Act.CFM Setpoint
AD	RM_331	Damper Command
BI	RM_331	Supply Fan Status
BO	RM_331	Supply Fan Command
AI	RM_331	Discharge Air Tempeture

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	RM_331	Heating Valve Command
BO	RM_237	Occupied \Unoccupied
AI	RM_237	Zone Tempeture
AD	RM_237	Heating Setpoint
AD	RM_237	Actual Supply CFM
AD	RM_237	Act.CFM Setpoint
AD	RM_237	Damper Command
BI	RM_237	Supply Fan Status
BO	RM_237	Supply Fan Command
AI	RM_237	Discharge Air Tempeture
AD	RM_237	Heating Valve Command
BO	RM_225	Occupied \Unoccupied
AI	RM_225	Zone Tempeture
AD	RM_225	Cooling Setpoint
AD	RM_225	Actual Supply CFM
AD	RM_225	Act.CFM Setpoint
AD	RM_225	Damper Command
BI	RM_225	Supply Fan Status
BO	RM_225	Supply Fan Command
AI	RM_225	Discharge Air Tempeture
AD	RM_225	Heating Valve Command
BO	RM_227	Occupied \Unoccupied
AI	RM_227	Zone Tempeture
AD	RM_227	Heating Setpoint
AD	RM_227	Actual Supply CFM
AD	RM_227	Act.CFM Setpoint
AD	RM_227	Damper Command
BI	RM_227	Supply Fan Status
BO	RM_227	Supply Fan Command
AI	RM_227	Discharge Air Tempeture
AD	RM_227	Heating Valve Command
BO	RM_228	Occupied \Unoccupied
AI	RM_228	Zone Tempeture
AD	RM_228	Heating Setpoint
AD	RM_228	Actual Supply CFM
AD	RM_228	Act.CFM Setpoint
AD	RM_228	Damper Command
BI	RM_228	Supply Fan Status
BO	RM_228	Supply Fan Command
AI	RM_228	Discharge Air Tempeture
AD	RM_228	Heating Valve Command
BO	RM_116	Occupied \Unoccupied
AI	RM_116	Zone Temperature
AD	RM_116	Heating Setpoint
AD	RM_116	Actual Supply CFM
AD	RM_116	Act.CFM Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	RM_116	Damper Command
BI	RM_116	Supply Fan Status
BO	RM_116	Supply Fan Command
AI	RM_116	Discharge Air Tempeture
AD	RM_116	Heating Valve Command
BO	RM_351	Occupied \Unoccupied
AI	RM_351	Zone Tempeture
AD	RM_351	Heating Setpoint
AD	RM_351	Actual Supply CFM
AD	RM_351	Act.CFM Setpoint
AD	RM_351	Damper Command
BI	RM_351	Supply Fan Status
BO	RM_351	Supply Fan Command
AI	RM_351	Discharge Air Tempeture
AD	RM_351	Heatimg Valve Command
BO	RM_323	Occupied \Unoccupied
AI	RM_323	Zone Tempeture
AD	RM_323	Heating Setpoint
AD	RM_323	Actual Supply CFM
AD	RM_323	Act.CFM Setpoint
AD	RM_323	Damper Command
BI	RM_323	Supply Fan Status
BO	RM_323	Supply Fan Command
AI	RM_323	Discharge Air Tempeture
AD	RM_323	Heating Valve Command
BO	RM_325A	Occupied \Unoccupied
AI	RM_325A	Zone Tempeture
AD	RM_325A	Heating Setpoint
AD	RM_325A	Actual Supply CFM
AD	RM_325A	Act.CFM Setpoint
AD	RM_325A	Damper Command
BI	RM_325A	Supply Fan Status
BO	RM_325A	Supply Fan Command
AI	RM_325A	Discharge Air Tempeture
AD	RM_325A	Heating Valve Command
BO	RM_324	Occupied \Unoccupied
AI	RM_324	Zone Tempeture
AD	RM_324	Heating Setpoint
AD	RM_324	Actual Supply CFM
AD	RM_324	Act.CFM Setpoint
AD	RM_324	Damper Command
BI	RM_324	Supply Fan Status
BO	RM_324	Supply Fan Command
AI	RM_324	Discharge Air Tempeture
AD	RM_324	Heating Valve Command
BO	RM_326	Occupied \Unoccupied

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	RM_326	Zone Tempeture
AD	RM_326	Heating Setpoint
AD	RM_326	Actual Supply CFM
AD	RM_326	Act.CFM Setpoint
AD	RM_326	Damper Command
BI	RM_326	Supply Fan Status
BO	RM_326	Supply Fan Command
AI	RM_326	Discharge Air Tempeture
AD	RM_326	Heating Valve Command
BO	RM_201	Occupied \Unoccupied
AI	RM_201	Zone Tempeture
AD	RM_201	Heating Setpoint
AD	RM_201	Actual Supply CFM
AD	RM_201	Act.CFM Setpoint
AD	RM_201	Damper Command
BI	RM_201	Supply Fan Status
BO	RM_201	Supply Fan Command
AI	RM_201	Discharge Air Tempeture
AD	RM_201	Heating Valve Command
BO	RM_322	Occupied \Unoccupied
AI	RM_322	Zone Tempeture
AD	RM_322	Cooling Setpoint
AD	RM_322	Actual Supply CFM
AD	RM_322	Act.CFM Setpoint
AD	RM_322	Damper Command
BI	RM_322	Supply Fan Status
BO	RM_322	Supply Fan Command
AI	RM_322	Discharge Air Tempeture
AD	RM_322	Heating Valve Command
BO	RM_300	Occupied \Unoccupied
AI	RM_300	Zone Tempeture
AD	RM_300	Heating Setpoint
AD	RM_300	Actual Supply CFM
AD	RM_300	Act.CFM Setpoint
AD	RM_300	Damper Command
BI	RM_300	Supply Fan Status
BO	RM_300	Supply Fan Command
AI	RM_300	Discharge Air Tempeture
AD	RM_300	Heating Valve Command
BO	RM_226	Occupied \Unoccupied
AI	RM_226	Zone Tempeture
AD	RM_226	Heating Setpoint
AD	RM_226	Actual Supply CFM
AD	RM_226	Act.CFM Setpoint
AD	RM_226	Damper Command
BI	RM_226	Supply Fan Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	RM_226	Supply Fan Command
AI	RM_226	Discharge Air Tempeture
AD	RM_226	Heating Valve Command
BO	RM_328	Occupied \Unoccupied
AI	RM_328	Zone Tempeture
AD	RM_328	Heating Setpoint
AD	RM_328	Actual Supply CFM
AD	RM_328	Act.CFM Setpoint
AD	RM_328	Damper Command
BI	RM_328	Supply Fan Status
BO	RM_328	Supply Fan Command
AI	RM_328	Discharge Air Tempeture
AD	RM_328	Heating Valve Command
BO	RM_224	Occupied \Unoccupied
AI	RM_224	Zone Tempeture
AD	RM_224	Heating Setpoint
AD	RM_224	Actual Supply CFM
AD	RM_224	Act.CFM Setpoint
AD	RM_224	Damper Command
BI	RM_224	Supply Fan Status
BO	RM_224	Supply Fan Command
AI	RM_224	Discharge Air Tempeture
AD	RM_224	Heating Valve Command
BO	RM_111	Occupied \Unoccupied
AI	RM_111	Zone Temperature
AD	RM_111	Heating Setpoint
AD	RM_111	Actual Supply CFM
AD	RM_111	Act.CFM Setpoint
AD	RM_111	Damper Command
BI	RM_111	Supply Fan Status
BO	RM_111	Supply Fan Command
AI	RM_111	Discharge Air Tempeture
AD	RM_111	Heating Valve Command
BO	RM_109	Occupied \Unoccupied
AI	RM_109	Zone Temperature
AD	RM_109	Heating Setpoint
AD	RM_109	Actual Supply CFM
AD	RM_109	Act.CFM Setpoint
AD	RM_109	Damper Command
BI	RM_109	Supply Fan Status
BO	RM_109	Supply Fan Command
AI	RM_109	Discharge Air Tempeture
AD	RM_109	Heating Valve Command
BO	RM_223	Occupied \Unoccupied
AI	RM_223	Zone Tempeture
AD	RM_223	Heating Setpoint

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AD	RM_223	Actual Supply CFM
AD	RM_223	Act.CFM Setpoint
AD	RM_223	Damper Command
BI	RM_223	Supply Fan Status
BO	RM_223	Supply Fan Command
AI	RM_223	Discharge Air Tempeture
AD	RM_223	Heating Valve Command
BO	RM_222	Occupied \Unoccupied
AI	RM_222	Zone Tempeture
AD	RM_222	Heating Setpoint
AD	RM_222	Actual Supply CFM
AD	RM_222	Act.CFM Setpoint
AD	RM_222	Damper Command
BI	RM_222	Supply Fan Status
BO	RM_222	Supply Fan Command
AI	RM_222	Discharge Air Tempeture
AD	RM_222	Heating Valve Command
BO	RM_250	Occupied \Unoccupied
AI	RM_250	Zone Tempeture
AD	RM_250	Heating Setpoint
AD	RM_250	Actual Supply CFM
AD	RM_250	Act.CFM Setpoint
AD	RM_250	Damper Command
BI	RM_250	Supply Fan Status
BO	RM_250	Supply Fan Command
AI	RM_250	Discharge Air Tempeture
AD	RM_250	Heating Valve Command
BO	AHU-05	Occupied Unoccupied
AI	AHU-05	Zone Temp
BI	AHU-05	Supply Fan Status
BI	AHU-05	Supply Smoke Detector
BO	AHU_10	Occupied \Unoccupied
AI	AHU_10	Zone Tempeture
AI	AHU_10	Zone Setpoint
AI	AHU_10	Discharge Air Tempeture
BD	AHU_10	Cooling Command
BD	AHU_10	Heating Command
BD	AHU_10	Supply Fan Command
BI	AHU_10	Supply Fan Status
BO	AHU_07	Occupied \Unoccupied
AI	AHU_07	Zone Temp
AD	AHU_07	Room Heating Setpoint
AD	AHU_07	Room Cooling Setpoint
AI	AHU_07	Discharge Air Temp
BO	AHU_07	Cooling Command
BO	AHU_07	Heating Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	AHU_07	Supply Fan Command
BI	AHU_07	Supply Fan Status
BO	RM_112	Occupied \Unoccupied
AI	RM_112	Zone Temperature
AD	RM_112	Zone Setpoint
AD	RM_112	Supply CFM
AD	RM_112	Supply CFM Setpoint
AD	RM_112	Damper Command
AI	RM_112	Discharge Air Tempeture
BI	RM_112	Supply Fan Status
BO	RM_112	Supply Fan Command
AD	RM_112	Heating Valve Command
BO	RM_241	Occupied \Unoccupied
AI	RM_241	Zone Tempeture
AD	RM_241	Heating Setpoint
AD	RM_241	Actual Supply CFM
AD	RM_241	Act.CFM Setpoint
AD	RM_241	Damper Command
BI	RM_241	Supply Fan Status
BO	RM_241	Supply Fan Command
AI	RM_241	Discharge Air Tempeture
AD	RM_241	Heating Valve Command
BO	RM_337	Occupied \Unoccupied
AI	RM_337	Zone Tempeture
AD	RM_337	Heating Setpoint
AD	RM_337	Actual Supply CFM
AD	RM_337	Act.CFM Setpoint
AD	RM_337	Damper Command
BI	RM_337	Supply Fan Status
BO	RM_337	Supply Fan Command
AI	RM_337	Discharge Air Tempeture
AD	RM_337	Heating Valve Command
BO	RM_345	Occupied \Unoccupied
AI	RM_345	Zone Tempeture
AD	RM_345	Heating Setpoint
AD	RM_345	Actual Supply CFM
AD	RM_345	Act.CFM Setpoint
AD	RM_345	Damper Command
BI	RM_345	Supply Fan Status
BO	RM_345	Supply Fan Command
AI	RM_345	Discharge Air Tempeture
AD	RM_345	Heating Valve Command
BO	AHU_06	Occupied \Unoccupied
AI	AHU_06	Zone Tempeture
BI	AHU_06	Supply Fan Staus
BI	AHU_06	Supply Smk Det. Status

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	RM_307	Occupied \Unoccupied
AI	RM_307	Zone Tempeture
AD	RM_307	Heating Setpoint
AD	RM_307	Actual Supply CFM
AD	RM_307	Act.CFM Setpoint
AD	RM_307	Damper Command
BI	RM_307	Supply Fan Status
BO	RM_307	Supply Fan Command
AI	RM_307	Discharge Air Tempeture
AD	RM_307	Heating Valve Command
AD	HW_CONV	Hot Water Enable Stpt
AD	HW_CONV	Hot Water Supply Temp
AD	HW_CONV	Hot Water Setpoint
AD	HW_CONV	Hot Water Return Temp
AI	HW_CONV	Outside Air Temp
AD	HW_CONV	Steam Valve Command
AD	HW_CONV	Steam Flow
CS	RM_220	VAV 2-1 CS-Object
CS	RM_203	VAV 2-2 CS-Object
CS	RM_307	VAV 2-5 CS-Object
CS	RM_321	VAV 2-3 CS-Object
CS	RM_320	VAV 2-4 CS-Object
CS	RM_303	VAV 2-6 CS-Object
CS	RTU-02	RTU-02
CS	AHU-10	AHU-10
CS	AHU-05	AHU-05
BO	RM_248	Occupied \Unoccupied
AI	RM_248	Zone Tempeture
AD	RM_248	Heating Setpoint
AD	RM_248	Actual Supply CFM
AD	RM_248	Act.CFM Setpoint
AD	RM_248	Damper Command
BI	RM_248	Supply Fan Status
BO	RM_248	Supply Fan Command
AI	RM_248	Discharge Air Tempeture
AD	RM_248	Heating Valve Command
BO	RM_327	Occupied \Unoccupied
AI	RM_327	Zone Tempeture
AD	RM_327	Heating Setpoint
AD	RM_327	Actual Supply CFM
AD	RM_327	Act.CFM Setpoint
AD	RM_327	Damper Command
BI	RM_327	Supply Fan Status
BO	RM_327	Supply Fan Command
AI	RM_327	Discharge Air Tempeture
AD	RM_327	Heating Valve Command

DRAFT

	Building 3	
Point	**Equipment**	**Type**
BO	RTU-04	Unoccupied Occupied BO
BD	RTU-04	Supply Fan S/S Feedback
BI	RTU-04	B-104 RTU #4 Sply Fan
AD	RTU-04	Caluated Discharge STPT
AI	RTU-04	B-104 RTU #4 Disch. Air
AI	RTU-04	Return Air Temp
AI	RTU-04	Mixed Air Temp
AD	RTU-04	Cooling Valve Feedback
AD	RTU-04	Heating Valve Feedback
AD	RTU-04	OA Damper Feedback
AD	RTU-04	Supply Fan Signal Fedbck
BI	RTU-04	Supply Air Smoke Detect
BI	RTU-04	Return Air Smoke Detect
BI	RTU-04	Low Limit Alarm
BI	RTU-04	High Pressure Alarm
AI	RTU-04	3rd Flr Static Pressure
AI	RTU-04	2nd Flr Static Pressure
AI	RTU-04	1st Flr Static Pressure
AD	RTU-04	Static Pressure STPT
AD	RTU-04	OutsideAir Temperature
AD	RTU-04	Optimized Heating Setpnt
AD	RTU-04	1=Off 2=On 3=Idle
AD	RTU-04	Optimin Deadband in Min
AD	RTU-04	Minimum Preheat Time
AD	RTU-04	Optimin Constant
AD	RTU-04	Maximum Preheat Time
BD	RTU-04	Warm-Up BD
JCB	RTU-04	OPTZ-GPL
JCB	RTU-04	WARM_GPL
BO	RTU-01	Unoccupied Occupied BO
BD	RTU-01	Supply Fan Com Feedback
BI	RTU-01	B-104 RTU #1 Sply Fan
AD	RTU-01	Discharge Air Setpoint
AI	RTU-01	B-104 RTU #1 Disch. Air
AI	RTU-01	Return Air Temp
AI	RTU-01	Mixed Air Temp
AD	RTU-01	Cooling Valve
AD	RTU-01	Heating Valve
AD	RTU-01	Supply Fan Feedback
AD	RTU-01	O.A.Damper Feedback
BI	RTU-01	Supply Air Smoke Detect
BI	RTU-01	Return Air Smoke Detect
BI	RTU-01	Low Limit Alarm
BI	RTU-01	High Pressure Alarm
AI	RTU-01	1st Flr Static Pressure
AI	RTU-01	2nd Flr Static Pressure

DRAFT

	Building 3	
Point	**Equipment**	**Type**
AI	RTU-01	3rd Flr Static Pressure
AD	RTU-01	Static Pressure Setpoint
AD	RTU-01	OutsideAir Temperature
AD	RTU-01	Optimized Heating Setpnt
AD	RTU-01	1=Off 2=On 3=Idle
AD	RTU-01	Optimin Deadband in Min
AD	RTU-01	Minimum Preheat Time
AD	RTU-01	Optimin Constant
AD	RTU-01	Maximum Preheat Time
BD	RTU-01	Warm-Up BD
JCB	RTU-01	OPTZ-GPL
JCB	RTU-01	WARM_GPL
BD	PUMP-S	Main Chill Wtr Pump Com
BD	PUMP-S	Main Chill Wtr Pump Sta
BD	PUMP-S	Hot Water Pump Command
BD	PUMP-S	Hot Water Pump Status
BD	PUMP-S	ACWC-1 Pump Command
BD	PUMP-S	ACWC-1 Pump Status
BD	PUMP-S	ACWC-2 Pump Command
BD	PUMP-S	ACWC-2 Pump Status
BD	PUMP-S	ACWC-3 Pump Command
BD	PUMP-S	ACWC-3 Pump Status
AOS	PUMP-S	P1 VFD Feedback
BO	PUMP-S	Sec Chw P1 Enable
JCB	Pump-S	SecChwp
CS	RM_113A	VAV 4-A CS-Object
CS	RM_113	VAV 4-1 CS-Object
CS	RM_115	VAV 4-2 CS-Object
CS	RM_127	VAV 4-3 CS-Object
CS	RM_116	VAV 4-4 CS-Object
CS	RM_225	VAV 4-5 CS-Object
CS	RM_227	VAV 4-6 CS-Object
CS	RM_250	VAV 4-7 CS-Object
CS	RM_228	VAV 4-8 CS-Object
CS	RM_325A	VAV 4-9 CS-Object
CS	RM_323	VAV 4-10 CS-Object
CS	RM_324	VAV 4-12 CS-Object
CS	RM_351	VAV 4-11 CS Object
CS	RM_328	VAV 1-11 CS-Object
CS	RM_327	VAV 1-12 CS-Object
CS	RM_112	VAV 1-1 CS-Object
CS	RM_111	VAV 1-3 CS-Object
CS	RM_109	VAV 1-4 CS-Object
CS	RM_224	VAV 1-6 CS-Object
CS	RM_223	VAV 1-7 CS-Object
CS	RM_226	VAV 1-8 CS-Object

DRAFT

	Building 3	
Point	**Equipment**	**Type**
CS	RM_326	VAV 1-13 CS-Object
CS	RM_322	VAV 1-14 CS-Object
CS	RM_300	VAV 1-15 CS-Object
CS	RM_114	VAV 1-2 CS-Object
CS	RM_101	VAV 1-5 CS-Object
CS	RM_222	VAV 1-9 CS-Object
CS	RM_201	VAV 1-10 CS-Object
CS	RTU-01	RTU-01
CS	RTU-04	RTU-04
CS	CS-VFD	CS Ach500 Sec Chwp
CS	CS-SEC	Sec Chwp CS Object
CS	104-MECH	OFFICE DX9100 1ST OD
JCB	NC-07-HW	OAT_GPL
(INTENTIOINLY LEFT BLANK) **(CONTINUES ON NEXT PAGE)**		

DRAFT

Building 249		
Point	**Equipment**	**Type**
	NC-5	Network controller
NC-05-HW	01AHU-01	AHU CONTROLLER
NC-05-HW	01UNT-02	UNT CONTROLLER
NC-05-HW	01UNT-03	UNT CONTROLLER
NC-05-HW	01UNT-04	UNT CONTROLLER
NC-05-HW	01UNT-05	UNT CONTROLLER
NC-05-HW	01UNT-06	UNT CONTROLLER
NC-05-HW	01UNT-07	UNT CONTROLLER
NC-05-HW	01UNT-08	UNT CONTROLLER
NC-05-HW	01UNT-09	UNT CONTROLLER
NC-05-HW	01UNT-10	UNT CONTROLLER
NC-05-HW	01DX-11	DX
NC-05-HW	01AHU-12	AHU CONTROLLER
NC-05-HW	01AHU-13	AHU CONTROLLER
NC-05-HW	01UNT-14	UNT CONTROLLER
NC-05-HW	01AHU-15	AHU 4 CONTROLLER
NC-05-HW	01UNT-16	FCU K CONTROLLER
NC-05-HW	01UNT-17	FCU L CONTROLLER
BO FCU_K	OCC-UNOC	Occupied \Unoccupied
AI FCU_K	ZN-T	Zone Temp
AI FCU_K	DA-T	Discharge Air Temp
BO FCU_K	CLG-VLV	Cooling Valve Command
AOS FCU_K	HTG-VLV	Heating Valve Command
AI FCU_K	ZN-H	Zone Humidity
BI FCU_K	SF-S	Supply Fan Status
BO FCU_K	SF-C	Supply Fan Command
CS FCU_K	FCU-STPT	Cooling Setpoint CS
AD	FCU-A	Zone Temp C.C. Room 100
AD	FCU-B	Zone Temp C.C Room 102
AD	FCU-C	Zone Temp C.C Room 104
AD	FCU-D	Zone Temp C.C Room 105
AD	FCU-E	Zone Temp C.C Room 106
AD	FCU-F	Zone Temp C.C. Room 111
AD	FCU-G	Zone Temp C.C Room 119
AD	FCU-H	Zone Temp C.C Room 115
AD	FCU-I	Zone Temp C.C Kitchen
AD	FCU-J	Zone Temp Family Advocacy
AD	FCU-K	FCU K Zone Temp
AD	FCU-L	FCU L Zone Temp
JCB	JCBASC5	L-LIMIT
JCB	JCBASC5	DAMPER
JCB	JCBASC5	WARMUP
JCB	JCBASC5	EXFANS

DRAFT

Building 249		
Point	**Equipment**	**Type**
AD	AHU-1	AHU 1 Discharge Air Temp
AD	AHU-2	AHU 2 Discharge Air Temp
AD	AHU-3	AHU 3 Discharge Air Temp
AD	AHU-4	AHU 4 Discharge Air Temp
BO FCU_C	OCC-UNOC	Occupied \Unoccupied
AI FCU_C	ZN-T	Zone Temp
AOS FCU_C	HTG-VLV	Heating Valve Command
BO FCU_C	CLG-VLV	Cooling Valve Command
AD FCU_C	HTG-STPT	Heating Setpoint
CS FCU_C	CLG-STPT	Cooling Setpoint CS
BI FCU_C	SF-S	Supply Fan Status
BO FCU_C	SF-C	Supply Fan Command
BI FCU_C	EF-2-S	Exhaust Fan 2 Status
BO FCU_C	EF-2-C	Exhaust Fan 2 Command
BO FCU_E	OCC-UNOC	Occupied \Unoccupied
AI FCU_E	ZN-T	Zone Temp
AOS FCU_E	HTG-VLV	Heating Valve Command
BO FCU_E	CLG-VLV	Cooling Valve Command
AD FCU_E	HTG-STPT	Heating Setpoint
CS FCU_E	CLG-STPT	Cooling Setpoint CS
BI FCU_E	SF-S	Supply Fan Status
BO FCU_E	SF-C	Supply Fan Command
BI FCU_E	EF-4-S	Exhaust Fan 4 Status
BO FCU_E	EF-4-C	Exhaust Fan 4 Command
BO FCU_F	OCC-UNOC	Occupied \Unoccupied
AI FCU_F	ZN-T	Zone Temp
AOS FCU_F	HTG-VLV	Heating Valve Command
BO FCU_F	CLG-VLV	Cooling Valve Command
AD FCU_F	HTG-STPT	Heating Setpoint
CS FCU_F	CLG-STPT	Cooling Setpoint CS
BI FCU_F	SF-S	Supply Fan Status
BO FCU_F	SF-C	Supply Fan Command
BI FCU_F	EF-7-S	Exhaust Fan 7 Status
BO FCU_F	EF-7-C	Exhaust Fan 7 Command
BO FCU_G	OCC-UNOC	Occupied \Unoccupied
AI FCU_G	ZN-T	Zone Temp
AOS FCU_G	HTG-VLV	Heating Valve Command
BO FCU_G	CLG-VLV	Cooling Valve Command
AD FCU_G	HTG-STPT	Heating Setpoint
CS FCU_G	CLG-STPT	Cooling Setpoint CS
BI FCU_G	SF-S	Supply Fan Status
BO FCU_G	SF-C	Supply Fan Command
BI FCU_G	EF-6-S	Exhaust Fan 6 Status
BO FCU_G	EF-6-C	Exhaust Fan 6 Command
BO FCU_D	OCC-UNOC	Occupied \Unoccupied

DRAFT

Building 249		
Point	**Equipment**	**Type**
AI FCU_D	ZN-T	Zone Temp
AOS FCU_D	HTG-VLV	Heating Valve Command
BO FCU_D	CLG-VLV	Cooling Valve Command
AD FCU_D	HTG-STPT	Heating Setpoint
CS FCU_D	CLG-STPT	Cooling Setpoint CS
BI FCU_D	SF-S	Supply Fan Status
BO FCU_D	SF-C	Supply Fan Command
BI FCU_D	EF-3-S	Exhaust Fan 3 Status
BO FCU_D	EF-3-C	Exhaust Fan 3 Command
BO FCU_I	Occupied \Unoccupied	Occupied \Unoccupied
AI FCU_I	Zone Temp	Zone Temp
AOS FCU_I	Heating Valve Command	Heating Valve Command
BO FCU_I	Cooling Valve Command	Cooling Valve Command
AD FCU_I	Heating Setpoint	Heating Setpoint
CS FCU_I	Cooling Setpoint CS	Cooling Setpoint CS
BI FCU_I	Supply Fan Status	Supply Fan Status
BO FCU_I	Supply Fan Command	Supply Fan Command
BI FCU_I	Exhaust Fan 5 Status	Exhaust Fan 5 Status
BO FCU_I	Exhaust Fan 5 Command	Exhaust Fan 5 Command
BO FCU_H	OCC-UNOC	Occupied \Unoccupied
AI FCU_H	ZN-T	Zone Temp
AD FCU_H	HTG-STPT	Heating Setpoint
CS FCU_H	CLG-STPT	Cooling Setpoint CS
AOS FCU_H	HTG-VLV	Heating Valve Command
BO FCU_H	CLG-VLV	Cooling Valve Command
BI FCU_H	SF-S	Supply Fan Status
BO FCU_H	SF-C	Supply Fan Command
BI FCU_H	EF-8-S	Exhaust Fan 8 Status
BO FCU_H	EF-8-C	Exhaust Fan 8 Command
BO FCU_A	OCC-UNOC	Occupied \Unoccupied
AI FCU_A	ZN-T	Zone Temp
CS FCU_A	CLG-STPT	Cooling Setpoint CS
AD FCU_A	HTG-STPT	Heating Setpoint
BO FCU_A	CLG-VLV	Cooling Valve Command
AOS FCU_A	HTG-VLV	Heating Valve Command
BI FCU_A	SF-S	Supply Fan Status
BO FCU_A	SF-C	Supply Fan Command
BO FCU_B	OCC-UNOC	Occupied \Unoccupied
AI FCU_B	ZN-T	Zone Temp
AOS FCU_B	HTG-VLV	Heating Valve Command
BO FCU_B	CLG-VLV	Cooling Valve Command
AD FCU_B	HTG-STPT	Heating Setpoint
CS FCU_B	CLG-STPT	Cooling Setpoint CS
BI FCU_B	SF-S	Supply Fan Status
BO FCU_B	SF-C	Supply Fan Command

DRAFT

Building 249		
Point	**Equipment**	**Type**
BI FCU_B	EF-1-S	Exhaust Fan 1 Status
BO FCU_B	EF-1-C	Exhaust Fan 1 Command
BD	EF-1-S	Exhaust Fan 1 Status
BD	EF-2-S	Exhaust Fan 2 Status
BD	EF-3-S	Exhaust Fan 3 Status
BD	EF-4-S	Exhaust Fan 4 Status
BD	EF-5-S	Exhaust Fan 5 Status
BD	EF-6-S	Exhaust Fan 6 Status
BD	EF-7-S	Exhaust Fan 7 Status
BD	EF-8-S	Exhaust Fan 8 Status
BI	EF-9-S	Interlocked with SF-1
BI	SF-1-S	Local Control
BO FCU_L	OCC-UNOC	Occupied \Unoccupied
AI FCU_L	ZN-T	Zone Temp
CS FCU_L	CLG-STPT	Cooling Setpoint CS
AD FCU_L	HTG-STPT	Heating Setpoint
AI FCU_L	DA-T	Discharge Air Temp
BO FCU_L	CLG-VLV	Cooling Valve Command
AOS FCU_L	HTG-VLV	Heating Valve Command
BI FCU_L	SF-S	Supply Fan Status
BO FCU_L	SF-C	Supply Fan Command
AI FCU_L	ZN-H	Zone Humdity
BO FCU_L	DAMPER	Outside Air Damper
CS FCU_L	FCU-STPT	Cooling Setpoint CS
BO FCU_J	OCC-UNOC	Occupied\ Unoccupied
AI FCU_J	ZN-T	Zone Temp
AD FCU_J	HTG-STPT	Heating Setpoint
CS FCU_J	CLG-STPT	Cooling Setpoint CS
BO FCU_J	CLG-CMD	Cooling Valve Command
AI FCU_J	DA-T	Discharge Air Temp
AOS FCU_J	HTG-VLV	Heating Valve Command
BI FCU_J	SF-S	Supply Fan Status
BO FCU_J	SF-C	Supply Fan Command
AI FCU_J	ZN-H	Zone Humdity
AI	CWS-T	Chill Water Supply Temp
AI	CWR-T	Chill Water Return Temp
AI	UCWR-T	Units Chill Water Retur
BI	CWP-S	Chill Water Pump Status
BO	CHLR-C	Chiller Command
BI	CHLR-S	Chiller Status
BO	CWP-C	Chill Water Pump Command
AD	CHW-ENA	CH Wtr Enable Setpoint
CS	OA-T	Outside air CS
MC	ALA-DIS	Alarm Disable
SLAVE		AI, CHILLR, CWS-T,

DRAFT

Building 249		
Point	**Equipment**	**Type**
		CHILLR, ALA-DIS
AI	HWS-T	Hot Water Supply Temp
AOS	STM-VLV	Steam Valve Command
AI	HWR-T	Hot Water Return Temp
AI	UHWR-T	Unit Hot Wtr Return Temp
BI	HWP-S	Hot Water Pump Status
BO	HWP-C	Hot Water Pump Command
BO	FCU-STM	Fan Coil Steam Valve Cmd
AD	FSTM-ENA	FCU Steam Ena Setpoint
AI	OA-T	Outside Air Temp
AD	HW-ENA	Hot Wtr Enable Setpoint
MC	ALA-DIS	Alarm Disable
SLAVE		AI, HEAT-XER, HWS-T, HEAT-XER, ALA-DIS
BO	AHU-01	Occupied \Unoccupied
CS	AHU-01	Discharge Air Setpoint
AOS	AHU-01	Reheat Valve Command
AI	AHU-01	Coil Discharge Temp
AOS	AHU-01	Cooling Valve Command
AOS	AHU-01	Preheat Valve Command
BI	AHU-01	Low Temp Alarm
BI	AHU-01	Filter Status
BO	AHU-01	Supply Fan Command
BI	AHU-01	Supply Fan Status
AI	AHU-01	Discharge Air Temp
BO	AHU-04	Occupied\ Unoccupied
AI	AHU-04	Return Air Temp
AOS	AHU-04	Cooling Valve Command
AOS	AHU-04	Heating Valve Command
BI	AHU-04	Supply Fan Status
BO	AHU-04	Supply Fan Command
AI	AHU-04	Discharge Air Temp
AI	AHU-04	Mixed Air Temp
AI	AHU-04	Zone Temp
AI	AHU-04	Zone Humidity
AI	AHU-04	Filter Press Drop
BO	AHU-04	Damper Command
CS	AHU-04	Return Air Setpoint CS
BO	AHU-02	Occupied \Unoccupied
CS	AHU-02	Return Air Setpoint CS
AI	AHU-02	Return Air Temp
AI	AHU-02	Discharge Air Temp
AI	AHU-02	Mixed Air Temp
AI	AHU-02	Zone Temp
AI	AHU-02	Zone Humidity
AOS	AHU-02	Heating Valve

DRAFT

Building 249		
Point	**Equipment**	**Type**
AOS	AHU-02	Cooling Valve
BO	AHU-02	Supply Fan Command
BI	AHU-02	Supply Fan Status
AI	AHU-02	Filter Press Drop
BO	AHU-03	Occupied\ Unoccupied
AI	AHU-03	Zone Temperature
AI	AHU-03	Discharge Air Temp
AI	AHU-03	Mixed Air Temp
AI	AHU-03	Return Air Temp
BO	AHU-03	Cooling Valve Command
AOS	AHU-03	Heating Valve Command
BO	AHU-03	Supply Fan Command
BI	AHU-03	Supply Fan Status
AI	AHU-03	Zone Humidity
BO	AHU-03	Damper Command
AI	AHU-03	Filter Press Drop
CS	AHU-03	Return Air Setpoint CS
(INTENTIOINLY LEFT BLANK) **(CONTINUES ON NEXT PAGE)**		

DRAFT

Building 250		
Point	**Equipment**	**Type**
	NC-6	**network controller**
N2OPEN	01AHU-07	7, 1, 3, AHU
N2OPEN	01AHU-02	2, 1, 3, AHU
N2OPEN	01AHU-04	4, 1, 3, AHU
N2OPEN	01AHU-05	5, 1, 3, AHU
N2OPEN	01AHU-08	8, 1, 3, AHU
N2OPEN	01UNT-03	3, 1, 3, UNT
N2OPEN	01UNT-01	1, 1, 3, UNT
N2OPEN	01UNT-06	6, 1, 3, UNT
DCDR	01DX-09	9, 1, 3, DX9100
N2OPEN	01UNT-10	10, 1, 3, UNT
N2OPEN	01UNT-11	11, 1, 3, UNT
N2OPEN	01UNT-12	12, 1, 3, UNT
N2OPEN	01UNT-13	13, 1, 3, UNT
N2OPEN	01UNT-14	14, 1, 3, UNT
N2OPEN	01UNT-15	15, 1, 3, UNT
AI	AHU_01	Zone Temp
CS	AHU_01	Zone Setpoint CS
BO	AHU_01	Occupied\ Unoccupied
AOS	AHU_01	Cooling Valve Command
AOS	AHU_01	Heating Valve Command
AI	AHU_01	Discharge Air Temp
AI	AHU_01	Mixed Air Temp
BI	AHU_01	Supply Fan Status
BO	AHU_01	Supply Fan Command
BO	AHU_01	Outside Air Damper
BI	AHU_01	Smoke Duct Det Status
BI	AHU_01	Low Temp Alarm
BI	AHU_01	Filter Status
BO	AHU_01	EF-3-C Mech.Rm. 1st Flr
BD	AHU_01	Optimal S\S Enable
AD	AHU_01	How Far Off Setpoint
BI	AHU_01	EF-3-S Mech.Rm. 1st Flr
AI	CHILLERB	B-250 Chill Wtr Sply
AI	CHILLERB	B-250 Chill Wtr Rtrn
BO	CHILLERB	B-250 CHILLERA #1Command
BI	CHILLERB	B-250 CHILLERA #1 Status
BO	CHILLERB	B-250 C/W Pmp #1 Command
BI	CHILLERB	B-250 C/W Pmp #1 Status
AD	CHILLERB	B-250 O.A. Temperature
BO	FCU_07	Occupied \Unoccupied
AI	FCU_07	Zone Temp
CS	FCU_07	Cooling Setpoint CS
AD	FCU_07	Heating Setpoint

DRAFT

Building 250		
Point	**Equipment**	**Type**
BO	FCU_07	Radiator 1 Valve Command
BO	FCU_07	Heating Valve Command
BO	FCU_07	Cooling Valve Command
AI	FCU_07	Discharge Air Temp
BI	FCU_07	Supply Fan Status
BO	FCU_07	Supply Fan Command
BO	FCU_09	Occupied \Unoccupied
AI	FCU_09	Zone Temp
CS	FCU_09	Cooling Setpoint CS
AD	FCU_09	Heating Setpoint
BO	FCU_09	Cooling Valve Command
BO	FCU_09	Radiator Valve
BO	FCU_09	Heating Valve Command
AI	FCU_09	Discharge Air Temp
BI	FCU_09	Supply Fan Status
BO	FCU_09	Supply Fan Command
BO	FCU_08	Occupied \Unoccupied
AI	FCU_08	Zone Temp
CS	FCU_08	Cooling Setpoint CS
BO	FCU_08	Cooling Valve Command
AI	FCU_08	Discharge Air Temp
BI	FCU_08	Supply Fan Status
BO	FCU_08	Supply Fan Command
BO	FCU_06	Occupied \Unoccupied
AI	FCU_06	Zone Temp
CS	FCU_06	Cooling Setpoint CS
AD	FCU_06	Heating Setpoint
BO	FCU_06	Cooling Valve Command
BO	FCU_06	Heating Valve Command
AI	FCU_06	Discharge Air Temp
BI	FCU_06	Supply Fan Status
BO	FCU_06	Supply Fan Command
BO	FCU_05	Occupied \Unoccupied
AI	FCU_05	Zone Temp
AD	FCU_05	Heating Setpoint
BO	FCU_05	Cooling Valve Command
BO	FCU_05	Heating Valve Command
AI	FCU_05	Discharge Air Temp
BI	FCU_05	Supply Fan Status
BO	FCU_05	Supply Fan Command
CS	FCU_05	Cooling Setpoint CS
BO	FCU_02	Occupied \Unoccupied
AI	FCU_02	Zone Temp
CS	FCU_02	Cooling Setpoint CS
AD	FCU_02	Heating Setpoint
BO	FCU_02	Cooling Valve Command
AOS	FCU_02	Heating Valve Command
BI	FCU_02	Supply Fan Status

DRAFT

Building 250		
Point	**Equipment**	**Type**
BO	FCU_02	Supply Fan Command
BO	FCU_01	Occupied \Unoccupied
AI	FCU_01	Zone Temp
CS	FCU_01	Cooling Setpoint CS
AD	FCU_01	Heating Setpoint
BO	FCU_01	Cooling Valve Command
AOS	FCU_01	Heating Valve Command
BI	FCU_01	Supply Fan Status
BO	FCU_01	Supply Fan Command
BO	FCU_01	Outside Air Damper
BO	AHU_03	Occupied\ Unoccupied
AI	AHU_03	Zone Temp
CS	AHU_03	Zone Setpoint CS
AOS	AHU_03	Cooling Valve Command
AOS	AHU_03	Heating Valve Command
AI	AHU_03	Discharge Air Temp
AI	AHU_03	Mixed Air Temp
AI	AHU_03	Return Air Temp
BI	AHU_03	Supply Fan Status
BO	AHU_03	Supply Fan Command
BO	AHU_03	Outside Air Damper
BI	AHU_03	Low Temp Alarm
BI	AHU_03	Filter Status
AD	AHU_01	Mangement Info Zone Temp
AD	AHU_02	Material Mant. Zone Temp
AD	AHU_03	1st Floor Zone Temp
AD	AHU_04	Recieving Zone Temp
AD	AHU_05	Civilian Payroll Z-Temp
AD	FCU_01	Room 134 Zone Temp
AD	FCU_02	Lounge Zone Temp
AD	FCU_04	Room 208 Zone Temp
AD	FCU_05	Room 212 Zone Temp
AD	FCU_06	Room 212 Zone Temp
AD	FCU_07	Room 215 Zone Temp
AD	FCU_08	Room 211 Zone Temp
AD	FCU_09	Room 224 Zone Temp
BO	AHU_05	Occupied \Unoccupied
AI	AHU_05	Zone Temperature
CS	AHU_05	Zone Setpoint CS
AOS	AHU_05	Cooling Valve Command
AOS	AHU_05	Heating Valve Command
AI	AHU_05	Discharge Air Temp
AI	AHU_05	Mixed Air Temp
AI	AHU_05	Outside Air Temp
AOS	AHU_05	Damper Command
BO	AHU_05	Min Damper Command
BO	AHU_05	Supply Fan Command

DRAFT

Building 250		
Point	**Equipment**	**Type**
BI	AHU_05	Supply Fan Status
AI	AHU_05	Return Air Static Press
BI	AHU_05	Filter Status
BI	AHU_05	Smoke Duct Detector
BI	AHU_05	Low Temperature Alarm
BD	AHU_05	Economizer Status
AOS	EF5_AO	Exhaust Fan 5 Command
BI	EF-5-S	Exhaust Fan 5 Status
BO	EF-5-C	Exhaust Fan 5 Command
BI	EF-1-S	EF-1-S Wms Bathrm 2nd Fl
BO	EF-1-C	EF-1-C Wms Bathrm 2nd Fl
BI	EF-2-S	EF-2-S Men Bathrm 2nd Fl
BO	EF-2-C	EF-2-C Men Bathrm 2nd Fl
CS	HEAT_XER	Outside Air Temp CS
CS	HEAT_XER	Outside Air Lockout CS
AI	HEAT_XER	Hot Water Supply Temp
CS	HEAT_XER	Calcuated Setpoint HWS
AI	HEAT_XER	Hot Water Return Temp
AOS	HEAT_XER	Steam Valve Command
BI	HEAT_XER	Hot Water Pump Status
BO	HEAT_XER	Hot Water Pump Command
BO	FCU_04	Occupied \Unoccupied
AI	FCU_04	Zone Temp
CS	FCU_04	Cooling Setpoint CS
AD	FCU_04	Heating Setpoint
AOS	FCU_04	Cooling Valve Command
AOS	FCU_04	Heating Valve Command
BO	FCU_04	Radiator Valve 1 Command
AI	FCU_04	Discharge Air Temp
BI	FCU_04	Supply Fan Status
BO	FCU_04	Supply Fan Command
BI	FCU_04	Filter Status
BI	EF-4-S	EF-4-S Kitchen 2nd Floor
BO	EF-4-C	EF-4-C Kitchen 2nd Floor
BO	FCU_04	Outside Air Damper
BI	FCU_04	Smoke Duct Detector
AI	CHILLERA	B-250 Chill Wtr Sply
AI	CHILLERA	B-250 Chill Wtr Rtrn
BO	CHILLERA	B-250 CHILLERA Command
BO	CHILLERA	B-250 C/W Pump Command
BI	CHILLERA	B-250 C/W Pump Status
AD	CHILLERA	B-250 O.A. Temperature
CS	CHILLERA	B-250 O.A. Lockout (CWS)
JCB	CHILLERA	Process
BD	EF-1-S	Interlocked to AHU-05
BD	EF-2-S	Interlocked to AHU-05

DRAFT

Building 250		
Point	**Equipment**	**Type**
BD	EF-3-S	Interlocked to AHU-01
BD	EF-4-S	Interlocked to FCU-04
BD	EF-5-S	Interlocked to AHU-05
BD	EF-10-S	Interlocked to AHU-02
BO	EF-11-C	Exhaust Fan 11 Command
BI	EF-11-S	Toilet \ Cage 1st Floor
BI	EF-13-S	Toilet
BO	EF-13-C	Exhaust Fan 13 Command
BO	EF-14-C	Exhaust Fan 14 Command
BI	EF-14-S	Exhaust Fan 14 status
JCB	TEMP-OCC	Process
JCB	EF5-CNTL	Process
JCB	EXFANS	Process
JCB	FCU4SMK	Process
JCB	SMOKE	Process
JCB	DAMPER	Process
JCB	VALVE	Process
JCB	OAT-GLB	Process
JCB	RAD	Process
BO	AHU_04	Occupied\ Unoccupied
AI	AHU_04	Zone Temp
CS	AHU_04	Zone Setpoint CS
AOS	AHU_04	Cooling Valve Command
AOS	AHU_04	Heating Valve Command
AI	AHU_04	Discharge Air Temp
AI	AHU_04	Mixed Air Temp
AI	AHU_04	Return Air Temp
BI	AHU_04	Supply Fan Status
BO	AHU_04	Supply Fan Command
BO	AHU_04	Outside Air Damper
BI	AHU_04	Smoke Duct Det Status
BI	AHU_04	Low Temp Alarm
BI	AHU_04	Filter Status
BI	AHU_04	Exhaust Fan 12 Status
BO	AHU_04	EXhaust Fan 12 Command
AI	AHU_04	Liebert Room-Temp
BO	AHU_02	Occupied\Unoccupied
AI	AHU_02	Zone Temp
CS	AHU_02	Zone Setpoint CS
AOS	AHU_02	Cooling Valve Command
AOS	AHU_02	Heating Valve Command
AI	AHU_02	Discharge Air Temp
AI	AHU_02	Mixed Air Temp
AI	AHU_02	Return Air Temp
BI	AHU_02	Supply Fan Status
BO	AHU_02	Supply Fan Command
BO	AHU_02	Outside Air Damper
BI	AHU_02	Smoke Duct Det Status

DRAFT

Building 250		
Point	**Equipment**	**Type**
BI	AHU_02	Low Temp Alarm
BI	AHU_02	Filter Status
BO	AHU_02	Exhaust Fan 10 Command
BI	AHU_02	Exhaust Fan 10 Status

(INTENTIOINLY LEFT BLANK)
(CONTINUES ON NEXT PAGE)

DRAFT

Building 252		
Points	**Equipment**	**Type**
NC-01		**Network controller**
NC1HRDW	UNT1	1, 1, 3, UNT
CS	Pool	CS-Pool
AI	Pool	ZN-T
AI	Pool	ZONE-RH
AI	Pool	Pool-T
AI	Pool	LA-T
BO	Pool	CMP-A
BI	Pool	CMPFLTA
BO	Pool	CMP-B
BI	Pool	CMPFLTB
BO	Pool	RC-VLVA
BO	Pool	RC-VLVB
BO	Pool	WTR-VLVA
BO	Pool	WTR-HTGA
BO	Pool	AIRHTG1
AI	Pool	EVA-DP
AI	Pool	RHT-DP
AI	Pool	EXH-DP
BI	Pool	AIRFLOW
BI	Pool	WTRFLW-A
BI	Pool	EBINTLK
AOS	Pool	HTG-CMD
AOS	Pool	OA-DMP
AOS	Pool	WRM-DMP
AOS	Pool	CL-DMP
AOS	Pool	EVAP-DMP
BI	Pumps	PMP-1
BI	Pumps	PMP-2
BO	Pumps	PMP1-EN
BO	Pumps	PMP2-EN
BI	Pumps	WATERFLW
BO	Pumps	STM-VLV
(INTENTIOINLY LEFT BLANK) **(CONTINUES ON NEXT PAGE)**		

DRAFT

Building 256		
Points	**Equipment**	**Type**
NC-22		**Network controller**
NC22HRDW	UNT2	2, 1, 3, UNT
NC22HRDW	UNT3	3, 1, 3, UNT
NC22HRDW	UNT4	4, 1, 3, UNT
NC22HRDW	UNT5	5, 1, 3, UNT
NC22HRDW	UNT6	6, 1, 3, UNT
NC22HRDW	VAV1	7, 1, 3, VAV
NC22HRDW	VAV2	8, 1, 3, VAV
NC22HRDW	VAV3	9, 1, 3, VAV
NC22HRDW	VAV4	10, 1, 3, VAV
NC22HRDW	VAV5	11, 1, 3, VAV
NC22HRDW	VAV6	12, 1, 3, VAV
NC22HRDW	VAV7	13, 1, 3, VAV
NC22HRDW	VAV8	14, 1, 3, VAV
NC22HRDW	BLR	15, 1, 3, UNT
AI	HWSYS	HWS-T
BO	HWSYS	HWP2-C
BO	HWSYS	HWP1-C
CS	HWSYS	OAT-CS
CS	MAUS	CS-MAUS
AI	MAUS	MAU1DT
AI	MAUS	MAU2DT
AI	MAUS	MAU3DT
BO	MAUS	MAU1-C
BO	MAUS	MAU2-C
BO	MAUS	MAU3-C
BO	MAUS	EF4-C
AOS	MAUS	MAU1H
AOS	MAUS	MAU2H
AOS	MAUS	MAU3H
BI	MAUS	EF6-S
BI	MAUS	EF7-S
BI	MAUS	EF9-S
CS	VAV1	CS-VAV1
BO	VAV1	RH-VLV
AI	VAV1	ZN-T
CS	VAV2	CS-VAV2

DRAFT

Building 256		
Points	**Equipment**	**Type**
BO	VAV2	RHT-VLV
AI	VAV2	Zone-T
CS	VAV3	CS-VAV3
BO	VAV3	RHT-VLV
AI	VAV3	ZN-T
CS	VAV4	CS-VAV4
BO	VAV4	RHT-VLV
AI	VAV4	ZN-T
CS	VAV5	CS-VAV5
BO	VAV5	RHT-VLV
AI	VAV5	ZN-T
CS	VAV6	CS-VAV6
BO	VAV6	RHT-VLV
AI	VAV6	ZN-T
CS	VAV7	CS-VAV7
BO	VAV7	RHT-VLV
AI	VAV7	ZN-T
AI	VAV8	ZN-T
BO	VAV8	RHT-VLV
CS	VAV8	CS-VAV8
BO	RTU1	SF-C
BI	RTU1	SF-S
JCB	RTU1	OA-SHARE
JCB	RTU1	RTU1DPR
AI	RTU1	DA-T
BO	RTU1	CLGSTG1
BO	RTU1	CLGSTG2
BO	RTU1	CLGSTG3
BI	RTU1	LL-A
AI	RTU1	MA-T
AI	RTU1	OA-T
CS	RTU1	CS-RTU1
AI	RTU2	ZN-T
AI	RTU2	WC-ADJ
AI	RTU2	DA-T
BO	RTU2	SF-C
BI	RTU2	SF-S
BO	RTU2	HTG-C

DRAFT

Building 256		
Points	**Equipment**	**Type**
BO	RTU2	DX-C1
BO	RTU2	DX-C2
AOS	RTU2	DPR-CMD
JCB	RTU2	RTU-2
CS	RTU2	CS-RTU2
AI	RTU3	ZN-T
AI	RTU3	WC-ADJ
AI	RTU3	DA-T
BO	RTU3	SF-C
BI	RTU3	SF-S
BO	RTU3	HX-1
BO	RTU3	DX-1C
BO	RTU3	DX-C2
AOS	RTU3	DPR-CMD
JCB	RTU3	LOHILIMT
CS	RTU3	CS-RTU3
AI	RTU4	ZN-T
AI	RTU4	WC-ADJ
BO	RTU4	SF-C
BI	RTU4	SF-S
AI	RTU4	DA-T
BO	RTU4	HTG-C
BO	RTU4	DX-C1
BO	RTU4	DX-C2
AOS	RTU4	DPR-CMD
JCB	RTU4	HILOLIMT
CS	RTU4	CS-RTU4
AI	RTU5	ZN-T
BO	RTU5	SF-C
BI	RTU5	SF-S
AI	RTU5	DA-T
BO	RTU5	HTG-C
BO	RTU5	DX-C1
BO	RTU5	DX-C2
AOS	RTU5	DPR-CMD
JCB	RTU5	HILOWLIM
CS	RTU5	CS-RTU5
AI	RTU5	Setpoint

DRAFT

Building 276		
Points	**Equipment**	**Type**
NC-10		**Network controller**
NC10HRDW	UNT1	2, 1, 3, UNT
NC10HRDW	UNT3	3, 1, 3, UNT
NC10HRDW	UNT4	4, 1, 3, UNT
NC10HRDW	UNT5	5, 1, 3, UNT
NC10HRDW	UNT6	6, 1, 3, UNT
NC10HRDW	UNT7	7, 1, 3, UNT
NC10HRDW	UNT8	8, 1, 3, UNT
NC10HRDW	UNT9	9, 1, 3, UNT
NC10HRDW	AHU10	10, 1, 3, AHU
NC10HRDW	UNT11	11, 1, 3, UNT
NC10HRDW	UNT12	12, 1, 3, UNT
NC10HRDW	DX13	13, 1, 3, DX9100
BO	CWLOOP	PLANT-EN
BO	CWLOOP	P3-C
BI	CWLOOP	P3-S
BO	CWLOOP	ACC1-EN
AI	CWLOOP	CHWS-T
AI	CWLOOP	CHWR-T
BI	CWLOOP	CHWS-FS
BI	CWLOOP	ACC1-LP
BI	CWLOOP	ACC1-SP
BO	CWLOOP	HT-EN
CS	CWLOOP	CWS
AD	CWLOOP	ENAB-STP
AD	CWLOOP	OA-T
JCB	CWLOOP	CHWS
CS	AH8	CS-AHU8
BO	AH8	HTG-VLV
BO	AH8	SF-C
BO	AH8	OADPR-C
AI	AH8	DA-T
AI	AH8	ZN-T
BI	AH8	SF-S
BI	AH8	FILTER-S
BI	AH8	SA-SD

DRAFT

Building 276		
Points	**Equipment**	**Type**
AOS	AH8	HTG-F&B
BO	AH8	DX1-C
BI	AH8	DX1-S
JCB	AH8	AH8INTLK
CS	AH6	CS-AHU6
AI	AH6	ZN-T
AI	AH6	MA-T
AI	AH6	DA-T
BO	AH6	SF-C
BI	AH6	SF-S
BI	AH6	LT-A
BI	AH6	SA-SD
AOS	AH6	DPR-C
AOS	AH6	PH-VLV
AOS	AH6	CLG-VLV
JCB	AH6	UNOC-INT
CS	AH1	CS-AHU1
AI	AH1	ZN-T
AI	AH1	DA-T
AI	AH1	MA-T
BO	AH1	SF-C
BI	AH1	SF-S
BI	AH1	Filter-S
BI	AH1	SA-SD
BI	AH1	DX1-S
BO	AH1	DX1-C
AOS	AH1	HTG-VLV
BO	AH1	OADPR-C
JCB	AH1	AH1-5
CS	AH9	CS-AHU9
AI	AH9	ZN-T
AI	AH9	ZN-T2
AI	AH9	DA-T
BO	AH9	SF-C
BI	AH9	SF-S
BI	AH9	LT-ALM
BI	AH9	SA-SD
BI	AH9	FILTER-S

DRAFT

Building 276		
Points	**Equipment**	**Type**
BO	AH9	DX-CMD
BI	AH9	DX1-S
AOS	AH9	HT-VLV1
AOS	AH9	HT-VLV2
CS	HWLOOP	CS-HWTR
BO	HWLOOP	P1-C
BI	HWLOOP	P1-S
AI	HWLOOP	HWS-T
AI	HWLOOP	HWR-T
AI	HWLOOP	OA-T
AOS	HWLOOP	STM-VLV
CS	AH2	CS-AHU2
AI	AH2	ZN-T
AI	AH2	DA-T
AI	AH2	MA-T
BO	AH2	SF-C
BI	AH2	SF-S
BI	AH2	FILTER-S
BI	AH2	SA-SD
BI	AH2	DX1-S
BO	AH2	DX1-C
AOS	AH2	HTG-VLV
BO	AH2	OADPR-C
CS	AH3	CS-AHU3
AI	AH3	ZN-T
AI	AH3	DA-T
AI	AH3	MA-T
BI	AH3	SF-S
BO	AH3	SF-C
BI	AH3	FILTER-S
BI	AH3	SA-SD
BI	AH3	DX1-S
BO	AH3	DX1-C
AOS	AH3	HTG-VLV
BO	AH3	OADPR-C
BI	AH3	EF2-S
BO	AH3	EF2-C
CS	AH4	CS-AHU4

DRAFT

Building 276		
Points	**Equipment**	**Type**
AI	AH4	ZN-T
AI	AH4	DA-T
AI	AH4	MA-T
BI	AH4	SF-S
BO	AH4	SF-C
BI	AH4	FILTER-S
BI	AH4	SA-SD
AOS	AH4	HTG-VLV
BI	AH4	DX1-S
BO	AH4	DX1-C
BO	AH4	OADPR-C
CS	AH5	CS-AHU5
AI	AH5	ZN-T
AI	AH5	DA-T
AI	AH5	MA-T
BI	AH5	SF-S
BI	AH5	FILTER-S
BI	AH5	SA-SD
BI	AH5	DX1-S
AOS	AH5	HTG-VLV
BO	AH5	DX1-C
BO	AH5	SF-C
BO	AH5	OADPR-C
BD	AH5	AHU-5a
CS	AH5	CS-AHU5A
AI	AH5	ZN-T-A
AI	AH5	DA-T-A
AI	AH5	MA-T-A
BI	AH5	SF-S-A
BI	AH5	FLT-S-A
BI	AH5	SA-SD-A
BI	AH5	DX1-S-A
AOS	AH5	HTG-V-A
BO	AH5	DX1-C-A
BO	AH5	SF-C-A
BO	AH5	DPR-C-A
CS	AH7	CS-AHU7
AI	AH7	ZN-T

DRAFT

Building 276		
Points	**Equipment**	**Type**
AI	AH7	MA-T
AI	AH7	DA-T
BI	AH7	SF-S
BI	AH7	SA-SD
BI	AH7	LT-A
AOS	AH7	DPR-C
AOS	AH7	HTG-VLV
AOS	AH7	CLG-VLV
BO	AH7	SF-C
AI	UH	UH-T
BO	UH	UH-C
BI	UH	UH-S
BO	EXFAN	EF1-C
BI	EXFAN	EF1-S
AI	EXFAN	EF3ZN-T
BO	EXFAN	EX3-C
BI	EXFAN	EF3-S
BO	EXFAN	EF4-C
BI	EXFAN	EF4-S
BO	EXFAN	EF5-C
BI	EXFAN	EF5-S
BI	EXFAN	EF6-S
BI	EXFAN	EFS7-S
AI	EXFAN	EF4ZN-T
JCB	EXFAN	EX-LOOP

DRAFT

Building 273		
Point	**Equipment**	**Type**
	NC-9	**network controller**
Nc9-Hrdw	DX1	1, 1, 3, DX9100
Nc9-Hrdw	UNT2	2, 1, 3, UNT
Nc9-Hrdw	UNT4	4, 1, 3, UNT
Nc9-Hrdw	UNT5	5, 1, 3, UNT
Nc9-Hrdw	UNT6	6, 1, 3, UNT
Nc9-Hrdw	UNT7	7, 1, 3, UNT
Nc9-Hrdw	UNT8	8, 1, 3, UNT
Nc9-Hrdw	UNT9	9, 1, 3, UNT
Nc9-Hrdw	UNT10	10, 1, 3, UNT
Nc9-Hrdw	UNT11	11, 1, 3, UNT
Nc9-Hrdw	UNT12	12, 1, 3, UNT
Nc9-Hrdw	UNT13	13, 1, 3, UNT
Nc9-Hrdw	UNT14	14, 1, 3, UNT
Nc9-Hrdw	UNT15	15, 1, 3, UNT
BO	UH1-C	Unit Heater 1 Command
BO	UH2-C	Unit Heater 2 Command
BO	UH3-C	Unit Heater 3 Command
BI	UH1-S	Unit Heater 1 Status
BI	UH2-S	Unit Heater 2 Status
BI	UH3-S	Unit Heater 3 Status
BO	EF18-C	Exhaust Fan18 Command
BO	EF19-C	Exhaust Fan19 Command
BI	EF17-S	Exhaust Fan 17 Status
BI	EF18-S	Exhaust Fan 18 Status
BI	EF19-S	Exhaust Fan 19 Status
AI	UH2-T	Unit Heater 2 Temp
AI	UH3-T	Unit Heater 3 Temp
AI	ZN18-T	Ex Fan 18 Zn Temp
AI	ZN19-T	Ex Fan 19 Zn Temp
BO	MERDPR-C	Mech Room OA Damper
BO	EF16-C	Ex Fan16 Command
BI	EF16-S	Ex Fan16 Status
AI	DU-1	Zone Temperature
BI	DU-1	Supply Fan Status
BI	DU-1	Condenser Unit Status
BO	DU-1	Unit Command
AI	RTU2	Zone Temperature
AI	RTU2	Discharge Air Temp
BO	RTU2	Unit Command
BI	RTU2	Supply Fan Status
BI	RTU2	Compressor 1 Status

DRAFT

Building 273		
Point	**Equipment**	**Type**
BI	RTU2	Smoke Detector
BI	RTU2	Filter Status
BD	RTU2	Shutdown Command
AI	RTU3	Zone Temperature
AI	RTU3	Discharge Air Temp
BO	RTU3	Unit Command
BI	RTU3	Supply Fan Status
BI	RTU3	Compressor 1 Status
BI	RTU3	Smoke Detector
BI	RTU3	Filter Status
BI	RTU3	Ex Fan 14 Status
BI	RTU3	Ex Fan 3 Status
AI	RTU3	Ex Fan3 Switch Status
AI	RTU3	Ex Fan14 Switch Status
BD	RTU3	Shutdown Command
AI	RTU1	Zone Temperature
AI	RTU1	Discharge Air Temp
BO	RTU1	Unit Command
BI	RTU1	Supply Fan Status
BI	RTU1	Compressor 1 Status
BI	RTU1	Smoke Detector
BI	RTU1	Filter Status
BD	RTU1	Shutdown Command
JCB	RTU1	RTU-SDWN
CS	AHU3	Cs Object For Ahu3
AI	AHU3	Zone Temperature
AI	AHU3	Discharge Air Temp
AD	AHU3	Mixed Air LL Setpoint
AI	AHU3	Mixed Air Temp
BD	AHU3	EXFan30 74=Off 25=On
AI	AHU3	Ex Fan 30 Status
AI	AHU3	Ex Fan 30 Switch Status
BO	AHU3	Supply Fan Command
BI	AHU3	Supply Fan Status
AOS	AHU3	Heating Valve
BO	AHU3	Cooling Stage 1 Command
BO	AHU3	Damper Open
BI	AHU3	Filter Status
BI	AHU3	Smoke Detector
BI	AHU3	Condenser Unit Status
BO	AHU3	Ex Fan 2 Command
BI	AHU3	Ex Fan2 Status
BI	AHU3	Ex Fan 15 Status
BO	AHU3	Ex Fan 15 Command

DRAFT

Building 273		
Point	**Equipment**	**Type**
CS	H&V1	Cs Object for H&V1
AI	H&V1	Zone Temperature
AI	H&V1	Mixed Air Temp
AOS	H&V1	Mixed Air LL Setpoint
AI	H&V1	Discharge Air Temp
BD	H&V1	EXFanS-S 70=Off 24=On
AI	H&V1	Ex Fan 4 Switch Status
AI	H&V1	Ex Fan 5 Switch Status
BO	H&V1	Supply Fan Command
BI	H&V1	Supply Fan Status
BI	H&V1	Filter Status
BI	H&V1	Smoke Detector
BI	H&V1	Ex Fan 4 Status
BI	H&V1	Ex Fan 5 Status
AOS	H&V1	Damper Command
AOS	H&V1	Heating Face Bypass Dmpr
AD	H&V1	All HVS Vent Setpoint
AD	H&V1	All HVS Heating Setpoint
JCB	H&V1	HV1EXF
CS	H&V2	Cs Object for H&V2
AI	H&V2	Zone Temperature
AI	H&V2	Mixed Air Temperature
AOS	H&V2	Mixed Air LL Setpoint
AI	H&V2	Discharge Air Temp
BD	H&V2	EXFanS-S 70=Off 24=On
AI	H&V2	Ex Fan 6 Switch Status
AI	H&V2	Ex Fan 7 Switch Status
BO	H&V2	Supply Fan Command
BI	H&V2	Supply Fan Status
BI	H&V2	Filter Status
BI	H&V2	Smoke Detector
BI	H&V2	Ex Fan 6 Status
BI	H&V2	Ex Fan 7 Status
AOS	H&V2	Damper Command
AOS	H&V2	Heating Face & Bypass
JCB	H&V2	HV2-EXF
CS	H&V3	Cs Object for H&V3
AI	H&V3	Zone Temperature
AI	H&V3	Mixed Air Temperature
AOS	H&V3	Mixed Air LL Setpoint
AI	H&V3	Discharge Air Temp
BD	H&V3	ExFanS-S 70=Off 25=On
AI	H&V3	Ex Fan 9 Switch Status
BI	H&V3	Ex Fan 9 Status

DRAFT

Building 273		
Point	**Equipment**	**Type**
BI	H&V3	Ex Fan8 Status
BI	H&V3	Ex Fan 8 Switch Status
BI	H&V3	Supply Fan Status
BO	H&V3	Supply Fan Command
BI	H&V3	Filter Status
BI	H&V3	Smoke Detector
AOS	H&V3	Damper Command
AOS	H&V3	Htg Face & Bypass
JCB	H&V3	HV3-EXFN
CS	H&V4	Cs Object for H&V4
AI	H&V4	Zone Temperature
AI	H&V4	Mixed Air Temperature
AOS	H&V4	Mixed Air LL Setpoint
AI	H&V4	Disch Air Temperature
BO	H&V4	Supply Fan Command
BD	H&V4	ExS-Switch 25=On,70=Off
AI	H&V4	Ex Fan10 Switch Status
AI	H&V4	Ex Fan11 Switch Status
AI	H&V4	Ex Fan20 Switch Status
BI	H&V4	Supply Fan Status
BI	H&V4	Filter Status
BI	H&V4	Smoke Detector
BI	H&V4	Ex Fan 20 Status
BI	H&V4	Ex Fan 10 Status
BI	H&V4	Ex Fan 11 Status
AOS	H&V4	Damper Command
AOS	H&V4	Htg Face And Bypass
JCB	H&V4	HV4-EXFN
CS	H&V5	Cs Object For H&V 5
AI	H&V5	Zone Temperature
AI	H&V5	Mixed Air Temperature
AOS	H&V5	Mixed Air LL Setpoint
AI	H&V5	Discharge Air Temp
BD	H&V5	EXS-STATUS 70=OFF25=ON
AI	H&V5	Ex Fan12 Switch Status
AI	H&V5	Ex Fan13 Switch Status
BI	H&V5	Ex Fan12 Status
BI	H&V5	Ex Fan13 Status
BI	H&V5	Filter Status
BI	H&V5	Smoke Detector
BI	H&V5	Supply Fan Status
BO	H&V5	Supply Fan Command
AOS	H&V5	Damper Command

DRAFT

Building 273		
Point	**Equipment**	**Type**
AOS	H&V5	Heating Face&Bypass
JCB	H&V5	HV5-EXFN
CS	AHU4	Cs Object For Ahu4
AI	AHU4	Zone Temperature
AI	AHU4	Discharge Air Temp
AI	AHU4	Mixed Air Temp
AD	AHU4	Mixed Air LL Setpoint
BO	AHU4	Supply Fan Command
BI	AHU4	Supply Fan Status
BI	AHU4	Filter Status
BI	AHU4	Smoke Detector
BI	AHU4	Condenser Unit Status
BI	AHU4	Exhaust Fan 27 Status
AOS	AHU4	Heating Valve
BO	AHU4	Damper Open
BO	AHU4	Cooling Stage 1 Command
CS	Heating	Cs Object DX9100
BO	Heating	Hot Water Pump Command
BI	Heating	Hotwater Pump Status
AI	Heating	Outside Air Temp
AI	Heating	Hotwater Supply Temp
AI	Heating	Hotwater Return Temp
AOS	Heating	Steam Valve
MC	Heating	Alarm Disable
SLAVE		AI, Heating, HWS-T, Heating, ALA-1DIS
CS	AHU1	Cs Object AHU1
AI	AHU1	Zone Temperature
AI	AHU1	Warm Cool Adjust
AD	AHU1	Actual Zone Clg Setpoint
AD	AHU1	Actual Zone Htg Setpoint
AI	AHU1	Discharge Air Temp
AI	AHU1	Mixed Air Temp
BO	AHU1	Supply Fan Command
BI	AHU1	Supply Fan Status
JCB	AHU1	UNOC-DPR
BO	AHU1	Cooling Command
BI	AHU1	Condenser Status
AOS	AHU1	Cooling Command
BI	AHU1	Smoke Detector
BI	AHU1	Filter Status
BO	AHU1	Damper Command
AOS	AHU1	Heating Valve
BO	AHU1	Exhaust 1 Fan Command

DRAFT

Building 273		
Point	**Equipment**	**Type**
BI	AHU1	Exhaust 1 Fan Status
JCB	AHU1	OA-GLBL
CS	AHU2	Cs Object AHU2
AI	AHU2	Zone Temperature
AI	AHU2	Warm Cool Adjust
AD	AHU2	Actual Zone Clg Setpoint
AD	AHU2	Actual Zone Htg Setpoint
AI	AHU2	Discharge Air Temp
AI	AHU2	Mixed Air Temp
BO	AHU2	Supply Fan Command
BI	AHU2	Supply Fan Status
BO	AHU2	Dx Cooling Stage 1
BO	AHU2	Dx Cooling Stage 2
AOS	AHU2	Cooling Command
BI	AHU2	Condenser Status
BI	AHU2	Smoke Detector
BI	AHU2	Filter Status
BO	AHU2	Damper Open Command
AOS	AHU2	Heating Valve

DRAFT

Building 274		
Points	**Equipment**	**Type**
NC-01		**Network controller**
NC1-HW	VAV-1	1, 1, 3, VAV
NC1-HW	VAV-2	2, 1, 3, VAV
NC1-HW	VAV-3	3, 1, 3, VAV
NC1-HW	VAV-4	4, 1, 3, VAV
NC1-HW	VAV-5	5, 1, 3, VAV
NC1-HW	VAV-6	6, 1, 3, VAV
NC1-HW	VAV-7	7, 1, 3, VAV
NC1-HW	VAV-8	55, 1, 3, VAV
NC1-HW	VAV-9	9, 1, 3, VAV
NC1-HW	VAV-10	10, 1, 3, VAV
NC1-HW	VAV-11	11, 1, 3, VAV
NC1-HW	VAV-12	12, 1, 3, VAV
NC1-HW	VAV-13	13, 1, 3, VAV
NC1-HW	VAV-14	14, 1, 3, VAV
NC1-HW	VAV-15	15, 1, 3, VAV
NC1-HW	VAV-16	16, 1, 3, VAV
NC1-HW	VAV-17	17, 1, 3, VAV
NC1-HW	VAV-18	18, 1, 3, VAV
NC1-HW	VAV-19	19, 1, 3, VAV
NC1-HW	VAV-20	20, 1, 3, VAV
NC1-HW	VAV-21	21, 1, 3, VAV
NC1-HW	VAV-22	22, 1, 3, VAV
NC1-HW	VAV-23	23, 1, 3, VAV
NC1-HW	VAV-24	24, 1, 3, VAV
NC1-HW	VAV-25	25, 1, 3, VAV
NC1-HW	VAV-26	26, 1, 3, VAV
NC1-HW	VAV-27	27, 1, 3, VAV
NC1-HW	VAV-28	28, 1, 3, VAV
NC1-HW	VAV-29	29, 1, 3, VAV
NC1-HW	VAV-30	30, 1, 3, VAV
NC1-HW	VAV-31	31, 1, 3, VAV
NC1-HW	VAV-32	32, 1, 3, VAV
NC1-HW	VAV-33	33, 1, 3, VAV
NC1-HW	VAV-34	34, 1, 3, VAV
NC1-HW	VAV-35	35, 1, 3, VAV

DRAFT

Building 274		
Points	**Equipment**	**Type**
NC1-HW	VAV-36	36, 1, 3, VAV
NC1-HW	VAV-37	37, 1, 3, VAV
NC1-HW	VAV-38	38, 1, 3, VAV
NC1-HW	VAV-39	39, 1, 3, VAV
NC1-HW	VAV-40	40, 1, 3, VAV
NC1-HW	VAV-41	41, 1, 3, VAV
NC1-HW	DC-6	64, 1, 3, UNT
NC1-HW	AHU-1	44, 1, 3, AHU
NC1-HW	AHU-2	45, 1, 3, AHU
NC1-HW	AHU-3	46, 1, 3, UNT
NC1-HW	AHU-4	47, 1, 3, UNT
NC1-HW	AHU-5	48, 1, 3, UNT
NC1-HW	AH-1	49, 1, 3, AHU
NC1-HW	AH-2	50, 1, 3, AHU
NC1-HW	AH-3	51, 1, 3, AHU
NC1-HW	AH-4	52, 1, 3, AHU
NC1-HW	AH-5	53, 1, 3, AHU
NC1-HW	AH-6	54, 1, 3, AHU
NC1-HW	UNT-55	56, 1, 3, UNT
NC1-HW	AHU-6	65, 1, 3, UNT
NC1-HW	ACC-1	66, 1, 3, UNT
NC1-HW	DX-67	67, 1, 3, DX9100
NC1-HW	XT-68	68, 1, 3, XT9100
NC1-HW	VND-69	69, 1, 3, VND
CS	AHU-5	CSAHU5
BD	AHU-5	AHU5_ALM
BI	AHU-5	SFANSTA
JCB	AHU-5	AHUCON
BO	AHU-5	AH5COMP
BO	AHU-5	EF15SS
BO	AHU-5	AHU5SS
AD	850407D	AIRCHANG
AD	850407D	ROOM_VOL
AD	850407D	ROOM_TMP
AD	850407D	CFM_SUP
AD	850407D	ROOM_EXH
AD	850407D	SUP-EXH
JCB	850407D	SUP_EXH

DRAFT

Building 274		
Points	**Equipment**	**Type**
JCB	850407D	AIR_EXCH
AD	850407D	ROOM_HUM
AD	850407C	AIRCHANG
AD	850407C	ROOM_VOL
AD	850407C	ROOM_TMP
AD	850407C	CFM_SUP
AD	850407C	ROOM_EXH
AD	850407C	SUP-EXH
JCB	850407C	SUP_EXH
JCB	850407C	AIR_EXCH
AD	850407C	ROOM_HUM
AD	850403D	AIRCHANG
AD	850403D	ROOM_VOL
AD	850403D	ROOM_TMP
AD	850403D	CFM_SUP
JCB	850403D	AIR_EXCH
AD	850403D	ROOM_EXH
AD	850403D	SUP-EXH
JCB	850403D	SUP_EXH
AD	850403D	ROOM_HUM
AD	850403C	AIRCHANG
AD	850403C	ROOM_VOL
AD	850403C	ROOM_TMP
AD	850403C	CFM_SUP
JCB	850403C	AIR_EXCH
AD	850403C	ROOM_EXH
AD	850403C	SUP-EXH
JCB	850403C	SUP_EXH
AD	850403C	ROOM_HUM
AD	850403J	AIRCHANG
AD	850403J	ROOM_VOL
AD	850403J	ROOM_TMP
AD	850403J	ROOM_HUM
AD	850403J	CFM_SUP
JCB	850403J	AIR_EXCH
AD	850403J	ROOM_EXH
AD	850403J	SUP-EXH
JCB	850403J	SUP_EXH

DRAFT

Building 274		
Points	**Equipment**	**Type**
AD	850403M	AIRCHANG
AD	850403M	ROOM_VOL
AD	850403M	ROOM_TMP
AD	850403M	CFM_SUP
JCB	850403M	AIR_EXCH
AD	850403M	ROOM_EXH
AD	850403M	SUP-EXH
JCB	850403M	SUP_EXH
AD	850403M	ROOM_HUM
AD	850403N	AIRCHANG
AD	850403N	ROOM_VOL
AD	850403N	ROOM_TMP
AD	850403N	CFM_SUP
JCB	850403N	AIR_EXCH
AD	850403N	ROOM_EXH
AD	850403N	SUP-EXH
JCB	850403N	SUP_EXH
AD	850403N	ROOM_HUM
AD	850421	AIRCHANG
AD	850421	ROOM_VOL
AD	850421	ROOM_TMP
AD	850421	CFM_SUP
JCB	850421	AIR_EXCH
AD	850421	ROOM_EXH
AD	850421	SUP-EXH
JCB	850421	SUP_EXH
AD	850421	ROOM_HUM
AD	850403E	AIRCHANG
AD	850403E	ROOM_VOL
AD	850403E	ROOM_TMP
AD	850403E	CFM_SUP
JCB	850403E	AIR_EXCH
AD	850403E	ROOM_EXH
AD	850403E	SUP-EXH
JCB	850403E	SUP_EXH
AD	850403E	ROOM_HUM
AD	850405A	AIRCHANG
AD	850405A	ROOM_VOL

DRAFT

Building 274		
Points	**Equipment**	**Type**
AD	850405A	ROOM_TMP
AD	850405A	CFM_SUP
AD	850405A	ROOM_EXH
AD	850405A	SUP-EXH
JCB	850405A	SUP_EXH
JCB	850405A	AIR_EXCH
AD	850405A	ROOM_HUM
AD	850403K	AIRCHANG
AD	850403K	ROOM_VOL
AD	850403K	ROOM_TMP
AD	850403K	CFM_SUP
JCB	850403K	AIR_EXCH
AD	850403K	ROOM_EXH
AD	850403K	SUP-EXH
JCB	850403K	SUP_EXH
AD	850403K	ROOM_HUM
AD	850403P	AIRCHANG
AD	850403P	ROOM_VOL
AD	850403P	ROOM_TMP
AD	850403P	ROOM_HUM
AD	850403P	CFM_SUP
JCB	850403P	AIR_EXCH
AD	850403P	ROOM_EXH
AD	850403P	SUP-EXH
JCB	850403P	SUP_EXH
AD	850423B	AIRCHANG
AD	850423B	ROOM_VOL
AD	850423B	ROOM_TMP
JCB	850423B	AIR_EXCH
AD	850423B	CFM_SUP
AD	850423B	ROOM_EXH
AD	850423B	SUP-EXH
JCB	850423B	SUP_EXH
AD	850423B	ROOM_HUM
AD	850423A	AIRCHANG
AD	850423A	ROOM_VOL
AD	850423A	ROOM_TMP
JCB	850423A	AIR_EXCH

DRAFT

Building 274		
Points	**Equipment**	**Type**
AD	850423A	CFM_SUP
AD	850423A	ROOM_EXH
AD	850423A	SUP-EXH
JCB	850423A	SUP_EXH
AD	850423A	ROOM_HUM
AD	850403L	AIRCHANG
AD	850403L	ROOM_VOL
AD	850403L	ROOM_TMP
AD	850403L	CFM_SUP
JCB	850403L	AIR_EXCH
AD	850403L	ROOM_EXH
AD	850403L	SUP-EXH
JCB	850403L	SUP_EXH
AD	850403L	ROOM_HUM
AD	850405B	AIRCHANG
AD	850405B	ROOM_VOL
AD	850405B	ROOM_TMP
AD	850405B	ROOM_HUM
JCB	850405B	AIR_EXCH
AD	850405B	ROOM_EXH
AD	850405B	SUP-EXH
JCB	850405B	SUP_EXH
AD	850405B	CFM_SUP
AD	850403F	AIRCHANG
AD	850403F	ROOM_VOL
AD	850403F	CFM_SUP
JCB	850403F	AIR_EXCH
AD	850403F	ROOM_EXH
AD	850403F	SUP-EXH
JCB	850403F	SUP_EXH
AD	850403F	ROOM_TMP
AD	850403F	ROOM_HUM
AD	850403B	AIRCHANG
AD	850403B	ROOM_VOL
AD	850403B	ROOM_TMP
AD	850403B	CFM_SUP
JCB	850403B	AIR_EXCH
AD	850403B	ROOM_EXH

DRAFT

Building 274		
Points	**Equipment**	**Type**
AD	850403B	SUP-EXH
JCB	850403B	SUP_EXH
AD	850403B	ROOM_HUM
AD	850403G	AIRCHANG
AD	850403G	ROOM_VOL
AD	850403G	ROOM_TMP
AD	850403G	CFM_SUP
JCB	850403G	AIR_EXCH
AD	850403G	ROOM_EXH
AD	850403G	SUP-EXH
JCB	850403G	SUP_EXH
AD	850403G	ROOM_HUM
AD	850403A	AIRCHANG
AD	850403A	ROOM_VOL
AD	850403A	ROOM_TMP
AD	850403A	CFM_SUP
JCB	850403A	AIR_EXCH
AD	850403A	ROOM_EXH
AD	850403A	SUP-EXH
JCB	850403A	SUP_EXH
AD	850403A	ROOM_HUM
AD	850403H	AIRCHANG
AD	850403H	ROOM_VOL
AD	850403H	CFM_SUP
JCB	850403H	AIR_EXCH
AD	850403H	ROOM_EXH
AD	850403H	SUP-EXH
JCB	850403H	SUP_EXH
AD	850403H	ROOM_TMP
AD	850403H	ROOM_HUM
CS	969105A	CSVAV4
CS	969105A	CSVAV5
CS	969105A	CSVAV7
CS	969105A	CSVAV10
CS	969105A	CSVAV11
CS	969105A	CSVAV29
CS	969105A	CSVAV30
CS	969105A	CSVAV31

DRAFT

Building 274		
Points	**Equipment**	**Type**
CS	969105A	CSVAV32
CS	969105A	CSVAV33
AI	969105A	VAV4HUM
AI	969105A	VAV5HUM
AI	969105A	VAV7HUM
AI	969105A	VAV10HUM
AI	969105A	VAV11HUM
AI	969105A	VAV29HUM
AI	969105A	VAV31HUM
AI	969105A	VAV30HUM
AI	969105A	VAV32HUM
AI	969105A	VAV33HUM
CS	969105B	CSVAV39
CS	969105B	CSVAV41
CS	969105B	CSVAV40
CS	969105B	CSVAV1
CS	969105B	CSVAV2
CS	969105B	CSVAV3
CS	969105B	CSVAV6
CS	969105B	CSVAV34
CS	969105B	CSVAV35
CS	969105B	CSVAV38
AI	969105B	VAV39HUM
AI	969105B	VAV41HUM
AI	969105B	VAV40HUM
AI	969105B	VAV1HUM
AI	969105B	VAV2HUM
AI	969105B	VAV3HUM
AI	969105B	VAV6HUM
AI	969105B	VAV34HUM
AI	969105B	VAV35HUM
AI	969105B	VAV38HUM
AD	850425	AIRCHANG
AD	850425	ROOM_VOL
AD	850425	ROOM_TMP
AD	850425	ROOM_HUM
AD	850425	CFM_SUP
JCB	850425	AIR_EXCH

DRAFT

Building 274		
Points	**Equipment**	**Type**
AD	850425	SUP-EXH
AD	850425	ROOM_EXH
JCB	850425	SUP_EXH
JCB	HUM_CSO	HUMCON
CS	HUM_CSO	AH_1
CS	HUM_CSO	AH-2
CS	HUM_CSO	AH-3
CS	HUM_CSO	AH-4
CS	HUM_CSO	AH-5
CS	HUM_CSO	AH-6
CS	850429	CSVAV12
CS	850429	CSVAV13
CS	850429	CSVAV14
CS	850429	CSVAV15
CS	850429	CSVAV16
AI	850429	PREPHUM
AI	850429	RECOVHUM
AI	850429	OR-S-HUM
AI	850429	ORNS-HUM
AI	AHU-1	OAT
AI	AHU-1	SA-TEMP
BO	AHU-1	AHU1SS
BI	AHU-1	SFST1
BO	AHU-1	EF1SS
BI	AHU-1	EF1STA
AI	AHU-1	STPRES1
BI	AHU-1	PREFILT
BI	AHU-1	FINALFIL
JCB	AHU-1	CRITLOAD
JCB	AHU-1	ALARM
JCB	AHU-1	AH1_2SWT
BD	AHU-1	CRITBD
BD	AHU-1	MAINT-SD
BO	AHU-1	DA-5
BO	AHU-1	DA-4
BO	AHU-1	DA-7
BO	AHU-1	DA-8
JCB	AHU-1	AHU1CON

DRAFT

Building 274		
Points	**Equipment**	**Type**
AOS	AHU-1	CLG-VLV
CS	AHU-1	AHU-1-CS
AI	AHU-2	SA-TEMP
AI	AHU-2	PRE-HEAT
BO	AHU-2	AHU2SS
BI	AHU-2	SFST2
BI	AHU-2	EF2STA
AD	AHU-2	EF2HIDEL
BI	AHU-2	PREFIL
BI	AHU-2	FINALFIL
AI	AHU-2	STPRES2
AI	AHU-2	STPRES3
BO	AHU-2	EXF2HIGH
JCB	AHU-2	EF1-2CON
JCB	AHU-2	ALARM
BO	AHU-2	DA-3
BO	AHU-2	DA-6
AOS	AHU-2	CLG-VLV
AI	AHU-2	Static-P
CS	AHU-2	CS-AHU-2
BO	CHILLER	SYS-EN
BO	CHILLER	CH1-EN
AI	CHILLER	CHWS-T
AI	CHILLER	CHWR-T
BO	CHILLER	CHWP1-C
BI	CHILLER	CHWP1-S
BO	CHILLER	CHWP2-C
BI	CHILLER	CHWP2-S
AI	CHILLER	CCHWS-T
AI	CHILLER	ACHWR-1
AI	CHILLER	ACHWR-2
AI	CHILLER	PMP-T
BO	CHILLER	UH-C
AOS	CHILLER	HTG-SP
AOS	CHILLER	OA-T
AOS	CHILLER	OAEN-STP
BO	CHILLER	P2-LEAD
JCB	CHILLER	OAT

DRAFT

Building 274		
Points	**Equipment**	**Type**
CS	AHU-3	CSAHU3
BD	AHU-3	AHU3_ALM
BI	AHU-3	SF3SS
JCB	AHU-3	AHU3C0N
AI	AHU-3	ZONE-T
BD	ALARMS	CIFALARM
BO	ALARMS	BELL
JCB	ALARMS	ALMCON
CS	969103A	CSVAV21
CS	969103A	CSVAV22
CS	969103A	CSVAV23
CS	9169035	CSVAV24
CS	9169035	CSVAV25
CS	9169035	CSVAV26
CS	9169035	CSVAV27
CS	969106	CSVAV28
CS	969106	CSVAV36
CS	969106	CSVAV37
BI	EF-3-8	EF3STA
BI	EF-3-8	EF4STA
BI	EF-3-8	EF5STA
BI	EF-3-8	EF6STA
BI	EF-3-8	EF7STA
BI	EF-3-8	EF8STA
CS	9691030	CSVAV8
CS	9691030	CSVAV9
CS	9691030	VAV-17
CS	9691030	CSVAV18
CS	9691030	CSVAV19
CS	9691030	CSVAV20
AD	BOILERS	BLRTOTAD
BD	BOILERS	BLRTOTBD
BD	BOILERS	LEAD_BLR
BD	BOILERS	MANRESET
BD	BOILERS	BLR_ALRM
AD	BOILERS	LEDBLRSP
AD	BOILERS	LAGBLRSP
AI	BOILERS	STMPRS

DRAFT

Building 274		
Points	**Equipment**	**Type**
BO	BOILERS	BLR2SS
BO	BOILERS	BLR1SS
JCB	BOILERS	BLRLDLG
JCB	BOILERS	BLRCON
AD	850418	AIRCHANG
AD	850418	ROOM_VOL
AD	850418	CFM_SUP
AD	850418	ROOM_TMP
JCB	850418	AIR_EXCH
AD	850418	ROOM_EXH
AD	850418	SUP-EXH
JCB	850418	SUP_EXH
AD	850203	AIRCHANG
AD	850203	ROOM_VOL
AD	850203	CFM_SUP
AD	850203	ROOM_TMP
JCB	850203	AIR_EXCH
AD	850203	ROOM_EXH
AD	850203	SUP-EXH
JCB	850203	SUP_EXH
AD	850211	AIRCHANG
AD	850211	ROOM_VOL
AD	850211	CFM_SUP
AD	850211	ROOM_TMP
JCB	850211	AIR_EXCH
AD	850211	ROOM_EXH
AD	850211	SUP-EXH
JCB	850211	SUP_EXH
AD	850209	AIRCHANG
AD	850209	ROOM_VOL
AD	850209	CFM_SUP
AD	850209	ROOM_TMP
JCB	850209	AIR_EXCH
AD	850209	ROOM_EXH
AD	850209	SUP-EXH
JCB	850209	SUP_EXH
AD	850303	AIRCHANG
AD	850303	ROOM_VOL

DRAFT

Building 274		
Points	**Equipment**	**Type**
AD	850303	CFM_SUP
AD	850303	ROOM_TMP
JCB	850303	AIR_EXCH
AD	850303	ROOM_EXH
AD	850303	SUP-EXH
JCB	850303	SUP_EXH
AD	850430	AIRCHANG
AD	850430	ROOM_VOL
AD	850430	CFM_SUP
AD	850430	ROOM_TMP
JCB	850430	AIR_EXCH
AD	850430	ROOM_EXH
AD	850430	SUP-EXH
JCB	850430	SUP_EXH
AD	850205	AIRCHANG
AD	850205	ROOM_VOL
AD	850205	CFM_SUP
AD	850205	ROOM_TMP
JCB	850205	AIR_EXCH
AD	850205	ROOM_EXH
AD	850205	SUP-EXH
JCB	850205	SUP_EXH
CS	AHU-4	CSAHU4
BD	AHU-4	AHU4_ALM
BI	AHU-4	SFANSTA
JCB	AHU-4	AHU4CON
AD	850407B	AIRCHANG
AD	850407B	ROOM_VOL
AD	850407B	ROOM_TMP
AD	850407B	ROOM_HUM
AD	850407B	DISC_HUM
AD	850407B	CFM_SUP
JCB	850407B	AIR_EXCH
AD	850407B	ROOM_EXH
AD	850407B	SUP-EXH
JCB	850407B	SUP_EXH
AD	850407A	AIRCHANG
AD	850407A	ROOM_VOL

DRAFT

Building 274		
Points	**Equipment**	**Type**
AD	850407A	ROOM_TMP
AD	850407A	ROOM_HUM
AD	850407A	DISC_HUM
AD	850407A	CFM_SUP
JCB	850407A	AIR_EXCH
AD	850407A	ROOM_EXH
AD	850407A	SUP-EXH
JCB	850407A	SUP_EXH
AD	850412A	AIRCHANG
AD	850412A	ROOM_VOL
AD	850412A	ROOM_TMP
JCB	850412A	AIR_EXCH
AD	850412A	CFM_SUP
AD	850412A	SUP-EXH
AD	850412A	ROOM_EXH
JCB	850412A	SUP_EXH
AD	BLDG-CFM	CFM-R01
AD	BLDG-CFM	CFM-R02
AD	BLDG-CFM	CFM-R03
AD	BLDG-CFM	CFM-R04
AD	BLDG-CFM	CFM-R05
AD	BLDG-CFM	CFM-R06
AD	BLDG-CFM	CFM-R07
AD	BLDG-CFM	CFM-R08
AD	BLDG-CFM	CFM-RM09
AD	BLDG-CFM	CFM-RM10
AD	BLDG-CFM	CFM-R11
AD	BLDG-CFM	CFM-R12
AD	BLDG-CFM	CFM-R13
AD	BLDG-CFM	CFM-R14
AD	BLDG-CFM	CFM-R15
AD	BLDG-CFM	CFM-R16
AD	BLDG-CFM	CFM-R17
AD	BLDG-CFM	CFM-R18
AD	BLDG-CFM	CFM-R19
AD	BLDG-CFM	CFM-R20
AD	BLDG-CFM	CFM-VAV8
AD	BLDG-CFM	CFM-VAV9

DRAFT

Building 274		
Points	**Equipment**	**Type**
AD	BLDG-CFM	CFMVAV12
AD	BLDG-CFM	CFMVAV13
AD	BLDG-CFM	CFMVAV14
AD	BLDG-CFM	CFMVAV15
AD	BLDG-CFM	CFMVAV16
AD	BLDG-CFM	CFMVAV17
AD	BLDG-CFM	CFMVAV18
AD	BLDG-CFM	CFMVAV19
AD	BLDG-CFM	CFMVAV20
AD	BLDG-CFM	CFMVAV21
AD	BLDG-CFM	CFMVAV22
AD	BLDG-CFM	CFMVAV23
AD	BLDG-CFM	CFMVAV25
AD	BLDG-CFM	CFMVAV24
BD	HX-1-2	P-1-2LED
BD	HX-1-2	PMP1-2EN
BD	HX-1-2	HX1_2RST
BO	HX-1-2	P1SS
BI	HX-1-2	P1STA
BO	HX-1-2	P2SS
BI	HX-1-2	P2STA
AI	HX-1-2	HWST
AI	HX-1-2	HWRT
BI	HX-1-2	HX1FLOST
BI	HX-1-2	HX2FLOST
PIDL	HX-1-2	HX1SETPT
AOD	HX-1-2	HX1VALVE
PIDL	HX-1-2	HX2SETPT
AOD	HX-1-2	HX2VALVE
AD	HX-1-2	PMP1TIME
AD	HX-1-2	PMP2TIME
AI	HX-1-2	BYPASS
PIDL	HX-1-2	BYPASPID
AOD	HX-1-2	BPVLV
JCB	HX-1-2	BYPASCON
AD	HX-1-2	HXTOTTIM
BD	HX-1-2	HX_TOTBD
JCB	HX-1-2	HX1-2LED

DRAFT

Building 274		
Points	**Equipment**	**Type**
JCB	HX-1-2	PMP1_2SS
JCB	HX-1-2	HX1_2CON
BD	HX-3-4	P-3-4LED
BD	HX-3-4	PMP3-4EN
BD	HX-3-4	HX3_4RES
BO	HX-3-4	P3SS
BI	HX-3-4	P3STA
BO	HX-3-4	P4SS
BI	HX-3-4	P4STA
BI	HX-3-4	HX3FLOST
BI	HX-3-4	HX4FLOST
AI	HX-3-4	HGWS
AI	HX-3-4	HGWR
PIDL	HX-3-4	HX3SETPT
AOD	HX-3-4	HX3VALVE
PIDL	HX-3-4	HX4SETPT
AOD	HX-3-4	HX4VALVE
AD	HX-3-4	PMP3TIME
AD	HX-3-4	PMP4TIME
AD	HX-3-4	HX_TOTAD
BD	HX-3-4	HX_TOTBD
JCB	HX-3-4	HX3-4LED
AD	HX-3-4	OA-P-SP
JCB	HX-3-4	P3-4TSS
JCB	HX-3-4	PMP3_4SS
JCB	HX-3-4	HX3_4CON
BI	ACC-1	CHLR-S
AI	ACC-1	CWS-TEMP
BI	ACC-1	CW-FLOW
BI	ACC-1	CWP8-S
BI	ACC-1	TWS-ALM
AI	ACC-1	OA-TEMP
AD	ACC-1	OA-T-SP
CS	ACC-1	ACC1-CS
BI	AHU-6	TSWI-S
BO	AHU-6	SF-CMD
BI	AHU-6	SF-STAT
BO	AHU-6	EF17-CMD

DRAFT

Building 274		
Points	**Equipment**	**Type**
BI	AHU-6	EF17-STA
AI	AHU-6	ZN-TEMP
AI	AHU-6	REM-SETP
AI	AHU-6	SA-TEMP
AI	AHU-6	PHT-TEMP
BI	AHU-6	PFLTR-S
BI	AHU-6	LT-ALM
BI	AHU-6	SA-SMOKE
AOS	AHU-6	PHT-VLV
AOS	AHU-6	HTG-VLV
AOS	AHU-6	CLG-VLV
JCB	AHU-6	INTLKPRC
CS	AHU-6	AHU-6CS
JCB	CLNSTM	STM-ALM
BI	CLNSTM	HIGH-WTR
BD	CLNSTM	CSTMALM
BI	CLNSTM	Low-Wtr
BI	CLNSTM	Low-Pres
BI	CLNSTM	HI-Press
MC	CLNSTM	CLNSTM-A
SLAVE		CS, AHU-1, CS-AHU1, CLNSTM, CLNSTM-A
SLAVE		CS, AHU-2, AHU-2, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-1, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-2, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-3, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-3, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-4, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-5, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-6, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-1, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-2, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-3, CLNSTM, CLNSTM-A

DRAFT

Building 274		
Points	**Equipment**	**Type**
SLAVE		CS, HUM_CSO, AH-4, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-5, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-6, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-1, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-2, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-3, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-4, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-5, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-6, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-1, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-2, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-3, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-4, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-5, CLNSTM, CLNSTM-A
SLAVE		CS, HUM_CSO, AH-6, CLNSTM, CLNSTM-A
AOS	CLNSTM	STM-STPT
AI	CLNSTM	STM-P
AOS	CLNSTM	STM-VLV
BO	CHILDATA	CH1-RUN
BO	CHILDATA	CH1-ALM
AOS	CHILDATA	EW-T
AOS	CHILDATA	LW-T
AOS	CHILDATA	SYS1-RUN
AOS	CHILDATA	SYS2-RUN
AOS	CHILDATA	SYS1-FLA
AOS	CHILDATA	SYS2-FLA
BO	CHILDATA	EP-S
BO	CHILDATA	EH-S
BO	CHILDATA	CMP1-S
BO	CHILDATA	CMP2-S
BO	CHILDATA	MODE

DRAFT

Building 274		
Points	**Equipment**	**Type**
AOS	CHILDATA	OA-T

Building 276		
Points	**Equipment**	**Type**
NC-10		**Network controller**
NC10HRDW	UNT1	2, 1, 3, UNT
NC10HRDW	UNT3	3, 1, 3, UNT
NC10HRDW	UNT4	4, 1, 3, UNT
NC10HRDW	UNT5	5, 1, 3, UNT
NC10HRDW	UNT6	6, 1, 3, UNT
NC10HRDW	UNT7	7, 1, 3, UNT
NC10HRDW	UNT8	8, 1, 3, UNT
NC10HRDW	UNT9	9, 1, 3, UNT
NC10HRDW	AHU10	10, 1, 3, AHU
NC10HRDW	UNT11	11, 1, 3, UNT
NC10HRDW	UNT12	12, 1, 3, UNT
NC10HRDW	DX13	13, 1, 3, DX9100
BO	CWLOOP	PLANT-EN
BO	CWLOOP	P3-C
BI	CWLOOP	P3-S
BO	CWLOOP	ACC1-EN
AI	CWLOOP	CHWS-T
AI	CWLOOP	CHWR-T
BI	CWLOOP	CHWS-FS
BI	CWLOOP	ACC1-LP
BI	CWLOOP	ACC1-SP
BO	CWLOOP	HT-EN
CS	CWLOOP	CWS
AD	CWLOOP	ENAB-STP
AD	CWLOOP	OA-T
JCB	CWLOOP	CHWS
CS	AH8	CS-AHU8
BO	AH8	HTG-VLV

DRAFT

Building 276		
Points	**Equipment**	**Type**
BO	AH8	SF-C
BO	AH8	OADPR-C
AI	AH8	DA-T
AI	AH8	ZN-T
BI	AH8	SF-S
BI	AH8	FILTER-S
BI	AH8	SA-SD
AOS	AH8	HTG-F&B
BO	AH8	DX1-C
BI	AH8	DX1-S
JCB	AH8	AH8INTLK
CS	AH6	CS-AHU6
AI	AH6	ZN-T
AI	AH6	MA-T
AI	AH6	DA-T
BO	AH6	SF-C
BI	AH6	SF-S
BI	AH6	LT-A
BI	AH6	SA-SD
AOS	AH6	DPR-C
AOS	AH6	PH-VLV
AOS	AH6	CLG-VLV
JCB	AH6	UNOC-INT
CS	AH1	CS-AHU1
AI	AH1	ZN-T
AI	AH1	DA-T
AI	AH1	MA-T
BO	AH1	SF-C
BI	AH1	SF-S
BI	AH1	Filter-S
BI	AH1	SA-SD
BI	AH1	DX1-S
BO	AH1	DX1-C
AOS	AH1	HTG-VLV
BO	AH1	OADPR-C
JCB	AH1	AH1-5
CS	AH9	CS-AHU9
AI	AH9	ZN-T

DRAFT

Building 276		
Points	**Equipment**	**Type**
AI	AH9	ZN-T2
AI	AH9	DA-T
BO	AH9	SF-C
BI	AH9	SF-S
BI	AH9	LT-ALM
BI	AH9	SA-SD
BI	AH9	FILTER-S
BO	AH9	DX-CMD
BI	AH9	DX1-S
AOS	AH9	HT-VLV1
AOS	AH9	HT-VLV2
CS	HWLOOP	CS-HWTR
BO	HWLOOP	P1-C
BI	HWLOOP	P1-S
AI	HWLOOP	HWS-T
AI	HWLOOP	HWR-T
AI	HWLOOP	OA-T
AOS	HWLOOP	STM-VLV
CS	AH2	CS-AHU2
AI	AH2	ZN-T
AI	AH2	DA-T
AI	AH2	MA-T
BO	AH2	SF-C
BI	AH2	SF-S
BI	AH2	FILTER-S
BI	AH2	SA-SD
BI	AH2	DX1-S
BO	AH2	DX1-C
AOS	AH2	HTG-VLV
BO	AH2	OADPR-C
CS	AH3	CS-AHU3
AI	AH3	ZN-T
AI	AH3	DA-T
AI	AH3	MA-T
BI	AH3	SF-S
BO	AH3	SF-C
BI	AH3	FILTER-S
BI	AH3	SA-SD

DRAFT

Building 276		
Points	**Equipment**	**Type**
BI	AH3	DX1-S
BO	AH3	DX1-C
AOS	AH3	HTG-VLV
BO	AH3	OADPR-C
BI	AH3	EF2-S
BO	AH3	EF2-C
CS	AH4	CS-AHU4
AI	AH4	ZN-T
AI	AH4	DA-T
AI	AH4	MA-T
BI	AH4	SF-S
BO	AH4	SF-C
BI	AH4	FILTER-S
BI	AH4	SA-SD
AOS	AH4	HTG-VLV
BI	AH4	DX1-S
BO	AH4	DX1-C
BO	AH4	OADPR-C
CS	AH5	CS-AHU5
AI	AH5	ZN-T
AI	AH5	DA-T
AI	AH5	MA-T
BI	AH5	SF-S
BI	AH5	FILTER-S
BI	AH5	SA-SD
BI	AH5	DX1-S
AOS	AH5	HTG-VLV
BO	AH5	DX1-C
BO	AH5	SF-C
BO	AH5	OADPR-C
BD	AH5	AHU-5a
CS	AH5	CS-AHU5A
AI	AH5	ZN-T-A
AI	AH5	DA-T-A
AI	AH5	MA-T-A
BI	AH5	SF-S-A
BI	AH5	FLT-S-A
BI	AH5	SA-SD-A

DRAFT

Building 276		
Points	**Equipment**	**Type**
BI	AH5	DX1-S-A
AOS	AH5	HTG-V-A
BO	AH5	DX1-C-A
BO	AH5	SF-C-A
BO	AH5	DPR-C-A
CS	AH7	CS-AHU7
AI	AH7	ZN-T
AI	AH7	MA-T
AI	AH7	DA-T
BI	AH7	SF-S
BI	AH7	SA-SD
BI	AH7	LT-A
AOS	AH7	DPR-C
AOS	AH7	HTG-VLV
AOS	AH7	CLG-VLV
BO	AH7	SF-C
AI	UH	UH-T
BO	UH	UH-C
BI	UH	UH-S
BO	EXFAN	EF1-C
BI	EXFAN	EF1-S
AI	EXFAN	EF3ZN-T
BO	EXFAN	EX3-C
BI	EXFAN	EF3-S
BO	EXFAN	EF4-C
BI	EXFAN	EF4-S
BO	EXFAN	EF5-C
BI	EXFAN	EF5-S
BI	EXFAN	EF6-S
BI	EXFAN	EFS7-S
AI	EXFAN	EF4ZN-T
JCB	EXFAN	EX-LOOP

DRAFT

Building 282		
Points	**Equipment**	**Type**
NC-1		**Network controller**
NC-1HW	AHU-2	46, 1, 3, AHU
NC-1HW	AHU-3	73, 1, 3, AHU
NC-1HW	AHU-7	129, 1, 3, AHU
NC-1HW	TABU1-2	2, 1, 3, VAV
NC-1HW	TABU1-3	3, 1, 3, VAV
NC-1HW	TABU1-4	4, 1, 3, VAV
NC-1HW	TABU1-5	5, 1, 3, VAV
NC-1HW	TABU1-6	6, 1, 3, VAV
NC-1HW	TABU1-7	7, 1, 3, VAV
NC-1HW	TABU1-9	9, 1, 3, VAV
NC-1HW	TABU1-10	10, 1, 3, VAV
NC-1HW	TABU1-11	11, 1, 3, VAV
NC-1HW	TABU1-12	12, 1, 3, VAV
NC-1HW	TABU1-13	13, 1, 3, VAV
NC-1HW	TABU1-14	14, 1, 3, VAV
NC-1HW	TABU1-15	15, 1, 3, VAV
NC-1HW	TABU1-16	16, 1, 3, VAV
NC-1HW	TABU1-17	17, 1, 3, VAV
NC-1HW	TABU1-18	18, 1, 3, VAV
NC-1HW	TABU1-19	19, 1, 3, VAV
NC-1HW	TABU1-20	20, 1, 3, VAV
NC-1HW	TABU1-21	21, 1, 3, VAV
NC-1HW	TABU1-22	22, 1, 3, VAV
NC-1HW	TABU1-23	23, 1, 3, VAV
NC-1HW	TABU1-24	24, 1, 3, VAV
NC-1HW	TABU1-25	25, 1, 3, VAV
NC-1HW	TABU1-26	26, 1, 3, VAV
NC-1HW	TABU1-27	27, 1, 3, VAV
NC-1HW	TABU1-28	28, 1, 3, VAV
NC-1HW	TABU2-32	32, 1, 3, VAV
NC-1HW	TABU2-33	33, 1, 3, VAV
NC-1HW	TABU2-34	34, 1, 3, VAV
NC-1HW	TABU2-35	35, 1, 3, VAV
NC-1HW	TABU2-36	36, 1, 3, VAV
NC-1HW	TABU2-37	37, 1, 3, VAV
NC-1HW	TABU2-38	38, 1, 3, VAV

DRAFT

Building 282		
Points	**Equipment**	**Type**
NC-1HW	TABU2-39	39, 1, 3, VAV
NC-1HW	TABU2-40	40, 1, 3, VAV
NC-1HW	TABU2-41	41, 1, 3, VAV
NC-1HW	TABU2-42	42, 1, 3, VAV
NC-1HW	TABU2-43	43, 1, 3, VAV
NC-1HW	TABU2-44	44, 1, 3, VAV
NC-1HW	TABU2-45	45, 1, 3, VAV
NC-1HW	TABU2-47	47, 1, 3, VAV
NC-1HW	TABU2-48	48, 1, 3, VAV
NC-1HW	TABU2-49	49, 1, 3, VAV
NC-1HW	TABU2-50	50, 1, 3, VAV
NC-1HW	TABU2-51	51, 1, 3, VAV
NC-1HW	TABU2-52	52, 1, 3, VAV
NC-1HW	TABU2-53	53, 1, 3, VAV
NC-1HW	TABU2-54	54, 1, 3, VAV
NC-1HW	TABU2-55	55, 1, 3, VAV
NC-1HW	TABU2-56	56, 1, 3, VAV
NC-1HW	TABU2-57	57, 1, 3, VAV
NC-1HW	TABU2-58	58, 1, 3, VAV
NC-1HW	TABU3-59	59, 1, 3, VAV
NC-1HW	TABU3-60	60, 1, 3, VAV
NC-1HW	TABU3-61	61, 1, 3, VAV
NC-1HW	TABU3-62	62, 1, 3, VAV
NC-1HW	TABU3-63	63, 1, 3, VAV
NC-1HW	TABU3-64	64, 1, 3, VAV
NC-1HW	TABU3-65	65, 1, 3, VAV
NC-1HW	TABU3-66	66, 1, 3, VAV
NC-1HW	TABU3-67	67, 1, 3, VAV
NC-1HW	TABU3-68	68, 1, 3, VAV
NC-1HW	TABU3-69	69, 1, 3, VAV
NC-1HW	TABU3-70	70, 1, 3, VAV
NC-1HW	TABU3-71	71, 1, 3, VAV
NC-1HW	TABU3-72	72, 1, 3, VAV
NC-1HW	TABU3-74	74, 1, 3, VAV
NC-1HW	TABU3-75	75, 1, 3, VAV
NC-1HW	TABU3-76	76, 1, 3, VAV
NC-1HW	TABU3-77	77, 1, 3, VAV
NC-1HW	TABU3-78	78, 1, 3, VAV

DRAFT

Building 282		
Points	**Equipment**	**Type**
NC-1HW	TABU3-79	79, 1, 3, VAV
NC-1HW	TABU3-80	80, 1, 3, VAV
NC-1HW	TABU3-81	81, 1, 3, VAV
NC-1HW	TABU3-82	82, 1, 3, VAV
NC-1HW	TABU3-83	83, 1, 3, VAV
NC-1HW	TABU3-84	84, 1, 3, VAV
NC-1HW	TABU3-85	85, 1, 3, VAV
NC-1HW	FCU1-HW	30, 1, 3, UNT
NC-1HW	FCU2-HW	31, 1, 3, UNT
NC-1HW	PLT_UNT	1, 1, 3, UNT
NC-1HW	OAMIN-1	86, 1, 3, VAV
NC-1HW	OAMIN-2	87, 1, 3, VAV
NC-1HW	OAMIN-3	88, 1, 3, VAV
CS	1ST_FL	BOX1-1
CS	1ST_FL	BOX2-1
CS	1ST_FL	BOX3-1
CS	1ST_FL	BOX4-1
CS	1ST_FL	BOX5-1
CS	1ST_FL	BOX6-1
CS	1ST_FL	BOX7-1
CS	1ST_FL	BOX8-1
CS	1ST_FL	BOX9-1
CS	1ST_FL	BOX10-1
CS	1ST_FL	BOX11-1
CS	1ST_FL	BOX12-1
CS	1ST_FL	BOX13-1
CS	1ST_FL	BOX14-1
CS	1ST_FL	BOX15-1
CS	1ST_FL	BOX16-1
CS	1ST_FL	BOX17-1
CS	1ST_FL	BOX18-1
CS	1ST_FL	BOX19-1
CS	1ST_FL	BOX20-1
CS	1ST_FL	BOX21-1
CS	1ST_FL	BOX22-1
CS	1ST_FL	BOX23-1
CS	1ST_FL	BOX24-1
CS	1ST_FL	BOX25-1

DRAFT

Building 282		
Points	**Equipment**	**Type**
CS	1ST_FL	BOX26-1
JCB	1ST_FL	SELECT
JCB	1ST_FL	SUMWIN
JCB	1ST_FL	TABU1-EX
JCB	1ST_FL	SHTDWN1
CS	1ST_FL	BOX27-1
CS	1ST_FL	BOX28-1
BI	EXFANLOB	EXFAN3ST
BI	EXFANLOB	EXFAN4ST
BI	EXFANLOB	EXFAN5ST
BI	EXFANLOB	EXFAN6ST
BI	EXFANLOB	EXFAN7ST
BI	HEATMISC	HTG-HWS1
BI	HEATMISC	HTG-HWS2
BI	HEATMECH	UH1_STAT
BI	HEATMECH	UH2_STAT
BI	HEATMECH	UN3_STAT
BI	HEATLNDR	CUH1STAT
CS	FCU-2	FCU2-CS
AI	FCU-2	TEMP
BO	FCU-2	FAN_SS
AD	FCU-2	HTG-AO
AD	FCU-2	CLG-AO
AD	FCU-2	VLV-CNTL
BI	EXFAN1ST	EXFAN101
BI	EXFAN1ST	EXFAN102
BI	EXFAN1ST	EXFAN103
BI	EXFAN1ST	EXFAN104
BI	EXFAN1ST	EXFAN105
BI	EXFAN1ST	EXFAN106
BI	EXFAN1ST	EXFAN107
BI	EXFAN1ST	EXFAN113
BI	EXFAN1ST	EXFAN114
BI	EXFAN1ST	EXFAN115
BI	EXFAN1ST	EXFAN116
BI	EXFAN1ST	EXFAN117
BI	EXFAN1ST	EXFAN118
BI	EXFAN2ND	EXFAN201

DRAFT

Building 282		
Points	**Equipment**	**Type**
BI	EXFAN2ND	EXFAN202
BI	EXFAN2ND	EXFAN203
BI	EXFAN2ND	EXFAN204
BI	EXFAN2ND	EXFAN205
BI	EXFAN2ND	EXFAN206
BI	EXFAN2ND	EXFAN207
BI	EXFAN2ND	EXFAN213
BI	EXFAN2ND	EXFAN214
BI	EXFAN2ND	EXFAN215
BI	EXFAN2ND	EXFAN216
BI	EXFAN2ND	EXFAN217
BI	EXFAN2ND	EXFAN218
BI	EXFAN3RD	EXFAN301
BI	EXFAN3RD	EXFAN302
BI	EXFAN3RD	EXFAN303
BI	EXFAN3RD	EXFAN304
BI	EXFAN3RD	EXFAN305
BI	EXFAN3RD	EXFAN306
BI	EXFAN3RD	EXFAN307
BI	EXFAN3RD	EXFAN313
BI	EXFAN3RD	EXFAN314
BI	EXFAN3RD	EXFAN315
BI	EXFAN3RD	EXFAN316
BI	EXFAN3RD	EXFAN317
BI	EXFAN3RD	EXFAN318
BO	AHU-7	SHUTDOWN
BI	AHU-7	Status
AI	AHU-7	DIS_TEMP
AI	AHU-7	RET_TEMP
CS	AHU-7	AHU7-CS
AOS	AHU-7	DPR-CONT
AD	AHU-7	HC_VLV
BI	AHU-7	Filter
BD	AHU-7	SUM_WIN
AI	AHU-7	Fan_Curr
JCB	AHU-7	AH7DAM
AD	MIS_STAT	OA-T
ACM	MIS_STAT	BEQ_KW

DRAFT

Building 282		
Points	**Equipment**	**Type**
CS	FCU-1	FCU1-CS
AI	FCU-1	TEMP
BO	FCU-1	FAN_SS
AD	FCU-1	HTG-AO
AD	FCU-1	VLV-CNTR
AD	FCU-1	CLG-AO
JCB	FCU-1	FCU-1
BO	AHU-1	SHUTDOWN
BD	AHU-1	Status
BI	AHU-1	Filter
BI	AHU-1	P_4Sts
AI	AHU-1	DA_Temp
AI	AHU-1	Ret_Tmp
AI	AHU-1	Stc_P_1
AI	AHU-1	Fan_Curr
AOS	AHU-1	SF_Ctrl
AOS	AHU-1	Htg_Clg
CS	AHU-1	AHU1-CS
CS	AHU-1	OAMIN-1
BD	AHU-1	SUM_WIN
JCB	AHU-1	AH1CUR
BO	AHU-3	SHUTDOWN
BI	AHU-3	Status
BI	AHU-3	Filter
AI	AHU-3	DA_Temp
AI	AHU-3	Ret_Tmp
AI	AHU-3	Stc_P_1
AI	AHU-3	Fan_Curr
AOS	AHU-3	SF_Ctrl
AOS	AHU-3	Htg_Clg
CS	AHU-3	AHU3-CS
CS	AHU-3	OAMIN-3
BD	AHU-3	SUM_WIN
JCB	AHU-3	AH3CUR
BO	AHU-2	SHUTDOWN
BI	AHU-2	Status
BI	AHU-2	Filter
AI	AHU-2	DA_Temp

DRAFT

Building 282		
Points	**Equipment**	**Type**
AI	AHU-2	Ret_Tmp
AI	AHU-2	Stc_P_1
AI	AHU-2	Fan_Curr
AOS	AHU-2	SF_Ctrl
AOS	AHU-2	Htg_Clg
CS	AHU-2	AHU2-CS
CS	AHU-2	OAMIN-2
BD	AHU-2	SUM_WIN
JCB	AHU-2	AHU2CUR
CS	2ND_FL	BOX1-2
CS	2ND_FL	BOX2-2
CS	2ND_FL	BOX3-2
CS	2ND_FL	BOX4-2
CS	2ND_FL	BOX5-2
CS	2ND_FL	BOX6-2
CS	2ND_FL	BOX7-2
CS	2ND_FL	BOX8-2
CS	2ND_FL	BOX9-2
CS	2ND_FL	BOX10-2
CS	2ND_FL	BOX11-2
CS	2ND_FL	BOX12-2
CS	2ND_FL	BOX13-2
CS	2ND_FL	BOX14-2
CS	2ND_FL	BOX15-2
CS	2ND_FL	BOX16-2
CS	2ND_FL	BOX17-2
CS	2ND_FL	BOX18-2
CS	2ND_FL	BOX19-2
CS	2ND_FL	BOX20-2
CS	2ND_FL	BOX21-2
CS	2ND_FL	BOX22-2
CS	2ND_FL	BOX23-2
CS	2ND_FL	BOX24-2
CS	2ND_FL	BOX25-2
CS	2ND_FL	BOX26-2
JCB	2ND_FL	SELEC2ND
JCB	2ND_FL	TABU2-EX
JCB	2ND_FL	SHTDWN2

DRAFT

Building 282		
Points	**Equipment**	**Type**
CS	3RD_FL	BOX1-3
CS	3RD_FL	BOX2-3
CS	3RD_FL	BOX3-3
CS	3RD_FL	BOX4-3
CS	3RD_FL	BOX5-3
CS	3RD_FL	BOX6-3
CS	3RD_FL	BOX7-3
CS	3RD_FL	BOX8-3
CS	3RD_FL	BOX9-3
CS	3RD_FL	BOX10-3
CS	3RD_FL	BOX11-3
CS	3RD_FL	BOX12-3
CS	3RD_FL	BOX13-3
CS	3RD_FL	BOX14-3
CS	3RD_FL	BOX15-3
CS	3RD_FL	BOX16-3
CS	3RD_FL	BOX17-3
CS	3RD_FL	BOX18-3
CS	3RD_FL	BOX19-3
CS	3RD_FL	BOX20-3
CS	3RD_FL	BOX21-3
CS	3RD_FL	BOX22-3
CS	3RD_FL	BOX23-3
CS	3RD_FL	BOX24-3
CS	3RD_FL	BOX25-3
CS	3RD_FL	BOX26-3
JCB	3RD_FL	3FLRESET
JCB	3RD_FL	TABU3-EX
JCB	3RD_FL	SHTDWN3
AD	NC-1HW	FREE_MEM
(INTENTIOINLY LEFT BLANK) **(CONTINUES ON NEXT PAGE)**		

DRAFT

Building 282		
Points	**Equipment**	**Type**
NC-02		**Network controller**
NC-2HW	AHU-5	N2 DEVICE AHU-5
NC-2HW	AHU-6	N2 DEVICE AHU-6
NC-2HW	TABU4-1	N2 DEVICE VAV
NC-2HW	TABU4-2	N2 DEVICE VAV
NC-2HW	TABU4-3	N2 DEVICE VAV
NC-2HW	TABU4-4	N2 DEVICE VAV
NC-2HW	TABU4-5	N2 DEVICE VAV
NC-2HW	TABU4-6	N2 DEVICE VAV
NC-2HW	TABU4-7	N2 DEVICE VAV
NC-2HW	TABU4-8	N2 DEVICE VAV
NC-2HW	TABU4-9	N2 DEVICE VAV
NC-2HW	TABU4-10	N2 DEVICE VAV
NC-2HW	TABU4-11	N2 DEVICE VAV
NC-2HW	TABU4-12	N2 DEVICE VAV
NC-2HW	TABU4-13	N2 DEVICE VAV
NC-2HW	TABU4-14	N2 DEVICE VAV
NC-2HW	TABU4-16	N2 DEVICE VAV
NC-2HW	TABU4-17	N2 DEVICE VAV
NC-2HW	TABU4-18	N2 DEVICE VAV
NC-2HW	TABU4-19	N2 DEVICE VAV
NC-2HW	TABU4-20	N2 DEVICE VAV
NC-2HW	TABU4-21	N2 DEVICE VAV
NC-2HW	TABU4-22	N2 DEVICE VAV
NC-2HW	TABU4-23	N2 DEVICE VAV
NC-2HW	TABU4-24	N2 DEVICE VAV
NC-2HW	TABU4-25	N2 DEVICE VAV
NC-2HW	TABU4-26	N2 DEVICE VAV
NC-2HW	TABU4-27	N2 DEVICE VAV
NC-2HW	TABU5-28	N2 DEVICE VAV
NC-2HW	TABU5-29	N2 DEVICE VAV
NC-2HW	TABU5-30	N2 DEVICE VAV
NC-2HW	TABU5-31	N2 DEVICE VAV
NC-2HW	TABU5-32	N2 DEVICE VAV
NC-2HW	TABU5-33	N2 DEVICE VAV
NC-2HW	TABU5-34	N2 DEVICE VAV

DRAFT

Building 282		
Points	**Equipment**	**Type**
NC-2HW	TABU5-35	N2 DEVICE VAV
NC-2HW	TABU5-36	N2 DEVICE VAV
NC-2HW	TABU5-37	N2 DEVICE VAV
NC-2HW	TABU5-38	N2 DEVICE VAV
NC-2HW	TABU5-39	N2 DEVICE VAV
NC-2HW	TABU5-40	N2 DEVICE VAV
NC-2HW	TABU5-41	N2 DEVICE VAV
NC-2HW	TABU5-43	N2 DEVICE VAV
NC-2HW	TABU5-44	N2 DEVICE VAV
NC-2HW	TABU5-45	N2 DEVICE VAV
NC-2HW	TABU5-46	N2 DEVICE VAV
NC-2HW	TABU5-47	N2 DEVICE VAV
NC-2HW	TABU5-48	N2 DEVICE VAV
NC-2HW	TABU5-49	N2 DEVICE VAV
NC-2HW	TABU5-50	N2 DEVICE VAV
NC-2HW	TABU5-51	N2 DEVICE VAV
NC-2HW	TABU5-52	N2 DEVICE VAV
NC-2HW	TABU5-53	N2 DEVICE VAV
NC-2HW	TABU5-54	N2 DEVICE VAV
NC-2HW	TABU6-55	N2 DEVICE VAV
NC-2HW	TABU6-56	N2 DEVICE VAV
NC-2HW	TABU6-57	N2 DEVICE VAV
NC-2HW	TABU6-58	N2 DEVICE VAV
NC-2HW	TABU6-59	N2 DEVICE VAV
NC-2HW	TABU6-60	N2 DEVICE VAV
NC-2HW	TABU6-61	N2 DEVICE VAV
NC-2HW	TABU6-62	N2 DEVICE VAV
NC-2HW	TABU6-63	N2 DEVICE VAV
NC-2HW	TABU6-64	N2 DEVICE VAV
NC-2HW	TABU6-65	N2 DEVICE VAV
NC-2HW	TABU6-66	N2 DEVICE VAV
NC-2HW	TABU6-67	N2 DEVICE VAV
NC-2HW	TABU6-68	N2 DEVICE VAV
NC-2HW	TABU6-71	N2 DEVICE VAV
NC-2HW	TABU6-72	N2 DEVICE VAV
NC-2HW	TABU6-73	N2 DEVICE VAV
NC-2HW	TABU6-74	N2 DEVICE VAV
NC-2HW	TABU6-75	N2 DEVICE VAV

DRAFT

Building 282		
Points	**Equipment**	**Type**
NC-2HW	TABU6-76	N2 DEVICE VAV
NC-2HW	TABU6-77	N2 DEVICE VAV
NC-2HW	TABU6-78	N2 DEVICE VAV
NC-2HW	TABU6-79	N2 DEVICE VAV
NC-2HW	TABU6-80	N2 DEVICE VAV
NC-2HW	TABU6-81	N2 DEVICE VAV
NC-2HW	TABU6-82	N2 DEVICE VAV
NC-2HW	DCM-83	DCM-83 IN NC-2
NC-2HW	DCM-84	DCM-84 IN NC-2
NC-2HW	OAMIN-4	AHU-4 O.A. MINIMUM
NC-2HW	OAMIN-5	AHU-5 O.A. MINIMUM
NC-2HW	OAMIN-6	AHU-6 O.A. MINIMUM
NC-2HW	FCU3-69	FAN COIL UNIT ELE.EQMT
BO	AHU-5	SHUTDOWN
BI	AHU-5	Status
BI	AHU-5	Filter
AI	AHU-5	DA_Temp
AI	AHU-5	Ret_Tmp
AI	AHU-5	Stc_P_1
AI	AHU-5	Fan_Curr
AOS	AHU-5	SF_Ctrl
AOS	AHU-5	Htg_Clg
CS	AHU-5	AHU5-CS
CS	AHU-5	OAMIN-5
BD	AHU-5	SUM_WIN
JCB	AHU-5	AH5ACUR
BD	HW_CONV	__
AI	HW_CONV	HWS-T
AI	HW_CONV	CHWS-T
AI	HW_CONV	HPS
AI	HW_CONV	LPS
AOD	HW_CONV	V1_CONT
PIDL	HW_CONV	SC1_PID
BD	HW_CONV	SUM_WIN
JCB	HW_CONV	SC1_CON
JCB	HW_CONV	RESET
MC	HW_CONV	ALARM_1
BO	AHU-4	SHUTDOWN

DRAFT

Building 282		
Points	**Equipment**	**Type**
BI	AHU-4	Status
BI	AHU-4	Filter
AI	AHU-4	DA_Temp
AI	AHU-4	Ret_Tmp
AI	AHU-4	Stc_P_1
AI	AHU-4	Fan_Curr
AOS	AHU-4	SF_Ctrl
AOS	AHU-4	Htg_Clg
CS	AHU-4	AHU4-CS
CS	AHU-4	OAMIN-4
BD	AHU-4	SUM_WIN
JCB	AHU-4	AH4-CUR
CS	FCU-ELEV	FCU3-CS
AI	PKG_CHLR	PCWS-T
AI	PKG_CHLR	PCWR-T
AI	PKG_CHLR	PCWS-F
AI	PKG_CHLR	CHWR-T
AI	PKG_CHLR	CWS-T
AI	PKG_CHLR	CHWS-F
AI	PKG_CHLR	OAT
BI	PKG_CHLR	C0-STS
BO	PKG_CHLR	V3_CONT
AOD	PKG_CHLR	V4_CONT
PIDL	PKG_CHLR	PROT-PID
BO	PKG_CHLR	CHLR-SS
AI	PKG_CHLR	CHLR-STA
JCB	PKG_CHLR	CHNG_OVR
JCB	PKG_CHLR	AH4_6SW
JCB	PKG_CHLR	AH1-3PMP
AI	WATER	CW-T
AI	WATER	DHWR-T
AI	WATER	DHWS-T
AOD	WATER	V2_CONT
JCB	WATER	DMHWSFTY
PIDL	WATER	DOM_CTL
CS	5TH_FL	BOX1-5
CS	5TH_FL	BOX2-5
CS	5TH_FL	BOX3-5

DRAFT

Building 282		
Points	**Equipment**	**Type**
CS	5TH_FL	BOX4-5
CS	5TH_FL	BOX5-5
CS	5TH_FL	BOX6-5
CS	5TH_FL	BOX7-5
CS	5TH_FL	BOX8-5
CS	5TH_FL	BOX9-5
CS	5TH_FL	BOX10-5
CS	5TH_FL	BOX11-5
CS	5TH_FL	BOX12-5
CS	5TH_FL	BOX13-5
CS	5TH_FL	BOX14-5
CS	5TH_FL	BOX15-5
CS	5TH_FL	BOX16-5
CS	5TH_FL	BOX17-5
CS	5TH_FL	BOX18-5
CS	5TH_FL	BOX19-5
CS	5TH_FL	BOX20-5
CS	5TH_FL	BOX21-5
CS	5TH_FL	BOX22-5
CS	5TH_FL	BOX23-5
CS	5TH_FL	BOX24-5
CS	5TH_FL	BOX25-5
CS	5TH_FL	BOX26-5
JCB	5TH_FL	SHTDWN
JCB	5TH_FL	TABU5-EX
JCB	5TH_FL	5FLRESET
BO	PUMPS	P_1SS
BO	PUMPS	P_2SS
BO	PUMPS	P_3SS
BI	PUMPS	P-5STS
AI	PUMPS	PMP1_AMP
AI	PUMPS	PMP2_AMP
AI	PUMPS	PMP3_AMP
BD	PUMPS	P_1STS
BD	PUMPS	P_2STS
BD	PUMPS	P_3STS
JCB	PUMPS	PMP_AMPS
BI	EXFAN4TH	EXFAN401

DRAFT

Building 282		
Points	**Equipment**	**Type**
BI	EXFAN4TH	EXFAN402
BI	EXFAN4TH	EXFAN403
BI	EXFAN4TH	EXFAN404
BI	EXFAN4TH	EXFAN405
BI	EXFAN4TH	EXFAN406
BI	EXFAN4TH	EXFAN407
BI	EXFAN4TH	EXFAN413
BI	EXFAN4TH	EXFAN414
BI	EXFAN4TH	EXFAN415
BI	EXFAN4TH	EXFAN416
BI	EXFAN4TH	EXFAN417
BI	EXFAN4TH	EXFAN418
BI	EXFAN5TH	EXFAN501
BI	EXFAN5TH	EXFAN502
BI	EXFAN5TH	EXFAN503
BI	EXFAN5TH	EXFAN504
BI	EXFAN5TH	EXFAN505
BI	EXFAN5TH	EXFAN506
BI	EXFAN5TH	EXFAN507
BI	EXFAN5TH	EXFAN513
BI	EXFAN5TH	EXFAN514
BI	EXFAN5TH	EXFAN515
BI	EXFAN5TH	EXFAN516
BI	EXFAN5TH	EXFAN517
BI	EXFAN5TH	EXFAN518
BI	EXFAN6TH	EXFAN601
BI	EXFAN6TH	EXFAN602
BI	EXFAN6TH	EXFAN603
BI	EXFAN6TH	EXFAN604
BI	EXFAN6TH	EXFAN605
BI	EXFAN6TH	EXFAN606
BI	EXFAN6TH	EXFAN607
BI	EXFAN6TH	EXFAN613
BI	EXFAN6TH	EXFAN614
BI	EXFAN6TH	EXFAN615
BI	EXFAN6TH	EXFAN616
BI	EXFAN6TH	EXFAN617
BI	EXFAN6TH	EXFAN618

DRAFT

Building 282		
Points	**Equipment**	**Type**
BO	AHU-6	SHUTDOWN
BI	AHU-6	Status
BI	AHU-6	Filter
AI	AHU-6	DA_Temp
AI	AHU-6	Ret_Tmp
AI	AHU-6	Stc_P_1
AI	AHU-6	Fan_Curr
AOS	AHU-6	SF_Ctrl
AOS	AHU-6	Htg_Clg
CS	AHU-6	AHU6-CS
CS	AHU-6	OAMIN-6
JCB	AHU-6	AH6CUR
BD	AHU-6	SUM_WIN
BI	EXFAN7TH	EXFAN2ST
BI	EXFAN7TH	EXFAN8ST
BI	EXFAN7TH	EXFAN9ST
BI	EXFAN7TH	EXFAN13
BI	EXFANMEC	EXFAN11
BI	EXFANMEC	EXFAN12
CS	6TH_FL	BOX1-6
CS	6TH_FL	BOX2-6
CS	6TH_FL	BOX3-6
CS	6TH_FL	BOX4-6
CS	6TH_FL	BOX5-6
CS	6TH_FL	BOX6-6
CS	6TH_FL	BOX7-6
CS	6TH_FL	BOX8-6
CS	6TH_FL	BOX9-6
CS	6TH_FL	BOX10-6
CS	6TH_FL	BOX11-6
CS	6TH_FL	BOX12-6
CS	6TH_FL	BOX13-6
CS	6TH_FL	BOX14-6
CS	6TH_FL	BOX15-6
CS	6TH_FL	BOX16-6
CS	6TH_FL	BOX17-6
CS	6TH_FL	BOX18-6
CS	6TH_FL	BOX19-6

DRAFT

Building 282		
Points	**Equipment**	**Type**
CS	6TH_FL	BOX20-6
CS	6TH_FL	BOX21-6
CS	6TH_FL	BOX22-6
CS	6TH_FL	BOX23-6
CS	6TH_FL	BOX24-6
CS	6TH_FL	BOX25-6
CS	6TH_FL	BOX26-6
JCB	6TH_FL	TABU6-EX
JCB	6TH_FL	6FLRESET
JCB	6TH_FL	SHTDWN6
CS	4TH_FL	BOX1-4
CS	4TH_FL	BOX2-4
CS	4TH_FL	BOX3-4
CS	4TH_FL	BOX4-4
CS	4TH_FL	BOX5-4
CS	4TH_FL	BOX6-4
CS	4TH_FL	BOX7-4
CS	4TH_FL	BOX8-4
CS	4TH_FL	BOX9-4
CS	4TH_FL	BOX10-4
CS	4TH_FL	BOX11-4
CS	4TH_FL	BOX12-4
CS	4TH_FL	BOX13-4
CS	4TH_FL	BOX14-4
CS	4TH_FL	BOX15-4
CS	4TH_FL	BOX16-4
CS	4TH_FL	BOX17-4
CS	4TH_FL	BOX18-4
CS	4TH_FL	BOX19-4
CS	4TH_FL	BOX20-4
CS	4TH_FL	BOX21-4
CS	4TH_FL	BOX22-4
CS	4TH_FL	BOX23-4
CS	4TH_FL	BOX24-4
CS	4TH_FL	BOX25-4
CS	4TH_FL	BOX26-4
JCB	4TH_FL	SHTDWN4
JCB	4TH_FL	4FLRESET

DRAFT

Building 282		
Points	**Equipment**	**Type**
JCB	4TH_FL	TABU4-EX
JCB	4TH_FL	SMWN4_6

Building 288		
Points	**Equipment**	**Type**
NC-1		**Network controller**
NC1-HRDW	ROOM-102	11, 1, 3, UNT
NC1-HRDW	ROOM-103	12, 1, 3, UNT
NC1-HRDW	ROOM-104	13, 1, 3, UNT
NC1-HRDW	ROOM-105	14, 1, 3, UNT
NC1-HRDW	ROOM-106	15, 1, 3, UNT
NC1-HRDW	ROOM-107	16, 1, 3, UNT
NC1-HRDW	ROOM-108	17, 1, 3, UNT
NC1-HRDW	ROOM-109	18, 1, 3, UNT
NC1-HRDW	ROOM-110	19, 1, 3, UNT
NC1-HRDW	ROOM-112	21, 1, 3, UNT
NC1-HRDW	ROOM-113	20, 1, 3, UNT
NC1-HRDW	ROOM-114	23, 1, 3, UNT
NC1-HRDW	ROOM-115	22, 1, 3, UNT
NC1-HRDW	ROOM-116	25, 1, 3, UNT
NC1-HRDW	ROOM-117	24, 1, 3, UNT
NC1-HRDW	ROOM-118	27, 1, 3, UNT
NC1-HRDW	ROOM-119	26, 1, 3, UNT
NC1-HRDW	ROOM-120	29, 1, 3, UNT
NC1-HRDW	ROOM-121	28, 1, 3, UNT
NC1-HRDW	ROOM-122	31, 1, 3, UNT
NC1-HRDW	ROOM-201	30, 1, 3, UNT
NC1-HRDW	ROOM-202	33, 1, 3, UNT
NC1-HRDW	ROOM-203	32, 1, 3, UNT
NC1-HRDW	ROOM-204	35, 1, 3, UNT
NC1-HRDW	ROOM-205	34, 1, 3, UNT
NC1-HRDW	ROOM-206	37, 1, 3, UNT
NC1-HRDW	ROOM-207	36, 1, 3, UNT
NC1-HRDW	ROOM-208	39, 1, 3, UNT
NC1-HRDW	ROOM-209	38, 1, 3, UNT

DRAFT

Building 288		
Points	**Equipment**	**Type**
NC1-HRDW	ROOM-210	41, 1, 3, UNT
NC1-HRDW	ROOM-212	43, 1, 3, UNT
NC1-HRDW	ROOM-213	40, 1, 3, UNT
NC1-HRDW	ROOM-214	45, 1, 3, UNT
NC1-HRDW	ROOM-215	42, 1, 3, UNT
NC1-HRDW	ROOM-216	47, 1, 3, UNT
NC1-HRDW	ROOM-217	44, 1, 3, UNT
NC1-HRDW	ROOM-218	49, 1, 3, UNT
NC1-HRDW	ROOM-219	46, 1, 3, UNT
NC1-HRDW	ROOM-220	51, 1, 3, UNT
NC1-HRDW	ROOM-221	48, 1, 3, UNT
NC1-HRDW	ROOM-222	53, 1, 3, UNT
NC1-HRDW	OFFICE	116, 1, 3, UNT
NC1-HRDW	LOBBY	114, 1, 3, UNT
NC1-HRDW	MAU-01	3, 1, 3, UNT
NC1-HRDW	MAU-02	4, 1, 3, UNT
NC1-HRDW	DCM-01	1, 1, 1
NC1-HRDW	DCM-02	2, 1, 1
BO	HEAT_XER	HWP-C
BI	HEAT_XER	HWP-S
AOD	HEAT_XER	STM-VLVZ
AI	HEAT_XER	HWS-T
AI	HEAT_XER	HWR-T
AI	HEAT_XER	OAT-T
AI	HEAT_XER	STM-S-F
AI	HEAT_XER	STM-S-P
BI	HEAT_XER	HEATFLOW
PIDL	HEAT_XER	HX1-PIDL
JCB	HEAT_XER	HEAT-XER
BD	MAU-01	SHUTDOWN
BD	MAU-01	SAF-ALRM
AD	MAU-01	PHT-TEMP
BD	MAU-01	SAF-STAT
AD	MAU-01	PHC-VALV
AD	MAU-01	DAT-TEMP
AD	MAU-01	RHC-VALV
BD	MAU-01	COMPR2SS
BD	MAU-01	COMPR1SS

DRAFT

Building 288		
Points	**Equipment**	**Type**
AI	MAU-01	DA-HUM
AI	MAU-01	CC-T
BD	MAU-02	SHUTDOWN
BD	MAU-02	SAF-ALRM
BD	MAU-02	SAF-STAT
AD	MAU-02	PHC-VALV
AD	MAU-02	RHC-VALV
BD	MAU-02	COMPR1SS
BD	MAU-02	COMPR2SS
AD	MAU-02	DAT-TEMP
AD	MAU-02	PHT-TEMP
AI	MAU-02	DA-HUM
AI	MAU-02	CC-T
BO	OFFICE	OCC-UNOC
AD	OFFICE	SPACETMP
AD	OFFICE	ACTHTSET
AD	OFFICE	ACTCLGSP
BD	OFFICE	TEMPOVRD
BD	OFFICE	SHUTDOWN
BD	OFFICE	SAF-STAT
BD	OFFICE	REV-VLVF
BD	OFFICE	COMPRSFB
BD	LOBBY	OCCUP-BD
AD	LOBBY	SPACETMP
AD	LOBBY	ACTHTSET
AD	LOBBY	ACTCLGSP
BD	LOBBY	TEMPOVRD
BD	LOBBY	SHUTDOWN
BD	LOBBY	SAF-STAT
BD	LOBBY	REV_VLVF
BD	LOBBY	COMPRSFB
BO	ROOM-101	OCC-UNOC
AD	ROOM-101	SPACETMP
AD	ROOM-101	ACTHTSET
AD	ROOM-101	ACTCLGSP
BD	ROOM-101	TEMPOVRD
BD	ROOM-101	SHUTDOWN
BD	ROOM-101	SAF-STAT

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-101	REV-VLVF
BD	ROOM-101	COMPRSFB
BO	ROOM-102	OCC-UNOC
AD	ROOM-102	SPACETMP
AD	ROOM-102	ACTHTSET
AD	ROOM-102	ACTCLGSP
BD	ROOM-102	TEMPOVRD
BD	ROOM-102	SHUTDOWN
BD	ROOM-102	SAF-STAT
BD	ROOM-102	REV-VLVF
BD	ROOM-102	COMPRSFB
BO	ROOM-103	OCC-UNOC
AD	ROOM-103	SPACETMP
AD	ROOM-103	ACTHTSET
AD	ROOM-103	ACTCLGSP
BD	ROOM-103	TEMPOVRD
BD	ROOM-103	SHUTDOWN
BD	ROOM-103	SAF-STAT
BD	ROOM-103	REV-VLVF
BD	ROOM-103	COMPRSFB
BO	ROOM-104	OCC-UNOC
AD	ROOM-104	SPACETMP
AD	ROOM-104	ACTHTSET
AD	ROOM-104	ACTCLGSP
BD	ROOM-104	TEMPOVRD
BD	ROOM-104	SHUTDOWN
BD	ROOM-104	SAF-STAT
BD	ROOM-104	REV-VLVF
BD	ROOM-104	COMPRSFB
BO	ROOM-105	OCC-UNOC
AD	ROOM-105	SPACETMP
AD	ROOM-105	ACTHTSET
AD	ROOM-105	ACTCLGSP
BD	ROOM-105	TEMPOVRD
BD	ROOM-105	SHUTDOWN
BD	ROOM-105	SAF-STAT
BD	ROOM-105	REV-VLVF
BD	ROOM-105	COMPRSFB

DRAFT

Building 288		
Points	**Equipment**	**Type**
BO	ROOM-106	OCC-UNOC
AD	ROOM-106	SPACETMP
AD	ROOM-106	ACTHTSET
AD	ROOM-106	ACTCLGSP
BD	ROOM-106	TEMPOVRD
BD	ROOM-106	SHUTDOWN
BD	ROOM-106	SAF-STAT
BD	ROOM-106	REV-VLVF
BD	ROOM-106	COMPRSFB
BO	ROOM-107	OCC-UNOC
AD	ROOM-107	SPACETMP
AD	ROOM-107	ACTHTSET
AD	ROOM-107	ACTCLGSP
BD	ROOM-107	TEMPOVRD
BD	ROOM-107	SHUTDOWN
BD	ROOM-107	SAF-STAT
BD	ROOM-107	REV-VLVF
BD	ROOM-107	COMPRSFB
BO	ROOM-108	OCC-UNOC
AD	ROOM-108	SPACETMP
AD	ROOM-108	ACTHTSET
AD	ROOM-108	ACTCLGSP
BD	ROOM-108	TEMPOVRD
BD	ROOM-108	SHUTDOWN
BD	ROOM-108	SAF-STAT
BD	ROOM-108	REV-VLVF
BD	ROOM-108	COMPRSFB
BO	ROOM-109	OCC-UNOC
AD	ROOM-109	SPACETMP
AD	ROOM-109	ACTHTSET
AD	ROOM-109	ACTCLGSP
BD	ROOM-109	TEMPOVRD
BD	ROOM-109	SHUTDOWN
BD	ROOM-109	SAF-STAT
BD	ROOM-109	REV-VLVF
BD	ROOM-109	COMPRSFB
BO	ROOM-110	OCC-UNOC
AD	ROOM-110	SPACETMP

DRAFT

Building 288		
Points	**Equipment**	**Type**
AD	ROOM-110	ACTHTSET
AD	ROOM-110	ACTCLGSP
BD	ROOM-110	TEMPOVRD
BD	ROOM-110	SHUTDOWN
BD	ROOM-110	SAF-STAT
BD	ROOM-110	REV-VLVF
BD	ROOM-110	COMPRSFB
BO	ROOM-112	OCC-UNOC
AD	ROOM-112	SPACETMP
AD	ROOM-112	ACTHTSET
AD	ROOM-112	ACTCLGSP
BD	ROOM-112	TEMPOVRD
BD	ROOM-112	SHUTDOWN
BD	ROOM-112	SAF-STAT
BD	ROOM-112	REV-VLVF
BD	ROOM-112	COMPRSFB
BO	ROOM-113	OCC-UNOC
AD	ROOM-113	SPACETMP
AD	ROOM-113	ACTHTSET
AD	ROOM-113	ACTCLGSP
BD	ROOM-113	TEMPOVRD
BD	ROOM-113	SHUTDOWN
BD	ROOM-113	SAF-STAT
BD	ROOM-113	REV-VLVF
BD	ROOM-113	COMPRSFB
BO	ROOM-114	OCC-UNOC
AD	ROOM-114	SPACETMP
AD	ROOM-114	ACTHTSET
AD	ROOM-114	ACTCLGSP
BD	ROOM-114	TEMPOVRD
BD	ROOM-114	SHUTDOWN
BD	ROOM-114	SAF-STAT
BD	ROOM-114	REV-VLVF
BD	ROOM-114	COMPRSFB
BO	ROOM-115	OCC-UNOC
AD	ROOM-115	SPACETMP
AD	ROOM-115	ACTHTSET
AD	ROOM-115	ACTCLGSP

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-115	TEMPOVRD
BD	ROOM-115	SHUTDOWN
BD	ROOM-115	SAF-STAT
BD	ROOM-115	REV-VLVF
BD	ROOM-115	COMPRSFB
BO	ROOM-116	OCC-UNOC
AD	ROOM-116	SPACETMP
AD	ROOM-116	ACTHTSET
AD	ROOM-116	ACTCLGSP
BD	ROOM-116	TEMPOVRD
BD	ROOM-116	SHUTDOWN
BD	ROOM-116	SAF-STAT
BD	ROOM-116	REV-VLVF
BD	ROOM-116	COMPRSFB
BO	ROOM-117	OCC-UNOC
AD	ROOM-117	SPACETMP
AD	ROOM-117	ACTHTSET
AD	ROOM-117	ACTCLGSP
BD	ROOM-117	TEMPOVRD
BD	ROOM-117	SHUTDOWN
BD	ROOM-117	SAF-STAT
BD	ROOM-117	REV-VLVF
BD	ROOM-117	COMPRSFB
BO	ROOM-118	OCC-UNOC
AD	ROOM-118	SPACETMP
AD	ROOM-118	ACTHTSET
AD	ROOM-118	ACTCLGSP
BD	ROOM-118	TEMPOVRD
BD	ROOM-118	SHUTDOWN
BD	ROOM-118	SAF-STAT
BD	ROOM-118	REV-VLVF
BD	ROOM-118	COMPRSFB
BO	ROOM-119	OCC-UNOC
AD	ROOM-119	SPACETMP
AD	ROOM-119	ACTHTSET
AD	ROOM-119	ACTCLGSP
BD	ROOM-119	TEMPOVRD
BD	ROOM-119	SHUTDOWN

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-119	SAF-STAT
BD	ROOM-119	REV-VLVF
BD	ROOM-119	COMPRSFB
BO	ROOM-120	OCC-UNOC
AD	ROOM-120	SPACETMP
AD	ROOM-120	ACTHTSET
AD	ROOM-120	ACTCLGSP
BD	ROOM-120	TEMPOVRD
BD	ROOM-120	SHUTDOWN
BD	ROOM-120	SAF-STAT
BD	ROOM-120	REV-VLVF
BD	ROOM-120	COMPRSFB
BO	ROOM-121	Occ-Unoc
AD	ROOM-121	SPACETMP
AD	ROOM-121	ACTHTSET
AD	ROOM-121	ACTCLGSP
BD	ROOM-121	TEMPOVRD
BD	ROOM-121	SHUTDOWN
BD	ROOM-121	SAF-STAT
BD	ROOM-121	REV-VLVF
BD	ROOM-121	COMPRSFB
BO	ROOM-122	OCC-UNOC
AD	ROOM-122	SPACETMP
AD	ROOM-122	ACTHTSET
AD	ROOM-122	ACTCLGSP
BD	ROOM-122	TEMPOVRD
BD	ROOM-122	SHUTDOWN
BD	ROOM-122	SAF-STAT
BD	ROOM-122	REV-VLVF
BD	ROOM-122	COMPRSFB
BO	ROOM-201	OCC-UNOC
AD	ROOM-201	SPACETMP
AD	ROOM-201	ACTHTSET
AD	ROOM-201	ACTCLGSP
BD	ROOM-201	TEMPOVRD
BD	ROOM-201	SHUTDOWN
BD	ROOM-201	SAF-STAT
BD	ROOM-201	REV-VLVF

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-201	COMPRSFB
BO	ROOM-202	OCC-UNOC
AD	ROOM-202	SPACETMP
AD	ROOM-202	ACTHTSET
AD	ROOM-202	ACTCLGSP
BD	ROOM-202	TEMPOVRD
BD	ROOM-202	SHUTDOWN
BD	ROOM-202	SAF-STAT
BD	ROOM-202	REV-VLVF
BD	ROOM-202	COMPRSFB
BO	ROOM-203	OCC-UNOC
AD	ROOM-203	SPACETMP
AD	ROOM-203	ACTHTSET
AD	ROOM-203	ACTCLGSP
BD	ROOM-203	TEMPOVRD
BD	ROOM-203	SHUTDOWN
BD	ROOM-203	SAF-STAT
BD	ROOM-203	REV-VLVF
BD	ROOM-203	COMPRSFB
BO	ROOM-204	OCC-UNOC
AD	ROOM-204	SPACETMP
AD	ROOM-204	ACTHTSET
AD	ROOM-204	ACTCLGSP
BD	ROOM-204	TEMPOVRD
BD	ROOM-204	SHUTDOWN
BD	ROOM-204	SAF-STAT
BD	ROOM-204	REV-VLVF
BD	ROOM-204	COMPRSFB
BO	ROOM-205	OCC-UNOC
AD	ROOM-205	SPACETMP
AD	ROOM-205	ACTHTSET
AD	ROOM-205	ACTCLGSP
BD	ROOM-205	TEMPOVRD
BD	ROOM-205	SHUTDOWN
BD	ROOM-205	SAF-STAT
BD	ROOM-205	REV-VLVF
BD	ROOM-205	COMPRSFB
BO	ROOM-206	OCC-UNOC

DRAFT

Building 288		
Points	**Equipment**	**Type**
AD	ROOM-206	SPACETMP
AD	ROOM-206	ACTHTSET
AD	ROOM-206	ACTCLGSP
BD	ROOM-206	TEMPOVRD
BD	ROOM-206	SHUTDOWN
BD	ROOM-206	SAF-STAT
BD	ROOM-206	REV-VLVF
BD	ROOM-206	COMPRSFB
BO	ROOM-207	OCC-UNOC
AD	ROOM-207	SPACETMP
AD	ROOM-207	ACTHTSET
AD	ROOM-207	ACTCLGSP
BD	ROOM-207	TEMPOVRD
BD	ROOM-207	SHUTDOWN
BD	ROOM-207	SAF-STAT
BD	ROOM-207	REV-VLVF
BD	ROOM-207	COMPRSFB
BO	ROOM-208	OCC-UNOC
AD	ROOM-208	SPACETMP
AD	ROOM-208	ACTHTSET
AD	ROOM-208	ACTCLGSP
BD	ROOM-208	TEMPOVRD
BD	ROOM-208	SHUTDOWN
BD	ROOM-208	SAF-STAT
BD	ROOM-208	REV-VLVF
BD	ROOM-208	COMPRSFB
BO	ROOM-209	OCC-UNOC
AD	ROOM-209	SPACETMP
AD	ROOM-209	ACTHTSET
AD	ROOM-209	ACTCLGSP
BD	ROOM-209	TEMPOVRD
BD	ROOM-209	SHUTDOWN
BD	ROOM-209	SAF-STAT
BD	ROOM-209	REV-VLVF
BD	ROOM-209	COMPRSFB
BO	ROOM-210	OCC-UNOC
AD	ROOM-210	SPACETMP
AD	ROOM-210	ACTHTSET

DRAFT

Building 288		
Points	**Equipment**	**Type**
AD	ROOM-210	ACTCLGSP
BD	ROOM-210	TEMPOVRD
BD	ROOM-210	SHUTDOWN
BD	ROOM-210	SAF-STAT
BD	ROOM-210	REV-VLVF
BD	ROOM-210	COMPRSFB
BO	ROOM-212	OCC-UNOC
AD	ROOM-212	SPACETMP
AD	ROOM-212	ACTHTSET
AD	ROOM-212	ACTCLGSP
BD	ROOM-212	TEMPOVRD
BD	ROOM-212	SHUTDOWN
BD	ROOM-212	SAF-STAT
BD	ROOM-212	REV-VLVF
BD	ROOM-212	COMPRSFB
BO	ROOM-213	OCC-UNOC
AD	ROOM-213	SPACETMP
AD	ROOM-213	ACTHTSET
AD	ROOM-213	ACTCLGSP
BD	ROOM-213	TEMPOVRD
BD	ROOM-213	SHUTDOWN
BD	ROOM-213	SAF-STAT
BD	ROOM-213	REV-VLVF
BD	ROOM-213	COMPRSFB
BO	ROOM-214	OCC-UNOC
AD	ROOM-214	SPACETMP
AD	ROOM-214	ACTHTSET
AD	ROOM-214	ACTCLGSP
BD	ROOM-214	TEMPOVRD
BD	ROOM-214	SHUTDOWN
BD	ROOM-214	SAF-STAT
BD	ROOM-214	REV-VLVF
BD	ROOM-214	COMPRSFB
BO	ROOM-215	OCC-UNOC
AD	ROOM-215	SPACETMP
AD	ROOM-215	ACTHTSET
AD	ROOM-215	ACTCLGSP
BD	ROOM-215	TEMPOVRD

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-215	SHUTDOWN
BD	ROOM-215	SAF-STAT
BD	ROOM-215	REV-VLVF
BD	ROOM-215	COMPRSFB
BO	ROOM-216	OCC-UNOC
AD	ROOM-216	SPACETMP
AD	ROOM-216	ACTHTSET
AD	ROOM-216	ACTCLGSP
BD	ROOM-216	TEMPOVRD
BD	ROOM-216	SHUTDOWN
BD	ROOM-216	SAF-STAT
BD	ROOM-216	REV-VLVF
BD	ROOM-216	COMPRSFB
BO	ROOM-217	OCC-UNOC
AD	ROOM-217	SPACETMP
AD	ROOM-217	ACTHTSET
AD	ROOM-217	ACTCLGSP
BD	ROOM-217	TEMPOVRD
BD	ROOM-217	SHUTDOWN
BD	ROOM-217	SAF-STAT
BD	ROOM-217	REV-VLVF
BD	ROOM-217	COMPRSFB
BO	ROOM-218	OCC-UNOC
AD	ROOM-218	SPACETMP
AD	ROOM-218	ACTHTSET
AD	ROOM-218	ACTCLGSP
BD	ROOM-218	TEMPOVRD
BD	ROOM-218	SHUTDOWN
BD	ROOM-218	SAF-STAT
BD	ROOM-218	REV-VLVF
BD	ROOM-218	COMPRSFB
BO	ROOM-219	OCC-UNOC
AD	ROOM-219	SPACETMP
AD	ROOM-219	ACTHTSET
AD	ROOM-219	ACTCLGSP
BD	ROOM-219	TEMPOVRD
BD	ROOM-219	SHUTDOWN
BD	ROOM-219	SAF-STAT

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-219	REV-VLVF
BD	ROOM-219	COMPRSFB
BO	ROOM-220	OCC-UNOC
AD	ROOM-220	SPACETMP
AD	ROOM-220	ACTHTSET
AD	ROOM-220	ACTCLGSP
BD	ROOM-220	TEMPOVRD
BD	ROOM-220	SHUTDOWN
BD	ROOM-220	SAF-STAT
BD	ROOM-220	REV-VLVF
BD	ROOM-220	COMPRSFB
BO	ROOM-221	OCC-UNOC
AD	ROOM-221	SPACETMP
AD	ROOM-221	ACTHTSET
AD	ROOM-221	ACTCLGSP
BD	ROOM-221	TEMPOVRD
BD	ROOM-221	SHUTDOWN
BD	ROOM-221	SAF-STAT
BD	ROOM-221	REV-VLVF
BD	ROOM-221	COMPRSFB
BO	ROOM-222	OCC-UNOC
AD	ROOM-222	SPACETMP
AD	ROOM-222	ACTHTSET
AD	ROOM-222	ACTCLGSP
BD	ROOM-222	TEMPOVRD
BD	ROOM-222	SHUTDOWN
BD	ROOM-222	SAF-STAT
BD	ROOM-222	REV-VLVF
BD	ROOM-222	COMPRSFB
AI	DOM_WTR	DHWS-T
BI	DOM_WTR	DHWP-S
BO	EX-FANS6	EF_6_C
BI	EX-FANS6	EF_6_S
CS	NC1-CSOB	RM101-CS
CS	NC1-CSOB	RM102-CS
CS	NC1-CSOB	RM103-CS
CS	NC1-CSOB	RM104-CS
CS	NC1-CSOB	RM105-CS

DRAFT

Building 288		
Points	**Equipment**	**Type**
CS	NC1-CSOB	RM106-CS
CS	NC1-CSOB	RM107-CS
CS	NC1-CSOB	RM108-CS
CS	NC1-CSOB	RM109-CS
CS	NC1-CSOB	RM110-CS
CS	NC1-CSOB	RM112-CS
CS	NC1-CSOB	RM113-CS
CS	NC1-CSOB	RM114-CS
CS	NC1-CSOB	RM115-CS
CS	NC1-CSOB	RM116-CS
CS	NC1-CSOB	RM117-CS
CS	NC1-CSOB	RM118-CS
CS	NC1-CSOB	RM119-CS
CS	NC1-CSOB	RM120-CS
CS	NC1-CSOB	RM121-CS
CS	NC1-CSOB	RM122-CS
CS	NC1-CSOB	RM201-CS
CS	NC1-CSOB	RM202-CS
CS	NC1-CSOB	RM203-CS
CS	NC1-CSOB	RM204-CS
CS	NC1-CSOB	RM205-CS
CS	NC1-CSOB	RM206-CS
CS	NC1-CSOB	RM207-CS
CS	NC1-CSOB	RM208-CS
CS	NC1-CSOB	RM209-CS
CS	NC1-CSOB	RM210-CS
CS	NC1-CSOB	RM212-CS
CS	NC1-CSOB	RM213-CS
CS	NC1-CSOB	RM214-CS
CS	NC1-CSOB	RM215-CS
CS	NC1-CSOB	RM216-CS
CS	NC1-CSOB	RM217-CS
CS	NC1-CSOB	RM218-CS
CS	NC1-CSOB	RM219-CS
CS	NC1-CSOB	RM220-CS
CS	NC1-CSOB	RM221-CS
CS	NC1-CSOB	RM222-CS
CS	NC1-CSOB	Off-CS

DRAFT

Building 288		
Points	**Equipment**	**Type**
CS	NC1-CSOB	Lob-CS
CS	NC1-CSOB	MAU1-CSO
CS	NC1-CSOB	MAU2-CSO
JCB	NC1-CSOB	MAU-DXLK
BD	COND_SYS	CDW_ALRM
BI	COND_SYS	CWP-S
BO	COND_SYS	CWP-C
AD	COND_SYS	CWS_HTCO
AI	COND_SYS	CWS-T
PIDL	COND_SYS	CTWR_PID
PIDL	COND_SYS	PFHXPIDL
AD	COND_SYS	CWS_LTCO
AI	COND_SYS	CWR-T
AOD	COND_SYS	CTWR-AOD
BO	COND_SYS	EC-D-C
BI	COND_SYS	CCEC-P-S
BO	COND_SYS	CCEC-P-C
BI	COND_SYS	FAN-LO-S
BO	COND_SYS	EC-F-LO
BI	COND_SYS	FAN-HI-S
BO	COND_SYS	EC-F-HI
AOD	COND_SYS	CW-BPV-Z
AI	COND_SYS	HX-CWS-T
AI	COND_SYS	HX-CWR-T
AI	COND_SYS	HX-HWS-T
AI	COND_SYS	HX-HWR-T
AI	COND_SYS	CCEC-S-T
AI	COND_SYS	EC-MUW-F
AI	COND_SYS	EC-MUW-P
JCB	COND_SYS	ALRM_GPL
JCB	COND_SYS	1STFLGPL
JCB	COND_SYS	2NDFLGPL
JCB	COND_SYS	3RDFLGPL
JCB	COND_SYS	4THFLGPL
JCB	COND_SYS	5THFLGPL
JCB	COND_SYS	CTWR_GPL
JCB	COND_SYS	PFHX_GPL

DRAFT

Building 288		
Points	**Equipment**	**Type**
Building 288		
Points	**Equipment**	**Type**
NC-2		**Network controller**
NC2-HRDW	ROOM-302	55, 1, 3, UNT
NC2-HRDW	ROOM-303	52, 1, 3, UNT
NC2-HRDW	ROOM-304	57, 1, 3, UNT
NC2-HRDW	ROOM-305	54, 1, 3, UNT
NC2-HRDW	ROOM-306	59, 1, 3, UNT
NC2-HRDW	ROOM-307	56, 1, 3, UNT
NC2-HRDW	ROOM-308	61, 1, 3, UNT
NC2-HRDW	ROOM-309	58, 1, 3, UNT
NC2-HRDW	ROOM-310	63, 1, 3, UNT
NC2-HRDW	ROOM-312	65, 1, 3, UNT
NC2-HRDW	ROOM-313	60, 1, 3, UNT
NC2-HRDW	ROOM-314	67, 1, 3, UNT
NC2-HRDW	ROOM-315	62, 1, 3, UNT
NC2-HRDW	ROOM-316	69, 1, 3, UNT
NC2-HRDW	ROOM-317	64, 1, 3, UNT
NC2-HRDW	ROOM-318	71, 1, 3, UNT
NC2-HRDW	ROOM-319	66, 1, 3, UNT
NC2-HRDW	ROOM-320	73, 1, 3, UNT
NC2-HRDW	ROOM-321	68, 1, 3, UNT
NC2-HRDW	ROOM-322	75, 1, 3, UNT
NC2-HRDW	ROOM-401	70, 1, 3, UNT
NC2-HRDW	ROOM-402	77, 1, 3, UNT
NC2-HRDW	ROOM-403	72, 1, 3, UNT
NC2-HRDW	ROOM-404	79, 1, 3, UNT
NC2-HRDW	ROOM-405	74, 1, 3, UNT
NC2-HRDW	ROOM-406	81, 1, 3, UNT
NC2-HRDW	ROOM-407	76, 1, 3, UNT
NC2-HRDW	ROOM-408	83, 1, 3, UNT
NC2-HRDW	ROOM-409	78, 1, 3, UNT
NC2-HRDW	ROOM-410	85, 1, 3, UNT
NC2-HRDW	ROOM-412	87, 1, 3, UNT
NC2-HRDW	ROOM-413	80, 1, 3, UNT
NC2-HRDW	ROOM-414	89, 1, 3, UNT

DRAFT

Building 288		
Points	**Equipment**	**Type**
NC2-HRDW	ROOM-415	82, 1, 3, UNT
NC2-HRDW	ROOM-416	91, 1, 3, UNT
NC2-HRDW	ROOM-417	84, 1, 3, UNT
NC2-HRDW	ROOM-418	93, 1, 3, UNT
NC2-HRDW	ROOM-419	86, 1, 3, UNT
NC2-HRDW	ROOM-420	95, 1, 3, UNT
NC2-HRDW	ROOM-421	88, 1, 3, UNT
NC2-HRDW	ROOM-422	97, 1, 3, UNT
NC2-HRDW	ROOM-501	90, 1, 3, UNT
NC2-HRDW	ROOM-502	99, 1, 3, UNT
NC2-HRDW	ROOM-503	92, 1, 3, UNT
NC2-HRDW	ROOM-504	101, 1, 3, UNT
NC2-HRDW	ROOM-505	94, 1, 3, UNT
NC2-HRDW	ROOM-506	103, 1, 3, UNT
NC2-HRDW	ROOM-507	96, 1, 3, UNT
NC2-HRDW	ROOM-508	105, 1, 3, UNT
NC2-HRDW	ROOM-509	98, 1, 3, UNT
NC2-HRDW	ROOM-510	107, 1, 3, UNT
NC2-HRDW	ROOM-512	111, 1, 3, UNT
NC2-HRDW	ROOM-513	102, 1, 3, UNT
NC2-HRDW	ROOM-514	113, 1, 3, UNT
NC2-HRDW	ROOM-515	104, 1, 3, UNT
NC2-HRDW	ROOM-516	115, 1, 3, UNT
NC2-HRDW	ROOM-517	106, 1, 3, UNT
NC2-HRDW	ROOM-518	117, 1, 3, UNT
NC2-HRDW	ROOM-519	108, 1, 3, UNT
NC2-HRDW	ROOM-520	119, 1, 3, UNT
NC2-HRDW	ROOM-521	110, 1, 3, UNT
NC2-HRDW	ROOM-522	121, 1, 3, UNT
NC2-HRDW	ELEV-RM	112, 1, 3, UNT
NC2-HRDW	W-COMRM	100, 1, 3, UNT
NC2-HRDW	E-COMRM	109, 1, 3, UNT
NC2-HRDW	MAU-03	5, 1, 3, UNT
NC2-HRDW	MAU-04	6, 1, 3, UNT
NC2-HRDW	MAU-05	7, 1, 3, UNT
NC2-HRDW	EF-120	120, 1, 3, UNT
NC2-HRDW	EF-118	118, 1, 3, UNT
NC2-HRDW	MECH-KWH	1, 1, 3, VND

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	W-COMRM	OCCUP-BD
BD	W-COMRM	SHUTDOWN
BD	W-COMRM	TEMPOVRD
BD	W-COMRM	SAF-STAT
AD	W-COMRM	ACTCLGSP
AD	W-COMRM	SPACETMP
AD	W-COMRM	ACTHTSET
BD	W-COMRM	REV-VLVF
BD	W-COMRM	COMPRSFB
BD	MAU-04	SHUTDOWN
BD	MAU-04	SAF-ALRM
BD	MAU-04	SAF-STAT
AD	MAU-04	PHT-TEMP
AD	MAU-04	PHC-VALV
AD	MAU-04	DAT-TEMP
AD	MAU-04	RHC-VALV
BD	MAU-04	COMPR1SS
BD	MAU-04	COMPR2SS
AI	MAU-04	DA-HUM
AI	MAU-04	CC-T
BD	MAU-03	SHUTDOWN
BD	MAU-03	SAF-ALRM
BD	MAU-03	SAF-STAT
AD	MAU-03	PHT-TEMP
AD	MAU-03	PHC-VALV
AD	MAU-03	DAT-TEMP
AD	MAU-03	RHC-VALV
BD	MAU-03	COMPR1SS
BD	MAU-03	COMPR2SS
AI	MAU-03	DA-HUM
AI	MAU-03	CC-T
BD	ELEV-RM	OCCUP-BD
BD	ELEV-RM	SHUTDOWN
BD	ELEV-RM	TEMPOVRD
BD	ELEV-RM	SAF-STAT
AD	ELEV-RM	ACTCLGSP
AD	ELEV-RM	SPACETMP
AD	ELEV-RM	ACTHTSET

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ELEV-RM	REV-VLVF
BD	ELEV-RM	COMPRSFB
BD	E-COMRM	OCCUP-BD
BD	E-COMRM	SHUTDOWN
BD	E-COMRM	TEMPOVRD
BD	E-COMRM	SAF-STAT
AD	E-COMRM	ACTCLGSP
AD	E-COMRM	SPACETMP
AD	E-COMRM	ACTHTSET
BD	E-COMRM	REV-VLVF
BD	E-COMRM	COMPRSFB
BI	EX-FANS1	EF-1
BO	EX-FANS1	EF-1-C
BI	EX-FANS2	EF-2
BO	EX-FANS2	EF-2-C
BI	EX-FANS5	EF-5
BO	EX-FANS5	EF-5-C
BO	ROOM-301	OCC-UNOC
AD	ROOM-301	SPACETMP
AD	ROOM-301	ACTHTSET
AD	ROOM-301	ACTCLGSP
BD	ROOM-301	TEMPOVRD
BD	ROOM-301	SHUTDOWN
BD	ROOM-301	SAF-STAT
BD	ROOM-301	REV-VLVF
BD	ROOM-301	COMPRSFB
BO	ROOM-302	OCC-UNOC
AD	ROOM-302	SPACETMP
AD	ROOM-302	ACTHTSET
AD	ROOM-302	ACTCLGSP
BD	ROOM-302	TEMPOVRD
BD	ROOM-302	SHUTDOWN
BD	ROOM-302	SAF-STAT
BD	ROOM-302	REV-VLVF
BD	ROOM-302	COMPRSFB
BO	ROOM-303	OCC-UNOC
AD	ROOM-303	SPACETMP
AD	ROOM-303	ACTHTSET

DRAFT

Building 288		
Points	**Equipment**	**Type**
AD	ROOM-303	ACTCLGSP
BD	ROOM-303	TEMPOVRD
BD	ROOM-303	SHUTDOWN
BD	ROOM-303	SAF-STAT
BD	ROOM-303	REV-VLVF
BD	ROOM-303	COMPRSFB
BO	ROOM-304	OCC-UNOC
AD	ROOM-304	SPACETMP
AD	ROOM-304	ACTHTSET
AD	ROOM-304	ACTCLGSP
BD	ROOM-304	TEMPOVRD
BD	ROOM-304	SHUTDOWN
BD	ROOM-304	SAF-STAT
BD	ROOM-304	REV-VLVF
BD	ROOM-304	COMPRSFB
BO	ROOM-305	OCC-UNOC
AD	ROOM-305	SPACETMP
AD	ROOM-305	ACTHTSET
AD	ROOM-305	ACTCLGSP
BD	ROOM-305	TEMPOVRD
BD	ROOM-305	SHUTDOWN
BD	ROOM-305	SAF-STAT
BD	ROOM-305	REV-VLVF
BD	ROOM-305	COMPRSFB
BO	ROOM-306	OCC-UNOC
AD	ROOM-306	SPACETMP
AD	ROOM-306	ACTHTSET
AD	ROOM-306	ACTCLGSP
BD	ROOM-306	TEMPOVRD
BD	ROOM-306	SHUTDOWN
BD	ROOM-306	SAF-STAT
BD	ROOM-306	REV-VLVF
BD	ROOM-306	COMPRSFB
BO	ROOM-307	OCC-UNOC
AD	ROOM-307	SPACETMP
AD	ROOM-307	ACTHTSET
AD	ROOM-307	ACTCLGSP
BD	ROOM-307	TEMPOVRD

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-307	SHUTDOWN
BD	ROOM-307	SAF-STAT
BD	ROOM-307	REV-VLVF
BD	ROOM-307	COMPRSFB
BO	ROOM-308	OCC-UNOC
AD	ROOM-308	SPACETMP
AD	ROOM-308	ACTHTSET
AD	ROOM-308	ACTCLGSP
BD	ROOM-308	TEMPOVRD
BD	ROOM-308	SHUTDOWN
BD	ROOM-308	SAF-STAT
BD	ROOM-308	REV-VLVF
BD	ROOM-308	COMPRSFB
BO	ROOM-309	OCC-UNOC
AD	ROOM-309	SPACETMP
AD	ROOM-309	ACTHTSET
AD	ROOM-309	ACTCLGSP
BD	ROOM-309	TEMPOVRD
BD	ROOM-309	SHUTDOWN
BD	ROOM-309	SAF-STAT
BD	ROOM-309	REV-VLVF
BD	ROOM-309	COMPRSFB
BO	ROOM-310	OCC-UNOC
AD	ROOM-310	SPACETMP
AD	ROOM-310	ACTHTSET
AD	ROOM-310	ACTCLGSP
BD	ROOM-310	TEMPOVRD
BD	ROOM-310	SHUTDOWN
BD	ROOM-310	SAF-STAT
BD	ROOM-310	REV-VLVF
BD	ROOM-310	COMPRSFB
BO	ROOM-312	OCC-UNOC
AD	ROOM-312	SPACETMP
AD	ROOM-312	ACTHTSET
AD	ROOM-312	ACTCLGSP
BD	ROOM-312	TEMPOVRD
BD	ROOM-312	SHUTDOWN
BD	ROOM-312	SAF-STAT

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-312	REV-VLVF
BD	ROOM-312	COMPRSFB
BO	ROOM-313	OCC-UNOC
AD	ROOM-313	SPACETMP
AD	ROOM-313	ACTHTSET
AD	ROOM-313	ACTCLGSP
BD	ROOM-313	TEMPOVRD
BD	ROOM-313	SHUTDOWN
BD	ROOM-313	SAF-STAT
BD	ROOM-313	REV-VLVF
BD	ROOM-313	COMPRSFB
BO	ROOM-314	OCC-UNOC
AD	ROOM-314	SPACETMP
AD	ROOM-314	ACTHTSET
AD	ROOM-314	ACTCLGSP
BD	ROOM-314	TEMPOVRD
BD	ROOM-314	SHUTDOWN
BD	ROOM-314	SAF-STAT
BD	ROOM-314	REV-VLVF
BD	ROOM-314	COMPRSFB
BO	ROOM-315	OCC-UNOC
AD	ROOM-315	SPACETMP
AD	ROOM-315	ACTHTSET
AD	ROOM-315	ACTCLGSP
BD	ROOM-315	TEMPOVRD
BD	ROOM-315	SHUTDOWN
BD	ROOM-315	SAF-STAT
BD	ROOM-315	REV-VLVF
BD	ROOM-315	COMPRSFB
BO	ROOM-316	OCC-UNOC
AD	ROOM-316	SPACETMP
AD	ROOM-316	ACTHTSET
AD	ROOM-316	ACTCLGSP
BD	ROOM-316	TEMPOVRD
BD	ROOM-316	SHUTDOWN
BD	ROOM-316	SAF-STAT
BD	ROOM-316	REV-VLVF
BD	ROOM-316	COMPRSFB

DRAFT

Building 288		
Points	**Equipment**	**Type**
BO	ROOM-317	OCC-UNOC
AD	ROOM-317	SPACETMP
AD	ROOM-317	ACTHTSET
AD	ROOM-317	ACTCLGSP
BD	ROOM-317	TEMPOVRD
BD	ROOM-317	SHUTDOWN
BD	ROOM-317	SAF-STAT
BD	ROOM-317	REV-VLVF
BD	ROOM-317	COMPRSFB
BO	ROOM-318	OCC-UNOC
AD	ROOM-318	SPACETMP
AD	ROOM-318	ACTHTSET
AD	ROOM-318	ACTCLGSP
BD	ROOM-318	TEMPOVRD
BD	ROOM-318	SHUTDOWN
BD	ROOM-318	SAF-STAT
BD	ROOM-318	REV-VLVF
BD	ROOM-318	COMPRSFB
BO	ROOM-319	OCC-UNOC
AD	ROOM-319	SPACETMP
AD	ROOM-319	ACTHTSET
AD	ROOM-319	ACTCLGSP
BD	ROOM-319	TEMPOVRD
BD	ROOM-319	SHUTDOWN
BD	ROOM-319	SAF-STAT
BD	ROOM-319	REV-VLVF
BD	ROOM-319	COMPRSFB
BO	ROOM-320	OCC-UNOC
AD	ROOM-320	SPACETMP
AD	ROOM-320	ACTHTSET
AD	ROOM-320	ACTCLGSP
BD	ROOM-320	TEMPOVRD
BD	ROOM-320	SHUTDOWN
BD	ROOM-320	SAF-STAT
BD	ROOM-320	REV-VLVF
BD	ROOM-320	COMPRSFB
BO	ROOM-321	OCC-UNOC
AD	ROOM-321	SPACETMP

DRAFT

Building 288		
Points	**Equipment**	**Type**
AD	ROOM-321	ACTHTSET
AD	ROOM-321	ACTCLGSP
BD	ROOM-321	TEMPOVRD
BD	ROOM-321	SHUTDOWN
BD	ROOM-321	SAF-STAT
BD	ROOM-321	REV-VLVF
BD	ROOM-321	COMPRSFB
BO	ROOM-322	OCC-UNOC
AD	ROOM-322	SPACETMP
AD	ROOM-322	ACTHTSET
AD	ROOM-322	ACTCLGSP
BD	ROOM-322	TEMPOVRD
BD	ROOM-322	SHUTDOWN
BD	ROOM-322	SAF-STAT
BD	ROOM-322	REV-VLVF
BD	ROOM-322	COMPRSFB
BO	ROOM-401	OCC-UNOC
AD	ROOM-401	SPACETMP
AD	ROOM-401	ACTHTSET
AD	ROOM-401	ACTCLGSP
BD	ROOM-401	TEMPOVRD
BD	ROOM-401	SHUTDOWN
BD	ROOM-401	SAF-STAT
BD	ROOM-401	REV-VLVF
BD	ROOM-401	COMPRSFB
BO	ROOM-402	OCC-UNOC
AD	ROOM-402	SPACETMP
AD	ROOM-402	ACTHTSET
AD	ROOM-402	ACTCLGSP
BD	ROOM-402	TEMPOVRD
BD	ROOM-402	SHUTDOWN
BD	ROOM-402	SAF-STAT
BD	ROOM-402	REV-VLVF
BD	ROOM-402	COMPRSFB
BO	ROOM-403	OCC-UNOC
AD	ROOM-403	SPACETMP
AD	ROOM-403	ACTHTSET
AD	ROOM-403	ACTCLGSP

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-403	TEMPOVRD
BD	ROOM-403	SHUTDOWN
BD	ROOM-403	SAF-STAT
BD	ROOM-403	REV-VLVF
BD	ROOM-403	COMPRSFB
BO	ROOM-404	OCC-UNOC
AD	ROOM-404	SPACETMP
AD	ROOM-404	ACTHTSET
AD	ROOM-404	ACTCLGSP
BD	ROOM-404	TEMPOVRD
BD	ROOM-404	SHUTDOWN
BD	ROOM-404	SAF-STAT
BD	ROOM-404	REV-VLVF
BD	ROOM-404	COMPRSFB
BO	ROOM-405	OCC-UNOC
AD	ROOM-405	SPACETMP
AD	ROOM-405	ACTHTSET
AD	ROOM-405	ACTCLGSP
BD	ROOM-405	TEMPOVRD
BD	ROOM-405	SHUTDOWN
BD	ROOM-405	SAF-STAT
BD	ROOM-405	REV-VLVF
BD	ROOM-405	COMPRSFB
BO	ROOM-406	OCC-UNOC
AD	ROOM-406	SPACETMP
AD	ROOM-406	ACTHTSET
AD	ROOM-406	ACTCLGSP
BD	ROOM-406	TEMPOVRD
BD	ROOM-406	SHUTDOWN
BD	ROOM-406	SAF-STAT
BD	ROOM-406	REV-VLVF
BD	ROOM-406	COMPRSFB
BO	ROOM-407	OCC-UNOC
AD	ROOM-407	SPACETMP
AD	ROOM-407	ACTHTSET
AD	ROOM-407	ACTCLGSP
BD	ROOM-407	TEMPOVRD
BD	ROOM-407	SHUTDOWN

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-407	SAF-STAT
BD	ROOM-407	REV-VLVF
BD	ROOM-407	COMPRSFB
BO	ROOM-408	OCC-UNOC
AD	ROOM-408	SPACETMP
AD	ROOM-408	ACTHTSET
AD	ROOM-408	ACTCLGSP
BD	ROOM-408	TEMPOVRD
BD	ROOM-408	SHUTDOWN
BD	ROOM-408	SAF-STAT
BD	ROOM-408	REV-VLVF
BD	ROOM-408	COMPRSFB
BO	ROOM-409	OCC-UNOC
AD	ROOM-409	SPACETMP
AD	ROOM-409	ACTHTSET
AD	ROOM-409	ACTCLGSP
BD	ROOM-409	TEMPOVRD
BD	ROOM-409	SHUTDOWN
BD	ROOM-409	SAF-STAT
BD	ROOM-409	REV-VLVF
BD	ROOM-409	COMPRSFB
BO	ROOM-410	OCC-UNOC
AD	ROOM-410	SPACETMP
AD	ROOM-410	ACTHTSET
AD	ROOM-410	ACTCLGSP
BD	ROOM-410	TEMPOVRD
BD	ROOM-410	SHUTDOWN
BD	ROOM-410	SAF-STAT
BD	ROOM-410	REV-VLVF
BD	ROOM-410	COMPRSFB
BO	ROOM-412	OCC-UNOC
AD	ROOM-412	SPACETMP
AD	ROOM-412	ACTHTSET
AD	ROOM-412	ACTCLGSP
BD	ROOM-412	TEMPOVRD
BD	ROOM-412	SHUTDOWN
BD	ROOM-412	SAF-STAT
BD	ROOM-412	REV-VLVF

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-412	COMPRSFB
BO	ROOM-413	OCC-UNOC
AD	ROOM-413	SPACETMP
AD	ROOM-413	ACTHTSET
AD	ROOM-413	ACTCLGSP
BD	ROOM-413	TEMPOVRD
BD	ROOM-413	SHUTDOWN
BD	ROOM-413	SAF-STAT
BD	ROOM-413	REV-VLVF
BD	ROOM-413	COMPRSFB
BO	ROOM-414	OCC-UNOC
AD	ROOM-414	SPACETMP
AD	ROOM-414	ACTHTSET
AD	ROOM-414	ACTCLGSP
BD	ROOM-414	TEMPOVRD
BD	ROOM-414	SHUTDOWN
BD	ROOM-414	SAF-STAT
BD	ROOM-414	REV-VLVF
BD	ROOM-414	COMPRSFB
BO	ROOM-415	OCC-UNOC
AD	ROOM-415	SPACETMP
AD	ROOM-415	ACTHTSET
AD	ROOM-415	ACTCLGSP
BD	ROOM-415	TEMPOVRD
BD	ROOM-415	SHUTDOWN
BD	ROOM-415	SAF-STAT
BD	ROOM-415	REV-VLVF
BD	ROOM-415	COMPRSFB
BO	ROOM-416	OCC-UNOC
AD	ROOM-416	SPACETMP
AD	ROOM-416	ACTHTSET
AD	ROOM-416	ACTCLGSP
BD	ROOM-416	TEMPOVRD
BD	ROOM-416	SHUTDOWN
BD	ROOM-416	SAF-STAT
BD	ROOM-416	REV-VLVF
BD	ROOM-416	COMPRSFB
BO	ROOM-417	OCC-UNOC

DRAFT

Building 288		
Points	**Equipment**	**Type**
AD	ROOM-417	SPACETMP
AD	ROOM-417	ACTHTSET
AD	ROOM-417	ACTCLGSP
BD	ROOM-417	TEMPOVRD
BD	ROOM-417	SHUTDOWN
BD	ROOM-417	SAF-STAT
BD	ROOM-417	REV-VLVF
BD	ROOM-417	COMPRSFB
BO	ROOM-418	OCC-UNOC
AD	ROOM-418	SPACETMP
AD	ROOM-418	ACTHTSET
AD	ROOM-418	ACTCLGSP
BD	ROOM-418	TEMPOVRD
BD	ROOM-418	SHUTDOWN
BD	ROOM-418	SAF-STAT
BD	ROOM-418	REV-VLVF
BD	ROOM-418	COMPRSFB
BO	ROOM-419	OCC-UNOC
AD	ROOM-419	SPACETMP
AD	ROOM-419	ACTHTSET
AD	ROOM-419	ACTCLGSP
BD	ROOM-419	TEMPOVRD
BD	ROOM-419	SHUTDOWN
BD	ROOM-419	SAF-STAT
BD	ROOM-419	REV-VLVF
BD	ROOM-419	COMPRSFB
BO	ROOM-420	OCC-UNOC
AD	ROOM-420	SPACETMP
AD	ROOM-420	ACTHTSET
AD	ROOM-420	ACTCLGSP
BD	ROOM-420	TEMPOVRD
BD	ROOM-420	SHUTDOWN
BD	ROOM-420	SAF-STAT
BD	ROOM-420	REV-VLVF
BD	ROOM-420	COMPRSFB
BO	ROOM-421	OCC-UNOC
AD	ROOM-421	SPACETMP
AD	ROOM-421	ACTHTSET

DRAFT

Building 288		
Points	**Equipment**	**Type**
AD	ROOM-421	ACTCLGSP
BD	ROOM-421	TEMPOVRD
BD	ROOM-421	SHUTDOWN
BD	ROOM-421	SAF-STAT
BD	ROOM-421	REV-VLVF
BD	ROOM-421	COMPRSFB
BO	ROOM-422	OCC-UNOC
AD	ROOM-422	SPACETMP
AD	ROOM-422	ACTHTSET
AD	ROOM-422	ACTCLGSP
BD	ROOM-422	TEMPOVRD
BD	ROOM-422	SHUTDOWN
BD	ROOM-422	SAF-STAT
BD	ROOM-422	REV-VLVF
BD	ROOM-422	COMPRSFB
BO	ROOM-501	OCC-UNOC
AD	ROOM-501	SPACETMP
AD	ROOM-501	ACTHTSET
AD	ROOM-501	ACTCLGSP
BD	ROOM-501	TEMPOVRD
BD	ROOM-501	SHUTDOWN
BD	ROOM-501	SAF-STAT
BD	ROOM-501	REV-VLVF
BD	ROOM-501	COMPRSFB
BO	ROOM-502	OCC-UNOC
AD	ROOM-502	SPACETMP
AD	ROOM-502	ACTHTSET
AD	ROOM-502	ACTCLGSP
BD	ROOM-502	TEMPOVRD
BD	ROOM-502	SHUTDOWN
BD	ROOM-502	SAF-STAT
BD	ROOM-502	REV-VLVF
BD	ROOM-502	COMPRSFB
BO	ROOM-503	OCC-UNOC
AD	ROOM-503	SPACETMP
AD	ROOM-503	ACTHTSET
AD	ROOM-503	ACTCLGSP
BD	ROOM-503	TEMPOVRD

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-503	SHUTDOWN
BD	ROOM-503	SAF-STAT
BD	ROOM-503	REV-VLVF
BD	ROOM-503	COMPRSFB
BO	ROOM-504	OCC-UNOC
AD	ROOM-504	SPACETMP
AD	ROOM-504	ACTHTSET
AD	ROOM-504	ACTCLGSP
BD	ROOM-504	TEMPOVRD
BD	ROOM-504	SHUTDOWN
BD	ROOM-504	SAF-STAT
BD	ROOM-504	REV-VLVF
BD	ROOM-504	COMPRSFB
BO	ROOM-505	OCC-UNOC
AD	ROOM-505	SPACETMP
AD	ROOM-505	ACTHTSET
AD	ROOM-505	ACTCLGSP
BD	ROOM-505	TEMPOVRD
BD	ROOM-505	SHUTDOWN
BD	ROOM-505	SAF-STAT
BD	ROOM-505	REV-VLVF
BD	ROOM-505	COMPRSFB
BO	ROOM-506	OCC-UNOC
AD	ROOM-506	SPACETMP
AD	ROOM-506	ACTHTSET
AD	ROOM-506	ACTCLGSP
BD	ROOM-506	TEMPOVRD
BD	ROOM-506	SHUTDOWN
BD	ROOM-506	SAF-STAT
BD	ROOM-506	REV-VLVF
BD	ROOM-506	COMPRSFB
BO	ROOM-507	OCC-UNOC
AD	ROOM-507	SPACETMP
AD	ROOM-507	ACTHTSET
AD	ROOM-507	ACTCLGSP
BD	ROOM-507	TEMPOVRD
BD	ROOM-507	SHUTDOWN
BD	ROOM-507	SAF-STAT

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-507	REV-VLVF
BD	ROOM-507	COMPRSFB
BO	ROOM-508	OCC-UNOC
AD	ROOM-508	SPACETMP
AD	ROOM-508	ACTHTSET
AD	ROOM-508	ACTCLGSP
BD	ROOM-508	TEMPOVRD
BD	ROOM-508	SHUTDOWN
BD	ROOM-508	SAF-STAT
BD	ROOM-508	REV-VLVF
BD	ROOM-508	COMPRSFB
BO	ROOM-509	OCC-UNOC
AD	ROOM-509	SPACETMP
AD	ROOM-509	ACTHTSET
AD	ROOM-509	ACTCLGSP
BD	ROOM-509	TEMPOVRD
BD	ROOM-509	SHUTDOWN
BD	ROOM-509	SAF-STAT
BD	ROOM-509	REV-VLVF
BD	ROOM-509	COMPRSFB
BO	ROOM-510	OCC-UNOC
AD	ROOM-510	SPACETMP
AD	ROOM-510	ACTHTSET
AD	ROOM-510	ACTCLGSP
BD	ROOM-510	TEMPOVRD
BD	ROOM-510	SHUTDOWN
BD	ROOM-510	SAF-STAT
BD	ROOM-510	REV-VLVF
BD	ROOM-510	COMPRSFB
BO	ROOM-512	OCC-UNOC
AD	ROOM-512	SPACETMP
AD	ROOM-512	ACTHTSET
AD	ROOM-512	ACTCLGSP
BD	ROOM-512	TEMPOVRD
BD	ROOM-512	SHUTDOWN
BD	ROOM-512	SAF-STAT
BD	ROOM-512	REV-VLVF
BD	ROOM-512	COMPRSFB

DRAFT

Building 288		
Points	**Equipment**	**Type**
BO	ROOM-513	OCC-UNOC
AD	ROOM-513	SPACETMP
AD	ROOM-513	ACTHTSET
AD	ROOM-513	ACTCLGSP
BD	ROOM-513	TEMPOVRD
BD	ROOM-513	SHUTDOWN
BD	ROOM-513	SAF-STAT
BD	ROOM-513	REV-VLVF
BD	ROOM-513	COMPRSFB
BO	ROOM-514	OCC-UNOC
AD	ROOM-514	SPACETMP
AD	ROOM-514	ACTHTSET
AD	ROOM-514	ACTCLGSP
BD	ROOM-514	TEMPOVRD
BD	ROOM-514	SHUTDOWN
BD	ROOM-514	SAF-STAT
BD	ROOM-514	REV-VLVF
BD	ROOM-514	COMPRSFB
BO	ROOM-516	OCC-UNOC
AD	ROOM-516	SPACETMP
AD	ROOM-516	ACTHTSET
AD	ROOM-516	ACTCLGSP
BD	ROOM-516	TEMPOVRD
BD	ROOM-516	SHUTDOWN
BD	ROOM-516	SAF-STAT
BD	ROOM-516	REV-VLVF
BD	ROOM-516	COMPRSFB
BO	ROOM-517	OCC-UNOC
AD	ROOM-517	SPACETMP
AD	ROOM-517	ACTHTSET
AD	ROOM-517	ACTCLGSP
BD	ROOM-517	TEMPOVRD
BD	ROOM-517	SHUTDOWN
BD	ROOM-517	SAF-STAT
BD	ROOM-517	REV-VLVF
BD	ROOM-517	COMPRSFB
BO	ROOM-518	OCC-UNOC
AD	ROOM-518	SPACETMP

DRAFT

Building 288		
Points	**Equipment**	**Type**
AD	ROOM-518	ACTHTSET
AD	ROOM-518	ACTCLGSP
BD	ROOM-518	TEMPOVRD
BD	ROOM-518	SHUTDOWN
BD	ROOM-518	SAF-STAT
BD	ROOM-518	REV-VLVF
BD	ROOM-518	COMPRSFB
BO	ROOM-519	OCC-UNOC
AD	ROOM-519	SPACETMP
AD	ROOM-519	ACTHTSET
AD	ROOM-519	ACTCLGSP
BD	ROOM-519	TEMPOVRD
BD	ROOM-519	SHUTDOWN
BD	ROOM-519	SAF-STAT
BD	ROOM-519	REV-VLVF
BD	ROOM-519	COMPRSFB
BO	ROOM-520	OCC-UNOC
AD	ROOM-520	SPACETMP
AD	ROOM-520	ACTHTSET
AD	ROOM-520	ACTCLGSP
BD	ROOM-520	TEMPOVRD
BD	ROOM-520	SHUTDOWN
BD	ROOM-520	SAF-STAT
BD	ROOM-520	REV-VLVF
BD	ROOM-520	COMPRSFB
BO	ROOM-521	OCC-UNOC
AD	ROOM-521	SPACETMP
AD	ROOM-521	ACTHTSET
AD	ROOM-521	ACTCLGSP
BD	ROOM-521	TEMPOVRD
BD	ROOM-521	SHUTDOWN
BD	ROOM-521	SAF-STAT
BD	ROOM-521	REV-VLVF
BD	ROOM-521	COMPRSFB
BD	ROOM-522	COMPRSFB
AD	ROOM-522	ACTHTSET
BD	ROOM-522	REV-VLVF
AD	ROOM-522	SPACETMP

DRAFT

Building 288		
Points	**Equipment**	**Type**
BD	ROOM-522	SAF-STAT
BD	ROOM-522	SHUTDOWN
BD	ROOM-522	TEMPOVRD
AD	ROOM-522	ACTCLGSP
BO	ROOM-522	OCC-UNOC
AI	MECH-RM	KILOWATT
ACM	MECH-RM	KWAT-ACC
BO	MECH-RM	RESET-KW
BI	CHAS-EF3	EF-3
BO	CHAS-EF3	EF-3-C
AI	CHAS-EF3	CH-T
AOS	CHAS-EF3	EF3_STPT
BI	CHAS-EF4	EF-4
BO	CHAS-EF4	EF-4-C
AI	CHAS-EF4	CH-T
AOS	CHAS-EF4	EF4-STPT
BO	ROOM-515	OCC-UNOC
AD	ROOM-515	ACTHTSET
AD	ROOM-515	ACTCLGSP
BD	ROOM-515	TEMPOVRD
BD	ROOM-515	SHUTDOWN
BD	ROOM-515	SAF-STAT
BD	ROOM-515	REV-VLVF
BD	ROOM-515	COMPRSFB
AD	ROOM-515	SPACETMP
CS	NC2-CSOB	RM301-CS
CS	NC2-CSOB	RM302-CS
CS	NC2-CSOB	RM303-CS
CS	NC2-CSOB	RM304-CS
CS	NC2-CSOB	RM305-CS
CS	NC2-CSOB	RM306-CS
CS	NC2-CSOB	RM307-CS
CS	NC2-CSOB	RM308-CS
CS	NC2-CSOB	RM309-CS
CS	NC2-CSOB	RM310-CS
CS	NC2-CSOB	RM312-CS
CS	NC2-CSOB	RM313-CS
CS	NC2-CSOB	RM314-CS

DRAFT

Building 288		
Points	**Equipment**	**Type**
CS	NC2-CSOB	RM315-CS
CS	NC2-CSOB	RM316-CS
CS	NC2-CSOB	RM317-CS
CS	NC2-CSOB	RM318-CS
CS	NC2-CSOB	RM319-CS
CS	NC2-CSOB	RM320-CS
CS	NC2-CSOB	RM321-CS
CS	NC2-CSOB	RM322-CS
CS	NC2-CSOB	RM401-CS
CS	NC2-CSOB	RM402-CS
CS	NC2-CSOB	RM403-CS
CS	NC2-CSOB	RM404-CS
CS	NC2-CSOB	RM405-CS
CS	NC2-CSOB	RM406-CS
CS	NC2-CSOB	RM407-CS
CS	NC2-CSOB	RM408-CS
CS	NC2-CSOB	RM409-CS
CS	NC2-CSOB	RM410-CS
CS	NC2-CSOB	RM412-CS
CS	NC2-CSOB	RM413-CS
CS	NC2-CSOB	RM414-CS
CS	NC2-CSOB	RM415-CS
CS	NC2-CSOB	RM416-CS
CS	NC2-CSOB	RM417-CS
CS	NC2-CSOB	RM418-CS
CS	NC2-CSOB	RM419-CS
CS	NC2-CSOB	RM420-CS
CS	NC2-CSOB	RM421-CS
CS	NC2-CSOB	RM422-CS
CS	NC2-CSOB	RM501-CS
CS	NC2-CSOB	RM502-CS
CS	NC2-CSOB	RM503-CS
CS	NC2-CSOB	RM504-CS
CS	NC2-CSOB	RM505-CS
CS	NC2-CSOB	RM506-CS
CS	NC2-CSOB	RM507-CS
CS	NC2-CSOB	RM508-CS
CS	NC2-CSOB	RM509-CS

DRAFT

Building 288		
Points	**Equipment**	**Type**
CS	NC2-CSOB	RM510-CS
CS	NC2-CSOB	RM512-CS
CS	NC2-CSOB	RM513-CS
CS	NC2-CSOB	RM514-CS
CS	NC2-CSOB	RM515-CS
CS	NC2-CSOB	RM516-CS
CS	NC2-CSOB	RM517-CS
CS	NC2-CSOB	RM518-CS
CS	NC2-CSOB	RM519-CS
CS	NC2-CSOB	RM520-CS
CS	NC2-CSOB	RM521-CS
CS	NC2-CSOB	RM522-CS
CS	NC2-CSOB	ELEV-CS
CS	NC2-CSOB	WCOM-CS
CS	NC2-CSOB	ECOM-CS
CS	NC2-CSOB	EF-3-CSO
CS	NC2-CSOB	EF-4-CSO
CS	NC2-CSOB	MAU3-CSO
CS	NC2-CSOB	MAU4-CSO
CS	NC2-CSOB	MAU5-CSO
BD	MAU-05	SHUTDOWN
BD	MAU-05	SAF-ALRM
BD	MAU-05	SAF-STAT
AD	MAU-05	PHT-TEMP
AD	MAU-05	PHC-VALV
AD	MAU-05	DAT-TEMP
AD	MAU-05	RHC-VALV
BD	MAU-05	COMPR1SS
BD	MAU-05	COMPR2SS
AI	MAU-05	DA-HUM
AI	MAU-05	CC-T

DRAFT

Boone Clinic	Boone
NAE-01	
NAE-1/N2-1.N2_1	VAV
NAE-1/N2-1.N2_2	VAV
NAE-1/N2-1.Chlr-1	VAV
NAE-1/N2-1.Chlr-Med	VAV
NAE-1/FC-2.CHILLER	VAV
NAE-1/FC-2.BOILER	VAV
NAE-1/FC-2.RTU-1	VAV
NAE-1/FC-2.RTU-2	VAV
NAE-1/FC-2.VAV-1-1	VAV
NAE-1/FC-2.VAV-1-2	VAV
NAE-1/FC-2.VAV-1-3	VAV
NAE-1/FC-2.VAV-1-4	VAV
NAE-1/FC-2.VAV-1-5	VAV
NAE-1/FC-2.VAV-1-6	VAV
NAE-1/FC-2.VAV-1-7	VAV
NAE-1/FC-2.VAV-1-8	VAV
NAE-1/FC-2.VAV-1-9	VAV
NAE-1/FC-2.VAV-1-10	VAV
NAE-1/FC-2.VAV-1-11	VAV
NAE-1/FC-2.VAV-1-12	VAV
NAE-1/FC-2.VAV-1-13	VAV
NAE-1/FC-2.VAV-1-14	VAV
NAE-1/FC-2.VAV-1-15	VAV
NAE-1/FC-2.VAV-1-16	VAV
NAE-1/FC-2.VAV-1-17	VAV
NAE-1/FC-2.VAV-1-18	VAV
NAE-1/FC-2.VAV-1-19	VAV
NAE-1/FC-2.VAV-1-20	VAV
NAE-1/FC-2.VAV-1-21	VAV
NAE-1/FC-2.VAV-1-22	VAV
NAE-1/FC-2.VAV-1-23	VAV
:NAE-1/FC-2.VAV-1-24	VAV
NAE-1/FC-2.VAV-1-25	VAV
NAE-1/FC-2.VAV-1-26	VAV
NAE-1/FC-2.VAV-1-27	VAV
NAE-1/FC-2.VAV-1-28	VAV
NAE-1/FC-2.VAV-1-29	VAV
NAE-1/FC-2.VAV-1-30	VAV
NAE-1/FC-2.VAV-1-31	VAV
NAE-1/FC-2.VAV-1-32	VAV
NAE-1/FC-2.VAV-1-33	VAV
NAE-1/FC-2.VAV-2-1	VAV
NAE-1/FC-2.VAV-2-2	VAV

DRAFT

Boone Clinic	Boone
NAE-1/FC-2.VAV-2-3	VAV
NAE-1/FC-2.VAV-2-4	VAV
NAE-1/FC-2.VAV-2-5	VAV
NAE-1/FC-2.VAV-2-6	VAV
NAE-1/FC-2.VAV-2-7	VAV
NAE-1/FC-2.VAV-2-8	VAV
NAE-1/FC-2.VAV-2-9	VAV
NAE-1/FC-2.VAV-2-10	VAV
NAE-1/FC-2.VAV-2-11	VAV
NAE-1/FC-2.VAV-2-12	VAV
NAE-1/FC-2.VAV-2-13	VAV
NAE-1/FC-2.VAV-2-14	VAV
NAE-1/FC-2.VAV-2-15	VAV
NAE-1/FC-2.VAV-2-16	VAV
NAE-1/FC-2.VAV-2-17	VAV
NAE-1/FC-2.VAV-2-18	VAV
NAE-1/FC-2.VAV-2-19	VAV
NAE-1/FC-2.VAV-2-20	VAV
NAE-1/FC-2.VAV-2-21	VAV
NAE-1/FC-2.VAV-2-22	VAV
NAE-1/FC-2.VAV-2-23	VAV
NAE-1/FC-2.VAV-2-24	VAV
NAE-1/FC-2.VAV-2-25	VAV
NAE-1/FC-2.VAV-2-26	VAV
NAE-1/FC-2.VAV-2-27	VAV
NAE-1/FC-2.VAV-2-28	VAV
NAE-1/FC-2.VAV-2-29	VAV
NAE-1/FC-2.VAV-2-30	VAV
NAE-1/FC-2.VAV-2-31	VAV
NAE-1/FC-2.VAV-2-32	VAV
NAE-1/FC-2.VAV-2-33	VAV
AI	Boone Clinic.R1SF-STA
AI	Boone Clinic.R1RF-STA
AI	Boone Clinic.RT1-SASP
AI	Boone Clinic.RT1-SPLP
AI	Boone Clinic.RT1-RAT
AI	Boone Clinic.RT1-MAT
AI	Boone Clinic.RT1-SAT
AI	Boone Clinic.OAT-AP
AI	Boone Clinic.RT1-CVLP
AI	Boone Clinic.RT1-HVLP
AI	Boone Clinic.3AVG-SPT
AI	Boone Clinic.R2SF-STA
AI	Boone Clinic.R2RF-STA
AI	Boone Clinic.RT2-SASP

DRAFT

Boone Clinic	Boone
AI	Boone Clinic.RT2-SPLP
AI	Boone Clinic.RT2-RAT
AI	Boone Clinic.RT2-MAT
AI	Boone Clinic.RT2-SAT
AI	Boone Clinic.RT2-CVLP
AI	Boone Clinic.RT2-HVLP
AI	Boone Clinic.4AVG-SPT
AI	Boone Clinic.RT2-DCLP
AI	Boone Clinic.CH-STA
AI	Boone Clinic.CST-DEN
AI	Boone Clinic.CRT-DEN
AI	Boone Clinic.HST-DEN
AI	Boone Clinic.HRT-DEN
AI	Boone Clinic.HWS-PT
AI	Boone Clinic.DPV-LP
AI	Boone Clinic.OUTSIDE
AI	Boone Clinic.V9-10SPT
AI	Boone Clinic.V9-10-LP
AI	Boone Clinic.VB11-SPT
AI	Boone Clinic.VB11-LP
AI	Boone Clinic.VB12-SPT
AI	Boone Clinic.VB12-LP
AI	Boone Clinic.VB13-SPT
AI	Boone Clinic.VB13-LP
AI	Boone Clinic.VVB1-SPC
AI	Boone Clinic.VVB1-LP1
AI	Boone Clinic.VVB1-LP2
AI	Boone Clinic.VVB2-SPT
AI	Boone Clinic.VVB2-LP1
AI	Boone Clinic.VVB2-LP2
AI	Boone Clinic.VB1-SPT
AI	Boone Clinic.VB1-LP
AI	Boone Clinic.VB2-SPT
AI	Boone Clinic.VB2-LP
AI	Boone Clinic.VB3-SPT
AI	Boone Clinic.VB3-LP
AI	Boone Clinic.VB4-SPT
AI	Boone Clinic.VB4-LP
AI	Boone Clinic.VB5-SPT
AI	Boone Clinic.VB5-LP
AI	Boone Clinic.VB6-SPT
AI	Boone Clinic.VB6-LP
AI	Boone Clinic.VB7-SPT
AI	Boone Clinic.VB7-LP
AI	Boone Clinic.VB8-SPT

DRAFT

Boone Clinic	Boone
AI	Boone Clinic.VB8-LP
AI	Boone Clinic.RESET
AI	Boone Clinic.OA-TEMP
AO	Boone Clinic.KEY2-MC
AO	Boone Clinic.RT1-SVD
AO	Boone Clinic.RT1-RVD
AO	Boone Clinic.RT1-CV
AO	Boone Clinic.RT1-HV
AO	Boone Clinic.RT1-DC
AO	Boone Clinic.RT1-DC-P
AO	Boone Clinic.RT1RF-MC
AO	Boone Clinic.RT2RF-MC
AO	Boone Clinic.RT2-SVD
AO	Boone Clinic.RT2-RVD
AO	Boone Clinic.RT2-CV
AO	Boone Clinic.RT2-HV
AO	Boone Clinic.RT2-DC
AO	Boone Clinic.R2-DC-P
AO	Boone Clinic.COOL-MC
AO	Boone Clinic.SCV-DEN
AO	Boone Clinic.HEAT-MC
AO	Boone Clinic.HWS-DPV
AO	Boone Clinic.V9-10-HV
AO	Boone Clinic.VB11-HV
AO	Boone Clinic.VB12-HV
AO	Boone Clinic.VB13-HV
AO	Boone Clinic.VVB1-DC
AO	Boone Clinic.VVB1-HV
AO	Boone Clinic.VVB2-DC
AO	Boone Clinic.VVB2-HV
AO	Boone Clinic.VB1-HV
AO	Boone Clinic.VB2-HV
AO	Boone Clinic.VB3-HV
AO	Boone Clinic.VB4-HV
AO	Boone Clinic.VB5-HV
AO	Boone Clinic.VB6-HV
AO	Boone Clinic.VB7-HV
AO	Boone Clinic.VB8-HV
BI	Boone Clinic.RTU1-SD
BI	Boone Clinic.SMK-KEY2
BI	Boone Clinic.RTU2-SD
BI	Boone Clinic.HWP1-STA
BI	Boone Clinic.HWP2-STA
BI	Boone Clinic.CWP-STA
BI	Boone Clinic.DENFLR1

DRAFT

Boone Clinic	Boone
BI	Boone Clinic.DENFLR2
BO	Boone Clinic.R1RF-SS
BO	Boone Clinic.R1SF-SS
BO	Boone Clinic.R2SF-SS
BO	Boone Clinic.R2RF-SS
BO	Boone Clinic.HWP1-SS
BO	Boone Clinic.HWP2-SS
BO	Boone Clinic.CWP-SS
BO	Boone Clinic.CH-SS-DN
AI	Boone Clinic.A1SF-STA
AI	Boone Clinic.A1RF-STA
AI	Boone Clinic.OAT-1
AI	Boone Clinic.AH1-RAT
AI	Boone Clinic.AH1-MAT
AI	Boone Clinic.AH1-CDT
AI	Boone Clinic.AH1-HDT
AI	Boone Clinic.AH1-HRS
AI	Boone Clinic.AH1-CVLP
AI	Boone Clinic.CDT-RSET
AI	Boone Clinic.1AVG-SPT
AI	Boone Clinic.A2SF-STA
AI	Boone Clinic.A2RF-STA
AI	Boone Clinic.AH2-RAT
AI	Boone Clinic.AH2-MAT
AI	Boone Clinic.AH2-CDT
AI	Boone Clinic.AH2-HDT
AI	Boone Clinic.AH2-HRS
AI	Boone Clinic.AH2-CVLP
AI	Boone Clinic.2AVG-SPT
AI	Boone Clinic.OAT-2
AI	Boone Clinic.MB47-SPT
AI	Boone Clinic.MB48-SPT
AI	Boone Clinic.MB49-SPT
AI	Boone Clinic.MB50-SPT
AI	Boone Clinic.MB51-SPT
AI	Boone Clinic.MB52-SPT
AI	Boone Clinic.MB54-SPT
AI	Boone Clinic.MB56-SPT
AI	Boone Clinic.MB43-SPT
AI	Boone Clinic.MB44-SPT
AI	Boone Clinic.MB45-SPT
AI	Boone Clinic.MB46-SPT
AI	Boone Clinic.MB61-SPT
AI	Boone Clinic.MB63-SPT
AI	Boone Clinic.MB67-SPT

DRAFT

Boone Clinic	Boone
AI	Boone Clinic.MB32-SPT
AI	Boone Clinic.MB41-SPT
AI	Boone Clinic.MB42-SPT
AI	Boone Clinic.MB70-SPT
AI	Boone Clinic.MB31-SPT
AI	Boone Clinic.MB65-SPT
AI	Boone Clinic.MB30-SPT
AI	Boone Clinic.MB33-SPT
AI	Boone Clinic.MB34-SPT
AI	Boone Clinic.MB35-SPT
AI	Boone Clinic.MB37-SPT
AI	Boone Clinic.MB38-SPT
AI	Boone Clinic.MB39-SPT
AI	Boone Clinic.MB40-SPT
AI	Boone Clinic.MB23-SPT
AI	Boone Clinic.MB24-SPT
AI	Boone Clinic.MB26-SPT
AI	Boone Clinic.MB27-SPT
AI	Boone Clinic.MB28-SPT
AI	Boone Clinic.MB29-SPT
AI	Boone Clinic.MB36-SPT
AI	Boone Clinic.MB16-SPT
AI	Boone Clinic.MB17-SPT
AI	Boone Clinic.MB18-SPT
AI	Boone Clinic.MB20-SPT
AI	Boone Clinic.MB21-SPT
AI	Boone Clinic.MB22-SPT
AI	Boone Clinic.MB19-SPT
AI	Boone Clinic.MB12-SPT
AI	Boone Clinic.MB13-SPT
AI	Boone Clinic.MB14-SPT
AI	Boone Clinic.MB15-SPT
AI	Boone Clinic.MB25-SPT
AI	Boone Clinic.MB68-SPT
AI	Boone Clinic.MB69-SPT
AI	Boone Clinic.MB71-SPT
AI	Boone Clinic.MB9-SPT
AI	Boone Clinic.MB10-SPT
AI	Boone Clinic.MB11-SPT
AI	Boone Clinic.MB62-SPT
AI	Boone Clinic.MB64-SPT
AI	Boone Clinic.MB72-SPT
AI	Boone Clinic.MB8-SPT
AI	Boone Clinic.MB1-SPT
AI	Boone Clinic.MB53-SPT

DRAFT

Boone Clinic	Boone
AI	Boone Clinic.MB55-SPT
AI	Boone Clinic.MB57-SPT
AI	Boone Clinic.MB59-SPT
AI	Boone Clinic.MB60-SPT
AI	Boone Clinic.MB58-SPT
AI	Boone Clinic.MB-2-SPT
AI	Boone Clinic.MB3-SPT
AI	Boone Clinic.MB4-SPT
AI	Boone Clinic.MB5-SPT
AI	Boone Clinic.MB6-SPT
AI	Boone Clinic.MB7-SPT
AI	Boone Clinic.P1-STA
AI	Boone Clinic.P2-STA
AI	Boone Clinic.P3-STA
AI	Boone Clinic.CH-STA-1
AI	Boone Clinic.CH-STA-2
AI	Boone Clinic.P-AIR-T
AI	Boone Clinic.P-AIR-P
AI	Boone Clinic.HST-MED
AI	Boone Clinic.HRT-MED
AI	Boone Clinic.CST-MED
AI	Boone Clinic.CRT-MED
AI	Boone Clinic.OAT
AI	Boone Clinic.RESET
AO	Boone Clinic.KEY1-MC
AO	Boone Clinic.AH1-CV
AO	Boone Clinic.AH1-DC
AO	Boone Clinic.AH1-HV
AO	Boone Clinic.AET1-DCP
AO	Boone Clinic.A1-SMOKE
AO	Boone Clinic.A2RF-MC
AO	Boone Clinic.KEY2-MC
AO	Boone Clinic.AH2-CV
AO	Boone Clinic.AH2-HV
AO	Boone Clinic.AH2-DC
AO	Boone Clinic.AET2-DCP
AO	Boone Clinic.A2-SMOKE
AO	Boone Clinic.MB47-DC
AO	Boone Clinic.MB48-DC
AO	Boone Clinic.MB49-DC
AO	Boone Clinic.MB50-DC
AO	Boone Clinic.MB51-DC
AO	Boone Clinic.MB52-DC
AO	Boone Clinic.MB54-DC
AO	Boone Clinic.MB56-DC

DRAFT

Boone Clinic	Boone
AO	Boone Clinic.MB43-DC
AO	Boone Clinic.MB44-DC
AO	Boone Clinic.MB45-DC
AO	Boone Clinic.MB46-DC
AO	Boone Clinic.MB61-DC
AO	Boone Clinic.MB63-DC
AO	Boone Clinic.MB67-CDC
AO	Boone Clinic.MB67-HDC
AO	Boone Clinic.MB32-DC
AO	Boone Clinic.MB41-DC
AO	Boone Clinic.MB42-DC
AO	Boone Clinic.MB70-DC
AO	Boone Clinic.MB31-HDC
AO	Boone Clinic.MB31-CDC
AO	Boone Clinic.MB65-HDC
AO	Boone Clinic.MB65-CDC
AO	Boone Clinic.MB30-DC
AO	Boone Clinic.MB33-DC
AO	Boone Clinic.MB34-DC
AO	Boone Clinic.MB35-DC
AO	Boone Clinic.MB37-DC
AO	Boone Clinic.MB38-DC
AO	Boone Clinic.MB39-DC
AO	Boone Clinic.MB40-DC
AO	Boone Clinic.MB23-DC
AO	Boone Clinic.MB24-DC
AO	Boone Clinic.MB26-DC
AO	Boone Clinic.MB27-DC
AO	Boone Clinic.MB28-DC
AO	Boone Clinic.MB29-DC
AO	Boone Clinic.MB36-CDC
AO	Boone Clinic.MB36-HDC
AO	Boone Clinic.MB16-DC
AO	Boone Clinic.MB17-DC
AO	Boone Clinic.MB18-DC
AO	Boone Clinic.MB20-DC
AO	Boone Clinic.MB21-DC
AO	Boone Clinic.MB22-DC
AO	Boone Clinic.MB19-CDC
AO	Boone Clinic.MB19-HDC
AO	Boone Clinic.MB12-DC
AO	Boone Clinic.MB13-DC
AO	Boone Clinic.MB14-DC
AO	Boone Clinic.MB15-DC
AO	Boone Clinic.MB25-DC

DRAFT

Boone Clinic	Boone
AO	Boone Clinic.MB68-DC
AO	Boone Clinic.MB69-DC
AO	Boone Clinic.MB71-DC
AO	Boone Clinic.MB9-DC
AO	Boone Clinic.MB10-DC
AO	Boone Clinic.MB11-DC
AO	Boone Clinic.MB62-DC
AO	Boone Clinic.MB64-DC
AO	Boone Clinic.MB72-DC
AO	Boone Clinic.MB8-CDC
AO	Boone Clinic.MB8-HDC
AO	Boone Clinic.MB1-DC
AO	Boone Clinic.MB53-DC
AO	Boone Clinic.MB55-DC
AO	Boone Clinic.MB57-DC
AO	Boone Clinic.MB59-DC
AO	Boone Clinic.MB60-DC
AO	Boone Clinic.MB58-CDC
AO	Boone Clinic.MB58-HDC
AO	Boone Clinic.MB2-DC
AO	Boone Clinic.MB3-DC
AO	Boone Clinic.MB4-DC
AO	Boone Clinic.MB5-DC
AO	Boone Clinic.MB6-CDC
AO	Boone Clinic.MB6-HDC
AO	Boone Clinic.MB7-CDC
AO	Boone Clinic.MB7-HDC
AO	Boone Clinic.HEAT-MC
AO	Boone Clinic.HEAT-IL
AO	Boone Clinic.COOL-MC
BI	Boone Clinic.AH1-SD
BI	Boone Clinic.SMK-KEY1
BI	Boone Clinic.AH2-SD
BI	Boone Clinic.PRV12-HL
BI	Boone Clinic.PRV16-HL
BI	Boone Clinic.PRV13-HL
BI	Boone Clinic.PRV20-HL
BI	Boone Clinic.PRV32-HL
BI	Boone Clinic.PRV29-HL
BI	Boone Clinic.PRV7-HL
BI	Boone Clinic.PRV28-HL
BI	Boone Clinic.PRV27-HL
BI	Boone Clinic.LOADSHED
BI	Boone Clinic.P-AIR-ST
BI	Boone Clinic.FLRPLN1A

DRAFT

Boone Clinic	Boone
BI	Boone Clinic.FLRPLN2A
BI	Boone Clinic.FLRPLN1B
BI	Boone Clinic.FLRPLN2B
BO	Boone Clinic.A1SF-SS
BO	Boone Clinic.A1RF-SS
BO	Boone Clinic.A2SF-SS
BO	Boone Clinic.A2RF-SS
BO	Boone Clinic.SPAREKEY
BO	Boone Clinic.PRV12-SS
BO	Boone Clinic.PRV16-SS
BO	Boone Clinic.PRV13-SS
BO	Boone Clinic.PRV20-SS
BO	Boone Clinic.PRV32-SS
BO	Boone Clinic.PRV29-SS
BO	Boone Clinic.PRV7-SS
BO	Boone Clinic.PRV28-SS
BO	Boone Clinic.PRV27-SS
BO	Boone Clinic.P1-CHILR
BO	Boone Clinic.P2-SPARE
BO	Boone Clinic.P3-HEAT
BO	Boone Clinic.CHILL-SS
BO	Boone Clinic.BOILER1
BO	Boone Clinic.BOILER2
AI	Boone Clinic.Evap-Leaving-Wtr -Temp
AI	Boone Clinic.Evap-Entering-Wtr-Temp
AI	Boone Clinic.%RLA
AI	Boone Clinic.Evaporator Refrig Pressure
AI	Boone Clinic.Evaporator Refrig Temperature
AI	Boone Clinic.Evaporator Refrig Temperature
AI	Boone Clinic.Condenser Refrig Pressure
AI	Boone Clinic.Condenser Refrig Pressure
AI	Boone Clinic.Condenser Refrig Temperature
AO	Boone Clinic.Chilled Water Setpoint
AO	Boone Clinic.Current Limit Setpoint
BI	Boone Clinic.Chiller Status
BO	Boone Clinic.Chiller Enable
BI	Boone Clinic.Auto Reset Alarm
BI	Boone Clinic.Manual Reset Alarm
BI	Boone Clinic.Compressor A Status
BI	Boone Clinic.Compressor B Status
AI	Boone Clinic.Evap-Leaving-Wtr-Temp
AI	Boone Clinic.Evap-Entering-Wtr-Temp
AI	Boone Clinic.%RLA

DRAFT

Boone Clinic	Boone
AI	Boone Clinic.Evaporator Refrig Pressure
AI	Boone Clinic.Evaporator Refrig Temperature
AI	Boone Clinic.Evaporator Refrig Temperature
AI	Boone Clinic.Condenser Refrig Pressure
AI	Boone Clinic.Condenser Refrig Pressure
AI	Boone Clinic.Condenser Refrig Temperature
AO	Boone Clinic.Chilled Water Setpoint
AO	Boone Clinic.Current Limit Setpoint
BI	Boone Clinic.Chiller Status
BI	Boone Clinic.Auto Reset Alarm
BO	Boone Clinic.Chiller Enable
BI	Boone Clinic.Manual Reset Alarm
BI	Boone Clinic.Compressor A Status
BI	Boone Clinic.Compressor B Status
AV	RTU-1 Zone Temp
AV	RTU-1 Zone Low 1
AV	RTU-1 Zone Low 2
AV	RTU-2 Zone Temp
AV	RTU-2 Zone Low 1
AV	RTU-2 Zone Low 2
AV	OST Heating Setpoint
AV	OST Cooling Setpoint
MV	RTU-1 WC-C
MV	RTU-2 WC-C
BV	Pump Rotate
AI	Dental.CHILLER.OA-T
BV	Dental.CHILLER.SYSTEM-EN
BV	Dental.CHILLER.CHWP-ROT
AV	Dental.CHILLER.CLGOATLOCKOUT-SP
AI	Dental.CHILLER.CHWS-T
AI	Dental.CHILLER.CHWR-T
BI	Dental.CHILLER.CHWP1-S
BO	Dental.CHILLER.CHWP1-C
BI	Dental.CHILLER.CHWP2-S
BO	Dental.CHILLER.CHWP2-C
AV	Dental.CHILLER.CHWP2-RUNTIME
AV	Dental.CHILLER.CHWP1-RUNTIME
MV	Dental.CHILLER.CHWP1-MS
MV	Dental.CHILLER.CHWP2-MS
MV	Dental.CHILLER.CH1-EN
BI	Dental.CHILLER.UH-S
BI	Dental.CHILLER.CH1-S
BI	Dental.CHILLER.CH1-A

DRAFT

Boone Clinic	Boone
BO	Dental.CHILLER.CH1-C
MV	Dental.Chiller.CH1-MS
AV	Dental.BOILER.OA-T
BV	Dental.BOILER.SYSTEM-EN
BV	Dental.BOILER.HWP-ROT
AV	Dental.BOILER.HTGOATLOCKOUT-SP
AI	Dental.BOILER.HWS-T
AI	Dental.BOILER.HWR-T
BI	Dental.BOILER.HWP3-S
BO	Dental.BOILER.HWP3-C
BI	Dental.BOILER.HWP4-S
BO	Dental.BOILER.HWP4-C
BO	Dental.BOILER.BLR1-C
BI	Dental.BOILER.BLR1-A
AV	Dental.BOILER.HWP3-RUNTIME
AV	Dental.BOILER.HWP4-RUNTIME
AV	Dental.BOILER.HWT-OARSTB
AV	Dental.BOILER.HWT-OARSTA
AV	Dental.BOILER.HWTLO-SP
AV	Dental.BOILER.HW-SP
AV	Dental.BOILER.HWTHI-SP
AO	Dental.Boiler.HW-VLV
BI	Dental.BOILER.BLR1-S
AV	Dental.RTU-1.OA-T
AV	Dental.RTU-1.ZN-T
MV	Dental.RTU-1.WC-C
AI	Dental.RTU-1.DA-T
MV	Dental.RTU-1.OCC-SCHEDULE
AV	Dental.RTU-1.EFFDAT-SP
AV	Dental.RTU-1.DAT-SP
AI	Dental.RTU-1.DA-P
AV	Dental.RTU-1.DAP-SP
AV	Dental.RTU-1.PHT-SP
BO	Dental.RTU-1.SF-C
BI	Dental.RTU-1.SF-S
AO	Dental.RTU-1.SF-O
AI	Dental.RTU-1.PH-T
AO	Dental.RTU-1.HTG-O
AO	Dental.RTU-1.CLG-O
AO	Dental.RTU-1.MAD-O
AV	Dental.RTU-1.OAD-MINPOS
AV	Dental.RTU-1.HTGUNOCC-SP
AV	Dental.RTU-1.CLGUNOCC-SP
MV	Dental.RTU-1.APP-MODE
BV	Dental.RTU-1.PH-EN

DRAFT

Boone Clinic	Boone
BV	Dental.RTU-1.CLG-EN
MV	Dental.RTU-1.UNITEN-MODE
BI	Dental.RTU-1.LT-A
BI	Dental.RTU-1.HP-A
BI	Dental.RTU-1.SF-A
BI	Dental.RTU-1.FINFLT-S
BI	Dental.RTU-1.PREFLT-S
AV	Dental.RTU-2.OA-T
AV	Dental.RTU-2.ZN-T
MV	Dental.RTU-2.WC-C
AI	Dental.RTU-2.DA-T
MV	Dental.RTU-2.OCC-SCHEDULE
AV	Dental.RTU-2.EFFDAT-SP
AV	Dental.RTU-2.DAT-SP
AI	Dental.RTU-2.DA-P
AV	Dental.RTU-2.DAP-SP
AV	Dental.RTU-2.PHT-SP
BO	Dental.RTU-2.SF-C
BI	Dental.RTU-2.SF-S
AO	Dental.RTU-2.SF-O
AI	Dental.RTU-2.PH-T
AO	Dental.RTU-2.HTG-O
AO	Dental.RTU-2.CLG-O
AO	Dental.RTU-2.MAD-O
AV	Dental.RTU-2.OAD-MINPOS
AV	Dental.RTU-2.HTGUNOCC-SP
AV	Dental.RTU-2.CLGUNOCC-SP
MV	Dental.RTU-2.APP-MODE
BV	Dental.RTU-2.PH-EN
BV	Dental.RTU-2.CLG-EN
MV	Dental.RTU-2.UNITEN-MODE
BI	Dental.RTU-2.LT-A
BI	Dental.RTU-2.HP-A
BI	Dental.RTU-2.SF-A
BI	Dental.RTU-2.FINFLT-S
BI	Dental.RTU-2.PREFLT-S
AI	Dental.VAV-1-1.RM-239.ZN-T
MV	Dental.VAV-1-1.RM-239.WC-C
AV	Dental.VAV-1-1.RM-239.SA-T
MV	Dental.VAV-1-1.RM-239.OCC-SCHEDULE
BO	Dental.VAV-1-1.RM-239.EF15-C
MV	Dental.VAV-1-1.RM-239.UNITEN-MODE
AV	Dental.VAV-1-1.RM-239.EFFHTG-SP
AV	Dental.VAV-1-1.RM-239.EFFCLG-SP

DRAFT

Boone Clinic	Boone
AO	Dental.VAV-1-1.RM-239.HTG-O
AI	Dental.VAV-1-1.RM-239.DA-T
AO	Dental.VAV-1-1.RM-239.DPR-O
AV	Dental.VAV-1-1.RM-239.SA-F
AV	Dental.VAV-1-1.RM-239.SAFLOW-SP
AI	Dental.VAV-1-1.RM-239.DA-VP
MV	Dental.VAV-1-1.RM-239.SYSTEM-MODE
BI	Dental.VAV-1-1.RM-239.EF15-S
AV	Dental.VAV-1-1.RM-239.ZN-SP
AI	Dental.VAV-1-2.RM-255.ZN-T
MV	Dental.VAV-1-2.RM-255.WC-C
AV	Dental.VAV-1-2.RM-255.SA-T
MV	Dental.VAV-1-2.RM-255.OCC-SCHEDULE
MV	Dental.VAV-1-2.RM-255.UNITEN-MODE
AV	Dental.VAV-1-2.RM-255.EFFHTG-SP
AV	Dental.VAV-1-2.RM-255.EFFCLG-SP
AO	Dental.VAV-1-2.RM-255.HTG-O
AI	Dental.VAV-1-2.RM-255.DA-T
AO	Dental.VAV-1-2.RM-255.DPR-O
AV	Dental.VAV-1-2.RM-255.SA-F
AV	Dental.VAV-1-2.RM-255.SAFLOW-SP
AI	Dental.VAV-1-2.RM-255.DA-VP
MV	Dental.VAV-1-2.RM-255.SYSTEM-MODE
AV	Dental.VAV-1-2.RM-255.ZN-SP
AI	Dental.VAV-1-3.RM-242.ZN-T
MV	Dental.VAV-1-3.RM-242.WC-C
AV	Dental.VAV-1-3.RM-242.SA-T
MV	Dental.VAV-1-3.RM-242.OCC-SCHEDULE
MV	Dental.VAV-1-3.RM-242.UNITEN-MODE
AV	Dental.VAV-1-3.RM-242.EFFHTG-SP
AV	Dental.VAV-1-3.RM-242.EFFCLG-SP
AO	Dental.VAV-1-3.RM-242.HTG-O
AI	Dental.VAV-1-3.RM-242.DA-T
AO	Dental.VAV-1-3.RM-242.DPR-O
AV	Dental.VAV-1-3.RM-242.SA-F
AV	Dental.VAV-1-3.RM-242.SAFLOW-SP
AI	Dental.VAV-1-3.RM-242.DA-VP
MV	Dental.VAV-1-3.RM-242.SYSTEM-MODE
AV	Dental.VAV-1-3.RM-242.ZN-SP
AI	Dental.VAV-1-4.RM-240.ZN-T
MV	Dental.VAV-1-4.RM-240.WC-C

DRAFT

Boone Clinic	Boone
AV	Dental.VAV-1-4.RM-240.SA-T
MV	Dental.VAV-1-4.RM-240.OCC-SCHEDULE
MV	Dental.VAV-1-4.RM-240.UNITEN-MODE
AV	Dental.VAV-1-4.RM-240.EFFHTG-SP
AV	Dental.VAV-1-4.RM-240.EFFCLG-SP
AO	Dental.VAV-1-4.RM-240.HTG-O
AI	Dental.VAV-1-4.RM-240.DA-T
AO	Dental.VAV-1-4.RM-240.DPR-O
AV	Dental.VAV-1-4.RM-240.SA-F
AV	Dental.VAV-1-4.RM-240.SAFLOW-SP
AI	Dental.VAV-1-4.RM-240.DA-VP
MV	Dental.VAV-1-4.RM-240.SYSTEM-MODE
AV	Dental.VAV-1-4.RM-240.ZN-SP
AI	Dental.VAV-1-5.RM-255.ZN-T
MV	Dental.VAV-1-5.RM-255.WC-C
AV	Dental.VAV-1-5.RM-255.SA-T
MV	Dental.VAV-1-5.RM-255.OCC-SCHEDULE
MV	Dental.VAV-1-5.RM-255.UNITEN-MODE
AV	Dental.VAV-1-5.RM-255.EFFHTG-SP
AV	Dental.VAV-1-5.RM-255.EFFCLG-SP
AO	Dental.VAV-1-5.RM-255.HTG-O
AI	Dental.VAV-1-5.RM-255.DA-T
AO	Dental.VAV-1-5.RM-255.DPR-O
AV	Dental.VAV-1-5.RM-255.SA-F
AV	Dental.VAV-1-5.RM-255.SAFLOW-SP
AI	Dental.VAV-1-5.RM-255.DA-VP
MV	Dental.VAV-1-5.RM-255.SYSTEM-MODE
AV	Dental.VAV-1-5.RM-255.ZN-SP
AI	Dental.VAV-1-6.RM-255.ZN-T
MV	Dental.VAV-1-6.RM-255.WC-C
AV	Dental.VAV-1-6.RM-255.SA-T
MV	Dental.VAV-1-6.RM-255.OCC-SCHEDULE
MV	Dental.VAV-1-6.RM-255.UNITEN-MODE
AV	Dental.VAV-1-6.RM-255.EFFHTG-SP
AV	Dental.VAV-1-6.RM-255.EFFCLG-SP
AO	Dental.VAV-1-6.RM-255.HTG-O
AI	Dental.VAV-1-6.RM-255.DA-T
AO	Dental.VAV-1-6.RM-255.DPR-O
AV	Dental.VAV-1-6.RM-255.SA-F
AV	Dental.VAV-1-6.RM-255.SAFLOW-SP
AI	Dental.VAV-1-6.RM-255.DA-VP

DRAFT

Boone Clinic	Boone
MV	Dental.VAV-1-6.RM-255.SYSTEM-MODE
AV	Dental.VAV-1-6.RM-255.ZN-SP
AI	Dental.VAV-1-7.RM-243.ZN-T
MV	Dental.VAV-1-7.RM-243.WC-C
AV	Dental.VAV-1-7.RM-243.SA-T
MV	Dental.VAV-1-7.RM-243.OCC-SCHEDULE
MV	Dental.VAV-1-7.RM-243.UNITEN-MODE
AV	Dental.VAV-1-7.RM-243.EFFHTG-SP
AV	Dental.VAV-1-7.RM-243.EFFCLG-SP
AO	Dental.VAV-1-7.RM-243.HTG-O
AI	Dental.VAV-1-7.RM-243.DA-T
AO	Dental.VAV-1-7.RM-243.DPR-O
AV	Dental.VAV-1-7.RM-243.SA-F
AV	Dental.VAV-1-7.RM-243.SAFLOW-SP
AI	Dental.VAV-1-7.RM-243.DA-VP
MV	Dental.VAV-1-7.RM-243.SYSTEM-MODE
AV	Dental.VAV-1-7.RM-243.ZN-SP
AI	Dental.VAV-1-8.RM-243.ZN-T
MV	Dental.VAV-1-8.RM-243.WC-C
AV	Dental.VAV-1-8.RM-243.SA-T
MV	Dental.VAV-1-8.RM-243.OCC-SCHEDULE
MV	Dental.VAV-1-8.RM-243.UNITEN-MODE
AV	Dental.VAV-1-8.RM-243.EFFHTG-SP
AV	Dental.VAV-1-8.RM-243.EFFCLG-SP
AO	Dental.VAV-1-8.RM-243.HTG-O
AI	Dental.VAV-1-8.RM-243.DA-T
AO	Dental.VAV-1-8.RM-243.DPR-O
AV	Dental.VAV-1-8.RM-243.SA-F
AV	Dental.VAV-1-8.RM-243.SAFLOW-SP
AI	Dental.VAV-1-8.RM-243.DA-VP
MV	Dental.VAV-1-8.RM-243.SYSTEM-MODE
AV	Dental.VAV-1-8.RM-243.ZN-SP
AI	Dental.VAV-1-9.RM-A3.ZN-T
MV	Dental.VAV-1-9.RM-A3.WC-C
AV	Dental.VAV-1-9.RM-A3.SA-T
MV	Dental.VAV-1-9.RM-A3.OCC-SCHEDULE
AV	Dental.VAV-1-9.RM-A3.ZN-SP
AI	Dental.VAV-1-9.RM-A3.DA-T
AO	Dental.VAV-1-9.RM-A3.HTG-O
AO	Dental.VAV-1-9.RM-A3.DPR-O
AI	Dental.VAV-1-9.RM-A3.DA-VP

DRAFT

Boone Clinic	Boone
AV	Dental.VAV-1-9.RM-A3.SAFLOW-SP
AV	Dental.VAV-1-9.RM-A3.SA-F
AV	Dental.VAV-1-9.RM-A3.EFFCLG-SP
AV	Dental.VAV-1-9.RM-A3.EFFHTG-SP
MV	Dental.VAV-1-9.RM-A3.SYSTEM-MODE
MV	Dental.VAV-1-9.RM-A3.UNITEN-MODE
AI	Dental.VAV-1-10.RM-251.ZN-T
MV	Dental.VAV-1-10.RM-251.WC-C
AV	Dental.VAV-1-10.RM-251.SA-T
MV	Dental.VAV-1-10.RM-251.OCC-SCHEDULE
BO	Dental.VAV-1-10.RM-251.EF10-C
MV	Dental.VAV-1-10.RM-251.UNITEN-MODE
AV	Dental.VAV-1-10.RM-251.EFFHTG-SP
AV	Dental.VAV-1-10.RM-251.EFFCLG-SP
AO	Dental.VAV-1-10.RM-251.HTG-O
AI	Dental.VAV-1-10.RM-251.DA-T
AO	Dental.VAV-1-10.RM-251.DPR-O
AV	Dental.VAV-1-10.RM-251.SA-F
AV	Dental.VAV-1-10.RM-251.SAFLOW-SP
AI	Dental.VAV-1-10.RM-251.DA-VP
MV	Dental.VAV-1-10.RM-251.SYSTEM-MODE
BI	Dental.VAV-1-10.RM-251.EF10-S
AV	Dental.VAV-1-10.RM-251.ZN-SP
AI	Dental.VAV-1-11.RM-200.ZN-T
MV	Dental.VAV-1-11.RM-200.WC-C
AV	Dental.VAV-1-11.RM-200.SA-T
MV	Dental.VAV-1-11.RM-200.OCC-SCHEDULE
MV	Dental.VAV-1-11.RM-200.UNITEN-MODE
AV	Dental.VAV-1-11.RM-200.EFFHTG-SP
AV	Dental.VAV-1-11.RM-200.EFFCLG-SP
AO	Dental.VAV-1-11.RM-200.HTG-O
AI	Dental.VAV-1-11.RM-200.DA-T
AO	Dental.VAV-1-11.RM-200.DPR-O
AV	Dental.VAV-1-11.RM-200.SA-F
AV	Dental.VAV-1-11.RM-200.SAFLOW-SP
AI	Dental.VAV-1-11.RM-200.DA-VP
MV	Dental.VAV-1-11.RM-200.SYSTEM-MODE
AV	Dental.VAV-1-11.RM-200.ZN-SP
AI	Dental.VAV-1-12.RM-202.ZN-T
MV	Dental.VAV-1-12.RM-202.WC-C
AV	Dental.VAV-1-12.RM-202.SA-T

DRAFT

Boone Clinic	Boone
MV	Dental.VAV-1-12.RM-202.OCC-SCHEDULE
MV	Dental.VAV-1-12.RM-202.UNITEN-MODE
AV	Dental.VAV-1-12.RM-202.EFFHTG-SP
AV	Dental.VAV-1-12.RM-202.EFFCLG-SP
AO	Dental.VAV-1-12.RM-202.HTG-O
AI	Dental.VAV-1-12.RM-202.DA-T
AO	Dental.VAV-1-12.RM-202.DPR-O
AV	Dental.VAV-1-12.RM-202.SA-F
AV	Dental.VAV-1-12.RM-202.SAFLOW-SP
AI	Dental.VAV-1-12.RM-202.DA-VP
MV	Dental.VAV-1-12.RM-202.SYSTEM-MODE
AV	Dental.VAV-1-12.RM-202ZN-SP
AI	Dental.VAV-1-13.RM-205.ZN-T
MV	Dental.VAV-1-13.RM-205.WC-C
AV	Dental.VAV-1-13.RM-205.SA-T
MV	Dental.VAV-1-13.RM-205.OCC-SCHEDULE
BO	Dental.VAV-1-13.RM-205.EF11-C
MV	Dental.VAV-1-13.RM-205.UNITEN-MODE
AV	Dental.VAV-1-13.RM-205.EFFHTG-SP
AV	Dental.VAV-1-13.RM-205.EFFCLG-SP
AO	Dental.VAV-1-13.RM-205.HTG-O
AI	Dental.VAV-1-13.RM-205.DA-T
AO	Dental.VAV-1-13.RM-205.DPR-O
AV	Dental.VAV-1-13.RM-205.SA-F
AV	Dental.VAV-1-13.RM-205.SAFLOW-SP
AI	Dental.VAV-1-13.RM-205.DA-VP
MV	Dental.VAV-1-13.RM-205.SYSTEM-MODE
BI	Dental.VAV-1-13.RM-205.EF11-S
AV	Dental.VAV-1-13.RM-205.ZN-SP
AI	Dental.VAV-1-14.RM-A4.ZN-T
MV	Dental.VAV-1-14.RM-A4.WC-C
AV	Dental.VAV-1-14.RM-A4.SA-T
MV	Dental.VAV-1-14.RM-A4.OCC-SCHEDULE
MV	Dental.VAV-1-14.RM-A4.UNITEN-MODE
AV	Dental.VAV-1-14.RM-A4.EFFHTG-SP
AV	Dental.VAV-1-14.RM-A4.EFFCLG-SP
AO	Dental.VAV-1-14.RM-A4.HTG-O
AI	Dental.VAV-1-14.RM-A4.DA-T
AO	Dental.VAV-1-14.RM-A4.DPR-O

DRAFT

Boone Clinic	Boone
AV	Dental.VAV-1-14.RM-A4.SA-F
AV	Dental.VAV-1-14.RM-A4.SAFLOW-SP
AI	Dental.VAV-1-14.RM-A4.DA-VP
MV	Dental.VAV-1-14.RM-A4.SYSTEM-MODE
AV	Dental.VAV-1-14.RM-A4.ZN-SP
AI	Dental.VAV-1-15.RM-252.ZN-T
MV	Dental.VAV-1-15.RM-252.WC-C
AV	Dental.VAV-1-15.RM-252.SA-T
MV	Dental.VAV-1-15.RM-252.OCC-SCHEDULE
MV	Dental.VAV-1-15.RM-252.UNITEN-MODE
AV	Dental.VAV-1-15.RM-252.EFFHTG-SP
AV	Dental.VAV-1-15.RM-252.EFFCLG-SP
AO	Dental.VAV-1-15.RM-252.HTG-O
AI	Dental.VAV-1-15.RM-252.DA-T
AO	Dental.VAV-1-15.RM-252.DPR-O
AV	Dental.VAV-1-15.RM-252.SA-F
AV	Dental.VAV-1-15.RM-252.SAFLOW-SP
AI	Dental.VAV-1-15.RM-252.DA-VP
MV	Dental.VAV-1-15.RM-252.SYSTEM-MODE
AV	Dental.VAV-1-15.RM-252.ZN-SP
AI	Dental.VAV-1-16.RM-208.ZN-T
MV	Dental.VAV-1-16.RM-208.WC-C
AV	Dental.VAV-1-16.RM-208.SA-T
MV	Dental.VAV-1-16.RM-208.OCC-SCHEDULE
MV	Dental.VAV-1-16.RM-208.UNITEN-MODE
AV	Dental.VAV-1-16.RM-208.EFFHTG-SP
AV	Dental.VAV-1-16.RM-208.EFFCLG-SP
AO	Dental.VAV-1-16.RM-208.HTG-O
AI	Dental.VAV-1-16.RM-208.DA-T
AO	Dental.VAV-1-16.RM-208.DPR-O
AV	Dental.VAV-1-16.RM-208.SA-F
AV	Dental.VAV-1-16.RM-208.SAFLOW-SP
AI	Dental.VAV-1-16.RM-208.DA-VP
MV	Dental.VAV-1-16.RM-208.SYSTEM-MODE
AV	Dental.VAV-1-16.RM-208.ZN-SP
AI	Dental.VAV-1-17.RM-209.ZN-T
MV	Dental.VAV-1-17.RM-209.WC-C
AV	Dental.VAV-1-17.RM-209.SA-T
MV	Dental.VAV-1-17.RM-209.OCC-SCHEDULE

DRAFT

Boone Clinic	Boone
MV	Dental.VAV-1-17.RM-209.UNITEN-MODE
AV	Dental.VAV-1-17.RM-209.EFFHTG-SP
AV	Dental.VAV-1-17.RM-209.EFFCLG-SP
AO	Dental.VAV-1-17.RM-209.HTG-O
AI	Dental.VAV-1-17.RM-209.DA-T
AO	Dental.VAV-1-17.RM-209.DPR-O
AV	Dental.VAV-1-17.RM-209.SA-F
AV	Dental.VAV-1-17.RM-209.SAFLOW-SP
AI	Dental.VAV-1-17.RM-209.DA-VP
MV	Dental.VAV-1-17.RM-209.SYSTEM-MODE
AV	Dental.VAV-1-17.RM-209.ZN-SP
AI	Dental.VAV-1-18.RM-121.ZN-T
MV	Dental.VAV-1-18.RM-121.WC-C
AV	Dental.VAV-1-18.RM-121.SA-T
MV	Dental.VAV-1-18.RM-121.OCC-SCHEDULE
BO	Dental.VAV-1-18.RM-121.EF1-C
MV	Dental.VAV-1-18.RM-121.UNITEN-MODE
AV	Dental.VAV-1-18.RM-121.EFFHTG-SP
AV	Dental.VAV-1-18.RM-121.EFFCLG-SP
AO	Dental.VAV-1-18.RM-121.HTG-O
AI	Dental.VAV-1-18.RM-121.DA-T
AO	Dental.VAV-1-18.RM-121.DPR-O
AV	Dental.VAV-1-18.RM-121.SA-F
AV	Dental.VAV-1-18.RM-121.SAFLOW-SP
AI	Dental.VAV-1-18.RM-121.DA-VP
MV	Dental.VAV-1-18.RM-121.SYSTEM-MODE
BI	Dental.VAV-1-18.RM-121.EF1-S
AV	Dental.VAV-1-18.RM-121.ZN-SP
AI	Dental.VAV-1-19.RM-G30.ZN-T
MV	Dental.VAV-1-19.RM-G30.WC-C
AV	Dental.VAV-1-19.RM-G30.SA-T
MV	Dental.VAV-1-19.RM-G30.OCC-SCHEDULE
MV	Dental.VAV-1-19.RM-G30.UNITEN-MODE
AV	Dental.VAV-1-19.RM-G30.EFFHTG-SP
AV	Dental.VAV-1-19.RM-G30.EFFCLG-SP
AO	Dental.VAV-1-19.RM-G30.HTG-O
AI	Dental.VAV-1-19.RM-G30.DA-T
AO	Dental.VAV-1-19.RM-G30.DPR-O
AV	Dental.VAV-1-19.RM-G30.SA-F
AV	Dental.VAV-1-19.RM-G30.SAFLOW-SP

DRAFT

Boone Clinic	Boone
AI	Dental.VAV-1-19.RM-G30.DA-VP
MV	Dental.VAV-1-19.RM-G30.SYSTEM-MODE
AV	Dental.VAV-1-19.RM-G30.ZN-SP
AI	Dental.VAV-1-20.RM-G27.ZN-T
MV	Dental.VAV-1-20.RM-G27.WC-C
AV	Dental.VAV-1-20.RM-G27.SA-T
MV	Dental.VAV-1-20.RM-G27.OCC-SCHEDULE
MV	Dental.VAV-1-20.RM-G27.UNITEN-MODE
AV	Dental.VAV-1-20.RM-G27.EFFHTG-SP
AV	Dental.VAV-1-20.RM-G27.EFFCLG-SP
AO	Dental.VAV-1-20.RM-G27.HTG-O
AI	Dental.VAV-1-20.RM-G27.DA-T
AO	Dental.VAV-1-20.RM-G27.DPR-O
AV	Dental.VAV-1-20.RM-G27.SA-F
AV	Dental.VAV-1-20.RM-G27.SAFLOW-SP
AI	Dental.VAV-1-20.RM-G27.DA-VP
MV	Dental.VAV-1-20.RM-G27.SYSTEM-MODE
AV	Dental.VAV-1-20.RM-G27.ZN-SP
AI	Dental.VAV-1-21.RM-G25.ZN-T
MV	Dental.VAV-1-21.RM-G25.WC-C
AV	Dental.VAV-1-21.RM-G25.SA-T
MV	Dental.VAV-1-21.RM-G25.OCC-SCHEDULE
MV	Dental.VAV-1-21.RM-G25.UNITEN-MODE
AV	Dental.VAV-1-21.RM-G25.EFFHTG-SP
AV	Dental.VAV-1-21.RM-G25.EFFCLG-SP
AO	Dental.VAV-1-21.RM-G25.HTG-O
AI	Dental.VAV-1-21.RM-G25.DA-T
AO	Dental.VAV-1-21.RM-G25.DPR-O
AV	Dental.VAV-1-21.RM-G25.SA-F
AV	Dental.VAV-1-21.RM-G25.SAFLOW-SP
AI	Dental.VAV-1-21.RM-G25.DA-VP
MV	Dental.VAV-1-21.RM-G25.SYSTEM-MODE
AV	Dental.VAV-1-21.RM-G25ZN-SP
AI	Dental.VAV-1-22.RM-G12.ZN-T
MV	Dental.VAV-1-22.RM-G12.WC-C
AV	Dental.VAV-1-22.RM-G12.SA-T
MV	Dental.VAV-1-22.RM-G12.OCC-SCHEDULE
MV	Dental.VAV-1-22.RM-G12.UNITEN-MODE
AV	Dental.VAV-1-22.RM-G12.EFFHTG-SP

DRAFT

Boone Clinic	Boone
AV	Dental.VAV-1-22.RM-G12.EFFCLG-SP
AO	Dental.VAV-1-22.RM-G12.HTG-O
AI	Dental.VAV-1-22.RM-G12.DA-T
AO	Dental.VAV-1-22.RM-G12.DPR-O
AV	Dental.VAV-1-22.RM-G12.SA-F
AV	Dental.VAV-1-22.RM-G12.SAFLOW-SP
AI	Dental.VAV-1-22.RM-G12.DA-VP
MV	Dental.VAV-1-22.RM-G12.SYSTEM-MODE
AV	Dental.VAV-1-22.RM-G12.ZN-SP
AI	Dental.VAV-1-23.RM-G23.ZN-T
MV	Dental.VAV-1-23.RM-G23.WC-C
AV	Dental.VAV-1-23.RM-G23.SA-T
MV	Dental.VAV-1-23.RM-G23.OCC-SCHEDULE
BO	Dental.VAV-1-23.RM-G23.EF2-C
MV	Dental.VAV-1-23.RM-G23.UNITEN-MODE
AV	Dental.VAV-1-23.RM-G23.EFFHTG-SP
AV	Dental.VAV-1-23.RM-G23.EFFCLG-SP
AO	Dental.VAV-1-23.RM-G23.HTG-O
AI	Dental.VAV-1-23.RM-G23.DA-T
AO	Dental.VAV-1-23.RM-G23.DPR-O
AV	Dental.VAV-1-23.RM-G23.SA-F
AV	Dental.VAV-1-23.RM-G23.SAFLOW-SP
AI	Dental.VAV-1-23.RM-G23.DA-VP
MV	Dental.VAV-1-23.RM-G23.SYSTEM-MODE
BI	Dental.VAV-1-23.RM-G23.EF2-S
AV	Dental.VAV-1-23.RM-G23.ZN-SP
AI	Dental.VAV-1-24.RM-G23.ZN-T
MV	Dental.VAV-1-24.RM-G23.WC-C
AV	Dental.VAV-1-24.RM-G23.SA-T
MV	Dental.VAV-1-24.RM-G23.OCC-SCHEDULE
MV	Dental.VAV-1-24.RM-G23.UNITEN-MODE
AV	Dental.VAV-1-24.RM-G23.EFFHTG-SP
AV	Dental.VAV-1-24.RM-G23.EFFCLG-SP
AO	Dental.VAV-1-24.RM-G23.HTG-O
AI	Dental.VAV-1-24.RM-G23.DA-T
AO	Dental.VAV-1-24.RM-G23.DPR-O
AV	Dental.VAV-1-24.RM-G23.SA-F
AV	Dental.VAV-1-24.RM-G23.SAFLOW-SP
AI	Dental.VAV-1-24.RM-G23.DA-VP
MV	Dental.VAV-1-24.RM-G23.SYSTEM-MODE

DRAFT

Boone Clinic	Boone
AV	Dental.VAV-1-24.RM-G23.ZN-SP
AI	Dental.VAV-1-25.RM-G23.ZN-T
MV	Dental.VAV-1-25.RM-G23.WC-C
AV	Dental.VAV-1-25.RM-G23.SA-T
MV	Dental.VAV-1-25.RM-G23.OCC-SCHEDULE
MV	Dental.VAV-1-25.RM-G23.UNITEN-MODE
AV	Dental.VAV-1-25.RM-G23.EFFHTG-SP
AV	Dental.VAV-1-25.RM-G23.EFFCLG-SP
AO	Dental.VAV-1-25.RM-G23.HTG-O
AI	Dental.VAV-1-25.RM-G23.DA-T
AO	Dental.VAV-1-25.RM-G23.DPR-O
AV	Dental.VAV-1-25.RM-G23.SA-F
AV	Dental.VAV-1-25.RM-G23.SAFLOW-SP
AI	Dental.VAV-1-25.RM-G23.DA-VP
MV	Dental.VAV-1-25.RM-G23.SYSTEM-MODE
AV	Dental.VAV-1-25.RM-G23.ZN-SP
AI	Dental.VAV-1-26.RM-G8.ZN-T
MV	Dental.VAV-1-26.RM-G8.WC-C
AV	Dental.VAV-1-26.RM-G8.SA-T
MV	Dental.VAV-1-26.RM-G8.OCC-SCHEDULE
MV	Dental.VAV-1-26.RM-G8.UNITEN-MODE
AV	Dental.VAV-1-26.RM-G8.EFFHTG-SP
AV	Dental.VAV-1-26.RM-G8.EFFCLG-SP
AO	Dental.VAV-1-26.RM-G8.HTG-O
AI	Dental.VAV-1-26.RM-G8.DA-T
AO	Dental.VAV-1-26.RM-G8.DPR-O
AV	Dental.VAV-1-26.RM-G8.SA-F
AV	Dental.VAV-1-26.RM-G8.SAFLOW-SP
AI	Dental.VAV-1-26.RM-G8.DA-VP
MV	Dental.VAV-1-26.RM-G8.SYSTEM-MODE
AV	Dental.VAV-1-26.RM-G8.ZN-SP
AI	Dental.VAV-1-27.RM-G9.ZN-T
MV	Dental.VAV-1-27.RM-G9.WC-C
AV	Dental.VAV-1-27.RM-G9.SA-T
MV	Dental.VAV-1-27.RM-G9.OCC-SCHEDULE
MV	Dental.VAV-1-27.RM-G9.UNITEN-MODE
AV	Dental.VAV-1-27.RM-G9.EFFHTG-SP
AV	Dental.VAV-1-27.RM-G9.EFFCLG-SP
AO	Dental.VAV-1-27.RM-G9.HTG-O

DRAFT

Boone Clinic	Boone
AI	Dental.VAV-1-27.RM-G9.DA-T
AO	Dental.VAV-1-27.RM-G9.DPR-O
AV	Dental.VAV-1-27.RM-G9.SA-F
AV	Dental.VAV-1-27.RM-G9.SAFLOW-SP
AI	Dental.VAV-1-27.RM-G9.DA-VP
MV	Dental.VAV-1-27.RM-G9.SYSTEM-MODE
AV	Dental.VAV-1-27.RM-G9.ZN-SP
AI	Dental.VAV-1-28.RM-113.ZN-T
MV	Dental.VAV-1-28.RM-113.WC-C
AV	Dental.VAV-1-28.RM-113.SA-T
MV	Dental.VAV-1-28.RM-113.OCC-SCHEDULE
MV	Dental.VAV-1-28.RM-113.UNITEN-MODE
AV	Dental.VAV-1-28.RM-113.EFFHTG-SP
AV	Dental.VAV-1-28.RM-113.EFFCLG-SP
AO	Dental.VAV-1-28.RM-113.HTG-O
AI	Dental.VAV-1-28.RM-113.DA-T
AO	Dental.VAV-1-28.RM-113.DPR-O
AV	Dental.VAV-1-28.RM-113.SA-F
AV	Dental.VAV-1-28.RM-113.SAFLOW-SP
AI	Dental.VAV-1-28.RM-113.DA-VP
MV	Dental.VAV-1-28.RM-113.SYSTEM-MODE
AV	Dental.VAV-1-28.RM-113.ZN-SP
AI	Dental.VAV-1-29.RM-113.ZN-T
MV	Dental.VAV-1-29.RM-113.WC-C
AV	Dental.VAV-1-29.RM-113.SA-T
MV	Dental.VAV-1-29.RM-113.OCC-SCHEDULE
MV	Dental.VAV-1-29.RM-113.UNITEN-MODE
AV	Dental.VAV-1-29.RM-113.EFFHTG-SP
AV	Dental.VAV-1-29.RM-113.EFFCLG-SP
AO	Dental.VAV-1-29.RM-113.HTG-O
AI	Dental.VAV-1-29.RM-113.DA-T
AO	Dental.VAV-1-29.RM-113.DPR-O
AV	Dental.VAV-1-29.RM-113.SA-F
AV	Dental.VAV-1-29.RM-113.SAFLOW-SP
AI	Dental.VAV-1-29.RM-113.DA-VP
MV	Dental.VAV-1-29.RM-113.SYSTEM-MODE
AV	Dental.VAV-1-29.RM-113.ZN-SP
AI	Dental.VAV-1-30.RM-G60.ZN-T
MV	Dental.VAV-1-30.RM-G60.WC-C
AV	Dental.VAV-1-30.RM-G60.SA-T

DRAFT

Boone Clinic	Boone
MV	Dental.VAV-1-30.RM-G60.OCC-SCHEDULE
BO	Dental.VAV-1-30.RM-G60.EF7-C
MV	Dental.VAV-1-30.RM-G60.UNITEN-MODE
AV	Dental.VAV-1-30.RM-G60.EFFHTG-SP
AV	Dental.VAV-1-30.RM-G60.EFFCLG-SP
AO	Dental.VAV-1-30.RM-G60.HTG-O
AI	Dental.VAV-1-30.RM-G60.DA-T
AO	Dental.VAV-1-30.RM-G60.DPR-O
AV	Dental.VAV-1-30.RM-G60.SA-F
AV	Dental.VAV-1-30.RM-G60.SAFLOW-SP
AI	Dental.VAV-1-30.RM-G60.DA-VP
MV	Dental.VAV-1-30.RM-G60.SYSTEM-MODE
BI	Dental.VAV-1-30.RM-G60.EF7-S
AV	Dental.VAV-1-30.RM-G60.ZN-SP
AI	Dental.VAV-1-31.RM-G62.ZN-T
MV	Dental.VAV-1-31.RM-G62.WC-C
AV	Dental.VAV-1-31.RM-G62.SA-T
MV	Dental.VAV-1-31.RM-G62.OCC-SCHEDULE
BO	Dental.VAV-1-31.RM-G62.EF8-C
MV	Dental.VAV-1-31.RM-G62.UNITEN-MODE
AV	Dental.VAV-1-31.RM-G62.EFFHTG-SP
AV	Dental.VAV-1-31.RM-G62.EFFCLG-SP
AO	Dental.VAV-1-31.RM-G62.HTG-O
AI	Dental.VAV-1-31.RM-G62.DA-T
AO	Dental.VAV-1-31.RM-G62.DPR-O
AV	Dental.VAV-1-31.RM-G62.SA-F
AV	Dental.VAV-1-31.RM-G62.SAFLOW-SP
AI	Dental.VAV-1-31.RM-G62.DA-VP
MV	Dental.VAV-1-31.RM-G62.SYSTEM-MODE
BI	Dental.VAV-1-31.RM-G62.EF8-S
AV	Dental.VAV-1-31.RM-G62ZN-SP
AI	Dental.VAV-1-32.RM-G57.ZN-T
MV	Dental.VAV-1-32.RM-G57.WC-C
AV	Dental.VAV-1-32.RM-G57.SA-T
MV	Dental.VAV-1-32.RM-G57.OCC-SCHEDULE
BO	Dental.VAV-1-32.RM-G57.EF9-C
MV	Dental.VAV-1-32.RM-G57.UNITEN-MODE
AV	Dental.VAV-1-32.RM-G57.EFFHTG-SP
AV	Dental.VAV-1-32.RM-G57.EFFCLG-SP

DRAFT

Boone Clinic	Boone
AO	Dental.VAV-1-32.RM-G57.HTG-O
AI	Dental.VAV-1-32.RM-G57.DA-T
AO	Dental.VAV-1-32.RM-G57.DPR-O
AV	Dental.VAV-1-32.RM-G57.SA-F
AV	Dental.VAV-1-32.RM-G57.SAFLOW-SP
AI	Dental.VAV-1-32.RM-G57.DA-VP
MV	Dental.VAV-1-32.RM-G57.SYSTEM-MODE
BI	Dental.VAV-1-32.RM-G57.EF9-S
AV	Dental.VAV-1-32.RM-G57ZN-SP
AI	Dental.VAV-1-33.RM-G57.ZN-T
MV	Dental.VAV-1-33.RM-G57.WC-C
AV	Dental.VAV-1-33.RM-G57.SA-T
MV	Dental.VAV-1-33.RM-G57.OCC-SCHEDULE
MV	Dental.VAV-1-33.RM-G57.UNITEN-MODE
AV	Dental.VAV-1-33.RM-G57.EFFHTG-SP
AV	Dental.VAV-1-33.RM-G57.EFFCLG-SP
AO	Dental.VAV-1-33.RM-G57.HTG-O
AI	Dental.VAV-1-33.RM-G57.DA-T
AO	Dental.VAV-1-33.RM-G57.DPR-O
AV	Dental.VAV-1-33.RM-G57.SA-F
AV	Dental.VAV-1-33.RM-G57.SAFLOW-SP
AI	Dental.VAV-1-33.RM-G57.DA-VP
MV	Dental.VAV-1-33.RM-G57.SYSTEM-MODE
AV	Dental.VAV-1-33.RM-G57.ZN-SP
AI	Dental.VAV-2-1.RM-257.ZN-T
MV	Dental.VAV-2-1.RM-257.WC-C
AV	Dental.VAV-2-1.RM-257.SA-T
MV	Dental.VAV-2-1.RM-257.OCC-SCHEDULE
BO	Dental.VAV-2-1.RM-257.EF17-C
MV	Dental.VAV-2-1.RM-257.UNITEN-MODE
AV	Dental.VAV-2-1.RM-257.EFFHTG-SP
AV	Dental.VAV-2-1.RM-257.EFFCLG-SP
AO	Dental.VAV-2-1.RM-257.HTG-O
AI	Dental.VAV-2-1.RM-257.DA-T
AO	Dental.VAV-2-1.RM-257.DPR-O
AV	Dental.VAV-2-1.RM-257.SA-F
AV	Dental.VAV-2-1.RM-257.SAFLOW-SP
AI	Dental.VAV-2-1.RM-257.DA-VP
MV	Dental.VAV-2-1.RM-257.SYSTEM-MODE
BI	Dental.VAV-2-1.RM-257.EF17-S
AV	Dental.VAV-2-1.RM-257.ZN-SP

DRAFT

Boone Clinic	Boone
AI	Dental.VAV-2-2.RM-257.ZN-T
MV	Dental.VAV-2-2.RM-257.WC-C
AV	Dental.VAV-2-2.RM-257.SA-T
MV	Dental.VAV-2-2.RM-257.OCC-SCHEDULE
BO	Dental.VAV-2-2.RM-257.EF16-C
MV	Dental.VAV-2-2.RM-257.UNITEN-MODE
AV	Dental.VAV-2-2.RM-257.EFFHTG-SP
AV	Dental.VAV-2-2.RM-257.EFFCLG-SP
AO	Dental.VAV-2-2.RM-257.HTG-O
AI	Dental.VAV-2-2.RM-257.DA-T
AO	Dental.VAV-2-2.RM-257.DPR-O
AV	Dental.VAV-2-2.RM-257.SA-F
AV	Dental.VAV-2-2.RM-257.SAFLOW-SP
AI	Dental.VAV-2-2.RM-257.DA-VP
MV	Dental.VAV-2-2.RM-257.SYSTEM-MODE
BI	Dental.VAV-2-2.RM-257.EF16-S
AV	Dental.VAV-2-2.RM-257.ZN-SP
AI	Dental.VAV-2-3.RM-254.ZN-T
MV	Dental.VAV-2-3.RM-254.WC-C
AV	Dental.VAV-2-3.RM-254.SA-T
MV	Dental.VAV-2-3.RM-254.OCC-SCHEDULE
MV	Dental.VAV-2-3.RM-254.UNITEN-MODE
AV	Dental.VAV-2-3.RM-254.EFFHTG-SP
AV	Dental.VAV-2-3.RM-254.EFFCLG-SP
AO	Dental.VAV-2-3.RM-254.HTG-O
AI	Dental.VAV-2-3.RM-254.DA-T
AO	Dental.VAV-2-3.RM-254.DPR-O
AV	Dental.VAV-2-3.RM-254.SA-F
AV	Dental.VAV-2-3.RM-254.SAFLOW-SP
AI	Dental.VAV-2-3.RM-254.DA-VP
MV	Dental.VAV-2-3.RM-254.SYSTEM-MODE
AV	Dental.VAV-2-3.RM-254.ZN-SP
AI	Dental.VAV-2-4.RM-226.ZN-T
MV	Dental.VAV-2-4.RM-226.WC-C
AV	Dental.VAV-2-4.RM-226.SA-T
MV	Dental.VAV-2-4.RM-226.OCC-SCHEDULE
MV	Dental.VAV-2-4.RM-226.UNITEN-MODE
AV	Dental.VAV-2-4.RM-226.EFFHTG-SP
AV	Dental.VAV-2-4.RM-226.EFFCLG-SP
AO	Dental.VAV-2-4.RM-226.HTG-O
AI	Dental.VAV-2-4.RM-226.DA-T

DRAFT

Boone Clinic	Boone
AO	Dental.VAV-2-4.RM-226.DPR-O
AV	Dental.VAV-2-4.RM-226.SA-F
AV	Dental.VAV-2-4.RM-226.SAFLOW-SP
AI	Dental.VAV-2-4.RM-226.DA-VP
MV	Dental.VAV-2-4.RM-226.SYSTEM-MODE
AV	Dental.VAV-2-4.RM-226.ZN-SP
AI	Dental.VAV-2-5.RM-225.ZN-T
MV	Dental.VAV-2-5.RM-225.WC-C
AV	Dental.VAV-2-5.RM-225.SA-T
MV	Dental.VAV-2-5.RM-225.OCC-SCHEDULE
MV	Dental.VAV-2-5.RM-225.UNITEN-MODE
AV	Dental.VAV-2-5.RM-225.EFFHTG-SP
AV	Dental.VAV-2-5.RM-225.EFFCLG-SP
AO	Dental.VAV-2-5.RM-225.HTG-O
AI	Dental.VAV-2-5.RM-225.DA-T
AO	Dental.VAV-2-5.RM-225.DPR-O
AV	Dental.VAV-2-5.RM-225.SA-F
AV	Dental.VAV-2-5.RM-225.SAFLOW-SP
AI	Dental.VAV-2-5.RM-225.DA-VP
MV	Dental.VAV-2-5.RM-225.SYSTEM-MODE
AV	Dental.VAV-2-5.RM-225.ZN-SP
AI	Dental.VAV-2-6.RM-B10.ZN-T
MV	Dental.VAV-2-6.RM-B10.WC-C
AV	Dental.VAV-2-6.RM-B10.SA-T
MV	Dental.VAV-2-6.RM-B10.OCC-SCHEDULE
MV	Dental.VAV-2-6.RM-B10.UNITEN-MODE
AV	Dental.VAV-2-6.RM-B10.EFFHTG-SP
AV	Dental.VAV-2-6.RM-B10.EFFCLG-SP
AO	Dental.VAV-2-6.RM-B10.HTG-O
AI	Dental.VAV-2-6.RM-B10.DA-T
AO	Dental.VAV-2-6.RM-B10.DPR-O
AV	Dental.VAV-2-6.RM-B10.SA-F
AV	Dental.VAV-2-6.RM-B10.SAFLOW-SP
AI	Dental.VAV-2-6.RM-B10.DA-VP
MV	Dental.VAV-2-6.RM-B10.SYSTEM-MODE
AV	Dental.VAV-2-6.RM-B10.ZN-SP
AI	Dental.VAV-2-7.RM-223.ZN-T
MV	Dental.VAV-2-7.RM-223.WC-C
AV	Dental.VAV-2-7.RM-223.SA-T
MV	Dental.VAV-2-7.RM-223.OCC-SCHEDULE
MV	Dental.VAV-2-7.RM-223.UNITEN-MODE

DRAFT

Boone Clinic	Boone
AV	Dental.VAV-2-7.RM-223.EFFHTG-SP
AV	Dental.VAV-2-7.RM-223.EFFCLG-SP
AO	Dental.VAV-2-7.RM-223.HTG-O
AI	Dental.VAV-2-7.RM-223.DA-T
AO	Dental.VAV-2-7.RM-223.DPR-O
AV	Dental.VAV-2-7.RM-223.SA-F
AV	Dental.VAV-2-7.RM-223.SAFLOW-SP
AI	Dental.VAV-2-7.RM-223.DA-VP
MV	Dental.VAV-2-7.RM-223.SYSTEM-MODE
AV	Dental.VAV-2-7.RM-223.ZN-SP
AI	Dental.VAV-2-8.RM-222.ZN-T
MV	Dental.VAV-2-8.RM-222.WC-C
AV	Dental.VAV-2-8.RM-222.SA-T
MV	Dental.VAV-2-8.RM-222.OCC-SCHEDULE
MV	Dental.VAV-2-8.RM-222.UNITEN-MODE
AV	Dental.VAV-2-8.RM-222.EFFHTG-SP
AV	Dental.VAV-2-8.RM-222.EFFCLG-SP
AO	Dental.VAV-2-8.RM-222.HTG-O
AI	Dental.VAV-2-8.RM-222.DA-T
AO	Dental.VAV-2-8.RM-222.DPR-O
AV	Dental.VAV-2-8.RM-222.SA-F
AV	Dental.VAV-2-8.RM-222.SAFLOW-SP
AI	Dental.VAV-2-8.RM-222.DA-VP
MV	Dental.VAV-2-8.RM-222.SYSTEM-MODE
AV	Dental.VAV-2-8.RM-222.ZN-SP
AI	Dental.VAV-2-9.RM-B11.ZN-T
MV	Dental.VAV-2-9.RM-B11.WC-C
AV	Dental.VAV-2-9.RM-B11.SA-T
MV	Dental.VAV-2-9.RM-B11.OCC-SCHEDULE
MV	Dental.VAV-2-9.RM-B11.UNITEN-MODE
AV	Dental.VAV-2-9.RM-B11.EFFHTG-SP
AV	Dental.VAV-2-9.RM-B11.EFFCLG-SP
AO	Dental.VAV-2-9.RM-B11.HTG-O
AI	Dental.VAV-2-9.RM-B11.DA-T
AO	Dental.VAV-2-9.RM-B11.DPR-O
AV	Dental.VAV-2-9.RM-B11.SA-F
AV	Dental.VAV-2-9.RM-B11.SAFLOW-SP
AI	Dental.VAV-2-9.RM-B11.DA-VP
MV	Dental.VAV-2-9.RM-B11.SYSTEM-MODE
AV	Dental.VAV-2-9.RM-B11.ZN-SP
AI	Dental.VAV-2-10.RM-A12.ZN-T

DRAFT

Boone Clinic	Boone
MV	Dental.VAV-2-10.RM-A12.WC-C
AV	Dental.VAV-2-10.RM-A12.SA-T
MV	Dental.VAV-2-10.RM-A12.OCC-SCHEDULE
MV	Dental.VAV-2-10.RM-A12.UNITEN-MODE
AV	Dental.VAV-2-10.RM-A12.EFFHTG-SP
AV	Dental.VAV-2-10.RM-A12.EFFCLG-SP
AO	Dental.VAV-2-10.RM-A12.HTG-O
AI	Dental.VAV-2-10.RM-A12.DA-T
AO	Dental.VAV-2-10.RM-A12.DPR-O
AV	Dental.VAV-2-10.RM-A12.SA-F
AV	Dental.VAV-2-10.RM-A12.SAFLOW-SP
AI	Dental.VAV-2-10.RM-A12.DA-VP
MV	Dental.VAV-2-10.RM-A12.SYSTEM-MODE
AV	Dental.VAV-2-10.RM-A12.ZN-SP
AI	Dental.VAV-2-11.RM-220.ZN-T
MV	Dental.VAV-2-11.RM-220.WC-C
AV	Dental.VAV-2-11.RM-220.SA-T
MV	Dental.VAV-2-11.RM-220.OCC-SCHEDULE
BO	Dental.VAV-2-11.RM-220.EF12-C
MV	Dental.VAV-2-11.RM-220.UNITEN-MODE
AV	Dental.VAV-2-11.RM-220.EFFHTG-SP
AV	Dental.VAV-2-11.RM-220.EFFCLG-SP
AO	Dental.VAV-2-11.RM-220.HTG-O
AI	Dental.VAV-2-11.RM-220.DA-T
AO	Dental.VAV-2-11.RM-220.DPR-O
AV	Dental.VAV-2-11.RM-220.SA-F
AV	Dental.VAV-2-11.RM-220.SAFLOW-SP
AI	Dental.VAV-2-11.RM-220.DA-VP
MV	Dental.VAV-2-11.RM-220.SYSTEM-MODE
BI	Dental.VAV-2-11.RM-220.EF12-S
AV	Dental.VAV-2-11.RM-220.ZN-SP
AI	Dental.VAV-2-12.RM-220.ZN-T
MV	Dental.VAV-2-12.RM-220.WC-C
AV	Dental.VAV-2-12.RM-220.SA-T
MV	Dental.VAV-2-12.RM-220.OCC-SCHEDULE
MV	Dental.VAV-2-12.RM-220.UNITEN-MODE
AV	Dental.VAV-2-12.RM-220.EFFHTG-SP
AV	Dental.VAV-2-12.RM-220.EFFCLG-SP
AO	Dental.VAV-2-12.RM-220.HTG-O

DRAFT

Boone Clinic	Boone
AI	Dental.VAV-2-12.RM-220.DA-T
AO	Dental.VAV-2-12.RM-220.DPR-O
AV	Dental.VAV-2-12.RM-220.SA-F
AV	Dental.VAV-2-12.RM-220.SAFLOW-SP
AI	Dental.VAV-2-12.RM-220.DA-VP
MV	Dental.VAV-2-12.RM-220.SYSTEM-MODE
AV	Dental.VAV-2-12.RM-220.ZN-SP
AI	Dental.VAV-2-13.RM-A11.ZN-T
MV	Dental.VAV-2-13.RM-A11.WC-C
AV	Dental.VAV-2-13.RM-A11.SA-T
MV	Dental.VAV-2-13.RM-A11.OCC-SCHEDULE
BO	Dental.VAV-2-13.RM-A11.EF13-C
MV	Dental.VAV-2-13.RM-A11.UNITEN-MODE
AV	Dental.VAV-2-13.RM-A11.EFFHTG-SP
AV	Dental.VAV-2-13.RM-A11.EFFCLG-SP
AO	Dental.VAV-2-13.RM-A11.HTG-O
AI	Dental.VAV-2-13.RM-A11.DA-T
AO	Dental.VAV-2-13.RM-A11.DPR-O
AV	Dental.VAV-2-13.RM-A11.SA-F
AV	Dental.VAV-2-13.RM-A11.SAFLOW-SP
AI	Dental.VAV-2-13.RM-A11.DA-VP
MV	Dental.VAV-2-13.RM-A11.SYSTEM-MODE
BI	Dental.VAV-2-13.RM-A11.EF13-S
AV	Dental.VAV-2-13.RM-A11.ZN-SP
AI	Dental.VAV-2-14.RM-216.ZN-T
MV	Dental.VAV-2-14.RM-216.WC-C
AV	Dental.VAV-2-14.RM-216.SA-T
MV	Dental.VAV-2-14.RM-216.OCC-SCHEDULE
BO	Dental.VAV-2-14.RM-216.EF14-C
MV	Dental.VAV-2-14.RM-216.UNITEN-MODE
AV	Dental.VAV-2-14.RM-216.EFFHTG-SP
AV	Dental.VAV-2-14.RM-216.EFFCLG-SP
AO	Dental.VAV-2-14.RM-216.HTG-O
AI	Dental.VAV-2-14.RM-216.DA-T
AO	Dental.VAV-2-14.RM-216.DPR-O
AV	Dental.VAV-2-14.RM-216.SA-F
AV	Dental.VAV-2-14.RM-216.SAFLOW-SP
AI	Dental.VAV-2-14.RM-216.DA-VP
MV	Dental.VAV-2-14.RM-216.SYSTEM-MODE
BI	Dental.VAV-2-14.RM-216.EF14-S

DRAFT

Boone Clinic	Boone
AV	Dental.VAV-2-14.RM-216.ZN-SP
AI	Dental.VAV-2-15.RM-A9.ZN-T
MV	Dental.VAV-2-15.RM-A9.WC-C
AV	Dental.VAV-2-15.RM-A9.SA-T
MV	Dental.VAV-2-15.RM-A9.OCC-SCHEDULE
MV	Dental.VAV-2-15.RM-A9.UNITEN-MODE
AV	Dental.VAV-2-15.RM-A9.EFFHTG-SP
AV	Dental.VAV-2-15.RM-A9.EFFCLG-SP
AO	Dental.VAV-2-15.RM-A9.HTG-O
AI	Dental.VAV-2-15.RM-A9.DA-T
AO	Dental.VAV-2-15.RM-A9.DPR-O
AV	Dental.VAV-2-15.RM-A9.SA-F
AV	Dental.VAV-2-15.RM-A9.SAFLOW-SP
AI	Dental.VAV-2-15.RM-A9.DA-VP
MV	Dental.VAV-2-15.RM-A9.SYSTEM-MODE
AV	Dental.VAV-2-15.RM-A9.ZN-SP
AI	Dental.VAV-2-16.RM-218.ZN-T
MV	Dental.VAV-2-16.RM-218.WC-C
AV	Dental.VAV-2-16.RM-218.SA-T
MV	Dental.VAV-2-16.RM-218.OCC-SCHEDULE
MV	Dental.VAV-2-16.RM-218.UNITEN-MODE
AV	Dental.VAV-2-16.RM-218.EFFHTG-SP
AV	Dental.VAV-2-16.RM-218.EFFCLG-SP
AO	Dental.VAV-2-16.RM-218.HTG-O
AI	Dental.VAV-2-16.RM-218.DA-T
AO	Dental.VAV-2-16.RM-218.DPR-O
AV	Dental.VAV-2-16.RM-218.SA-F
AV	Dental.VAV-2-16.RM-218.SAFLOW-SP
AI	Dental.VAV-2-16.RM-218.DA-VP
MV	Dental.VAV-2-16.RM-218.SYSTEM-MODE
AV	Dental.VAV-2-16.RM-218.ZN-SP
AI	Dental.VAV-2-17.RM-252.ZN-T
MV	Dental.VAV-2-17.RM-252.WC-C
AV	Dental.VAV-2-17.RM-252.SA-T
MV	Dental.VAV-2-17.RM-252.OCC-SCHEDULE
MV	Dental.VAV-2-17.RM-252.UNITEN-MODE
AV	Dental.VAV-2-17.RM-252.EFFHTG-SP
AV	Dental.VAV-2-17.RM-252.EFFCLG-SP
AO	Dental.VAV-2-17.RM-252.HTG-O

DRAFT

Boone Clinic	Boone
AI	Dental.VAV-2-17.RM-252.DA-T
AO	Dental.VAV-2-17.RM-252.DPR-O
AV	Dental.VAV-2-17.RM-252.SA-F
AV	Dental.VAV-2-17.RM-252.SAFLOW-SP
AI	Dental.VAV-2-17.RM-252.DA-VP
MV	Dental.VAV-2-17.RM-252.SYSTEM-MODE
AV	Dental.VAV-2-17.RM-252.ZN-SP
AI	Dental.VAV-2-18.RM-253.ZN-T
MV	Dental.VAV-2-18.RM-253.WC-C
AV	Dental.VAV-2-18.RM-253.SA-T
MV	Dental.VAV-2-18.RM-253.OCC-SCHEDULE
MV	Dental.VAV-2-18.RM-253.UNITEN-MODE
AV	Dental.VAV-2-18.RM-253.EFFHTG-SP
AV	Dental.VAV-2-18.RM-253.EFFCLG-SP
AO	Dental.VAV-2-18.RM-253.HTG-O
AI	Dental.VAV-2-18.RM-253.DA-T
AO	Dental.VAV-2-18.RM-253.DPR-O
AV	Dental.VAV-2-18.RM-253.SA-F
AV	Dental.VAV-2-18.RM-253.SAFLOW-SP
AI	Dental.VAV-2-18.RM-253.DA-VP
MV	Dental.VAV-2-18.RM-253.SYSTEM-MODE
AV	Dental.VAV-2-18.RM-253.ZN-SP
AI	Dental.VAV-2-19.RM-121.ZN-T
MV	Dental.VAV-2-19.RM-121.WC-C
AV	Dental.VAV-2-19.RM-121.SA-T
MV	Dental.VAV-2-19.RM-121.OCC-SCHEDULE
MV	Dental.VAV-2-19.RM-121.UNITEN-MODE
AV	Dental.VAV-2-19.RM-121.EFFHTG-SP
AV	Dental.VAV-2-19.RM-121.EFFCLG-SP
AO	Dental.VAV-2-19.RM-121.HTG-O
AI	Dental.VAV-2-19.RM-121.DA-T
AO	Dental.VAV-2-19.RM-121.DPR-O
AV	Dental.VAV-2-19.RM-121.SA-F
AV	Dental.VAV-2-19.RM-121.SAFLOW-SP
AI	Dental.VAV-2-19.RM-121.DA-VP
MV	Dental.VAV-2-19.RM-121.SYSTEM-MODE
AV	Dental.VAV-2-19.RM-121.ZN-SP
AI	Dental.VAV-2-20.RM-121.ZN-T
MV	Dental.VAV-2-20.RM-121WC-C
AV	Dental.VAV-2-20.RM-121.SA-T

DRAFT

Boone Clinic	Boone
MV	Dental.VAV-2-20.RM-121.OCC-SCHEDULE
MV	Dental.VAV-2-20.RM-121.UNITEN-MODE
AV	Dental.VAV-2-20.RM-121.EFFHTG-SP
AV	Dental.VAV-2-20.RM-121.EFFCLG-SP
AO	Dental.VAV-2-20.RM-121.HTG-O
AI	Dental.VAV-2-20.RM-121.DA-T
AO	Dental.VAV-2-20.RM-121.DPR-O
AV	Dental.VAV-2-20.RM-121.SA-F
AV	Dental.VAV-2-20.RM-121.SAFLOW-SP
AI	Dental.VAV-2-20.RM-121.DA-VP
MV	Dental.VAV-2-20.RM-121.SYSTEM-MODE
AV	Dental.VAV-2-20.RM-121.ZN-SP
AI	Dental.VAV-2-21.RM-119.ZN-T
MV	Dental.VAV-2-21.RM-119.WC-C
AV	Dental.VAV-2-21.RM-119.SA-T
MV	Dental.VAV-2-21.RM-119.OCC-SCHEDULE
MV	Dental.VAV-2-21.RM-119.UNITEN-MODE
AV	Dental.VAV-2-21.RM-119.EFFHTG-SP
AV	Dental.VAV-2-21.RM-119.EFFCLG-SP
AO	Dental.VAV-2-21.RM-119.HTG-O
AI	Dental.VAV-2-21.RM-119.DA-T
AO	Dental.VAV-2-21.RM-119.DPR-O
AV	Dental.VAV-2-21.RM-119.SA-F
AV	Dental.VAV-2-21.RM-119.SAFLOW-SP
AI	Dental.VAV-2-21.RM-119.DA-VP
MV	Dental.VAV-2-21.RM-119.SYSTEM-MODE
AV	Dental.VAV-2-21.RM-119.ZN-SP
AI	Dental.VAV-2-22.RM-G5.ZN-T
MV	Dental.VAV-2-22.RM-G5.WC-C
AV	Dental.VAV-2-22.RM-G5.SA-T
MV	Dental.VAV-2-22.RM-G5.OCC-SCHEDULE
MV	Dental.VAV-2-22.RM-G5.UNITEN-MODE
AV	Dental.VAV-2-22.RM-G5.EFFHTG-SP
AV	Dental.VAV-2-22.RM-G5.EFFCLG-SP
AO	Dental.VAV-2-22.RM-G5.HTG-O
AI	Dental.VAV-2-22.RM-G5.DA-T
AO	Dental.VAV-2-22.RM-G5.DPR-O
AV	Dental.VAV-2-22.RM-G5.SA-F
AV	Dental.VAV-2-22.RM-G5.SAFLOW-SP

DRAFT

Boone Clinic	Boone
AI	Dental.VAV-2-22.RM-G5.DA-VP
MV	Dental.VAV-2-22.RM-G5.SYSTEM-MODE
AV	Dental.VAV-2-22.RM-G5.ZN-SP
AI	Dental.VAV-2-23.RM-G20.ZN-T
MV	Dental.VAV-2-23.RM-G20.WC-C
AV	Dental.VAV-2-23.RM-G20.SA-T
MV	Dental.VAV-2-23.RM-G20.OCC-SCHEDULE
MV	Dental.VAV-2-23.RM-G20.UNITEN-MODE
AV	Dental.VAV-2-23.RM-G20.EFFHTG-SP
AV	Dental.VAV-2-23.RM-G20.EFFCLG-SP
AO	Dental.VAV-2-23.RM-G20.HTG-O
AI	Dental.VAV-2-23.RM-G20.DA-T
AO	Dental.VAV-2-23.RM-G20.DPR-O
AV	Dental.VAV-2-23.RM-G20.SA-F
AV	Dental.VAV-2-23.RM-G20.SAFLOW-SP
AI	Dental.VAV-2-23.RM-G20.DA-VP
MV	Dental.VAV-2-23.RM-G20.SYSTEM-MODE
AV	Dental.VAV-2-23.RM-G20.ZN-SP
AI	Dental.VAV-2-24.RM-114.ZN-T
MV	Dental.VAV-2-24.RM-114.WC-C
AV	Dental.VAV-2-24.RM-114.SA-T
MV	Dental.VAV-2-24.RM-114.OCC-SCHEDULE
MV	Dental.VAV-2-24.RM-114.UNITEN-MODE
AV	Dental.VAV-2-24.RM-114.EFFHTG-SP
AV	Dental.VAV-2-24.RM-114.EFFCLG-SP
AO	Dental.VAV-2-24.RM-114.HTG-O
AI	Dental.VAV-2-24.RM-114.DA-T
AO	Dental.VAV-2-24.RM-114.DPR-O
AV	Dental.VAV-2-24.RM-114.SA-F
AV	Dental.VAV-2-24.RM-114.SAFLOW-SP
AI	Dental.VAV-2-24.RM-114.DA-VP
MV	Dental.VAV-2-24.RM-114.SYSTEM-MODE
AV	Dental.VAV-2-24.RM-114.ZN-SP
AI	Dental.VAV-2-25.RM-113.ZN-T
MV	Dental.VAV-2-25.RM-113.WC-C
AV	Dental.VAV-2-25.RM-113.SA-T
MV	Dental.VAV-2-25.RM-113.OCC-SCHEDULE
MV	Dental.VAV-2-25.RM-113.UNITEN-MODE
AV	Dental.VAV-2-25.RM-113.EFFHTG-SP

DRAFT

Boone Clinic	Boone
AV	Dental.VAV-2-25.RM-113.EFFCLG-SP
AO	Dental.VAV-2-25.RM-113.HTG-O
AI	Dental.VAV-2-25.RM-113.DA-T
AO	Dental.VAV-2-25.RM-113.DPR-O
AV	Dental.VAV-2-25.RM-113.SA-F
AV	Dental.VAV-2-25.RM-113.SAFLOW-SP
AI	Dental.VAV-2-25.RM-113.DA-VP
MV	Dental.VAV-2-25.RM-113.SYSTEM-MODE
AV	Dental.VAV-2-25.RM-113.ZN-SP
AI	Dental.VAV-2-26.RM-G68.ZN-T
MV	Dental.VAV-2-26.RM-G68.WC-C
AV	Dental.VAV-2-26.RM-G68.SA-T
MV	Dental.VAV-2-26.RM-G68.OCC-SCHEDULE
MV	Dental.VAV-2-26.RM-G68.UNITEN-MODE
AV	Dental.VAV-2-26.RM-G68.EFFHTG-SP
AV	Dental.VAV-2-26.RM-G68.EFFCLG-SP
AO	Dental.VAV-2-26.RM-G68.HTG-O
AI	Dental.VAV-2-26.RM-G68.DA-T
AO	Dental.VAV-2-26.RM-G68.DPR-O
AV	Dental.VAV-2-26.RM-G68.SA-F
AV	Dental.VAV-2-26.RM-G68.SAFLOW-SP
AI	Dental.VAV-2-26.RM-G68.DA-VP
MV	Dental.VAV-2-26.RM-G68.SYSTEM-MODE
AV	Dental.VAV-2-26.RM-G68.ZN-SP
AI	Dental.VAV-2-27.RM-G54.ZN-T
MV	Dental.VAV-2-27.RM-G54.WC-C
AV	Dental.VAV-2-27.RM-G54.SA-T
MV	Dental.VAV-2-27.RM-G54.OCC-SCHEDULE
MV	Dental.VAV-2-27.RM-G54.UNITEN-MODE
AV	Dental.VAV-2-27.RM-G54.EFFHTG-SP
AV	Dental.VAV-2-27.RM-G54.EFFCLG-SP
AO	Dental.VAV-2-27.RM-G54.HTG-O
AI	Dental.VAV-2-27.RM-G54.DA-T
AO	Dental.VAV-2-27.RM-G54.DPR-O
AV	Dental.VAV-2-27.RM-G54.SA-F
AV	Dental.VAV-2-27.RM-G54.SAFLOW-SP
AI	Dental.VAV-2-27.RM-G54.DA-VP
MV	Dental.VAV-2-27.RM-G54.SYSTEM-MODE
AV	Dental.VAV-2-27.RM-G54.ZN-SP
AI	Dental.VAV-2-28.RM-G54.ZN-T

DRAFT

Boone Clinic	Boone
MV	Dental.VAV-2-28.RM-G54.WC-C
AV	Dental.VAV-2-28.RM-G54.SA-T
MV	Dental.VAV-2-28.RM-G54.OCC-SCHEDULE
MV	Dental.VAV-2-28.RM-G54.UNITEN-MODE
AV	Dental.VAV-2-28.RM-G54.EFFHTG-SP
AV	Dental.VAV-2-28.RM-G54.EFFCLG-SP
AO	Dental.VAV-2-28.RM-G54.HTG-O
AI	Dental.VAV-2-28.RM-G54.DA-T
AO	Dental.VAV-2-28.RM-G54.DPR-O
AV	Dental.VAV-2-28.RM-G54.SA-F
AV	Dental.VAV-2-28.RM-G54.SAFLOW-SP
AI	Dental.VAV-2-28.RM-G54.DA-VP
MV	Dental.VAV-2-28.RM-G54.SYSTEM-MODE
AV	Dental.VAV-2-28.RM-G54ZN-SP
AI	Dental.VAV-2-29.RM-G47.ZN-T
MV	Dental.VAV-2-29.RM-G47.WC-C
AV	Dental.VAV-2-29.RM-G47.SA-T
MV	Dental.VAV-2-29.RM-G47.OCC-SCHEDULE
MV	Dental.VAV-2-29.RM-G47.UNITEN-MODE
AV	Dental.VAV-2-29.RM-G47.EFFHTG-SP
AV	Dental.VAV-2-29.RM-G47.EFFCLG-SP
AO	Dental.VAV-2-29.RM-G47.HTG-O
AI	Dental.VAV-2-29.RM-G47.DA-T
AO	Dental.VAV-2-29.RM-G47.DPR-O
AV	Dental.VAV-2-29.RM-G47.SA-F
AV	Dental.VAV-2-29.RM-G47.SAFLOW-SP
AI	Dental.VAV-2-29.RM-G47.DA-VP
MV	Dental.VAV-2-29.RM-G47.SYSTEM-MODE
AV	Dental.VAV-2-29.RM-G47.ZN-SP
AI	Dental.VAV-2-30.RM-115.ZN-T
MV	Dental.VAV-2-30.RM-115.WC-C
AV	Dental.VAV-2-30.RM-115.SA-T
MV	Dental.VAV-2-30.RM-115.OCC-SCHEDULE
BO	Dental.VAV-2-30.RM-115.EF3-C
MV	Dental.VAV-2-30.RM-115.UNITEN-MODE
AV	Dental.VAV-2-30.RM-115.EFFHTG-SP
AV	Dental.VAV-2-30.RM-115.EFFCLG-SP
AO	Dental.VAV-2-30.RM-115.HTG-O
AI	Dental.VAV-2-30.RM-115.DA-T

DRAFT

Boone Clinic	Boone
AO	Dental.VAV-2-30.RM-115.DPR-O
AV	Dental.VAV-2-30.RM-115.SA-F
AV	Dental.VAV-2-30.RM-115.SAFLOW-SP
AI	Dental.VAV-2-30.RM-115.DA-VP
MV	Dental.VAV-2-30.RM-115.SYSTEM-MODE
BI	Dental.VAV-2-30.RM-115.EF3-S
AV	Dental.VAV-2-30.RM-115.ZN-SP
AI	Dental.VAV-2-31.RM-G44.ZN-T
MV	Dental.VAV-2-31.RM-G44.WC-C
AV	Dental.VAV-2-31.RM-G44.SA-T
MV	Dental.VAV-2-31.RM-G44.OCC-SCHEDULE
MV	Dental.VAV-2-31.RM-G44.UNITEN-MODE
AV	Dental.VAV-2-31.RM-G44.EFFHTG-SP
AV	Dental.VAV-2-31.RM-G44.EFFCLG-SP
AO	Dental.VAV-2-31.RM-G44.HTG-O
AI	Dental.VAV-2-31.RM-G44.DA-T
AO	Dental.VAV-2-31.RM-G44.DPR-O
AV	Dental.VAV-2-31.RM-G44.SA-F
AV	Dental.VAV-2-31.RM-G44.SAFLOW-SP
AI	Dental.VAV-2-31.RM-G44.DA-VP
MV	Dental.VAV-2-31.RM-G44.SYSTEM-MODE
AV	Dental.VAV-2-31.RM-G44.ZN-SP
AI	Dental.VAV-2-32.RM-G54.ZN-T
MV	Dental.VAV-2-32.RM-G54.WC-C
AV	Dental.VAV-2-32.RM-G54.SA-T
MV	Dental.VAV-2-32.RM-G54.OCC-SCHEDULE
MV	Dental.VAV-2-32.RM-G54.UNITEN-MODE
AV	Dental.VAV-2-32.RM-G54.EFFHTG-SP
AV	Dental.VAV-2-32.RM-G54.EFFCLG-SP
AO	Dental.VAV-2-32.RM-G54.HTG-O
AI	Dental.VAV-2-32.RM-G54.DA-T
AO	Dental.VAV-2-32.RM-G54.DPR-O
AV	Dental.VAV-2-32.RM-G54.SA-F
AV	Dental.VAV-2-32.RM-G54.SAFLOW-SP
AI	Dental.VAV-2-32.RM-G54.DA-VP
MV	Dental.VAV-2-32.RM-G54.SYSTEM-MODE
AV	Dental.VAV-2-32.RM-G54.ZN-SP
AI	Dental.VAV-2-33.RM-G48.ZN-T
MV	Dental.VAV-2-33.RM-G48.WC-C
AV	Dental.VAV-2-33.RM-G48.SA-T

DRAFT

Boone Clinic	Boone
MV	Dental.VAV-2-33.RM-G48.OCC-SCHEDULE
AV	Dental.VAV-2-33.RM-G48.ZN-SP
AI	Dental.VAV-2-33.RM-G48.DA-T
AO	Dental.VAV-2-33.RM-G48.HTG-O
AO	Dental.VAV-2-33.RM-G48.DPR-O
AI	Dental.VAV-2-33.RM-G48.DA-VP
AV	Dental.VAV-2-33.RM-G48.SA-F
MV	Dental.VAV-2-33.RM-G48.SYSTEM-MODE
MV	Dental.VAV-2-33.RM-G48.UNITEN-MODE
AV	Dental.VAV-2-33.RM-G48.EFFCLG-SP
AV	Dental.VAV-2-33.RM-G48.EFFHTG-SP
AV	Dental.VAV-2-33.RM-G48.SAFLOW-SP
BV	RTU-1 Occupancy
BV	RTU-2 Occupancy

CD2	
Point	Type
NAE-08	
BACnet1.VAV 1Q	VAV 1Q
BACnet1.AHU-1	AHU-1
BACnet1.VAV-1RR	VAV-1RR
BACnet1.VAV 1QQ	VAV 1QQ
BACnet1.VAV 1 PP	VAV 1 PP
BACnet1.VAV 1 MM	VAV 1 MM
BACnet1.AHU1-B Multiplexor	AHU1-B Multiplexor
BACnet1.VAV 1 NN	VAV 1 NN
BACnet1.VAV 1 OO	VAV 1 OO
BACnet1.VAV 1 AA	VAV 1 AA
BACnet1.VAV 1 JJ	VAV 1 JJ
BACnet1.AHU-2	AHU-2
BACnet1.VAV 1 II	VAV 1 II
BACnet1.VAV 1 LL	VAV 1 LL
BACnet1.VAV 1 KK	VAV 1 KK
BACnet1.AHU2-B Multiplexor	AHU2-B Multiplexor
BACnet1.VAV 1 HH	VAV 1 HH
BACnet1.AHU-3	AHU-3
BACnet1.VAV 1 FF	VAV 1 FF
BACnet1.VAV 1 GG	VAV 1 GG
BACnet1.VAV 1 W	VAV 1 W
BACnet1.VAV 1 X	VAV 1 X
BACnet1.VAV 1 Y	VAV 1 Y
BACnet1.VAV 1 BB	VAV 1 BB

DRAFT

CD2	
Point	Type
BACnet1.VAV 1 CC	VAV 1 CC
BACnet1.AHU3-B Multiplexor	AHU3-B Multiplexor
BACnet1.VAV 1 DD	VAV 1 DD
BACnet1.AHU-4	AHU-4
BACnet1.VAV 1 EE	VAV 1 EE
BACnet1.VAV 1 TT	VAV 1 TT
BACnet1.VAV 1A	VAV 1 A
BACnet1.AHU4-B Multiplexor	AHU4-B Multiplexor
BACnet1.VAV 1 B	VAV 1 B
BACnet1.VAV 1 C	VAV 1 C
BACnet1.VAV 1 D	VAV 1 D
BACnet1.AHU-5	AHU-5
BACnet1.VAV 1 E	VAV 1 E
BACnet1.VAV 1 F	VAV 1 F
BACnet1.VAV 1 U	VAV 1 U
BACnet1.AHU5-B Multiplexor	AHU5-B Multiplexor
BACnet1.VAV 1 V	VAV 1 V
BACnet1.VAV 1 T	VAV 1 T
BACnet1.AHU-6	AHU-6
BACnet1.VAV 1 S	VAV 1 S
BACnet1.VAV 1 R	VAV 1 R
BACnet1.VAV 1 P	VAV 1 P
BACnet1.VAV 1 O	VAV 1 O
BACnet1.VAV 1 N	VAV 1 N
BACnet1.VAV 1 M	VAV 1 M
BACnet1.AHU6-B Multiplexor	AHU6-B Multiplexor
BACnet1.VAV 1 L	VAV 1 L
BACnet1.AHU-7	AHU-7
BACnet1.VAV 1 J	VAV 1 J
BACnet1.VAV 1 K	VAV 1 K
BACnet1.VAV 1 I	VAV 1 I
BACnet1.AHU7-B Multiplexor	AHU7-B Multiplexor
BACnet1.VAV 1 G	VAV 1 G
BACnet1.VAV 1 H	VAV 1 H
BACnet1.VAV 1 SS	VAV 1 SS
BACnet1.VAV 2 O	VAV 2 O
BACnet1.VAV 2 P	VAV 2 P
BACnet1.VAV 2 M	VAV 2 M
BACnet1.VAV 2 L	VAV 2 L
BACnet1.VAV 2 K	VAV 2 K
BACnet1.VAV 2 J	VAV 2 J
BACnet1.VAV 2 I	VAV 2 I
BACnet1.VAV 2 H	VAV 2 H
BACnet1.VAV 2 F	VAV 2 F

DRAFT

CD2	
Point	Type
BACnet1.VAV 2 G	VAV 2 G
BACnet1.VAV 2 N	VAV 2 N
BACnet1.VAV 2 E	VAV 2 E
BACnet1.VAV 2 D	VAV 2 D
BACnet1.VAV 2 C	VAV 2 C
BACnet1.VAV 2 B	VAV 2 B
BACnet1.VAV 2 A	VAV 2 A
BACnet1.Chilled Water Controller -2	Chilled Water Controller -2
BACnet1.VAV 3 I	VAV 3 I
BACnet1.VAV 3 H	VAV 3 H
BACnet1.VAV 3 G	VAV 3 G
BACnet1.Chilled Water Controller - 1	Chilled Water Controller - 1
BACnet1.VAV 3 F	VAV 3 F
BACnet1.VAV 3 E	VAV 3 E
BACnet1.VAV 3 D	VAV 3 D
BACnet1.VAV 3 C	VAV 3 C
BACnet1.VAV 3 B	VAV 3 B
BACnet1.VAV 3 A	VAV 3 A
BACnet1.VAV 3 M	VAV 3 M
BACnet1.VAV 3 K	VAV 3 K
BACnet1.VAV 3 L	VAV 3 L
BACnet1.Hot Water Controller - 1	Hot Water Controller - 1
BACnet1.VAV 3 J	VAV 3 J
BACnet1.VAV 4 G	VAV 4 G
BACnet1.VAV 4 F	VAV 4 F
BACnet1.Hot Water Controller - 2	Hot Water Controller - 2
BACnet1.VAV 4 H	VAV 4 H
BACnet1.VAV 4 I	VAV 4 I
BACnet1.VAV 4 J	VAV 4 J
BACnet1.VAV 4 K	VAV 4 K
BACnet1.VAV 4 L	VAV 4 L
BACnet1.VAV 4 M	VAV 4 M
BACnet1.VAV 4 N	VAV 4 N
BACnet1.VAV 4 O	VAV 4 O
BACnet1.VAV 4 E	VAV 4 E
BACnet1.VAV 4 D	VAV 4 D
BACnet1.VAV 4 C	VAV 4 C
BACnet1.VAV 4 B	VAV 4 B
BACnet1.VAV 4 A	VAV 4 A
BACnet1.BTI Global Functions	BTI Global Functions
BACnet1.VAV 5 B	VAV 5 B

DRAFT

CD2	
Point	Type
BACnet1.VAV 5 C	VAV 5 C
BACnet1.VAV 5 D	VAV 5 D
BACnet1.VAV 5 F	VAV 5 F
BACnet1.VAV 5 G	VAV 5 G
BACnet1.VAV 5 E	VAV 5 E
BACnet1.VAV 5 N	VAV 5 N
BACnet1.VAV 5 M	VAV 5 M
BACnet1.VAV 5 L	VAV 5 L
BACnet1.VAV 5 K	VAV 5 K
BACnet1.VAV 5 R	VAV 5 R
BACnet1.VAV 5 Q	VAV 5 Q
BACnet1.VAV 5 P	VAV 5 P
BACnet1.VAV 5 O	VAV 5 O
BACnet1.VAV 5 S	VAV 5 S
BACnet1.VAV 5 J	VAV 5 J
BACnet1.VAV 5 I	VAV 5 I
BACnet1.VAV 5 H	VAV 5 H
BACnet1.VAV 5 A	VAV 5 A
BACnet1.VAV 5 T	VAV 5 T
BACnet1.VAV 6 P	VAV 6 P
BACnet1.VAV 6 Q	VAV 6 Q
BACnet1.VAV 6 R	VAV 6 R
BACnet1.VAV 6 CCC	VAV 6 CCC
BACnet1.VAV 6 BBB	VAV 6 BBB
BACnet1.VAV 6 AAA	VAV 6 AAA
BACnet1.VAV 6 XX	VAV 6 XX
BACnet1.VAV 6 W	VAV 6 W
BACnet1.VAV 6 SS	VAV 6 SS
BACnet1.VAV 6 ZZ	VAV 6 ZZ
BACnet1.VAV 6 RR	VAV 6 RR
BACnet1.VAV 6 TT	VAV 6 TT
BACnet1.VAV 6 UU	VAV 6 UU
BACnet1.VAV 6 WW	VAV 6 WW
BACnet1.VAV 6 YY	VAV 6 YY
BACnet1.VAV 7 A	VAV 7 A
BACnet1.VAV 6 CA	VAV 6 CA
BACnet1.VAV 7 B	VAV 7 B
BACnet1.VAV 6 CC	VAV 6 CC
BACnet1.VAV 7 C	VAV 7 C
BACnet1.VAV 6 BB	VAV 6 BB
BACnet1.VAV 7 D	VAV 7 D
BACnet1.VAV 6 AA	VAV 6 AA
BACnet1.VAV 7 E	VAV 7 E
BACnet1.VAV 6 Y	VAV 6 Y

DRAFT

CD2	
Point	Type
BACnet1.VAV 7 F	VAV 7 F
BACnet1.VAV 6 Z	VAV 6 Z
BACnet1.VAV 7 G	VAV 7 G
BACnet1.VAV 7 H	VAV 7 H
BACnet1.VAV 7 I	VAV 7 I
BACnet1.VAV 7 J	VAV 7 J
BACnet1.VAV 7 K	VAV 7 K
BACnet1.VAV 7 L	VAV 7 L
BACnet1.VAV 7 M	VAV 7 M
BACnet1.VAV 7 N	VAV 7 N
BACnet1.VAV 7 O	VAV 7 O
BACnet1.VAV 6 HH	VAV 6 HH
BACnet1.VAV 7 P	VAV 7 P
BACnet1.VAV 6 JJ	VAV 6 JJ
BACnet1.VAV 6 LL	VAV 6 LL
BACnet1.VAV 6 NN	VAV 6 NN
BACnet1.VAV 6 MM	VAV 6 MM
BACnet1.VAV 6 KK	VAV 6 KK
BACnet1.VAV 6 II	VAV 6 II
BACnet1.VAV 6 GG	VAV 6 GG
BACnet1.VAV 7 Q	VAV 7 Q
BACnet1.VAV 7 R	VAV 7 R
BACnet1.VAV 7 S	VAV 7 S
BACnet1.VAV 7 T	VAV 7 T
BACnet1.VAV 7 U	VAV 7 U
BACnet1.VAV 7 V	VAV 7 V
BACnet1.VAV 7 W	VAV 7 W
BACnet1.VAV 7 X	VAV 7 X
BACnet1.VAV 7 Y	VAV 7 Y
BACnet1.VAV 7 Z	VAV 7 Z
BACnet1.VAV 7 AA	VAV 7 AA
BACnet1.VAV 7 BB	VAV 7 BB
BACnet1.VAV 7 CC	VAV 7 CC
BACnet1.VAV 7 DD	VAV 7 DD
BACnet1.VAV 7 EE	VAV 7 EE
BACnet1.VAV 7 FF	VAV 7 FF
BACnet1.VAV 6 QQ	VAV 6 QQ
BACnet1.VAV 6 PP	VAV 6 PP
BACnet1.VAV 6 OO	VAV 6 OO
BACnet1.VAV 6 FF	VAV 6 FF
BACnet1.VAV 6 EE	VAV 6 EE
BACnet1.VAV 6 DD	VAV 6 DD
BACnet1.VAV 6 U	VAV 6 U
BACnet1.VAV 6 T	VAV 6 T

DRAFT

CD2	
Point	Type
BACnet1.VAV 6 N	VAV 6 N
BACnet1.VAV 6 X	VAV 6 X
BACnet1.VAV 6 V	VAV 6 V
BACnet1.VAV 6 M	VAV 6 M
BACnet1.VAV 6 S	VAV 6 S
BACnet1.VAV 6 O	VAV 6 O
BACnet1.VAV 6 L	VAV 6 L
BACnet1.VAV 6 K	VAV 6 K
BACnet1.VAV 6 J	VAV 6 J
BACnet1.VAV 6 H	VAV 6 H
BACnet1.VAV 6 I	VAV 6 I
BACnet1.VAV 6 G	VAV 6 G
BACnet1.VAV 6 A	VAV 6 A
BACnet1.VAV 6 C	VAV 6 C
BACnet1.VAV 6 B	VAV 6 B
BACnet1.VAV 6 D	VAV 6 D
BACnet1.VAV 6 F	VAV 6 F
BACnet1.VAV 6 E	VAV 6 E
BACnet1.VAV 6 VV	VAV 6 VV
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Offset
AV	MicroTouch Lever Value
BV	Supply Air Filter Dirty Alarm
BV	Return Air Filter Dirty Alarm
BV	Return Fan Alarm
BV	Supply Fan Alarm
BV	Fan Alarm Reset
BV	Smoke Alarm
BV	Occupied
BI	HIgh Duct Pressure Alarm
BI	Low Limit Alarm
BI	Return Fan Status
BI	Supply Fan Status
AV	Chilled Water Return
AV	Chilled Water Supply

DRAFT

CD2	
Point	Type
AV	Return DAMP %OPEN
AV	Chilled Water Valve Feed Back
AV	Cooling Valve Command
AV	Return Air CFM STPT
AV	Return DAMP %CLOSED
AV	Supply Air STPT
AV	Supply Air CFM
AV	Return Fan CFM
AV	Outside Air CFM STPT
AV	Outside Air CFM
AV	Current Supply Pressure STPT
AV	Outside Air Temp. to Microset
AO	Return Fan Speed
AO	Supply Fan Speed
AI	Duct Pressure
AI	Supply Air Temp
AI	Return Air Temp
AO	Modulating CW Valve
AO	Modulating Return Air Damper
BO	EF 1-6 & 1-8 S/S
BO	EF 1-5 S/S
BO	EF 1-4 S/S
BO	EF 1-3 S/S
BO	EF 1-2 S/S
BO	EF 1-1 S/S
BO	SAF/RAF VFD S/S
BO	OA Damper Actuator
BV	EF 1-6 & 1-8 Alarm
BV	EF 1-5 Alarm
BV	EF 1-4 Alarm
BV	EF 1-3 Alarm
BV	EF 1-2 Alarm
BV	EF 1-1 Alarm
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AV	MicroTouch Lever Value
BI	AHU-1 Smoke Det Relay Status
BI	EF 1-8 Status
BI	EF 1-6 Status
BI	EF 1-5 Status
BI	EF 1-4 Status
BI	EF 1-3 Status
BI	EF 1-2 Status
BI	EF 1-1 Status
BV	Force Damper Closed
BV	Force Damper Open

DRAFT

CD2	
Point	Type
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Supply Air Filter Dirty Alarm
BV	Return Air Filter Dirty Alarm
BV	Return Fan Alarm
BV	Supply Fan Alarm
BV	Fan Alarm Reset
BV	Smoke Alarm
BV	Occupied
BV	EF 2-2 Alarm
BV	EF 2-1 Alarm
BO	EF 2-2 S/S
BO	EF 2-1 S/S
BO	SAF/RAF VFD S/S
BO	OA Damper Actuator
BI	High Duct Pressure Alarm
BI	Low Limit Alarm
BI	Return Fan Status
BI	Supply Fan Status
AV	Chilled Water Return
AV	Chilled Water Supply
AV	Return Damper % Open
AV	Chilled Water Valve Feed Back
AV	Cooling Valve Command
AV	Return Air CFM STPT
AV	Return Damper % Closed
AV	Supply Air STPT
AV	Supply Air CFM
AV	Return Fan CFM
AV	Outside Air CFM STPT
AV	Outside Air CFM
AV	Current Supply Pressure STPT
AV	Outside Air Temp. to Microset
AO	Return Fan Speed
AO	Modulating CW Valve
AO	Modulating Return Air Damper
AO	Supply Fan Speed
AI	Duct Pressure
AI	Supply Air Temp
AI	Return Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position

DRAFT

CD2	
Point	Type
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BI	AHU-2 Smoke Det Relay Status
BI	EF 2-2 Status
BI	EF 2-1 Status
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.

DRAFT

CD2	
Point	Type
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Supply Air Filter Dirty Alarm
BV	Return Air Filter Dirty Alarm
BV	Return Fan Alarm
BV	Supply Fan Alarm
BV	Fan Alarm Reset
BV	Smoke Alarm
BV	Occupied
BV	EF 3-1 Alarm
BO	EF 3-1 S/S
BO	SAF/RAF VFD S/S
BO	OA Damper Actuator
BI	High Duct Pressure Alarm
BI	Low Limit Alarm
BI	Return Fan Status
BI	Supply Fan Status
AV	Chilled Water Return
AV	Chilled Water Supply
AV	Return Damper % Open
AV	Chilled Water Valve Feed Back
AV	Cooling Valve Command
AV	Return Air CFM STPT
AV	Return Damper % Closed
AV	Supply Air STPT
AV	Supply Air CFM
AV	Return Fan CFM
AV	Outside Air CFM STPT
AV	Outside Air CFM
AV	Current Supply Pressure STPT
AV	Outside Air Temp. to Microset
AO	Return Fan Speed
AO	Modulating CW Valve
AO	Modulating Return Air Damper
AO	Supply Fan Speed
AI	Duct Pressure
AI	Supply Air Temp
AI	Return Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position

DRAFT

CD2	
Point	Type
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed

DRAFT

CD2	
Point	Type
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BI	AHU-3 Smoke Det Relay Status
BI	EF 3-1 Status
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Supply Air Filter Dirty Alarm
BV	Return Air Filter Dirty Alarm
BV	Return Fan Alarm
BV	Supply Fan Alarm
BV	Fan Alarm Reset
BV	Smoke Alarm
BV	Occupied
BV	EF 4-1 Alarm
BO	EF 4-1 S/S
BO	SAF/RAF VFD S/S
BO	OA Damper Actuator
BI	High Duct Pressure Alarm
BI	Low Limit Alarm
BI	Return Fan Status
BI	Supply Fan Status
AV	Chilled Water Return
AV	Chilled Water Supply
AV	Return Damper % Open
AV	Chilled Water Valve Feed Back
AV	Cooling Valve Command
AV	Return Air CFM STPT
AV	Return Damper % Closed
AV	Supply Air STPT
AV	Supply Air CFM
AV	Return Fan CFM
AV	Outside Air CFM STPT
AV	Outside Air CFM
AV	Current Supply Pressure STPT
AV	Outside Air Temp. to Microset
AO	Return Fan Speed
AO	Modulating CW Valve
AO	Modulating Return Air Damper
AO	Supply Fan Speed
AI	Duct Pressure
AI	Supply Air Temp
AI	Return Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command

DRAFT

CD2	
Point	Type
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	CD2 VAV 1 EE Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BI	AHU-4 Smoke Det Relay Status
BI	EF 4-1 Status
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.

DRAFT

CD2	
Point	Type
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Supply Air Filter Dirty Alarm
BV	Return Air Filter Dirty Alarm
BV	Return Fan Alarm
BV	Supply Fan Alarm
BV	Fan Alarm Reset
BV	Smoke Alarm
BV	Occupied
BV	EF 5-2 Alarm
BV	EF 5-1 Alarm
BO	EF 5-2 S/S
BO	EF 5-1 S/S
BO	SAF/RAF VFD S/S
BO	OA Damper Actuator
BI	High Duct Pressure Alarm
BI	Low Limit Alarm
BI	Return Fan Status
BI	Supply Fan Status

DRAFT

CD2	
Point	Type
AV	Chilled Water Return
AV	Chilled Water Supply
AV	Return Damper % Open
AV	Chilled Water Valve Feed Back
AV	Cooling Valve Command
AV	Return Air CFM STPT
AV	Return Damper % Closed
AV	Supply Air STPT
AV	Supply Air CFM
AV	Return Fan CFM
AV	Outside Air CFM STPT
AV	Outside Air CFM
AV	Current Supply Pressure STPT
AV	Outside Air Temp. to Microset
AO	Return Fan Speed
AO	Modulating CW Valve
AO	Modulating Return Air Damper
AO	Supply Fan Speed
AI	Duct Pressure
AI	Supply Air Temp
AI	Return Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BI	AHU-5 Smoke Det Relay Status
BI	EF 5-2 Status
BI	EF 5-1 Status
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Supply Air Filter Dirty Alarm
BV	Return Air Filter Dirty Alarm
BV	Return Fan Alarm
BV	Supply Fan Alarm

DRAFT

CD2	
Point	Type
BV	Fan Alarm Reset
BV	Smoke Alarm
BV	Occupied
BV	EF 6-3 Alarm
BV	EF 6-2 Alarm
BV	EF 6-1 Alarm
BO	EF 6-3 S/S
BO	EF 6-2 S/S
BO	EF 6-1 S/S
BO	SAF/RAF VFD S/S
BO	OA Damper Actuator
BI	High Duct Pressure Alarm
BI	Low Limit Alarm
BI	Return Fan Status
BI	Supply Fan Status
AV	Chilled Water Return
AV	Chilled Water Supply
AV	Return Damper % Open
AV	Chilled Water Valve Feed Back
AV	Cooling Valve Command
AV	Return Air CFM STPT
AV	Return Damper % Closed
AV	Supply Air STPT
AV	Supply Air CFM
AV	Return Fan CFM
AV	Outside Air CFM STPT
AV	Outside Air CFM
AV	Current Supply Pressure STPT
AV	Outside Air Temp. to Microset
AO	Return Fan Speed
AO	Modulating CW Valve
AO	Modulating Return Air Damper
AO	Supply Fan Speed
AI	Duct Pressure
AI	Supply Air Temp
AI	Return Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset

DRAFT

CD2	
Point	Type
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position

DRAFT

CD2	
Point	Type
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BI	AHU-6 Smoke Det Relay Status
BI	EF 6-3 Status
BI	EF 6-2 Status
BI	EF 6-1 Status
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Supply Air Filter Dirty Alarm
BV	Return Air Filter Dirty Alarm
BV	Return Fan Alarm
BV	Supply Fan Alarm
BV	Fan Alarm Reset
BV	Smoke Alarm
BV	Occupied
BV	EF 7-1 Alarm

DRAFT

CD2	
Point	Type
BO	EF 7-1 S/S
BO	SAF/RAF VFD S/S
BO	OA Damper Actuator
BI	High Duct Pressure Alarm
BI	Low Limit Alarm
BI	Return Fan Status
BI	Supply Fan Status
AV	Chilled Water Return
AV	Chilled Water Supply
AV	Return Damper % Open
AV	Chilled Water Valve Feed Back
AV	Cooling Valve Command
AV	Return Air CFM STPT
AV	Return Damper % Closed
AV	Supply Air STPT
AV	Supply Air CFM
AV	Return Fan CFM
AV	Outside Air CFM STPT
AV	Outside Air CFM
AV	Current Supply Pressure STPT
AV	Outside Air Temp. to Microset
AO	Return Fan Speed
AO	Modulating CW Valve
AO	Modulating Return Air Damper
AO	Supply Fan Speed
AI	Duct Pressure
AI	Supply Air Temp
AI	Return Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position

DRAFT

CD2	
Point	Type
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BI	AHU-7 Smoke Det Relay Status
BI	EF 7-1 Status
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT

DRAFT

CD2	
Point	Type
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open

DRAFT

CD2	
Point	Type
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT

DRAFT

CD2	
Point	Type
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Current Chiller Lead/Lag
BV	PCWP 1A Alarm
BV	PCWP 1 Alarm
BV	PCWP 2A Alarm
BV	PCWP 2 Alarm
BV	PCWP 1 Lead
BV	Chiller 2 Alarm
BV	Chiller 1 Alarm
BV	Chiller Manual Lead Select
BV	PCWP 2 Manual Lead Select
BV	PCWP 1 Manual Lead Select
BV	Call For Cooling From AHUs
BV	PCWP 2A Lead
BV	PCWP 2 Lead

DRAFT

CD2	
Point	Type
BV	PCWP 1A Lead
BO	Chiller 2 Enable
BO	Chiller 1 Enable
BO	PCWP 2A S/S
BO	PCWP 2 S/S
BO	PCWP 1A S/S
BO	PCWP 1 S/S
BI	Chiller 2 Status
BI	Chiller 1 Status
BI	Chiller 2 Flow Switch
BI	Chiller 1 Flow Switch
BI	PCWP 2A Status
BI	PCWP 2 Status
BI	PCWP 1A Status
BI	PCWP 1 Status
AV	Lead Select Chiller For Manual Mode
AV	CW Return STPT
AI	Chiller 2 Supply Temp
AI	Chiller 1 Supply Temp
AI	Chiller 2 Return Temp
AI	Chiller 1 Return Temp
BV	Chiller Alarm Reset
BV	Primary Chilled Water Pump Alarm Reset
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.

DRAFT

CD2	
Point	Type
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	SCWP 2 Alarm
BV	SCWP 1 Alarm
BV	SCWP 2 Lead
BV	SCWP 1 Lead
BV	SCWP 2 Manual VFD Speed
BV	SCWP 1 Manual VFD Speed
BO	SCWP 2 VFD S/S
BO	SCWP 1 VFD S/S
BI	SCWP 1 Status
BI	SCWP 2 Status
AV	SCWP 2 Manual VFD Speed
AV	SCWP 1 Manual VFD Speed
AV	Loop 2 Tons Refrigeration Demand
AV	Loop 1 Tons Refrigeration Demand
AV	Loop Averaging Differential
AV	SCWP Output STPT PSI
AO	SCWP 2 VFD Speed Command
AO	SCWP 1 VFD Speed Command
AI	Flow Meter
AI	Loop 2 Differential Pressure
AI	Loop 1 Differential Pressure
AI	SCWP 2 VFD Speed
AI	SCWP 1 VFD Speed
AI	Secondary CWR Temp
AV	CW Differential Pressure STPT
BV	SCWP Lead Select
BV	Secondary Chilled Water Pump Alarm Reset
BV	Force Damper Closed

DRAFT

CD2	
Point	Type
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.

DRAFT

CD2	
Point	Type
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Offset
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
AV	MicroTouch Lever Value
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT

DRAFT

CD2	
Point	Type
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Current Loop Lead/Lag
BV	System 2 Stage 3
BV	System 1 Stage 3
BV	System 2 Stage 2
BV	System 1 Stage 2
BV	System 2 Stage 1
BV	System 1 Stage 1
BV	System 2 Active
BV	System 1 Active
BV	HWP Manual Lead Select
BV	HWP-1A Alarm
BV	HWP-1 Alarm
BV	HW System Enable
BO	HWP-1A S/S
BO	HWP-1 S/S
BI	HW Flow Switch
BI	HWP-1A Status
BI	HWP-1 Status
AV	Controlling OAT
AV	Steam Valve 2B Command
AV	Steam Valve 2A Command
AV	Steam Valve 1B Command
AV	Steam Valve 1A Command
AV	HW Bypass Valve Actual STPT
AV	Lead Select for HWP Manual Mode
AV	HW Bypass Valve Position
AV	Steam Valve 2B 1/3 Position
AV	Steam Valve 2A 2/3 Position

DRAFT

CD2	
Point	Type
AV	Steam Valve 1B 1/3 Position
AV	Steam Valve 1A 2/3 Position
AV	Control Signal Steam Valve
AV	HW Bypass Valve Command
AV	HW Bypass Valve Manual STPT
AV	HW Temp STPT
AV	OA Low Temp STPT
AV	OA High Temp STPT
AV	HW Low Temp STPT
AV	HW High Temp STPT
AO	PBP-1 Bypass Valve Command
AO	AO 03
AO	CV-2A Valve Manual Output Command
AO	CV-1B Valve Manual Output Command
AO	CV-1A Valve Manual Output Command
AI	HW PBP-1 Bypass Valve Position
AI	CV-2B 1/3 Valve Position
AI	CV-2A 2/3 Valve Position
AI	CV-1B 1/3 Valve Position
AI	CV-1A 2/3 Valve Position
AI	Loop Differnetial Pressure
AI	HW OA Temp
AI	HW Supply Temp
BV	Hot Water Pump Alarm Reset
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.

DRAFT

CD2	
Point	Type
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BI	Fuel Leak Panel Alarm
AI	HW Flow Meter
AI	HW Return Temp
AI	Steam Flow
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position

DRAFT

CD2	
Point	Type
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position

DRAFT

CD2	
Point	Type
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position

DRAFT

CD2	
Point	Type
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	AHU-2 Global VAV Occupied STPT
BV	AHU-1 Global VAV Occupied STPT
BV	AHU-3 Global VAV Occupied STPT
BV	AHU-5 Global VAV Occupied STPT
BV	AHU-4 Global VAV Occupied STPT
BV	AHU-7 Global VAV Occupied STPT
BV	AHU-6 Global VAV Occupied STPT
AV	Occupied STPT
SCH	sched 4
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)

DRAFT

CD2	
Point	Type
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value

DRAFT

CD2	
Point	Type
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value

DRAFT

CD2	
Point	Type
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value

DRAFT

CD2	
Point	Type
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	AI 04
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value

DRAFT

CD2	
Point	Type
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value

DRAFT

CD2	
Point	Type
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value

DRAFT

CD2	
Point	Type
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	AV 05
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow

DRAFT

CD2	
Point	Type
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
BV	Force Damper Closed
BV	Force Damper Open
BV	Occupied Command
AV	Heating Valve Position
AV	Damper Position
AV	Desired Air Flow STPT
AV	Setpoint (SP)
AV	MicroTouch Lever Value
AV	Microset Room Temp.
AI	Current Air Flow
AI	Discharge Air Temp
(INTENTIOINLY LEFT BLANK)	
(CONTINUES ON NEXT PAGE)	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
NAE -04		**Network controller**
Non-FEC BACnet Device	HP-2	Device 1002/VLC-651RC3
Non-FEC BACnet Device	HP-4	Device 1004/VLC-651RC3
Non-FEC BACnet Device	HP-5	Device 1005/VLC-651RC3
Non-FEC BACnet Device	HP-6	Device 1006/VLC-651RC3
Non-FEC BACnet Device	HP-7	Device 1007/VLC-651RC3
Non-FEC BACnet Device	HP-7B	Device 1009/VLC-651RC3
Non-FEC BACnet Device	HP-7A	Device 1008/VLC-651RC3
Non-FEC BACnet Device	HP-19	Device 1023/VLC-651RC3
Non-FEC BACnet Device	HP-9	Device 1011/VLC-651RC3
Non-FEC BACnet Device	HP-10	Device 1012/VLC-651RC3
Non-FEC BACnet Device	HP-11	Device 1013/VLC-651RC3
Non-FEC BACnet Device	HP-3	Device 1003/VLC-651RC3
Non-FEC BACnet Device	HP-12	Device 1014/VLC-651RC3
Non-FEC BACnet Device	HP-13	Device 1015/VLC-651RC3
Non-FEC BACnet Device	HP-14	Device 1016/VLC-651RC3
Non-FEC BACnet Device	HP-16A	Device 1018/VLC-651RC3
Non-FEC	HP-16B	Device 1019/VLC-651RC3

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
BACnet Device		
Non-FEC BACnet Device	HP-17	Device 1020/VLC-651RC3
Non-FEC BACnet Device	HP-17B	Device 1021/VLC-651RC3
Non-FEC BACnet Device	HP-18	Device 1022/VLC-651RC3
Non-FEC BACnet Device	HP-21	Device 1025/VLC-651RC3
Non-FEC BACnet Device	HP-8	Device 1010/VLC-651RC3
Non-FEC BACnet Device	HP-23	Device 1027/VLC-651RC3
Non-FEC BACnet Device	HP-24	Device 1028/VLC-651RC3
Non-FEC BACnet Device	HP-25	Device 1029/VLC-651RC3
Non-FEC BACnet Device	HP-26	Device 1030/VLC-651RC3
Non-FEC BACnet Device	HP-27	Device 1031/VLC-651RC3
Non-FEC BACnet Device	HP-28A	Device 1032/VLC-651RC3
Non-FEC BACnet Device	HP-28B	Device 1033/VLC-651RC3
Non-FEC BACnet Device	HP-29	Device 1034/VLC-651RC3
Non-FEC BACnet Device	HP-30A	Device 1035/VLC-651RC3
Non-FEC BACnet Device	HP-30B	Device 1036/VLC-651RC3
Non-FEC BACnet Device	HP-31	Device 1037/VLC-651RC3
Non-FEC BACnet Device	HP-32	Device 1038/VLC-651RC3

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
Non-FEC BACnet Device	HP-33	Device 1039/VLC-651RC3
Non-FEC BACnet Device	HP-34	Device 1040/VLC-651RC3
Non-FEC BACnet Device	HP-35	Device 1041/VLC-651RC3
Non-FEC BACnet Device	HP-36	Device 1042/VLC-651RC3
Non-FEC BACnet Device	HP-37A	Device 1042/VLC-651RC3
Non-FEC BACnet Device	HP-37B	Device 1044/VLC-651RC3
Non-FEC BACnet Device	HP-39	Device 1046/VLC-651RC3
Non-FEC BACnet Device	HP-40	Device 1047/VLC-651RC3
Non-FEC BACnet Device	HP-41	Device1048/VLC-651RC3
Non-FEC BACnet Device	HP-42	Device 1049/VLC-651RC3
Non-FEC BACnet Device	HP-43	Device 1050/VLC-651RC3
Non-FEC BACnet Device	HP-45	Device 1052/VLC-651RC3
Non-FEC BACnet Device	HP-46	Device 1053/VLC-651RC3
Non-FEC BACnet Device	HP-47	Device 1054/VLC-651RC3
Non-FEC BACnet Device	HP-48	Device 1055/VLC-651RC3
Non-FEC BACnet Device	HP-44	Device 1051/VLC-651RC3
Non-FEC BACnet Device	HP-49	Device 1056/VLC-651RC3
Non-FEC BACnet	HP-50	Device 1057/VLC-651RC3

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
Device		
Non-FEC BACnet Device	HP-51	Device 1058/VLC-651RC3
Non-FEC BACnet Device	HP-52	Device 1059/VLC-651RC3
Non-FEC BACnet Device	HP-53	Device 1060/VLC-651RC3
Non-FEC BACnet Device	HP-54	Device 1061/VLC-651RC3
Non-FEC BACnet Device	HP-55A	Device 1062/VLC-651RC3
Non-FEC BACnet Device	HP-55B	Device 1063/VLC-651RC3
Non-FEC BACnet Device	HP-55C	Device 1064/VLC-651RC3
Non-FEC BACnet Device	FANS 1 & 2	Device 1/VLC 16160
Non-FEC BACnet Device	FANS 3 & 4	Device 1/VLC 16160
Non-FEC BACnet Device	Device 1026-VLC-651 {HP-22}	Device 1026-VLC-651 {HP-22}
Non-FEC BACnet Device	Device 1065VLC-651RC3 {HP-55D}	Device 1065VLC-651RC3 {HP-55D}
Non-FEC BACnet Device	Device-105(Cooling Tower)	Device-105(Cooling Tower)
NAE-05	Oceana Clinic	
Controller	Trunk.UNT-1	UNT-1
Controller	Trunk.UNT-24	HP-20 (2-6-28-P)
Controller	Trunk.UNT-45	HP-38
Controller	Trunk.UNT-145	HP-45
Controller	Trunk.HP-16B	HP-16B
Controller	Trunk.HP-22	HP-22
Controller	Trunk.HP-28A (UNT-28)	HP-28A (UNT-28)
BV	HP-2.Hi/Low Condensor Water Alarm	
BI	HP-2.Compressor Status	
BI	HP-2.Fan Status	
AV	HP-2.Cooling Signal	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	HP-2.Heating Signal	
AV	HP-2.Setpoint (SP)	
AV	HP-2.Space Humidity	
AV	HP-2.Microset Room Temp.	
AV	HP-2.Current Heating SP	
AV	HP-2.Current Cooling SP	
AI	HP-2.Return Air Temp	
AI	HP-2.Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AI	Return Air Temp	
AI	Supply Air Temp	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
BV	Hi/Low Condensor Water Alarm	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BI	Compressor Status	
BI	Fan Status	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AI	Supply Air Temp	
BI	Compressor Status	
BI	Fan Status	
BV	Hi/Low Condensor Water Alarm	
AI	Return Air Temp	
AI	Supply Air Temp	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
BV	Hi/Low Condensor Water Alarm	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BI	Compressor Status	
BI	Fan Status	
BV	Hi/Low Condensor Water Alarm	
AV	Cooling Signal	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Supply Air Temp	
AI	Return Air Temp	
BV	Occupied / Unoccupied Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AI	Return Air Temp	
AI	Supply Air Temp	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
AI	Return Air Temp	
AI	Supply Air Temp	
BI	Compressor Status	
BI	Fan Status	
BV	Hi/Low Condensor Water Alarm	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BI	BI 03	
BI	BI 01	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AI	Supply Air Temp	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Fan Status	
BI	Compressor Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	
AI	Supply Air Temp	
BV	Hi/Low Condensor Water Alarm	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Signal	
AV	Heating Signal	
AV	Setpoint (SP)	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AI	Return Air Temp	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AI	Supply Air Temp	
BV	Fan #2 Disable Unit	
BV	Fan #1 Disable Unit	
BI	Fan #2 Exhaust Fan Status	
BI	Fan #2 Intake Fan Status	
BI	Fan #2 Smoke Detector	
BI	Fan #1 Exhaust Fan Status	
BI	Fan #1 Intake Fan Status	
BI	Fan #1 Smoke Detector	
AV	Cooling Setpoint Offset	
AV	Setpoint Low Limit	
AV	Setpoint High Limit	
AV	Setpoint	
AV	Fan #2 Heat Wheel Runtime	
AV	Fan #2 Exhaust Fan Runtime	
AV	Fan #2 Intake Fan Runtime	
AV	Fan #1 Heat Wheel Runtime	
AV	Fan #1 Exhaust Fan Runtime	
AV	Fan #2 Reheat Return Air Temp	
AV	Demand Offset	
AV	MicroTouch Lever Value	
AV	MicroTouch Lever Offset	
AV	Outside Air Temp. for Microset	
AV	Space Humidity from Microset	
AV	Microset Room Temp.	
AV	Current Heating Setpoint	
AV	Current Cooling Setpoint	
AV	After Hours Timer	
AV	After Hours Timer Duration	
AV	Unoccupied Heating Setpoint	
AI	Fan #1 Reheat Supply Air Temp	
AI	Fan #2 Return Air Temp	
AI	Fan #2 Reheat Supply Air Temp	
AI	Fan #1 Reheat Return Air Temp	
AI	Fan #1 Return Air Temp	
AI	Fan #1 Return Air Temp	
BV	Fan #4 Disable Unit	
BV	Fan #3 Disable Unit	
BV	Occupied / Unoccupied Status	
BI	Fan #4 Exhaust Fan Status	
BI	Fan #4 Intake Fan Status	
BI	Fan #4 Smoke Detector	
BI	Fan #3 Exhaust Fan Status	
BI	Fan #3 Intake Fan Status	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
BI	Fan #3 Smoke Detector	
AV	Heating SP Offset	
AV	Cooling SP Offset	
AV	Setpoint Low Limit	
AV	Setpoint High Limit	
AV	Setpoint (SP)	
AV	Fan #4 Heat Wheel Runtime	
AV	Fan #4 Exhaust Fan Runtime	
AV	Fan #4 Intake Fan Runtime	
AV	Fan #3 Heat Wheel Runtime	
AV	Fan #3 Heat Wheel Runtime	
AV	Fan #3 Intake Fan Runtime	
AV	Outside Humidity	
AV	Demand Offset	
AV	MicroTouch Lever Value	
AV	MicroTouch Lever Offset	
AV	Outside Air Temp. to Microset	
AV	Space Humidity	
AV	Microset Room Temp.	
AV	Current Heating SP	
AV	Current Cooling SP	
AV	After Hours Timer	
AV	After Hours Timer	
AV	Unoccupied Heating SP	
AI	Fan #4 Reheat Return Air Temp	
AI	Fan #4 Reheat Return Air Temp	
AI	Fan #4 Reheat Supply Air Temp	
AI	Fan #3 Reheat Return Air Temp	
AI	Fan #3 Return Air Temp	
AI	Fan #3 Reheat Supply Air Temp	
AV	Setpoint (SP)	
AV	Current Heating SP	
AV	Current Cooling SP	
BV	Hi Low Condensor Water Alarm	
AV	Microset Room Temperature	
AV	Cooling Signal	
AV	Heating Signal	
AI	Supply Air Temp	
AI	Return Air Temperature	
BI	Compressor Status	
BI	Fan Status	
AV	Cooling Setpoint	
AV	Heating Setpoint	
AV	Setpoint (SP)	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AV	Microset Room Temp.	
BV	Hi/Low Condensor Water Alarm	
AI	Return Air Temperature	
AI	Supply Air Temperature	
AI	AI 02	
AI	AI 01	
BI	BI 07	
BI	BI 06	
BV	BV 10	
BV	BV 00	
BV	BV 25	
BV	BV 21	
BV	BV 20	
BV	Door Open ICON	
BV	Fan High Speed	
BV	Fan Medium Speed	
BV	Fan Low Speed	
AI	BLR WTR SUPP TMP TO TWR BASIN	
BO	Pump Shutdown	
AI	ZN-T	
BI	SF-S	
BO	SF-C	
BO	CMPR-C	
BO	RVLV-C	
AI	OCCCLG-SP	
AI	OCCHTG-SP	
AI	DA-T	
BI	CMPR-S	
AI	ZN-T	
BI	SF-S	
BO	SF-C	
BO	CMPR-C	
BO	RVLV-C	
AI	OCCCLG-SP	
AI	OCCHTG-SP	
AI	DA-T	
BI	CMPR-S	
AI	Return Temperature	
AI	Discharge Air Temp	
BI	Supply Fan Status	
BO	Supply Fan Command	
BO	Compressor Command	
BO	Reversing Valve Command	

DRAFT

NAS Oceana, Building 285		
Points	**Equipment**	**Type**
AI	Occ Cooling Setpoint	
AI	Occ Heating Setpoint	
BI	Compressor Status	
BI	Filter Status	
AI	Return Temperature	
AI	Discharge Air Temp	
BI	Supply Fan Status	
BO	Supply Fan Command	
BO	Compressor Command	
BO	Reversing Valve	
BI	Compressor Status	
BI	Filter Status	
AO	Occ Cooling Setpoint	
AO	Occ Heating Setpoint	
AI	Return Temperature	
AI	Discharge Air Temp	
BI	Supply Fan Status	
BO	Supply Fan Command	
BO	Commpressor Command	
BO	Reversing Valve Command	
AI	Occ Cooling Setpoint	
AI	Occ Heating Setpoint	
BI	Compressor Status	
BI	Filter Status	

DRAFT

NNSY Clinic	
NAE-03	**NAE-03 NNSY Clinic**
NAE-03/N2-1.AHU-1	AHU-1
NAE-03/N2-1.UNT-1	UNT-1
NAE-03/N2-1.E0U1	E01U
NAE-03/N2-1.E02U	E02U
NAE-03/N2-1.E03U	E03U
NAE-03/N2-1.E04U	E04U
NAE-03/N2-1.E05U	E05U
NAE-03/N2-1.E06U	E06U
NAE-03/N2-1.E07U	E07U
NAE-03/N2-1.E08U	E08U
NAE-03/N2-1.E09U	E09U
NAE-03/N2-1.E10U	E10U
NAE-03/N2-1.E11U	E11U
NAE-03/N2-1.E12U	E12U
NAE-03/N2-1.E13U	E13U
NAE-03/N2-1.E14U	E14U
NAE-03/N2-1.E15U	E15U
NAE-03/N2-1.E16U	E16U
NAE-03/N2-1.E17U	E17U
NAE-03/N2-1.E18U	E18U
NAE-03/N2-1.E19U	E19U
NAE-03/N2-1.E20U	E20U
NAE-03/N2-1.E21U	E21U
NAE-03/N2-1.E22U	E22U
NAE-03/N2-1.E23U	E23U
NAE-03/N2-1.E212U	E212U
NAE-03/N2-1.E213U	E213U
NAE-03/N2-1.E240U	E240U
NAE-03/N2-1.YRK-GATEWAY	YRK-GATEWAY
NAE-03/N2-1.YRK-CHLR	YRK-CHLR
AI	NNSY.AHU-1.OA-T
AI	NNSY.AHU-1.RET-T
AI	NNSY.AHU-1.DAT
AI	NNSY.AHU-1.Steam-Fl
AI	NNSY.AHU-1.SA-P
AI	NNSY.AHU-1.RA-VP
AI	NNSY.AHU-1.S-VP
AI	NNSY.AHU-1.MA-T
BO	NNSY.AHU-1.CHILLER ENABLE
BO	NNSY.AHU-1.CHILL WATER PUMP ENABLE
BO	NNSY.AHU-1.AHU HOT WATER PUMP ENABLE
BO	NNSY.AHU-1.HOT WATER PUMP ENABLE

DRAFT

NNSY Clinic	
BO	NNSY.AHU-1.EXHAUST FAN 2 ENABLE
BO	NNSY.AHU-1.EXHAUST FAN 3 ENABLE
BO	NNSY.AHU-1.EXHAUST FAN 7 ENABLE
BO	NNSY.AHU-1.EXHAUST FAN 8 ENABLE
BO	NNSY.AHU-1.SF-C
BO	NNSY.AHU-1.RF-C
BI	NNSY.AHU-1.OCC-S
AO	NNSY.AHU-1.RSTRTDLY
BI	NNSY.AHU-1.SDWN-S
BI	NNSY.AHU-1.ECON-S
BI	NNSY.AHU-1.RESTASTS
BO	NNSY.AHU-1.SDWN-C
AO	NNSY.AHU-1.DAT-SP
AO	NNSY.AHU-1.DHDB
AO	NNSY.AHU-1.DHPB
AO	NNSY.AHU-1.DHIT
AO	NNSY.AHU-1.DCPB
AO	NNSY.AHU-1.DCIT
AO	NNSY.AHU-1.MINPOSSP
AI	NNSY.AHU-1.MAT-SP
AO	NNSY.AHU-1.MAPB
AO	NNSY.AHU-1.MAIT
AO	NNSY.AHU-1.MADB
AO	NNSY.AHU-1.MALL
AO	NNSY.AHU-1.MALLPB
AO	NNSY.AHU-1.MALLIT
AO	NNSY.AHU-1.MALLDB
AO	NNSY.AHU-1.DBSWOV
AO	NNSY.AHU-1.SWOVDIF
AO	NNSY.AHU-1.PHPB
AO	NNSY.AHU-1.SP-SET
AO	NNSY.AHU-1.SP-PB
AO	NNSY.AHU-1.SPO
AO	NNSY.AHU-1.SP-IT
AO	NNSY.AHU-1.SP-DB
AO	NNSY.AHU-1.SP-DW
AI	NNSY.AHU-1.SA-F
AO	NNSY.AHU-1.OCCFLODF
AO	NNSY.AHU-1.SPRAMPST
AO	NNSY.AHU-1.SUPDUCTA
AO	NNSY.AHU-1.SPSUP-K
AO	NNSY.AHU-1.FANDLTTM
BI	NNSY.AHU-1.SF-A
AI	NNSY.AHU-1.RA-F
AO	NNSY.AHU-1.SP-RVPB

DRAFT

NNSY Clinic	
AO	NNSY.AHU-1.SP-RVIN
AO	NNSY.AHU-1.SP-RVO
AO	NNSY.AHU-1.SP-RVDB
AO	NNSY.AHU-1.SP-RVDW
AO	NNSY.AHU-1.SPRET-DA
AO	NNSY.AHU-1.RET-K
BI	NNSY.AHU-1.RF-A
AO	NNSY.AHU-1.COMPSP
AO	NNSY.AHU-1.DIFF
AO	NNSY.AHU-1.FSINPT
AO	NNSY.AHU-1.COMPSP-2
AO	NNSY.AHU-1.DIFF-2
AO	NNSY.AHU-1.FSINPT-2
AO	NNSY.AHU-1.COMPSP-3
AO	NNSY.AHU-1.DIFF-3
AO	NNSY.AHU-1.FSINPT-3
BI	NNSY.AHU-1.SF-S
BI	NNSY.AHU-1.HI STAT
BI	NNSY.AHU-1.FRZ-ALM
BI	NNSY.AHU-1.RF-S
BI	NNSY.AHU-1.CHILL WATER PUMP STATUS
BI	NNSY.AHU-1.Hwp-Man
BI	NNSY.AHU-1.HWP2-ST
BI	NNSY.AHU-1.SMK-DET
AO	NNSY.AHU-1.CLG-O
AO	NNSY.AHU-1.HTG-O
AO	NNSY.AHU-1.SF-O
AO	NNSY.AHU-1.RF-O
AO	NNSY.AHU-1.PH-O
AO	NNSY.AHU-1.DPR-O
AO	NNSYPISTPT
AO	NNSYPI-IT
AO	NNSYPIPB
AO	NNSYPIDB
AO	NNSYPIOFST
AO	NNSYPIFOUT
AO	NNSYRSTRTDLY
BI	NNSYOCCSTS
BI	NNSYSHUTSTS
BI	NNSYRESTASTS
BO	NNSYOCCCMD
BO	NNSYSHUTDOWN
AI	NNSYHWS-T
AI	NNSYHWR-T
AI	NNSYCHWS-T

DRAFT

NNSY Clinic	
AI	NNSYCHWR-T
BI	NNSYHOT WATER PUMP STATUS
BI	NNSYCWP1-M
BI	NNSYCHLR-ALM
AO	NNSYHX VLV-C
BO	NNSYOA-Fan C
AI	NNSYRoom-T
AO	NNSYDayClgSt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSY.E02U.Room-T
AO	NNSY.E02U.DayClgSt
AO	NNSY.E02U.DmprPos
AO	NNSY.E02U.Vlv-Pos
AO	NNSY.E02U.FlowStpt
AO	NNSY.E02U.Flow
BO	NNSY.E02U.DayNight
BO	NNSY.E02U.Fan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight

DRAFT

NNSY Clinic	
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos

DRAFT

NNSY Clinic	
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYDayClgSt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T

DRAFT

NNSY Clinic	
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYDayClgSt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow

DRAFT

NNSY Clinic	
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYCtlStpt
AO	NNSYDmprPos
AO	NNSYVlv-Pos
AO	NNSYFlowStpt
AO	NNSYFlow
BO	NNSYDayNight
BO	NNSYFan-SS
AI	NNSYRoom-T
AO	NNSYDayClgSt
BO	NNSYDayNight
AI	NNSYRoom-T
AO	NNSYDayClgSt
BO	NNSYDayNight
AI	NNSYRoom-T
AO	NNSYDayClgSt
BO	NNSYDayNight
AI	NNSYYRK-LCWT
AI	NNSYYRK-RCWT
BI	NNSYYRK-SYS1ALM
BI	NNSYYRK-SYS2ALM
AI	NNSYYRK-SYS1COMPRS
AI	NNSYYRK-SYS2COMPRS
BO	NNSYCW-ENABL
BO	NNSYPMP-ROT
BI	NNSYCHLR-STA
BI	NNSYPMP1-STA
BI	NNSYPMP2-STA
AI	NNSYYRK-CWS-T
BO	NNSYCHLR-CMD
BO	NNSYPMP1-CMD
BO	NNSYPMP2-CMD
AI	NNSYRK-CWR-T

DRAFT

Yorktown Clinic		
NAE 02	Yorktown	
CHWS	N2-1.Chilled Water-Hot Water System	Controller
AHU-01	N2-1.AHU-01	Controller
VAV-B(Pharmacy Storage)	N2-1.VAV-B(Pharmacy Storage)	Controller
VAV-C(Emergency Entry)	N2-1.VAV-C(Emergency Entry)	Controller
VAV-D(RM 112)	N2-1.VAV-D(RM 112)	Controller
VAV-E(RM MIL Sick Call Hallway)	N2-1.VAV-E(RM MIL Sick Call Hallway)	Controller
VAV-F(RM 114)	N2-1.VAV-F(RM 114)	Controller
VAV-G(RM 117)	N2-1.VAV-G(RM 117)	Controller
VAV-H(RM 119)	N2-1.VAV-H(RM 119)	Controller
VAV-I	N2-1.VAV-I	Controller
VAV-J	N2-1.VAV-J	Controller
VAV-K	N2-1.VAV-K	Controller
VAV-L	N2-1.VAV-L	Controller
VAV-M(RM 211)	N2-1.VAV-M(RM 211)	Controller
VAV-N(RM 304)	N2-1.VAV-N(RM 304)	Controller
VAV-O(RM 308)	N2-1.VAV-O(RM 308)	Controller
VAV-P(RM 312)	N2-1.VAV-P(RM 312)	Controller
VAV-Q	N2-1.VAV-Q	Controller
VAV-R(RM 400B)	N2-1.VAV-R(RM 400B)	Controller
VAV-S(RM 400G)	N2-1.VAV-S(RM 400G)	Controller
VAV-T(RM 400C)	N2-1.VAV-T(RM 400C)	Controller
VAV-U(RM 400D)	N2-1.VAV-U(RM 400D)	Controller
VAV-V(RM 404)	N2-1.VAV-V(RM 404)	Controller
VAV-W(RM 122)	N2-1.VAV-W(RM 122)	Controller
VAV-X(RM 111)	N2-1.VAV-X(RM 111)	Controller
VAV-Y(RM 109	N2-1.VAV-Y(RM 109	Controller

DRAFT

Yorktown Clinic		
VAV-Z(RM 104)	N2-1.VAV-Z(RM 104)	Controller
VAV-AA(RM 100)	N2-1.VAV-AA(RM 100)	Controller
VAV-BB(RM 213	N2-1.VAV-BB(RM 213	Controller
VAV-CC(RM 212)	N2-1.VAV-CC(RM 212)	Controller
VAV-DD(RM 211)	N2-1.VAV-DD(RM 211)	Controller
VAV-EE(RM 209)	N2-1.VAV-EE(RM 209)	Controller
VAV-FF(BloodWorks Waiting Room)	N2-1.VAV-FF(BloodWorks Waiting Room)	Controller
VAV-GG(BloodWorks Waiting Room	N2-1.VAV-GG(BloodWorks Waiting Room	Controller
VAV-HH(RM 304)	N2-1.VAV-HH(RM 304)	Controller
VAV-II(RM 403)	N2-1.VAV-II(RM 403)	Controller
VAV-JJ(RM 125E)	N2-1.VAV-JJ(RM 125E)	Controller
VAV-KK(RM 125	N2-1.VAV-KK(RM 125	Controller
VAV-LL(RM 125)	N2-1.VAV-LL(RM 125)	Controller
VAV-MM(RM 125A)	N2-1.VAV-MM(RM 125A)	Controller
VAV-A(407 Supply)	N2-1.VAV-A(407 Supply)	Controller
BV	How Water Pump Alarm	
BV	Chill Water Pump Alarm	
BI	CHWS.ECON-C	Economizer Command(LRS)
BI	CHWS.HWP1-C(LRS)	Hot Water Pump 1 Command(LRS)
BI	CHWS.HWP2-C(LRS)	Hot Water Pump 2 Command(LRS)
BI	CHWS.CHWP1-C(LRS)	Chill Water Pump 1 Command(LRS)
BI	CHWS.CHWP2-C(LRS)	Chill Water ump 2 Command(LRS)
AI	CHWS.OA-T	Outdoor Air Temp
AI	CHWS.HWS-T	Hot Water Supply Temp
AI	CHWS.HWR-T	Hot Water Return Temp
AI	CHWS.CHWR-T	Chill Water Return Temp
AI	CHWS-T	Chill Water Supply Temp

DRAFT

Yorktown Clinic		
BI	CHWS.BLR1-A	Boiler 1 Alarm
BI	CHWS.CH1-A	Chiller 1 Alarm
BI	CHWS.HWP1-S	Hot Water Pump 1 Status
BI	CHWS.HWP2-S	Hot Water Pump 2 Status
BI	CHWS.CHWP1-S	Chill Water Pump 1 Statu
BI	CHWS.CHWP2-S	Chill Water Pump 2 Statu
BI	CHWS.FLOW-S	Chill Water Flow
BI	CHWS.CHLR1-S	Chiller 1 Status
BO	CHWS.BLR1-C	Boiler 1 Command
BO	CHWS.CH1-C	Chiller 1 Command
BO	CHWS.HWP1-C	Hot Water Pump 1 Command
BO	CHWS.HWP2-C	Hot Water Pump 2 Command
BO	CHWS.CHWP1-C	Chill Water Pump 1 Cmd
BO	CHWS.CHWP2-C	Chill Water Pump 2 Cmd
AO	CHWS.ECON-SP	Economizer Setpoint(ACO)
BO	CHWS.HTG-RUN	Heating Run(DCO
BO	CHWS.CLG-RUN	Cooling Run(DCO)
BO	CHWS.ROTATE-C	Rotate Command(DCO)
BO	CHWS.SETUP80	Setup Greater Than 80(DCO)
BO	CHWS.SETBK60	Setback Less Than 60(DCO)
BI	CHWS.HWP1-EN	Hot Water Pump 1 Enable(LRS)
BI	CHWS.HWP2-EN	Hot Water Pump 2 Enable(LRS)
BI	CHWS.CHWP1-EN	Chill Water Pump 1 Enable(LRS)
BI	CHWS.CHWP2-EN	Chill Water Pump 2 Enable(LRS)
BI	CHWS.CHLR1-C	Chiller 1 Command(LRS)
BI	CHWS.BOILER-C	Boiler Command(LRS)
BI	CHWS.B1-RUN	Boiler 1 Run(LRS)
BI	CHWS.C1-RUN	Chiller 1 Run(LRS)
BO	AHU-01.ECON-EN	Economizer Enable(DCO)
BO	AHU-01.VAVCLG-C	VAV Cooling Command(DCO)
AI	AHU-01.HD-T	Hot Deck Temp
AI	AHU-01.CD-P	Cold Deck Down Duct
AI	AHU-01.HD-P	Hot Deck Down Duct

DRAFT

Yorktown Clinic		
AI	AHU-01.SA-P	Discharge Static Press
AI	AHU-01.MA-T	Mixed Air Temp
BI	AHU-01.SF-S	Supply Fan Status
BI	AHU-01.RF-S	Return Fan Status
BI	AHU-01.LT-A	Low Limit Alarm
BI	AHU-01.SMOKE	Supply Air Smoke Alarm
BI	AHU-01.FILTER-S	Prefilter Alarm
BI	AHU-01.OAD-S	Outside Air Dmpr Status
BI	AHU-01.EAD-S	Exhuast Air Dmpr Status
BI	AHU-01.MAD-S	Mixed Air Dmpr Status
AO	AHU-01.CLG-O	Cooling Valve Control
AO	AHU-01.HTG-O	Heating Valve Control
AO	AHU-01.SFAN-O	Supply Fan VFD Control
AO	AHU-01.RFAN-O	Return Fan VFD Control
AO	AHU-01.OAD-O	Outside Air Damper
AO	AHU-01.MAD-O	Return Air Damper
AO	AHU-01.EAD-O	Exhaust Air Damper
BO	AHU-01.SF-C	Supply Fan Command
BO	AHU-01.RF-C	Return Fan Command
BI	AHU-01.ECON-C	Economizer Command(LRS)
BI	AHU-01.CLG-C	Cooling Command(LRS)
BI	AHU-01.HTG-C	Heating Command(LRS)
BI	AHU-01.STATIC-C	Static Command(LRS)
BI	AHU-01.SF-RUN	Supply Fan Run(LRS)
BI	AHU-01.RF-RUN	Return Fan Run(LRS)
BI	AHU-01.SF-ALARM	Supply Fan Alarm(LRS)
BI	AHU-01.RF-ALARM	Return Fan Alarm(LRS)
BI	AHU-01.SFAN-C	Supply Fan Command(LRS)
BI	AHU-01.RFAN-C	Return Fan Command(LRS)
BI	AHU-01.SA-PRS-A	Supply Air Pressure Alarm(LRS)
BO	AHU-01.SCHEDOCC	Scheduled Occupancy(DCO)
BO	AHU-01.VAVHTG-C	VAV Heating Command(DCO)
BO	AHU-01.SETUP80	Setup Geater Than 80F(DCO)
BO	AHU-01.SETBK60	Setback Greater less that 60F(DCO)
BO	AHU-01.RESET	Reset(DCO)
AO	AHU-01.COOL-SP	Cooling Setpoint(ACO)
AO	AHU-01.HEAT-SP	Heating Setpoint(ACO)
AO	AHU-01.DD-SP	Down Duct Static Pressure Setpoint(ACO)
AO	AHU-01.MALL-SP	Low Aalrm(ACO)

DRAFT

Yorktown Clinic		
AO	AHU-01.HI-ALMSP	High Alarm(ACO)
AO	AHU-01.MIN-POS	Minimum Positiong(ACO)
AI	CD-T	Cold Deck Temp
AI	VAV-B(Pharmacy Storage).CD-O	Cold Deck Damper Output
MO	VAV-B(Pharmacy Storage).OCC-C	Occupied Command
MO	VAV-B(Pharmacy Storage).BOX-MODE	Vav Box Mode
AI	VAV-B(Pharmacy Storage).CDFLOW	Cold Deck Flow
AO	VAV-B(Pharmacy Storage).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-B(Pharmacy Storage).HDFLOW	Hot Deck Flow
AO	VAV-B(Pharmacy Storage).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-B(Pharmacy Storage).HD-O	Hot Deck Damper Output
AI	VAV-B(Pharmacy Storage).ZN-T	Zone Temperature
AI	VAV-B(Pharmacy Storage).DA-T	Discharge Air Temperature
AI	VAV-B(Pharmacy Storage).ZNT-SP	Zone Temp Setpoint
AO	VAV-.WC-ADJ	Warmer Cooler Adjust
AI	VAV-C(Emergency Entry).CD-O	Cold Deck Damper Output
MO	VAV-C(Emergency Entry).OCC-C	Occupied Command
MO	VAV-C(Emergency Entry).BOX-MODE	Vav Box Mode
AI	VAV-C(Emergency Entry).CDFLOW	Cold Deck Flow
AO	VAV-C(Emergency Entry).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-C(Emergency Entry).HDFLOW	Hot Deck Flow
AO	VAV-C(Emergency Entry).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-C(Emergency Entry).HD-O	Hot Deck Damper Output
AI	VAV-C(Emergency Entry).ZN-T	Zone Temperature
AI	VAV-C(Emergency Entry).DA-T	Discharge Air Temperature
AI	VAV-C(Emergency Entry).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-D(RM 112).CD-O	Cold Deck Damper Output
MO	VAV-D(RM 112).OCC-C	Occupied Command
MO	VAV-D(RM 112).BOX-MODE	Vav Box Mode
AI	VAV-D(RM 112).CDFLOW	Cold Deck Flow
AO	VAV-D(RM 112).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-D(RM 112).HDFLOW	Hot Deck Flow
AO	VAV-D(RM 112).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-D(RM 112).HD-O	Hot Deck Damper Output
AI	VAV-D(RM 112).ZN-T	Zone Temperature
AI	VAV-D(RM 112).DA-T	Discharge Air Temperature
AI	VAV-D(RM 112).ZNT-SP	Zone Temp Setpoint

DRAFT

Yorktown Clinic		
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-E(RM MIL Sick Call Hallway).CD-O	Cold Deck Damper Output
MO	VAV-E(RM MIL Sick Call Hallway).OCC-C	Occupied Command
MO	VAV-E(RM MIL Sick Call Hallway).BOX-MODE	Vav Box Mode
AI	VAV-E(RM MIL Sick Call Hallway).CDFLOW	Cold Deck Flow
AO	VAV-E(RM MIL Sick Call Hallway).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-E(RM MIL Sick Call Hallway).HDFLOW	Hot Deck Flow
AO	VAV-E(RM MIL Sick Call Hallway).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-E(RM MIL Sick Call Hallway).HD-O	Hot Deck Damper Output
AI	VAV-E(RM MIL Sick Call Hallway).ZN-T	Zone Temperature
AI	VAV-E(RM MIL Sick Call Hallway).ZNT-SP	Zone Temperature Setpoint
AI	VAV-E(RM MIL Sick Call Hallway).DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-F(RM 114).CD-O	Cold Deck Damper Output
MO	VAV-F(RM 114).OCC-C	Occupied Command
MO	VAV-F(RM 114).BOX-MODE	Vav Box Mode
AI	VAV-F(RM 114).CDFLOW	Cold Deck Flow
AO	VAV-F(RM 114).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-F(RM 114).HDFLOW	Hot Deck Flow
AO	VAV-F(RM 114).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-F(RM 114).HD-O	Hot Deck Damper Output
AI	VAV-F(RM 114).ZN-T	Zone Temperature
AI	VAV-F(RM 114).ZNT-SP	Zone Temperature Setpoint
AI	VAV-F(RM 114).DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-G(RM 117).CD-O	Cold Deck Damper Output
MO	VAV-G(RM 117).OCC-C	Occupied Command
MO	VAV-G(RM 117).BOX-MODE	Vav Box Mode
AI	VAV-G(RM 117).CDFLOW	Cold Deck Flow
AO	VAV-G(RM 117).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-G(RM 117).HDFLOW	Hot Deck Flow
AO	VAV-G(RM 117).HDF-SP	Hot Deck Flow Setpoint

DRAFT

Yorktown Clinic		
AI	VAV-G(RM 117).HD-O	Hot Deck Damper Output
AI	VAV-G(RM 117).ZN-T	Zone Temperature
AI	VAV-G(RM 117).DA-T	Discharge Air Temperature
AI	VAV-G(RM 117).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-H(RM 119).CD-O	Cold Deck Damper Output
MO	VAV-H(RM 119).OCC-C	Occupied Command
MO	VAV-H(RM 119).BOX-MODE	Vav Box Mode
AI	VAV-H(RM 119).CDFLOW	Cold Deck Flow
AO	VAV-H(RM 119).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-H(RM 119).HDFLOW	Hot Deck Flow
AO	VAV-H(RM 119).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-H(RM 119).HD-O	Hot Deck Damper Output
AI	VAV-H(RM 119).ZN-T	Zone Temperature
AI	VAV-H(RM 119).DA-T	Discharge Air Temperature
AI	VAV-H(RM 119).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-I.CD-O	Cold Deck Damper Output
MO	VAV-I.OCC-C	Occupied Command
MO	VAV-I.BOX-MODE	Vav Box Mode
AI	VAV-I.CDFLOW	Cold Deck Flow
AO	VAV-I.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-I.HDFLOW	Hot Deck Flow
AO	VAV-I.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-I.HD-O	Hot Deck Damper Output
AI	VAV-I.ZN-T	Zone Temperature
AI	VAV-I.DA-T	Discharge Air Temperature
AI	VAV-I.ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-J.CD-O	Cold Deck Damper Output
MO	VAV-J.OCC-C	Occupied Command
MO	VAV-J.BOX-MODE	Vav Box Mode
AI	VAV-J.CDFLOW	Cold Deck Flow
AO	VAV-J.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-J.HDFLOW	Hot Deck Flow
AO	VAV-J.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-J.HD-O	Hot Deck Damper Output
AI	VAV-J.ZN-T	Zone Temperature
AI	VAV-J.DA-T	Discharge Air Temperature
AI	VAV-J.ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust

DRAFT

Yorktown Clinic		
AI	VAV-K.CD-O	Cold Deck Damper Output
MO	VAV-K.OCC-C	Occupied Command
MO	VAV-K.BOX-MODE	Vav Box Mode
AI	VAV-K.CDFLOW	Cold Deck Flow
AO	VAV-K.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-K.HDFLOW	Hot Deck Flow
AO	VAV-K.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-K.HD-O	Hot Deck Damper Output
AI	VAV-K.ZN-T	Zone Temperature
AI	VAV-K.ZNT-SP	Zone Temperature Setpoint
AI	VAV-K.DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-L.CD-O	Cold Deck Damper Output
MO	VAV-L.OCC-C	Occupied Command
MO	VAV-L.BOX-MODE	Vav Box Mode
AI	VAV-L.CDFLOW	Cold Deck Flow
AO	VAV-L.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-L.HDFLOW	Hot Deck Flow
AO	VAV-L.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-L.HD-O	Hot Deck Damper Output
AI	VAV-L.ZN-T	Zone Temperature
AI	VAV-L.ZNT-SP	Zone Temperature Setpoint
AI	VAV-L.DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-M(RM 211).CD-O	Cold Deck Damper Output
MO	VAV-M(RM 211).OCC-C	Occupied Command
MO	VAV-M(RM 211).BOX-MODE	Vav Box Mode
AI	VAV-M(RM 211).CDFLOW	Cold Deck Flow
AO	VAV-M(RM 211).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-M(RM 211).HDFLOW	Hot Deck Flow
AO	VAV-M(RM 211).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-M(RM 211).HD-O	Hot Deck Damper Output
AI	VAV-M(RM 211).ZN-T	Zone Temperature
AI	VAV-M(RM 211).DA-T	Discharge Air Temperature
AI	VAV-M(RM 211).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-N(RM 304).CD-O	Cold Deck Damper Output
MO	VAV-N(RM 304).OCC-C	Occupied Command
MO	VAV-N(RM 304).BOX-MODE	Vav Box Mode
AI	VAV-N(RM 304).CDFLOW	Cold Deck Flow

DRAFT

Yorktown Clinic		
AO	VAV-N(RM 304).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-N(RM 304).HDFLOW	Hot Deck Flow
AO	VAV-N(RM 304).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-N(RM 304).HD-O	Hot Deck Damper Output
AI	VAV-N(RM 304).ZN-T	Zone Temperature
AI	VAV-N(RM 304).ZNT-SP	Zone Temperature Setpoint
AI	VAV-N(RM 304).DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-O(RM 308).CD-O	Cold Deck Damper Output
MO	VAV-O(RM 308).OCC-C	Occupied Command
MO	VAV-O(RM 308).BOX-MODE	Vav Box Mode
AI	VAV-O(RM 308).CDFLOW	Cold Deck Flow
AO	VAV-O(RM 308).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-O(RM 308).HDFLOW	Hot Deck Flow
AO	VAV-O(RM 308).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-O(RM 308).HD-O	Hot Deck Damper Output
AI	VAV-O(RM 308).ZN-T	Zone Temperature
AI	VAV-O(RM 308).ZNT-SP	Zone Temperature Setpoint
AI	VAV-O(RM 308).DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-P(RM 312).CD-O	Cold Deck Damper Output
MO	VAV-P(RM 312).OCC-C	Occupied Command
MO	VAV-P(RM 312).BOX-MODE	Vav Box Mode
AI	VAV-P(RM 312).CDFLOW	Cold Deck Flow
AO	VAV-P(RM 312).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-P(RM 312).HDFLOW	Hot Deck Flow
AO	VAV-P(RM 312).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-P(RM 312).HD-O	Hot Deck Damper Output
AI	VAV-P(RM 312).ZN-T	Zone Temperature
AI	VAV-P(RM 312).DA-T	Discharge Air Temperature
AI	VAV-P(RM 312).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-Q.CD-O	Cold Deck Damper Output
MO	VAV-Q.OCC-C	Occupied Command
MO	VAV-Q.BOX-MODE	Vav Box Mode
AI	VAV-Q.CDFLOW	Cold Deck Flow
AO	VAV-Q.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-Q.HDFLOW	Hot Deck Flow
AO	VAV-Q.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-Q.HD-O	Hot Deck Damper Output

DRAFT

Yorktown Clinic		
AI	VAV-Q.ZN-T	Zone Temperature
AI	VAV-Q.DA-T	Discharge Air Temperature
AI	VAV-Q.ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-R(RM 400B).CD-O	Cold Deck Damper Output
MO	VAV-R(RM 400B).OCC-C	Occupied Command
MO	VAV-R(RM 400B).BOX-MODE	Vav Box Mode
AI	VAV-R(RM 400B).CDFLOW	Cold Deck Flow
AO	VAV-R(RM 400B).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-R(RM 400B).HDFLOW	Hot Deck Flow
AO	VAV-R(RM 400B).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-R(RM 400B).HD-O	Hot Deck Damper Output
AI	VAV-R(RM 400B).ZN-T	Zone Temperature
AI	VAV-R(RM 400B).ZNT-SP	Zone Temperature Setpoint
AI	VAV-R(RM 400B).DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-S(RM 400G).CD-O	Cold Deck Damper Output
MO	VAV-S(RM 400G).OCC-C	Occupied Command
MO	VAV-S(RM 400G).BOX-MODE	Vav Box Mode
AI	VAV-S(RM 400G).CDFLOW	Cold Deck Flow
AO	VAV-S(RM 400G).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-S(RM 400G).HDFLOW	Hot Deck Flow
AO	VAV-S(RM 400G).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-S(RM 400G).HD-O	Hot Deck Damper Output
AI	VAV-S(RM 400G).ZN-T	Zone Temperature
AI	VAV-S(RM 400G).DA-T	Discharge Air Temperature
AI	VAV-S(RM 400G).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-T(RM 400C).CD-O	Cold Deck Damper Output
MO	VAV-T(RM 400C).OCC-C	Occupied Command
MO	VAV-T(RM 400C).BOX-MODE	Vav Box Mode
AI	VAV-T(RM 400C).CDFLOW	Cold Deck Flow
AO	VAV-T(RM 400C).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-T(RM 400C).HDFLOW	Hot Deck Flow
AO	VAV-T(RM 400C).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-T(RM 400C).HD-O	Hot Deck Damper Output
AI	VAV-T(RM 400C).ZN-T	Zone Temperature
AI	VAV-T(RM 400C).ZNT-SP	Zone Temperature Setpoint
AI	VAV-T(RM 400C).DA-T	Discharge Air Temperature

DRAFT

Yorktown Clinic		
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-U(RM 400D).CD-O	Cold Deck Damper Output
MO	VAV-U(RM 400D).OCC-C	Occupied Command
MO	VAV-U(RM 400D).BOX-MODE	Vav Box Mode
AI	VAV-U(RM 400D).CDFLOW	Cold Deck Flow
AO	VAV-U(RM 400D).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-U(RM 400D).HDFLOW	Hot Deck Flow
AO	VAV-U(RM 400D).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-U(RM 400D).HD-O	Hot Deck Damper Output
AI	VAV-U(RM 400D).ZN-T	Zone Temperature
AI	VAV-U(RM 400D).ZNT-SP	Zone Temperature Setpoint
AI	VAV-U(RM 400D).DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-V(RM 404).CD-O	Cold Deck Damper Output
MO	VAV-V(RM 404).OCC-C	Occupied Command
MO	VAV-V(RM 404).BOX-MODE	Vav Box Mode
AI	VAV-V(RM 404).CDFLOW	Cold Deck Flow
AO	VAV-V(RM 404).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-V(RM 404).HDFLOW	Hot Deck Flow
AO	VAV-V(RM 404).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-V(RM 404).HD-O	Hot Deck Damper Output
AI	VAV-V(RM 404).ZN-T	Zone Temperature
AI	VAV-V(RM 404).ZNT-SP	Zone Temperature Setpoint
AI	VAV-V(RM 404).DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-W(RM 122).CD-O	Cold Deck Damper Output
MO	VAV-W(RM 122).OCC-C	Occupied Command
MO	VAV-W(RM 122).BOX-MODE	Vav Box Mode
AI	VAV-W(RM 122).CDFLOW	Cold Deck Flow
AO	VAV-W(RM 122).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-W(RM 122).HDFLOW	Hot Deck Flow
AO	VAV-W(RM 122).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-W(RM 122).HD-O	Hot Deck Damper Output
AI	VAV-W(RM 122).ZN-T	Zone Temperature
AI	VAV-W(RM 122).DA-T	Discharge Air Temperature
AI	VAV-W(RM 122).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-X(RM 111).CD-O	Cold Deck Damper Output
MO	VAV-X(RM 111).OCC-C	Occupied Command
MO	VAV-X(RM 111).BOX-MODE	Vav Box Mode

DRAFT

Yorktown Clinic		
AI	VAV-X(RM 111).CDFLOW	Cold Deck Flow
AO	VAV-X(RM 111).CDF-SP	Cold Deck Flow Setpoint
AO	VAV-X(RM 111).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-X(RM 111).HD-O	Hot Deck Damper Output
AI	VAV-X(RM 111).ZN-T	Zone Temperature
AI	VAV-X(RM 111).DA-T	Discharge Air Temperature
AI	VAV-X(RM 111).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-Y(RM 109.CD-O	Cold Deck Damper Output
MO	VAV-Y(RM 109.OCC-C	Occupied Command
MO	VAV-Y(RM 109.BOX-MODE	Vav Box Mode
AI	VAV-Y(RM 109.CDFLOW	Cold Deck Flow
AO	VAV-Y(RM 109.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-Y(RM 109.HDFLOW	Hot Deck Flow
AO	VAV-Y(RM 109.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-Y(RM 109.HD-O	Hot Deck Damper Output
AI	VAV-Y(RM 109.ZN-T	Zone Temperature
AI	VAV-Y(RM 109.DA-T	Discharge Air Temperature
AI	VAV-Y(RM 109.ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-Z(RM 104).CD-O	Cold Deck Damper Output
MO	VAV-Z(RM 104).OCC-C	Occupied Command
MO	VAV-Z(RM 104).BOX-MODE	Vav Box Mode
AI	VAV-Z(RM 104).CDFLOW	Cold Deck Flow
AO	VAV-Z(RM 104).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-Z(RM 104).HDFLOW	Hot Deck Flow
AO	VAV-Z(RM 104).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-Z(RM 104).HD-O	Hot Deck Damper Output
AI	VAV-Z(RM 104).ZN-T	Zone Temperature
AI	VAV-Z(RM 104).DA-T	Discharge Air Temperature
AI	VAV-Z(RM 104).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-AA(RM 100).CD-O	Cold Deck Damper Output
MO	VAV-AA(RM 100).OCC-C	Occupied Command
MO	VAV-AA(RM 100).BOX-MODE	Vav Box Mode
AI	VAV-AA(RM 100).CDFLOW	Cold Deck Flow
AO	VAV-AA(RM 100).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-AA(RM 100).HDFLOW	Hot Deck Flow
AO	VAV-AA(RM 100).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-AA(RM 100).HD-O	Hot Deck Damper Output
AI	VAV-AA(RM 100).ZN-T	Zone Temperature

DRAFT

Yorktown Clinic		
AI	VAV-AA(RM 100).DA-T	Discharge Air Temperature
AI	VAV-AA(RM 100).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-BB(RM 213.CD-O	Cold Deck Damper Output
MO	VAV-BB(RM 213.OCC-C	Occupied Command
MO	VAV-BB(RM 213.BOX-MODE	Vav Box Mode
AI	VAV-BB(RM 213.CDFLOW	Cold Deck Flow
AO	VAV-BB(RM 213.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-BB(RM 213.HDFLOW	Hot Deck Flow
AO	VAV-BB(RM 213.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-BB(RM 213.HD-O	Hot Deck Damper Output
AI	VAV-BB(RM 213.ZN-T	Zone Temperature
AI	VAV-BB(RM 213.DA-T	Discharge Air Temperature
AI	VAV-BB(RM 213.ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-CC(RM 212).CD-O	Cold Deck Damper Output
MO	VAV-CC(RM 212).OCC-C	Occupied Command
MO	VAV-CC(RM 212).BOX-MODE	Vav Box Mode
AI	VAV-CC(RM 212).CDFLOW	Cold Deck Flow
AO	VAV-CC(RM 212).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-CC(RM 212).HDFLOW	Hot Deck Flow
AO	VAV-CC(RM 212).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-CC(RM 212).HD-O	Hot Deck Damper Output
AI	VAV-CC(RM 212).ZN-T	Zone Temperature
AI	VAV-CC(RM 212).DA-T	Discharge Air Temperature
AI	VAV-CC(RM 212).ZNT-SP	Zone Temp Setpoint
AI	BLDG1806VAV-CC9(RM212) W-C Adjst	Warm/Cool Adjust
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-DD(RM 211).CD-O	Cold Deck Damper Output
MO	VAV-DD(RM 211).OCC-C	Occupied Command
MO	VAV-DD(RM 211).BOX-MODE	Vav Box Mode
AI	VAV-DD(RM 211).CDFLOW	Cold Deck Flow
AO	VAV-DD(RM 211).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-DD(RM 211).HDFLOW	Hot Deck Flow
AO	VAV-DD(RM 211).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-DD(RM 211).HD-O	Hot Deck Damper Output
AI	VAV-DD(RM 211).ZN-T	Zone Temperature
AI	VAV-DD(RM 211).DA-T	Discharge Air Temperature
AI	VAV-DD(RM 211).ZNT-SP	Zone Temp Setpoint
AI	BLDG1806VAV-DD(RM 211) W-C Adjst	Warm/Cool Adjust

DRAFT

Yorktown Clinic		
AO	WC-ADJ	Warmer Cooler Adjust
BI	Autocal Enable	Autocal Enable
BI	Autocal Active	Autocal Active
BI	Starved Cold Deck	Starved Cold Deck
BI	Starved Hot Deck	Starved Hot Deck
AI	VAV-EE(RM 209).CD-O	Cold Deck Damper Output
MO	VAV-EE(RM 209).OCC-C	Occupied Command
MO	VAV-EE(RM 209).BOX-MODE	Vav Box Mode
AI	VAV-EE(RM 209).CDFLOW	Cold Deck Flow
AO	VAV-EE(RM 209).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-EE(RM 209).HDFLOW	Hot Deck Flow
AO	VAV-EE(RM 209).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-EE(RM 209).HD-O	Hot Deck Damper Output
AI	VAV-EE(RM 209).ZN-T	Zone Temperature
AI	VAV-EE(RM 209).ZNT-SP	Zone Temperature Setpoint
AI	VAV-EE(RM 209).DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-FF(BloodWorks Waiting Room).CD-O	Cold Deck Damper Output
MO	VAV-FF(BloodWorks Waiting Room).OCC-C	Occupied Command
MO	VAV-FF(BloodWorks Waiting Room).BOX-MODE	Vav Box Mode
AI	VAV-FF(BloodWorks Waiting Room).CDFLOW	Cold Deck Flow
AO	VAV-FF(BloodWorks Waiting Room).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-FF(BloodWorks Waiting Room).HDFLOW	Hot Deck Flow
AO	VAV-FF(BloodWorks Waiting Room).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-FF(BloodWorks Waiting Room).HD-O	Hot Deck Damper Output
AI	VAV-FF(BloodWorks Waiting Room).ZN-T	Zone Temperature
AI	VAV-FF(BloodWorks Waiting Room).DA-T	Discharge Air Temperature
AI	VAV-FF(BloodWorks Waiting Room).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-GG(BloodWorks Waiting Room.CD-O	Cold Deck Damper Output

DRAFT

Yorktown Clinic		
MO	VAV-GG(BloodWorks Waiting Room.OCC-C	Occupied Command
MO	VAV-GG(BloodWorks Waiting Room.BOX-MODE	Vav Box Mode
AI	VAV-GG(BloodWorks Waiting Room.CDFLOW	Cold Deck Flow
AO	VAV-GG(BloodWorks Waiting Room.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-GG(BloodWorks Waiting Room.HDFLOW	Hot Deck Flow
AO	VAV-GG(BloodWorks Waiting Room.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-GG(BloodWorks Waiting Room.HD-O	Hot Deck Damper Output
AI	VAV-GG(BloodWorks Waiting Room.ZN-T	Zone Temperature
AI	VAV-GG(BloodWorks Waiting Room.ZNT-SP	Zone Temperature Setpoint
AI	VAV-GG(BloodWorks Waiting Room.DA-T	Discharge Air Temperature
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-HH(RM 304).CD-O	Cold Deck Damper Output
MO	VAV-HH(RM 304).OCC-C	Occupied Command
MO	VAV-HH(RM 304).BOX-MODE	Vav Box Mode
AI	VAV-HH(RM 304).CDFLOW	Cold Deck Flow
AO	VAV-HH(RM 304).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-HH(RM 304).HDFLOW	Hot Deck Flow
AO	VAV-HH(RM 304).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-HH(RM 304).HD-O	Hot Deck Damper Output
AI	VAV-HH(RM 304).ZN-T	Zone Temperature
AI	VAV-HH(RM 304).DA-T	Discharge Air Temperature
AI	VAV-HH(RM 304).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-II(RM 403).CD-O	Cold Deck Damper Output
MO	VAV-II(RM 403).OCC-C	Occupied Command
MO	VAV-II(RM 403).BOX-MODE	Vav Box Mode
AI	VAV-II(RM 403).CDFLOW	Cold Deck Flow
AO	VAV-II(RM 403).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-II(RM 403).HDFLOW	Hot Deck Flow
AO	VAV-II(RM 403).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-II(RM 403).HD-O	Hot Deck Damper Output
AI	VAV-II(RM 403).ZN-T	Zone Temperature
AI	VAV-II(RM 403).DA-T	Discharge Air Temperature

DRAFT

Yorktown Clinic		
AI	VAV-II(RM 403).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-JJ(RM 125E).CD-O	Cold Deck Damper Output
MO	VAV-JJ(RM 125E).OCC-C	Occupied Command
MO	VAV-JJ(RM 125E).BOX-MODE	Vav Box Mode
AI	VAV-JJ(RM 125E).CDFLOW	Cold Deck Flow
AO	VAV-JJ(RM 125E).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-JJ(RM 125E).HDFLOW	Hot Deck Flow
AO	VAV-JJ(RM 125E).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-JJ(RM 125E).HD-O	Hot Deck Damper Output
AI	VAV-JJ(RM 125E).ZN-T	Zone Temperature
AI	VAV-JJ(RM 125E).DA-T	Discharge Air Temperature
AI	VAV-JJ(RM 125E).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-KK(RM 125.CD-O	Cold Deck Damper Output
MO	VAV-KK(RM 125.OCC-C	Occupied Command
MO	VAV-KK(RM 125.BOX-MODE	Vav Box Mode
AI	VAV-KK(RM 125.CDFLOW	Cold Deck Flow
AO	VAV-KK(RM 125.CDF-SP	Cold Deck Flow Setpoint
AI	VAV-KK(RM 125.HDFLOW	Hot Deck Flow
AO	VAV-KK(RM 125.HDF-SP	Hot Deck Flow Setpoint
AI	VAV-KK(RM 125.HD-O	Hot Deck Damper Output
AI	VAV-KK(RM 125.ZN-T	Zone Temperature
AI	VAV-KK(RM 125.DA-T	Discharge Air Temperature
AI	VAV-KK(RM 125.ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-LL(RM 125).CD-O	Cold Deck Damper Output
MO	VAV-LL(RM 125).OCC-C	Occupied Command
MO	VAV-LL(RM 125).BOX-MODE	Vav Box Mode
AI	VAV-LL(RM 125).CDFLOW	Cold Deck Flow
AO	VAV-LL(RM 125).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-LL(RM 125).HDFLOW	Hot Deck Flow
AO	VAV-LL(RM 125).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-LL(RM 125).HD-O	Hot Deck Damper Output
AI	VAV-LL(RM 125).ZN-T	Zone Temperature
AI	VAV-LL(RM 125).DA-T	Discharge Air Temperature
AI	VAV-LL(RM 125).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-MM(RM 125A).CD-O	Cold Deck Damper Output
MO	VAV-MM(RM 125A).OCC-C	Occupied Command
MO	VAV-MM(RM 125A).BOX-MODE	Vav Box Mode
AI	VAV-MM(RM 125A).CDFLOW	Cold Deck Flow

DRAFT

Yorktown Clinic		
AO	VAV-MM(RM 125A).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-MM(RM 125A).HDFLOW	Hot Deck Flow
AO	VAV-MM(RM 125A).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-MM(RM 125A).HD-O	Hot Deck Damper Output
AI	VAV-MM(RM 125A).ZN-T	Zone Temperature
AI	VAV-MM(RM 125A).DA-T	Discharge Air Temperature
AI	VAV-MM(RM 125A).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
AI	VAV-A(407 Supply).CD-O	Cold Deck Damper Output
MO	VAV-A(407 Supply).OCC-C	Occupied Command
MO	VAV-A(407 Supply).BOX-MODE	Vav Box Mode
AI	VAV-A(407 Supply).CDFLOW	Cold Deck Flow
AO	VAV-A(407 Supply).CDF-SP	Cold Deck Flow Setpoint
AI	VAV-A(407 Supply).HDFLOW	Hot Deck Flow
AO	VAV-A(407 Supply).HDF-SP	Hot Deck Flow Setpoint
AI	VAV-A(407 Supply).HD-O	Hot Deck Damper Output
AI	VAV-A(407 Supply).ZN-T	Zone Temperature
AI	VAV-A(407 Supply).DA-T	Discharge Air Temperature
AI	VAV-A(407 Supply).ZNT-SP	Zone Temp Setpoint
AO	WC-ADJ	Warmer Cooler Adjust
NH - 95	Equipment	Quanity
NH - 95	Digital Controls Thermostats	432
NH - 95	JCI, ASC, DX – 9100 Controller	18
NH - 95	JCI ASC, UNT Controller	25
NH - 95	JCI ASC, VMA Controller	424
NH - 95	JCI Point, Control Loop Tune	12
NH - 95	JCI Suervisory Control, NAE	1
NH - 95	JCI Suervisory NCM 300	8
NH - 95	Variable Drive VFD 15 HP	23

DRAFT

Pnuematic controls	
Building 3	
Equipment Description	Quanity
Pneumatic Valve Actautaors	70
Pneumatic E/P'S Switches	120
Pneumatic Damper Actuators	50
Pneumatic Duplex Air Compressor	3
Pneumatic Air Dryer	3
Dam Neck Building 504	
Equipment Description	Quanity
Pneumatic Valve Actautaors	12
Pneumatic Receiving /Controllers	9
Pneumatic Transmitters	16
Pneumatic E/P'S Switches	10
Pneumatic Damper Actuators	28
Pneumatic Room Thermostat	17
Pneumatic Duplex Air Compressor	1
Pneumatic Air Dryer	1
Sewells point NH - 95	
Equipment Description	Quanity
Valve Actuator	40
Air Switching Vavle	11
Control valve ½ - 2 steam	27
Pneumatic Room Thermostat	2
Pneumatic Duplex Air Compressor	8
Pneumatic Air Dryer	8
Sewells point NH - 94	
Equipment Description	Quanity
Danper Actuator	25
Air Switching Vavle	4
Receiver Controller	2
Pneumatic Room Thermostat	11
Pneumatic Duplex Air Compressor	8
Pneumatic Air Dryer	2
(INTENTIOINLY LEFT BLANK) **(END OF INVENTORY)**	

DRAFT

Portsmouth Naval Hospital data points on METASYS

Metasys PMI (Old Format):

Bldg. 1
2056 data points

Bldg. 2
11350 data points

Bldg. 104
725 data points

Bldg. 3
8630 data points

Bldg. 250
236 data points

Bldg. 273
233 data points

Bldg. 274
645 data points

Bldg. 276
175 data points

Bldg. 282
600 data points

Bldg. 288
1348 data points

Metasys Extended Architecture (New Format):

Bldg. 249
347 data points

Norfolk Naval Shipyard Clinic
320 data points

Boone Clinic
1489 data points

Bldg. 272
105 data points

Yorktown Naval Weapons Station
565 data points

DRAFT

Oceana Clinic
833 data points

Bldg. 1 Command Center
28 data points

Sewell's Point CD-2
2923 data points

Sewell's Point NH-94

Sewell's Point NH-95

Bldg. 3
9th Floor:
460 data points

8th Floor:
880 data points

7th Floor:
Not connected yet. Estimated 1000 data points.

VFDs (5) pumps

Building 282
VFDs (7) fan motors

DRAFT

ATTACHMENT J-1502000-06
Life Safety tested Air handlers

Air Handler	Location
12.01	MER 12 ROOM 122101
13.01	MER 13 ROOM 134250
13.02	MER 13 ROOM 134250
13.03	MER 13 ROOM 134250
14.01	MER 14 ROOM 142601
15.01	MER 15 ROOM 150521
18	MER 13 ROOM 170101
21.01	MER 21 ROOM 210321
21.02	MER 21 ROOM 210321
22.01	MER 22 ROOM 222702
22.02	MER 22 ROOM 222702
23.01	MER 23 ROOM 230221
23.02	MER 23 ROOM 230221
24.01	MER 24 ROOM 242901
25.01	MER 25 ROOM 252001
28.01	MER 28 ROOM 270301
29.01	2ND FLOOR ROOF FROM MER 21 ROOM 210321
32.01	MER 32 ROOM 323402
32.02	MER 32 ROOM 323402
33.01	MER 33 ROOM 333201 ACCESSED FROM MER 23 ROOM230221
33.02	MER 33 ROOM 333201 ACCESSED FROM MER 23 ROOM230221
33.03	MER 33 ROOM 333201 ACCESSED FROM MER 23 ROOM230221
33.04	MER 33 ROOM 333201 ACCESSED FROM MER 23 ROOM230221
36.01	MER 36 ROOM 360601
36.02	MER 36 ROOM 360601
36.03	MER 36 ROOM 360601
36.04	MER 36 ROOM 360601
36.05	MER 36 ROOM 360601
37.01	MER 37 ROOM 360301
37.02	MER 37 ROOM 360301
37.03	MER 37 ROOM 360301
37.04	MER 37 ROOM 360301
37.05	MER 37 ROOM 360301
52	MER 52 ROOM 520000
54.01	MER 54 ROOM 540000
55.01	MER 55 ROOM 550000
55.02	MER 55 ROOM 550000
58	MER 58 ROOM 570000
63.01	MER 63 ROOM 630000
63.02	MER 63 ROOM 630000

DRAFT

ATTACHMENT J-1502000-07
Life Safety test Check list

Life Safety Testing

AHU #

SMOKE CONTAINMENT MODE

√ 1. Simulate a Smoke alarm by jumping AUTO relay in Fire Alarm Panel.
√ 2. Verify the Supply fan turns OFF.
√ 3. Verify the Return fan continues to RUN.
√ 4. Verify the Outside and Relief dampers go to 100% OPEN.
√ 5. Verify the Return damper closes to 0%.
√ 6. Verify the Supply smoke dampers close after a time delay.
√ 7. Verify the Return Smoke dampers stay OPEN.
√ 8. Verify the heating valve is 100% OPEN.
√ 9. Verify the heating Pump is ON.
√ 10. Verify all interlocked Exhaust Fans are ON.

SMOKE PURGE

√ 1. Place Fire Fighter panel into Purge. (Auto relay is also jumped).
√ 2. Verify the Supply and Return Smoke dampers OPEN.
√ 3. Verify the Supply fan comes back ON.
√ 4. Verify the Return fan comes back ON.
√ 5. Verify the Outside and relief dampers are OPEN to 100%.
√ 6. Verify the Return damper is CLOSED.
√ 7. Verify the heating valve is OPEN to 100%.
√ 8. Verify the heating pump is ON.
√ 9.Verify all interlocked E_ Fans are ON.
√ 10. Test low limit stat TS-1.
√ 11.Verify nothing changes.
√ 12. Verify the Supply and Return fans are ON.
√ 13. Verify the Outside and relief dampers are OPEN to 100%.
√ 14. Verify the Return damper is CLOSED.
√ 15. Verify the heating valve is OPEN to 100%.
√ 16. Verify the heating pump is ON.
√ 17. Verify all interlocked E_ Fans are ON.
√ 18. Turn the AHU OFF thru the DDC AUTO s/s relay. (Command the Unit OFF thru the DDC Workstation). Verify LED on relay in DDC panel goes out (2 relays-Supply & Return Fan).
√ 19. Verify the Unit continues to RUN.
√ 20. Test low limit stat TS-2.
√ 21. Verify nothing changes.
√ 22. Verify the Supply and Return fans are ON.
√ 23. Verify the Outside and relief dampers are OPEN to 100%.
√ 24. Verify the Return damper is CLOSED.
√ 25. Verify the heating valve is OPEN to 100%.
√ 26. Verify the heating pump is ON.

DRAFT

Life Safety Testing

AHU #

√ 27. Verify all interlocked E_ Fans are ON.
√ 28. Turn the AHU On thru the DDC AUTO s/s relay. (Command the Unit ON thru the DDC Workstation.) Verify LED on relay in DDC panel is lit (2 relays-Supply & Return Fan)
√ 29. Verify the Unit continues to RUN.
√ 30. Reset TS-1 and TS-2.

AHU #

SUPPLY SMOKE DETECTOR SHUTDOWN

Detector #M2-102 used.

√ 1. Test the Air Handler's main Supply Duct detector. (Auto relay and Purge relay are still jumped.
√ 2. Verify the Supply fan is OFF.
√ 3. Verify the Return fan is ON.
√ 4. Verify the Outside and relief dampers are OPEN to 100%.
√ 5. Verify the Return damper is CLOSED.
√ 6. Verify the heating valve is OPEN to 100%.
√ 7. Verify the heating pump is ON.
√ 8. Verify all interlocked Exhaust Fans are ON.
√ 9. Verify the Supply smoke dampers CLOSE.
√ 10. Remove the Smoke Detector Alarm jumper.
√ 11. Verify the Supply and Return Smoke dampers OPEN.
√ 12. Verify the Supply fan Starts.
√ 13. Verify the Return fan Starts.
√ 14. Remove Purge.

SYSTEM SHUTDOWN FROM FIRE PANEL WHILE IN SMOKE CONTAINMENT MODE

√ 1. Place the Fire Fighter Panel into Shutdown by jumping shutdown relay in Fire Alarm Panel. (Auto relay is still jumped.)
√ 2. Verify the Supply and Return fans turn OFF.
√ 3. Verify the Outside and Relief air dampers go to their normally closed positions.
√ 4. Verify the Return damper goes to its normally open position.
X 5. Verify the Return Smoke dampers go CLOSED after a short time delay.
√ 6. Verify the Supply Smoke dampers go CLOSED after a time delay.
√ 7. Verify all interlocked E_ Fans turn OFF.
√ 8. Remove the Shutdown relay and Auto relay jumpers.
√ 9. Verify the Supply and Return Smoke dampers OPEN.
√ 10. Verify the Supply fan Starts.
√ 11. Verify the Return fan Starts.

DRAFT

ATTACHMENT J-1502000-08
Smoke Damper Listing

AHU NUMBER	SUPPLY SMOKE DAMPER (78 total)	RETURN SMOKE DAMPER (76 total)
NON-CRIT AHU 1201	805104	805461
	805106	805462
	805460	805463
	805102	
NON-CRIT AHU 1301	805464	805465
	805108	805466
	805107	
NON-CRIT AHU 1302	805467	805469
	805468	805470
	805112	805472
NON-CRIT AHU 1401	805118	805119
	805120	805117
	805121	805116
	805122	805471
		805115
CRIT AHU 1501	803908	803909
	805452	805451
CRIT AHU 1801	804383	
	805459	
NON-CRIT AHU 2101	804397	804398
	805473	
NON-CRIT AHU 2102	805499	805502
	805500	805503
	805501	805504

DRAFT

AHU NUMBER	SUPPLY SMOKE DAMPER (78 total)	RETURN SMOKE DAMPER (76 total)
CRIT AHU 2201	805454	805453
	805455	805457
	805456	805458
CRIT AHU 2202	805157	805156
NON-CRIT AHU 2301	805135	805130
	805134	805132
NON-CRIT AHU 2302	805129	805476
	805474	805125
	805475	803918
CRIT AHU 2401	803927	803928
	805438	805439
NON-CRIT AHU 2501	805480	805477
	805481	805478
	805482	805479
NON-CRIT AHU 2801	805506	805484
	805483	
	804384	
NON-CRIT AHU 2901	802944	802942
	805505	802943
CRIT AHU 3201	805423	805424
CRIT AHU 3202	805425	805155
CRIT AHU 3301	805432	805433
		805434
CRIT AHU 3302	803944	803943

DRAFT

AHU NUMBER	SUPPLY SMOKE DAMPER (78 total)	RETURN SMOKE DAMPER (76 total)
CRIT AHU 3303	803945	803946
CRIT AHU 3304	803948	805437
CRIT AHU 3305	805435	805436
CRIT AHU 3601	805427	805426
	805428	805429
CRIT AHU 3602	803962	805430
	803961	805431
NON-CRIT AHU 3603	803933	803932
	805401	805402
NON-CRIT AHU 3604	805485	805486
CRIT AHU 3605		
CRIT AHU 3701	805493	805494
CRIT AHU 3702	805496	805495
CRIT AHU 3703	805403	805405
	805404	805406
CRIT AHU 3704	805407	805408
CRIT AHU 5201	805409	805410

DRAFT

AHU NUMBER	SUPPLY SMOKE DAMPER (78 total)	RETURN SMOKE DAMPER (76 total)
	805411	805413
	805412	
CRIT AHU 5401	802623	805414
	805417	802626
	805419	805415
	805418	805420
	803950	805421
		805422
CRIT AHU 5501	805442	805441
	803952	805440
		803951
		805443
CRIT AHU 5801	805444	805447
	805445	805448
	805446	805449
		805450
NON-CRIT AHU 6301	805487	805488
NON-CRIT AHU 6302	805489	805490
	805491	805492
	805497	805498

DRAFT