

1503030 – Integrated Solid Waste Management Table of Contents

Spec Item	Title
1	General Information
1.1	Concept of Operations
2	Management and Administration
2.1	Definitions and Acronyms
2.1.1	Wood Debris
2.1.2	Yard Waste Debris
2.2	Personnel
2.2.1	Certification, Training, and Licensing
2.3	Special Requirements
2.3.1	Workmanship and Material Standards
2.3.2	Recyclable Accounting
2.3.3	Weight Tickets (Non-Recyclable)
2.4	References and Technical Documents
3	Not used.
4	IDIQ Work
4.1	Wood Grinding Operations
4.2	Yard Waste Grinding Operations

1503030 – Integrated Solid Waste Management		
Spec Item	Title	Description
1	General Information	The Contractor shall provide all labor, management, supervision, tools, material, and equipment required to perform wood and yard waste grinding in support of landfill operations at Marine Corps Base, Camp Lejeune.
1.1	Concept of Operations	The Contractor shall perform wood grinding and yard waste services at Base Sanitary Landfill. The contractor shall grind piles of wood debris such as tree limbs, stumps, logs, pallets, plywood, dimensional lumber, and other wood debris and haul chips off base for disposal.

1503030 – Integrated Solid Waste Management Table of Contents

Spec Item	Title	Description
2	Management and Administration	
2.1	Definitions and Acronyms	
2.1.1	Wood Debris	Green tree debris such as tree limbs, stumps, logs, and limbs; dry wood waste such as lumber, pallets, plywood, and dimensional lumber.
2.1.2	Yard Waste Debris	Yard debris such as leaves, pine straw, yard clippings, and small limbs
2.2	Personnel	
2.2.1	Certification, Training, and Licensing	The contractor shall have all licenses, certifications and permits required by state and Federal laws and regulations to accomplish the services described in the contract. All work performed shall be in accordance with Federal, state, and local laws, and installation regulations. Proof of certification shall be provided to the KO 15 days prior to the start of work.
2.3	Special Requirements	
2.3.1	Workmanship and Material Standards	Best commercial practices shall be applied in the performance of work. All work shall be completed per approved and accepted industry and equipment manufacturers' standards and shall comply with building and safety codes, applicable activity, local, state, and federal regulations, and other technical requirements identified within this technical sub-annex. Repairs shall be made in accordance with the manufacturers' specifications and guidelines, and standard building codes. The quality of repairs shall meet the applicable standards and shall prevent any malfunction reoccurrences caused by poor workmanship or other contractor inadequacies. Contractor shall provide replacement of any/all equipment listed in para 2.5.1 within three working days of equipment failure. The Contractor shall not allow debris to accumulate in the work area. All such debris, excess material, and parts shall be cleaned up and removed at the completion of the job and at the end of each day work is in progress. Upon completion of work, any stains and other unsightly marks shall be removed.
2.3.2	Recyclable Accounting	The Contractor shall submit receipts denoting the date, type and quantity of material recycled, and receipts of revenue generated by sale of recyclable materials with the Contractor's monthly invoice.
2.3.3	Weight Tickets	Weight tickets are required if trucks are weighed off base due to the base scales being closed. Include tonnage of each truck and submit weight tickets to the Base Landfill. The Contractor shall also provide the total tonnage weighed during the month on their monthly invoice.
2.4	References and Technical Documents	References and Technical Documents are listed in J-0200000-02.

1503030 – Integrated Solid Waste Management Table of Contents

Spec Item	Title	Performance Objective	Related Information	Performance Standard
3	FFP Work	Not used.		

1503030 – Integrated Solid Waste Management Table of Contents

Spec Item	Title	Performance Objective	Related Information	Performance Standard
4	IDIQ Work	IDIQ work may be ordered utilizing DoD EMALL in accordance with Section H or on a task order in accordance with the PROCEDURES FOR ISSUING ORDERS clause in Section G. The order will specify the exact locations and types of work to be accomplished. The period of performance will be specified in each order.	Refer to IDIQ ELINs for task listings, descriptions, and related requirements. All periods of performance are measured from issue date of order to acceptance of the work.	

4.1	Wood Grinding Operations	<p>The contractor shall grind piles of wood debris identified during a site inspection with the Landfill Manager, to include but not limited to plant growth such as tree limbs, stumps, logs, pallets, plywood, dimensional lumber, and various other wood debris. Activities will include, but are not limited to, grinder operation, land clearing of waste, and hauling chips off site.</p> <p>Of the total tonnage, at least 75% shall be processed wood chips. No more than 25% shall be screened dirt from the tree debris and that the dirt must be hauled to the Camp Lejeune Landfill for daily cover. The contractor shall not be paid for any screened dirt in excess of 25% of the total tonnage. Excess dirt shall be piled at work site. The landfill manager can change the ratio of wood chips to screened dirt if the contractor presents evidence that wood chip market conditions warrant it.</p> <p>The wood chips become the property of the Contractor and shall be hauled off base for disposal. Revenue receipts from the sale of the wood chips shall be submitted with the monthly invoice.</p> <p>Each truck hauling debris shall be weighed empty and full at the base sanitary landfill scales. Weight tickets will be kept and maintained by the government.</p> <p>Contractors must operate in a manner that soil erosion and run-off are controlled as well as keeping dust from becoming a hazard and must minimize airborne emissions.</p> <p>If any material is hauled away after the landfill scales close for the day, a weight ticket for each load is required to be turned in to the Landfill Office or</p>	<p>The Government will contact the contractor when a minimum of 5,000 tons of wood debris and yard waste are on site to be ground. The Government will direct the Contractor to the debris on the ground. The Contractor may have to mobilize and demobilize several times over the course of the year. Once the Contractor mobilizes, the work shall proceed diligently to completion.</p> <p>Once work has been started, work will continue full time until all work is complete. If a work day falls on an observed holiday, work shall be performed on the following work day.</p> <p>All contaminated materials, i.e., metals, concrete, bricks, dirt, fencing, etc. will be separated and disposed of by the contractor either off base or in a designated area confirmed by the Landfill Manager.</p> <p>The dirt in the wood debris can be screened as clean and fine as possible and disposed of off base or in the Camp Lejeune Landfill as daily cover, per the Landfill Manager's instructions.</p> <p>The Government will not be held liable, under any condition, for incidental matters occurring during transportation of said</p>	<p>All wood chips are ground and disposed of within the time limit on the task order.</p> <p>The Contractor shall grind and ship 5,500 tons of processed wood each month.</p>
-----	--------------------------	---	--	--

1503030 – Integrated Solid Waste Management Table of Contents				
Spec Item	Title	Performance Objective	Related Information	Performance Standard
		<p>the FSC Representative. All outbound weight must be captured for recycling credit.</p> <p>After all processed materials are removed from the working area, the area shall be returned to a condition that allows vehicles to access the area and storm water to run off and not pond on the facility.</p>	<p>debris on or off base.</p> <p>The Contractor shall ensure that any equipment downtime is limited to a maximum of 3 days.</p> <p>Specific equipment specifications are listed in paragraph 2.5.1 of Annex 0200000.</p>	
4.2	Yard Waste Grinding Operations	<p>The contractor shall grind piles of yard waste identified during a site inspection with the Landfill Manager, to include but not limited to leaves, pine straw, yard clippings, small limbs, and various other yard debris.</p> <p>Activities will include grinder operation. Yard waste shall be ground on site and remain at that location for government use.</p> <p>After all grinding is completed, the area shall be returned to a condition that allows vehicles to access the area and storm water to run off and not pond on the facility.</p> <p>Contractors must operate in a manner that soil erosion and run-off are controlled as well as keeping dust from becoming a hazard and must minimize airborne emissions.</p>	<p>The Government will contact the contractor when a minimum of 5,000 tons of wood debris and yard waste are on site to be ground.</p> <p>Once work has been started, work will continue full time until all work is complete. If a work day falls on an observed holiday, work shall be performed on the following work day.</p> <p>All contaminated materials, i.e., metals, concrete, bricks, dirt, fencing, etc. will be separated and disposed of by the contractor either off base or in a designated area confirmed by the Landfill Manager.</p> <p>Contaminated materials shall be disposed of by the contractor either off base or in a designated area confirmed by the Landfill Manager.</p> <p>The Contractor shall ensure that any equipment downtime is limited to a maximum of 3 days.</p>	All yard waste is ground within the time limit on the task order.