



**DEPARTMENT OF THE NAVY**  
NAVAL FACILITIES ENGINEERING COMMAND, MID ATLANTIC  
PUBLIC WORKS DEPARTMENT, NAVAL STATION NEWPORT  
ONE SIMONPIETRI DRIVE  
NEWPORT, RHODE ISLAND 02841-1711

### **AMENDMENT 01**

Date: 28 July 2015

eProject Number: 1386816  
B1171 NUWC Replace Roof

From: Bethany Collard  
Project Manager  
Naval Station Newport

Sheet 3 of 8 Roof Demolition Details, #4, Demolition Roof Scuttle, the note states "Exist. Steel roof scuttle to remain. Clean exterior of all asphalt & adhesives & paint with latex base paint" This will be changed to remove and dispose of existing roof scuttles and associated curbs/hardware. Provide and Install new in-kind roof scuttles, associated curbing and hardware, to fit within the existing openings. Typical in two locations, one located on Roof Section "A" - 3 Story Office Tower and one on Roof Section "C" - High Bay.