

Statement of Work for Materials and Labor to renovate Wardroom onboard

USS ARLEIGH BURKE (DDG 51)

The Officer's Wardroom onboard USS ARLEIGH BURKE is in need of renovation and the project outlined is in line with the Commanding Officer's strategy for the enhancement of living spaces. Workmanship will be of standard quality and the design and layout of the project is described below. Work required must be complete no later than 01 July 2015. If proposing an alternate timeframe for completion, please state the time for completion.

The required work includes the following:

Wardroom:

- 1. WALL COVERING:** Contractor shall remove existing wall covering, prep bulkhead by removing 2" trim strips and securing panels with counter sink pop rivets and flush seams to create a smooth and continuous surface for the new vinyl wall covering and wainscoting underneath. Contractor shall provide/install amount of wall covering and wainscoting for entire wardroom. Wall covering shall be an eggshell/beige color, and wainscoting shall be lacquered wood colored similar to antique cherry, but final color will be chosen by ship's representative. Remove and install new bulkhead lights & light switches (design to be chosen by ship's representative).
- 2. COFFEE & SIDEBOARD UNITS:** Contractor shall remove existing coffee mess and replace with 25"x 50" granite top w/ 4" back splash, (2) drawer and cabinet units. All sideboard units will be the same color and matching style as wainscoting. Contractor shall provide/install sheet metal facade to conceal and secure wiring and piping. Contractor will provide and install a stainless steel microwave unit above coffee mess. Contractor shall remove existing sideboard units and provide/install three (3) drawer style sideboard units and three (3) drawer/cabinet combination style sideboard units. Units shall be similar to shipboard furniture catalog # B-4A-1. All units shall have new granite tops and 4" back splash. Granite color will be chosen from available options, but will be dark tan, with flecks/streaks of black and brown. One unit shall be used as a buffet and the other shall be used for a salad bar w/ sneeze shield. Drawer fronts shall be covered in laminate. Tops shall be comprised of (1) piece.
- 3. AIR CON. DOORS:** Doors shall be laminated on the inside of compartment. Color to be the same as sideboard units/wainscoting.
- 4. L-SHAPE SOFA:** Contractor shall remove existing sofas and provide/install one (1) approximately 6' sofa (three man) and one (1) corner section, (1) (one man), and one separate sofa 2 man sofa. Sofas shall be upholstered in Naugahyde Vinyl (Imitation Leather). Color shall be deep blue (the same color as the material covering the table). Behind the L-shape sofa there will be filler with a laminated top and access door for storage.
- 5. END TABLES:** Contractor shall provide/install two end tables (similar to shipboard furniture catalog # B-4C-1, (1) rectangular in shape) and (1) triangular in shape.
- 6. SHADOW BOX /BOOK SHELVES:** Contractor shall provide/install two (2) approximately 24" wide x 36" tall x 6" deep book shelves. Book shelves shall be surfaced in polycarbonate laminate (of the same color as the wainscoting) and shall have glass fronts. Shelves shall include LED lighting on each shelf. Final configuration to be determined by ship's representative prior to installation. In between the book

shelves will be a shadow box with LED lighting for each shelf. Unit will placed in far corner of wardroom behind “L”-shaped couch.

7. **TROPHY CASE:** Contractor shall provide labor and material to new-laminate existing trophy case to match shadow box/wainscoting/book shelves. Case will be mounted flush to the wall, and lower portion shall be removed. Trophy case lights shall be replaced with LED lights and trophy case locks shall be replaced. All keys to locks shall be provided to ship’s representative upon installation.

8. **FIRE PLACE /MANTLE:** Contractor shall provide and install a fireplace and mantle of the same color and material as the sideboard units/wainscoting/book shelves. Fireplace will be provided and mounted to bulkhead by contractor and shall be non-heat producing, electric, and be black in color. Fireplace will be positioned over escape scuttle, but not so as to obstruct access from scuttle. Wood paneling of the same color and type as the sideboard units/wainscoting/book shelves will encompass the fireplace and run from the deck to the overhead. Mantle will be made of before mentioned granite. Contractor shall provide a full length portrait of ARLEIGH BURKE to be placed above mantle, and provide/install LED lighting to illuminate the portrait.

9. **ENTERTAINMENT CENTER CABINET:** Contractor shall remove existing entertainment center and provide/install new entertainment center around existing 60” flat screen television. New entertainment center shall be approximately 88” wide and 16” deep and shall run from deck to bottom of existing TV. Entertainment center shall contain one (1) shadowbox on each side of the TV that runs from the top of the lower unit (underneath TV) to the top of existing TV. Boxes on sides shall have glass fronts, latched doors, and approximately 6” deep shelving. Lower unit shall have cabinet with shelving on both sides and open storage space in center (for various audio and video equipment). Entertainment center cabinet shall be surfaced with laminate, top shall be granite. The color of the laminate shall be the same as sideboard units/wainscoting/book shelves/fireplace. The color of the granite shall the same as found on top of sideboard units/mantle.

10. **COFFEE MUG RACK:** Contractor shall install a coffee mug rack in the area above the door leading to the wardroom galley. Coffee mug rack will be of the same color and material as the sideboard units/wainscoting/book shelves/fireplace and shall securely hold approximately 30 regular sized mugs and extend the entire length of that bulkhead.

11. **WARDROOM GALLEY DOOR:** Contractor shall laminate one side (the side in the wardroom) of the door leading into the wardroom galley with the same material and color as the sideboard units/wainscoting/book shelves/fireplace.

12. **ENTRANCE DOOR:** Contractor shall provide labor and material to re-laminate both sides of entrance door in same color/material as sideboard units/wainscoting/book shelves/fireplace. Contractor shall remove existing window and replace with a 12” diameter circular frosted glass window that has the words “OFFICER’S WARDROOM” etched into the glass. Glass shall not be see through.

13. **DINING TABLE COVER:** Contractor shall provide/install one (1) new 4’ x 14’ vinyl dining table cover. Ship’s crest shall be located in center of table when cover is placed on table. Contractor shall also provide/ install fourteen (14) vinyl dining chair covers. Ship’s crest shall be located on each cover and shall be centered on the back of chair when cover is placed on chair. One (1) dining chair cover shall contain the letters “CO” underneath ship’s crest and the command-at-sea pin embroidered on the front of

the chair cover at the same height as the letters “CO”. One (1) dining chair cover shall contain the letters “XO” underneath ship’s crest. Color shall be deep blue and match the table covering and sofas.

14. **FALSE OVERHEAD:** Contractor shall provide/install new vinyl clad aluminum panels and grid for an area measuring approximately 500 square feet. Contractor shall ensure that all overhead cables are hidden and secured. Retain existing overhead lighting, but re-arrange to more uniform grid.

Method of Payment: LOA

Place of Ship Visit: Naval Station Norfolk, Pier 4

Place of Performance: BAE Systems Norfolk, Pier 3

Government Point of Contact for SHIP Visit:

LT JOSE LOPEZ
SUPPLY OFFICER
USS ARLEIGH BURKE (DDG 51)
Email: suppo@ddg51.navy.mil

* All parties who intend to attend the mandatory site visit – please submit your name and contact information to contracting officer, LT Peter Azubike at peter.u.azubike1@navy.mil