

KHAKI BARBER SHOP (03-84-12-L)

POP: 1 JAN 2016 - 31 MAY 2016

Key Event: CCMA

OSR: LTjg Alex Cooper

BASE MOLDING. Provide and install 40 lineal feet of new, 3" tall base; color and style to be determined by ship's representative prior to installation.

TWO-STATION VANITY WITH STORAGE CABINETS. Remove all existing vanity materials and provide labor and materials to provide/install approx. 14ft of new vanity cabinets along the forward bulkhead, providing three functional barber stations. Each station shall be configured similar to existing and shall be equipped with a tip-out bin, four hooks within the cabinet, electrical outlets within the cabinet (QTY 4, 4-way outlets). Cabinets shall be finished in wood grain laminate; color and style to be determined by ships representative. All doors and drawers shall be overlay in style and shall be fit with an aluminum positive latch mechanism (paddle latches, magnetic catches and ball catches are not acceptable).

SINKS AND COUNTERTOP. Remove existing sinks and countertop and provide labor and materials to provide/install new countertop measuring 14 ft. L x 24" D x 1.25" thick. Countertop shall be stainless steel. Provide labor and materials to provide/install QTY 2 stainless steel, 16" oval sinks and gooseneck style faucet sets. Sink shall be similar to type furnished by ELKAY Mfg. Co. of Oak Brook, ILL. Model No. LLVR-1916, or equal. Configuration shall be similar to existing.

QUICK-ACTION ACCESS PANEL. Provide labor and materials to provide/install a quick-action access panel on the outboard bulkhead, providing access to necessary valve(s). Access panel shall be equipped with doors. Doors shall be overlay in style and shall be fit with an aluminum positive latch mechanism (paddle latches, magnetic catches and ball catches are not acceptable).

VANITY MIRRORS. Provide labor and materials to provide/install 3 each laminated glass mirrors measuring 60" L x 36" T. Mirrors shall have the word "LAMINATED" etched in lower, left corner. Mirrors shall be installed on the forward bulkhead above vanity/countertop. Frames shall be constructed of #4 stainless steel.

VANITY LIGHTING. Remove all existing sconce/vanity lighting and

components. Provide labor and materials to provide/install QTY 3 approximately 48" standard vanity lights (one light above each station); lighting design and placement to be approved by ship representative prior to installation.

DOOR. Remove existing door. Provide labor and materials to provide/install QTY 1 approximately 28"W x 76"H locking door and frame similar to the existing style door. Door shall have a tempered glass panel displaying ships supply logo.

STORAGE CABINET. Provide labor and materials to provide/install QTY 1 L-shaped storage cabinet measuring approximately 42" H x 42" W (each way) x 18"D on the outboard bulkhead opposite the barber stations. The cabinet with doors shall have adjustable shelves. Storage cabinet shall be finished in wood grain laminate; color and style to be determined by ships representative prior to installation. All doors and drawers shall be overlay in style and shall be fit with an aluminum positive latch mechanism (paddle latches, magnetic catches and ball catches are not acceptable).

MAGAZINE RACK. Provide labor and materials to provide/install QTY 1 magazine rack on the forward bulkhead behind the seating area. Magazine rack shall be similar to Navy Shipboard Furniture Catalog Item # B-6B-3.

WAITING AREA. Provide labor and materials to remove all existing seating materials and install approximately 42 square feet of new seating; seating to be finished in wood grain laminate; color and design to be determined by ship's representative upon advisement from contractor's interior designer.

BARBER POLE. Provide labor and materials to hang existing barber pole in the p-way outside of the barber shop.

BARBER CHAIRS. Provide labor and materials to install and test 3 barber chairs. Replace barber chairs with new, shipboard approved chairs, TEI Model 478-115. Ensure minimum distance of 60" from center to center of adjacent chairs.

INTERIOR DESIGN THEME. Provide interior design expertise to decide barbershop theme and design. Provide conceptual drawing and concept boards as required.

NOTES: The installation and construction of flashings, closure plates, shields, and sheathing shall be such that there are no crevices or inaccessible voids which might harbor vermin, food

waste or other extraneous matter. Access shall be provided to all areas requiring cleaning or treating. Corners formed in flashings, closure plates, shields or sheathing shall be rounded. All exposed surfaces shall be easily accessible for cleaning.

All materials provided shall be NAVSEA shipboard approved. All installations shall be in accordance with manufacturer's directions, NAVSEA standards, and Section C Shipboard Regulations. At no additional charge to the Government, the Contractor shall, at the request of the Supply Officer or his designated representative, provide design and/or installation drawings of any/all items being provided and/or installed within the contract resulting from this solicitation.

Upon completion of work, contractor shall obtain sign-off from Supply Officer or his designated representative.