



STATEMENT OF WORK (SOW)  
HABITABILITY PROJECT FOR USS PORT ROYAL CG (73)  
MESSDECK UPGRADE

1. INTRODUCTION

- 1.1 USS PORT ROYAL intends to purchase materials and services to upgrade the MESSDECK.

2. SCOPE

- 2.1 USS PORT ROYAL requires the contractor to upgrade and renovate the MESSDECK, using Military and Federal Specifications materials. USS PORT ROYAL requires the contractor to provide a quote for the labor, materials, delivery, and installation.

3. SPECIFIC TASKS

- 3.1 Contractor shall remove and dispose of existing wall covering and install new vinyl 27 oz. wallpaper in the MESSDECK IAW Fed. Spec: CCC-W-408A, Type II; Area: 1,080 sq.ft. Pattern: White cove plus painting of trims and poles to match. All materials used in fabrication and installation shall meet the fire performance requirements of MIL-STD-1623
- 3.2 Contractor shall remove and dispose of existing wall covering and install new high density plastic laminate IAW Spec: MIL-P-17171, Type IV. Area: 1,380 sq.ft. Pattern: Mambo. All materials used in fabrication and installation shall meet the fire performance requirements of MIL-STD-1623
- 3.3 Contractor shall rearrange/ repair old tables and booths to match new agreed upon layout of Messdecks, remove swivel chairs and deliver and install 42 new fabricated metal swivel bar stools with chrome base and accent in accordance with mil spec, MIL-PRF-32038, and seats shall be covered fire retardant vinyl covering in accordance to commercial item description A-A-59517, Class 4, Condition A. All materials used in fabrication and installation shall meet the fire performance requirements of MIL-STD-1623
- 3.4 Contractor shall deliver and install new fabricated sliding doors for the storage cabinet in accordance with mil spec, MIL-PRF-32038, and shall be covered with Type I high pressure laminate in accordance with mil spec, MIL-P-17171. Size: 79" X 35" Pattern: Mambo. All materials used in fabrication and installation shall meet the fire performance requirements of MIL-STD-1623
- 3.5 Contractor shall reupholster existing MESSDECK benches with vinyl fire retardant covering with 2 tone combination. Color: Navy Blue/ Textured Navy Blue in accordance to commercial item description A-A-59517, Class 4,

Condition A. All materials used in fabrication and installation shall meet the fire performance requirements of MIL-STD-1623

- 3.6 Contractor shall remove and dispose existing Stratica and glue and install new fire retardant deck flooring IAW MIL SPEC ASTM E648 Class 1; ASTM E662 <450 - Area: 1500 sq.ft. IAW MIL-PRF-32170; underlayment: IAW MIL--3135 Type III or IV. Pattern: Spacia - Warm Walnut. All materials used in fabrication and installation shall meet the fire performance requirements of MIL-STD-1623
- 3.7 Contractor shall deliver and install new fabricated long table 16.7' x 30" x 42" with bottom storage and doors in accordance with mil spec, MIL-PRF-32038, and shall be covered with Type I high pressure laminate in accordance with mil spec, MIL-P-17171. Pattern: Mambo. All materials used in fabrication and installation shall meet the fire performance requirements of MIL-STD-1623
- 3.8 Contractor shall fabricated, deliver, and install new MESSDECK table cover to fit fabricated long table with Ship's Crest with vinyl fire retardant covering. Color: Navy Blue in accordance to commercial item description A-A-59517, Class 4, Condition A. All materials used in fabrication and installation shall meet the fire performance requirements of MIL-STD-1623

#### 4. WORK LOCATION

- 4.0 Coordinate renovation and installation schedule with USS PORT ROYAL. TPOC: LT Steve Gubbins - Supply Officer.
- 4.1 Work will be performed onboard USS PORT ROYAL, Pearl Harbor, HI. Base Access shall be coordinated with USS PORT ROYAL TPOC: LT Gubbins.

#### 5. WORK HOURS/SCHEDULE

- 5.1 Regular working hours shall consist of a 10-hour period, between 7:30 am and 5:30 pm, Monday through Sunday, with the option to continue work on Government holiday(s) with approval from the TPOC, LT Gubbins.
- 5.2 Work outside regular working hours requires USS PORT ROYAL; TPOC: LT Gubbins' approval.
- 5.3 Specific work schedule and sequence of work will be coordinated closely with TPOC: LT Gubbins.
- 5.4 Contractor can begin work upon agreed schedule with USS PORT ROYAL.

#### 6. SECURITY REQUIREMENTS

- 6.1 USS PORT ROYAL will be provided a list of personnel associated with the completion of above work by company contracted to complete work. The Contractor shall provide picture ID laminated cards for all Contracted personnel. All Contracted personnel will be required to possess visitor badges while on-site.
- 6.2 USS PORT ROYAL shall provide escorts for Contractors if escorts are required for personnel entering, departing, and working on restricted areas.
- 6.3 Contractor's employees performing services shall comply with all USS PORT ROYAL's rules and regulations applicable to safety, security, and procedures governing site entry and exit. USS PORT ROYAL's Security point of contact is LT. Gubbins.

## 7. POINT OF CONTACT

- 7.1 TPOC (Technical Point of Contact): LT Gubbins, Phone: 808-474-9298, Email: [suppo@cg73.navy.mil](mailto:suppo@cg73.navy.mil).