

Amendment #1 - Itemized List

1. Responses to a total of 56 RFI's.
2. Equipment List for furniture to be salvaged.
3. Revised Construction Drawings
 - a. Building 36 Revised drawings include:
 - i. Removal of second set of paper towel dispenser and trash cans from Men's Restroom MT1A, Women's Restroom WT1A, and Men's Restroom MT1B. See sheets **A-201, A-401, and A-403**.
 - ii. Clarification of signage types throughout floor plan and addition of Note #5 to Signage Specifications located on sheet **IG-101**. Note #5 states, "Provide signage of the same material and size for the Fleet and Family Service Center. Government to provide camera ready logo image."
 - iii. Floor plan backgrounds and electrical outlet locations in the Executive Suite, Room 118, where corrected on sheet **EP-401**. New Work Notes – Note #6 was revised to say, "Provide in-set recessed receptacle at 54" AFF for (2) adjacent wall-mounted TVs. Provide (2) CATV outlets adjacent to power receptacle.
 - iv. Floor plan backgrounds and data port locations in the Executive Suite, Room 118, where corrected on sheets **T-300 and T-303**.
 - b. Building 196 Revised drawings include:
 - i. Receptacles were provided for TVs located in the Kitchens of both Suite 208 and 231. See sheet **E-401**.
4. Specification section **DEMOLITION 02 41 00** – Replaced paragraph under section 3.1.7.5 FURNISHING with:

"Contractor shall provide all supervision, labor, material and equipment to disassemble, transport and dispose of existing furniture, furnishings and workstations according to the (concept/ equipment list) (approximately 160 cubicles) from Building 36 and Building 196.

Government will remove all existing personal belongings and equipment prior to construction. 30-days prior to demolition of office cubicles, contractor shall submit to the Contracting Officer written notification prior to execution of this task. Government shall contact DLA determining if the existing furniture can be donated to other Government agencies or non-profit organizations. All remaining existing furniture and furnishing which are not selected to be salvaged shall dispose off-site to the Defense Logistics Agency (DLA) Disposition Services at Meade, 77 Rock Avenue/P.O. Box 388, Fort Meade, MD 20755-0388. Contractor is responsible to schedule the turn-in disposal visit with DLA within the overall construction schedule. Contractor shall also make reasonable effort to separate the material in kind (metal, wood, glass, etc.) for the disposal of existing furniture."
5. Specification section **SOLID POLYMER (SOLID SURFACING) FABRICATIONS 06 61 16** – Deleted "...in restrooms, and to underside of wall cabinets in kitchenettes..." from 2.3.4 COUNTER TOPS.

6. Specification section **SOLID POLYMER (SOLID SURFACING) FABRICATIONS 06 61 16** – Deleted section 2.3.5 TOILET/SHOWER PARTITION SYSTEM.
7. Specification section **TOILET COMPARTMENTS 10 21 13** – Replaced references to “...solid polyethylene, Finish 5 Basis of Design: Global Partitions polymer HDPE: color: Black...” with “stainless steel”, in 2.3.1 TOILET ENCLOSURES and 2.3.2 URINAL SCREENS.