1. CONTRACT ID CODE	PAGE	OF PAGES
J	1	2

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	PROJECT NO. (If applicable)
0004	9-Oct-2015		

6. ISSUED BY Code OPHA
NAVFAC MID ATLANTIC
HAMPTON ROADS IPT
9324 VIRGINIA AVENUE
NORFOLK, VA 23511

7. ADMINISTERED BY (If other than item 6.) Code

8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)

CODE FACILITY CODE

☒ 9A. AMENDMENT OF SOLICITATION NO.
N40085-15-R-0027

☒ 9B. DATED (SEE ITEM 11)
21-July -2015

☐ 10A. MODIFICATION OF CONTRACT/ORDER NO.

10B. DATED (SEE ITEM 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in item 14. The hour and date specified for receipt of Offers ☐ **is extended** ☒ **is not extended**. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning __ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (if required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS,
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

☐ A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14. ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

☐ B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATION CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103 (b).

☐ C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

☐ D. OTHER: (specify type of modification and authority)

E. IMPORTANT: Contractor ☒ is not ☐ is required to sign this document and return copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

DESIGN-BUILD/DESIGN-BID-BUILD MULTIPLE AWARD CONSTRUCTION CONTRACT (MACC) FOR NAVFAC MID-ATLANTIC'S ENTIRE AREA OF RESPONSIBILITY, NORTH CAROLINA TO MAINE, INCLUDING WEST VIRGINIA

N40085-15-R-0027, P-334, Design-Build LOGSU Two Operations Facility, Joint Expeditionary Base Little Creek-Fort Story, Va. (Work Order #1298159)

The purpose of this amendment is to open discussions and provide additional information as it appears on the following continuation pages.

The due date for revised proposals is Thursday, October 15, 2015 at 2:00 pm local time.

You are required to acknowledge ALL amendments in the price proposal form.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR (Same as Item 8) (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY (Signature of Contracting Officer)	16C. DATE SIGNED

This Amendment is being issued to provide:

- RFP PART 4, SECTION G20 Site Improvements and SECTION G30, Site Civil/Mechanical Utilities by Attachment

End of Amendment

CONTINUATION SHEET FOR AMENDMENT 0004

Change	Change Format
Add PART 4, G20 Site Improvements	PART 4 – PERFORMANCE TECHNICAL SPECIFICATIONS ADD G20 SITE IMPROVEMENTS attached to this amendment.
Add PART 4, G30 Site Civil/Mechanical Utilities	PART 4 – PERFORMANCE TECHNICAL SPECIFICATIONS ADD G30 SITE CIVIL/MECHANICAL UTILITIES attached to this amendment.

---- END OF AMENDMENT ----

SECTION G20

SITE IMPROVEMENTS
06/13

G20 GENERAL

RFP Part 3 including the Engineering System Requirements (ESR) provide project specific requirements. The RFP Part 4, Performance Technical Sections (PTS) provide generalized technical requirements that apply to multiple facility types and include more requirements than are applicable to any one project. Therefore, only the RFP Part 4 requirements that apply to the project and further define the RFP Part 3 project specific requirements are required.

G20 1.1 DESIGN GUIDANCE

Industry standards, codes, and Government standards referenced in the section text that are not found in the Unified Master Reference List (UMRL) in the Construction Criteria Base (CCB) at the Whole Building Design Guide Website, are listed below for basic designation identification. Comply with the required and advisory portions of the current edition of the referenced standard at the time of contract award.

G20 1.1.1 Industry Standards and Codes

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

AMERICAN SOD PRODUCERS ASSOCIATION (ASPA)

NATIONAL FEDERATION OF STATE HIGH SCHOOL ASSOCIATIONS (NF)

U.S CONSUMER PRODUCT SAFETY COMMISSION, PUBLICATION NO. 325

Refer to UMRL for reference designation identification.

G20 1.1.2 Government Standards

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS RR-F-191	Fencing and Wire and Post Metal (and Gates, Chain-link Fence Fabric, and Accessories)

UNIFIED FACILITIES CRITERIA (UFC)

UFC 1-200-01	General Building Requirements(A reference in this PTS section to UFC 1-200-01 requires compliance with the Tri-Service Core UFCs that are listed in UFGS Section 01 33 10.05 20, which includes the following significant UFC(s):UFC 3-201-01, Civil Engineering; UFC 3-201-02, Landscape Architecture; UFC 3-220-01N, Geotechnical Engineering))
UFC 3-250-01FA	Pavement Design for Roads, Streets, Walks, and Open Storage Areas
UFC 3-270-01	Asphalt Maintenance and Repair
UFC 3-270-02	Asphalt Crack Repair
UFC 3-270-03	Concrete Crack and Partial Depth Spall Repair
UFC 3-270-04	Concrete Crack Repair
UFC 3-800-10N	Environmental Engineering for Facility Construction
UFC 4-022-02	Selection and Application of Vehicle Barriers

G20 1.2 QUALITY ASSURANCE

G20 1.2.1 Qualifications of Tree Location Contractor

Contractor is required to be a professional tree moving company holding landscape contractor's license in the state where the work is to be performed and have a minimum ten years of tree relocation experience. Contractor must be a Certified Arborist certified by the International Society of Arboriculture. Arborist shall oversee all tree moving operations during construction.

G20 1.2.2 Qualifications of New Landscape Contractor

Construction company must hold a landscape contractor's license in the state where the work is to be performed and have a minimum five years of landscape construction experience.

G20 1.3 PERFORMANCE VERIFICATION AND ACCEPTANCE TESTING

Compliance with the requirements will be determined by a review of the design and construction submittals and by field inspection. See Section 01 33 10.05 20, *Design Submittal Procedures*, and Section 01 33 00.05 20, *Construction Submittal Procedures*, for additional requirements.

Verify satisfactory performance via Performance Verification, as detailed in this section of the RFP. Verify satisfactory performance also via testing as detailed in the paragraph, Field Quality Control, in applicable UFGS Specification Sections utilized.

G20 1.3.1 Subgrade Preparation Performance Verification

Perform subgrade preparation in accordance with PTS Section G10. If required by the Designer of Record, perform proof rolling. Perform proof rolling in the presence of the Contracting Officer. Rutting or pumping of material is required to be undercut as directed by the Contracting Officer and replaced with satisfactory soil materials as defined in Section G10, *Site Preparation*.

G20 1.3.2 Base Course Performance Verification

G20 1.3.2.1 Aggregate Base Course

a. a. Sampling: ASTM D75/D75M.b. Gradation: ASTM C136.c. Thickness: Confirm in-place compacted thickness. Acceptable tolerances are plus or minus 0.5 inches (13 mm). One test for every 500 square yards (418 square meters); minimum 2 tests.d. Density: ASTM D1556 or ASTM D6938. One field test for every 1000 square yards (836 square meters); minimum 2 tests. ASTM D1557, Method A, B or C; one laboratory test for the project.e. Visual: Surface must be smooth with no ruts.

G20 1.3.2.2 Other Types of Base Courses

For other types of base courses, provide field testing in accordance with the SHS.

G20 1.3.3 Bituminous Concrete Pavement Performance Verification

a. Visual: Finished surface must be uniform in texture and appearance and free of cracks and creases.

b. Sampling: ASTM D979.

c. Job Mix: Determine gradation and bitumen content. One sample for every 400 tons (362,500 kilograms); minimum 1 test.

d. Thickness: ASTM D3549. Confirm in-place compacted thickness. Acceptable tolerances are plus or minus 0.5 inches (13 mm) for bituminous base course and plus or minus 0.25 inches (6 mm) for bituminous surface course. One test for every 500 square yards (418 square meters); minimum 2 tests.

e. Surface Smoothness: Test surface smoothness by using a 10 foot (3 meter) straightedge in transverse and longitudinal directions to pavement. Acceptable tolerances are plus or minus 0.25 inches (6 mm) for bituminous base and surface courses.

f. Density: Conduct field density of in-place compacted pavement in accordance with ASTM D2950 and correlated with ASTM D1188 or ASTM D2726. One field test for every 1000 square yards (836 square meters); minimum 2 tests. One laboratory test for the project.

G20 1.3.4 Portland Cement Concrete Pavement Performance Verification

a. Visual: Finished surface must be uniform in texture and appearance and free of cracks.

b. Sampling: ASTM C31/C31M.

c. Thickness: Acceptable tolerances are plus or minus 0.5 inches (13 mm). One test for every 500 square feet (418 square meters); minimum 2 tests.

d. Surface Smoothness: Test surface smoothness by using a 10 foot (3 meter) straightedge in transverse and longitudinal directions to pavement. The finished surfaces of the pavements must have no abrupt change of 0.12 inch (3 mm) or more.

e. Strength: Samples for strength tests of each mix design of concrete placed each day are required to be taken not less than once a day, nor less than once for each 100 cubic yards (120 cubic meters) of concrete, nor less than once for each 5000 square feet (500 square meters).

1) Compressive Strength: ASTM C39/C39M. Make five test cylinders for each set of tests. Test two cylinders at 7 days, two cylinders at 28 days, and hold one cylinder in reserve. Determine each strength test result by the average of two cylinders from the same concrete sample tested at 28 days. If the average of any three consecutive strength test results is less than f'c or if any strength test result falls below f'c by more than 500 psi, take a minimum of three ASTM C42/C42M core samples from the in-place work represented by the low test cylinder results and test. Consider the concrete represented by core test structurally adequate if the average of three cores is equal to at least 85 percent of f'c and if no single core is less than 75 percent of f'c. Retest locations represented by erratic core strengths.

2) Flexural Strength: ASTM C78/C78M. Make four test specimens for each set of tests. Test two specimens at 28 days, and the other two at 90 days. Concrete strength will be considered satisfactory when the minimum of the 90-day test results equals or exceeds the specified 90-day flexural strength, and no individual strength test is less than the design strength. If the ratio of the 28-day strength test to the specified 90-day strength is less than 65 percent, make necessary adjustments for conformance.

f. Remove concrete not meeting strength criteria and provide new acceptable concrete at no expense to the government. Repair core holes with nonshrink grout. Match color and finish of adjacent concrete.

G20 1.3.5 Concrete Joint Performance Verification

Install a test section of 500 linear feet (150 m) at start of sealing operation for each type sealant to be used. Obtain approval of test section by Contracting Officer prior to installing additional joint seal. Reject joint sealer that fails to cure properly, or fails to bond to joint walls, or reverts to uncured state or fails in cohesion, or shows excessive air voids, blisters, or has surface defects, swells, or other deficiencies, or is not recessed within indicated tolerances. Remove rejected sealer and reclean and reseal joints.

G20 1.3.6 Topsoil Performance Verification

Prior to planting design, provide a commercial soil analysis. Amend planting areas based on the soil test's interpretation, amendment type, and quantity recommendations (including soil nutrients and texture, with percentages shown). Use additional topsoil only in areas where soil analysis shows that the existing soil is inadequate for growth of plant materials.

G20 1.3.7 Final Inspection for Planting and Irrigation

Request the final inspection in writing at least 10 days prior to the last day of the planting and irrigation Establishment Period. The Landscape Contractor must attend the inspection with the Contracting Officer and document the inspection. The Landscape Architect-of-Record must also attend the inspection and provide the Contracting Officer with a letter certifying that the planting and irrigation is installed per the plans and irrigation coverage is correct and appropriate for optimum plant survival. At the end of the Establishment Period, remove all stakes and guy cables.

G20 1.3.8 Landscape and Irrigation Establishment Period and Guarantee

Guarantee all transplanted trees, newly planted vegetation and irrigation systems for a period of one year after the Contracting Officer's final acceptance. This acceptance, and the submittal of irrigation as-builts and controller charts, begins the Establishment Period. Replace all trees, shrubs, and ground covers that die or have 20 percent or more of their crowns that die during planting operations or the guarantee period with healthy plants of the same species or variety during the appropriate planting season. The Landscape Architect-of-Record must, along with the Contracting Officer, attend, approve and document the start of the Establishment Period and document quarterly and final inspections. The Landscape Architect of Record must document quarterly and final inspections by submitting written reports with photographs to the Contracting Officer. During this period, perform tasks including, but not limited to: watering, mowing, overseeding, fertilizing, mulching, pruning, weeding, eradicating pests (rodents, rabbits, insects, mammals and fungus), restaking, adjusting guy wires, adjusting irrigation systems, maintaining erosion control materials, removing dead or broken branches by pruning in accordance with ANSI A300 Part 1, maintaining edging of planter beds, checking for girdling of trees, removal of trash and debris, and replenishing mulch to assure all plant material is in a healthy and thriving condition or replace plant material at Contractor's expense. Reseed broadcast seeded or hydro-seeded areas that do not achieve the 95-percent coverage by the end of the Establishment Period by the same method and maintain an additional 120 days to ensure coverage requirements are met. Maintain turf in a manner that promotes proper health, growth, rich natural green color, and a neat, uniform, manicured appearance, free of bare areas, ruts, holes, weeds, pests, dead vegetation, debris, and unwanted vegetation that present an unsightly appearance. Mow weekly during the growing season and remove excess clippings.

G20 1.4 DESIGN SUBMITTALS

Design Submittals must be in accordance with UFC 1-200-01, General Building Requirements, UFGS section 01 33 10.05 20, *Design Submittal Procedures*, UFC 1-300-09N, *Design Procedures*, and UFC 3-201-01, *Civil Engineer*ing.

In addition, UFGS sections listed below or in the body of the PTS text are to be used by the Designer of Record (DOR) as a part of the design submittal. If the UFGS products or systems are applicable to the project, the DOR is required to edit these referenced UFGS sections and submit them as a part of the design submittal specification. Edit the specification sections in accordance with the limitations stated in PTS section Z10, *General Performance Technical Specifications*.

32 11 16.13, *Sand-Clay [Base] [Subbase] Course*

32 11 16.16, *[Base Course for Rigid] [and Subbase Course for Flexible] Paving*

32 11 24, G*raded Crushed Aggregate Base Course for Flexible Pavement*

32 11 26.16, Bituminous Concrete Base Course

32 11 33, *Cement Stabilized [Base] [Subbase] Course at Airfields and Roads*

32 11 36.13, *Lean Concrete Base Course*

32 12 17, *Hot Mix Bituminous Pavement*

32 13 13.16, *Portland Cement Concrete Pavement for Roads and Site Facilities*

32 13 43, *Pervious Concrete Paving*

32 16 15, *Concrete Block Pavements*

G20 1.5 CONSTRUCTION SUBMITTALS

Submit a transplanting plan for all projects which include transplanting trees. Submit the plan showing existing and proposed locations of transplanted trees. Include in the plan delineate methods and times for root pruning, digging, balling, removing, storing, transporting, planting, watering, and maintenance to ensure survivability. Include also in the plan equipment, anti-desiccant, and pesticides to be used. Provide a listing of the plant material to be transplanted by common name and botanical name as listed under "Nomenclature" in ANSI Z60.1; classification; caliper; and height.

G20 1.5.1 Transplanting Plan

Submit a transplanting plan for all projects which include transplanting trees. Submit the plan showing existing and proposed locations of transplanted trees. Include in the plan delineate methods and times for root pruning, digging, balling, removing, storing, transporting, planting, watering, and maintenance to ensure survivability. Include also in the plan equipment, anti-desiccant, and pesticides to be used. Provide a listing of the plant material to be transplanted by common name and botanical name as listed under "Nomenclature" in ANSI Z60.1; classification; caliper; and height.

G20 1.5.2 As-Builts

Submit a complete set of irrigation as-builts to the Contracting Officer, to include the recording of measurements onto a record set of full-size project irrigation plans. Indicate measurements for locating water meters, pressure supply lines at 100 foot (30 m) intervals, backflow prevention devices, rain/freeze sensors, valves (including quick couplers and hose bibbs), controllers (and control wire, if routed separately from pressure supply line); all dimensioned from two permanent points of reference, such as building corners, sidewalks, and other permanent features.

G20 1.6 ANTITERRORISM (AT) STANDARDS

INCORPORATE THE MINIMUM AT STANDARDS INDICATED IN UFC 4-010-01, *DOD MINIMUM ANTITERRORISM STANDARD FOR BUILDINGS*.

G20 1.7 PROJECT LIMITATIONS

Prior to the start of design, determine the exact limit-of-work line for the project periphery, considering items such as, but not limited to, utility work, landscape areas, and laydown areas. See PTS G2050 for limits of landscape areas.

G2010 ROADWAYS

G2010 1.1 PAVEMENT DESIGN

Provide geometric and pavement design, including minimum pavement sections, in accordance with UFC 3-201-01, *Civil Engineering*, and the State Department of Transportation. Provide pavement calculations in accordance with UFC 1-300-09N, *Design Procedures*. Provide any required additional pavement design to provide a complete and useable facility.

For pavements subject to aircraft traffic or aircraft ground support equipment traffic consult Government Civil Reviewer for design criteria and requirements. State Department of Transportation standards are not acceptable for airfield pavements.

G2010 1.2 PAVEMENT AESTHETICS

Provide surfaces consistent in color and finish.

G2010 1.3 LANDSCAPING

Include adequate space for trees and other landscape material in the design for streets, roads, and parking lots in accordance with PTS G2050.

G2010 1.4 TRAFFIC CONTROL DEVICES

Provide and install new traffic control devices (i.e., signs and markings) in accordance with the United States Department of Transportation Federal Highway Administration's *Manual on Uniform Traffic Control Devices* and their standard, "Rigid Sign Supports". Also provide new traffic control devices along/in the existing streets adjacent to the project site as necessary to provide complete traffic control to the new facilities.

G2010 1.5 EXISTING UTILITY STRUCTURES

Adjust existing utility structures to meet the new finished pavement grades as required.

G201001 BASES & SUBBASES

Prepare subgrade in accordance with Section G10, *Site Preparation*. Geotextiles may be used for separation or reinforcement in accordance with manufacturer's instructions. Provide base course under paved areas in accordance with the State Highway specifications (SHS) in the state where the project is located.

Place base course in accordance with the SHS for that particular base course and in layers of equal thickness with no compacted layer more than 6 inches (150 mm) thick. Compact base course at optimum moisture content to 100 percent ASTM D 1557 maximum dry density.

Where SHS are not available or applicable, the Designer of Record must utilize the applicable UFGS Specification Sections referenced under paragraph 1.1.2 entitled "Government Standards" for the project specification. Submit these specifications in edited form as a part of the design submittal for the project.

G201002 CURBS & GUTTERS

Provide concrete curbs and gutters in accordance with the SHS and standards or as specified in UFC 3-201-01, Civil Engineering, whichever is more stringent. Where the SHS do not include concrete materials for curbs and gutters, provide concrete in accordance with the applicable standard mix of the SHS for a minimum compressive strength at 28 days of 3500 psi (25 MPa) concrete.

G201003 PAVED SURFACES

Where SHS are not available or applicable, the Designer of Record must utilize the applicable UFGS Specification Sections referenced under paragraph 1.1.2 entitled "Government Standards" for the project specification. Submit these specifications in edited form as a part of the design submittal for the project.

G201003 1.1 PAVEMENT MIX

G201003 1.1.1 Bituminous Concrete Pavement

Provide bituminous concrete pavement in accordance with the applicable standard mix of the SHS based on the pavement design and vehicle loading indicated in this RFP.

G201003 1.1.1.1 Bituminous Concrete Placement

Provide bituminous concrete placement, including minimum temperature during placement, joints, and maximum lift thickness in accordance with the SHS. Compact bituminous concrete in accordance with the SHS, modified to 96 percent of maximum laboratory density.

G201003 1.1.2 Portland Cement Concrete Pavement

If reinforced, the welded wire fabric shall conform to ASTM A 185. Bar reinforcement shall conform to ASTM A 615/A 615M, Grade 400 (Grade 60).

Provide concrete in accordance with the applicable standard mix of the SHS for the design strength plus any allowable deviations.

G201003 1.1.3 Portland Cement Concrete Pavement

If reinforced, provide the welded wire fabric in conformance to ASTM A185. Provide bar reinforcement in conformance to ASTM A615/A615M, Grade 400 (Grade 60).

Provide concrete in accordance with the applicable standard mix of the SHS for the design strength required by UFC 3-201-01, *Civil Engineering*, plus any allowable deviations. Provide a minimum compressive strength at 28 days of 3500 psi (25 MPa) concrete.

If required for applicable LEED credit, provide Portland cement concrete pavement with a Solar Reflectance Index (SRI) greater than or equal to 29.

G201003 1.2 JOINTS FOR PORTLAND CEMENT CONCRETE PAVEMENT

Provide joints in accordance with SHS and the applicable portions of UFC 3-250-01FA, *Pavement Design for Roads, Streets, Walks, and Open Storage Areas*. Install joints in a manner and at such time to prevent random or uncontrolled cracking. Joints must form a regular rectangular pattern. Wherever curved pavement edges occur, make joints to intersect tangents to curve at right angles.

G201003 1.2.1 Expansion Joints

Provide thickened edge expansion joints at the intersection of two rigid pavements. Use preformed joint filler, ASTM D1751. Filler must be compatible with joint sealer material. Securely hold preformed joint filler in position during concreting operations.

G201003 1.2.2 Isolation Joints

Provide thickened edge isolation joints by placing a 1/2-inch (12 mm) preformed joint filler (ASTM D 1751) around each structure that extends into or through the pavement before concrete is placed at that location.

G201003 1.2.3 Contraction Joints

Saw joint lines within specified tolerance, straight, and extend for width of transverse joint, and for entire length of longitudinal joint.

G201003 1.2.4 Construction Joints

If an emergency stop occurs remove the concrete back to location of transverse joint and install a construction joint.

G201003 1.2.5 Joint Sealants

ASTM D5893/D5893M; Provide single component cold-applied silicone. Silicone sealant must be self-leveling and non-acid curing.

G201003 1.2.6 Preformed Compression Seals

Use performed compression seals in areas where silicone joint sealant does not perform, such as areas subject to water inundation, blasts, or constant/repeated fuel spillage.

ASTM D 2628. ASTM D 2835, for lubricant.

G201003 1.3 PRIME COAT

Use prime coat in accordance with the SHS. Prime coat must be emulsified asphalt materials.

G201003 1.4 TACK COAT

Tack coat is required for bituminous pavement overlays and on vertical cut faces of pavement patches. Provide tack coat in accordance with the SHS.

G201003 1.5 PAVEMENT PATCHES

Provide pavement patches for existing pavements where required for installation of utility trenches. Sawcut 12 inches beyond edge of trench. Provide thicknesses of pavement materials equal to or greater than the existing pavement section.

For spalls or repairs of existing concrete pavement, perform repairs in conformance with UFC 3-270-03, *Concrete Crack and Partial Depth Spall Repair*, and UFC 3-270-04, *Concrete Repair*. Spall repair materials must be either Rapid Setting Cementitious Concrete (RSCC), epoxy concrete, or polymer-modified Portland Cement (non-sag mortar) products specially formulated for spall repairs, with a proven record (in service at least three years) of satisfactory use under loading and environmental conditions

similar to those at the location of intended use. Provide a manufacturer's data sheet and certificate supporting the satisfactory use to the Contracting Officer with the design. A product manufacturer's representative is required to be present during the initial two days of product application to verify that manufacturer's instructions for use are adhered to. Give the Contracting Officer 7 days notice prior to the initial application in order to be present.

G201004 MARKING & SIGNAGE

G201004 1.1 MARKING

Provide pavement markings in accordance with the SHS. Design materials for life expectancy of at least 3 years under an average daily traffic count per lane of approximately 9000 vehicles. Water based paints must have durability rating of at least 4 when determined in the wheel path area.

Provide a half-rate initial marking application on bituminous pavements. Provide the remaining application at the end of the normal curing period.

G201004 1.2 SIGNAGE

Provide signage in accordance with the MUTCD.

G201005 GUARDRAILS & BARRIERS

G201005 1.1 GUARDRAILS

Provide guard (guide) rails in accordance with the SHS. Where the SHS do not include materials for guardrails, provide guardrails in accordance with the applicable portions of the *AASHTO Roadside Design Guide*.

G201005 1.2 BOLLARDS

For bollards to prevent damage, provide minimum 4 feet height, 4 inch diameter steel pipe filled with concrete, painted, and embedded in a portland cement concrete foundation.

For bollards located at building entries or other high-visibility areas provide decorative bollards matching the design of the facility or consistent with the Base Exterior Architecture Plan (BEAP) and the Installation Appearance Plan.

Bollards for security are specified in Section G204004, "Security Structures".

G201006 RESURFACING

Adjust rims of existing utility structures to match proposed grades after resurfacing.

G201006 1.1 SLURRY SEAL

ASTM D 3910 and in accordance with the SHS.

G201006 1.2 BITUMINOUS CONCRETE OVERLAY

Remove old pavement by cold milling to depths required to provide new surface and leave underlying materials intact. Clean the pavement of excessive dirt, clay or other foreign matter with power brooms and hand brooms immediately prior to the milling operation.

Repair or replace damaged utility structures, valve boxes, or pavement that is torn, cracked, gouged, rutted, broken or undercut at no addition expense to the government.

Provide bituminous concrete overlay produced from hot or cold recycling of the milled material or from virgin materials in accordance with the applicable provisions of UFC 3-201-01, *Civil Engineering*, and the standard mix of the SHS based on the pavement design and vehicle loading as indicated in this RFP.

G201006 1.3 CRACK SEALING

Use fiber reinforced crack sealer for sealing cracks in asphalt pavement after milling and prior to resurfacing. Provide crack sealing conforming to the following requirements in UFC 3-270-01, *Asphalt Maintenance and Repair*, and UFC 3-270-02, *Asphalt Crack Repair*.

G2020 PARKING LOTS

Refer to Section G2010.

G202001 BASES & SUBBASES

Refer to Section G201001.

G202002 CURBS & GUTTERS

Refer to Section G201002.

G202003 PAVED SURFACES

Refer to Section G201003.

G202004 MARKING & SIGNAGE

Refer to Section G201004. Provide water-based paints only.

Mark neatly to denote traffic lanes and parking spaces; mark in accordance with the requirements of UFC 3-201-01, *Civil Engineering*.

G202005 GUARDRAILS & BARRIERS

Refer to Section G201005.

G202005 1.1 WHEELSTOPS

Provide precast concrete wheelstops.

G202006 RESURFACING

Refer to Section G201006.

G2030 PEDESTRIAN PAVING

Locate new sidewalks such that they maintain continuity of pedestrian traffic to and from the existing sidewalks adjacent to the site(s).

G203001 BASES & SUBBASES

Provide as required by local standards or geotechnical report; refer to Section

G201001.

G203003 PAVED SURFACES

G203003 1.1 SIDEWALKS

Provide sidewalks of Portland cement concrete pavement with 4 inches (100 mm) thick minimum or permeable pavement Provide concrete and permeable pavement in accordance with Section G201003. For PCC sidewalks, provide a broomed finish. Provide sidewalks of at least 5 feet (1.5 meters) wide, except that sidewalks connecting entry points of housing units to the housing unit's parking are required to be at least 36 inches (900 mm) wide. In housing areas, offset sidewalks paralleling streets to maintain a minimum grassed separation of 5 feet (1.5 meters) from the back face of the curb to the closest edge of the sidewalk.

Unless indicated otherwise, provide a transverse slope of 1/48. Limit variation in cross section to 0.25 inch in 5 feet (6 mm in 1.50 m).

Submit samples boards per ESR G2050 and PTS G2050 and finish schedule on final plans.

G203003 1.1.1 Joints for PCC Pavement Sidewalks

Provide contraction joints spaced at intervals equivalent to the width of the sidewalk. Provide 0.5 inch (13 mm) thick transverse expansion joints at changes in direction where sidewalk abuts curb, steps, rigid pavement, or other similar structures; space expansion joints every 50 feet (15 m) maximum. Provide isolation joints by placing a 1/2-inch (12 mm) preformed expansion joint filler around each structure that extends into or through the sidewalk before concrete is placed at that location.

G203003 1.2 HANDICAPPED RAMPS

Provide handicapped ramps of PCC pavement with an exposed aggregate finish, truncated domes, or as required by the SHS at roadway intersections.

G203004 GUARDRAILS & BARRIERS

Refer to Section G201005.

G2040 SITE DEVELOPMENT

G204001 FENCING & GATES

G204001 1.1 CHAIN LINK FENCE

Do not use aluminum fabric, posts or accessories.

Chain link fence fabric must be at least 9 gauge (3 mm) steel wire mesh material (before any coating) with mesh openings not larger than 2 inches (51 mm). Install fence in accordance with ASTM F567 and the manufacturer's written installation instructions.

G204001 1.1.1 Tensions Wires and Top Rails

Provide rails in accordance with FS RR-F-191/3, Class 1, steel pipe, Grade A.

G204001 1.1.2 Gates

Provide gates in accordance with FS RR-F-191/2 with posts and fabric as specified for fence.

G204001 1.1.3 Posts and Braces

Provide posts and braces in accordance with FS RR-F-191/3, Class 1, steel pipe, Grade A. Each gate, terminal and end post will be braced with truss rods.

G204001 1.1.4 Fencing Accessories

Provide fencing accessories in accordance with FS RR-F-191/4. If PVC coating is required, provide accessories with PVC color coating similar to that specified for chain-link fabric or framework.

G204001 1.2 ORNAMENTAL FENCE

G204001 1.3 SECURITY FENCE

Provide security fencing systems in accordance with UFC 3-201-01, *Civil Engineering*, and this RFP.

G204001 1.3.1 Chain Link Security Fence

Provide chain link fence in accordance with paragraph G204001 - 1.1, excepted as noted otherwise. Ensure that the fabric has twisted and barbed selvage at the top and bottom. Do not provide top rails. Locate all posts and structural supports on the inner side of the fencing. Install outriggers facing outward except when the fence must be mounted directly on the property line.

G204001 1.3.2 Signage

Provide signage at a minimum of 200 foot (61 m) intervals along the entire perimeter.

G204001 1.3.3 Drainage Culverts and Utility Openings

Provide protective measures to prevent access through culverts, storm drains, sewers, air intakes, exhaust tunnels and utility openings or across drainage ditches or swales.

G204001 1.4 OPENINGS IN PERIMETER AND SECURITY FENCING

Do not cover, block or lace openings in perimeter fencing and security fencing with material which would prevent a clear view of personnel, vehicles or material in the outer or inner vicinity of the fence line.

G204001 1.5 FENCE GROUNDING

Ground fencing on either side of every gate and at other locations when the fencing is near and parallel to high tension power lines. Grounding is also required at intervals of 1000 feet (305 meters) to 1500 feet (457 meters) when the fencing runs through isolated areas and at lesser distances depending on the proximity of the fencing to public roads, highways and buildings where the fencing is around or within any explosive storage, production, operating or handling areas.

G204001 1.6 ENCLOSURES FOR UTILITY EQUIPMENT

Where fencing is used to provide an enclosure for utility equipment, ensure a minimum clearance is provided no less than 3 feet (900 mm) around the equipment to permit maintenance access and ventilation. Provide stone, gravel or concrete paving within the enclosure.

G204002 RETAINING WALLS AND FREESTANDING WALLS

Provide retaining walls to permanently resist soil pressures as well as live loads. Provide wall drainage to minimize lateral loading and protect wall materials against degradation.

G204003 EXTERIOR FURNISHINGS

Refer to ESR G20 and other portions of the RFP for exterior furnishings required on this project. Permanently attach all site furnishings to concrete pads. Provide site furnishings in conformance with the Base Exterior Architecture Plan (BEAP) and or Installation Appearance Plan for each Activity. If no product guidance is given, coordinate material, finish and color with architecture (fiberglass and aluminum are not acceptable) and provide to the greatest extent possible, materials with industrial recycled content, preferably from regionally local manufacturers.

G204003 1.1 PICNIC AND PASSIVE RECREATION AREAS

Include tables, with attached benches, on concrete bases sloped to drain and permanent barbecue grill(s) for picnic areas. Additionally, provide separate receptacles for trash, recycling and barbecue ashes. Permanently attach all site furnishings to concrete paving extending a minimum of 12 inches (300 mm) past the furnishing, with the exception of picnic tables and benches, which require concrete paving extending 2 feet (600mm) minimum on all sides. The elevation of the finished concrete must be plus 1 inch (25 mm) above adjacent grade.

G204003 1.2 TRASH RECEPTACLES

Provide trash receptacles with drain hole and stationary or self-closing lids with anchor chains secured to the receptacle to protect the contents from weather. Design receptacles to hold heavy-duty plastic or galvanized steel liners of the same manufacturer. Consider potential weight of full containers when deciding on 'top loading' or 'side loading' receptacles. Include a concrete pad 12 inches (300 mm) larger on all sides than the size of the trash receptacles.

G204003 1.3 BENCH

Minimum 6 feet (1.8 meter) length to match trash and recycling receptacle material & color, installed a minimum of 18 inches (450 mm) above finish grade, permanently installed with anchor bolts or in-ground. For benches located in nonpaved areas, provide concrete pads extending a minimum 2 feet (0.6 meters) beyond the edge of the seat portion of the bench (or both front and back if accessible from either).

G204003 1.4 RECYCLING RECEPTACLES

Provide recycling receptacles, single-piece with separate slots for cans, bottles, newspaper. Match height, material, and style of the trash receptacle.

G204003 1.5 BARBEQUE

Minimum 12 inches (300 mm) x 18 inches (450 mm) with heavy-duty grill and hinged stainless steel lid, factory primed and painted with rust-resistant

paint. Install so coal height is a minimum of 36 inches (0.91 meter) above finish grade.

G204003 1.6 HOT ASH RECEPTACLE

Minimum 28 square inches (181 square centimeters) x 42 inches (1.1 meter) high pre-cast reinforced concrete with drain hole with steel ash grate and cast in "Hot Coals Only" logos on each side with white letters on a red background.

G204004 SECURITY STRUCTURES

Where identified for project elsewhere in this RFP, provide active and passive vehicle barriers to effectively stop or detect penetration by explosive-laden vehicles through the perimeter of a protected area in accordance with UFC 4-022-02, *Selection and Application of Vehicle Barriers*.

G204005 SIGNAGE

Provide facility signage as required by local code, the Installation and Appearance Guide, the Base Exterior Architectural Plan (BEAP) and this RFP.

Size messages and graphics on signs according to the functional viewing distance. Typically, at least 1 inch (25 mm) of letter height per 25 feet (7.62 meters) of viewing distance is required for readability.

Refer to Section G201004, "Marking & Signage" for traffic signage.

G204007 PLAYING FIELDS

G204007 1.1 PLAYGROUNDS

Design playgrounds and provide surfacing and equipment in accordance with this RFP and U.S. Consumer Products Safety Commission Publication 325 and ASTM F1487. Border tot-lots and play-lots with reinforced concrete curbing to a depth appropriate to the type safety surfacing utilized. Provide shade and wind protection where these elements may significantly limit the use of the facilities. For tot-lots and play-lots provide separated areas with appropriately sized equipment and materials to serve their developmental levels. Separate areas by a buffer zone, which can be an area of shrubs, hardscape or benches. Provide signage to give guidance to adults as to the age appropriateness of the equipment.

G204007 1.1.1 Tot Lots

Design each "tot lot" to accommodate children from ages 2 through 5 to provide a variety of play activities and motor skill development opportunities which may include, as a minimum:

For multi-activity structures provide a minimum of two platforms and two slides, one wheel chair accessible, swing set for young children, paired spring mounted 'riders' or other similar types of apparatus. Locate at least two benches with backs on concrete bases for convenience to, and observation of, the tot-lot.

G204007 1.1.2 Play Lots

Design each "play lot" to accommodate children from ages 5 to 12 which provide a wider range of activities and opportunities for greater motor skills development and improvement. These may include, as a minimum:

For a multi-activity structure, provide a minimum of three platforms and two slides, one wheel chair accessible. A swing set, or other similar types of apparatus. Locate at least two benches with backs on concrete bases for convenience to, and observation of, the play-lot.

G204007 1.1.3 Equipment

Tot lot and play lot equipment must be factory finished institutional quality, in compliance with ASTM F1487, the United States Consumer Products Safety Commission's *Guidelines for Public Playgrounds*, and the UFC 3-201-01, *Civil Engineering*. Use only equipment that has been approved by IPEMA and installed by a NPCA contractor.

Site tot lot and play lot equipment to provide use and no encroachment zones in accordance with ASTM F1487. A use zone is a clear, unobstructed area under and around play equipment where a child would be expected to land when jumping or falling from a piece of play equipment. Requirements for use zones vary for the age group and for different pieces of equipment. Show all use zones for play equipment on the site plan to ensure there is no conflict between play activities on the ground and swinging or jumping from the equipment. The No-encroachment zone is an additional area beyond the use zone where children using the equipment can be expected to move about and should have no encroaching obstacles. This area will vary according to the types of adjacent equipment, and their orientation to one another.

G204007 1.1.4 CCA-Treated Lumber

Do not use CCA-treated lumber in recreational facilities for children.

G204007 1.1.5 Playground Safety Surface

Provide a playground safety surface, in accordance with ASTM F355 and ASTM F1292, throughout all use zones and under all play equipment in tot lots and play lots. Natural wood products and decomposed granite are not allowed for surfacing. Loose fill surfacing must be a minimum of 4 inches (100 mm) below the top of edging. Consider local climate, soil conditions, location and size of area, type of activity, age of users, and intensity of use when choosing surfacing material. Provide soil separator fabric between playground loose-fill material and subgrade soil. Design play areas with permeable surface and adequate drainage. Drain to sump a minimum of 20 feet out from the playground curbing or to storm drain.

G204007 1.2 PLAYING FIELDS

Provide playing surfaces in accordance with this RFP. Use synthetic turf systems approved by the reviewing Government Landscape Architect or Civil Engineer.

G204090 OTHER SITE IMPROVEMENTS

Provide other site improvements in conformance to the BEAP or Installation Appearance Plan and to the requirements of UFC 4-010-01.

G204090 1.1 DUMPSTER PADS AND ENCLOSURES

G2050 LANDSCAPING

Landscape area is defined as all permeable areas within the project boundaries not covered by buildings, roads, parking lots, sidewalks, and other non-permeable areas. All site areas disturbed by construction must receive landscape

improvements.

G2050 1.1 DESIGN

The design of landscaped areas must be in accordance with Presidential Executive Order 13148 of April 2000, with a goal to reduce fertilizers, pesticides, and water use. The intent is to achieve a base-wide ratio of 20 percent maximum non-native plants and 80 percent minimum locally or regionally native plants. Do not use plants deemed invasive by the project state or region's Exotic Pest Plant Council, State Department of Agriculture or local chapter of the American Society of Landscape Architects as a threat to ecosystems or agriculture. Select only plant species which require little or no supplemental irrigation after the initial establishment period. Only nursery-grown plants are acceptable. Cover all non-paved site areas disturbed by construction operations with plant material or inorganic mulch. Stabilized soil, decomposed granite, and organic mulch are not acceptable as ground covers. Provide landscape architectural work in accordance with UFC 3-201-02, *Landscape Architecture*. For all projects with planting and or irrigation areas, utilize the design services of a Landscape Architect licensed in the state of the project. The Landscape Architect of Record must visit the site at least once prior to design, twice during construction, and quarterly during the Establishment Period, including the Establishment Period start and completion. The Landscape Architect of Record must attend the kickoff partnering meeting and CDWs. Courtyards and plazas are to be designed by the Landscape Architect. For the CDW, provide a Site Analysis Plan to demonstrate the design thought process. It is the Contractor's responsibility to coordinate between disciplines including architecture, civil engineering, electrical engineering, mechanical engineering, fire protection, and landscape architecture. Coordinate location of utilities, structures, and equipment. For projects in dry climates (arid and semi-arid), eliminate or minimize the use of turf, except when needed for active or passive recreation.

The Landscape Architect-of-Record is required to submit 5 sample boards of landscape materials. Sample boards to include but not limited to colors, finishes, textures of hardscape paving, walls, signs, monument piers, inorganic mulches, organic mulches, and other site improvements. Include cut sheets of all proposed plant material.

G205001 FINE GRADING AND SOIL PREPARATION

See Section G10, Site Preparation. Provide 4 inches (102 mm) of topsoil with appropriate soil amendments, as recommended by a current soil composition test, for all areas to be planted with turf grass.

G205002 EROSION CONTROL MEASURES

See Section G10, Site Preparation.

G205003 TOP SOIL AND PLANTING BEDS

See paragraph titled, G205005 PLANTINGS.

G205004 SEEDING, SPRIGGING, AND SODDING

Hydroseed areas that are to be seeded and are larger than 1,000 square feet (92.90 square meters). Hydroseed mix composition must be appropriate for surrounding land use and compatible and consistent with local application rates, seed availability and established practice in the project area. If project dates are unknown, specify required planting dates or alternative species for different

seasons. Apply seed at a time best suited for germination of the selected species. Seeded areas are required to achieve a 95-percent coverage of the selected species and be weed free at the end of the Establishment Period.

G205005 PLANTINGS

G205005 1.1 EXISTING PLANT MATERIAL TO REMAIN OR BE TRANSPLANTED

Preserve existing trees to the greatest extent possible. Identify preserved trees on the plans with tree species, caliper and dripline. Tag trees to be saved with plastic or vinyl tape tied to the tree caliper. Protect existing trees by fencing planting areas to remain from compaction and any other damage with a barrier of metal poles a maximum 8 feet (2.4 meter) on center with plastic netting to a minimum of 10 feet (3.0 meter) radius from outside of the tree's trunk. Where tree drip lines are greater than 10 feet (3.0 meter) from the tree's trunk, locate barrier fencing at the drip line of the tree. Install signs on each Tree Protection Zone fence indicating that the barrier must not be taken down or moved without the participation of a Certified Arborist. Ensure that the details and specifications clearly state that none of the following activities occur within the tree protection barricade: driving, parking, storing materials, dumping waste, concrete washout, adding fill soil, trenching, removing soil, grubbing, or any other disturbance to the tree or the associated roots. Do not allow debris from tree or stump removal operations to fall on or otherwise damage plants that are not scheduled for removal. Do not remove plastic tape and barrier fencing until planting operations are ready to begin and or instructed by the Contracting Officer. Replace existing trees to remain or to be transplanted that are unhealthy, that die, or have 20 percent or more of their crowns that die during the establishment period with healthy plants of the same species or variety during the appropriate planting season. During the landscape establishment period, replace trees, turf, shrubs, and ground cover that are damaged or destroyed during construction operations by the Contractor at no additional cost to the Government. At the direction of the Contracting Officer, remove the existing tree and stump and replace it with trees of the same genus and species equal to the total caliper of the existing tree. Minimum caliper of replacement trees must be 4 inch (100 mm). Replace shrubs with 5 gallon (18.9 liter) size container, ground cover with flat containers planted at 8 inches (200 mm) on center, and turf with sod, all of the same genus and species.

G205005 1.2 UTILITIES

Do not place trees within 10 feet (3 meter) of any above or below-grade utility line or structure. Within roadway sightlines, mature shrubs must not be greater than 3 feet (1 m) in height and trees must be limbed up a minimum of 6 feet (2 m) so their mature growth will not obstruct views from vehicle intersections or points of vehicle ingress or egress. Coordinate utilities between the Landscape Architect and appropriate disciplines.

G205005 1.3 RECYCLING

Green waste: Contact the Public Works Department for potential green waste collection and hauling by the Government. Separate green waste not collected by the Government from construction debris and deliver to the base's or local landfill's green waste recycling area. Quantify and report diverted waste to the Contracting Officer.

G205005 1.4 PLANTING

G205005 1.4.1 Plant Quantities

Provide trees at the minimum rate of one (1) tree per 1,000 square feet (92.9 square meters) of Landscape Area. Parking areas must have a

minimum of one (1) tree per every 5 parking spaces around the parking perimeter and one (1) tree per every 10 parking spaces within the parking area. Provide a minimum of one (1) tree in each end aisle planter. Total minimum quantities may be reduced only by the reviewing Government Landscape Architect. Tree quantities reduced by the Government Landscape Architect will be included on the ADD/DEDUCT List by the Contracting Officer. For bioretention areas, minimum quantities of trees, shrubs, and ground covers must be as required by State regulations. Provide a minimum tree size of 24 inch (600 mm) box/2 inch (50 mm) caliper, or if within an anti-terrorism zone provide a minimum size of 36 inch (910 mm) box/3 inch (76 mm) caliper. For trees within concrete or other non-permeable paved areas, allow a minimum non-paved planting area of 4 feet by 8 feet (1.2 m by 2.4 m) per tree.

For dry climates (arid and semi-arid)only: Plant a minimum of forty percent (40%) of the landscaped areas with shrubs and groundcover so that at 50 percent (50%) plant maturity, they will form mass plantings. Utilize a minimum ratio of 60 percent (60%) 5 gallon (18.9 liter) shrubs or groundcover and 40 percent (40%) 1 gallon (3.79 liter) shrubs or groundcover. The remaining sixty percent (60%) of the landscape area may be inorganic mulch, planted or a combination thereof. For inorganic mulch, provide 3 inch (76 mm) depth of 3/4-inch (19 mm) and smaller rock, and for larger than 3/4-inch (19 mm) size, assure complete ground surface coverage. Provide plant material calculation summary matrix on planting plan. For all other climate zones: Plant the majority of shrubs at major entrances to buildings and at other important planting zones that are specific to each site. The overall design intent should be to plant mostly trees and turf, with shrubs and ground covers used sparingly, to reduce maintenance costs while still providing for functional planting requirements (e.g., soil stabilization, energy conservation, force protection, and aesthetics). Provide a minimum size 3 gallon (11.4 liter) container for shrubs and 1 gallon (3.79 liter) container for ground covers.

G205005 1.4.2 Plant Quality

All plants must comply with ANSI Z60.1 and ANSI A300, Part 1, current editions. All plants must be in a healthy, disease and pest free condition. All seed, sod, and sprigs must be State Certified.

G205005 1.4.3 Plant Selection

The reviewing Government Landscape Architect has final approval authority on all selected plant material. Species deemed unsuitable for planting by the Government Landscape Architect will not be allowed.

G205005 1.4.4 Plant Installation

Planting operations, including but not limited to planting soil mixes and fertilization, must comply with local established practices and agricultural extension service recommendations. Stake or guy new or transplanted trees with three stakes [2-2 Â½inch(63.5 mm) x 8 feet (2.4 m) hardwood], or three guy cables [five-strand, 3/16 inch (5 mm) diameter galvanized steel cable]. Install linear tree root barriers at the edge of paving where trees are planted within 10 feet (3 m) of sidewalks, curbs, walls, columns, and other hard surface areas. Do not encircle tree root balls with root barriers.

G205005 1.4.5 Edging Materials and Mulching Materials

Provide 3/16 inch (5 mm) minimum thick by 5 inch (127 mm) minimum deep aluminumedging or 6 inch (150 mm) by 6 inch (150 mm) minimum, concrete edging dividing all turf and planting beds and dividing all planted

and non-planted inorganic mulch areas. Provide stake type and spacing for aluminum edging per manufacturer's recommendations. Plastic edging is not allowed. Mulch planted areas not mulched with inorganic mulch with a 3-inch (75 mm) depth of organic shredded hardwood mulch. For inorganic mulch where rock cobble size is greater than half of the profile depth, provide Â¾ inch (19 mm) comparable color and shape rock mulch in bottom half of profile. For dry climates only, organic mulch must be shredded redwood bark unless approved otherwise by the reviewing Government Landscape Architect. All mulches (organic and inorganic) must not be subject to sloughing off on sloped sites. Submit samples of mulches to the reviewing Government Landscape Architect for approval prior to installation. Decomposed granite must not be used. Provide a 3-inch (75 mm) depth of organic shredded hardwood mulch between plants used to form a mass (in dry climates, mulch in the remainder of planting beds with inorganic mulch). Install mulching materials prior to the start of the Establishment Period.

G205005 1.4.6 Fertilizer

Fertilize all transplanted trees, new trees, shrubs, ground covers, turf, perennials and ornamental grasses as recommended by local agricultural extension services.

G205005 1.4.7 Weed Fabric and Erosion Control Fabric

Provide a weed barrier fabric of sheet polypropylene or polyester fabric specifically designed for weed control purposes beneath all planted or mulched non-planted areas. Treat fabric for protection against deterioration due to ultraviolet radiation. Fabric must be a minimum 99 percent opaque to prevent photosynthesis and seed germination from occurring, yet allowing air, water and nutrients to pass through to the roots. Minimum weight must be 5 ounces per square yard (0.11 kg per square meter) with a minimum thickness of 20 mils (0.50 mm) with a 20 year minimum guarantee. Provide a biodegradable product designed specifically for erosion control on all sloped areas 3:1 and greater in slope. Do not place weed fabric over the root balls of trees.

G205005 1.4.8 Drainage

Provide for proper grading and drainage of turf and planting areas. Provide sub-surface drainage where soil or other conditions do not allow surface drainage. Do not drain roof gutters into planter areas.

G205007 IRRIGATION SYSTEMS

G205007 1.1 IRRIGATION

Where an irrigation system is required per other parts of this RFP, provide a permanent, below-grade system. Provide 100 percent sprinkler head to head coverage. Provide pop-up heads in turf and landscape zones when adjacent to walks, roads, parking lots, or in sparsely planted landscape areas where pedestrians may circulate. Provide pop-up heads project-wide on high-traffic sites such as, but not limited to, dining, housing, entertainment, daycare, education and recreation facilities. For dry climates, provide deep root watering systems for trees. Verify adequate water pressure for irrigation purposes and provide booster pumps and or pressure regulation as required. Provide minimum 18 inch (450 mm) cover over pressurized (mainline) PVC irrigation pipe and 12 inch (300 mm) cover over non-pressurized (lateral line) PVC irrigation pipe. 1/2-inch (13mm) pipe is not allowed. Provide pressurized (mainline) pipe in conformance with ASTM D1785, PVC 1120, Schedule 40. Provide non-pressurized (lateral) pipe in conformance with

ASTM D2241, PVC 1120 SDR 21, Class 200. The Landscape Contractor must test the entire system in the presence of the Contracting Officer and Landscape Architect-of-Record to ensure proper performance. All irrigation components must be commercial or institutional quality. Provide rain shut-off device and watertight splices. Provide sprinkler heads, bodies and nozzles of the same manufacturer. All irrigation heads on the same valve must have nozzles with matched precipitation rates.

G205007 1.2 OPERATION AND CONTROL

Assure systems will automatically operate on an "irrigation window" between 2000-0530. Provide compatible and fully functional control if a central control system exists on base. Otherwise, provide evapotranspiration-measuring control with flow meter and master valve with controller capable of indicating visible or auditory notification, such as a blinking light or beeping sound, of system shut-off.

G205007 1.3 ZONING

Provide separate control valves for differing plant species coefficients, landscape coefficients, and solar exposures, for areas with differing irrigation head types or differing precipitation rates, and top and bottom of slopes. Provide a separate irrigation backflow prevention device and water meter. Turf, trees, and shrubs/groundcover are not allowed on the same valve. Provide separate concrete valve box with cast iron lid and valve ID for each valve and wire splice. Provide quick coupling valves at 100 feet (30 m) on center. Provide in-head check valves for sloped areas with 0.5 feet (150 mm) or more in elevation change.

G205007 1.4 TEMPORARY IRRIGATION

Provide ultra-violet resistant pipe and fittings for above-grade, temporary irrigation. Only non-pressure pipe is allowed above grade. Install irrigation systems intended to remain in place longer than one year below grade.

G205007 1.5 NON-POTABLE IRRIGATION

Provide lavender-colored pipe, sprinkler head and quick coupler caps, valve tags, signage, and associated filtration equipment.

G205007 1.5.1 Controller Charts

Provide one chart for each new controller or existing re-sequenced controller. The chart must be an actual plan reduced to fit inside maximum dimensions of the controller housing. Use black line print for chart and a different color to indicate each station area of coverage. After chart is completed and approved for final acceptance, seal chart between two 20 mil (0.5 mm) pieces of clear plastic. Affix the chart to the inside of the controller cabinet door using approved mastic or fastening system. Provide one additional copy of the chart in electronic format. Additionally, the Landscape Architect of Record must provide the Base with a maintenance plan and schedule as part of the turn-over items.

-- End of Section --

SECTION G30

SITE CIVIL/MECHANICAL UTILITIES
11/10

G30 GENERAL

RFP Part 3 including the Engineering System Requirements (ESR) provide project specific requirements. The RFP Part 4, Performance Technical Sections (PTS) provide generalized technical requirements that apply to multiple facility types and include more requirements than are applicable to any one project. Therefore, only the RFP Part 4 requirements that apply to the project and further define the RFP Part 3 project specific requirements are required.

G30 1.1 DESIGN GUIDANCE

Provide the design and installation in accordance with the following references. This Performance Technical Specification (PTS) adds clarification to the fundamental requirements contained in the following Government Standards. The general requirements of this PTS section are located in PTS Section Z10, *General Performance Technical Specification*.

G30 1.1.1 Industry Standards and Codes

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

G30 1.1.2 Government Standards

UNIFIED FACILITIES CRITERIA (UFC)

UFC 1-200-01	General Building Requirements(A reference in this PTS section to UFC 1-200-01 requires compliance with the Tri-Service Core UFCs that are listed in UFGS Section 01 33 10.05 20, which includes the following significant UFC(s):UFC 3-201-01, Civil EngineeringUFC 3-401-01, Mechanical Engineering)
UFC 3-800-10N	Environmental Engineering for Facility Construction

G30 1.2 QUALITY ASSURANCE

Materials and assemblies installed in the work shall be inspected and found to be in compliance with industry standards and these specifications prior to acceptance of the work. Items found not to be in compliance shall be removed, or corrective measures taken, to assure compliance with the referenced standard. The Contractor shall perform field tests and provide labor, equipment and incidentals required for testing.

G30 1.2.1 Materials

All materials shall be new, and shall bear the label of standardizing agency whenever standards have been established and label service is normally and regularly furnished by the agency. All equipment provided shall be listed and labeled suitable for the specified purpose,

environment, and application and installed in accordance with manufacturer’s recommendations.

G30 1.2.2 Additional Work

Provide such other labor and materials as are required for a complete and usable system in accordance with the requirements of the criteria listed, regardless of whether such materials and associated labor are called for elsewhere in this RFP.

G30 1.2.3 Qualifications of Well Drillers for Water Supply Wells

If required by the state waterworks' regulations, the well driller shall be certified by the state and shall remain certified while constructing the well.

G30 1.2.4 Qualifications of Coating Contractors for Water Storage Tanks

All contractors and subcontractors that perform surface preparation or coating application shall be certified by the Society for Protective Coatings (formerly Steel Structures Painting Council)(SSPC) to the requirements of SSPC QP 1 prior to contract award, and shall remain certified while accomplishing any surface preparation or coating application.

G30 1.2.5 Qualifications of Oil/Water Separator Manufacturers

Manufacturers shall have produced packaged oil/water separate units of similar size required for over five years.

G30 1.3 PERFORMANCE VERIFICATION AND ACCEPTANCE TESTING

Compliance with the requirements will be determined by a review of the design and construction submittals and by field inspection. See Section 01 33 10.05 20, *Design Submittal Procedures*, and Section 01 33 00.05 20, *Construction Submittal Procedures*, for additional requirements.

Verification of satisfactory utility system performance shall be via Performance Verification Testing, as detailed in this section of the RFP. Verification of satisfactory performance shall also be via testing as detailed in the paragraph, "Field Quality Control", in applicable UFGS Specification Sections utilized.

G30 1.3.1 Water Supply Well Performance Verification

Upon completion of the permanent well, conduct performance testing for well capacity, drawdown and pump equipment and water quality testing in accordance with AWWA A100 and its appendices and the state waterworks' regulations.

G30 1.3.2 Water Distribution System Verification Testing

Provide testing on water mains and service lines in accordance with the state waterworks’ regulations and the following:

a. Ductile Iron and other materials: AWWA C600.
b. PVC: AWWA C605.

Do not begin testing on any section of a pipeline where concrete thrust blocks have been provided until at least 5 days after placing of the concrete.

G30 1.3.3 Water Booster Pump Station Verification Testing

Test the water booster pump station in accordance with the state waterworks' regulations. Conduct testing on discharge and site piping in accordance with tests for water distribution mains; see G30, paragraph 1.3.2. Test pumps, controls, and alarms, in operation, under design conditions to ensure proper operation of all equipment.

G30 1.3.4 Sanitary Sewer Distribution System Verification Testing

Provide testing on sewer mains and laterals in accordance with the state sewerage regulations.

G30 1.3.4.1 Deflection Test

Deflection of pipe in the installed pipeline under external loads shall not exceed 4.5 percent of the average inside diameter of pipe, in accordance with ASTM D 2412.

G30 1.3.4.2 Leakage Tests

G30 1.3.5 Sanitary Sewer Manholes Verification Testing

Provide testing on sanitary sewer manholes in accordance with the state sewerage regulations. At minimum, perform hydraulic testing in accordance with ASTM C 969M (ASTM C 969).

G30 1.3.6 Wastewater Pump Station Verification Testing

Test the wastewater pump station in accordance with the state sewerage regulations. Conduct testing on discharge piping and force main in accordance with tests for water distribution mains; see G30, paragraph 1.3.2. Test pumps, controls, and alarms, in operation, under design conditions to ensure proper operation of all equipment.

G30 1.3.7 Storm Sewer System Verification Testing

G30 1.3.7.1 Deflection Test

Deflection of pipe in the installed pipeline under external loads shall not exceed 4.5 percent of the average inside diameter of pipe, in accordance with ASTM D 2412.

G30 1.3.7.2 Leakage Tests for Storm Sewer Under Pavements

Test lines for leakage by either infiltration tests or exfiltration tests, or by low-pressure air tests in accordance with the following:

a. Exfiltration Tests:

ASTM C 969M (ASTM C 969) and perform calculations in accordance with its Appendix.

b. Low-pressure Air Tests:

1) Pipelines: ASTM C 924M (ASTM C 924) and perform calculations in accordance with its Appendix.

2) PVC plastic pipelines: UBPPA UNI-B-6 and perform calculations in accordance with its Appendix.

G30 1.4 DESIGN SUBMITTALS

Design Submittals shall be in accordance with UFGS section 01 33 10.05 20, *Design Submittal Procedures*, UFC 1-300-09N, *Design Procedures*, UFC 3-201-01, *Civil Engineering*, and UFC 3-401-01, *Mechanical Engineering*.

G30 1.5 CONSTRUCTION SUBMITTALS

Submit construction submittals in accordance with PTS Section Z10, *General Performance Technical Specifications*. In addition to the Z10 requirements, the Designer of Record (DOR) shall approve the following construction submittals as a minimum:

All test reports.

G30 1.6 COORDINATION

To the extent that site work is indicated on the RFP drawings, the Contractor shall verify that the locations and inverts of all site utility lines are coordinated with building utility lines. If necessary, the Contractor shall make adjustments to the locations and inverts indicated on the RFP drawings in accordance with applicable codes and standards.

G30 1.7 ANTITERRORISM (AT) STANDARDS

Incorporate the minimum AT standards indicated in UFC 4-010-01, *DoD Minimum Antiterrorism Standards for Buildings*.

G30 1.8 BACKFLOW PREVENTION

The Contractor shall submit backflow prevention training certificates and backflow preventer devices certification in accordance with Section 01 50 00.05 20 (01501N), *Temporary Facilities and Controls for Design-Build*.

G30 1.9 WATER STORAGE TANK

The Contractor shall submit a certificate signed by a registered professional engineer providing a (1) description of the entire tank and foundation structural design loading conditions; (2) description of structural design methods and codes used in establishing allowable stresses and safety factors; (3) statement that the structural design has been checked by experienced engineers specializing in hydraulic structures to ensure that design calculations for member sizes, dimensions and fabrication processes are as prescribed by ACI and AWWA standards; and (4) certification that the completed work was inspected in accordance with AWWA D100 or AWWA D103 as applicable.

G30 1.10 NACE CERTIFIED CATHODIC PROTECTION SPECIALIST QUALIFICATIONS

Submit prior to site welding. Certifications shall not be more than one year old. Submit documentation of NACE certification.

G30 1.11 EXCAVATION, BACKFILLING AND COMPACTION OF UTILITIES

Refer to Section G10, *Site Preparation*.

G30 1.12 DELIVERY, STORAGE AND HANDLING OF MATERIALS

Inspect materials delivered to site for damage. Unload and store with minimum handling. Store materials on site in enclosures or under protective covering. Store plastic piping, jointing materials and rubber gaskets under

cover out of direct sunlight. Do not store materials directly on the ground. Keep inside of pipes, fittings, valves, and hydrants free of dirt and debris. Handle in a manner to ensure delivery to the trench in sound undamaged condition. Take special care to avoid injury to coatings and linings on pipe and fittings; make satisfactory repairs if coatings or linings are damaged. Carry, do not drag pipe to the trench.

G3010 WATER SUPPLY

G3010 1.1 WATER SYSTEM DESIGN

The Contractor shall determine domestic and fire demands for the facility and shall verify the design of all components of the domestic and fire protection supply systems. The water system design and construction shall be in accordance with UFC 3-230-01, *Water supply: Storage, Distribution, and Transmission;* the state waterworks' regulations, and the utility provider's requirements. Design the water supply systems to provide required flows and maintain residual pressures based upon peak demands.

If the new water system is an extension of an existing water system, the Contractor shall obtain all necessary static pressure, residual pressure and flow characteristics of the existing distribution system by actual field tests. The Contractor shall conduct flow and pressure tests and provide design calculations that show the existing lines are capable of handling the additional flows. The new water system shall connect to the nearest existing fitting or water line.

The Contractor shall design the connections to the water system including the necessary meter assemblies and backflow-preventing devices in accordance with the requirements of the Activity or utility provider and the state waterworks regulations.

Wherever possible, valve boxes and all other utility access structures shall be located out of paved areas.

G301001 WELL SYSTEMS

The potable water well system shall be designed and constructed in accordance with AWWA A100 and its appendices; the state waterworks' regulations, and the system owner's preferences and requirements.

G301001 1.1 WATER METER

Provide a water meter on the well pump discharge piping aboveground in a pump enclosure or in a meter vault underground. Provide type of water meter and remote reading capability in accordance with system owner's preferences and requirements: AWWA C700, displacement type; AWWA C701, turbine type; or AWWA C702, compound type.

G301001 1.2 TEST HOLE

Drill test hole(s) at the well site before construction of the permanent well to determine the existing site-specific geologic/hydrologic conditions and groundwater-quality parameters. A test hole may be incorporated into the finished construction provided it meets the requirements for a finished well. Seal test holes not used in finished construction as recommended in accordance with AWWA C654 and the state waterworks' regulations. Upon completion of test hole, provide recommendations for permanent wells and submit data obtained at each well site. Include with the recommendations the appropriate depth, details of construction, length and location of screens, screen openings, gravel size, grout, and an estimation of the quantity of water that can be obtained from each water-bearing stratum and

from each completed well. Submit electric log, a drillers log drawn to scale with coarseness and fineness modulus of each strata, time penetration log (time to drill through each formation), and sieve analysis to substantiate recommendations.

G301001 1.3 WELL CONSTRUCTION

G301001 1.3.1 Well Development

Provide well development in accordance with AWWA A100 and the state waterworks' regulations.

G301001 1.3.2 Disinfection

Disinfect well, equipment, and material in accordance with AWWA C654 and the state waterworks' regulations. Provide a sanitary seal for the well to prevent contamination until the pump foundation and pump are installed on the well.

G301001 1.4 ABANDONMENT OF EXISTING WELLS

Abandon and seal existing wells in accordance with AWWA A100 and the state waterworks' regulations.

G301002 POTABLE WATER DISTRIBUTION

G301002 1.1 WATER SYSTEM DESIGN

Provide all materials, equipment, labor, testing, and miscellaneous related items for water distribution mains and service lines to the facility and connections to the existing water system in accordance with UFC 3-23-01, *Water Supply: Storage, Distribution, and Transmission*; the utility provider's requirements; and the state waterworks' regulations; whichever is more stringent.

Available flow at the residual pressure at each point of connection shall be determined by conducting flow tests in accordance with AWWA M17 and NFPA 291.

Water main piping, service lines, fittings, valves, accessories and all other materials shall meet the American Water Works Association (AWWA) standards for a minimum system working pressure of 150 psi (1050 kPa).

G301002 1.2 WATER DISTRIBUTION MAINS

For underground applications, water mains 12 inches (300 mm) in diameter and less shall be ductile iron, PVC, or high density polyethylene (HDPE). Water mains deeper than 10 feet (3.0 m) or larger than 12 inches (300 mm) in diameter shall be ductile iron.

For aboveground applications, water mains shall be flanged ductile iron pipe.

G301002 1.2.1 Materials

a. Ductile Iron Pressure Pipe

1) Pipe: AWWA C151, Pressure Class 350.

2) Fittings: AWWA C110 or AWWA C153.

3) Interior Lining: AWWA C104.

4) Exterior Protection (if required): AWWA C105, polyethylene encasement.

b. PVC Pressure Pipe

1) Pipe: AWWA C900, Pressure Class 150.

2) Fittings: Ductile Iron (AWWA C110 or AWWA C153).

c. HDPE Pressure Pipe: AWWA C906.

d. Flanged Ductile Iron Pipe

1) Pipe: AWWA C115 and its appendices.

2) Fittings: AWWA C110 or AWWA C153.

3) Lining: AWWA C104.

G301002 1.2.2 Installation

a. Ductile Iron: AWWA C600.
b. PVC: AWWA C605.
c. HDPE: applicable requirements of ASTM D 2774.

Provide a continuous length of tracer wire for the full length of each run of nonmetallic pipe.

G301002 1.2.3 Connections to Existing Water Lines

Make connections to existing water lines after approval from the system owner is obtained and with a minimum interruption of service on the existing line. Make connections to existing lines under pressure in accordance with the recommended procedures of the manufacturer of the pipe being tapped.

G301002 1.3 WATER SERVICE LINES

Water service lines less than 4 inches (100 mm) in diameter shall be copper tubing, PVC, or polyethylene (PEX) tubing. Water service lines 4 inches (100 mm) and 6 inches (150 mm) in diameter shall be ductile iron pipe and PVC pressure pipe; see G301002, paragraph 1.2, "Water Distribution Mains" for additional requirements for ductile iron and PVC piping.

G301002 1.3.1 Materials

a. Copper Tubing

1) Pipe: ASTM B 88M (ASTM B 88), Type K.

2) Fittings for Solder-Type Joint: ANSI B16.8 or ASME B16.22.

3) Fittings for Compression-Type Joint: ASME B16.26, flared tube type.

b. PVC Pressure Pipe

1) Pipe: ASTM D1785, Schedule 40 or ASTM D 2241, with SDR rating for 160 psi (1.1 MPa) pressure rating.

2) Fittings: ASTM D 2466.

3) Joints: Elastomeric gaskets for pressure rating; solvent cement joints, ASTM D 2564.

c. Polyethylene Tubing: AWWA C901.

G301002 1.3.2 Service Connections

Connect service lines 2-inch (50 mm) diameter or less to the main by a corporation stop and install a gate valve on service line below the frostline.

a. Ductile-iron water mains: AWWA C600.
b. PVC water mains: UBPPA UNI-B-8 and the recommendations of AWWA M23, Chapter 9, "Service Connections."

G301002 1.3.3 Installation

Install pipe, fittings and accessories in accordance with manufacturer's instructions.

a. Metallic Piping: applicable requirements of AWWA C600.
b. PVC: applicable requirements of ASTM D 2774 and ASTM D 2855.
c. Polyethylene: applicable requirements of ASTM D 2774 and ASTM F 645.

G301002 1.4 CORROSION PROTECTION

G301002 1.4.1 Insulating Joints

Provide insulating joints to prevent contact between dissimilar metals at the joint between adjacent sections of piping in accordance with the pipe manufacturer’s recommendations. Ensure that there is no metal-to-metal contact between dissimilar metals after the joint has been assembled.

To prevent the possibility of bi-metallic corrosion, service lines of dissimilar metal to the water mains and the attendant corporation stops shall be wrapped with polyethylene or suitable dielectric tape for a minimum clear distance of 3 feet (900 mm) from the main.

G301002 1.5 VALVES

Valves shall be the same diameter and have the same joint ends as the mains to which they are installed. Each type of valve shall be of one manufacturer.

G301002 1.5.1 Gate Valves

G301002 1.5.1.1 Location

Valves shall be installed at all new points of connection. At a minimum, valves shall be located to ensure that no more than two fire hydrants will be out of service in the event of a single break in a water main. Valves shall be located outside of pavement and heavy traffic areas whenever possible.

G301002 1.5.1.2 Gate Valves 3-inch (75 mm) and Larger in Diameter

a. Valves (20-inch and smaller in diameter): AWWA C509 or AWWA C515, nonrising stem and of one manufacturer.
b. Valves (greater than 20-inch in diameter): AWWA C500.
c. Valves for Indicator Post: AWWA C500 with indicator post flange in accordance with applicable requirements of UL 262.
d. Interior Coating: AWWA C550.

G301002 1.5.1.3 Gate Valves Smaller than 3-inch (75 mm) in Diameter

MSS SP-80, Class 150, solid wedge. Valves shall have flanged or threaded end connections, with unions on both sides of the valve and a handwheel operator.

G301002 1.5.1.4 Valve Box

Provide a cast iron, adjustable, valve box for each gate valve on buried piping. Valve boxes shall be of a size suitable for the valve on which it is to be used with a minimum diameter of 5-1/4 inches (130 mm). Provide a round head and cast the word "WATER" on the lid.

G301002 1.5.2 Check Valves

Valves sized 2-inches (50 mm) to 24-inches (600 mm) shall be swing-check type (AWWA C508) and have a protective epoxy interior coating conforming to AWWA C550. For underground applications, provide check valve in a valve vault.

G301002 1.5.3 Air Release, Air/Vacuum, and Combination Air Valves

AWWA C512 and AWWA M51.

G301002 1.5.4 Corporation Stops

If service lines 2-—inch diameter or less are tapping water mains, provide corporation stops. The corporation stops shall be ground key type, bronze, ASTM B61 or ASTM B62.

G301002 1.5.5 Installation of Valves

Make and assemble joints to valves as specified for making and assembling the same type of joints between pipe and fittings.

G301002 1.6 WATER METERS

Provide water meter and remote reading as required by the utility provider and in accordance with AWWA standards.

G301002 1.7 BACKFLOW PREVENTION

Provide backflow prevention and cross connection control in accordance with AWWA M-14 and governing local/state plumbing codes and waterworks' regulations.

G301002 1.8 FIRE HYDRANTS

Fire hydrants must be of one manufacturer and in accordance with UFC 3-600-01, *Fire Protection Engineering*. Coordinate with the project's fire protection designer of record. Provide protection for fire hydrants located in areas subject to vehicle damage. Fire hydrants must have National Standard threads on hose and pumper connections. Provide a 6 inch (150 mm) inlet, two 2.5 inch (62 mm) hose connections and one pumper connection sized to accommodate local fire department equipment requirements. Stencil hydrant number and main size on the hydrant barrel using black stencil paint.

a. Dry Barrel Fire Hydrants: AWWA C502 with frangible sections.
b. Wet Barrel Fire Hydrants: AWWA C503 or UL 246, "Wet Barrel" design, with breakable features.
c. Installation: Install hydrants with the pumper connection facing the

adjacent paved surface. If there are two, paved adjacent surfaces, contact the Contracting Officer for further direction.

G301002 1.9 THRUST RESTRAINT

Provide thrust restraint for all piping, valves, fittings, and other appurtenances of the water distribution system.

a. Concrete Thrust Blocks: AWWA C600.
b. Restrained Joints: Pipe manufacturer's recommendations and required length of pipe to be restrained calculated in accordance with UFC 3-201-01, *Civil Engineering*.

G301002 1.10 DISINFECTION

Disinfect new water piping and existing water piping affected by Contractor's operations in accordance with the state waterworks' regulations and AWWA C651.

G301003 POTABLE WATER STORAGE

G301003 1.1 POTABLE WATER STORAGE TANKS

Provide potable water storage facilities in accordance with UFC 3-230-01, *Water Supply: Storage, Distribution, and Transmission;* and the state waterworks' regulations.

An elevated, steel water storage tank shall be in accordance with AWWA D100. A ground, steel water storage tank shall be in accordance with AWWA D100 for welded tanks and AWWA D103 for bolted tanks.

G301003 1.2 TANK ACCESSORIES

Piping and valves shall be in accordance with G301002. An altitude valve shall be installed in a valve vault with appropriate shut off valves and check valve.

G301003 1.3 TANK COATINGS

G301003 1.3.1 Interior Coating System

Provide interior coating system complying with NSF 61 and the state waterworks' regulations.

G301003 1.3.2 Exterior Coating System

Primer coat shall be epoxy polyamide, MIL-DTL-24441/19 (Formula 159, Type III). Intermediate coat shall be epoxy polyamide, MIL-DTL-24441/31 (Formula 152, Type IV, White (Tinted)). Tint to approximately FED-STD-595 color number 27778 parchment using pigment dispersions prepared for epoxy paint tinting. Manufacturer shall tint material and appropriately label. All other requirements of this Military Specification apply.

Provide polyurethane coating topcoat of MIL-PRF-85285, Type II, Beige FED-STD-595 color number 27769 in gloss. The color of the final coat shall be approved in writing by the Contracting Officer before application begins.

G301004 FIRE PROTECTION WATER DISTRIBUTION

G301004 1.1 GENERAL REQUIREMENTS

Refer to applicable portions of Section G301002 and Section D40, *Fire Protection Systems*. Water main piping, service lines, fittings, valves, accessories and all other materials shall meet the American Water Works Association (AWWA) standards for a minimum system working pressure of 200 psi (1380 kPa).

G301004 1.2 DETECTOR CHECKS

UL 312; detector check shall include bypass meter, piping, gate valves, check valve and connections to detector check valve. Set valve to allow minimal water flow through bypass meter when major water flow is required.

G301004 1.3 FIRE DEPARTMENT CONNECTIONS

UL 405.

G301004 1.4 INDICATOR POSTS

UL 789.

G301005 FIRE PROTECTION WATER STORAGE

Refer to G301003.

G301006 NON-POTABLE WATER DISTRIBUTION

Refer to G301002; note that system disinfection is not required.

G301007 PUMPING STATIONS

If a pump station is allowed, provide a packaged booster pump station including pumps, piping, valves, sensors, controls, and accessories to maintain the water system pressure in accordance with UFC 3-230-01, *Water Supply: Storage, Distribution, and Transmission;* and the state waterworks' regulations.

The packaged booster pump station shall have an Underwriter’s Laboratories (UL) label indicating compliance of the equipment under the packaged pumping systems UL listing category. This label shall be inclusive of the entire station with enclosure so as to demonstrate compliance with the National Electrical Code requirements for working clearances and wiring procedures.

All interior coatings of pumps, piping, valves and other accessories shall be a National Standard Foundation (NSF) Standard 61 certified material for potable water.

G301008 PACKAGED WATER TREATMENT PLANTS

Provide packaged water treatment plants in accordance with UFC 3-230-03, *Water Treatment;* for pipeline materials and the state waterworks' regulations for treatment plant requirements.

G3020 SANITARY SEWER

G3020 1.1 GENERAL REQUIREMENTS

The gravity sanitary sewage collection system shall be designed and constructed in accordance with UFC 3-240-01, *Wastewater Collection;*and the state sewer collection and treatment regulations. The new sanitary sewage collection system shall connect to the nearest existing sanitary manholes

or sanitary line adjacent to the project site. The Contractor shall provide design calculations that show the existing system is capable of handling the additional flows.

In areas where chemicals and other substances may be stored (including mechanical and electrical rooms), the contractor shall eliminate floor drains or shall make provisions made to prevent spills from entering the sanitary sewer system. If there is process flow from equipment, discharge can be hard piped, with air gap, to the sanitary sewer.

Wherever possible, manholes and all other utility access structures shall be located out of paved areas.

G302001 SANITARY SEWER PIPING

G302001 1.1 GENERAL REQUIREMENTS

Provide all materials, equipment, labor, testing, and miscellaneous related items to provide sanitary sewage lines necessary for collection and services from the buildings.

G302001 1.2 GRAVITY SEWER PIPING

Gravity sewer mains and laterals shall be PVC sewer pipe and fittings, except under roadways or at depths greater than 10 feet (3.0 m) where ductile iron pipe shall be provided.

G302001 1.2.1 Materials

a. PVC Gravity Sewer Pipe

1) Piping and Fittings: ASTM D 3034, SDR 35.

2) Joints: ASTM D 3212 and ASTM F 477.

b. Ductile Iron Gravity Sewer Pipe

1) Piping: ASTM A 746. Provide required Thickness Class based on design information and methods in ASTM A 746.

2) Fittings: AWWA C110 or AWWA C153.

3) Joints: AWWA C111.

4) Interior Coating: AWWA C104.

5) Exterior Protection (if required): AWWA C105, polyethylene encasement.

G302001 1.2.2 Connections to Existing Lines

Obtain approval from the Contracting Officer before making a connection to an existing line. Conduct work so that there is minimum interruption of service on existing line and provide a new manhole at the connection point.

G302001 1.2.3 Installation

Install pipe, fittings and accessories in accordance with manufacturer's instructions.

a. PVC: ASTM D 2321. Do not use ASTM D 2321 Class IV or V materials for bedding, haunching or initial backfill materials.

b. Ductile Iron: AWWA C600.

G302001 1.3 PIPING FOR CLEANOUTS

G302001 1.3.1 Materials

a. Cast-Iron Soil Pipe for Cleanouts

1) Pipe: ASTM A 74, service.

2) Joints: ASTM C 564 compression-type rubber gaskets.

3) Exterior Protection (if required): AWWA C105, polyethylene encasement.

G302001 1.3.2 Installation

Install cast iron pipe and fittings in accordance with the recommendations of the pipe manufacturer.

G302002 SANITARY SEWER MANHOLES & CLEANOUTS

G302002 1.1 GENERAL REQUIREMENTS

Provide all materials, equipment, labor, testing, and miscellaneous related items for the sanitary manholes in accordance with the following:

a. Manhole rim elevations shall be set flush with finished surface of paved areas or 1 inch (25 mm) above finished grade in unpaved areas.
b. Resilient connectors for making joints between manhole and pipes entering manhole shall conform to ASTM C 923M (ASTM C 923).
c. Provide drop manholes when a gravity sewer pipe enters a manhole at an elevation of 24 inches (610 mm) or more above the manhole invert.

G302002 1.2 PRECAST CONCRETE MANHOLES

ASTM C 478M (ASTM C 478); base and first riser shall be monolithic.

Precast manhole sections shall have:

a. ASTM C 990M (ASTM C 990) butyl gaskets;
b. ASTM C 443M (ASTM C 443) rubber O-ring joints; or
c. AASHTO M 198, Type B preformed plastic gaskets.

G302002 1.3 CAST-IN-PLACE CONCRETE MANHOLES

Reinforced concrete; designed according to ASTM C 890 for A-16 (AASHTO HS20-44), heavy-traffic, structural loading. Concrete work shall be in accordance with ACI 301M (ACI 301) and ACI 350-01; provide a minimum compressive strength of 4000 psi (28 MPa).

G302002 1.4 MANHOLE FRAMES AND COVERS

FS A-A-60005; cast iron or ductile iron; designed to accommodate the traffic loadings. The word "Sewer" shall be stamped or cast into covers so that it is plainly visible.

G302002 1.5 MANHOLE STEPS

a. Zinc-coated steel: 29 CFR 1910.27.
b. Plastic or rubber coating pressure molded to steel: ASTM D 4101,

copolymer polypropylene; or ASTM C 443M (ASTM C 443), except shore A durometer hardness shall be 70 plus or minus 5.

Aluminum steps or rungs will not be permitted.

Steps are not required in manholes less than 4 feet (1.2 m) deep.

G302002 1.6 MANHOLE CONSTRUCTION

Where a new manhole is constructed on an existing line, remove existing pipe as necessary to construct the manhole. Cut existing pipe so that pipe ends are approximately flush with the interior face of manhole wall, but not protruding into the manhole. For changes in direction of the sewer and entering branches into the manhole, make a circular curve in the manhole invert of as large a radius as manhole size will permit. For cast-in-place concrete, no parging will be permitted on interior manhole walls.

G302002 1.7 CONNECTIONS TO EXISTING MANHOLES

Pipe connections to existing manholes shall be centered on the manhole. Holes for the new pipe shall be of sufficient diameter to allow packing cement mortar around the entire periphery of the pipe but no larger than 1.5 times the diameter of the pipe. Cutting the manhole shall be done in a manner that will cause the least damage to the walls.

G302002 1.8 CLEANOUTS

Construct cleanouts of cast iron soil pipe and fittings; see G302001, paragraph 1.3.

G302003 LIFT STATIONS AND PUMPING STATIONS

G302003 1.1 GENERAL REQUIREMENTS

If a pump station is allowed, provide all materials, equipment, labor, testing and miscellaneous related items for a packaged lift or pump station system for the facility in compliance with the UFC 3-240-01, *Wastewater Collection*; the state sewerage regulations; and the utility provider's requirements.

G302003 1.2 SUBMERSIBLE PUMPS

Pumps handling raw wastewater shall be capable of passing spheres of at least 3 inches (75 mm) in diameter. The pump's suction and discharge openings shall be at least 4 inches (100 mm) in diameter.

Provide submersible type sewage pumps, with guide rail system. Include ASTM A48M (ASTM A48), Class 25, nonclog, cast-iron impeller; and hermetically sealed motor with moisture-sensing probe, mechanical seals, and waterproof power cable. Guide rail system shall be constructed of stainless steel. Provide a stainless steel lifting chain for raising and lowering the pump in the basin.

G302003 1.3 GRINDER PUMPS

Provide grinder-type sewage pumps, with guide rail system. Include stainless steel or bronze impeller and hermetically sealed motor with moisture-sensing probe, mechanical seals, and waterproof power cable. Guide rail system shall be constructed of stainless steel. Provide a stainless steel lifting chain for raising and lowering the pump in the basin.

G302003 1.4 SUCTION LIFT PUMPS

Pumps handling raw wastewater shall be capable of passing spheres of at least 3 inches (75 mm) in diameter. The pump's suction and discharge openings shall be at least 4 inches (100 mm) in diameter.

Provide dry-chamber-mounting, vacuum-primed, nonclog sewage pumps located in dry compartment above wet pit. Include ASTM A48M (ASTM A48), Class 25, nonclog, cast iron impeller; mechanical or stuffing box seals; pedestal mounted motor; and suction piping extending to bottom of wet pit.

Suction-lift pumps shall be capable of automatic rapid self priming and re-priming at the "lead pump on" elevation. Suction piping shall not exceed 25 feet (7.6 meters) in total length. Priming lift at the ‘‘lead pump on’’ elevation shall include a safety factor of at least 4 feet (1.2 meters) from the maximum allowable priming lift for the specific equipment at design operating conditions. The combined total of dynamic suction-lift at the "pump off" elevation and the required net positive suction head at design operating conditions shall not exceed 22 feet (6.7 meters).

G302003 1.5 PUMP MOTOR

Provide pump motor sized to accommodate pump operation along the entire impeller curve.

G302003 1.6 STATION PIPING WITHIN WET WELL AND VALVE VAULT

G302003 1.6.1 Piping Less than 4-Inch (100 mm) in Diameter

a. PVC Pressure Pipe

1) Pipe: ASTM D 1785, Schedule 80.

2) Fittings: Schedule 80 socket fittings, ASTM D 2467; Schedule 80 threaded fittings, ASTM D 2464.

G302003 1.6.2 Piping 4 inch (100 mm) Diameter and Larger

a. Flanged Ductile Iron Pipe

1) Pipe: AWWA C115 and its appendices.

2) Fittings: AWWA C110 or AWWA C153.

3) Lining: AWWA C104.

G302003 1.7 FORCE MAINS

G302003 1.7.1 Force Mains for Submersible and Suction Lift Pumps

Force mains shall be at least 4 inches (100 mm) in diameter and shall be either ductile iron or PVC pressure pipe.

a. Ductile Iron Pressure Pipe

1) Pipe: AWWA C151, Pressure Class 350.

2) Fittings: AWWA C110 or AWWA C153.

3) Interior Lining: AWWA C104.

4) Exterior Protection (if required): AWWA C105,

polyethylene encasement.

b. PVC Pressure Pipe

1) Pipe: AWWA C900, Pressure Class 150.

2) Fittings: Ductile Iron (AWWA C110 or AWWA C153).

G302003 1.7.2 Force Mains for Grinder Pumps

Force mains less than 4 inches (100 mm) in diameter shall be PVC pressure pipe:

a. PVC Pressure Pipe

1) Pipe: ASTM D 1785, Schedule 40 or ASTM D 2241, with SDR rating for 160 psi (1.1 MPa) pressure rating.

2) Fittings: ASTM D 2466.

3) Joints: Elastomeric gaskets for pressure rating; solvent cement joints, ASTM D 2564.

G302003 1.8 PIPING ACCESSORIES

G302003 1.8.1 Insulating Joints

Provide between pipes of dissimilar metals a rubber gasket or other approved type of insulating joint or dielectric coupling to effectively prevent metal-to-metal contact between adjacent sections of piping.

G302003 1.8.2 Accessories

Provide flanges, connecting pieces, transition glands, transition sleeves, and other adapters as required.

G302003 1.8.3 Flexible Flanged Coupling

Provide flexible flanged coupling applicable for sewage as indicated. Use flexible flanged coupling designed for a working pressure of 350 psi (2400 kPa).

G302003 1.9 VALVES

Suitable shutoff and check valves shall be provided on the discharge line of each pump. Locate the check valve between the shutoff valve and the pump. Locate valves in accordance with state sewerage regulations. Check valves shall be suitable for the material being handled and placed on the horizontal portion of the discharge piping except for ball check valves, which may be placed in the vertical run. Valves shall be capable of withstanding normal pressure and water hammer. Use valves from one manufacturer.

G302003 1.9.1 Shut Off Valves

G302003 1.9.1.1 Shut Off Valves Less than 4 Inch (100 mm) in Diameter

PVC ball valves.

G302003 1.9.1.2 Shut Off Valves 4 Inch (100 mm) and Larger in Diameter

AWWA C509 or AWWA C515, nonrising stem, and flanged. Provide valves with handwheels that open by counterclockwise rotation of the valve stem. Provide epoxy coating in accordance with AWWA C550.

G302003 1.9.2 Check Valves

G302003 1.9.2.1 Check Valves Less than 4-Inch (100 mm) in Diameter

Neoprene ball check valve with integral hydraulic sealing flange, designed for a hydraulic working pressure of 175 psi (1200 kPa).

G302003 1.9.2.2 Check Valves 4-Inch (100 mm) and Larger in Diameter

AWWA C508, flanged. Provide a nonclog, swing check valve rated for not less than 175 psig (1200 kPa) working pressure capable of passing 3-inch (75 mm) diameter solids.

G302003 1.9.3 Air Relief Valves

Provide air relief valves at high points in the force main to prevent air locking in accordance with AWWA M51. Provide vacuum relief valves, where required, to relieve negative pressures on force mains.

G302003 1.10 IDENTIFICATION TAGS AND PLATES

Provide valves with tags or plates numbered and stamped for their usage. Use plates and tags of brass or nonferrous material and mounted or attached to the valve.

G302003 1.11 THRUST RESTRAINT

Provide thrust restraint for force mains, valves and other features of the wastewater distribution system.

a. Concrete Thrust Blocks: AWWA C600.
b. Restrained Joints: Pipe manufacturer's recommendations and required length of pipe to be restrained calculated in accordance with UFC 3-201-01, *Civil Engineering*.

G302003 1.12 STATION CONTROL SYSTEM

G302003 1.12.1 Operating Controls

G302003 1.12.2 Alarm Controls

Provide alarms for all pumping and lift stations; at minimum provide alarms for high level, power failure, pump failure, unauthorized entry or any cause of station malfunction. Provide alarms as required by the pump manufacturer to obtain warranty.

G302003 1.12.3 Telemetry

If required, provide a telemetry system in accordance with state sewer collection and treatment regulations and system owner's requirements to relay alarms to a facility that is manned 24 hours a day.

G302003 1.13 UNDERGROUND ENCLOSURES

G302003 1.14 STATION ACCESSORIES

G302003 1.14.1 Ventilation

Covered wet wells shall have provisions for air displacement venting to the outside. Galvanized ASTM A 53/A 53M pipe with insect screening.

Provide adequate ventilation for all pump stations.

G302003 1.14.2 Metering

Provide devices for measuring wastewater flow at all pumping stations. Provide indicating, totalizing and recording flow measurement at pumping stations with a 1200 gpm (76 l/s) or greater design peak hourly flow. For smaller stations, provide elapsed time meters in conjunction with pumping rate tests.

G302003 1.14.3 Pipe and Valve Supports

Use schedule 40 galvanized steel piping conforming to ASTM A 53/A 53M for pipe and valve supports. Provide either ANSI B16.3 or ANSI B16.11 galvanized threaded fittings.

G302003 1.14.4 Miscellaneous Metals

Use stainless steel bolts, nuts, washers, anchors, and supports for installation of equipment.

G302004 PACKAGED SANITARY SEWER TREATMENT PLANTS

Provide packaged wastewater treatment facilities in accordance with UFC 3-240-02, *Domestic Wastewater Treatment;* for pipeline materials and the state sewer collection and treatment regulations for treatment plant requirements.

G302005 SEPTIC TANKS

Provide septic tanks in accordance with the state and treatment regulations and the International Private Sewage Disposal Code 2000.

G302006 DRAIN FIELDS

Provide drain fields in accordance with the state and treatment regulations and the International Private Sewage Disposal Code 2000.

G302090 OTHER SANITARY SEWER

G302090 1.1 OIL/WATER SEPARATOR

Refer to G303090.

G3030 STORM SEWER

Provide all materials, equipment, labor, testing, and miscellaneous related items to provide storm drainage collection system necessary to drain the site. The storm sewer collection system shall be designed and constructed in accordance with UFC 3-201-01, *Civil Engineering*; the utility provider's requirements; and the state stormwater management laws and regulations. Design project site to prevent stormwater runoff in excess of the capacity of the existing utility system.

G303001 STORM SEWER PIPING

G303001 1.1 PIPING

Storm sewer piping less than 12 inches (300 mm) in diameter shall be PVC or ductile iron. Storm sewer piping 12 inches (300 mm) and larger in diameter shall be reinforced concrete or corrugated steel; corrugated aluminum and HDPE pipe may only be used when written approval is received by the Government's Civil Reviewer or indicated in another part of the RFP.

Subsurface drainage piping shall be perforated PVC or HDPE.

G303001 1.1.1 Materials

a. PVC Pipe

1) Piping and Fittings: ASTM D 3034, SDR 35.

2) Joints: ASTM D 3212 and ASTM F 477.

b. Ductile Iron Pipe

1) Piping: ASTM A 746. Provide required Thickness Class based on design information and methods in ASTM A 746.

2) Fittings: AWWA C110 or AWWA C153.

3) Joints: AWWA C111.

4) Interior Coating: AWWA C104.

5) Exterior Protection (if required): AWWA C105, polyethylene encasement.

c. Reinforced Concrete Pipe

1) Circular Pipe: ASTM C 76M (ASTM C 76). Provide required Class based on design information and methods in ASTM C 76M (ASTM C 76). Class III minimum.

2) Elliptical Pipe: ASTM C 507M (ASTM C 507). Provide required Class based on design information and methods in ASTM C 76M (ASTM C 76).

3) Joints:

a) ASTM C 990M (ASTM C 990) butyl gaskets;

b) ASTM C 443M (ASTM C 443) rubber O-ring joints; or

c) AASHTO M 198, Type B preformed plastic gaskets.

d. Corrugated Aluminum Pipe

1) Piping: ASTM B 745.

2) Joints: Coupling bands conforming to ASTM B 745.

3) Coating: Fully bituminous coated for all applications in accordance with ASTM A 849. For applications where piping is part of a piped storm sewer system (not a culvert), pipe shall be fully bituminous coated, invert (half) paved with concrete lining in accordance with ASTM A 849.

e. Corrugated Steel Pipe

1) Piping: ASTM A 760.

2) Joints: Coupling bands conforming to ASTM A 760.

3) Coating: Fully bituminous coated for all applications in accordance with ASTM A 849. For applications where piping is part of a piped storm sewer system (not a culvert), pipe shall be fully bituminous coated, invert (half) paved with concrete lining in accordance with ASTM A 849.

f. HDPE

1) Piping: AASHTO M 294 Type S, corrugated.

2) Joints: Soiltight.

g. Perforated PVC Pipe: ASTM D 2729.

h. Perforated HDPE Pipe

1) Piping and Fittings: AASHTO M 252, Type S, corrugated.

2) Joints: Soiltight.

G303001 1.1.2 Installation

Install piping in accordance with manufacturer’s recommendations.

a. PVC: ASTM D 2321. Do not use ASTM D 2321 Class IV or V materials for bedding, haunching or initial backfill materials.
b. Ductile Iron: AWWA C600.
c. Reinforced Concrete: ACPA 01-102 and 01-103.
d. Corrugated Aluminum: ASTM B 788.
e. Corrugated Steel: ASTM A 798.
f. HDPE: CPPA 100.
g. Perforated PVC and Perforated HDPE: ASTM D 2321. Do not use ASTM D 2321 Class IV or V materials for bedding, haunching or initial backfill materials.

G303001 1.2 PIPING FOR CLEANOUTS

G303001 1.2.1 Materials

a. Cast-Iron Soil Pipe for Cleanouts

1) Pipe: ASTM A 74, service.

2) Joints: ASTM C 564 compression-type rubber gaskets.

3) Exterior Protection (if required): AWWA C105, polyethylene encasement.

G303001 1.2.2 Installation

Install cast iron pipe and fittings in accordance with the recommendations of the pipe manufacturer.

G303002 STORM SEWER STRUCTURES

G303002 1.1 GENERAL REQUIREMENTS

Provide all materials, equipment, labor, testing, and miscellaneous related items for the drainage structures in accordance with the following:

a. Structure rim elevations shall be set flush with finished surface of paved areas or 1 inch (25 mm) above finished grade in unpaved areas.
b. Resilient connectors for making joints between manhole and pipes

entering manhole shall conform to ASTM C 923M (ASTM C 923).

c. Provide precast or cast-in-place concrete drainage structures, except cast-in-place concrete is required for airfield drainage structures, headwalls and gutters.

G303002 1.2 PRECAST CONCRETE INLETS

Provide work and materials in accordance with applicable requirements of the State Highway Specifications (SHS) and standards where the project is located.

G303002 1.3 CAST-IN-PLACE CONCRETE DRAINAGE STRUCTURES

Provide work and materials in accordance with drainage structures indicated in the State Highway Specifications (SHS) and standards where the project is located.

For airfield drainage structures, provide work and materials in accordance with FAA ACA 150/5370-10B.

G303002 1.4 DRAINAGE STRUCTURE FRAMES AND COVERS

FS A-A-60005; cast iron or ductile iron; designed to accommodate the traffic loadings. The word "Storm" shall be stamped or cast into covers so that it is plainly visible.

For airfield drainage structures, fabricate frames and covers of standard commercial grade steel welded by qualified welders in accordance with AWS D1.1/D1.1M. Covers shall be of rolled steel floor plate having an approved anti-slip surface. Steel frames and covers shall be hot dipped galvanized after fabrication. At the contractor's option, ductile iron covers and frames may be used for airfield drainage structures if designed for a minimum proof load of 100,000 pounds (45,000 kg) in lieu of the steel frames and covers. Covers shall be of the same material as the frames (i.e. ductile iron frame with ductile iron cover, galvanized steel frame with galvanized steel cover). Proof loading shall be performed in accordance with FS A-A-60005 and ASTM A 48/A 48M. Proof loads shall be physically stamped into the cover. Provide the Contracting Officer copies of previous proof load test results performed on the same frames and covers as proposed for this contract. The top of the structure shall be modified to accept the ductile iron structure in lieu of the steel structure indicated. The finished structure shall be level and non-rocking, with the top flush with the surrounding pavement.

G303002 1.5 DRAINAGE STRUCTURE STEPS

a. Zinc-coated steel: 29 CFR 1910.27.
b. Plastic or rubber coating pressure molded to steel: ASTM D 4101, copolymer polypropylene; or ASTM C 443M (ASTM C 443), except shore A durometer hardness shall be 70 plus or minus 5.

Aluminum steps or rungs will not be permitted.

Steps are not required in structures less than 4 feet (1.2 m) deep.

G303002 1.6 DRAINAGE STRUCTURE CONSTRUCTION

Where a new structure is constructed on an existing line, remove existing pipe as necessary to construct the structure. Cut existing pipe so that pipe ends are approximately flush with the interior face of structure wall, but not protruding into the structure.

G303002 1.7 CONNECTIONS TO EXISTING STRUCTURES

Pipe connections to existing structures shall be centered on the structure. Holes for the new pipe shall be of sufficient diameter to allow packing cement mortar around the entire periphery of the pipe but no larger than 1.5 times the diameter of the pipe. Cutting the structure shall be done in a manner that will cause the least damage to the walls.

G303002 1.8 CLEANOUTS

Construct cleanouts of cast iron soil pipe and fittings; see G303001, paragraph 1.2.

G303003 LIFT STATIONS

A stormwater pump station(s) will not be allowed.

G303004 CULVERTS

Culverts less than 12 inches (300 mm) in diameter shall be PVC or ductile iron. Culverts 12 inches (300 mm) and larger in diameter shall be reinforced concrete or corrugated steel; corrugated aluminum and HDPE pipe may only be used when written approval is received by the Government's Civil Reviewer or indicated in another part of the RFP.

Flared end sections shall the same material as pipe material.

Provide erosion control riprap in accordance with the State Highway Specifications (SHS) and standards where the project is located.

See G303001, paragraphs 1.1.1 and 1.1.2 for material and installation requirements.

G303005 HEADWALLS

Provide cast-in-place concrete headwalls in accordance with the State Highway Specification (SHS) and standards where the project is located.

G303006 EROSION & SEDIMENT CONTROL MEASURES

Refer to Section G103011.

G303007 STORMWATER MANAGEMENT

G303007 1.1 STORMWATER COLLECTION AND STORAGE

Provide permanent detention/retention ponds and other drainage features to regulate stormwater runoff and to prevent damage to the site and off-site. Integrate permanent stormwater management ponds, swales, and other stormwater management features, into the total site design to provide an aesthetically pleasing and harmonious landscape. Develop and construct the ponds and other drainage features in accordance with UFC 3-201-01, *Civil Engineering*, and the state stormwater management Laws and Regulations.

G303090 OTHER STORM SEWER

G303090 1.1 OIL/WATER SEPARATOR

Provide an oil/water separator to remove free oil from oil-in-water mixtures originating from proposed facility operations. Provide grit protection upstream of the oil/water separator.

The oil/water separator shall utilize coalescing media and conform to the applicable guidelines of the American Petroleum Institute (API).

Provide materials or a coating system which will protect the separator from the oil-in-water mixture, atmosphere, and in-situ soil conditions.

Use a separator with a completely removable cover.

G3040 HEATING DISTRIBUTION

G304001 OVERHEAD HOT WATER SYSTEMS

G304001 1.1 PIPING & FITTINGS

Hot water piping shall be ASTM A 53, Type E (electric-resistance welded), Grade A or B), or Type S (seamless, Grade A or B); black steel, Weight Class XS (Extra Strong). ASTM A 106, Grade A or B, black steel, Schedule 80 may be used.

G304001 1.2 INSULATION

Mineral fiber, calcium silicate, or cellular glass pipe insulation with aluminum jacket which matches existing or surrounding insulation. Paint jacket to suit Base Architectural Plan. The minimum insulation thickness shall be in accordance with the following table:

Table 1 Insulation Thickness for Hot Water Systems

Nominal Pipe Diameterinches (mm)	Mineral Fiberinches (mm)	Calcium Silicateinches (mm)	Cellular Glassinches (mm)
1.00 (25)	1.5 (38)	1.5 (38)	1.5 (38)
1.5 (38)	1.5 (38)	1.5 (38)	1.5 (38)
2.0 (51)	1.5 (38)	1.5 (38)	1.5 (38)
2.5 (64)	1.5 (38)	1.5 (38)	1.5 (38)
3.0 (76)	1.5 (38)	1.5 (38)	1.5 (38)
4.0 (100)	2.0 (51)	2.5 (64)	1.5 (38)
5.0 (125)	2.0 (51)	2.5 (64)	1.5 (38)
6.0 (150)	2.5 (64)	2.5 (64)	1.5 (38)
8.0 (200)	2.5 (64)	2.5 (64)	1.5 (38)
10.0 (250)	2.5 (64)	2.5 (64)	1.5 (38)
12.0 (300)	2.5 (64)	2.5 (64)	1.5 (38)
14.0 (350)	2.5 (64)	2.5 (64)	1.5 (38)
16.0 (400)	2.5 (64)	2.5 (64)	1.5 (38)
18.0 (450)	2.5 (64)	2.5 (64)	1.5 (38)

G304001 1.3 EXPANSION

Compensate for piping expansion by utilizing expansion loops and joints. Provide guided slip or flexible ball type expansion joints.

G304001 1.4 SUPPORTS

MSS SP-58 and MSS SP-69, adjustable supports with insulation protection saddles. Provide stainless steel axles for rollers. Provide support poles with guy wires and hardware.

G304002 OVERHEAD STEAM SYSTEMS

G304002 1.1 PIPING & FITTINGS

G304002 1.1.1 Steam Piping

Steam piping shall be ASTM A 53, Type E (electric-resistance welded, Grade A or B) or Type S (seamless, Grade A or B), black steel. Provide Weight Class STD (Standard) for welding end connections. Provide Weight Class XS (Extra Strong) for threaded end connections. ASTM A 106, Grade A or B, black steel, Schedule 40 may be used for pipe sizes through 9 inches (250 mm), and minimum pipe wall thickness of 0.35 inches (9.5 mm) for pipe sizes 12 inches (300 mm) and larger for welding end connections. Provide Schedule 80 for threaded end connections.

G304002 1.1.2 Condensate Piping

Condensate piping shall be ASTM A 53, Type E (electric-resistance welded), Grade A or B), or Type S (seamless, Grade A or B); black steel, Weight Class XS (Extra Strong). ASTM A 106, Grade A or B, black steel, Schedule 80 may be used.

G304002 1.2 INSULATION

Fibrous glass, calcium silicate, or cellular glass pipe insulation with aluminum jacket which matches existing or surrounding insulation. Paint jacket to suit Base Architectural Plan. The minimum insulation thickness shall be in accordance with the following tables:

Table 1 Insulation Thickness for Steam Systems

Nominal Pipe Diameterinches (mm)	Fibrous Glassinches (mm)	Calcium Silicateinches (mm)	Cellular Glassinches (mm)
1.00 (25)	3.5 (90)	4.0 (100)	*
1.5 (38)	3.5 (90)	4.0 (100)	*
2.0 (51)	3.5 (90)	4.0 (100)	*
2.5 (64)	3.5 (90)	4.0 (100)	*
3.0 (76)	4.0 (100)	4.5 (115)	*
4.0 (100)	4.0 (100)	4.5 (115)	*

5.0 (125)	4.5 (115)	5.0 (125)	*
6.0 (150)	4.5 (115)	5.0 (125)	*
8.0 (200)	5.0 (125)	6.0 (150)	*
10.0 (250)	5.0 (125)	6.0 (150)	*
12.0 (300)	5.0 (125)	6.0 (150)	*
14.0 (350)	5.0 (125)	6.0 (150)	*
16.0 (400)	5.0 (125)	6.0 (150)	*
18.0 (450)	5.0 (125)	6.0 (150)	*

* Cellular glass pipe insulation having an insulating efficiency not less than that of the specified thickness of calcium silicate may be provided.

Table 2 Insulation Thickness for Condensate Systems

Nominal Pipe Diameterinches (mm)	Mineral Fiberinches (mm)	Fibrous Glassinches (mm)
1.00 (25)	2.5 (64)	*
1.5 (38)	2.5 (64)	*
2.0 (51)	2.5 (64)	*
2.5 (64)	2.5 (64)	*
3.0 (76)	3.0 (76)	*
4.0 (100)	3.0 (76)	*
5.0 (125)	3.5 (90)	*
6.0 (150)	3.5 (90)	*
8.0 (200)	3.5 (90)	*
10.0 (250)	3.5 (90)	*
12.0 (300)	3.5 (90)	*
14.0 (350)	3.5 (90)	*
16.0 (400)	3.5 (90)	*
18.0 (450)	3.5 (90)	*

* Fibrous glass pipe insulation having an insulating efficiency not less than that of the specified thickness of mineral fiber may be provided.

G304002 1.3 EXPANSION

Compensate for piping expansion by utilizing expansion loops and joints. Provide guided slip or flexible ball type expansion joints.

G304002 1.4 SUPPORTS

MSS SP-58 and MSS SP-69, adjustable supports with insulation protection saddles. Provide stainless steel axles for rollers. Provide support poles with guy wires and hardware.

G304003 UNDERGROUND HOT WATER SYSTEMS

G304003 1.1 PIPING & FITTINGS

Direct buried, factory pre-fabricated, pre-insulated, piping systems shall consist of a service pipe with polyurethane insulation and a high-density polyethylene (HDPE) jacket. Provide factory fabricated fittings and components. Field insulation of fittings will not be allowed.

G304003 1.2 INSULATION

The minimum insulation thickness shall be in accordance with the following tables:

Table 1 Insulation Thickness for Drainable/Dryable Systems

Nominal Pipe Diameterinches (mm)	Parocinches (mm)	Epitherminches (mm)	Kaylo-10 Thermo-12 Super Caltempinches (mm)
1.00 (25)	2.0 (51)	2.5 (64)	4.0 (100)
1.5 (38)	2.0 (51)	2.5 (64)	4.0 (100)
2.0 (51)	2.5 (64)	3.5 (90)	4.5 (115)
2.5 (64)	2.5 (64)	3.5 (90)	4.5 (115)
3.0 (76)	3.0 (76)	4.0 (100)	5.0 (125)
4.0 (100)	3.0 (76)	4.0 (100)	5.0 (125)
5.0 (125)	3.0 (76)	4.0 (100)	5.0 (125)
6.0 (150)	3.5 (90)	4.5 (115)	5.5 (140)
8.0 (200)	3.5 (90)	4.5 (115)	5.5 (140)
10.0 (250)	4.0 (100)	5.0 (125)	6.0 (150)
12.0 (300)	4.0 (100)	5.0 (125)	6.0 (150)
14.0 (350)	4.0 (100)	5.0 (125)	6.0 (150)
16.0 (400)	4.0 (100)	5.0 (125)	6.0 (150)

18.0 (450)	4.0 (100)	5.0 (125)	6.0 (150)

Table 2 Insulation Thickness for Water Spread Limiting Systems

Nominal Pipe Diameterinches (mm)	Calcium Silicateinches (mm)	Polyurethaneinches (mm)
1.00 (25)	N/A	N/A
1.5 (38)	N/A	N/A
2.0 (51)	N/A	N/A
2.5 (64)	N/A	N/A
3.0 (76)	1.00 (25)	1.23 (31)
4.0 (100)	1.00 (25)	1.23 (31)
5.0 (125)	N/A	N/A
6.0 (150)	1.5 (38)	1.34 (34)
8.0 (200)	2.0 (51)	1.21 (30)
10.0 (250)	2.5 (64)	1.31 (33)
12.0 (300)	2.0 (51)	1.29 (33)
14.0 (350)	N/A	N/A
16.0 (400)	N/A	N/A
18.0 (450)	N/A	N/A

G304003 1.3 UHDS DESIGN

Design and provide direct buried, factory-prefabricated, pre-insulated main hot water piping, including piping in manholes. Asbestos cement or plastic conduit is not acceptable. The UHDS representative shall be certified in writing by the UHDS manufacturer to be technically qualified and experienced in the installation of the system. Provide a Certificate of Satisfactory Operation certifying that at least 3 systems installed by the UHDS manufacturer within the previous 10 years have and are operating satisfactorily for not less than 5 years. The certificate shall include verification information.

G304003 1.4 VALVING

Provide isolation valves on supply and return lines at take-offs for service to each building. Valves shall be located in valve boxes. Valves shall be ASME class 150.

G304003 1.5 EXPANSION

Compensate for piping expansion by utilizing expansion loops.

G304004 UNDERGROUND STEAM DISTRIBUTION SYSTEMS

G304004 1.1 PIPING & FITTINGS

Direct buried, factory pre-fabricated, pre-insulated, steam and condensate piping systems shall consist of a steel service pipe with polyurethane insulation and a high-density polyethylene (HDPE) jacket. Provide factory fabricated fittings and components. Field insulation of fittings will not be allowed.

G304004 1.2 INSULATION

The minimum insulation thickness shall be in accordance with the following tables:

Table 1 Insulation Thickness for Drainable/Dryable Systems

Nominal Pipe Diameterinches (mm)	Parocinches (mm)	Epitherminches (mm)	Kaylo-10 Thermo-12 Super Caltempinches (mm)
1.00 (25)	2.0 (51)	2.5 (64)	4.0 (100)
1.5 (38)	2.0 (51)	2.5 (64)	4.0 (100)
2.0 (51)	2.5 (64)	3.5 (90)	4.5 (115)
2.5 (64)	2.5 (64)	3.5 (90)	4.5 (115)
3.0 (76)	3.0 (76)	4.0 (100)	5.0 (125)
4.0 (100)	3.0 (76)	4.0 (100)	5.0 (125)
5.0 (125)	3.0 (76)	4.0 (100)	5.0 (125)
6.0 (150)	3.5 (90)	4.5 (115)	5.5 (140)
8.0 (200)	3.5 (90)	4.5 (115)	5.5 (140)
10.0 (250)	4.0 (100)	5.0 (125)	6.0 (150)
12.0 (300)	4.0 (100)	5.0 (125)	6.0 (150)
14.0 (350)	4.0 (100)	5.0 (125)	6.0 (150)
16.0 (400)	4.0 (100)	5.0 (125)	6.0 (150)
18.0 (450)	4.0 (100)	5.0 (125)	6.0 (150)

Table 2 Insulation Thickness for Water Spread Limiting Systems

Nominal Pipe Diameterinches	Calcium Silicateinches (mm)	Polyurethaneinches (mm)

(mm)		
1.00 (25)	N/A	N/A
1.5 (38)	N/A	N/A
2.0 (51)	N/A	N/A
2.5 (64)	N/A	N/A
3.0 (76)	1.00 (25)	1.23 (31)
4.0 (100)	1.00 (25)	1.23 (31)
5.0 (125)	N/A	N/A
6.0 (150)	1.5 (38)	1.34 (34)
8.0 (200)	2.0 (51)	1.21 (30)
10.0 (250)	2.5 (64)	1.31 (33)
12.0 (300)	2.0 (51)	1.29 (33)
14.0 (350)	N/A	N/A
16.0 (400)	N/A	N/A
18.0 (450)	N/A	N/A

Table 3 Insulation Thickness for Condensate Return Systems

Nominal Pipe Diameterinches (mm)	Parocinches (mm)	Epitherminches (mm)	Kaylo-10 Thermo-12 Super Caltempinches (mm)
1.00 (25)	2.0 (51)	2.5 (64)	4.0 (100)
1.5 (38)	2.0 (51)	2.5 (64)	4.0 (100)
2.0 (51)	2.5 (64)	3.5 (90)	4.5 (115)
2.5 (64)	2.5 (64)	3.5 (90)	4.5 (115)
3.0 (76)	3.0 (76)	4.0 (100)	5.0 (125)
4.0 (100)	3.0 (76)	4.0 (100)	5.0 (125)
5.0 (125)	3.0 (76)	4.0 (100)	5.0 (125)
6.0 (150)	3.5 (90)	4.5 (115)	5.5 (140)
8.0 (200)	3.5 (90)	4.5 (115)	5.5 (140)
10.0 (250)	4.0 (100)	5.0 (125)	6.0 (150)

12.0 (300)	4.0 (100)	5.0 (125)	6.0 (150)
14.0 (350)	4.0 (100)	5.0 (125)	6.0 (150)
16.0 (400)	4.0 (100)	5.0 (125)	6.0 (150)
18.0 (450)	4.0 (100)	5.0 (125)	6.0 (150)

G304004 1.3 UHDS DESIGN

Design and provide direct buried, factory-prefabricated, pre-insulated main steam and condensate piping in separate conduits and including piping in manholes. Asbestos cement or plastic conduit is not acceptable. The UHDS representative shall be certified in writing by the UHDS manufacturer to be technically qualified and experienced in the installation of the system. Provide a Certificate of Satisfactory Operation certifying that at least 3 systems installed by the UHDS manufacturer within the previous 10 years have and are operating satisfactorily for not less than 5 years. The certificate shall include verification information.

G304004 1.4 VALVING

Provide isolation valves on supply and return lines at take-offs for service to each building. Valves shall be located in manholes. Valves shall be ASME class 150.

G304004 1.5 EXPANSION

Compensate for piping expansion by utilizing expansion loops. Locate anchors outside manholes.

G304005 REINFORCED CONCRETE MANHOLES & VALVE BOXES

G304005 1.1 MANHOLE CONSTRUCTION

Manholes shall be shall be constructed of reinforced, 3000 psi (206.8 bar) concrete and shall extend a minimum of 6 inches (300 mm) above grade. Depth shall be as required to maintain proper pipe slopes. Construct manhole floor and sides in one monolithic pour. Provide galvanized steel or sectioned aluminum, open grate or solid cover as indicated in ESR Section G30. Provide ventilation openings for solid cover. Provide ladder. Ladder shall be steel with non-slip surfaces and anchored to the wall. Manhole floor and walls shall be watertight. Provide sleeves or core drill openings for pipes with modular mechanical seals. Provide sump pit for pump.

G304005 1.2 VALVE BOX CONSTRUCTION

Cast-iron or ductile-iron box of a suitable size. Provide cast-iron or ductile-iron cover for the box with word(s) describing the utility cast on the cover.

G304005 1.3 MANHOLE SUMP PUMPS

Vertical sump pump. Operating temperature design must be 195 degrees F (93 degrees C) minimum. Provide with 2-pole float control.

G304090 OTHER HEATING DISTRIBUTION

G304090 1.1 WARNING & IDENTIFICATION TAPE

Polyethylene plastic tape manufactured specifically for warning and identifying buried utility lines.

G304090 1.2 CORROSION PROTECTION

Provide a cathodic protection system for the underground piping system. System shall be designed by a National Association of Corrosion Engineers (NACE) certified Cathodic Protection Engineer. The corrosion engineer shall obtain soil data and existing system conditions. Corrosion engineer shall supervise, inspect and test the installation and performance of the cathodic protection system. Test stations shall be post mounted and placed at the manhole or nearby building. Test stations shall be located at each end of each cathodically protected section.

G3050 COOLING DISTRIBUTION

G305001 OVERHEAD COOLING SYSTEMS

G305001 1.1 PIPING & FITTINGS

G305001 1.1.1 Chilled and Condenser Water Piping

Chilled and condenser water piping shall be electric resistance welded or seamless Schedule 40 black steel pipe conforming to ASTM A 53. Piping 4 inch (100 mm) and smaller may be ASTM B 88 Type K or L copper.

G305001 1.1.2 Steel Pipe Fittings

For piping 2 inch (50 mm) and smaller, provide ANSI/ASME B16.3 malleable iron screwed fittings or ASME B16.11 socket welding (Class 3000) or threaded type (Class 2000). Provide ASME/ANSI B16.9 butt-welding fittings or ASME/ANSI B16.5 flanged type for piping 2-1/2 inch (63 mm) and larger. Grooved joint pipe coupling systems of appropriate pressure rating are acceptable in lieu of welded or screwed fittings.

G305001 1.1.3 Copper Fittings

Provide ANSI B16.18 cast bronze solder joint type or ASME/ANSI B16.22 wrought copper solder joint type.

G305001 1.2 INSULATION

Mineral fiber, Urethane, cellular glass, Faced Phenolic Foam, or Flexible Cellular pipe insulation with aluminum jacket in accordance with ESR Section G30. The minimum insulation thickness shall be in accordance with the following table:

Table 1 Insulation Thickness for Cold Water Systems

Nominal Pipe Diameterinches (mm)	Mineral Fiberinches (mm)	Urethaneinches (mm)	Cellular Glassinches (mm)	Faced Phenolic Foaminches (mm)	Flexible Cellularinches (mm)
1.00 (25)	1.00 (25)	0.75 (19)	1.5 (38)	1.00 (25)	0.75 (19)
1.5 (38)	1.00 (25)	0.75 (19)	1.5 (38)	1.00 (25)	0.75 (19)
2.0 (51)	1.00 (25)	0.75 (19)	1.5 (38)	1.00 (25)	0.75 (19)

2.5 (64)	1.00 (25)	0.75 (19)	1.5 (38)	1.00 (25)	0.75 (19)
3.0 (76)	1.00 (25)	0.75 (19)	1.5 (38)	1.00 (25)	0.75 (19)
4.0 (100)	1.5 (38)	0.75 (19)	1.5 (38)	1.00 (25)	0.75 (19)
5.0 (125)	1.5 (38)	0.75 (19)	1.5 (38)	1.00 (25)	0.75 (19)
6.0 (150)	1.5 (38)	1.00 (25)	1.5 (38)	1.5 (38)	1.00 (25)
8.0 (200)	1.5 (38)	1.00 (25)	1.5 (38)	1.5 (38)	1.00 (25)
10.0 (250)	1.5 (38)	1.00 (25)	1.5 (38)	1.5 (38)	1.00 (25)
12.0 (300)	1.5 (38)	1.00 (25)	1.5 (38)	1.5 (38)	1.00 (25)
14.0 (350)	1.5 (38)	1.00 (25)	1.5 (38)	1.5 (38)	1.00 (25)
16.0 (400)	1.5 (38)	1.00 (25)	1.5 (38)	1.5 (38)	1.00 (25)
18.0 (450)	1.5 (38)	1.00 (25)	1.5 (38)	1.5 (38)	1.00 (25)

G305001 1.3 SUPPORTS

Provide MSS SP-58 and MSS SP-69, adjustable supports with insulation protection saddles. Provide stainless steel axles for rollers. Provide support poles with guy wires and hardware.

G305001 1.4 EXPANSION

Compensate for piping expansion by utilizing expansion loops and joints. Provide guided slip or flexible ball type expansion joints.

G305002 UNDERGROUND COOLING SYSTEMS

G305002 1.1 PIPING & FITTINGS

Direct buried, factory-prefabricated, pre-insulated, chilled water piping systems. All fittings and accessories shall be designed and factory-fabricated to prevent moisture from entering into the system. Backfill and overall installation shall meet the requirements of the piping system manufacturer.

G305002 1.2 VALVES

Provide isolation valves on supply and return lines at take-offs for service to each building. Valves shall be located in valve boxes.

G305090 OTHER COOLING DISTRIBUTION

G305090 1.1 EXPANSION

Compensate for piping expansion by utilizing expansion loops. Locate anchors outside manholes.

G305090 1.2 WARNING & IDENTIFICATION TAPE

Polyethylene plastic tape manufactured specifically for warning and identifying buried utility lines.

G305090 1.3 CORROSION PROTECTION

Provide a cathodic protection system for the underground chilled water and condenser water piping system. System shall be designed by a National Association of Corrosion Engineers (NACE) certified Cathodic Protection Engineer. The corrosion engineer shall obtain soil data and existing system conditions. Corrosion engineer shall supervise, inspect and test the installation and performance of the cathodic protection system. Test stations shall be post mounted and placed at the manhole or nearby building. Test stations shall be located at each end of each cathodically protected section.

G3060 FUEL DISTRIBUTION

G306001 LIQUID FUEL DISTRIBUTION PIPING

G306001 1.1 GASOLINE/DIESEL

Fuel piping shall be ASTM A 53, Type E (electric-resistance welded, Grade A or B) or Type S (seamless, Grade A or B), black steel or API SPEC 5L, seamless, submerged-arc weld or gas metal-arc weld, Grade B, black steel. Provide Weight Class STD (Standard) for welding end connections. Provide Weight Class XS (Extra Strong) for threaded end connections.

G306003 LIQUID FUEL STORAGE TANKS

G306003 1.1 STORAGE TANKS

Aboveground, concrete encased or double wall in accordance with UL 142 and UL 2085 with secondary containment and leak monitoring with a capacity to meet the system requirements. Provide with overfill/spill containment, overfill protection and vents.

G306003 1.2 FUEL PUMPS

Fuel pumps shall comply with NEMA MG 1, NFPA 70, and be designed for use with hydrocarbon fuels and working pressure of 275 psig (1896 kilopascals) at 100 degrees F (38 degrees C).

G306003 1.3 FUEL METERS

Continuous duty, positive displacement type, with electronic thermal compensation capability, suitable for outdoor installation, and designed for use with hydrocarbon fuels and working pressure of 275 psig (1896 kilopascals) at 100 degrees F (38 degrees C).

G306004 LIQUID FUEL DISPENSING TANKS

The same as storage tanks except, include tank mounted dispenser with filter, vacuum breaker, safety breakaway, hose and nozzle.

G306006 GAS DISTRIBUTION PIPING (NATURAL & PROPANE)

G306006 1.1 STEEL PIPE

Gas piping shall be ASTM A 53, Type E (electric-resistance welded, Grade A or B) or Type S (seamless, Grade A or B), black steel. Provide Weight Class

STD (Standard) for welding end connections. Provide Weight Class XS (Extra Strong) for threaded end connections.

G306006 1.2 POLYETHYLENE (PE)

PE pipe and heat fusion fittings shall conform to ASTM D 2513, Grade PE2406 or PE3408.

G306007 GAS STORAGE TANKS

G306007 1.1 PROPANE STORAGE TANKS

ASME labeled tank in accordance with NFPA 58 with a capacity to meet the system requirements.

G306009 OTHER GAS DISTRIBUTION

G306009 1.1 WARNING & IDENTIFICATION TAPE

Detectable aluminum foil, plastic backed tape or detectable magnetic plastic tape manufactured specifically for warning and identifying buried piping.

-- End of Section --