Energy, Mineral
and Land Resources
ENVIRONMENTAL QUALITY

PAT MCCRORY
Governor

DONALD R. VAN DER VAART
Secretary

TRACY DAVIS

August 4, 2016

LETTER OF APPROVAL WITH MODIFICATIONS AND PERFORMANCE RESERVATIONS

MCB - Camp Lejeune
ATTN: Thomas Bradshaw
1005 Michael Road
Camp Lejeune, NC 28547

RE: Project Name: SOF INTEL OPS EXPANSION P-1396B
Acres Approved: 1.0
Project ID: ONSLO-2017-006
County: Onslow, City: Camp Lejeune
Address: Loop & Everett Creek
River Basin: White Oak
Stream Classification: High Quality
Submitted By: Steve Medvick, PE, NAVFAC MIDLANT
Date Received by LQS: July 18, 2016 and July 28, 2016
Plan Type: Other

Dear Mr. Bradshaw:

This office has reviewed the subject erosion and sedimentation control plan. We find the plan to be acceptable and hereby issue this Letter of Approval. The enclosed Certificate of Approval must be posted at the job site. This plan approval shall expire three (3) years following the date of approval, if no land-disturbing activity has been undertaken, as is required by Title 15A NCAC 4B .0129.

Please be aware that your project will be covered by the enclosed NPDES Construction Stormwater General Permit NCG010000. Please become familiar with all the requirements and conditions of this permit in order to achieve compliance.

Title 15A NCAC 4B .0118(a) requires that a copy of the approved erosion control plan be on file at the job site. Also, this letter gives the notice required by G.S. 113A-61.1(a) of our right of periodic inspection to ensure compliance with the approved plan.

North Carolina's Sedimentation Pollution Control Act is performance-oriented, requiring protection of existing natural resources and adjoining properties. If, following the commencement of this project, the erosion and sedimentation control plan is inadequate to meet the requirements of the Sedimentation Pollution Control Act of 1973 (North Carolina General Statute 113A-51 through 66), this office may require revisions to the plan and implementation of the revisions to ensure compliance with the Act.

Acceptance and approval of this plan is conditioned upon your compliance with Federal and State water quality laws, regulations, and rules. In addition, local city or county ordinances or rules may also apply to this land-disturbing activity. This approval does not supersede any other permit or approval.

Please note that this approval is based in part on the accuracy of the information provided in the Financial Responsibility Form, which you provided. You are requested to file an amended form if there is any change in the information included on the form. In addition, it would be helpful if you notify this office of the proposed starting date for this project. Please notify us if you plan to have a preconstruction conference.

Your cooperation is appreciated.

Sincerely,

Rhonda Hall

Rhonda Hall
Regional Engineering Associate
Land Quality Section

Enclosures: Certificate of Approval
Modifications and Performance Reservations
NPDES Permit

cc: Steve Medvick, PE, NAVFAC MIDLANT
Marine Corps IPT
Building Z-140, Room 104
9324 Virginia Avenue
Norfolk, VA 23511-3095

MODIFICATIONS AND PERFORMANCE RESERVATIONS

Project Name: SOF INTEL OPS EXPANSION P-1396B
Project ID: ONSLO-2017-006
County: Onslow

1. This plan approval shall expire three (3) years following the date of approval, if no land-disturbing activity has been undertaken, as is required by Title 15A NCAC 4B .0129.

2. The developer is responsible for the control of sediment on-site. If the approved erosion and sedimentation control measures prove insufficient, the developer must take those additional steps necessary to stop sediment from leaving this site (NCGS 113A-57(3)). Each sediment storage device must be inspected after each storm event (NCGS 113A-54.1(e)). Maintenance and/or clean out is necessary anytime the device is at 50% capacity. All sediment storage measures will remain on site and functional until all grading and final landscaping of the project is complete (15A NCAC 04B .0113).

3. Any and all existing ditches on this project site are assumed to be left undisturbed by the proposed development unless otherwise noted. The removal of vegetation within any existing ditch or channel is prohibited unless the ditch or channel is to be regarded with side slopes of 2 horizontal to 1 vertical or less steep (15A NCAC 04B .0124 (d)). Bank slopes may be mowed, but stripping of vegetation is considered new earth work and is subject to the same erosion control requirements as new ditches (NCGS 113A-52(6)).

4. The developer is responsible for obtaining any and all permits and approvals necessary for the development of this project prior to the commencement of this land disturbing activity. This could include our agency's Stormwater regulations and the Division of Water Resources' enforcement requirements within Section 401 of the Clean Water Act, the U.S. Army Corps of Engineers' jurisdiction of Section 404 of the Clean Water Act, the Division of Coastal Management's CAMA requirements, the Division of Solid Waste Management's landfill regulations, the Environmental Protection Agency and/or The U.S. Army Corps of Engineers jurisdiction of the Clean Water Act, local County or Municipalities' ordinances, or others that may be required. This approval cannot supersede any other permit or approval; however, in the case of a Cease and Desist Order from the Corps of Engineers, that Order would only apply to wetland areas. All highland would still have to be in compliance with the N.C. Sedimentation Pollution Control Act.

5. If any area on site falls within the jurisdiction of Section 401 or 404 of the Clean Water Act, the developer is responsible for compliance with the requirements of the Division of Water Resources (DWR), the Corps of Engineers and the Environmental Protection Agency (EPA) respectively. Any erosion control measures that fall within jurisdictional wetland areas must be approved by the aforementioned agencies prior to installation. The Land Quality Section must be notified of a relocation of the measures in question to the transition point between the wetlands and the uplands to assure that the migration of sediment will not occur. If that relocation presents a problem or contradicts any requirements of either DWR, the Corps, or the EPA, it is the responsibility of the developer to inform the Land Quality Section regional office so that an adequate contingency plan can be made to assure sufficient erosion control remains on site. Failure to do so will be considered a violation of this approval (NCGS 113A-54.1(b)).

6. Any borrow material brought onto this site must be from a legally operated mine or other approved source. Any soil waste that leaves this site can be transported to a permitted mine or separately permitted construction sites without additional permits under NCGS 74-49(7)(d). Disposal at any other location would have to be included as a permit revision for this approval.

7. This permit allows for a land disturbance, as called for on the application plan, not to exceed **1.0** acres. Exceeding that acreage will be a violation of this permit and would require a revised plan and additional application fee. Any addition in impervious surface, over that already noted on the approved plan, would also require a revised plan to verify the appropriateness of the erosion control measures and stormwater retention measures (NCGS 113A-54.1(b)).

8. The construction detail for the proposed silt fence requires reinforcing wire and **steel** posts a maximum of eight (8) feet apart. Omission of the reinforcing wire is a construction change that necessitates more posts for support, i.e., the spacing distance needs to be reduced to no greater than six (6) feet apart (E&SC Planning & Design Manual 6.63, Rev. 6/06).

9. A graveled construction entrance must be located at each point of access and egress available to construction vehicles during the grading and construction phases of this project. Access and egress from the project site at a point without a graveled entrance will be considered a violation of this approval. Routine maintenance of the entrances is critical (113A-54.1(b)).

10. As a condition of the provided NPDES General Stormwater Permit (NCG010000), groundcover stabilization must meet specific time frames. Slopes (including cuts, fills, and ditch banks) that are steeper than 3 horizontal to 1 vertical left exposed will, within seven (7) calendar days after completion of any phase of grading, be provided with groundcover. Slopes that are 3 horizontal to 1 vertical or flatter will be provided with groundcover within fourteen (14) calendar days.

11. As a part of routine monitoring of the approved land-disturbing activity, the financially responsible party shall assure inspections of the area covered by the approved plan after each phase of the plan has been completed and after establishment of temporary ground cover in accordance with North Carolina General Statute 113A-54.1(e).