

PARTIAL FIRST FLOOR AREA "A" DEMO PLAN
1/8"=1'-0"

LEGEND

- SUITE [D132] DEMOLITION ROOM NUMBER WITH 'D' PREFIX.
- DASHED LINE INDICATES ITEM TO BE DEMOLISHED.
- SOLID LINE INDICATES EXISTING ITEM TO REMAIN.
- FILL OPENING WITH CONCRETE.
- REMOVE TILE, THRESHOLD AND THICK SET GROUT.
- (4'-0" +/-) EXISTING CONSTRUCTION, DIMENSION TO BE VERIFIED BY THE CONTRACTOR.


KEYPLAN

GRAPHIC SCALE

- GENERAL DEMOLITION NOTES**
- A. ALL DEMOLITION DEBRIS SHALL BE SEPARATED BY TYPE FOR RECYCLING TO COMPLY WITH LEED REQUIREMENTS.
 - B. REMOVE ALL EXISTING FLOOR COVERINGS TO EXPOSE CONCRETE SLAB. STRIP ALL ADHESIVE RESIDUE, PATCH AND REPAIR EXPOSED CONCRETE FLOOR TO RECEIVE NEW FLOOR COVERING AS SCHEDULED. PRODUCTS USED TO REMOVE EXISTING ADHESIVE(S) MUST NOT CONTAIN CHEMICALS OR PROPERTIES THAT MAY PREVENT ADHESION AND VOID WARRANTY OF ANY NEW FLOORING PRODUCTS TO INCLUDE GFGI CARPET. GFGI CARPET WILL BE PROVIDED WITH STANDARD ADHESIVE PRODUCTS WHICH COULD BE SIMILAR TO THE FOLLOWING: PREMIUM MULTIPURPOSE ADHESIVE - AAT-275; PARABOND 4092; POWERBOND 4096. PATCHING PRODUCTS - PLANI-PATCH OR ANY EQUAL PORTLAND BASED PATCH; MAPEI PLANI PATCH (FOR ANY EXTENSIVE PATCHING WILL REQUIRE MAPEI SM PRIMER FIRST); ARDEX SD-F. SEAM SEALER - ORCON, FAST LOCK OR ANY LATEX BASED SEAM SEALER. TACKSTRIP ADHESIVE - CHEMREX 948; POWERHOLD 949.
 - C. DEMOLISH EXISTING WALLS, PARTIAL WALLS, PARTITIONS, WALL COVERING, AND EQUIPMENT AS INDICATED.
 - D. REMOVE ALL CEILINGS AND SUSPENSION SYSTEMS IN THEIR ENTIRETY. PATCH AND REPAIR ADJACENT WALLS AND CONCRETE STRUCTURE AS REQUIRED WHERE LIGHT FIXTURES, PIPING, AND MECHANICAL SYSTEMS ARE REMOVED.
 - E. REMOVE INTERIOR WALLS INDICATED IN THEIR ENTIRETY DOWN TO THE FLOOR STRUCTURE. INCLUDE ALL ELECTRICAL, PLUMBING, AND MECHANICAL SERVICES ATTACHED TO THE WALL UNLESS NOTED OTHERWISE. PATCH AND REPAIR ADJACENT FLOOR, WALL SURFACES AND UNDERSIDE OF CONCRETE DECK ABOVE WHERE WALLS TERMINATED.
 - F. MICROWAVES AND MICROFRIDGES TO BE REMOVED BY THE GOVERNMENT PRIOR TO TURNOVER. CONTRACTOR TO DEMOLISH REMAINING ITEMS INCLUDING CABINETS AND KITCHEN EQUIPMENT.
 - G. REPAIR ALL ADJACENT SURFACES OF WALLS AND STRUCTURAL ELEMENTS TO REMAIN INCLUDING WALLS, SLABS, AND COLUMNS THAT ARE DAMAGED AS A RESULT OF DEMOLITION ACTIVITY. PATCH DAMAGED AREAS TO MATCH ADJACENT SURFACE AS REQUIRED TO RECEIVE NEW FINISHES.
 - H. REMOVE CHAIR RAIL, WALL COVERING, CARPET, BASE AND CEILINGS IN CORRIDORS.
 - I. DIMENSIONS IN PARENTHESES SHOWN AS (+/-) ARE FOR REFERENCE AND ARE TO BE VERIFIED IN THE FIELD.
 - J. LOCKSETS WITH ACCESS CARD READER TO BE REMOVED BY THE GOVERNMENT AND TO BE RE-INSTALLED IN NEW DOORS BY THE CONTRACTOR. CONTRACTOR NOT RESPONSIBLE FOR LOCKSET FUNCTIONALITY UPON RE-INSTALLATION.
 - K. COORDINATE HAZARDOUS MATERIAL WORK WITH THE HAZARDOUS MATERIAL REPORT.
 - L. EXISTING FLOOR OPENINGS TO BE FILLED-IN WITH CONCRETE STRUCTURE TO BE FLUSH WITH EXISTING SLAB TYPICAL SIZE IS (8'X6" +/-). SEE STRUCTURAL DRAWINGS FOR DETAILS.
 - M. GOVERNMENT TO REMOVE REMOVE FFE PRIOR TO TURNOVER ALL OTHER ITEMS ATTACHED TO WALLS SUCH DRAPERY RODS, TOWEL BARS, CLOSET SHELVES, ETC. ARE TO BE REMOVED BY THE CONTRACTOR.

- SHEET KEYED NOTES**
1. REMOVE WOOD DOOR, HARDWARE AND MTL FRAME. DOOR IS (2'-8" X 7'-0" +/-) UNO.
 2. REMOVE WOOD DOOR AND HARDWARE, LEAVE FRAME FOR REUSE. DOOR IS (3'-6" X 7'-0" +/-).
 3. REMOVE EXISTING RUBBER SHEET FLOORING, BASE AND STAIR TREAD AND RISER COVERINGS.
 4. REMOVE GYP BD ON MTL STUD CHASE WALLS AND ASSOCIATED DUCTWORK AND PIPING. SEE MECHANICAL AND PIPING DRAWINGS..
 5. REMOVE CERAMIC TILE, THRESHOLD AND THICK SET GROUT AT SHOWER AND BATHROOM FLOOR. PATCH AND FILL CONCRETE SLAB AS REQUIRED TO RECEIVE TILE.
 6. DEMOLISH TELECOM CLOSET GYP BD ON MTL STUD WALLS AND (3'-6" X 7'-0" +/-) WOOD DOOR AND MTL FRAME. SEE TELECOM DRAWINGS.
 7. REMOVE THINSET CERAMIC TILE AT SHOWER AND BATHROOM FLOOR AND PREPARE FLOOR AS REQUIRED TO RECEIVE NEW TILE.
 8. REMOVE ENTIRE KITCHENETTE CABINETS AND TILE FLOORING (3'-6" X 4'-6" +/-). MICROFRIDGE AND MICROWAVES TO BE REMOVED BY GOVERNMENT PRIOR TO TURN OVER.
 9. REMOVE 4" CMU WALLS W/ PLASTER FINISH, 4" CMU WALLS AT BATHROOMS W/ CERAMIC WALL TILES UP TO (4' AFF +/-), 4" CMU WALLS WITH CERAMIC WALL TILES FULL HEIGHT AT SHOWERS, ACT CEILINGS, FIXTURES, CLOSET SHELF AND ROD, DOORS AND FRAMES COMPLETELY.
 10. REMOVE EXISTING HEATER UNIT. SEE MECHANICAL DRAWING.
 11. REMOVE EXISTING PIPING ROUGH-IN. SEE MECHANICAL AND PIPING DRAWINGS.
 12. REMOVE EXISTING ELECTRIC WATER COOLER COMPLETELY. SEE PIPING AND ELECTRICAL DRAWINGS.
 13. REMOVE PORTION OF EXISTING 6" CMU WALL AS REQUIRED FOR DOOR FRAME AND DOOR. SEE A5/AE501 AND DOOR SCHEDULE.
 14. REMOVE EXISTING GYPSUM BOARD ON METAL FURRING DOWN TO CMU WALL.
 15. REMOVE WOOD DOOR AND HARDWARE, LEAVE FRAME FOR REUSE. DOOR IS (2'-4" X 7'-0" +/-).
 16. DEMOLISH MECHANICAL EQUIPMENT-SEE MECHANICAL DRAWINGS.
 17. REMOVE WOOD DOOR, AND HARDWARE LEAVE FRAME FOR REUSE (3'-0" X 7'-0" +/-).
 18. REMOVE ALUMINUM FRAME WINDOW (4'-4" X 5'-8" SILL @ 2'-9" AFF +/-).

NO.	DESCRIPTION	DATE	APP'D.
2	UPDATED GENERAL DEMO NOTE	02/22/16	
1	TITLE BLOCK REVISIONS		



CH2MHILL CLARK NEXSEN
(a joint venture)
5701 Cleveland Street
Suite 200
Virginia Beach, VA 23462

APPROVED	A/E: [Signature]
FOR COMMANDER NAVFAC	
ACTIVITY	
SATISFACTORY TO	DATE 12/10/15
DES TJE	DRW TJE
CHK SHR	
BRANCH MANAGER	
CHIEF ENGINEER	
FIRE PROTECTION	

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
MIDNANT
VIRGINIA BEACH, VA

**REPAIRS TO NGIS BUILDING 225
DAM NECK ANNEX**

FIRST FLOOR DEMO PLAN AREA A

SCALE: 1/8"=1'-0"
PROJECT NO.: 1308656
CONSTR. CONTR. NO.
NAVFAC DRAWINGS NO. 12704547
SHEET 18 OF 252
AD101

FINAL DESIGN

PLOT DATE: 02/22/2016 PLOT TIME: 3:49 PM

CONTINUATION OF FINISH MATERIAL LEGEND FROM SHEET IS101


FINISH MATERIAL LEGEND					
ITEM CODE	ITEM DECS.	LOCATION	MANUFACTURER	DESCRIPTION	APPROVED SUBMITTALS
CPB-600D	CARPET BASE	GUEST CORRIDORS	MILIKEN HOSPITALITY CARPET (NIC/ PROVIDED BY OTHERS /GFGI)	PATTERN: SERENE SIMPLICITY COLOR: E109 SOLID (BROWN) SIZE: 4" HT FINISH: BOUND TOP CAP	COLOR SAMPLE REQUIRED
ACT-601	ACOUSTICAL CEILING TILE	LOBBY AREA, GUEST CORRIDORS, STAIRWELLS USE WITH ARMSTRONG PRELUDE XL HRC GRID, 9/16"	ARMSTRONG	PATTERN: ULTIMA TEGULAR #1912 COLOR: WHITE SIZE: 24" x 24" x 3/4" EDGE PROFILE: TEGULAR GRID FACE: 9/16" EXPOSED TEE GRID GRID COLOR: WHITE	SAMPLE REQUIRED
SS-600	SOLID SURFACE	GUEST BATHROOM SHOWER WALLS & PAN, GUEST BATH UNDERMOUNT SINK, GUEST LAUNDRY COUNTERTOPS	CORIAN	PATTERN: GLACIER WHITE FINISH: MATTE SIZE: 1/2" THICK	COLOR SAMPLE REQUIRED
SS-601	SOLID SURFACE	STAFF BREAKROOM, STAFF TOILET COUNTERTOPS.	CORIAN	PATTERN: FOSSIL FINISH: MATTE Size: 1/2" THICK	COLOR SAMPLE REQUIRED
SS-602	SOLID SURFACE	ALL WINDOW SILLS	CORIAN	PATTERN: BISQUE FINISH: MATTE SIZE: 1/2" THICK	COLOR SAMPLE REQUIRED
QS-606	ENGINEERED QUARTZ STONE	GUEST VANITY COUNTERTOPS, GUEST KITCHENETTE COUNTERTOP	DUPONT ZODIAQ	COLOR: SAVORY FINISH: POLISHED	COLOR SAMPLE REQUIRED
QS-607	ENGINEERED QUARTZ STONE	PUBLIC TOILET COUNTERTOPS	DUPONT ZODIAQ	COLOR: NUTMEG FINISH: POLISHED	COLOR SAMPLE REQUIRED
HIGH PRESSURE PLASTIC LAMINATE					
PL-609	HIGH PRESSURE PLASTIC LAMINATE	ALL FRONT OF HOUSE BUILT-IN CABINERY, GUEST ROOM KITCHENETTE BUILT-IN CABINERY	WILSON-ART	PATTERN: 7943-07 COLOR: COLUMBIAN WALNUT FINISH: MATTE	COLOR SAMPLE REQUIRED
PL-610	HIGH PRESSURE PLASTIC LAMINATE	STAFF BREAK ROOM BUILT-IN CABINERY	NEVAMAR	PATTERN: SERENE STARDOM COLOR: VA5001T FINISH: MATTE	COLOR SAMPLE REQUIRED
PL-611	HIGH PRESSURE PLASTIC LAMINATE	GUEST BATH VANITY BASE STAIN (TO BE MATCHED W/ PIONITE "WITCHCRAFT")	PIONITE	PATTERN: WITCHCRAFT/HI-BRIGHT COLOR: WX421-H FINISH: HI-BRIGHT	COLOR SAMPLE REQUIRED

FINISH MATERIAL LEGEND					
ITEM CODE	ITEM DECS.	LOCATION	MANUFACTURER	DESCRIPTION	APPROVED SUBMITTALS
WALL PROTECTION					
WSP-600	HANDRAIL	GUEST CORRIDORS	KOROGARD RACHEL LONGCRIER, CELL: 865.805.4182 EMAIL: rlongcrier@koroseal.com WEB: Koroseal.com	PATTERN: BELLAGARD TOP CAP- HR01 ME ROUND GRIP WOOD - CUSTOM COLUMBIAN WALNUT STAIN INSERT: BELLALUCENT MTO4-4F "BAYOU"; TEXTURE: STIPPLE BOTTOM CAP: HR01-M3 ROUND GRIP WOOD-CUSTOM TO MATCH COLUMBIAN WALNUT STAIN STAND OFF: ST22-00 CLEAR BUTTON CAP BC01-8E CHROME	COLOR SAMPLE REQUIRED
WSP-601	CORNER GUARDS	WALL CORNERS- OUTSIDE CORNERS IN ALL CORRIDORS	KOROGARD RACHEL LONGCRIER, CELL: 865.805.4182 EMAIL: rlongcrier@koroseal.com web:Koroseal.com	G-100 SERIES SURFACE MOUNT COLOR: SAND HEIGHT: 5'-0" OFF 4" WALL BASE	COLOR SAMPLE REQUIRED
WSP-602	CORNER GUARDS	WALL CORNERS- OUTSIDE CORNERS IN ALL GUEST ROOMS	KOROGARD RACHEL LONGCRIER, CELL: 865.805.4182 EMAIL: rlongcrier@koroseal.com web:Koroseal.com	J-212 SERIES SURFACE MOUNT COLOR: CLEAR HEIGHT: FROM TOP OF 4" BASE UP TO 4'-0" HT.	COLOR SAMPLE REQUIRED
MISCELLANEOUS PRODUCTS PROVIDED BY CONTRACTOR					
LK-500P	LOCKERS	STAFF LOCKER ROOM	SCRANTON 1-866-753-4954 scrantonproducts.com	SERIES: TUFFTEK HEALTHCARE STYLE: Z-LOCKERS COLOR: DESERT BEIGE SIZE: 15" X 15" X 60" HT TOPS: SLOPED ERGONOMIC HANDLE TO BE USED WITH PERSONAL PADLOCK; DOUBLE- PRONG BLACK HOOK INCLD. BASE: SEE ARCHITECTURAL DRAWINGS FOR CUSTOM BASE FOR LOCKERS.	COLOR SAMPLE REQUIRED
B-500	BENCH	STAFF LOCKER ROOM	SCRANTON 1-866-753-4954 scrantonproducts.com	SERIES: TUFFTEK COLOR: DESERT BEIGE 1 1/2" THICK PLASTIC BENCH TO MATCH LOCKERS	COLOR SAMPLE REQUIRED
SOSH-110	SOLAR SHADES	GUEST ROOMS, HOUSEKEEPING RM. #2241	MECHO SHADES mechoshade.com	SHADE: 5% SLAT TYPE/SIZE: EUORMOVEIL FABRIC: 5300 BASKETWEAVE COLOR: 5304 SAND	COLOR SAMPLE REQUIRED
EMAT-600	ENTRY MATT (NON- RECESSED)	ALL EXTERIOR ENTRY DOORS	RONICK MATTING SYSTEMS 877-242-8821 www.ronick.com	PEDIMAT TREADLINE T1 LEED CERTIFIED FINISH: BROWN VINYL INSERTS: HEAVY DUTY CARPET INSERTS INSERT COLOR: 9042 TAN SIZE: SEE ARCHITECTURAL DRAWINGS	COLOR SAMPLE REQUIRED
NOTE: FINISHES INDICATED ARE THE APPROVED BASIS OF DESIGN. NO SUBSTITUTIONS ARE ALLOWED WITHOUT WRITTEN CONSENT OF THE NAVFAC INTERIOR DESIGNER AND/OR CONTRACTING OFFICER.					

GENERAL INTERIOR NOTES

- A. REFER TO ROOM FINISH SCHEDULES ON SHEETS IS104, IS105, AND IS106 FOR ADDITIONAL FINISH INFORMATION.
- B. REFER TO INTERIOR ELEVATIONS ON SHEETS AE401, AE402 AND AE403 FOR COORDINATION OF CUSTOM CABINETS AND WALLS WHERE MULTIPLE FINISHES ARE IDENTIFIED.
- C. ALL GYPSUM BOARD WALLS AND CEILINGS TO BE PAINTED WITH LEVEL 5 FINISH. NO EXPOSED CONCRETE CEILINGS.
- D. ALL FLOOR TRANSITIONS TO OCCUR AT CENTERLINE OF DOOR UNLESS OTHERWISE NOTED.
- E. WHERE COLOR IS SHOWN AS BEING SPECIFIC TO THE MANUFACTURER, AN EQUIVALENT COLOR BY ANOTHER MANUFACTURER **MAY NOT** BE SUBMITTED UNLESS ACCOMPANIED WITH WRITTEN CONSENT FROM NAVFAC INTERIOR DESIGNER OR CONTRACTING OFFICER.
- F. INTERIOR WALL COLOR SHALL APPLY TO THE ENTIRE WALL SURFACE INCLUDING REVEALS, VERTICAL FURRED SPACES, GRILLES, DIFFUSERS, ELECTRICAL ACCESS PANELS, PIPING, AND CONDUIT ADJACENT TO WALL SURFACES UNLESS OTHERWISE SPECIFIED. ITEMS NOT SPECIFIED OTHERWISE SHALL BE PAINTED TO MATCH ADJACENT WALL SURFACES.
- G. CEILING COLORS SHALL APPLY TO CEILING SURFACES INCLUDING SOFFITS, FURRED DOWN AREAS, GRILLES, DIFFUSERS, REGISTERS AND ACCESS PANELS.
- H. RUBBER COVE BASE TO BE USED WITH RUBBER FLOORING AND SEALED CONCRETE FLOORS.
- J. ALL WINDOW SILLS SHALL BE SOLID SURFACE SS-602 AND SHALL BE 3/4" THICK.
- K. COORDINATE ALL DECORATIVE PLUMBING FIXTURES WITH MECHANICAL DRAWINGS. SEE SID BINDER FOR CUT SHEETS.
- L. REFER TO SHEET AE401 - AE403 FOR WALL AND FLOOR TILE PATTERNS FOR GUEST BATHS, PUBLIC TOILET AND LOBBY. SEE SHEET IN105 FOR FLOOR TILE LOCATIONS.
- M. EGGSHELL PAINT ON ALL WALLS UNLESS OTHERWISE NOTED. REFER TO FINISH MATERIAL LEGEND ON SHEET IS101 FOR ADDITIONAL PAINT INFORMATION.
- N. REFER TO REFLECTED CEILING PLANS FOR CEILING HEIGHTS. COORDINATE ALL DECORATIVE FIXTURE PLACEMENTS WITH ELECTRICAL DRAWINGS. SEE SID BINDER FOR ALL CUT SHEETS.
- O. CARPET FOR ENTIRE PROJECT IS N.I.C. FLOOR PATTERNS ARE USED TO EXPLAIN CARPET DESIGN AND USE OF MULTIPLE PATTERNS/COLORS.
- P. SHEET IN101 AT SUITE 2132 REPRESENTS TYPICAL FINISHES FOR ALL HOTEL GUEST SUITES ON FIRST FLOOR INCLUDING ADA GUEST SUITES. SEE SHEET IN105 FOR ROOM ENLARGEMENTS.
- Q. HANDRAILS/WALL GUARDS (WSP-600) TO BE INSTALLED ON PAINTED WALL PT-602 ONLY. DO NOT INSTALL HANDRAILS/WALL GUARDS ON GUEST CORRIDOR ACCENTS WALLS PAINTED PT-604.
- R. CONTRACTOR TO PROVIDE CONTINUOUS CLEAR PLASTIC CORNER GUARDS ON ALL EXPOSED CORNERS IN GUEST ROOMS FROM TOP OF 4" CARPET BASE UP 4'-0" HT.
- S. ALL PORCELAIN AND TILE GROUT SHALL BE EPOXY.

DATE	02/22/16	02/17/16
DESCRIPTION	CORNER GUARD CHANGE	ACOUSTIC TILE TYPE CHANGE
BY	3	2
DATE	1	1



CH2MHILL
CLARK • NEXSEN
(a joint venture)
5701 Cleveland Street
Suite 200
Virginia Beach, VA 23462

APPROVED: _____
FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO DATE: 12/10/15
DES: DWD | DRW: DWD | CHK: BCE

BRANCH MANAGER
CHIEF ENGINEER
FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
MIDJANT
VIRGINIA BEACH, VA

REPAIRS TO NGIS BUILDING 225
DAM NECK ANNEX

INTERIOR FINISH SPECIFICATIONS

SCALE: NONE
PROJECT NO.: 1308656
CONSTR. CONTR. NO.

NAVFAC DRAWING NO.: 12704602
SHEET 73 OF 252

IS102

DRAWING REVISIONS: 10 MARCH 2009

PLOT DATE: 02/22/2016
PLOT TIME: 10:51 AM

495211

NAVY GATEWAY INN & SUITES, VIRGINIA BEACH, VA

SID FINISH SCHEDULE - FIRST FLOOR

SPACE	ROOM NO.	WALLS	TRIM	FLOOR	BASE	CEILING	CABINETRY	ACCESSORIES/ LIGHTING	FINISH NOTES
STAIR	2110	PT-607, PT-609	PT-609 SEE FINISH NOTES	RF-600, RF-601	RF602	PAINTED GYP, PT-605	NA	NA	STAIRWELL DOOR TRIM COMMON WITH GUEST CORRIDORS ARE TO BE PAINTED PT-602. SEE ELECTRICAL PLAN FOR EMERGENCY LIGHTING PLACEMENT
CORRIDOR	2111	PT-602, PT-604	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFGI) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600D (NIC/PROVIDED BY OTHERS / GFGI)	ACT-600, PT-605	WSP-600, WSP-601;REFER TO SID BINDER FOR SPEC INFORMATION.	COR-304-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT.
STAIR	2112	PT-607, PT-609	PT-609 SEE FINISH NOTES	RF-600,RF-601	RF602	PAINTED GYP, PT-605	NA	NA	STAIRWELL DOOR TRIM COMMON WITH GUEST CORRIDORS ARE TO BE PAINTED PT-602. SEE ELECTRICAL PLAN FOR EMERGENCY LIGHTING PLACEMENT
CORRIDOR	2113	PT-602, PT-604	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFGI) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600D (NIC/PROVIDED BY OTHERS/GFGI)	ACT-600, PT-605	WSP-600, WSP-601;REFER TO SID BINDER FOR SPEC INFORMATION.	COR-304-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT
STAIR VESTIBULE	2114	PT-607, PT-609	PT-609 SEE FINISH NOTES	RF-600, RF-601	RF-602	PAINTED GYP, PT-605	NA	NA	STAIRWELL DOOR TRIM COMMON WITH GUEST CORRIDORS ARE TO BE PAINTED PT-602. SEE ELECTRICAL PLAN FOR EMERGENCY LIGHTING PLACEMENT
CORRIDOR	2115	PT-602, PT-604	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFGI) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600D (NIC/PROVIDED BY OTHERS/GFGI)	ACT-600, PT-605	WSP-600, WSP-601;REFER TO SID BINDER FOR SPEC INFORMATION.	COR-304-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT
CORRIDOR	2116	PT-602, PT-604	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFGI) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600D (NIC/PROVIDED BY OTHERS/GFGI)	ACT-600, PT-605	WSP-600, WSP-601;REFER TO SID BINDER FOR SPEC INFORMATION.	COR-304-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT
STAIR	2117	PT-607, PT-609	PT-609 SEE FINISH NOTES	RF-600,RF-601	RF-602	PAINTED GYP, PT-605	NA	NA	STAIRWELL DOOR TRIM COMMON WITH GUEST CORRIDORS ARE TO BE PAINTED PT-602. SEE ELECTRICAL PLAN FOR EMERGENCY LIGHTING PLACEMENT
MECHANICAL STORAGE	2118	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
STORAGE	2127	PT-607	PT-606	EPX-600	EPXB-600	PAINTER GYP, PT-605	NA	NA	
STORAGE	2128	PT-607	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFGI) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFGI)	RF-602	PAINTED GYP, PT-605	NA	NA	
MECHANICAL	2129	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
DIRTY LINEN	2130	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
GUEST SUITE LIVING AREA "F"	2131,2132, 2133,2135,2136,2139,2147,2148, 2150,2152,2156,2157,2158,2159, 2161,2162,2163,2165,2167,2169, 2170,2171,2172, 2173	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	WSP-602; CUSTOM 24" D X 48" W CABINETRY AT KITCHENETTE AREA. PROVIDE 48" W X 36" HT KITCHENETTE BASE CABINET WITH SINGLE DRAWER AND DOOR. MATCH FINISH WITH WILSON ART LAMINATE # 7943K-07 COLOMBIAN WALNUT. COUNTERTOP: QS-606, BACKSPLASH: T-607. REFER TO SHEET AE401 FOR ELEVATIONS.	CEILING MOUNT CEILING FAN, 5 BLADE, SATIN FINISH, NO LIGHT KIT	SEE ELECTRICAL PLAN FOR UNDERCOUNTER LIGHTING PLACEMENT. PROVIDE MINIMUM 48"W. SOLID ENGINEERED QUARTZ STONE COUTERTOP AND BACK/SIDE SPLASHED. PROVIDE STAINLESS STEEL UNDER-MOUNT BAR SINK WITH GOOSENECK FAUCET. SINK (MINIMUM 8" D.) WITH A REMOVABLE TRAP AND DRAIN PLUG. SOSH-110 ON ALL GUEST ROOM WINDOWS.
GUEST SUITE BATH "A"	2131,2132, 2133,2135,2136,2139,2147,2148, 2150,2152,2156,2157,2158,2159, 2161,2162,2163,2165,2167,2169, 2170,2171,2172, 2173	T-601,T-604,T-606; TO BE LAID IN RUNNING BOND PATTERN; REFER TO SHEET AE402 FOR TILE PATTERNS	PT-606	T-601; TO BE LAID IN RUNNING BOND PATTERN; REFER TO SHEET AE401 AND AE402 FOR TILE PATTERNS	WALL TILE TO MEET FLOOR TILE AT 90 DEGREE ANGLE	PAINTED GYP, PT-608	GB-200.1-CG CUSTOM CASEWORK, GB-500-MR (MIRROR FRAME) SS-600 SOLID SURFACE UNDER COUNTER MOUNT SINK. CASEWORK FINISH: PIONITE WITCHCRAFT /H-BRIGHT; QS-606 GUEST VANITY COUNTERTOPS	GB300-LT OR GB-301-LT, (ACCORDING TO WIDTH OF VANITY) GB-700-AC,GB-701-AC, GB-702-AC, GB-703-AC, GB-704-AC, GB-705-AC.	SS-600 SOLID SURFACE SHOWER WALLS AND SHOWER PAN. PROVIDE A FULL-SIZE (48" L X 30" D WHERE POSSIBLE) SHOWER WITH AN ENTRY CURB SLOPING TO A FLOOR DRAIN. PROVIDE A MUD-SET, THREE-PIECE FULL-HEIGHT, SOLID-SURFACE SHOWER SURROUND WITH 2 SOLID SURFACE CORNER SHELVES INSIDE SHOWER. SOSH-110 ON ALL GUEST BATH WINDOWS.
GUEST SUITE HALL "B"	2131,2132, 2133,2135,2136,2139,2147,2148, 2150,2152,2156,2159, 2161,2162,2163,2165,2167,2169, 2170,2171,2172, 2173	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	WSP-602	GR-304-LT	
GUEST SUITE CLOSET "C"	2131,2132, 2133,2135,2136,2139,2147,2148, 2150,2152,2156,2157,2158,2159, 2161,2162,2163,2165,2167,2169, 2170,2171,2172, 2173	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	PROVIDE CLOSET SHELF AND HANGING ROD - COMMERCIAL GRADE HEAVY DUTY WIRE MESH SHELVING SYSTEM. 300LB CAPACITY. SHELVING LAYOUT MUST ACCOMODATE FULL SIZE IRONING BOARD BRACKET WITH HOLDER FOR IRON ABOVE.	NA	PROVIDE AND COORDINATE BLOCKING.
GUEST SUITE BEDROOM "D"	2131,2132, 2133,2135,2136,2139,2147,2148, 2150,2152,2156,2157,2158,2159, 2161,2162,2163,2165,2167,2169, 2170,2171,2172, 2173	PT-602, PT-603 PROVIDE PAINTED ACCENT WALL ON HEAD BOARD WALL.	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	WSP-602	CEILING MOUNT CEILING FAN, 5 BLADE, SATIN FINISH, NO LIGHT KIT. PROVIDE A CEILING FAN WITH SPEED CONTROL. PROVIDE SEPERATE CONTRLS AT THE HEADBOARD FOR THE CEILING FAN SPEED.	SOSH-110 ON ALL GUEST ROOM WINDOWS.
GUEST SUITE MECHANICAL RM. "E"	2131,2132, 2133,2135,2136,2139,2147,2148, 2150,2152,2156,2157,2158,2159, 2161,2162,2163,2165,2167,2169, 2170,2171,2172, 2173	PT-602	PT-606	SC-600	RF-602	PAINTED GYP, PT-605	NA	NA	

DATE	02/22/16
DESCRIPTION	CORNER GUARD CHANGE
REV	1
DATE	02/22/16
DESCRIPTION	TITLE BLOCK REVISIONS
REV	2




CH2MHILL
CLARK • NEXSEN
(a joint venture)

5701 Cleveland Street
Suite 200
Virginia Beach, VA 23462

APPROVED FOR COMMANDER NAFAC

ACTIVITY

FACTORY TO DATE 12/10/15

DES: DWD | DRW: DWD | CHK: BCE

BRANCH MANAGER

CHIEF ENGINEER

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
MID-JAN
VIRGINIA BEACH, VA

REPAIRS TO NGIS BUILDING 225
DAM NECK ANNEX

INTERIOR FINISH SPECIFICATIONS

SCALE: NONE

PROJECT NO.: 1308656

CONSTR. CONTR. NO.

NAFAC DRAWING NO. 12704604

SHEET 75 OF 252

IS104

FINAL DESIGN



PLOT DATE: 02/23/2016 PLOT TIME: 7:33 AM

NAVY GATEWAY INN & SUITES, VIRGINIA BEACH, VA

SID FINISH SCHEDULE - FIRST FLOOR

SPACE	ROOM NO.	WALLS	TRIM	FLOOR	BASE	CEILING	CABINETRY	ACCESSORIES/LIGHTING	FINISH NOTES
GUEST ADA SUITE LIVING "F"	2134,2137,2154 2160	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	WSP-602; CUSTOM 24" D X 48" W CABINETRY AT KITCHENETTE AREA. PROVIDE 48" W X 36" HT KITCHENETTE BASE CABINET WITH SINGLE DRAWER AND DOOR. MATCH FINISH WITH WILSON ART LAMINATE # 7943K-07 COLOMBIAN WALNUT. COUNTERTOP: QS-606, BACKSPLASH: T-607. REFER TO SHEET AE401 FOR ELEVATIONS.	CEILING MOUNT CEILING FAN, 5 BLADE, SATIN FINISH, NO LIGHT KIT	SEE ELECTRICAL PLAN FOR UNDERCOUNTER LIGHTING PLACEMENT. PROVIDE MINIMUM 48"W. SOLID ENGINEERED QUARTZ STONE COUTERTOP AND BACK/SIDE SPLASHED. PROVIDE STAINLESS STEEL UNDER-MOUNT BAR SINK WITH GOOSENECK FAUCET. SINK (MINIMUM 8" D.) WITH A REMOVABLE TRAP AND DRAIN PLUG. SOSH-110 ON ALL GUEST ROOM WINDOWS.
GUEST ADA SUITE BATH "A"	2134, 2137, 2154, 2160	T-604,T-606; TO BE LAID IN RUNNING BOND PATTERN; REFER TO SHEET AE401 AND AE402 FOR TILE	PT-606	T-601; TO BE LAID IN RUNNING BOND PATTERN; REFER TO SHEET AE402 FOR TILE PATTERNS	WALL TILE TO MEET FLOOR TILE AT 90 DEGREE ANGLE	PAINTED GYP, PT-608	GB-200.2-CG CUSTOM CASEWORK, GB-500-MR (MIRROR FRAME) SS-600 SOLID SURFACE UNDER COUNTER MOUNT SINK. QS-606 GUEST VANITY COUNTERTOPS	GB300-LT OR GB-301-LT, (ACCORDING TO WIDTH OF VANITY) GB-700-AC,GB-701-AC, GB-702-AC, GB-703-AC, GB-704-AC, GB-705-AC.	SS-600 SOLID SURFACE SHOWER WALLS AND SHOWER PAN. PROVIDE A FULL-SIZE (48" L x 30" D WHERE POSSIBLE) SHOWER WITH AN ENTRY CURB SLOPING TO A FLOOR DRAIN. PROVIDE A MUD-SET, THREE-PIECE FULL-HEIGHT, SOLID-SURFACE SHOWER SURROUND WITH 2 SOLID SURFACE CORNER SHELVES INSIDE SHOWER. SOSH-110 ON ALL GUEST BATH WINDOWS.
GUEST ADA SUITE HALL "B"	2134,2137,2154 2160	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	WSP-602	GR-304-LT	
GUEST ADA SUITE CLOSET "C"	2134,2137,2154 2160	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	PROVIDE CLOSET SHELF AND HANGING ROD - COMMERCIAL GRADE HEAVY DUTY WIRE MESH SHELVING SYSTEM. 300LB CAPACITY. SHELVING LAYOUT MUST ACCOMODATE FULL SIZE IRONING BOARD BRACKET WITH HOLDER FOR IRON ABOVE.	NA	PROVIDE AND COORDINATE BLOCKING.
GUEST ADA SUITE BEDROOM "D"	2134,2137,2154 2160	PT-602, PT-603 PROVIDE PAINTED ACCENT WALL ON HEAD BOARD WALL.	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	WSP-602	CEILING MOUNT CEILING FAN, 5 BLADE, SATIN FINISH, NO LIGHT KIT. PROVIDE A CEILING FAN WITH SPEED CONTROL. PROVIDE SEPERATE CONTRLS AT THE HEADBOARD FOR THE CEILING FAN SPEED.	SOSH-110 ON ALL GUEST ROOM WINDOWS.
GUEST ADA SUITE MECHANICAL RM. "E"	2134,2137,2154 2160	PT-602	PT-606	SC-600	RF-602	PAINTED GYP, PT-605	NA	NA	
LAUNDRY	2138	PT-602	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	BUILT-IN COUNTER. SS-600 COUNTERTOP AND BACK/SIDE SPLASHES. SEE SHEET AE403 FOR ELEVATION DETAIL.	NA	PROVIDE HANGING ROD -COMMERCIAL GRADE HEAVY DUTY WIRE MESH SHELVING SYSTEM CAPABLE OF SUPPORTING 100LBS.
VENDING LOBBY	2140 2141	PT-602 PT-602, PT-604 ACCENT WALL	PT-606 PT-606	EPX-600 T-601, CP-601A,	EPXB-600 TB-601 OR T-601, 4" HT CUT 12" X 24" TILE, CP-601B	PAINTED GYP, PT-605 PAINTED GYP, PT-605	NA NA	NA COR-305-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT. SOSH-110 ON ALL LOBBY AREA WINDOWS.
CART STORAGE	2142	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
BELL CART	2143	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
JANITOR PUBLIC TOILET	2144 2145	PT-607 T-604, T-607. REFER TO SHEET AE402 FOR TILE PATTERNS	PT-606 PT-606	EPX-600 T-601	EPXB-600 WALL TILE TO MEET FLOOR TILE AT 90 DEGREE ANGLE	PAINTED GYP, PT-605 PAINTED GYP, PT-605	NA PROVIDE SOLID ENGINEERED QUARTZ STONE COUNTERTOP AND 4" BACK/SIDE SPLASHES AND UNDERMOUNTED SINK. COUNTER SHALL BE 36" HT. PR-506-MR FULL WIDTH FRAMED MIRROR OVER VANITY. FINISH TO MATCH WILSON-ART #7943-07 COLUMBIAN WALNUT	A PR-306-LT.	PROVIDE THE FOLLOWING ACCESSORIES: • AUTOMATIC PAPER TOWLE DISPENSER • BUILT-IN TRASH RECEPTACLES •AUTOMATIC SOAP DISPENSER
CLEAN LINEN	2146	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
ELECTRICAL	2149	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
TELE/COM	2151	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
MECHANICAL	2153	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
JANITOR	2155	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
MECHANICAL	2164	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
ELECTRICAL	2166	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
TELE/COM	2168	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	

DATE	02/22/16
DESCRIPTION	CORNER GUARD CHANGE
NO.	2
DATE	02/22/16
DESCRIPTION	TITLE BLOCK REVISIONS
NO.	1



CH2MHILL
CLARK • NEXSEN
(a joint venture)

5701 Cleveland Street
Suite 200
Virginia Beach, VA 23462

APPROVED: _____
FOR COMMANDER NAVFAC

ACTIVITY

SATISFACTORY TO DATE 12/10/15
DES: DWD [CHK] DWD [CHK] BCE

BRANCH MANAGER

CHIEF ENGINEER

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
MID-JAN
VIRGINIA BEACH, VA
REPAIRS TO NGIS BUILDING 225
DAM NECK ANNEX
INTERIOR FINISH SPECIFICATIONS

SCALE: NONE

EPROJCT NO.: 1308656
CONSTR. CONTR. NO.

NAVFAC DRAWING NO. 12704605
SHEET 76 OF 252

IS105

PLOT DATE: 02/23/2016 PLOT TIME: 7:38 AM

D

C

B

A

D

C

B

A

FINAL DESIGN

NAVY GATEWAY INN & SUITES, VIRGINIA BEACH, VA

SID FINISH SCHEDULE - SECOND FLOOR

SPACE	ROOM NO.	WALLS	TRIM	FLOOR	BASE	CEILING	CABINETRY	ACCESSORIES/LIGHTING	FINISH NOTES
STAIR	2210	PT-607, PT-609	PT-609 SEE FINISH NOTES	RF-600,RF-601	RF602	PAINTED GYP. PT-605	NA	NA	STAIRWELL DOOR TRIM COMMON WITH GUEST CORRIDORS ARE TO BE PAINTED PT-602. SEE ELECTRICAL PLAN FOR EMERGENCY LIGHTING PLACEMENT
CORRIDOR	2211	PT-602, PT-604	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFG) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFG)	CPB-600D (NIC/PROVIDED BY OTHERS / GFG)	ACT-600, PT-605	WSP-600, WSP-601; REFER TO SID BINDER FOR SPEC INFORMATION.	COR-304-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT.
STAIR	2212	PT-607, PT-609	PT-609 SEE FINISH NOTES	RF-600,RF-601	RF-602	PAINTED GYP.PT-605	NA	NA	STAIRWELL DOOR TRIM COMMON WITH GUEST CORRIDORS ARE TO BE PAINTED PT-602. SEE ELECTRICAL PLAN FOR EMERGENCY LIGHTING PLACEMENT
CORRIDOR	2213	PT-602, PT-604	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFG) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFG)	CPB-600D (NIC/PROVIDED BY OTHERS / GFG)	ACT-600, PT-605	WSP-600, WSP-601; REFER TO SID BINDER FOR SPEC INFORMATION.	COR-304-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT.
STAIR VESTIBULE	2214	PT-607, PT-609	PT-609 SEE FINISH NOTES	T-602	T-602	PAINTED GYP. PT-605	NA	NA	STAIRWELL DOOR TRIM COMMON WITH GUEST CORRIDORS ARE TO BE PAINTED PT-602. SEE ELECTRICAL PLAN FOR EMERGENCY LIGHTING PLACEMENT
CORRIDOR	2215	PT-602, PT-604	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFG) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFG)	CPB-600D (NIC/PROVIDED BY OTHERS / GFG)	PAINTED GYP. PT-605	WSP-600, WSP-601; REFER TO SID BINDER FOR SPEC INFORMATION.	COR-304-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT.
CORRIDOR	2216	PT-602, PT-604	PT-606	CP-601-A (NIC/PROVIDED BY OTHERS/GFG) ACCENT:CP-601-B (NIC/PROVIDED BY OTHERS/GFG)	CPB-600D (NIC/PROVIDED BY OTHERS / GFG)	PAINTED GYP. PT-605	WSP-600, WSP-601; REFER TO SID BINDER FOR SPEC INFORMATION.	COR-304-LT	SEE ELECTRICAL PLAN FOR LIGHTING PLACEMENT.
STAIR	2217	PT-607, PT-609	PT-609 SEE FINISH NOTES	RF-600,RF-601	RF602	PAINTED GYP. PT-605	NA	NA	STAIRWELL DOOR TRIM COMMON WITH GUEST CORRIDORS ARE TO BE PAINTED PT-602. SEE ELECTRICAL PLAN FOR EMERGENCY LIGHTING PLACEMENT
EMP. LOUNGE	2226	PT-602	PT-606	VWF-60	RF-602	PAINTED GYP. PT-605	PROVIDE A MINIMUM 24 " DEEP SS-601 SOLID SURFACE COUNTERTOP AND BACK/SIDE SPLASHES. PROVIDE WALL HUNG UPPER AND BASE CABINETS. CABINETS TO BE CLAD IN NEVAMAR "SERENE STARDOM" #VA5001T. REFER TO SHEET AE403 FOR ELEVATIONS.	PROVIDE THE FOLLOWING FOOD SERVICE EQUIPMENT: • COMMERCIAL GRADE UNDER COUNTER DISHWASHER, • Commercial GRADE IN-SINK FOOD DISPOSAL • FULL SIZE REFRIGERATOR WITH ICE MAKER • TWO (2) COUNTERTOP COMMERCIAL GRADE MICROWAVE.	PROVIDE AN UNDER-MOUNT DOUBLE BOWL STAINLESS STEEL KITCHEN SINK WITH A REMOVABLE TRAP AND DRAIN PLUG. MINIMUM 7" DEEP. PROVIDE GOOSENECK SINGLE LEVER FAUCET
EMP. LOCKERS	2227	PT-602	PT-606	VWF-60	RF-602	PAINTED GYP. PT-605	NA	TUFFTEK HEALTHCARE Z-LOCKERS COLOR: PARCHMENT; TUFFTEK BENCH, COLOR: PARCHMENT. REFER TO SID BINDER FOR SPEC INFORMATION.	
STORAGE	2228	PT-607	PT-606	SC-600	RF-602	PAINTED GYP. PT-605	NA	NA	
EMP. TOILET	2229	T-603, T-605 REFER TO SHEET AE402 FOR TILE PATTERNS	PT-606	T-602	WALL TILE TO MEET FLOOR TILE AT 90 DEGREE ANGLE	PAINTED GYP. PT-605	CUSTOM 24" D X 48" W X 36" HT. CABINETRY. BASE CABINET WITH SINGLE DRAWER AND DOOR. CABINETS TO BE CLAD IN NEVAMAR "SERENE STARDOM" #VA5001T. PROVIDE A MINIMUM 24 " DEEP SS-601 SOLID SURFACE COUNTERTOP AND BACK/SIDE SPLASHES. REFER TO SHEET AE402 FOR ELEVATIONS.	PROVIDE THE FOLOWING ACCESSORIES: TOILET PAPER DISPENSER, AUTOMATIC PAPER TOWEL DISPENSER, AUTOMATIC SOAP DISPENSER, PROVIDE FULL WIDTH MIRROR OVER VANITY	SS-600 SOLID SURFACE SHOWER WALLS AND SHOWER PAN. PROVIDE A FULL-SIZE (48" L x 30" D WHERE POSSIBLE) SHOWER WITH AN ENTRY CURB SLOPING TO A FLOOR DRAIN. PROVIDE A MUD-SET, THREE-PIECE FULL-HEIGHT, SOLID-SURFACE SHOWER SURROUND WITH 2 SOLID SURFACE CORNER SHELVES INSIDE SHOWER
GUEST SUITE LIVING AREA "F"	2230,2231,2232,2233,2234,2235,2236,2237,2239,2247,2248,2250,2252,2254,2256,2257,2258,2259,2260,2262,2263,2265,2267,2269,2270,2271,2272, 2273	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFG)	CPB-600 (NIC/PROVIDED BY OTHERS/GFG)	PAINTED GYP, PT-605	WSP-602; CUSTOM 24" D X 48" W CABINETRY AT KITCHENETTE AREA. PROVIDE 48" W x 36" HT KITCHENETTE BASE CABINET WITH SINGLE DRAWER AND DOOR. MATCH FINISH WITH WILSON ART LAMINATE # 7943K-07 COLOMBIAN WALNUT, COUNTERTOP: QS-606, BACKSPLASH: T-607. REFER TO SHEET AE401 FOR ELEVATIONS.	CEILING MOUNT CEILING FAN, 5 BLADE, SATIN FINISH, NO LIGHT KIT	SEE ELECTRICAL PLAN FOR UNDERCOUNTER LIGHTING PLACEMENT. PROVIDE MINIMUM 48"W. SOLID ENGINEERED QUARTZ STONE COUTERTOP AND BACK/SIDE SPLASHED. PROVIDE STAINLESS STEEL UNDER-MOUNT BAR SINK WITH GOOSENECK FAUCET. SINK (MINIMUM 8" D.) WITH A REMOVABLE TRAP AND DRAIN PLUG. SOSH-110 ON ALL GUEST ROOM WINDOWS.
GUEST SUITE BATH "A"	2230,2231,2232,2233,2234,2235,2236,2237,2239,2247,2248,2250,2252,2254,2256,2257,2258,2259,2260,2262,2263,2265,2267,2269,2270,2271,2272, 2273	T-601,T-604,T-606; TO BE LAID IN RUNNING BOND PATTERN; REFER TO SHEET AE401 AND AE402 FOR TILE PATTERNS	PT-606	T-601; TO BE LAID IN RUNNING BOND PATTERN; REFER TO SHEET AE401 AND AE402 FOR TILE PATTERNS	WALL TILE TO MEET FLOOR TILE AT 90 DEGREE ANGLE	PAINTED GYP. PT-608	GB-200.1-CG CUSTOM CASEWORK, GB-500-MR (MIRROR FRAME) SS-600 SOLID SURFACE UNDER COUNTER MOUNT SINK. CASEWORK FINISH: PIONITE WITCHCRAFT /HI-BRIGHT; QS-606 GUEST VANITY COUNTERTOPS. SEE SID BINDER FOR SPECS. REFER TO SHEET AE402 FOR ELEVATIONS	GB300-LT OR GB-301-LT, (ACCORDING TO WIDTH OF VANITY) GB-700-AC,GB-701-AC, GB-702-AC, GB-703-AC, GB-704-AC, GB-705-AC,	SS-600 SOLID SURFACE SHOWER WALLS AND SHOWER PAN. PROVIDE A FULL-SIZE (48" L x 30" D WHERE POSSIBLE) SHOWER WITH AN ENTRY CURB SLOPING TO A FLOOR DRAIN. PROVIDE A MUD-SET, THREE-PIECE FULL-HEIGHT, SOLID-SURFACE SHOWER SURROUND WITH 2 SOLID SURFACE CORNER SHELVES INSIDE SHOWER. SOSH-110 ON ALL GUEST BATH WINDOWS
GUEST SUITE HALL "B"	2230,2231, 2232,2233, 2234,2235, 2236,2237, 2239,2247, 2248,2250, 2252,2254, 2256,2257, 2258,2259, 2260,2262, 2263,2265, 2267,2269, 2270,2271, 2272, 2273	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFG)	CPB-600 (NIC/PROVIDED BY OTHERS/GFG)	PAINTED GYP, PT-605	WSP-602	GR-304-LT	

DATE	02/22/16
DESCRIPTION	CORNER GUARD CHANGE TITLE BLOCK REVISIONS
REV	2 1
DATE	
DESCRIPTION	
	
	
	
5701 Cleveland Street Suite 200 Virginia Beach, VA 23462	
APPROVED	A/E: HNS
FOR COMMANDER NAVFAC	
ACTIVITY	
SATISFACTORY TO DATE	12/10/15
DES: DWD	CHK: BCE
BRANCH MANAGER	
CHIEF ENGINEER	
TRN PROTECTION	
DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND VIRGINIA BEACH, VA REPAIRS TO NGIS BUILDING 225 DAM NECK ANNEX INTERIOR FINISH SPECIFICATIONS	
SCALE:	NONE
PROJECT NO.:	1308656
CONSTR. CONTR. NO.	
NAVFAC DRAWING NO.	12704606
SHEET	77 OF 252
IS106	

PLOT DATE: 02/23/2016 PLOT TIME: 9:19 AM

D

C

B

A

D

C

B

A

FINAL DESIGN

NAVY GATEWAY INN & SUITES, VIRGINIA BEACH, VA

SID FINISH SCHEDULE - SECOND FLOOR

SPACE	ROOM NO.	WALLS	TRIM	FLOOR	BASE	CEILING	CABINETS	ACCESSORIES/LIGHTING	FINISH NOTES
GUEST SUITE CLOSET "C"	2230,2231,2232,2233,2234,2235,2236,2237,2239,2246,2247,2248,2250,2252,2254,2256,2257,2258,2259,2260,2261,2263,2265,2267,2268,2269,2270,2271,2273	PT-602	PT-606	P	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	PROVIDE CLOSET SHELF AND HANGING ROD - COMMERCIAL GRADE HEAVY DUTY WIRE MESH SHELVING SYSTEM. 300LB CAPACITY. SHELVING LAYOUT MUST ACCOMMODATE FULL SIZE IRONING BOARD BRACKET WITH HOLDER FOR IRON ABOVE.	NA	PROVIDE AND COORDINATE BLOCKING
GUEST SUITE BEDROOM "D"	2230,2231,2232,2233,2234,2235,2236,2237,2239,2246,2247,2248,2250,2252,2254,2256,2257,2258,2259,2260,2261,2263,2265,2267,2268,2269,2270,2271,2273	PT-602, PT-603 PROVIDE PAINTED ACCENT WALL ON HEAD BOARD WALL.	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	WSP-602	CEILING MOUNT CEILING FAN, 5 BLADE, SATIN FINISH, NO LIGHT KIT. PROVIDE A CEILING FAN WITH SPEED CONTROL. PROVIDE SEPERATE CONTRLS AT THE HEADBOARD FOR THE CEILING FAN SPEED.	SOSH-110 ON ALL GUEST ROOM WINDOWS
GUEST SUITE MECHANICAL RM. "E"	2230,2231,2232,2233,2234,2235,2236,2237,2239,2246,2247,2248,2250,2252,2254,2256,2257,2258,2259,2260,2261,2263,2265,2267,2268,2269,2270,2271,2273	PT-602	PT-606	SC-600	RF-602	PAINTED GYP, PT-605	NA	NA	
LAUNDRY	2238	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	BUILT-IN COUNTER. SS-600 COUNTERTOP AND BACK/SIDE SPLASHES.	NA	PROVIDE HANGING ROD -COMMERCIAL GRADE HEAVY DUTY WIRE MESH SHELVING SYSTEM CAPABLE OF SUPPORTING 100LBS.
VENDING	2240	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
GEAR LOCKER	2241	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
JANITOR	2242	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
CLOSET	2243	PT-602	PT-606	CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605	PROVIDE CLOSET SHELF AND HANGING ROD - COMMERCIAL GRADE HEAVY DUTY WIRE MESH SHELVING SYSTEM. 300LB CAPACITY.	NA	
CLEAN LINEN OFFICE	2244 2245	PT-607 PT-602	PT-606 PT-606	EPX-600 CP-600 (NIC/PROVIDED BY OTHERS/GFGI)	EPXB-600 CPB-600 (NIC/PROVIDED BY OTHERS/GFGI)	PAINTED GYP, PT-605 PAINTED GYP, PT-605	NA NA	NA NA	SOSH-110 ON ALL OFFICE WINDOWS
ELECTRICAL	2249	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
TELE/COM	2251	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
MECHANICAL	2253	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
JANITOR	2255	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
LAUNDRY	2264	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
ELECTRICAL	2266	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	
TELE/COM	2268	PT-607	PT-606	EPX-600	EPXB-600	PAINTED GYP, PT-605	NA	NA	

DATE	02/22/16
TITLE BLOCK REVISIONS	
NO.	1
DESCRIPTION	
NO.	2
DESCRIPTION	



CH2MHILL
CLARK • NEXSEN
(a joint venture)

5701 Cleveland Street
Suite 200
Virginia Beach, VA 23462

A/E REF:

FOR COMMANDER NAFAC

ACTIVITY

DATE 12/10/15

DES: DWD | DRW: DWD | CHK: BCE

BRANCH MANAGER

CHIEF ENGINEER

FIRE PROTECTION

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
MIL/JAF
VIRGINIA BEACH, VA
REPAIRS TO NGIS BUILDING 225
DAM NECK ANNEX
INTERIOR FINISH SPECIFICATIONS

SCALE:
PROJECT NO.: 1308656
CONSTR. CONTR. NO.
NAFAC DRAWING NO.: 12704607
SHEET 78 OF 252
IS107

FINAL DESIGN

PLOT DATE: 02/23/2016 PLOT TIME: 9:41 AM