

**REPAIR UNINTERRUPTED POWER SUPPLY (UPS) SYSTEM
NAVAL HOSPITAL NH-100
CAMP LEJEUNE, NORTH CAROLINA
SOLICITATION N40085-16-T-6424**

1. GENERAL INTENTION. It is the declared and acknowledged intention of this solicitation to obtain the supervision, expertise, labor, materials, and equipment to replace batteries and perform startup of the UPS at NH100.

2. LOCATION. The work location is in boiler room at Naval Hospital, NH100 Camp Lejeune, NC.

3. DETAILED REQUIREMENTS. The Contractor shall:

a. **A site visit is required.** The date and time for the site visit will be issued via an amendment to the solicitation.

b. Remove and replace 240 each East Penn AVR95-13L batteries located in the battery rack system. Installation shall follow manufacture specifications.

c. After installation of new batteries, perform startup and diagnostic of the UPS for proper operation per manufacture specifications.

d. Provide a list of necessary material and labor cost for any additional material needed to make UPS operational per manufacture specifications.

e. Disposal of existing batteries shall be done off base to an authorized disposal site for lead batteries.

f. Provide a work schedule.

5. SPECIAL REQUIREMENTS. The Contractor shall be required to:

a. Follow all Lock Out Tag Out procedures before commencing work. Coordinate with Naval Hospital Facilities Maintenance personnel.

b. Commence work under this contract within fifteen (15) calendar days after award notification or any other communication authorizing the Contractor to proceed by the Contracting Officer.

c. Notify the Contracting Officer prior to the commencement of work.

d. The contractor shall be prepared for **weekend** working arrangements to complete the job.

e. Complete the work within 120 calendar days.