

damage to roads caused by construction operations.

3.3.3 Dust Control

Dust control methods and procedures must be approved by the Contracting Officer. Treat dust abatement on access roads with applications of calcium chloride, water sprinklers, or similar methods or treatment.

3.4 CONTRACTOR'S TEMPORARY FACILITIES

3.4.1 Safety

Protect the integrity of any installed safety systems or personnel safety devices. If entrance into systems serving safety devices is required, the Contractor must obtain prior approval from the Contracting Officer. If it is temporarily necessary to remove or disable personnel safety devices in order to accomplish contract requirements, provide alternative means of protection prior to removing or disabling any permanently installed safety devices or equipment and obtain approval from the Contracting Officer.

3.4.2 Administrative Field Offices

Provide and maintain administrative field office facilities within the construction area at the designated site. Government office and warehouse facilities will not be available to the Contractor's personnel.

3.4.3 Storage Area

Construct a temporary 6 foot high chain link fence around trailers and materials. Include plastic strip insert so that visibility through the fence is obstructed. Fence posts may be driven, in lieu of concrete bases, where soil conditions permit. Do not place or store Trailers, materials, or equipment outside the fenced area unless such trailers, materials, or equipment are assigned a separate and distinct storage area by the Contracting Officer away from the vicinity of the construction site but within the installation boundaries. Trailers, equipment, or materials must not be open to public view with the exception of those items which are in support of ongoing work on any given day. Do not stockpile materials outside the fence in preparation for the next day's work. Park mobile equipment, such as tractors, wheeled lifting equipment, cranes, trucks, and like equipment within the fenced area at the end of each work day.

To facilitate easier logistics and efficiency, approval has just been received to provide additional adjacent street-side laydown area next to the construction site. The extent of the laydown area will be from "G wing" exit door to ~~approx. 45' west of "H Wing" (adjacent to J wing exit path as shown on drawing G-001, Building Key Plan).~~ A 1015' walking path from the curb must be provided. A personnel gate with a latch feature must be provided for courtyard emergency exit from existing courtyard doors between "H" and "G" Wings. The entire fencing shall be screened with dark brown slats. Posts shall be placed and secured not to disturb existing brick pavers. The existing curbs, concrete sidewalk and brick paving must be protected during construction and if damaged or depressed must be restored to original condition / level. Additional temporary fencing may be allowed up to curb and slightly into access road on a case by case basis to facilitate crane operations, heavy equipment mob / demob, etc. Other areas may be allowed on a case by case basis upon request to Contracting Officer, Bldg. 2000 Facility & Security manager.