

Q1:

Section 3.5 outlines 5 Total TV's to be mounted however there are a total of 8ea in the bill of materials and on the system drawing. Are there currently 3ea TV's already installed or does the contractor have to mount 8ea TV's?

A1: Two GOE 75' displays and three 50' displays to be mounted in room 113. Additional 3 displays already installed in RH-111a. GOE mounts provided.

Q2:

The system drawing and bill of materials shows 2ea video projectors. Are these projectors currently installed or do they need to be installed & mounted?

A2: Panasonic PT-RZ370 without GOE installation plate will replace old projector in RH-111b, mount station in place. Panasonic DW5100 already installed in RH-109.

Q3:

Are mounts for the video cameras provided as GOE?

A3: Camera mounts not included in GOE.

Q4:

The bill of materials and scope outlines 6ea Shure MX202 microphones. What room(s) do these microphones get installed in?

A4: RH-109 and RH-113. Audio cable is not GOE.

Q5:

On the bill of materials line item #2. Can you specifically list the exact part number of the XTP 4i and 4o cards or supply a picture of these cards?

A5: XTP CP 4i part # 70-940-01. XTP CP 4o part # 70-943-01

Q6:

The microphone component is a little confusing. Not sure how they intend to use them. Just between rooms or over audio conference? (Please clarify intended use)

A6: Intention is to be able to interconnect audio from 109, 111b, 113 to 111a. Mic's already installed in 111b and 111a. Best interconnection outcome with GOE is acceptable.