

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>			1. CONTRACT ID CODE	PAGE OF PAGES 1   3
2. AMENDMENT/MODIFICATION NO. 0001	3. EFFECTIVE DATE 01-Mar-2016	4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO.(If applicable)
6. ISSUED BY NAVFAC SOUTHEAST SOUTH TEXAS AREA PWD CORPUS CHRISTI/PWD INGLESIDE 8851 OCEAN DRIVE, BLDG 19 CORPUS CHRISTI TX 78419-5525	CODE N69450	7. ADMINISTERED BY (If other than item 6) <b>See Item 6</b>		
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)		X	9A. AMENDMENT OF SOLICITATION NO. N69450-16-Q-5319	
		X	9B. DATED (SEE ITEM 11) 08-Feb-2016	
			10A. MOD. OF CONTRACT/ORDER NO.	
			10B. DATED (SEE ITEM 13)	
CODE	FACILITY CODE			
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS				
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended. Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.				
12. ACCOUNTING AND APPROPRIATION DATA (If required)				
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.				
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.				
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).				
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:				
D. OTHER (Specify type of modification and authority)				
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.				
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)  PPI LOG				
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.				
15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) JOEL OVERSON / CONTRACTING OFFICER TEL: 361-961-3397 EMAIL: joel.overson@navy.mil		
15B. CONTRACTOR/OFFEROR  (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA  BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED 01-Mar-2016	

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

**SUMMARY OF CHANGES**

SECTION SF 30 - BLOCK 14 CONTINUATION PAGE

The following have been added by full text:

PPI LOG

Pre-Proposal Inquiries

Q1 – I want to confirm that this project Requires 3000 PSI concrete.  
PSI required is listed on Attachment C Line 3

A1 - In accordance to the contract Section 13 - Civil/Structural #5, the concrete shall be a minimum of 3000psi at 28 days.

Q2 – For the Hand Hole does the Government want Traffic Rated or Pedestrian Rated?

A2 - Traffic rated

Q3 – Will a Inter Duct be required within the 2” Conduit?

A3 - Inner Duct is not required. Government will install Maxcell Fabric in the future if necessary.

Q4 – If a Inter Duct is required is required what size does the Government Require?

A4 - Inner Duct is not required.

Q5 – Where the Sign is being located and as per the SOW we need to be 7' deep x 36”

(a) Question is What depth is the Sewer Line that we'll be working above or next to?

(b) Question is What is the Size of the Sewer Line?

As we might not have enough room in this area if the Sewer line is 24” or above.

A5(a) - The depth varies,

A5(b) - The 24" Storm Sewer line is running longitudinal and under existing sidewalk, approximately 9'-10' away from proposed location of footing construction. Contractor is still responsible to acquire dig permit and locate all existing utility lines prior to commencement of work.

Q6 – Will the Contractor be Responsible for the Damage that already exist on the Sidewalk?

A6 - The contractor will not be responsible for the existing damage to the sidewalk. However in accordance to Section 6 of the contract "existing work to remain shall be protected from damage. Work damaged by the Contractor shall be repaired to original condition at no additional cost to the government. Any required excavating through a paved or cemented area falls under Section 6 and shall be repaired to original condition.

Q7 – Need to confirm the Size of Hand Hole?

A7 - Hand hold is 2ft x 3ft with cover.

Q8 – What type of Hand Hole is required?

(a) Concrete or Quazite

A8 - Quazite/Polymer concrete

Q9 - Does the concrete need to be tested?

(a) If so, does it need to be a 7 day break, 14 day break and 30 day break?

A9 - Use 3000-3500 psi concrete. Testing is not required.

Q10 - Could we get information on what is beneath the Ocean Drive roadway to provide to boring contractors to provide an accurate bid.

A10 - The profile/cross section of Ocean Drive Roadway consists of 3" surface/HMAC course 12" thick compacted base material/caliche and 6" thick compacted subgrade. As utility drawings shown, there are no underground lines on Ocean Drive; however, electrical distribution, communication and storm water lines are located on the pedestrian sides/grassy area. The existing utility lines depth may vary and contractor must acquire dig permit prior to commencement of work and locate all existing utility lines.

(End of Summary of Changes)